# The ARRL

ANTENNA BOOK

21st Edition

The *ultimate* reference for Amateur Radio antennas, transmission lines and propagation

INSIDE: Includes the fully searchable book on CD-ROM

Complete CD
for THE ARRL
ANTENNA BOOK

The ARRL Antenna Book

All the information you need to design your own complete antenna system.

Since the first edition in September 1939, radio amateurs and professional engineers have turned to **The ARRL Antenna Book** as THE source of current antenna theory and a wealth of practical how-to construction projects. Use this book to discover even the most basic antenna designs— wire and loop antennas, verticals, and Yagis—and for advanced antenna theory and applications. Many of the antennas in this edition benefit directly from advances in sophisticated computer modeling.

This 21st edition has been extensively revised to include information you can use to build highly optimized or specialized antennas. The book includes new content on Near Vertical Incidence Skywave (NVIS) techniques, phased arrays, S-parameters as used in modern vector network analyzers (VNA), Beverage receiving antennas, mobile "screwdriver" antennas, ionospheric area-coverage maps, *and much…much more*.

Fully searchable CD-ROM included!
Bundled with this book is a CD-ROM containing **The ARRL Antenna Book** in its entirety, using the popular Adobe® Reader® software for Microsoft® Windows® and Macintosh® systems. View, search and print from the entire text, including images, photographs, drawings…**everything!**

The CD-ROM contains additional utility programs, including:

- **YW**—Yagi for Windows
- **TLW**—Transmission Line for Windows
- **HFTA**—HF Terrain Assessment for Windows
- **Range-Bearing**— compute range/bearing or latitude/longitude
- **Arrayfeed1**— designing phased-array feed systems

- **EZNEC-ARRL**— antenna modeling for Windows

PLUS propagation forecast tables for more than 170 locations around the world for all portions of the solar cycle!

CONTENTS

Safety First
Antenna Fundamentals
The Effects of Ground
Antenna Modeling and System Planning
Loop Antennas
Low-Frequency Antennas
Multiband Antennas
Multielement Arrays
Broadband Antenna Matching
Log Periodic Arrays
HF Yagi Arrays

Quad Arrays
Long-Wire and Traveling-Wave Antennas
Direction Finding Antennas
Portable Antennas
Mobile and Maritime Antennas
Repeater Antenna Systems
VHF and UHF Antenna Systems
Antenna Systems for Space Communications
Antenna Materials and Accessories
Antenna Products Suppliers
Antenna Supports

Radio Wave Propagation
Transmission Lines
Coupling the Transmitter to the Line
Coupling the Line to the Antenna
Antenna and Transmission-Line Measurements
Smith Chart Calculations

Includes a comprehensive glossary and index

Published by:

ARRL The national association for **AMATEUR RADIO**

225 Main Street, Newington, CT 06111-1494 USA

www.arrl.org

The ARRL

Antenna Book

21st Edition

Editor
R. Dean Straw, N6BV

Contributing Editors
L. B. Cebik, W4RNL
Dave Hallidy, K2DH
Dick Jansson, WD4FAB
Roy Lewallen, W7EL
Rudy Severns, N6LF
Frank Witt, AI1H

Production
Michelle Bloom, WB1ENT
Sue Fagan, KB1OKW—Cover Art
Jodi Morin, KA1JPA
David Pingree, N1NAS
Kathy Ford

Software Beta Testers
Ahti Aintila, OH2RZ
Alan Bloom, N1AL
L. B. Cebik, W4RNL
Loney Duncan, WØGZV
Chuck Hutchinson, K8CH
Steve London, N2IC
Dan Maguire, AC6LA
Steve Miller, N8SM (SK)
Bob Neece, KØKR,
Danny Richardson, K6MHE
Rudy Severns, N6LF
Jim Tabor, KU5S
Bill Tippett, W4ZV
Don Toman, K2KQ
Pete Smith, N4ZR
Scott Tuthill, K7ZO
Frank Witt, AI1H.

The Covers:

Tower photo at sunset (front and back): Tower and beam at the station of Francisco R.F. Aragao, PT2TD, in Brasilia, Brazil.

Center image: Kurt Andress, K7NV, working on 40-meter Yagi at N6RO in Oakley, CA. Photo by Dean Straw, N6BV.

Upper right image: UHF antenna. Photo credit: ShutterStock.com.

Lower right image: Some of the members of the C5Z contest DXpedition near Banjul, The Gambia. Photo by Henryk Kotowski, SMØJHF.

We strive to produce books without errors. Sometimes mistakes do occur, however. When we become aware of problems in our books (other than obvious typographical errors that should not cause our readers any problems) we post an Adobe Portable Document Format (PDF) file on ARRLWeb. If you think you have found an error, please check **www.arrl.org/notes** for corrections. If you don't find a correction there, please let us know, either using the Feedback Form in the back of this book or by sending an e-mail to **pubsfdbk@arrl.org**.

Foreword

We are pleased to offer the 21st edition of *The ARRL Antenna Book*. Since the first edition in September 1939, each new *Antenna Book* has provided more and better information about the fascinating subject of radio antennas. We've sold more than a million *Antenna Books* over the years to amateurs and professionals alike, making it one of the most successful books in our extensive lineup of publications.

Fundamentals about antennas rarely change from edition to edition, but modern application of these fundamentals can result in more highly optimized or specialized antennas. For example, many of the antennas in this new edition benefit directly from advances in sophisticated computer modeling.

We usually update at least 20% of the material in a new edition, and this book is no exception. There have been major revisions in the following chapters:

- Chapter 2: Updated information the concept of "gain."
- Chapter 6: Further insights into the importance of low elevation angles for the lower frequencies, plus a whole new section on NVIS (Near Vertical Incidence Skywave) operation.
- Chapter 8: Completely new section on feeding of phased arrays by W7EL.
- Chapter 13: Updates on Beverage receiving antennas.
- Chapter 14: New "tape-measure" portable Yagi for fox hunting.
- Chapter 16: New information on mobile "screwdriver" antennas.
- Chapter 23: Expanded section on ionospheric area-coverage maps.
- Chapter 27: New section on S-parameters, as used in Vector Network Analyzers (VNAs)

We are fortunate to have the expertise of some well-known and highly talented authorities, who either wrote or reviewed a number of chapters for technical accuracy:

- Rudy Severns, N6LF, and Roy Lewallen, W7EL—low-frequency antennas.
- LB Cebik, W4RNL—Modeling antennas.
- Dick Jansson, WD4FAB—satellite antennas.
- Dave Hallidy, K2DH—EME arrays.
- Bob Hunsucker, AB7VP, and Carl Luetzelschwab, K9LA—HF propagation.

In addition, some exceptional software writers have contributed programs and data for the *Antenna Book*.

- Roy Lewallen, the author of *EZNEC*, has created a special *EZNEC ARRL* program, just for the *Antenna Book*. *EZNEC ARRL* uses the multitude of specialized modeling files also included on the CD-ROM. These models were used in almost every chapter in the book.
- W7EL has also supplied *Arrayfeed1.exe*, a program to design feed systems for phased-arrays.
- Dr Peter Guth and the US Naval Academy have again graciously allowed ARRL to include the versatile *MicroDEM* mapping program on the CD-ROM. *MicroDEM* can easily and quickly generate customized terrain files for the *HFTA* terrain-assessment program, as well as map terrain all around the country using free US topographic data files from the Internet.
- Jim Tabor, NU5S, wrote *GeoAlert-ARRL*, a wonderful freeware program to track propagation trends and to keep tabs on the latest Internet propagation bulletins.
- Dean Straw, N6BV, editor of *The ARRL Antenna Book* has updated and upgraded his *YW* (Yagi for Windows), *TLW* (Transmission Line for Windows) and *HFTA* (HF Terrain Assessment) programs from the 20th edition. A large number of statistical elevation-angle files for QTHs all around the world are included as well. N6BV has also written a new *Range-Bearing* program that is included on the CD-ROM.
- Also included on the CD-ROM are DOS-based utility programs by several authors that analyze antenna tuners, design mobile antennas and LPDAs, and that scale Yagis for *YW*.
- Are you planning on going on a DXpedition to somewhere you've never been before? The CD-ROM now includes both Simplified and Detailed propagation prediction tables for more than 150 QTHs all around the world. Even if you don't journey to distant lands, these tables will give you plenty of insight on planning contesting or DXing strategies—They can also help you set up that Saturday afternoon schedule with your uncle Harry in Cleveland!

You now have in one place the information you need to design your own complete antenna system scientifically—the elevation angles to aim for from your part of the world and the effects of your own local terrain.

As usual, in a publishing effort of this magnitude, errors creep into the process, despite our best efforts. We appreciate hearing from you, our readers, about errors or about suggestions on how future editions might be made even more useful to you. A form for mailing your comments is included at the back of the book, or you can e-mail us at: **pubsfdbk@arrl.org**.

David Sumner, K1ZZ
Executive Vice President
Newington, Connecticut
February 2007

Contents

Schematic Symbols Used in Circuit Diagrams

RESISTORS
FIXED VARIABLE PHOTO
ADJUSTABLE TAPPED THERMISTOR t°

CAPACITORS
FIXED NON-POLARIZED SPLIT-STATOR
ELECTROLYTIC VARIABLE FEED-THROUGH

INDUCTORS
AIR-CORE ADJUSTABLE PHASING
IRON-CORE OR
FERRITE-BEAD TAPPED

METERS
*~ ■~ V, mV,
~ A, mA, |m~ A

WIRING
CONDUCTORS NOT JOINED CONDUCTORS JOINED SHIELDED WIRE OR COAXIAL CABLE
TERMINAL ADDRESS OR DATA BUS MULTIPLE CONDUCTOR CABLE

SWITCHES
SPST SPDT NORMALLY OPEN
TOGGLE
NORMALLY CLOSED
MULTIPOINT MOMENTARY THERMAL

BATTERIES
SINGLE CELL MULTI CELL

GROUNDS
CHASSIS EARTH A-ANALOG D-DIGITAL

DIODES (D#)
LED (DS#) VOLTAGE VARIABLE CAPACITOR THYRISTOR (SCR) BRIDGE RECTIFIER
DIODE/RECTIFIER
ZENER SCHOTTKY TUNNEL TRIAC (U#)
T T G

TRANSFORMERS
AIR CORE ADJUSTABLE INDUCTANCE ADJUSTABLE COUPLING
WITH CORE WITH LINK
3-PIN CERAMIC RESONATOR

MISCELLANEOUS
ANTENNA FUSE
QUARTZ CRYSTAL HAND KEY
MOT MOTOR Z ASSEMBLY OR MODULE (OTHER THAN IC)

TRANSISTORS
PNP P-CHANNEL P-CHANNEL P-CHANNEL P-CHANNEL P-CHANNEL
B C E E B2 B1 G D S G D S G2 G1 D S G D S
NPN N-CHANNEL N-CHANNEL N-CHANNEL N-CHANNEL N-CHANNEL
B C E E B2 B1 G D S G D S G2 G1 D S G D S
BIPOLAR UJT JUNCTION FET SINGLE-GATE DUAL-GATE SINGLE-GATE
DEPLETION MODE MOSFET ENHANCEMENT MODE MOSFET

LOGIC (U#)
AND NAND
OR NOR
XOR INVERT
SCHMITT OTHER

RELAYS
SPST SPDT DPDT
THERMAL

INTEGRATED CIRCUITS (U#)
GENERAL AMPLIFIER OTHER
OP AMP

CONNECTORS
COMMON CONNECTIONS LABEL PHONE JACK PHONE PLUG
CONTACTS
MALE FEMALE
COAXIAL CONNECTORS
FEMALE MALE
MULTIPLE, MOVABLE
MULTIPLE, FIXED
240 V FEMALE
GROUND
FEMALE MALE MALE CHASSIS-MOUNT
HOT 120 V NEUT HOT 120 V HOT 120 V NEUT
GND GND GND

TUBES
TUBE ELEMENTS
ANODE HEATER OR FILAMENT
GRID GAS FILLED
CATHODE COLD CATHODE
DEFLECTION PLATES
TRIODE PENTODE CRT

LAMPS
INCANDESCENT NEON (AC)

vi

About the ARRL

The seed for Amateur Radio was planted in the 1890s, when Guglielmo Marconi began his experiments in wireless telegraphy. Soon he was joined by dozens, then hundreds, of others who were enthusiastic about sending and receiving messages through the air—some with a commercial interest, but others solely out of a love for this new communications medium. The United States government began licensing Amateur Radio operators in 1912.

By 1914, there were thousands of Amateur Radio operators—hams—in the United States. Hiram Percy Maxim, a leading Hartford, Connecticut inventor and industrialist, saw the need for an organization to band together this fledgling group of radio experimenters. In May 1914 he founded the American Radio Relay League (ARRL) to meet that need.

Today ARRL, with approximately 150,000 members, is the largest organization of radio amateurs in the United States. The ARRL is a not-for-profit organization that:
- promotes interest in Amateur Radio communications and experimentation
- represents US radio amateurs in legislative matters, and
- maintains fraternalism and a high standard of conduct among Amateur Radio operators.

At ARRL headquarters in the Hartford suburb of Newington, the staff helps serve the needs of members. ARRL is also International Secretariat for the International Amateur Radio Union, which is made up of similar societies in 150 countries around the world.

ARRL publishes the monthly journal *QST*, as well as newsletters and many publications covering all aspects of Amateur Radio. Its headquarters station, W1AW, transmits bulletins of interest to radio amateurs and Morse code practice sessions. The ARRL also coordinates an extensive field organization, which includes volunteers who provide technical information and other support services for radio amateurs as well as communications for public-service activities. In addition, ARRL represents US amateurs with the Federal Communications Commission and other government agencies in the US and abroad.

Membership in ARRL means much more than receiving *QST* each month. In addition to the services already described, ARRL offers membership services on a personal level, such as the ARRL Volunteer Examiner Coordinator Program and a QSL bureau.

Full ARRL membership (available only to licensed radio amateurs) gives you a voice in how the affairs of the organization are governed. ARRL policy is set by a Board of Directors (one from each of 15 Divisions). Each year, one-third of the ARRL Board of Directors stands for election by the full members they represent. The day-to-day operation of ARRL HQ is managed by a Chief Executive Officer.

No matter what aspect of Amateur Radio attracts you, ARRL membership is relevant and important. There would be no Amateur Radio as we know it today were it not for the ARRL. We would be happy to welcome you as a member! (An Amateur Radio license is not required for Associate Membership.) For more information about ARRL and answers to any questions you may have about Amateur Radio, write or call:

ARRL—The national association for Amateur Radio
225 Main Street
Newington CT 06111-1494
Voice: 860-594-0200
Fax: 860-594-0259
E-mail: **hq@arrl.org**
Internet: **www.arrl.org/**

Prospective new amateurs call (toll-free):
800-32-NEW HAM (800-326-3942)
You can also contact us via e-mail at **newham@arrl.org**
or check out *ARRLWeb* at **http://www.arrl.org/**

FEEDBACK

Please use this form to give us your comments on this book and what you'd like to see in future editions, or e-mail us at **pubsfdbk@arrl.org** (publications feedback). If you use e-mail, please include your name, call, e-mail address and the book title, edition and printing in the body of your message. Also indicate whether or not you are an ARRL member.

Where did you purchase this book?
☐ From ARRL directly   ☐ From an ARRL dealer

Is there a dealer who carries ARRL publications within:
☐ 5 miles   ☐ 15 miles   ☐ 30 miles of your location?   ☐ Not sure.

License class:
☐ Novice   ☐ Technician   ☐ Technician with code   ☐ General   ☐ Advanced   ☐ Amateur Extra

Name _____   ARRL member? ☐ Yes ☐ No

Call Sign _____

Daytime Phone (   ) _____   Age _____

Address _____

City, State/Province, ZIP/Postal Code_____E-mail: _____

If licensed, how long? _____

Other hobbies_____

_____

Occupation _____

For ARRL use only	ANT BK
Edition	0 21 22 23 24 25 26
Printing 1 2 3 4 5 6 7 8 9 10 11 12	

From   _____

     _____

     _____

EDITOR, ARRL ANTENNA BOOK
ARRL—THE NATIONAL ASSOCIATION FOR
   AMATEUR RADIO
225 MAIN STREET
NEWINGTON CT 06111-1494

— — — — — — — — — — — — — — — — — please fold and tape — — — — — — — — — — — — — — — — — —

Safety First

Safety begins with your attitude. If you make it a habit to plan your work carefully and to consider the safety aspects of a project before you begin the work, you will be much safer than "Careless Carl," who just jumps in, proceeding in a haphazard manner. Learn to have a positive attitude about safety. Think about the dangers involved with a job before you begin the work. Don't be the one to say, "I didn't think it could happen to me."

Having a good attitude about safety isn't enough, however. You must be knowledgeable about common safety guidelines and follow them faithfully. Safety guidelines can't possibly cover all the situations you might face, but if you approach a task with a measure of "common sense," you should be able to work safely.

This chapter offers some safety guidelines and protective measures for you and your Amateur Radio station. You should not consider it to be an all-inclusive discussion of safety practices, though. Safety considerations will affect your choice of materials and assembly procedures when building an antenna. Other chapters of this book will offer further suggestions on safe construction practices. For example, Chapter 22 includes some very important advice on a tower installation.

PUTTING UP SIMPLE WIRE ANTENNAS

No matter what type of antenna you choose to erect, you should remember a few key points about safety. If you are using a slingshot or bow and arrow to get a line over a tree, make sure you keep everyone away from the "downrange" area. Hitting one of your helpers with a rock or fishing sinker is considered not nice, and could end up causing a serious injury.

Make sure the ends of the antenna are high enough to be out of reach of passers-by. Even when you are transmitting with low power there may be enough voltage at the ends of your antenna to give someone nasty "RF burns." If you have a vertical antenna with its base at ground level, build a wooden safety fence around it at least 4 feet away from it. Do not use metal fence, as this will interfere with the proper operation of the antenna. Be especially certain that your antenna is not close to any power wires. That is the only way you can be sure it won't come in contact with them!

Antenna work often requires that one person climb up on a tower, into a tree or onto the roof of a house. Never work alone! Work slowly, thinking out each move before you make it. The person on the ladder, tower, tree or rooftop should wear a safety belt, and keep it securely anchored. It is helpful (and safe!) to tie strings or lightweight ropes to all tools. If your tools are tied on, you'll save time getting them back if you drop them, and you'll greatly reduce the risk of injuring a helper on the ground. (There are more safety tips for climbing and working on towers later in this chapter. Those tips apply to any work that you must do above the ground to install even the simplest antenna.)

Tower Safety

Working on towers and antennas is dangerous, and possibly fatal, if you do not know what you are doing. Your tower and antenna can cause serious property damage and personal injury if any part of the installation should fail. Always use the highest quality materials in your system. Follow the manufacturer's specifications, paying close attention to base pier and guying details. Do not overload the tower. If you have any doubts about your ability to work on your tower and antennas safely, contact another amateur with experience in this area or seek professional assistance.

Chapter 22, Antenna Supports, provides more detailed guidelines for constructing a tower base and putting up a tower. It also explains how to properly attach guy wires and install guy anchors in the ground. These are extremely important parts of a tower installation, and

you should not take shortcuts or use second-rate materials. Otherwise the strength and safety of your entire antenna system may be compromised.

Any mechanical job is easier if you have the right tools. Tower work is no exception. In addition to a good assortment of wrenches, screwdrivers and pliers, you will need some specialized tools to work safely and efficiently on a tower. You may already own some of these tools. Others may be purchased or borrowed. Don't start a job until you have assembled all of the necessary tools. Shortcuts or improvised tools can be fatal if you gamble and lose at 70 feet in the air. The following sections describe in detail the tools you will need to work safely on a tower.

CLOTHING

The clothing you wear when working on towers and antennas should be selected for maximum comfort and safety. Wear clothing that will keep you warm, yet allow complete freedom of movement. Long denim pants and a long-sleeve shirt will protect you from scrapes and cuts. (A pull-on shirt, like a sweat shirt with no openings or buttons to snag on tower parts, is best.) Wear work shoes with heavy soles, or better yet, with steel shanks (steel inserts in the soles), to give your feet the support they need to stand on a narrow tower rung.

Gloves are necessary for both the tower climber and all ground-crew members. Good quality leather gloves will protect hands from injury and keep them warm. They also offer protection and a better grip when you are handling rope. In cooler weather, a pair of gloves with light insulation will help keep your hands warm. The insulation should not be so bulky as to inhibit movement, however.

Ground-crew members should have hard hats for protection in case something falls from the tower. It is not uncommon for the tower climber to drop tools and hardware. A wrench dropped from 100 feet will bury itself several inches in soft ground; imagine what it might do to an unprotected skull.

SAFETY BELT AND CLIMBING ACCESSORIES

Any amateur with a tower must own a high-quality safety belt, such as the one shown in **Fig 1**. *Do not attempt* to climb a tower, even a short distance, without a belt. The climbing belt is more than just a safety device for the experienced climber. It is a tool to free up both hands for work. The belt allows the climber to lean back away from the tower to reach bolts or connections. It also provides a solid surface to lean against to exert greater force when hoisting antennas into place.

A climber must trust his life to his safety belt. For this reason, nothing less than a professional quality, commercially made, tested and approved safety belt is acceptable. Check the suppliers' list in Chapter 21, Antenna Product Suppliers, and ads in *QST* for suppliers of climbing belts and accessories. Examine your belt for defects

Fig 1—Bill Lowry, W1VV, uses a good quality safety belt, a requirement for working on a tower. The belt should contain large steel loops for the strap snaps. Leather loops at the rear of the belt are handy for holding tools. (*Photo by K1WA*)

before each use. If the belt or lanyard (tower strap) are cracked, frayed or worn in any way, destroy the damaged piece and replace it with a new one. You should never have to wonder if your belt will hold.

Along with your climbing belt, you should seriously consider purchasing some climbing accessories. A canvas bucket is a great help for carrying tools and hardware up the tower. Two buckets, a large one for carrying tools and a smaller one for hardware, make it easier to find things when needed. A few extra snap hooks like those on the ends of your belt lanyard are useful for attaching tool bags and equipment to the tower at convenient spots. These hooks are better than using rope and tying knots because in many cases they can be hooked and unhooked with one hand.

Many hams use climbing belts such as shown in Fig 1. But fully integrated fall-arrest and positioning safety harnesses are preferable. The model ASL-301 in **Fig 2** has a D-ring on the back of the harness to which a safety lanyard is attached. These harnesses are available through Champion Radio Products, Box 572, Woodinville, WA 98072, **www.championradio.com**.

Rope and Pulley

Every amateur who owns a tower should also own a

Fig 2—Fall-arrest safety harness integrated with positioning safety belt for tower climbing. *(Courtesy of Champion Radio Products)*

Fig 4—A gin pole is a mechanical device that can be clamped to a tower leg to aid in the assembly of sections as well as the installation of the mast. The aluminum tubing extends through the clamp and may be slipped into position before the tubing clamp is tightened. A rope should be routed through the tubing and over the pulley mounted at the top.

Fig 3—A good quality rope and pulley are essential for anyone working on towers and antennas. This pulley is encased in wood so the rope cannot jump out of the pulley wheel and jam.

good quality rope at least twice as long as the tower height. The rope is essential for safely erecting towers and installing antennas and cables. For most installations, a good quality $1/2$-inch diameter manila hemp rope will do the job, although a thicker rope is stronger and may be easier to handle. Some types of polypropylene rope are acceptable also; check the manufacturer's strength ratings. Nylon rope is not recommended because it tends to stretch and cannot be securely knotted without difficulty.

Check your rope before each use for tearing or chafing. Do not attempt to use damaged rope; if it breaks with a tower section or antenna in mid-air, property damage and personal injury are likely results. If your rope should get wet, let it air dry thoroughly before putting it away.

Another very worthwhile purchase is a pulley like the one shown in **Fig 3**. Use the right size pulley for your rope. Be sure that the pulley you purchase will not jam or bind as the rope passes through it.

THE GIN POLE

A gin pole, like the one shown in **Fig 4**, is a handy device for working with tower sections and masts. This gin pole is designed to clamp onto one leg of Rohn No. 25 or 45 tower. The tubing, which is about 12 feet long,

Fig 5—The assembly of tower sections is made simple when a gin pole is used to lift each one into position. Note that the safety belts of both climbers are fastened below the pole, thereby preventing the strap from slipping over the top section. *(Photo by K1WA)*

has a pulley on one end. The rope is routed through the tubing and over the pulley. When the gin pole is attached to the tower and the tubing extended into place, the rope may be used to haul tower sections or the mast into place. **Fig 5** shows the basic process. A gin pole can be expensive for an individual to buy, especially for a one-time tower installation. Some radio clubs own a gin pole for use by their members. Stores that sell tower sections to amateurs and commercial customers frequently will rent a gin pole to erect the tower. If you attempt to make your own gin pole, use materials heavy enough for the job. Provide a means for securely clamping the pole to the tower. There are many cases on record where homemade gin poles have failed, sending tower sections crashing down amidst the ground crew.

When you use a gin pole, make every effort to keep the load as vertical as possible. Although gin poles are strong, you are asking for trouble if you apply too much lateral force.

INSTALLING ANTENNAS ON THE TOWER

All antenna installations are different in some respects. Therefore, thorough planning is the most important first step in installing any antenna. At the beginning, before anyone climbs the tower, the whole process should be thought through. The procedure should be discussed to be sure each crew member understands what is to be done. Plan how to work out all bugs. Consider what tools and parts must be assembled and what items must be taken up the tower. Extra trips up and down the tower can be avoided by using forethought.

Getting ready to raise a beam requires planning. Done properly, the actual work of getting the antenna into position can be accomplished quite easily with only one person at the top of the tower. The trick is to let the ground crew do all the work and leave the person on the tower free to guide the antenna into position.

Before the antenna can be hoisted into position, the tower and the area around it must be prepared. The ground crew should clear the area around the base while someone climbs the tower to remove any wire antennas or other objects that might get in the way. The first person to climb the tower should also rig the rope and pulley that will be used to raise the antenna. The time to prepare the tower is before the antenna leaves the ground, not after it becomes hopelessly entwined with your 3.5-MHz dipole.

SOME TOWER CLIMBING TIPS

The following tower climbing safety tips were compiled by Tom Willeford, N8ETU. The most important safety factor in any kind of hazardous endeavor is the right attitude. Safety is important and worthy of careful consideration and implementation. The right attitude toward safety is a requirement for tower climbers. Lip service won't do, however; safety must be practiced.

The safe ham's safety attitude is simple: *Don't take any unnecessary chances*. There are no exceptions to this plain and simple rule. It is the first rule of safety and, of course, of climbing. The second rule is equally simple: *Don't be afraid to terminate an activity* (climbing, in this case) at any time if things don't seem to be going well.

Take time to plan your climb; this time is never wasted, and it's the first building block of safety. Talk the climb over with friends who will be helping you. Select the date and alternative dates to do the work. Choose someone to be responsible for all activities on the ground and for all communication with the climbers. Study the structure to be climbed and choose the best route to your objective. Plan emergency ascent and descent paths and methods.

Make a list of emergency phone numbers to keep by your phone, even though they may never be used. Develop a plan for rescuing climbers from the structure, should that become necessary.

Give careful thought to how much time you will need to complete the project. Allow enough time to go up, do the work, and then climb down during daylight hours. Include time for resting during the climb and for completing the work in a quality fashion. Remember that the

Fig 6—If the switch box feeding power to equipment on your tower is equipped with a lock-out hole, use it. With a lock through the hole on the box, the power cannot be accidentally turned back on. (*Photos courtesy of American ED CO®, at left, and Osborn Mfg Corp, at right.*)

temperature changes fast as the sun goes down. Climbing up or down a tower with cold hands and feet is very difficult—and dangerous.

Give careful consideration to the weather, and climb only in good weather. Investigate wind conditions, the temperature, and the weather forecast. The weather can change quickly, so if you're climbing a really tall tower, it may be a good idea to have a weather alert radio handy during the climb. *Never* climb a wet tower.

The person who is going to do the climbing should be the one to disconnect and tag all sources of power to the structure. All switches or circuit breakers should be labeled clearly with DO NOT TOUCH instructions. Use locks on any switches designed to accept them. (See **Fig 6**.) Only the climber should reconnect power sources.

An important part of the climbing plan is to review notes on the present installation and any previous work. It's a good idea to keep a notebook, listing every bolt and nut size on your tower/antenna installation. Then, when you have to go up to make repairs, you'll be able to take the minimum number of tools with you to do the job. If you take too many tools up the tower, there is a much greater chance of dropping something, risking injury to the ground crew and possibly damaging the tool.

It is also a good idea to review the instruction sheets and take them with you. In other words, plan carefully what you are going to do, and what you'll need to do it efficiently and safely.

It's better to use a rope and pulley to hoist tools. Climbing is hard work and there's no sense making it more difficult by carrying a big load of tools. Always rig the pulley and rope so the ground crew raises and lowers tools and equipment.

Climbing Equipment

Equipment is another important safety consideration. By equipment, we don't just mean tools. We mean safety equipment. Safety equipment should be selected and cared for as if your life depends on it—because it does!

The list of safety equipment essential to a safe climb and safe work on the tower should include:
1) A first class safety belt,
2) Safety glasses,
3) Hard hat,
4) Long-sleeved, pull-over shirt with no buttons or openings to snag (long sleeves are especially important for climbing wooden poles),
5) Long pants without cuffs,
6) Firm, comfortable, steel-shank shoes with no-slip soles and well-defined heels, and
7) Gloves that won't restrict finger movement (insulated gloves if you MUST work in cold weather).

Your safety belt should be approved for use on the structure you are climbing. Different structures may require different types of safety hooks or straps. The belt should be light weight, but strength should not be sacrificed to

Fig 7—Mark Wilson, K1RO, shows the proper way to attach a safety hook, with the hook opening facing away from the tower. That way the hook can't be accidentally released by pressing it against a tower leg.

save weight. It should fit you comfortably. All moving parts, such as snap hooks, should work freely. You should inspect safety belts and harnesses carefully and thoroughly before each climb, paying particular attention to stitching, rivets and weight-bearing mechanical parts.

Support belt hooks should always be hooked to the D rings in an outward configuration. That is, the opening part of the hook should face away from the tower when engaged in the D rings (see **Fig 7**). Hooks engaged this way are easier to unhook deliberately but won't get squeezed open by a part of the tower or engage and snag a part of the tower while you are climbing. The engagement of these hooks should always be checked visually. A snapping hook makes the same sound whether it's engaged or not. Never check by sound—look to be sure the hook is engaged properly before trusting it.

Remember that the D rings on the safety belt are for support hooks *only*. No tools or lines should be attached to these hooks. Such tools or lines may prevent the proper engagement of support belt hooks, or they may foul the hooks. At best, they could prevent the release of the hooks in an emergency. No one should have to disconnect a support hook to get a tool and then have to reconnect the support hook before beginning to work again. That's foolish.

Equipment you purchase new is best. Homemade belts or home-spliced lines are dangerous. Used belts may have worn or defective stitching, or other faulty components. Be careful of so-called "bargains" that could cost you your life.

Straps, lanyards and lines should be as short as possible. Remember, in general knots reduce the load strength of a line by approximately 50%.

Before actually climbing, check the structure visually. Review the route. Check for obstacles, both natural (like wasp's nests) and man-made. Check the structure supports and add more if necessary. Guy wires can be obstacles to the climb, but it's better to have too many supports than not enough. Check your safety belt, support belts and hooks at the base of the tower. Really test them before you need them. Never leave the ground without a safety belt—even 5 or 10 feet. After all of this, the climb will be a "cake walk" if you are careful.

Climb slowly and surely. Don't overreach or overstep. Patience and watchfulness is rewarded with good hand and foot holds. Take a lesson from rock climbers. Hook on to the tower and rest periodically during the climb. Don't try to rest by wedging an arm or leg in some joint; to rest, hook on. Rests provide an opportunity to review the remainder of the route and to make sure that your safety equipment feels good and is working properly. Rest periods also help you conserve a margin of energy in case of difficulty.

Finally, keep in mind that the most dangerous part of working on a tower occurs when you are actually climbing. Your safety equipment is not hooked up at this time, so be extra careful during the ascent or descent.

You must climb the tower to install or work on an antenna. Nevertheless, any work that can be done on the ground should be done there. If you can do any assembly or make any adjustments on the ground, that's where you should do the work! The less time you have to spend on the tower, the better off you'll be.

When you arrive at the work area, hook on to the tower and review what you have to do. Determine the best position to do the work from, disconnect your safety strap and move to that position. Then reconnect your safety strap at a safe spot, away from joints and other obstacles. If you must move around an obstacle, try to do it while hooked on to the tower. Find a comfortable position and go to work. Don't overreach—move to the work.

Use the right tool for the task. If you don't have it, have the ground crew haul it up. Be patient. Lower tools, don't drop them, when you are finished with them. Dropped tools can bounce and cause injury or damage, or can be broken or lost. It's a good idea to tie a piece of string or light rope to the tools, and to tie the other end to the tower or some other point so if you do drop a tool, it won't fall all the way to the ground. Don't tie tools to the D ring or your safely belt, however!

Beware of situations where an antenna may be off balance. It's hard to obtain the extra leverage needed to handle even a small beam when you are holding it far from the balance point. Leverage can apply to the climber as well as the device being levered. Many slips and skinned knuckles result from such situations. A severely injured hand or finger can be a real problem to a climber.

Before descending, be sure to check all connections and the tightness of all the bolts and nuts that you have worked with. Have the ground crew use the rope and pulley to lower your tools. Lighten your load as much as possible. Remember, you're more tired coming down than going up. While still hooked on, wiggle your toes and move a little to get your senses working again. Check your downward route and begin to descend slowly and even more surely than you went up. Rest is even more important during the descent.

The ground captain is the director of all activities on the ground, and should be the only one to communicate with a person on a tower. Hand-held transceivers can be very helpful for this communication, but no one else should transmit to the workers on the tower. Even minor confusion or misunderstanding about a move to be made could be very dangerous.

"Antenna parties" can be lots of fun, but the joking and fooling around should wait until the job is done and everyone is down safely. Save the celebrating until after the work is completed, even for the ground crew.

These are just a few ideas on tower climbing safety; no list can include everything that you might run into. Check Chapter 22 for additional ideas. *Just remember— you can't be too careful when climbing*. Keep safety in mind while doing antenna work, and help ensure that after you have fallen *for* ham radio, you don't fall *from* ham radio.

THE TOWER SHIELD

A tower can be legally classified as an "attractive nuisance" that could cause injuries. You should take some precautions to ensure that "unauthorized climbers" can't get hurt on your tower. This tower shield was originally described by Baker Springfield, W4HYY, and Richard Ely, WA4VHM, in September 1976 *QST*, and should eliminate the worry.

Generally, the attractive-nuisance doctrine applies to your responsibility to trespassers on your property. (The law is much stricter with regard to your responsibility to an invited guest.) You should expect your tower to attract children, whether they are already technically trespassing


Fig 8—Z-bracket component pieces.

Fig 9—Assembly of the Z bracket.

Fig 10—Installation of the shield on a tower rung.

Notes:

1. Standard Rodstock 1/4"-20 X 36" was Used.
2. Two Pieces were Cut from Rod Stock.
   Each Approximately 10 7/8".
3. Make The Three Bends of The Rod in Vise.
4. Two Nuts 1/4-20 of The Same Threads as
   Rods. Jam or Lock Together. This Makes
   a Handle Stop.

Fig 11—Removable handle construction.

or whether the tower itself lures them onto your property. A tower is dangerous to children, especially because of their inability to appreciate danger. (What child could resist trying to climb a tower once they see one?) Because of this danger, you have a legal duty to exercise reasonable care to eliminate the danger or otherwise protect children against the perils of the attraction.

The tower shield is composed simply of panels that enclose the tower and make climbing practically impossible. These panels are 5 feet in height and are wide enough to fit snugly between the tower legs and flat against the rungs. A height of 5 feet is sufficient in almost every case. The panels are constructed from 18-gauge galvanized sheet metal obtained and cut to proper dimensions from a local sheet-metal shop. A lighter gauge could probably be used, but the extra physical weight of the heavier gauge is an advantage if no additional means of securing the panels to the tower rungs are used. The three types of metals used for the components of the shield are supposedly rust proof and nonreactive. The panels are galvanized sheet steel, the brackets aluminum, and the screws and nuts are brass. For a triangular tower, the shield consists of three panels, one for each of the three sides, supported by two brackets. Construct these brackets from 6-inch pieces of thin aluminum angle stock. Bolt two of the pieces together to form a Z bracket (see **Figs 8**, **9** and **10**). The Z brackets are bolted together with binding head brass machine screws.

Lay the panels flat for measuring, marking and drilling. First measure from the top of the upper mounting rung on the tower to the top of the bottom rung. (Mount-

ing rungs are selected to position the panel on the tower.) Then mark this distance on the panels. Use the same size brass screws and nuts throughout the shield. Bolt the top vertical portion of each Z bracket to the panel. Drill the mounting-screw holes about 1 inch from the end of the Z

Fig 12— Installed tower shield. Note the holes for using the handles.

brackets so there is an offset clearance between the Z-bracket binding-screw holes and the panel-bracket mounting-screw holes. Drill holes in each panel to match the Z-bracket holes.

The panels are held on the tower by their own weight. They are not easy to grasp because they fit snugly between the tower legs. If you feel a need for added safety against deliberate removal of the panels, this can be accomplished by means of tie wires. Drill a small hole in the panel just above, just below, and in the center of each Z bracket. Run a piece of heavy galvanized wire through the top hole, around the Z bracket, and then back through the hole just below the Z bracket. Twist together the two ends of the wire. One tie wire should be sufficient for each panel, but use two if desired.

The completed panels are rather bulky and difficult to handle. A feature that is useful if the panels have to be removed often for tower climbing or accessibility is a pair of removable handles. The removable handles can be constructed from one threaded rod and eight nuts (see **Fig 11**). Drill two pair of handle holes in the panels a few inches below the top Z bracket and several inches above the bottom Z bracket. For panel placement or removal, you can hook the handles in these panel holes. The hook, on the top of the handle, fits into the top hole of each pair of the handle holes. The handle is optional, but for the effort required it certainly makes removal and replacement much safer and easier.

Fig 12 shows the shield installed on a tower. This relatively simple device could prevent an accident.

Electrical Safety

Although the RF, ac and dc voltages in most amateur stations pose a potentially grave threat to life and limb, common sense and knowledge of safety practices will help you avoid accidents. Building and operating an Amateur Radio station can be, and is for almost all amateurs, a perfectly safe pastime. However, carelessness can lead to severe injury, or even death. The ideas presented here are only guidelines; it would be impossible to cover all safety precautions. Remember, there is no substitute for common sense.

A fire extinguisher is a requirement for the well-equipped amateur station. The fire extinguisher should be of the carbon-dioxide type to be effective in electrical fires. Store it in an easy-to-reach spot and check it at recommended intervals.

Family members should know how to turn the power off in your station. They should also know how to apply artificial respiration. Many community groups offer courses on cardiopulmonary resuscitation (CPR).

AC AND DC SAFETY

The primary wiring for your station should be controlled by one master switch, and other members of your household should know how to kill the power in an emergency. All equipment should be connected to a good ground. All wires carrying power around the station should be of the proper size for the current to be drawn and should be insulated for the voltage level involved. Bare wire, open-chassis construction and exposed connections are an invitation to accidents. Remember that high-current, low-voltage power sources are just as dangerous as high-voltage, low-current sources. Possibly the most-dangerous voltage source in your station is the 120-V primary supply; it is a hazard often overlooked

because it is a part of everyday life. Respect even the lowliest power supply in your station.

Whenever possible, kill the power and unplug equipment before working on it. Discharge capacitors with an insulated screwdriver; don't assume the bleeder resistors are 100% reliable. In a power amplifier, always short the tube plate cap to ground just to be sure the supply is discharged. If you must work on live equipment, keep one hand in your pocket. Avoid bodily contact with any grounded object to prevent your body from becoming the return path from a voltage source to ground. Use insulated tools for adjusting or moving any circuitry. Never work alone. Have someone else present; it could save your life in an emergency.

National Electrical Code

The National Electrical Code® is a comprehensive document that details safety requirements for all types of electrical installations. In addition to setting safety standards for house wiring and grounding, the Code also contains a section on Radio and Television Equipment — Article 810. Sections C and D specifically cover Amateur Transmitting and Receiving Stations. Highlights of the section concerning Amateur Radio stations follow. If you are interested in learning more about electrical safety, you may purchase a copy of *The National Electrical Code* or *The National Electrical Code Handbook*, edited by Peter Schram, from the National Fire Protection Association, Batterymarch Park, Quincy, MA 02269.

Antenna installations are covered in some detail in the Code. It specifies minimum conductor sizes for different length wire antennas. For hard-drawn copper wire, the Code specifies #14 wire for open (unsupported) spans less than 150 feet, and #10 for longer spans. Copper-clad

steel, bronze or other high-strength conductors may be #14 for spans less than 150 feet and #12 wire for longer runs. Lead-in conductors (for open-wire transmission line) should be at least as large as those specified for antennas.

The Code also says that antenna and lead-in conductors attached to buildings must be firmly mounted at least 3 inches clear of the surface of the building on nonabsorbent insulators. The only exception to this minimum distance is when the lead-in conductors are enclosed in a "permanently and effectively grounded" metallic shield. The exception covers coaxial cable.

According to the Code, lead-in conductors (except those covered by the exception) must enter a building through a rigid, noncombustible, nonabsorbent insulating tube or bushing, through an opening provided for the purpose that provides a clearance of at least 2 inches or through a drilled window pane. All lead-in conductors to transmitting equipment must be arranged so that accidental contact is difficult.

Transmitting stations are required to have a means of draining static charges from the antenna system. An antenna discharge unit (lightning arrester) must be installed on each lead-in conductor (except where the lead-in is protected by a continuous metallic shield that is permanently and effectively grounded, or the antenna is permanently and effectively grounded). An acceptable alternative to lightning arrester installation is a switch that connects the lead-in to ground when the transmitter is not in use.

Grounding conductors are described in detail in the Code. Grounding conductors may be made from copper, aluminum, copper-clad steel, bronze or similar erosion-resistant material. Insulation is not required. The "protective grounding conductor" (main conductor running to the ground rod) must be as large as the antenna lead-in, but not smaller than #10. The "operating grounding conductor" (to bond equipment chassis together) must be at least #14. Grounding conductors must be adequately supported and arranged so they are not easily damaged. They must run in as straight a line as practical between the mast or discharge unit and the ground rod.

The Code also includes some information on safety inside the station. All conductors inside the building must be at least 4 inches away from conductors of any lighting or signaling circuit except when they are separated from other conductors by conduit or a nonconducting material. Transmitters must be enclosed in metal cabinets, and the cabinets must be grounded. All metal handles and controls accessible by the operator must be grounded. Access doors must be fitted with interlocks that will disconnect all potentials above 350 V when the door is opened.

Ground

An effective ground system is necessary for every amateur station. The mission of the ground system is twofold. First, it reduces the possibility of electrical shock if

something in a piece of equipment should fail and the chassis or cabinet becomes "hot." If connected properly, three-wire electrical systems ground the chassis, but older amateur equipment may use the ungrounded two-wire system. A ground system to prevent shock hazards is generally referred to as "dc ground."

The second job the ground system must perform is to provide a low-impedance path to ground for any stray RF current inside the station. Stray RF can cause equipment to malfunction and contributes to RFI problems. This low-impedance path is usually called "RF ground." In most stations, dc ground and RF ground are provided by the same system.

The first step in building a ground system is to bond together the chassis of all equipment in your station. Ordinary hookup wire will do for a dc ground, but for a good RF ground you need a low-impedance conductor. Copper strap, sold as "flashing copper," is excellent for this application, but it may be hard to find. Braid from coaxial cable is a popular choice; it is readily available, makes a low-impedance conductor, and is flexible.

Grounding straps can be run from equipment chassis to equipment chassis, but a more convenient approach is illustrated in **Fig 13**. In this installation, a $^1/_2$-inch diameter copper water pipe runs the entire length of the operating bench. A thick braid (from discarded RG-8 cable) runs from each piece of equipment to a clamp on the pipe. Copper water pipe is available at most hardware stores and home centers. Alternatively, a strip of flashing copper may be run along the rear of the operating bench.

After the equipment is bonded to a common ground bus, the ground bus must be wired to a good earth ground. This run should be made with a heavy conductor (braid is a popular choice, again) and should be as short and direct as possible. The earth ground usually takes one of two forms.

In most cases, the best approach is to drive one or more ground rods into the earth at the point where the conductor from the station ground bus leaves the house. The best ground rods to use are those available from an electrical supply house. These rods are 8 to 10 feet long and are made from steel with a heavy copper plating. Do not depend on shorter, thinly plated rods sold by some home electronics suppliers. These rods begin to rust almost immediately after they are driven into the soil, and they become worthless within a short time. Good ground rods, while more expensive initially, offer long-term protection.

If your soil is soft and contains few rocks, an acceptable alternative to "genuine" ground rods is $^1/_2$-inch diameter copper water pipe. A 6- to 8-foot length of this material offers a good ground, but it may bend while being driven into the earth. Some people have recommended that you make a connection to a water line and run water down through the copper pipe so that it forces its own

Fig 13—An effective station ground bonds the chassis of all equipment together with low-impedance conductors and ties into a good earth ground.

hole in the ground. There may be a problem with this method, however. When the ground dries, it may shrink away from the pipe and not make proper contact with the ground rod. This would provide a rather poor ground.

Once the ground rod is installed, clamp the conductor from the station ground bus to it with a clamp that can be tightened securely and will not rust. Copper-plated clamps made especially for this purpose are available from electrical supply houses, but a stainless-steel hose clamp will work too. Alternatively, drill several holes through the pipe and bolt the conductor in place.

Another popular station ground is the cold water pipe system in the building. To take advantage of this ready-made ground system, run a low-impedance conductor from the station ground bus to a convenient cold water pipe, preferably somewhere near the point where the main water supply enters the house. Avoid hot water pipes; they do not run directly into the earth. The advent of PVC (plastic) plumbing makes it mandatory to inspect the cold water system from your intended ground connection to the main inlet. PVC is an excellent insulator, so any PVC pipe or fittings rule out your cold water system for use as a station ground.

For some installations, especially those located above the first floor, a conventional ground system such as that just described will make a fine dc ground but will not provide the necessary low-impedance path to ground for RF. The length of the conductor between the ground bus and the ultimate ground point becomes a problem. For example, the ground wire may be about $1/4$ λ (or an odd multiple of $1/4$ λ) long on some amateur band. A $1/4$-λ wire acts as an impedance inverter from one end to the other. Since the grounded end is at a very low impedance, the equipment end will be at a high impedance. The likely result is RF hot spots around the station while the transmitter is operating. A ground system like this may be worse than having no ground at all.

An alternative RF ground system is shown in **Fig 14**. Connect a system of $1/4$-λ radials to the station ground bus. Install at least one radial for each band used. You

Fig 14—Here is an alternative to earth ground if the station is located far from the ground point and RF in the station is a problem. Install at least one $1/4$-λ radial for each band used.

should still be sure to make a connection to earth ground for the ac power wiring. Try this system if you have problems with RF in the shack. It may just solve a number of problems for you. Be careful, however, to prevent contact with the ends of the radials, where there is high-voltage RF for powers greater than QRP level.

Ground Noise

Noise in ground systems can affect sensitive radio equipment. It is usually related to one of three problems:

1) Insufficient ground conductor size,
2) Loose ground connections, or
3) Ground loops.

These matters are treated in precise scientific research equipment and some industrial instruments by paying attention to certain rules. The ground conductor should be at least as large as the largest conductor in the primary power circuit. Ground conductors should provide a solid connection to both ground and to the equipment being grounded. Liberal use of lock washers and star washers is highly recommended. A loose ground connection is a tremendous source of noise, particularly in a sensitive receiving system.

Ground loops should be avoided at all costs. A short discussion of what a ground loop is and how to avoid them may lead you down the proper path. A ground loop

is formed when more than one ground current is flowing in a single conductor. This commonly occurs when grounds are "daisy-chained" (series linked). The correct way to ground equipment is to bring all ground conductors out radially from a common point to either a good driven earth ground or to a cold water system.

Ground noise can affect transmitted as well as received signals. With the low audio levels required to drive amateur transmitters, and with the ever-increasing sensitivity of our receivers, correct grounding is critical.

Lightning and EMP Protection

The National Fire Protection Association (NFPA) publishes a booklet called *Lightning Protection Code* (NFPA no. 78-1983) that should be of interest to radio amateurs. For information about obtaining a copy of this booklet, write to the National Fire Protection Association, Batterymarch Park, Quincy, MA 02269. Two paragraphs of particular interest to amateurs are presented below:

"3-26 Antennas. Radio and television masts of metal, located on a protected building, shall be bonded to the lightning protection system with a main size conductor and fittings.

"3-27 Lightning arresters, protectors or antenna discharge units shall be installed on electric and telephone service entrances and on radio and television antenna lead-ins."

The best protection from lightning is to disconnect all antennas from equipment and disconnect the equipment from the power lines. Ground antenna feed lines to safely bleed off static buildup. Eliminate the possible paths for lightning strokes. Rotator cables and other control cables from the antenna location should also be disconnected during severe electrical storms.

In some areas, the probability of lightning surges entering homes via the 120/240-V line may be high. Lightning produces both electrical and magnetic fields that vary with distance. These fields can be coupled into power lines and destroy electronic components in equipment that is miles from where the lightning occurred. Radio equipment can be protected from these surges to some extent by using transient-protective devices.

ELECTROMAGMETIC PULSE AND THE RADIO AMATEUR

The following material is based on a 4-part *QST* article by Dennis Bodson, W4PWF, that appeared in the August through November 1986 issues of *QST*. The series was condensed from the National Communications System report NCS TIB 85-10.

An equipment test program demonstrated that most Amateur Radio installations can be protected from lightning and electromagnetic pulse (EMP) transients with a basic protection scheme. Most of the equipment is not susceptible to damage when all external cabling is removed. You can duplicate this stand-alone configuration simply by unplugging the ac power cord from the outlet, disconnecting the antenna feed line at the rear of the radio, and isolating the radio gear from any other long metal conductors. Often it is not practical to completely disconnect the equipment whenever it is not being used. Also, there is the danger that a lightning strike several miles away could induce a large voltage transient on the power lines or antenna while the radio is in use. You can add two transient-protection devices to the interconnected system, however, that will also closely duplicate the safety of the stand-alone configuration.

The ac power line and antenna feed line are the two important points that should be outfitted with transient protection. This is the minimum basic protection scheme recommended for all Amateur Radio installations. (For fixed installations, consideration should also be given to the rotator connections—see **Fig 15**.) Hand-held radios equipped with a "rubber duck" require no protection at the antenna jack. If a larger antenna is used with the hand-held, however, a protection device should be installed.

General Considerations

Because of the unpredictable energy content of a nearby lightning strike or other large transient, it is possible for a metal-oxide varistor (MOV) to be subjected to an energy surge in excess of its rated capabilities. This may result in the destruction of the MOV and explosive rupture of the package. These fragments can cause damage to nearby components or operators and possibly ignite flammable material. Therefore, the MOV should be physically shielded.

A proper ground system is a key factor in achieving protection from lightning and EMP transients. A low-impedance ground system should be installed to eliminate transient paths through radio equipment and to provide a good physical ground for the transient-suppression devices. A single-point ground system is recommended (**Fig 16**) to help prevent lightning from getting into the shack on the shields of antenna feed-line coaxes. Many hams use a well-grounded radio-entrance panel mounted *outside* the shack to ground their coaxes before they enter the house. **Fig 17** shows an entrance panel at K8CH's home in Michigan. All external conductors going to the radio equipment should enter and exit the station through this panel. Install all transient-suppression devices directly on the panel. Use

Legend:
P1–P2 — Plug in AC Power Transient Suppressor
C1–C2 — Coaxial Line RF Transient Suppressor
R1–R2 — Varistor Boxes and Control Cable Can Be Shielded

Antenna

C2

Antenna Rotator   R2

Rotator Control Cable

Coax (RG–8)

C1   R1

Fig 15—Transient suppression techniques applied to an Amateur Radio station.

Ground Panel (Bus Bar) #2 Gauge Solid Wire or Solid Strap

Ground   Ground   Ground   Ground   Ground

Ham Shack (System Ground)

AC Power   P2

AC Power

Coax (RG–8)

P1   AC Power

Rotator Control Cable

Audio Cable   Coax

Speaker   Power Supply   Transceiver   Antenna Matching Network   Rotator Remote Control Unit

13.8 V dc

MIC

Antenna Matching Network Control Cable

the shortest length(s) possible of #6 solid wire to connect the radio equipment case(s) to the ground bus.

Ac Power-Line Protection

Tests have indicated that household electrical wiring inherently limits the maximum transient current that it will pass to approximately 120 A. Therefore, if possible, the amateur station should be installed away from the house ac entrance panel and breaker box to take advantage of these limiting effects.

Ac power-line protection can be provided with easy-to-install, plug-in transient protectors. Ten such devices were tested for the article series in 1986. The plug-in-strip units are the best overall choice for a typical amateur installation. They provide the protection needed, they're simple to install and can be easily moved to other operating locations with the equipment.

In their tests, NCS found that the model that provided transient paths to ground from the hot and neutral lines (common mode) as well as the transient path between the hot and neutral lines (normal mode) performed best. The best model used three MOVs and a 3-electrode gas-discharge-tube arrester to provide fast operation and large power dissipation capabilities. This unit was tested repeatedly and operated without failure.

The flood of low-cost computers in the 1990s spawned a host of surge protection devices designed to limit transient voltage spikes coming from the ac line and also through the telephone line into a modem connected to a computer. Many of these devices are well-designed and can be relied upon to provide the protection they claim.

You can, however, easily find a variety of really low-cost bargain strips at flea markets and discount hardware stores. A bargain-brand $6 unit may prove to be a poor bargain indeed if it allows a spike to get through to damage your $2000 computer or $4000 transceiver.

You should be careful to find one that carries a sticker indicating that it meets Underwriters Laboratories safety standard UL 1449. This defines the minimum level of clamping voltage beyond which a surge protector will "fire" to protect the device connected to its output. The UL 1149 limit is 330 V ac. Prices for brand-name units from Tripp Lite, APC or Curtis vary from about $30 to $80, depending on how many ac sockets they have and the number of indicator lights and switched/unswitched sockets. A brand-name device is well worth the small additional cost over the bargain-basement units.

A transient suppressor requires a 3-wire outlet; the outlet should be tested to ensure all wires are properly connected. In older houses, an ac ground may have to be installed by a qualified electrician. The ac ground must be available for the plug-in transient suppressor to function properly. The ac ground of the receptacle should be attached to the station ground bus, and the plug-in receptacle should be installed on the ground panel behind the radio equipment.

Emergency Power Generators

Emergency power generators provide two major transient-protection advantages. First, the station is disconnected from the commercial ac power system. This isolates the radio equipment from a major source of damaging transients. Second, tests have shown that the emergency power generator may not be susceptible to EMP transients.

When the radio equipment is plugged directly into the generator outlets, transient protection may not be

Fig 16—At A, the proper method of tying all ground points together. The transient path to ground with a single-point ground system and use of transient suppressors is shown at B. You want to keep transients from nearby lighning strikes from getting into the radio room.

needed. If an extension cord or household wiring is used, transient protection should be employed.

An emergency power generator should be wired into the household circuit only by a qualified electrician. When properly connected, a switch is used to disconnect the commercial ac power source from the house lines before the generator is connected to them. This keeps the generator output from feeding back into the commercial power system. If this is not done, death or injury to unsuspecting linemen can result.

Feed-Line Protection

Coaxial cable is recommended for use as the trans-mission line because it provides a certain amount of transient surge protection for the equipment to which it is attached. The outer conductor shields the center conductor from the transient field. Also, the cable limits the maximum conducted transient voltage on the center by arcing the differential voltage from the center conductor to the grounded cable shield.

By providing a path to ground ahead of the radio equipment, the gear can be protected from the large currents impressed upon the antenna system by lightning and EMP. A single protection device installed at the radio antenna jack will protect the radio, but not the transmission line. To protect the transmission line, another tran-

Fig 17—Radio-entrance panel at K8CH. A flat aluminum plate serves as a common grounding point for all coax cables to prevent transients from nearby lightning strikes from getting into the shack on the feed lines. "Spark-gap" protectors to kill transients on the coax inner conductors are located behind the panel. A spark-gap protector is also used on the two open-wire feeder insulators mounted on the Plexiglas sheet behind the aluminum panel.

Table 1
RF Coaxial-Line Protectors

Manufacturer	Device	Approximate Cost (US Dollars)	Measured High-Z Clamping Voltage (Volts)
Fischer	FCC-250-300-UHF	55	393
Fischer	FCC-250-350-UHF	55	260
Fischer	FCC-250-150-UHF	55	220
Fischer	FCC-250-120-UHF	55	240
Fischer	FCC-450-120-UHF	55	120
Polyphaser	IS-NEMP	83	140
Polyphaser	IS-NEMP-1	83	150
Polyphaser	IS-NEMP-2	83	160

Note: The transmitter output power, frequency of operation, and transmission line SWR must be considered when selecting any of these devices.

sient protector must be installed between the antenna and the transmission line. (See Fig 15).

RF transient protection devices from several manufacturers were tested (see **Table 1**) using RG-8 cable equipped with UHF connectors. All of the devices shown can be installed in a coaxial transmission line. Recall that during the tests the RG-8 cable acted like a suppressor; damaging EMP energy arced from the center conductor to the cable shield when the voltage level approached 5.5 kV.

Low price and a low clamping-voltage rating must be considered in the selection of an RF transient-protection device. The lower cost devices have the higher clamping voltages, however, and the higher-cost devices have the lower clamping voltages. Because of this, medium-priced devices manufactured by Fischer Custom Communications were selected for testing. The Fischer Spikeguard Suppressors ($55 price class) for coaxial lines can be made to order to operate at a specific clamping voltage. The Fischer devices satisfactorily suppressed the damaging transient pulses, passed the transmitter RF output power without interfering with the signal, and operated effectively over a wide frequency range.

Polyphaser Corporation devices are also effective in providing the necessary transient protection. The devices available limited the transmitter RF output power to 100 W or less, however. These units cost approximately $83 each.

RF coaxial protectors should be mounted on the station ground bus bar. If the Fischer device is used, it should

be attached to a grounded UHF receptacle that will serve as a hold-down bracket. This creates a conductive path between the outer shield of the protector and the bus bar. The Polyphaser device can be mounted directly to the bus bar with the bracket provided.

Attach the transceiver or antenna matching network to the grounded protector with a short (6 foot or less) piece of coaxial cable. Although the cable provides a ground path to the bus bar from the radio equipment, it is not a satisfactory transient-protection ground path for the transceiver. Another ground should be installed between the transceiver case and the ground bus using solid #6 wire. The coaxial cable shield should be grounded to the antenna tower leg at the tower base. Each tower leg should have an earth ground connection and be connected to the single-point ground system as shown in Fig 16.

Antenna Rotators

Antenna rotators can be protected by plugging the control box into a protected ac power source and adding protection to the control lines to the antenna rotator. When the control lines are in a shielded cable, the shield must be grounded at both ends. MOVs of the proper size should be installed at both ends of the control cable. At the station end, terminate the control cable in a small metal box that is connected to the station ground bus. Attach MOVs from each conductor to ground inside the box. At the antenna end of the control cable, place the MOVs inside the rotator case or in a small metal box that is properly grounded.

For example, the Alliance HD73 antenna rotator uses a 6-conductor unshielded control cable with a maximum control voltage of 24.7 V dc. Select an MOV with a clamping voltage level 10% higher (27 V or more) so the MOV won't clamp the control signal to ground. If the control voltage is ac, be sure to convert the RMS voltage value to peak voltage when considering the clamping voltage level.

Mobile Power Supply Protection

The mobile amateur station environment exposes radio equipment to other transient hazards in addition to those of lightning and EMP. Currents as high as 300 A are switched when starting the engine, and this can produce voltage spikes of over 200 V on the vehicle's electrical system. Lightning and EMP are not likely to impact the vehicle's electrical system as much as they would that of a fixed installation because the automobile chassis is not normally grounded. This would not be the case if the vehicle is inadvertently grounded; for example, when the vehicle is parked against a grounded metal conductor. The mobile radio system has two advantages over a fixed installation: Lightning is almost never a problem, and the vehicle battery is a natural surge suppressor.

Mobile radio equipment should be installed in a way that takes advantage of the protection provided by the battery. See **Fig 18**. To do this, connect the positive power lead of the radio directly to the positive battery post, not to intermediate points in the electrical system such as the fuse box or the auxiliary contacts on the ignition switch. To prevent equipment damage or fire, in-line fuses should be installed in the positive lead where they are attached to the battery post.

An MOV should be installed between the two leads of the equipment power cord. A GE MOV (V36ZA80) is recommended for this application. This MOV provides the lowest measured clamping voltage (170 V) and is low in cost.

Mobile Antenna Installation

Although tests indicate that mobile radios can survive an EMP transient without protection for the antenna system, protection from lightning transients is still required. A coaxial-line transient suppressor should be installed on the vehicle chassis between the antenna and the radio's antenna connector.

A Fischer suppressor can be attached to a UHF receptacle that is mounted on, and grounded to, the vehicle chassis. The Polyphaser protector can be mounted on, and grounded to, the vehicle chassis with its flange. Use a short length of coaxial cable between the radio and the transient suppressor.

Clamping Voltage Calculation

When selecting any EMP-protection device to be used at the antenna port of a radio, several items must be considered. These include transmitter RF power output, the SWR, and the operating frequency. The protection device must allow the outgoing RF signal to pass without clamping. A clamping voltage calculation must be made for each amateur installation.

The RF-power input to a transmission line develops a corresponding voltage that becomes important when a voltage-surge arrester is in the line. SWR is important because of its influence on the voltage level. The maximum voltage developed for a given power input is determined by:

$$V = \sqrt{2 \times P \times Z \times SWR} \qquad \text{(Eq 1)}$$

where

P = peak power in W
Z = impedance of the coaxial cable (Ω)
V = peak voltage across the cable

Eq 1 should be used to determine the peak voltage present across the transmission line. Because the RF transient-protection devices use gas-discharge tubes, the voltage level at which they clamp is not fixed; a safety margin must be added to the calculated peak voltage. This is done

Fig 18—Recommended method of connecting mobile radio equipment to the vehicle battery and antenna.

by multiplying the calculated value by a factor of three. This added safety margin is required to ensure that the transmitter's RF output power will pass through the transient suppressor without causing the device to clamp the RF signal to ground. The final clamping voltage obtained is then high enough to allow normal operation of the transmitter while providing the lowest practical clamping voltage for the suppression device. This ensures the maximum possible protection for the radio system.

Here's how to determine the clamping voltage required. Let's assume the SWR is 1.5:1. The power output of the transceiver is 100 W PEP. RG/8 coaxial cable has an impedance of 52 Ω. Therefore:

P = 100 W
Z = 52 Ω
SWR = 1.5

Substituting these values into Eq 1:

$$V = \sqrt{2 \times 100 \times 52 \times 1.5} = 124.89 \text{ V peak}$$

Note that the voltage, V, is the peak value at the peak of the RF envelope. The final clamping voltage (FCV) is three times this value, or 374.7 V. Therefore, a coaxial-line transient suppressor that clamps at or above 375 V should be used.

The cost of a two-point basic protection scheme is estimated to be $100 for each fixed amateur station. This includes the cost of a good quality plug-in power-line protector ($45) and one Fischer coaxial-line protector ($55).

Inexpensive Transient-Protection Devices

Here are two low-cost protection devices you can assemble. They performed flawlessly in the tests.

The radio antenna connection can be protected by means of another simple device. As shown in **Fig 19**, two spark gaps (Siemens BI-A350) are installed in series at one end of a coaxial-cable T connector. Use the shortest practical lead length (about 1/4 inch) between the two spark gaps. One lead is bent forward and forced between the split sections of the inner coaxial connector until the spark gaps approach the body of the connector. A short length of insulating material (such as Mylar) is placed between the spark gaps and the connector shell. The other spark-gap lead is folded over the insulator, then conductive (metallic) tape is wrapped around the assembly. This construction method proved durable enough to allow many insertions and removals of the device during testing. Estimated cost of this assembly is $9. Similar devices can be built using components from Joslyn, General Electric, General Semiconductor or Siemens.

Summary

Amateurs should be aware of which components in their radio system are most likely to be damaged by EMP. They should also know how to repair the damaged equipment. Amateurs should know how to reestablish commu-

Fig 19—Pictorial diagram of an inexpensive, homemade RF coax transient protector.

nications after an EMP event, taking into consideration its adverse effects on the earth's atmosphere and radio equipment. One of the first things that would be noticed, providing the radio equipment is operative, is a sudden silence in radio transmissions across all frequencies below approximately 100 MHz. This silence would be caused in part by damage to unprotected radio gear from the EMP transient. Transmissions from one direction, the direction of the nuclear blast, would be completely out. RF signal loss by absorption and attenuation by the nuclear fireball are the reasons for this.

After an EMP event, the amateur should be prepared to operate CW. CW gives the most signal power under adverse conditions. It also provides a degree of message security from the general public.

Amateurs should develop the capability and flexibility to operate in more than one frequency band. The lower ground-wave frequencies should be useful for long-distance communications immediately after an EMP event. Line-of-sight VHF would be of value for local communications.

What can be done to increase the survivability of an Amateur Radio station? Here are some suggestions:

1) If you have spare equipment, keep it disconnected; use only the primary station gear. The spare equipment would then be available after an EMP event.
2) Keep equipment turned off and antenna and power lines disconnected when the equipment is not in use.
3) Connect only those external conductors necessary for the current mode of operation.
4) Tie all fixed equipment to a single-point earth ground to prevent closed loops through the ground.
5) Obtain schematic diagrams of your equipment and tools for repair of the equipment.
6) Have spare parts on hand for sensitive components of the radio equipment and antenna system.
7) Learn how to repair or replace the sensitive components of the radio equipment.
8) Use nonmetallic guy lines and antenna structural parts where possible.
9) Obtain an emergency power source and operate from

it during periods of increased world political tension. The power source should be completely isolated from the commercial power lines.

10) Equipment power cords should be disconnected when the gear is idle. Or the circuit breaker for the line feeding the equipment should be kept in the OFF position when the station is off the air.

11) Disconnect the antenna lead-in when the station is off the air. Or use a grounding antenna switch and keep it in the GROUND position when the equipment is not in use.

12) Have a spare antenna and transmission line on hand to replace a damaged antenna system.

13) Install EMP surge arresters and filters on all primary conductors attached to the equipment and antenna.

14) Retain tube type equipment and spare components; keep them in good working order.

15) Do not rely on a microprocessor to control the station after an EMP event. Be able to operate without microprocessor control.

The recommendations contained in this section were developed with low cost in mind; they are not intended to cover all possible combinations of equipment and installation methods found in the amateur community. Amateurs should examine their own requirements and use this report as a guideline in providing protection for the equipment.

RF Radiation and Electromagnetic Field Safety

Amateur Radio is basically a safe activity. In recent years, however, there has been considerable discussion and concern about the possible hazards of electromagnetic radiation (EMR), including both RF energy and power-frequency (50-60 Hz) electromagnetic (EM) fields. FCC regulations set limits on the maximum permissible exposure (MPE) allowed from the operation of radio transmitters. These regulations do not take the place of RF-safety practices, however. This section deals with the topic of RF safety.

This section was prepared by members of the ARRL RF Safety Committee and coordinated by Dr Robert E. Gold, WBØKIZ. It summarizes what is now known and offers safety precautions based on the research to date.

All life on Earth has adapted to survive in an environment of weak, natural, low-frequency electromagnetic fields (in addition to the Earth's static geomagnetic field). Natural low-frequency EM fields come from two main sources: the sun, and thunderstorm activity. But in the last 100 years, man-made fields at much higher intensities and with a very different spectral distribution have altered this natural EM background in ways that are not yet fully understood. Researchers continue to look at the effects of RF exposure over a wide range of frequencies and levels.

Both RF and 60-Hz fields are classified as *nonionizing radiation,* because the frequency is too low for there to be enough photon energy to ionize atoms. (*Ionizing radiation*, such as X-rays, gamma rays and even some ultraviolet radiation has enough energy to knock electrons loose from their atoms. When this happens, positive and negative ions are formed.) Still, at sufficiently high power densities, EMR poses certain health hazards. It has been known since the early days of radio that RF energy can cause injuries by heating body tissue. (Anyone who has ever touched an improperly grounded radio chassis or energized antenna and received an *RF burn* will agree that this type of injury can be quite painful.) In extreme cases, RF-induced heating in the eye can result in cataract formation, and can even cause blindness. Excessive RF heating of the reproductive organs can cause sterility. Other health problems also can result from RF heating. These heat-related health hazards are called *thermal effects.* A microwave oven is a positive application of this thermal effect.

There also have been observations of changes in physiological function in the presence of RF energy levels that are too low to cause heating. These functions return to normal when the field is removed. Although research is ongoing, no harmful health consequences have been linked to these changes.

In addition to the ongoing research, much else has been done to address this issue. For example, FCC regulations set limits on exposure from radio transmitters. The Institute of Electrical and Electronics Engineers, the American National Standards Institute and the National Council for Radiation Protection and Measurement, among others, have recommended voluntary guidelines to limit human exposure to RF energy. The ARRL has established the RF Safety Committee, consisting of concerned medical doctors and scientists, serving voluntarily to monitor scientific research in the fields and to recommend safe practices for radio amateurs.

THERMAL EFFECTS OF RF ENERGY

Body tissues that are subjected to *very high* levels of RF energy may suffer serious heat damage. These effects depend on the frequency of the energy, the power density of the RF field that strikes the body and factors such as the polarization of the wave.

At frequencies near the body's natural resonant frequency, RF energy is absorbed more efficiently, and an increase in heating occurs. In adults, this frequency usually is about 35 MHz if the person is grounded, and about 70 MHz if insulated from the ground. Individual body parts may be resonant at different frequencies. The adult head, for example, is resonant around 400 MHz, while a baby's smaller head resonates near 700 MHz. Body size thus determines the frequency at which most RF energy is absorbed. As the frequency is moved farther from resonance, less RF heating generally occurs. *Specific absorption rate (SAR)* is a term that describes the rate at which RF energy is absorbed in tissue.

Maximum permissible exposure (MPE) limits are based on whole-body SAR values, with additional safety factors included as part of the standards and regulations. This helps explain why these safe exposure limits vary with frequency. The MPE limits define the maximum electric and magnetic field strengths or the plane-wave equivalent power densities associated with these fields, that a person may be exposed to without harmful effect—and with an acceptable safety factor. The regulations assume that a person exposed to a specified (safe) MPE level also will experience a safe SAR.

Nevertheless, thermal effects of RF energy should not be a major concern for most radio amateurs, because of the power levels we normally use and the intermittent nature of most amateur transmissions. Amateurs spend more time listening than transmitting, and many amateur transmissions such as CW and SSB use low-duty-cycle modes. (With FM or RTTY, though, the RF is present continuously at its maximum level during each transmission.) In any event, it is rare for radio amateurs to be subjected to RF fields strong enough to produce thermal effects, unless they are close to an energized antenna or un- shielded power amplifier. Specific suggestions for avoiding excessive exposure are offered later in this chapter.

ATHERMAL EFFECTS OF EMR

Research about possible health effects resulting from exposure to the lower level energy fields, the athermal effects, has been of two basic types: epidemiological research and laboratory research.

Scientists conduct laboratory research into biological mechanisms by which EMR may affect animals including humans. Epidemiologists look at the health patterns of large groups of people using statistical methods. These epidemiological studies have been inconclusive. By their basic design, these studies do not demonstrate cause and effect, nor do they postulate mechanisms of disease. Instead, epidemiologists look for associations between an environmental factor and an observed pattern of illness. For example, in the earliest research on malaria, epidemiologists observed the association between populations with high prevalence of the disease and the proximity of mosquito infested swamplands. It was left to the biological and medical scientists to isolate the organism causing malaria in the blood of those with the disease, and identify the same organisms in the mosquito population.

In the case of athermal effects, some studies have identified a weak association between exposure to EMF at home or at work and various malignant conditions including leukemia and brain cancer. A larger number of equally well designed and performed studies, however, have found no association. A risk ratio of between 1.5 and 2.0 has been observed in positive studies (the number of observed cases of malignancy being 1.5 to 2.0 times the "expected" number in the population). Epidemiologists generally regard a risk ratio of 4.0 or greater to be indicative of a strong association between the cause and effect under study. For example, men who smoke one pack of cigarettes per day increase their risk for lung cancer tenfold compared to non-smokers, and two packs per day increases the risk to more than 25 times the nonsmokers' risk.

Epidemiological research by itself is rarely conclusive, however. Epidemiology only identifies health patterns in groups—it does not ordinarily determine their cause. And there are often confounding factors: Most of us are exposed to many different environmental hazards that may affect our health in various ways. Moreover, not all studies of persons likely to be exposed to high levels of EMR have yielded the same results.

There also has been considerable laboratory research about the biological effects of EMR in recent years. For example, some separate studies have indicated that even fairly low levels of EMR might alter the human body's circadian rhythms, affect the manner in which T lymphocytes function in the immune system and alter the nature of the electrical and chemical signals communicated through the cell membrane and between cells, among other things. Although these studies are intriguing, they do not demonstrate any effect of these low-level fields on the overall organism.

Much of this research has focused on low-frequency magnetic fields, or on RF fields that are keyed, pulsed or modulated at a low audio frequency (often below 100 Hz). Several studies suggested that humans and animals can adapt to the presence of a steady RF carrier more readily than to an intermittent, keyed or modulated energy source.

The results of studies in this area, plus speculations concerning the effect of various types of modulation, were and have remained somewhat controversial. None of the research to date has demonstrated that low-level EMR causes adverse health effects.

Fig 20—1991 RF protection guidelines for body exposure of humans. It is known officially as the "IEEE Standard for Safety Levels with Respect to Human Exposure to Radio Frequency Electromagnetic Fields, 3 kHz to 300 GHz."

Given the fact that there is a great deal of ongoing research to examine the health consequences of exposure to EMF, the American Physical Society (a national group of highly respected scientists) issued a statement in May 1995 based on its review of available data pertaining to the possible connections of cancer to 60-Hz EMF exposure. This report is exhaustive and should be reviewed by anyone with a serious interest in the field. Among its general conclusions were the following:

1. The scientific literature and the reports of reviews by other panels show no consistent, significant link between cancer and power line fields.
2. No plausible biophysical mechanisms for the systematic initiation or promotion of cancer by these extremely weak 60-Hz fields has been identified.
3. While it is impossible to prove that no deleterious health effects occur from exposure to any environmental factor, it is necessary to demonstrate a consistent, significant, and causal relationship before one can conclude that such effects do occur.

In a report dated October 31, 1996, a committee of the National Research Council of the National Academy of Sciences has concluded that no clear, convincing evidence exists to show that residential exposures to electric and magnetic fields (EMFs) are a threat to human health.

A National Cancer Institute epidemiological study of residential exposure to magnetic fields and acute lymphoblastic leukemia in children was published in the *New England Journal of Medicine* in July 1997. The exhaustive, seven-year study concludes that if there is any link at all, it is far too weak to be concerned about.

Readers may want to follow this topic as further studies are reported. Amateurs should be aware that exposure to RF and ELF (60 Hz) electromagnetic fields at all power levels and frequencies has not been fully studied under all circumstances. "Prudent avoidance" of any avoidable EMR is always a good idea. Prudent avoidance doesn't mean that amateurs should be fearful of using their equipment. Most amateur operations are well within the MPE limits. If any risk does exist, it will almost surely fall well down on the list of causes that may be harmful to your health (on the other end of the list from your automobile). It does mean, however, that hams should be aware of the potential for exposure from their stations, and take whatever reasonable steps they can take to minimize their own exposure and the exposure of those around them.

Safe Exposure Levels

How much EM energy is safe? Scientists and regulators have devoted a great deal of effort to deciding upon safe RF-exposure limits. This is a very complex problem, involving difficult public health and economic considerations. The recommended safe levels have been revised downward several times over the years —and not all scientific bodies agree on this question even today. An Institute of Electrical and Electronics Engineers (IEEE) standard for recommended EM exposure limits was published in 1991 (see Bibliography). It replaced a 1982 American National Standards Institute (ANSI) standard. In the new standard, most of the permitted exposure levels were revised downward (made more stringent), to better reflect the current research. The new IEEE stan-

FCC RF-Exposure Regulations

FCC regulations control the amount of RF exposure that can result from your station's operation (§§97.13, 97.503, 1.1307 (b)(c)(d), 1.1310 and 2.1093). The regulations set limits on the maximum permissible exposure (MPE) allowed from operation of transmitters in all radio services. They also require that certain types of stations be evaluated to determine if they are in compliance with the MPEs specified in the rules. The FCC has also required that five questions on RF environmental safety practices be added to Novice, Technician and General license examinations.

These rules went into effect on January 1, 1998 for new stations or stations that file a Form 605 application with the FCC. Other existing stations have until September 1, 2000 to be in compliance with the rules.

The Rules

Maximum Permissible Exposure (MPE)

All radio stations regulated by the FCC must comply with the requirements for MPEs, even QRP stations running only a few watts or less. The MPEs vary with frequency, as shown in **Table A**. MPE limits are specified in maximum electric and magnetic fields for frequencies below 30 MHz, in power density for frequencies above 300 MHz and all three ways for frequencies from 30 to 300 MHz. For compliance purposes, all of these limits must be considered *separately*. If any one is exceeded, the station is not in compliance.

The regulations control human exposure to RF fields, not the strength of RF fields. There is no limit to how strong a field can be as long as no one is being exposed to it, although FCC regulations require that amateurs use the minimum necessary power at all times (§97.311 [a]).

Environments

The FCC has defined two exposure environments — *controlled* and *uncontrolled*. A controlled environment is one in which the people who are being exposed are aware of that exposure and can take steps to minimize that exposure, if appropriate. In an uncontrolled environment, the people being exposed are not normally aware of the exposure. The uncontrolled environment limits are more stringent than the controlled environment limits.

Although the controlled environment is usually intended as an occupational environment, the FCC has determined that it generally applies to amateur operators and members of their immediate households. In most cases, controlled-environment limits can be applied to your home and property to which you can control physical access. The uncontrolled environment is intended for areas that are accessible by the general public, such as your neighbors' properties.

The MPE levels are based on average exposure. An averaging time of 6 minutes is used for controlled exposure; an averaging period of 30 minutes is used for uncontrolled exposure.

Station Evaluations

The FCC requires that certain amateur stations be evaluated for compliance with the MPEs. Although an amateur can have someone else do the evaluation, it is not difficult for hams to evaluate their own stations. The ARRL book *RF Exposure and You* contains extensive information about the regulations and a large chapter of tables that show compliance distances for specific antennas and power levels. Generally, hams will use these tables to evaluate their stations. Some of these tables have been included in the FCC's information — *OET Bulletin 65* and its *Supplement B*. If hams choose, however, they can do more extensive calculations, use a computer to model their antenna and exposure, or make actual measurements.

Table A—(From §1.1310) Limits for Maximum Permissible Exposure (MPE)

(A) Limits for Occupational/Controlled Exposure

Frequency Range (MHz)	Electric Field Strength (V/m)	Magnetic Field Strength (A/m)	Power Density (mW/cm²)	Averaging Time (minutes)
0.3-3.0	614	1.63	(100)*	6
3.0-30	1842/f	4.89/f	(900/f²)*	6
30-300	61.4	0.163	1.0	6
300-1500	—	—	f/300	6
1500-100,000	—	—	5	6

f = frequency in MHz
* = Plane-wave equivalent power density (see Note 1).

(B) Limits for General Population/Uncontrolled Exposure

Frequency Range (MHz)	Electric Field Strength (V/m)	Magnetic Field Strength (A/m)	Power Density (mW/cm²)	Averaging Time (minutes)
0.3-1.34	614	1.63	(100)*	30
1.34-30	824/f	2.19/f	(180/f²)*	30
30-300	27.5	0.073	0.2	30
300-1500	—	—	f/1500	30
1500-100,000	—	—	1.0	30

f = frequency in MHz
* = Plane-wave equivalent power density (see Note 1).

Note 1: This means the equivalent far-field strength that would have the E or H-field component calculated or measured. It does not apply well in the near field of an antenna. The equivalent far-field power density can be found in the near or far field regions from the relationships: $P_d = |E_{total}|^2 / 3770$ mW/cm² or from $P_d = |H_{total}|^2 \times 37.7$ mW/cm².

Table B—Power Thresholds for Routine Evaluation of Amateur Radio Stations

Wavelength Band	Evaluation Required if Power* (watts) Exceeds:
MF	
160 m	500
HF	
80 m	500
75 m	500
40 m	500
30 m	425
20 m	225
17 m	125
15 m	100
12 m	75
10 m	50
VHF (all bands)	50
UHF	
70 cm	70
33 cm	150
23 cm	200
13 cm	250
SHF (all bands)	250
EHF (all bands)	250
Repeater stations (all bands)	*non-building-mounted antennas*: height above ground level to lowest point of antenna < 10 m *and* power > 500 W ERP *building-mounted antennas*: power > 500 W ERP

*Transmitter power = Peak-envelope power input to antenna. For repeater stations **only,** power exclusion based on ERP (effective radiated power).

Categorical Exemptions

Some types of amateur stations do not need to be evaluated, but these stations must still comply with the MPE limits. The station licensee remains responsible for ensuring that the station meets these requirements.

The FCC has exempted these stations from the evaluation requirement because their output power, operating mode and frequency are such that they are presumed to be in compliance with the rules.

Stations using power equal to or less than the levels in **Table B** do not have to be evaluated. For the 100-W HF ham station, for example, an evaluation would be required *only* on 12 and 10 meters.

Hand-held radios and vehicle-mounted mobile radios that operate using a push-to-talk (PTT) button are also categorically exempt from performing the routine evaluation. Repeater stations that use less than 500 W ERP or those with antennas not mounted on buildings, if the antenna is at least 10 meters off the ground, also do not need to be evaluated.

Correcting Problems

Most hams are already in compliance with the MPE requirements. Some amateurs, especially those using indoor antennas or high-power, high-duty-cycle modes such as a RTTY bulletin station and specialized stations for moonbounce operations and the like may need to make adjustments to their station or operation to be in compliance.

The FCC permits amateurs considerable flexibility in complying with these regulations. As an example, hams can adjust their operating frequency, mode or power to comply with the MPE limits. They can also adjust their operating habits or control the direction their antenna is pointing.

More Information

This discussion offers only an overview of this topic; additional information can be found in *RF Exposure and You* and on *ARRLWeb* at **www.arrl.org/news/rfsafety/**. *ARRLWeb* has links to the FCC Web site, with *OET Bulletin 65* and *Supplement B* and links to software that hams can use to evaluate their stations.

---

dard was adopted by ANSI in 1992.

The IEEE standard recommends frequency-dependent and time-dependent maximum permissible exposure levels. Unlike earlier versions of the standard, the 1991 standard recommends different RF exposure limits in controlled environments (that is, where energy levels can be accurately determined and everyone on the premises is aware of the presence of EM fields) and in uncontrolled environments (where energy levels are not known or where people may not be aware of the presence of EM fields). FCC regulations also include controlled/occupational and uncontrolled/general population exposure environments.

The graph in **Fig 20** depicts the 1991 IEEE standard. It is necessarily a complex graph, because the standards differ not only for controlled and uncontrolled environments but also for electric (E) fields and magnetic (H) fields. Basically, the lowest E-field exposure limits occur at frequencies between 30 and 300 MHz. The lowest H-field exposure levels occur at 100-300 MHz. The ANSI standard sets the maximum E-field limits between 30 and 300 MHz at a power density of 1 mW/cm^2 (61.4 V/m) in controlled environments—but at one-fifth that level (0.2 mW/cm^2 or 27.5 V/m) in uncontrolled environments. The H-field limit drops to 1 mW/cm^2 (0.163 A/m) at 100-300 MHz in controlled environments and 0.2 mW/cm^2 (0.0728 A/m) in uncontrolled environments. Higher power densities are permitted at frequencies below 30 MHz (below 100 MHz for H fields) and above 300 MHz, based on the concept that the body will not be resonant at those frequencies and will therefore absorb less energy.

In general, the 1991 IEEE standard requires averaging the power level over time periods ranging from 6 to

30 minutes for power-density calculations, depending on the frequency and other variables. The ANSI exposure limits for uncontrolled environments are lower than those for controlled environments, but to compensate for that the standard allows exposure levels in those environments to be averaged over much longer time periods (generally 30 minutes). This long averaging time means that an intermittently operating RF source (such as an Amateur Radio transmitter) will show a much lower power density than a continuous-duty station—for a given power level and antenna configuration.

Time averaging is based on the concept that the human body can withstand a greater rate of body heating (and thus, a higher level of RF energy) for a short time than for a longer period. Time averaging may not be appropriate, however, when considering nonthermal effects of RF energy.

The IEEE standard excludes any transmitter with an output below 7 W because such low-power transmitters would not be able to produce significant whole-body heating. (Recent studies show that hand-held transceivers often produce power densities in excess of the IEEE standard within the head.)

There is disagreement within the scientific community about these RF exposure guidelines. The IEEE standard is still intended primarily to deal with thermal effects, not exposure to energy at lower levels. A small but significant number of researchers now believe athermal effects also should be taken into consideration. Several European countries and localities in the United States have adopted stricter standards than the recently updated IEEE standard.

Another national body in the United States, the National Council for Radiation Protection and Measurement (NCRP), also has adopted recommended exposure guidelines. NCRP urges a limit of 0.2 mW/cm^2 for non-occupational exposure in the 30-300 MHz range. The NCRP guideline differs from IEEE in two notable ways: It takes into account the effects of modulation on an RF carrier, and it does not exempt transmitters with outputs below 7 W.

The FCC MPE regulations are based on parts of the 1992 IEEE/ANSI standard and recommendations of the National Council for Radiation Protection and Measurement (NCRP). The MPE limits under the regulations are slightly different than the IEEE/ANSI limits. Note that the MPE levels apply to the FCC rules put into effect for radio amateurs on January 1, 1998. These MPE requirements do not reflect and include all the assumptions and exclusions of the IEEE/ANSI standard.

Cardiac Pacemakers and RF Safety

It is a widely held belief that cardiac pacemakers may be adversely affected in their function by exposure to electromagnetic fields. Amateurs with pacemakers may ask whether their operating might endanger themselves or visitors to their shacks who have a pacemaker. Because of this, and similar concerns regarding other sources of electromagnetic fields, pacemaker manufacturers apply design methods that for the most part shield the pacemaker circuitry from even relatively high EM field strengths.

It is recommended that any amateur who has a pacemaker, or is being considered for one, discuss this matter with his or her physician. The physician will probably put the amateur into contact with the technical representative of the pacemaker manufacturer. These representatives are generally excellent resources, and may have data from laboratory or "in the field" studies with specific model pacemakers.

One study examined the function of a modern (dual chamber) pacemaker in and around an Amateur Radio station. The pacemaker generator has circuits that receive and process electrical signals produced by the heart, and also generate electrical signals that stimulate (pace) the heart. In one series of experiments, the pacemaker was connected to a heart simulator. The system was placed on top of the cabinet of a 1-kW HF linear amplifier during SSB and CW operation. In another test, the system was placed in close proximity to several 1 to 5-W 2-meter hand-held transceivers. The test pacemaker was connected to the heart simulator in a third test, and then placed on the ground 9 meters below and 5 meters in front of a three-element Yagi HF antenna. No interference with pacemaker function was observed in these experiments.

Although the possibility of interference cannot be entirely ruled out by these few observations, these tests represent more severe exposure to EM fields than would ordinarily be encountered by an amateur—with an average amount of common sense. Of course, prudence dictates that amateurs with pacemakers, who use hand-held VHF transceivers, keep the antenna as far as possible from the site of the implanted pacemaker generator. They also should use the lowest transmitter output required for adequate communication. For high power HF transmission, the antenna should be as far as possible from the operating position, and all equipment should be properly grounded.

Low-Frequency Fields

Although the FCC doesn't regulate 60-Hz fields, some recent concern about EMR has focused on low-frequency energy rather than RF. Amateur Radio equipment can be a significant source of low-frequency magnetic fields, although there are many other sources of this kind of energy in the typical home. Magnetic fields can be measured relatively accurately with inexpensive 60-Hz meters that are made by several manufacturers.

Table 2 shows typical magnetic field intensities of Amateur Radio equipment and various household items. Because these fields dissipate rapidly with distance, "prudent avoidance" would mean staying perhaps 12 to 18 inches away from most Amateur Radio equipment (and

24 inches from power supplies with 1-kW RF amplifiers).

Determining RF Power Density

Unfortunately, determining the power density of the RF fields generated by an amateur station is not as simple as measuring low-frequency magnetic fields. Although sophisticated instruments can be used to measure RF power densities quite accurately, they are costly and require frequent recalibration. Most amateurs don't have access to such equipment, and the inexpensive field-

Table 2
Typical 60-Hz Magnetic Fields Near Amateur Radio Equipment and AC-Powered Household Appliances

Values are in milligauss.

Item	Field	Distance
Electric blanket	30-90	Surface
Microwave oven	10-100	Surface
	1-10	12″
IBM personal computer	5-10	Atop monitor
	0-1	15″ from screen
Electric drill	500-2000	At handle
Hair dryer	200-2000	At handle
HF transceiver	10-100	Atop cabinet
	1-5	15″ from front
1-kW RF amplifier	80-1000	Atop cabinet
	1-25	15″ from front

(Source: measurements made by members of the ARRL RF Safety Committee)

Table 3
Typical RF Field Strengths Near Amateur Radio Antennas

A sampling of values as measured by the Federal Communications Commission and Environmental Protection Agency, 1990

Antenna Type	Freq (MHz)	Power (W)	E Field (V/m)	Location
Dipole in attic	14.15	100	7-100	In home
Discone in attic	146.5	250	10-27	In home
Half sloper	21.5	1000	50	1 m from base
Dipole at 7-13 ft	7.14	120	8-150	1-2 m from earth
Vertical	3.8	800	180	0.5 m from base
5-element Yagi at 60 ft	21.2	1000	10-20	In shack
			14	12 m from base
3-element Yagi at 25 ft	28.5	425	8-12	12 m from base
Inverted V at 22-46 ft	7.23	1400	5-27	Below antenna
Vertical on roof	14.11	140	6-9	In house
			35-100	At antenna tuner
Whip on auto roof	146.5	100	22-75	2 m antenna
			15-30	In vehicle
			90	Rear seat
5-element Yagi at 20 ft	50.1	500	37-50	10 m antenna

Table 4
RF Awareness Guidelines

These guidelines were developed by the ARRL RF Safety Committee, based on the FCC/EPA measurements of Table 3 and other data.

• Although antennas on towers (well away from people) pose no exposure problem, make certain that the RF radiation is confined to the antennas' radiating elements themselves. Provide a single, good station ground (earth), and eliminate radiation from transmission lines. Use good coaxial cable or other feed line properly. Avoid serious imbalance in your antenna system and feed line. For high-powered installations, avoid end-fed antennas that come directly into the transmitter area near the operator.

• No person should ever be near any transmitting antenna while it is in use. This is especially true for mobile or ground-mounted vertical antennas. Avoid transmitting with more than 25 W in a VHF mobile installation unless it is possible to first measure the RF fields inside the vehicle. At the 1-kW level, both HF and VHF directional antennas should be at least 35 ft above inhabited areas. Avoid using indoor and attic-mounted antennas if at all possible. If open-wire feeders are used, ensure that it is not possible for people (or animals) to come into acciden-

tal contact with the feed line.

• Don't operate high-power amplifiers with the covers removed, especially at VHF/UHF.

• In the UHF/SHF region, never look into the open end of an activated length of waveguide or microwave feed-horn antenna or point it toward anyone. (If you do, you may be exposing your eyes to more than the maximum permissible exposure level of RF radiation.) Never point a high-gain, narrow-bandwidth antenna (a paraboloid, for instance) toward people. Use caution in aiming an EME (moonbounce) array toward the horizon; EME arrays may deliver an effective radiated power of 250,000 W or more.

• With hand-held transceivers, keep the antenna away from your head and use the lowest power possible to maintain communications. Use a separate microphone and hold the rig as far away from you as possible. This will reduce your exposure to the RF energy.

• Don't work on antennas that have RF power applied.

• Don't stand or sit close to a power supply or linear amplifier when the ac power is turned on. Stay at least 24 inches away from power transformers, electrical fans and other sources of high-level 60-Hz magnetic fields.

strength meters that we do have are not suitable for measuring RF power density.

Table 3 shows a sampling of measurements made at Amateur Radio stations by the Federal Communications Commission and the Environmental Protection Agency in 1990. As this table indicates, a good antenna well removed from inhabited areas poses no hazard under any of the IEEE/ANSI guidelines. However, the FCC/EPA survey also indicates that amateurs must be careful about using indoor or attic-mounted antennas, mobile antennas, low directional arrays or any other antenna that is close to inhabited areas, especially when moderate to high power is used.

Ideally, before using any antenna that is in close proximity to an inhabited area, you should measure the RF power density. If that is not feasible, the next best option is make the installation as safe as possible by observing the safety suggestions listed in **Table 4**.

It also is possible, of course, to calculate the probable power density near an antenna using simple equations. Such calculations have many pitfalls. For one, most of the situations where the power density would be high enough to be of concern are in the near field. In the near field, ground interactions and other variables produce power densities that cannot be determined by simple arithmetic. In the far field, conditions become easier to predict with simple calculations.

The boundary between the near field and the far field depends on the wavelength of the transmitted signal and the physical size and configuration of the antenna. The boundary between the near field and the far field of an antenna can be as much as several wavelengths from the antenna.

Computer antenna-modeling programs are another approach you can use. *MININEC* or other codes derived from *NEC* (Numerical Electromagnetics Code) are suitable for estimating RF magnetic and electric fields around amateur antenna systems.

These models have limitations. Ground interactions must be considered in estimating near-field power densities, and the "correct ground" must be modeled. Computer modeling is generally not sophisticated enough to predict "hot spots" in the near field—places where the field intensity may be far higher than would be expected, due to reflections from nearby objects. In addition, "nearby objects" often change or vary with weather or the season,

so the model so laboriously crafted may not be representative of the actual situation, by the time it is running on the computer.

Intensely elevated but localized fields often can be detected by professional measuring instruments. These "hot spots" are often found near wiring in the shack, and metal objects such as antenna masts or equipment cabinets. But even with the best instrumentation, these measurements also may be misleading in the near field.

One need not make precise measurements or model the exact antenna system, however, to develop some idea of the relative fields around an antenna. Computer modeling using close approximations of the geometry and power input of the antenna will generally suffice. Those who are familiar with *MININEC* can estimate their power densities by computer modeling, and those who have access to professional power-density meters can make useful measurements.

While our primary concern is ordinarily the intensity of the signal radiated by an antenna, we also should remember that there are other potential energy sources to be considered. You also can be exposed to RF radiation directly from a power amplifier if it is operated without proper shielding. Transmission lines also may radiate a significant amount of energy under some conditions. Poor microwave waveguide joints or improperly assembled connectors are another source of incidental radiation.

Further RF Exposure Suggestions

Potential exposure situations should be taken seriously. Based on the FCC/EPA measurements and other data, the "RF awareness" guidelines of Table 4 were developed by the ARRL RF Safety Committee. A longer version of these guidelines, along with a complete list of references, appeared in a *QST* article by Ivan Shulman, MD, WC2S ("Is Amateur Radio Hazardous to Our Health?" *QST* , Oct 1989, pp 31-34). For more information or background, see the list of RF Safety References in the next section.

In addition, the ARRL has published a book, *RF Exposure and You*, that is helping hams comply with the FCC's RF-exposure regulations. The ARRL also maintains an RF-exposure news page on its Web site. See **www.arrl.org/news/rfsafety**. This site contains reprints of selected *QST* articles on RF exposure and links to the FCC and other useful sites.

Antenna Fundamentals

Antennas belong to a class of devices called *transducers*. This term is derived from two Latin words, meaning literally "to lead across" or "to transfer." Thus, a transducer is a device that transfers, or converts, energy from one form to another. The purpose of an antenna is to convert radio-frequency electric current to *electromagnetic waves*, which are then *radiated* into space. [For more details on the properties of electromagnetic waves themselves, see Chapter 23, Radio Wave Propagation.]

We cannot directly see or hear, taste or touch electromagnetic waves, so it's not surprising that the process by which they are launched into space from our antennas can be a little mystifying, especially to a newcomer. In everyday life we come across many types of transducers, although we don't always recognize them as such. A comparison with a type of transducer that you can actually see and touch may be useful. You are no doubt familiar with a *loudspeaker*. It converts audio-frequency electric current from the output of your radio or stereo into acoustic pressure waves, also known as *sound waves*. The sound waves are propagated through the air to your ears, where they are converted into what you perceive as sound.

We normally think of a loudspeaker as something that converts electrical energy into sound energy, but we could just as well turn things around and apply sound energy to a loudspeaker, which will then convert it into electrical energy. When used in this manner, the loudspeaker has become a microphone. The loudspeaker/microphone thus exhibits the principle of *reciprocity*, derived from the Latin word meaning to move back and forth.

Now, let's look more closely at that special transducer we call an *antenna*. When fed by a transmitter with RF current (usually through a transmission line), the antenna launches electromagnetic waves, which are propagated through space. This is similar to the way sound waves are propagated through the air by a loudspeaker. In the next town, or perhaps on a distant continent, a similar transducer (that is, a receiving antenna) intercepts some of these electromagnetic waves and converts them into electrical current for a receiver to amplify and detect.

In the same fashion that a loudspeaker can act as a microphone, a radio antenna also follows the principle of reciprocity. In other words, an antenna can transmit as well as receive signals. However, unlike the loudspeaker, an antenna does not require a *medium*, such as air, through which it radiates electromagnetic waves. Electromagnetic waves can be propagated through air, the vacuum of outer space or the near vacuum of the upper ionosphere. This is the miracle of radio—electromagnetic waves can propagate without a physical medium.

Essential Characteristics of Antennas

What other things make an antenna different from an ordinary electronic circuit? In ordinary circuits, the dimensions of coils, capacitors and connections usually are small compared with the wavelength of the frequency in use. Here, we define wavelength as the distance in free space traveled during one complete cycle of a wave. The velocity of a wave in free space is the speed of light, and the wavelength is thus:

$$\lambda_{\text{meters}} = \frac{299.7925 \times 10^6 \text{ meters/sec}}{f \text{ hertz}} = \frac{299.7925}{f \text{ MHz}} \qquad \text{(Eq 1)}$$

where λ_{meters} , the Greek letter lambda, is the free-space wavelength in meters.

Expressed in feet, Eq 1 becomes:

$$\lambda_{feet} = \frac{983.5712}{f\,MHz} \approx \frac{983.6}{f\,MHz} \qquad (Eq\ 2)$$

When circuit dimensions are small compared to λ, most of the electromagnetic energy is confined to the circuit itself, and is used up either performing useful work or is converted into heat. However, when the dimensions of wiring or components become significant compared with the wavelength, some of the energy escapes by radiation in the form of electromagnetic waves.

Antennas come in an enormous, even bewildering, assortment of shapes and sizes. This chapter on fundamentals will deal with the theory of simple forms of antennas, usually in *free space*, away from the influence of ground. Subsequent chapters will concentrate on more exotic or specialized antenna types. Chapter 3 deals with the complicated subject of the effect of ground, including the effect of uneven local terrain. Ground has a profound influence on how an antenna performs in the real world.

No matter what form an antenna takes, simple or complex, its electrical performance can be characterized according to the following important properties:

1. Feed-point Impedance
2. Directivity, Gain and Efficiency
3. Polarization

FEED-POINT IMPEDANCE

The first major characteristic defining an antenna is its *feed-point impedance*. Since we amateurs are free to choose our operating frequencies within assigned bands, we need to consider how the feed-point impedance of a particular antenna varies with frequency, within a particular band, or even in several different bands if we intend to use one antenna on multiple bands.

There are two forms of impedance associated with any antenna: *self impedance* and *mutual impedance*. As you might expect, self impedance is what you measure at the feed-point terminals of an antenna located completely away from the influence of any other conductors.

Mutual, or coupled, impedance is due to the parasitic effect of nearby conductors; that is, conductors located within the antenna's reactive near field. (The subject of fields around an antenna will be discussed in detail later.) This includes the effect of ground, which is a lossy conductor, but a conductor nonetheless. Mutual impedance is defined using Ohm's Law, just like self impedance. However, mutual impedance is the ratio of voltage in one conductor, divided by the current in another (coupled) conductor. Mutually coupled conductors can distort the pattern of a highly directive antenna, as well as change the impedance seen at the feed point.

In this chapter on fundamentals, we won't directly deal with mutual impedance, considering it as a side effect of nearby conductors. Instead, here we'll concentrate on simple antennas in free space, away from ground and any other conductors. Mutual impedance will be considered in detail in Chapter 11, HF Yagi Arrays, where it is essential for proper operation of these beam antennas.

Self Impedance

The current that flows into an antenna's feed point must be supplied at a finite voltage. The self impedance of the antenna is simply equal to the voltage applied to its feed point divided by the current flowing into the feed point. Where the current and voltage are exactly in phase, the impedance is purely resistive, with zero reactive component. For this case the antenna is termed *resonant*. (Amateurs often use the term "resonant" rather loosely, usually meaning "nearly resonant" or "close-to resonant.")

Please recognize that an antenna *need not be resonant* in order to be an effective radiator. There is in fact nothing magic about having a resonant antenna, provided of course that you can devise some efficient means to feed the antenna. Many amateurs use non-resonant (even random-length) antennas fed with open-wire transmission lines and antenna tuners. They radiate signals just as well as those using coaxial cable and resonant antennas, and as a bonus they usually can use these antenna systems on multiple frequency bands. It is important to consider an antenna and its feed line as a *system*, in which all losses should be kept to a minimum. See Chapter 24, Transmission Lines, for details on transmission-line loss as a function of impedance mismatch.

Except at the one frequency where it is truly resonant, the current in an antenna is at a different phase compared to the applied voltage. In other words, the antenna exhibits a feed-point *impedance*, not just a pure resistance. The feed-point impedance is composed of either capacitive or inductive reactance in series with a resistance.

Radiation Resistance

The power supplied to an antenna is dissipated in two ways: radiation of electromagnetic waves, and heat losses in the wire and nearby dielectrics. The radiated power is what we want, the useful part, but it represents a form of "loss" just as much as the power used in heating the wire or nearby dielectrics is a loss. In either case, the dissipated power is equal to I^2R. In the case of heat losses, R is a real resistance. In the case of radiation, however, R is a "virtual" resistance, which, if replaced with an actual resistor of the same value, would dissipate the power actually radiated from the antenna. This resistance is called the *radiation resistance*. The total power in the antenna is therefore equal to $I^2(R_0+R)$, where R_0 is the radiation resistance and R represents the total of all the loss resistances.

In ordinary antennas operated at amateur frequencies, the power lost as heat in the conductor does not exceed a few percent of the total power supplied to the antenna. Expressed in decibels, the loss is less than 0.1 dB. The RF loss resistance of copper wire even as small as #14 is very low compared with the radiation resistance of an antenna that is reasonably clear of surrounding objects and is not too close to the ground. You can therefore assume that the ohmic loss in a reasonably well-located antenna is negligible, and that the total resistance shown by the antenna (the feed-point resistance) is radiation resistance. As a radiator of electromagnetic waves, such an antenna is a highly efficient device.

Impedance of a Center-Fed Dipole

A fundamental type of antenna is the *center-fed half-wave dipole*. Historically, the λ/2 dipole has been the most popular antenna used by amateurs worldwide, largely because it is very simple to construct and because it is an effective performer. It is also a basic building block for many other antenna systems, including beam antennas, such as Yagis.

A center-fed half-wave *dipole* consists of a straight wire, one-half wavelength long as defined in Eq 1, and fed in the center. The term "dipole" derives from Greek words meaning "two poles." See **Fig 1**. A λ/2-long dipole is just one form a dipole can take. Actually, a center-fed dipole can be any length electrically, as long as it is configured in a symmetrical fashion with two equal-length legs. There are also versions of dipoles that are not fed in the center. These are called *off-center-fed dipoles*, sometimes abbreviated as "OCF dipoles."

In free space—with the antenna remote from everything else—the theoretical impedance of a physically half-wave long antenna made of an infinitely thin conductor is $73 + j\,42.5\;\Omega$. This antenna exhibits both resistance and reactance. The positive sign in the $+\,j\,42.5$-Ω reactive term indicates that the antenna exhibits an inductive reactance at its feed point. The antenna is slightly long electrically, compared to the length necessary for exact

resonance, where the reactance is zero.

The feed-point impedance of any antenna is affected by the wavelength-to-diameter ratio (λ/dia) of the conductors used. Theoreticians like to specify an "infinitely thin" antenna because it is easier to handle mathematically.

What happens if we keep the physical length of an antenna constant, but change the thickness of the wire used in its construction? Further, what happens if we vary the frequency from well below to well above the half-wave resonance and measure the feed-point impedance? **Fig 2** graphs the impedance of a 100-foot long, center-fed dipole in free space, made with extremely thin wire—in this case, wire that is only 0.001 inches in diameter. There is nothing particularly significant about the choice here of 100 feet. This is simply a numerical example.

We could never actually build such a thin antenna (and neither could we install it in free space), but we can model how this antenna works using a very powerful piece of computer software called *NEC-4.1*. See Chapter 4, Antenna Modeling and System Planning, for details on antenna modeling.

The frequency applied to the antenna in Fig 2 is varied from 1 to 30 MHz. The x-axis has a logarithmic scale because of the wide range of feed-point resistance seen over the frequency range. The y-axis has a linear scale representing the reactive portion of the impedance. Inductive reactance is positive and capacitive reactance is negative on the y-axis. The bold figures centered on the spiraling line show the frequency in MHz.

At 1 MHz, the antenna is very short electrically, with a resistive component of about 2 Ω and a series capaci-

Fig 2—Feed-point impedance versus frequency for a theoretical 100-foot long dipole in free space, fed in the center and made of extremely thin 0.001-inch diameter wire. The y-axis is calibrated in positive (inductive) series reactance up from the zero line, and negative (capacitive) series reactance in the downward direction. The range of reactance goes from –6500 Ω to +6000 Ω. Note that the x-axis is logarithmic because of the wide range of the real, resistive component of the feed-point impedance, from roughly 2 Ω to 10,000 Ω. The numbers placed along the curve show the frequency in MHz.

Fig 1—The center-fed dipole antenna. It is assumed that the source of power is directly at the antenna feed point, with no intervening transmission line. Most commonly in amateur applications, the overall length of the dipole is λ/2, but the antenna can in actuality be any length.

Fig 3—Feed-point impedance versus frequency for a theoretical 100-foot long dipole in free space, fed in the center and made of thin 0.1-inch (#10) diameter wire. Note that the range of change in reactance is less than that shown in Fig 2, ranging from −2700 Ω to +2300 Ω. At about 5,000 Ω, the maximum resistance is also less than that in Fig 2 for the thinner wire, where it is about 10,000 Ω.

Fig 4—Feed-point impedance versus frequency for a theoretical 100-foot long dipole in free space, fed in the center and made of thick 1.0-inch diameter wire. Once again, the excursion in both reactance and resistance over the frequency range is less with this thick wire dipole than with thinner ones.

tive reactance about −5000 Ω. Close to 5 MHz, the line crosses the zero-reactance line, meaning that the antenna goes through half-wave resonance there. Between 9 and 10 MHz the antenna exhibits a peak inductive reactance of about 6000 Ω. It goes through full-wave resonance (again crossing the zero-reactance line) between 9.5 and 9.6 MHz. At about 10 MHz, the reactance peaks at about −6500 Ω. Around 14 MHz, the line again crosses the zero-reactance line, meaning that the antenna has now gone through 3/2-wave resonance.

Between 19 and 20 MHz, the antenna goes through 4/2-wave resonance, which is twice the full-wave resonance or four times the half-wave frequency. If you allow your mind's eye to trace out the curve for frequencies beyond 30 MHz, it eventually spirals down to a resistive component somewhere between 200 and 3000 Ω. Thus, we have another way of looking at an antenna—as a sort of *transformer*, one that transforms the free-space impedance into the impedance seen at its feed point.

Now look at **Fig 3**, which shows the same kind of spiral curve, but for a thicker-diameter wire, one that is 0.1 inches in diameter. This diameter is close to #10 wire, a practical size we might actually use to build a real dipole. Note that the y-axis scale in Fig 3 is different from that in Fig 2. The range is from ±3000 Ω in Fig 3, while it was ±7000 Ω in Fig 2. The reactance for the thicker antenna ranges from +2300 to −2700 Ω over the whole frequency range from 1 to 30 MHz. Compare this with the range of +5800 to −6400 Ω for the very thin wire in Fig 2.

Fig 4 shows the impedance for a 100-foot long dipole using really thick, 1.0-inch diameter wire. The reactance varies from +1000 to −1500 Ω, indicating once again that a larger diameter antenna exhibits less of an excursion in the reactive component with frequency. Note that at the

Fig 5—Feed-point impedance versus frequency for a theoretical 100-foot long dipole in free space, fed in the center and made of very thick 10.0-inch diameter wire. This ratio of length to diameter is about the same as a typical rod type of dipole element commonly used at 432 MHz. The maximum resistance is now about 1,000 Ω and the peak reactance range is from about −625 Ω to +380 Ω. This performance is also found in "cage" dipoles, where a number of paralleled wires are used to simulate a fat conductor.

half-wave resonance just below 5 MHz, the resistive component of the impedance is still about 70 Ω, just about what it is for a much thinner antenna. Unlike the reactance, the half-wave radiation resistance of an antenna doesn't radically change with wire diameter, although the maximum level of resistance at full-wave resonance is lower for thicker antennas.

Fig 5 shows the results for a very thick, 10-inch diameter wire. Here, the excursion in the reactive component is even less: about +400 to −600 Ω. Note that the full-wave resonant frequency is about 8 MHz for this

Fig 6—Expansion of frequency range around half-wave resonant point of three center-fed dipoles of three different thicknesses. The frequency is shown along the curves in MHz. The slope of change in series reactance versus series resistance is steeper for the thinner antennas than for the thick 1.0-inch antenna, indicating that the Q of the thinner antennas is higher.

Fig 7—Another way of looking at the data for a 100-foot, center-fed dipole made of #14 wire in free space. The numbers along the curve represent the fractional wavelength, rather than frequency as shown in Fig 6. Note that this antenna goes through its half-wave resonance about 0.488 λ, rather than exactly at a half-wave physical length.

extremely thick antenna, while thinner antennas have full-wave resonances closer to 9 MHz. Note also that the full-wave resistance for this extremely thick antenna is only about 1,000 Ω, compared to the 10,000 Ω shown in Fig 2. All half-wave resonances shown in Figs 2 through 5 remain close to 5 MHz, regardless of the diameter of the antenna wire. Once again, the extremely thick, 10-inch diameter antenna has a resistive component at half-wave resonance close to 70 Ω. And once again, the change in reactance near this frequency is very much less for the extremely thick antenna than for thinner ones.

Now, we grant you that a 100-foot long antenna made with 10-inch diameter wire sounds a little odd! A length of 100 feet and a diameter of 10 inches represent a ratio of 120:1 in length to diameter. However, this is about the same length-to-diameter ratio as a 432-MHz half-wave dipole using 0.25-inch diameter elements, where the ratio is 109:1. In other words, the ratio of length-to-diameter for the 10-inch diameter, 100-foot long dipole is not that far removed from what might actually be used at UHF.

Another way of highlighting the changes in reactance and resistance is shown in **Fig 6**. This shows an expanded portion of the frequency range around the half-wave resonant frequency, from 4 to 6 MHz. In this region, the shape of each spiral curve is almost a straight line. The slope of the curve for the very thin antenna (0.001-inch diameter) is steeper than that for the thicker antennas (0.1 and 1.0-inch diameters). **Fig 7** illustrates another way of looking at the impedance data above and below the half-wave resonance. This is for a 100-foot dipole made of #14 wire. Instead of showing the frequency for each impedance point, the wavelength is

Fig 8—Effect of antenna diameter on length for half-wavelength resonance, shown as a multiplying factor, K, to be applied to the free-space, half-wavelength.

shown, making the graph more universal in application.

Just to show that there are lots of ways of looking at the same data, **Fig 8** graphs the constant "K" used to multiply the free-space half-wavelength as a function of the ratio between the half-wavelength and the conductor diameter. The curve approaches the value of 1.00 for an infinitely thin conductor, in other words an infinitely large ratio of half-wavelength to diameter.

The behavior of antennas with different λ/diameter ratios corresponds to the behavior of ordinary series-resonant circuits having different values of Q. When the Q of a circuit is low, the reactance is small and changes rather slowly as the applied frequency is varied on either side of resonance. If the Q is high, the converse is true. The

response curve of the low-Q circuit is *broad*; that of the high-Q circuit *sharp*. So it is with antennas—the impedance of a thick antenna changes slowly over a comparatively wide band of frequencies, while a thin antenna has a faster change in impedance. Antenna Q is defined

$$Q = \frac{f_0 \Delta X}{2R_0 \Delta f} \qquad \text{(Eq 3)}$$

where f_0 is the center frequency, ΔX is the change in the reactance for a Δf change in frequency, and R_0 is the resistance the f_0. For the "Very Thin," 0.001-inch diameter dipole in Fig 2, a change of frequency from 5.0 to 5.5 MHz yields a reactance change from 86 to 351 Ω, with an R_0 of 95 Ω. The Q is thus 14.6. For the 1.0-inch-diameter "Thick" dipole in Fig 4, $\Delta X = 131$ Ω and R_0 is still 95 Ω, making Q = 7.2 for the thicker antenna, roughly half that of the thinner antenna.

Let's recap. We have described an antenna first as a transducer, then as a sort of transformer to a range of free-space impedances. Now, we just compared the antenna to a series-tuned circuit. Near its half-wave resonant frequency, a center-fed $\lambda/2$ dipole exhibits much the same characteristics as a conventional series-resonant circuit. Exactly at resonance, the current at the input terminals is in phase with the applied voltage and the feed-point impedance is purely resistive. If the frequency is below resonance, the phase of the current leads the voltage; that is, the reactance of the antenna is capacitive. When the frequency is above resonance, the opposite occurs; the current lags the applied voltage and the antenna exhibits inductive reactance. Just like a conventional series-tuned circuit, the antenna's reactance and resistance determines its Q.

ANTENNA DIRECTIVITY AND GAIN

The Isotropic Radiator

Before we can fully describe practical antennas, we must first introduce a completely theoretical antenna, the *isotropic radiator*. Envision, if you will, an infinitely small antenna, a point located in outer space, completely removed from anything else around it. Then consider an infinitely small transmitter feeding this infinitely small, point antenna. You now have an isotropic radiator.

The uniquely useful property of this theoretical *point-source* antenna is that it radiates equally well in all directions. That is to say, an isotropic antenna favors no direction at the expense of any other—in other words, it has absolutely no *directivity*. The isotropic radiator is useful as a *measuring stick* for comparison with actual antenna systems.

You will find later that real, practical antennas all exhibit some degree of directivity, which is the property of radiating more strongly in some directions than in others. The radiation from a practical antenna never has

the same intensity in all directions and may even have zero radiation in some directions. The fact that a practical antenna displays directivity (while an isotropic radiator does not) is not necessarily a bad thing. The directivity of a real antenna is often carefully tailored to emphasize radiation in particular directions. For example, a receiving antenna that favors certain directions can discriminate against interference or noise coming from other directions, thereby increasing the signal-to-noise ratio for desired signals coming from the favored direction.

Directivity and the Radiation Pattern— a Flashlight Analogy

The directivity of an antenna is directly related to the *pattern* of its radiated field intensity in free space. A graph showing the actual or relative field intensity at a fixed distance, as a function of the direction from the antenna system, is called a *radiation pattern*. Since we can't actually see electromagnetic waves making up the radiation pattern of an antenna, we can consider an analogous situation.

Fig 9 represents a flashlight shining in a totally darkened room. To quantify what our eyes are seeing, we might use a sensitive light meter like those used by photographers, with a scale graduated in units from 0 to 10. We place the meter directly in front of the flashlight and adjust the distance so the meter reads 10, exactly full scale. We also carefully note the distance. Then, always keeping the meter the same distance from the flashlight and keeping it at the same height above the floor, we move the light meter around the flashlight, as indicated by the

Fig 9—The beam from a flashlight illuminates a totally darkened area as shown here. Readings taken with a photographic light meter at the 16 points around the circle may be used to plot the radiation pattern of the flashlight.

arrow, and take light readings at a number of different positions.

After all the readings have been taken and recorded, we plot those values on a sheet of polar graph paper, like that shown in **Fig 10**. The values read on the meter are plotted at an angular position corresponding to that for which each meter reading was taken. Following this, we connect the plotted points with a smooth curve, also shown in Fig 10. When this is finished, we have completed a radiation pattern for the flashlight.

Antenna Pattern Measurements

Antenna radiation patterns can be constructed in a similar manner. Power is fed to the antenna under test, and a field-strength meter indicates the amount of signal. We might wish to rotate the antenna under test, rather than moving the measuring equipment to numerous positions about the antenna. Or we might make use of antenna reciprocity, since the pattern while receiving is the same as that while transmitting. A source antenna fed by a low-power transmitter illuminates the antenna under test, and the signal intercepted by the antenna under test is fed to a receiver and measuring equipment. Additional information on the mechanics of measuring antenna patterns is contained in Chapter 27, Antennas and Transmission-Line Measurements.

Some precautions must be taken to assure that the measurements are accurate and repeatable. In the case of the flashlight, let's assume that the separation between the light source and the light meter is 2 meters, about 6.5 feet. The wavelength of visible light is about one-half micron, where a micron is one-millionth of a meter.

For the flashlight, a separation of 2 meters between source and detector is $2.0/(0.5{\times}10^{-6}) = 4$ million λ, a very large number of wavelengths. Measurements of practical HF or even VHF antennas are made at much closer distances, in terms of wavelength. For example, at 3.5 MHz a full wavelength is 85.7 meters, or 281.0 feet. To duplicate the flashlight-to-light-meter spacing in wavelengths at 3.5 MHz, we would have to place the field-strength measuring instrument almost on the surface of the Moon, about a quarter-million miles away!

The Fields Around an Antenna

Why should we be concerned with the separation between the source antenna and the field-strength meter, which has its own receiving antenna? One important reason is that if you place a receiving antenna very close to an antenna whose pattern you wish to measure, mutual coupling between the two antennas may actually alter the pattern you are trying to measure.

This sort of mutual coupling can occur in the region very close to the antenna under test. This region is called the *reactive near-field* region. The term "reactive" refers to the fact that the mutual impedance between the transmitting and receiving antennas can be either capacitive

Fig 10—The radiation pattern of the flashlight in Fig 9. The measured values are plotted and connected with a smooth curve.

or inductive in nature. The reactive near field is sometimes called the "induction field," meaning that the magnetic field usually is predominant over the electric field in this region. The antenna acts as though it were a rather large, lumped-constant inductor or capacitor, storing energy in the reactive near field rather than propagating it into space.

For simple wire antennas, the reactive near field is considered to be within about a half wavelength from an antenna's radiating center. Later on, in the chapters dealing with Yagi and quad antennas, you will find that mutual coupling between elements can be put to good use to purposely shape the radiated pattern. For making pattern measurements, however, we do not want to be too close to the antenna being measured.

The strength of the reactive near field decreases in a complicated fashion as you increase the distance from the antenna. Beyond the reactive near field, the antenna's radiated field is divided into two other regions: the *radiating near field* and the *radiating far field*. Historically, the terms *Fresnel* and *Fraunhöfer* fields have been used for the radiating near and far fields, but these terms have been largely supplanted by the more descriptive terminology used here. Even inside the reactive near-field

Fig 11—The fields around a radiating antenna. Very close to the antenna, the reactive field dominates. Within this area mutual impedances are observed between antenna and any other antennas used to measure response. Outside of the reactive field, the near radiating field dominates, up to a distance approximately equal to 2L²/λ, where L is the length of the largest dimension of the antenna. Beyond the near/far field boundary lies the far radiating field, where power density varies as the inverse square of radial distance.

region, both radiating and reactive fields coexist, although the reactive field predominates very close to the antenna.

Because the boundary between the fields is rather fuzzy, experts debate where one field begins and another leaves off, but the boundary between the radiating near and far fields is generally accepted as:

$$D \approx \frac{2L^2}{\lambda} \qquad \text{(Eq 4)}$$

where L is the largest dimension of the physical antenna, expressed in the same units of measurement as the wavelength λ. Remember, many specialized antennas do not follow the rule of thumb in Eq 4 exactly. **Fig 11** depicts the three fields in front of a simple wire antenna.

Throughout the rest of this book we will discuss mainly the radiating far-fields, those forming the traveling electromagnetic waves. Far-field radiation is distinguished by the fact that the intensity is inversely proportional to the distance, and that the electric and magnetic components, although perpendicular to each other in the wave front, are in time phase. The total energy is equally divided between the electric and magnetic fields. Beyond several wavelengths from the antenna, these are the only fields we need to consider. For accurate measurement of radiation patterns, we must place our measuring instrumentation at least several wavelengths away from the antenna under test.

Pattern Planes

Patterns obtained above represent the antenna radiation in just one plane. In the example of the flashlight, the plane of measurement was at one height above the floor. Actually, the pattern for any antenna is three dimensional, and therefore cannot be represented in a single-plane drawing. The *solid* radiation pattern of an antenna in free space would be found by measuring the field strength at every point on the surface of an imaginary sphere having the antenna at its center. The information so obtained would then be used to construct a solid figure, where the distance from a fixed point (representing the antenna) to the surface of the figure is proportional to the field strength from the antenna in any given direction. **Fig 12B** shows a three-dimensional wire-grid representation of the radiation pattern of a half-wave dipole.

For amateur work, *relative* values of field strength (rather than absolute) are quite adequate in pattern plotting. In other words, it is not necessary to know how many microvolts per meter a particular antenna will produce at a distance of 1 mile when excited with a specified power level. (This is the kind of specifications that AM broadcast stations must meet to certify their antenna systems to the FCC.)

For whatever data is collected (or calculated from theoretical equations), it is common to normalize the plotted values so the field strength in the direction of maximum radiation coincides with the outer edge of the chart. On a given system of polar coordinate scales, the *shape* of the pattern is not altered by proper normalization, only its size.

E and H-Plane Patterns

The solid 3-D pattern of an antenna in free space cannot adequately be shown with field-strength data on a flat sheet of paper. Cartographers making maps of a round Earth on flat pieces of paper face much the same kind of problem. As we discussed above, cross-sectional or plane diagrams are very useful for this purpose. Two such diagrams, one in the plane containing the straight wire of a dipole and one in the plane perpendicular to the wire, can convey a great deal of information. The pattern in the plane containing the axis of the antenna is called the *E-plane pattern*, and the one in the plane perpendicular to the axis is called the *H-plane pattern*. These designations are used because they represent the planes in which the electric (symbol E), and the magnetic (symbol H) lines of force lie, respectively.

The E lines represent the *polarization* of the antenna. Polarization will be covered in more detail later in this chapter. As an example, the electromagnetic field pictured in Fig 1 of Chapter 23, Radio Wave Propagation, is the field that would be radiated from a vertically polarized antenna; that is, an antenna in which the conductor is mounted perpendicular to the earth.

When a radiation pattern is shown for an antenna mounted over ground rather than in free space, we automatically gain two frames of reference—an *azimuth angle* and an *elevation angle*. The azimuth angle is usually ref-

Fig 12—Directive diagram of a free-space dipole. At A, the pattern in the plane containing the wire axis. The length of each dashed-line arrow represents the relative field strength in that direction, referenced to the direction of maximum radiation, which is at right angles to the wire's axis. The arrows at approximately 45° and 315° are the half-power or –3 dB points. At B, a wire grid representation of the solid pattern for the same antenna. These same patterns apply to any center-fed dipole antenna less than a half wavelength long.

Introduction to the Decibel

The power gain of an antenna system is usually expressed in *decibels*. The decibel is a practical unit for measuring power ratios because it is more closely related to the actual effect produced at a distant receiver than the power ratio itself. One decibel represents a just-detectable change in signal strength, regardless of the actual value of the signal voltage. A 20-decibel (20-dB) increase in signal, for example, represents 20 observable steps in increased signal. The power ratio (100 to 1) corresponding to 20 dB gives an entirely exaggerated idea of the improvement in communication to be expected. The number of decibels corresponding to any power ratio is equal to 10 times the common logarithm of the power ratio, or

$$dB = 10 \log_{10} \frac{P_1}{P_2}$$

If the voltage ratio is given, the number of decibels is equal to 20 times the common logarithm of the ratio. That is,

$$dB = 20 \log_{10} \frac{V_1}{V_2}$$

When a *voltage* ratio is used, both voltages must be measured across the same value of impedance. Unless this is done the decibel figure is meaningless, because it is fundamentally a measure of a *power* ratio.

The main reason a decibel is used is that successive power gains expressed in decibels may simply be added together. Thus a gain of 3 dB followed by a gain of 6 dB gives a total gain of 9 dB. In ordinary power ratios, the ratios must be multiplied together to find the total gain.

A *reduction* in power is handled simply by subtracting the requisite number of decibels. Thus, reducing the power to ½ is the same as *subtracting* 3 decibels. For example, a power gain of 4 in one part of a system and a reduction to ½ in another part gives a total power gain of 4 × ½ = 2. In decibels, this is 6 – 3 = 3 dB. A power reduction or *loss* is simply indicated by including a negative sign in front of the appropriate number of decibels.

erenced to the maximum radiation lobe of the antenna, where the azimuth angle is defined at 0°, or it could be referenced to the Earth's True North direction for an antenna oriented in a particular compass direction. The E-plane pattern for an antenna over ground is now called the *azimuth pattern*.

The elevation angle is referenced to the horizon at the Earth's surface, where the elevation angle is 0°. Of course, the Earth is round but because its radius is so large, it can in this context be considered to be flat in the area directly under the antenna. An elevation angle of 90° is straight over the antenna, and a 180° elevation is toward the horizon directly behind the antenna.

Professional antenna engineers often describe an antenna's orientation with respect to the point directly overhead—using the *zenith angle*, rather than the elevation angle. The elevation angle is computed by subtracting the zenith angle from 90°.

Referenced to the horizon of the Earth, the H-plane pattern is now called the *elevation pattern*. Unlike the free-space H-plane pattern, the over-ground elevation pattern is drawn as a half-circle, representing only positive elevations above the Earth's surface. The ground reflects or blocks radiation at negative elevation angles, making below-surface radiation plots unnecessary.

After a little practice, and with the exercise of some imagination, the complete solid pattern can be visualized with fair accuracy from inspection of the two planar diagrams, provided of course that the solid pattern of the antenna is *smooth*, a condition that is true for simple antennas like λ/2 dipoles.

Plane diagrams are plotted on polar coordinate paper, as described earlier. The points on the pattern where the radiation is zero are called *nulls*. The curved section from one null to the next on the plane diagram, or the corresponding section on the solid pattern, is called a *lobe*. The strongest lobe is commonly called the *main lobe*. Fig 12A shows the E-plane pattern for a half-wave dipole. In Fig 12, the dipole is placed in free space. In addition to the labels showing the main lobe and nulls in the pattern, the so-called *half-power* points on the main lobe are shown. These are the points where the power is 3 dB down from the peak value in the main lobe.

Directivity and Gain

Let us now examine directivity more closely. As mentioned previously, all practical antennas, even the simplest types such as dipoles, exhibit directivity. Here's another picture that may help explain the concept of directivity. **Fig 13A** shows a balloon blown into its usual spherical shape. This represents a "reference" isotropic source. Squeezing the balloon in the middle in Fig 13B produces a dipole-like figure-8 pattern whose peak levels at top and bottom are larger than the reference sphere. Compare this with Fig 13C. Next, squeezing the bottom end of the balloon produces a pattern that gives even more "gain" compared to the reference.

Free-space directivity can be expressed quantitatively by comparing the three-dimensional pattern of the antenna under consideration with the perfectly spherical three-dimensional pattern of an isotropic antenna. The field strength (and thus power per unit area, or *power density*) is the same everywhere on the surface of an imaginary sphere having a radius of many wavelengths and having an isotropic antenna at its center. At the surface of the same imaginary sphere around an antenna radiating the same total power, the directive pattern results in greater power density at some points on this sphere and less at others. The ratio of the maximum power density to the average power density taken over the entire sphere (which is the same as from the isotropic antenna under the specified conditions) is the numerical measure of the directivity of the antenna. That is,

$$D = \frac{P}{P_{av}}$$ (Eq 5)

Fig 13—Demonstrating antenna pattern gain with balloons. Take a balloon, blow it up so that it is roughly circular in shape and then declare that this is a radiation pattern from an isotropic radiator. Next, blow up another balloon to the same size and shape and tell the audience that this will be the "reference" antenna (A). Then, squeeze the first balloon in the middle to form a sort of figure-8 shape and declare that this is a dipole and compare the maximum size to that of the reference "antenna" (B). The dipole can be seen to have some "gain" over the reference isotropic. Next, squeeze the end of the first balloon to come up with a sausage-like shape to demonstrate the sort of pattern a beam antenna creates (C).

where

D = directivity
P = power density at its maximum point on the surface of the sphere
P_{av} = average power density

The *gain* of an antenna is closely related to its direc-

tivity. Because directivity is based solely on the *shape* of the directive pattern, it does not take into account any power losses that may occur in an actual antenna system. To determine gain, these losses must be subtracted from the power supplied to the antenna. The loss is normally a constant percentage of the power input, so the antenna gain is

$$G = k\frac{P}{P_{av}} = kD \qquad \text{(Eq 6)}$$

where

      G = gain (expressed as a power ratio)
      D = directivity
      k = efficiency (power radiated divided by power input) of the antenna
      P and P_{av} are as above

For many of the antenna systems used by amateurs, the efficiency is quite high (the loss amounts to only a few percent of the total). In such cases the gain is essentially equal to the directivity. The more the directive diagram is compressed—or, in common terminology, the *sharper* the lobes—the greater the power gain of the antenna. This is a natural consequence of the fact that as power is taken away from a larger and larger portion of the sphere surrounding the radiator, it is added to the volume represented by the narrow lobes. Power is therefore concentrated in some directions, at the expense of others. In a general way, the smaller the volume of the solid radiation pattern, compared with the volume of a sphere having the same radius as the length of the largest lobe in the actual pattern, the greater the power gain.

As stated above, the gain of an antenna is related to its directivity, and directivity is related to the shape of the directive pattern. A commonly used index of directivity, and therefore the gain of an antenna, is a measure of the width of the major lobe (or lobes) of the plotted pattern. The width is expressed in degrees at the half-power or −3 dB points, and is often called the *beamwidth*.

This information provides only a general idea of relative gain, rather than an exact measure. This is because an absolute measure involves knowing the power density at every point on the surface of a sphere, while a single diagram shows the pattern shape in only one plane of that sphere. It is customary to examine at least the E-plane and the H-plane patterns before making any comparisons between antennas.

A simple approximation for gain over an isotropic radiator can be used, but only if the sidelobes in the antenna's pattern are small compared to the main lobe and if the resistive losses in the antenna are small. When the radiation pattern is complex, numerical integration is employed to give the actual gain.

$$G \approx \frac{41253}{H_{3dB} \times E_{3dB}} \qquad \text{(Eq 7)}$$

where H_{3dB} and E_{3dB} are the half-power points, in degrees, for the H and E-plane patterns.

Radiation Patterns for Center-Fed Dipoles at Different Frequencies

Earlier, we saw how the feed-point impedance of a fixed-length center-fed dipole in free space varies as the frequency is changed. What happens to the radiation pattern of such an antenna as the frequency is changed?

In general, the greater the length of a center-fed antenna, in terms of wavelength, the larger the number of lobes into which the pattern splits. A feature of all such patterns is the fact that the main lobe—the one that gives the largest field strength at a given distance—always is the one that makes the smallest angle with the antenna wire. Furthermore, this angle becomes smaller as the length of the antenna is increased.

Let's examine how the free-space radiation pattern changes for a 100-foot long wire made of #14 wire as the frequency is varied. (Varying the frequency effectively changes the wavelength for a fixed-length wire.) **Fig 14** shows the E-plane pattern at the λ/2 resonant frequency of 4.8 MHz. This is a classical dipole pattern, with a gain in free space of 2.14 dBi referenced to an isotropic radiator.

Fig 15 shows the free-space E-plane pattern for the same antenna, but now at the full-wave (2λ/2) resonant frequency of 9.55 MHz. Note how the pattern has been pinched in at the top and bottom of the figure. In other words, the two main lobes have become sharper at this frequency, making the gain 3.73 dBi, higher than at the λ/2 frequency.

Fig 14—Free-space E-Plane radiation pattern for a 100-foot dipole at its half-wave resonant frequency of 4.80 MHz. This antenna has 2.14 dBi of gain. The dipole is located on the line from 90° to 270°.

Coordinate Scales for Radiation Patterns

A number of different systems of coordinate scales or *grids* are in use for plotting antenna patterns. Antenna patterns published for amateur audiences are sometimes placed on rectangular grids, but more often they are shown using polar coordinate systems. Polar coordinate systems may be divided generally into three classes: linear, logarithmic and modified logarithmic.

A very important point to remember is that the shape of a pattern (its general appearance) is highly dependent on the grid system used for the plotting. This is exemplified in **Fig A**, where the radiation pattern for a beam antenna is presented using three coordinate systems discussed in the paragraphs that follow.

Linear Coordinate Systems

The polar coordinate system for the flashlight radiation pattern, Fig 10, uses linear coordinates. The concentric circles are equally spaced, and are graduated from 0 to 10. Such a grid may be used to prepare a linear plot of the power contained in the signal. For ease of comparison, the equally spaced concentric circles have been replaced with appropriately placed circles representing the decibel response, referenced to 0 dB at the outer edge of the plot. In these plots the minor lobes are suppressed. Lobes with peaks more than 15 dB or so below the main lobe disappear completely because of their small size. This is a good way to show the pattern of an array having high directivity and small minor lobes.

Logarithmic Coordinate System

Another coordinate system used by antenna manufacturers is the logarithmic grid, where the concentric grid lines are spaced according to the logarithm of the voltage in the signal. If the logarithmically spaced concentric circles are replaced with appropriately placed circles representing the decibel response, the decibel circles are graduated linearly. In that sense, the logarithmic grid might be termed a linear-log grid, one having linear divisions calibrated in decibels.

This grid enhances the appearance of the minor lobes. If the intent is to show the radiation pattern of an array supposedly having an omnidirectional response, this grid enhances that appearance. An antenna having a difference of 8 or 10 dB in pattern response around the compass appears to be closer to omnidirectional on this grid than on any of the others. See Fig A-(B).

ARRL Log Coordinate System

The modified logarithmic grid used by the ARRL has a system of concentric grid lines spaced according to the logarithm of 0.89 times the value of the signal voltage. In this grid, minor lobes that are 30 and 40 dB down from the main lobe are distinguishable. Such lobes are of concern in VHF and UHF work. The spacing between plotted points at 0 dB and −3 dB is significantly greater than the spacing between −20 and −23 dB, which in turn is significantly greater than the spacing between −50 and −53 dB.

For example, the scale distance covered by 0 to −3 dB is about $^1/_{10}$ of the radius of the chart. The scale distance for the next 3-dB increment (to −6 dB) is slightly less, 89% of the first, to be exact. The scale distance for the next 3-dB increment (to −9 dB) is again 89% of the second. The scale is constructed so that the progression ends with −100 dB at chart center.

The periodicity of spacing thus corresponds generally to the relative significance of such changes in antenna performance. Antenna pattern plots in this publication are made on the modified-log grid similar to that shown in Fig A-(C).

(A)

(B)

(C)

Fig 15—Free-space E-Plane radiation pattern for a 100-foot dipole at its full-wave resonant frequency of 9.55 MHz. The gain has increased to 3.73 dBi, because the main lobes have been focused and sharpened compared to Fig 13.

Fig 16—Free-space E-Plane radiation pattern for a 100-foot dipole at its 3/2λ resonant frequency of 14.60 MHz. The pattern has broken up into six lobes, and thus the peak gain has dropped to 3.44 dBi.

Fig 16 shows the pattern at the 3λ/2 frequency of 14.6 MHz. More lobes have developed compared to Fig 14. This means that the power has split up into more lobes and consequently the gain decreases a small amount, down to 3.44 dBi. This is still higher than the dipole at its λ/2 frequency, but lower than at its full-wave frequency. **Fig 17** shows the E-plane response at 19.45 MHz, the 4λ/2, or 2λ, resonant frequency. Now the pattern has reformed itself into only four lobes, and the gain has as a consequence risen to 3.96 dBi.

In **Fig 18** the response has become quite complex at the 5λ/2 resonance point of 24.45 MHz, with ten lobes showing. Despite the presence all these lobes, the main lobes now show a gain of 4.78 dBi. Finally, **Fig 19** shows the pattern at the 3λ (6λ/2) resonance at 29.45 MHz. Despite the fact that there are fewer lobes taking up power

than at 24.45 MHz, the peak gain is slightly less at 29.45 MHz, at 4.70 dBi.

The pattern—and hence the gain—of a fixed-length antenna varies considerably as the frequency is changed. Of course, the pattern and gain change in the same fashion if the frequency is kept constant and the length of the wire is varied. In either case, the wavelength is changing. It is also evident that certain lengths reinforce the pattern to provide more peak gain. If an antenna is not rotated in azimuth when the frequency is changed, the peak gain may occur in a different direction than you might like. In other words, the main lobes change direction as the frequency is varied.

POLARIZATION

We've now examined the first two of the three major properties used to characterize antennas: the radiation pattern and the feed-point impedance. The third general property is *polarization*. An antenna's polarization is defined to be that of its electric field, in the direction where the field strength is maximum.

For example, if a λ/2 dipole is mounted horizontally over the Earth, the electric field is strongest perpendicular to its axis (that is, at right angle to the wire) and parallel to the earth. Thus, since the maximum electric field is horizontal, the polarization in this case is also considered to be *horizontal* with respect to the earth. If the dipole is mounted vertically, its polarization will be *vertical*. See **Fig 20**. Note that if an antenna is mounted in free space, there is no frame of reference and hence its

---

Fig A—Radiation pattern plots for a high-gain Yagi antenna on three different grid coordinate systems. At A, the pattern on a linear-power dB grid. Notice how details of sidelobe structure are lost with this grid. At B, the same pattern on a grid with constant 5 dB circles. The sidelobe level is exaggerated when this scale is employed. At B, the same pattern on the modified log grid used by ARRL. The side and rearward lobes are clearly visible on this grid. The concentric circles in all three grids are graduated in decibels referenced to 0 dB at the outer edge of the chart. The patterns look quite different, yet they all represent the same antenna response!

Fig 17—Free-space E-Plane radiation pattern for a 100-foot dipole at twice its full-wave resonant frequency of 19.45 MHz. The pattern has been refocused into four lobes, with a peak gain of 3.96 dBi.

Fig 19—Free-space E-Plane radiation pattern for a 100-foot dipole at three times its full-wave resonant frequency of 29.45 MHz. The pattern has returned to six lobes, with a peak gain of 4.70 dBi.

Fig 18—Free-space E-Plane radiation pattern for a 100-foot dipole at its 5/2λ resonant frequency of 24.45 MHz. The pattern has broken down into ten lobes, with a peak gain of 4.78 dBi.

Fig 20—Vertical and horizontal polarization of a dipole above ground. The direction of polarization is the direction of the maximum electric field with respect to the earth.

polarization is indeterminate.

Antennas composed of a number of λ/2 elements arranged so that their axes lie in the same or parallel directions have the same polarization as that of any one of the elements. For example, a system composed of a group of horizontal dipoles is horizontally polarized. If both horizontal and vertical elements are used in the same plane and radiate in phase, however, the polarization is the

resultant of the contributions made by each set of elements to the total electromagnetic field at a given point some distance from the antenna. In such a case the resultant polarization is still *linear*, but is tilted between horizontal and vertical.

In directions other than those where the radiation is maximum, the resultant wave even for a simple dipole is a combination of horizontally and vertically polarized components. The radiation off the ends of a horizontal dipole is actually vertically polarized, albeit at a greatly reduced amplitude compared to the broadside horizontally polarized radiation—the sense of polarization

changes with compass direction.

Thus it is often helpful to consider the radiation pattern from an antenna in terms of polar coordinates, rather than trying to think in purely linear horizontal or vertical coordinates. See **Fig 21**. The reference axis in a polar system is vertical to the earth under the antenna. The zenith angle is usually referred to as θ (Greek letter theta), and the azimuth angle is referred to as ϕ (Greek letter phi). Instead of zenith angles, most amateurs are more familiar with *elevation angles*, where a zenith angle of 0° is the same as an elevation angle of 90°, straight overhead. Native *NEC* or *MININEC* computer programs use zenith angles rather than elevation angles, although most commercial versions automatically reduce these to elevation angles.

If vertical and horizontal elements in the same plane are fed out of phase (where the beginning of the RF period applied to the feed point of the vertical element is not in time phase with that applied to the horizontal), the resultant polarization is *elliptical*. Circular polarization is a special case of elliptical polarization. The wave front of a circularly polarized signal appears (in passing a fixed observer) to rotate every 90° between vertical and horizontal, making a complete 360° rotation once every period. Field intensities are *equal* at all instantaneous polarizations. Circular polarization is frequently used for space communications, and is discussed further in Chapter 19, Antenna Systems for Space Communications.

Sky-wave transmission usually changes the polarization of traveling waves. (This is discussed in Chapter 23, Radio Wave Propagation.) The polarization of receiving and transmitting antennas in the 3 to 30-MHz range, where almost all communication is by means of sky wave, need not be the same at both ends of a communication circuit (except for distances of a few miles). In this range the choice of polarization for the antenna is usually determined by factors such as the height of available antenna supports, polarization of man-made RF noise from nearby sources, probable energy losses in nearby objects, the likelihood of interfering with neighborhood broadcast or TV reception and general convenience.

Fig 21—Diagram showing polar representation of a point P lying on an imaginary sphere surround a point-source antenna. The various angles associated with this coordinate system are shown referenced to the x, y and z-axes.

Other Antenna Characteristics

Besides the three main characteristics of impedance, pattern (gain) and polarization, there are some other useful properties of antennas.

RECIPROCITY IN RECEIVING AND TRANSMITTING

Many of the properties of a resonant antenna used for reception are the same as its properties in transmission. It has the same directive pattern in both cases, and delivers maximum signal to the receiver when the signal comes from a direction in which the antenna has its best response. The impedance of the antenna is the same, at the same point of measurement, in receiving as in transmitting.

In the receiving case, the antenna is the source of power delivered to the receiver, rather than the load for a source of power (as in transmitting). Maximum possible output from the receiving antenna is obtained when the load to which the antenna is connected is the same as the impedance of the antenna. We say that the antenna is *matched* to its load.

The power gain in receiving is the same as the gain in transmitting, when certain conditions are met. One such condition is that both antennas (usually $\lambda/2$-long antennas) must work into load impedances matched to their own impedances, so that maximum power is transferred in both cases. In addition, the comparison antenna should be oriented so it gives maximum response to the signal used in the test. That is, it should have the same polarization as the incoming signal and should be placed so its direction of maximum gain is toward the signal source.

In long-distance transmission and reception via the ionosphere, the relationship between receiving and transmitting, however, may not be exactly reciprocal. This is because the waves do not always follow exactly the same

paths at all times and so may show considerable variation in the time between alternations between transmitting and receiving. Also, when more than one ionospheric layer is involved in the wave travel (see Chapter 23, Radio Wave Propagation), it is sometimes possible for reception to be good in one direction and poor in the other, over the same path.

Wave polarization usually shifts in the ionosphere. The tendency is for the arriving wave to be elliptically polarized, regardless of the polarization of the transmitting antenna. Vertically polarized antennas can be expected to show no more difference between transmission and reception than horizontally polarized antennas. On the average, however, an antenna that transmits well in a certain direction also gives favorable reception from the same direction, despite ionospheric variations.

FREQUENCY SCALING

Any antenna design can be scaled in size for use on another frequency or on another amateur band. The dimensions of the antenna may be scaled with Eq 8 below.

$$D = \frac{f1}{f2} \times d \qquad \text{(Eq 8)}$$

where
   D = scaled dimension
   d = original design dimension
   f1 = original design frequency
   f2 = scaled frequency (frequency of intended operation)

From this equation, a published antenna design for, say, 14 MHz can be scaled in size and constructed for operation on 18 MHz, or any other desired band. Similarly, an antenna design could be developed experimentally at VHF or UHF and then scaled for operation in one of the HF bands. For example, from Eq 8, an element of 39.0 inches length at 144 MHz would be scaled to 14 MHz as follows: D = 144/14 × 39 = 401.1 inches, or 33.43 feet.

To scale an antenna properly, *all* physical dimensions must be scaled, including element lengths, element spacings, boom diameters and element diameters. Lengths and spacings may be scaled in a straightforward manner as in the above example, but element diameters are often not as conveniently scaled. For example, assume a 14-MHz antenna is modeled at 144 MHz and perfected with ³/₈-inch cylindrical elements. For proper scaling to 14 MHz, the elements should be cylindrical, of 144/14 × ³/₈ or 3.86 inches diameter. From a realistic standpoint, a 4-inch diameter might be acceptable, but cylindrical elements of 4-inch diameter in lengths of 33 feet or so would be quite unwieldy (and quite expensive, not to mention heavy). Choosing another, more suitable diameter is the only practical answer.

Diameter Scaling

Simply changing the diameter of dipole type elements during the scaling process is not satisfactory without making a corresponding element-length correction. This is because changing the diameter results in a change in the λ/dia ratio from the original design, and this alters the corresponding resonant frequency of the element. The element length must be corrected to compensate for the effect of the different diameter actually used.

To be more precise, however, the purpose of diameter scaling is not to maintain the same resonant frequency for the element, but to maintain the same ratio of self-resistance to self-reactance at the operating frequency—that is, the Q of the scaled element should be the same as that of the original element. This is not always possible to achieve exactly for elements that use several telescoping sections of tubing.

Tapered Elements

Rotatable beam antennas are usually constructed with elements made of metal tubing. The general practice at HF is to taper the elements with lengths of telescoping tubing. The center section has a large diameter, but the ends are relatively small. This reduces not only the weight, but also the cost of materials for the elements. Tapering of HF Yagi elements is discussed in detail in Chapter 11, HF Yagi Arrays.

Length Correction for Tapered Elements

The effect of tapering an element is to alter its electrical length. That is to say, two elements of the same length, one cylindrical and one tapered but with the same average diameter as the cylindrical element, will not be resonant at the same frequency. The tapered element must be made longer than the cylindrical element for the same resonant frequency.

A procedure for calculating the length for tapered elements has been worked out by Dave Leeson, W6NL (ex-W6QHS), from work done by Schelkunoff at Bell Labs and is presented in Leeson's book, *Physical Design of Yagi Antennas*. In the software accompanying this book is a subroutine called EFFLEN.FOR. It is written in Fortran and is used in the *SCALE* program to compute the effective length of a tapered element. The algorithm uses the W6NL-Schelkunoff algorithm and is commented step-by-step to show what is happening. Calculations are made for only one half of an element, assuming the element is symmetrical about the point of boom attachment.

Also, read the documentation SCALE.PDF for the *SCALE* program, which will automatically do the complex mathematics to scale a Yagi design from one frequency to another, or from one taper schedule to another.

The Vertical Monopole

So far in this discussion on Antenna Fundamentals, we have been using the free-space, center-fed dipole as our main example. Another simple form of antenna derived from a dipole is called a *monopole*. The name suggests that this is one half of a dipole, and so it is. The monopole is always used in conjunction with a *ground plane*, which acts as a sort of electrical mirror. See **Fig 22**, where a $\lambda/2$ dipole and a $\lambda/4$ monopole are compared. The *image antenna* for the monopole is the dotted line beneath the ground plane. The image forms the missing second half of the antenna, transforming a monopole into the functional equivalent of a dipole. From this explanation you can see where the term *image plane* is sometimes used instead of ground plane.

Although we have been focusing throughout this chapter on antennas in free space, practical monopoles are usually mounted vertically with respect to the surface of the ground. As such, they are called *vertical monopoles*, or simply *verticals*. A practical vertical is supplied power by feeding the radiator against a ground system, usually made up of a series of paralleled wires radiating from and laid out in a circular pattern around the base of the antenna. These wires are termed *radials*.

The term *ground plane* is also used to describe a vertical antenna employing a $\lambda/4$-long vertical radiator working against a *counterpoise* system, another name for the ground plane that supplies the missing half of the antenna. The counterpoise for a ground-plane antenna usually consists of four $\lambda/4$-long radials elevated well above the earth. See **Fig 23**.

Chapter 3, The Effects of Ground, devotes much attention to the requirements for an efficient grounding system for vertical monopole antennas, and Chapter 6, Low-Frequency Antennas, gives more information on ground-plane verticals.

Characteristics of a $\lambda/4$ Monopole

The free-space directional characteristics of a $\lambda/4$ monopole with its ground plane are very similar to that of a $\lambda/2$ antenna in free space. The gain for the $\lambda/4$ monopole is slightly less because the H-plane for the $\lambda/2$ antenna is compressed compared to the monopole. Like a $\lambda/2$ antenna, the $\lambda/4$ monopole has an *omnidirectional* radiation pattern in the plane perpendicular to the monopole.

The current in a $\lambda/4$ monopole varies practically sinusoidally (as is the case with a $\lambda/2$ wire), and is highest at the ground-plane connection. The RF voltage is highest at the open (top) end and minimum at the ground plane. The feed-point resistance close to $\lambda/4$ resonance of a vertical monopole over a perfect ground plane is one-half that for a $\lambda/2$ dipole at its $\lambda/2$ resonance. In this case, a "perfect ground plane" is an infinitely large, lossless conductor.

See **Fig 24**, which shows the feed-point impedance of a vertical antenna made of #14 wire, 50 feet long, located over perfect ground. This is over the whole HF range from 1 to 30 MHz. Again, there is nothing special about the choice of 50 feet for the length of the vertical radiator; it is simply a convenient length for evaluation. **Fig 25** shows an expanded portion of the frequency range above and below the $\lambda/4$ resonant point, but now calibrated in terms of wavelength. Note that this particular antenna goes through $\lambda/4$ resonance at a length of 0.244 λ, not at exactly 0.25 λ. The exact length for resonance varies with the diameter of the wire used, just as it does for the $\lambda/2$ dipole at its $\lambda/2$ resonance.

The word *height* is usually used for a vertical monopole antenna whose base is on or near the ground, and in this context, height has the same meaning as *length* when applied to $\lambda/2$ dipole antennas. Older texts often refer to heights in electrical degrees, referenced to a free-space wavelength of 360°, but here height is expressed in terms of the free-space wavelength. The range shown in Fig 24 is from 0.132 λ to 0.300 λ, corresponding to a frequency range of 2.0 to 5.9 MHz.

Fig 22—The $\lambda/2$ dipole antenna and its $\lambda/4$ ground-plane counterpart. The "missing" quarter wavelength is supplied as an image in "perfect" (that is, high-conductivity) ground.

Fig 23—The ground-plane antenna. Power is applied between the base of the vertical radiator and the center of the four ground plane wires.

Fig 24—Feed-point impedance versus frequency for a theoretical 50-foot-high grounded vertical monopole made of #14 wire. The numbers along the curve show the frequency in MHz. This was computed using "perfect" ground. Real ground losses will add to the feed-point impedance shown in an actual antenna system.

Fig 25—Feed-point impedance for the same antennas as in Fig 21, but calibrated in wavelength rather than frequency, over the range from 0.132 to 0.300λ, above and below the quarter-wave resonance.

The reactive portion of the feed-point impedance depends highly on the length/dia ratio of the conductor, as was discussed previously for a horizontal center-fed dipole. The impedance curve in Figs 24 and 25 is based on a #14 conductor having a length/dia ratio of about 800 to 1. As usual, thicker antennas can be expected to show less reactance at a given height, and thinner antennas will show more.

Efficiency of Vertical Monopoles

This topic of the efficiency of vertical monopole systems will be covered in detail in Chapter 3, The Effects of Ground, but it is worth noting at this point that the efficiency of a real vertical antenna over real earth often suffers dramatically compared with that of a λ/2 antenna. Without a fairly elaborate grounding system, the efficiency is not likely to exceed 50%, and it may be much less, particularly at monopole heights below λ/4.

BIBLIOGRAPHY

J. S. Belrose, "Short Antennas for Mobile Operation," *QST*, Sep 1953.

G. H. Brown, "The Phase and Magnitude of Earth Currents Near Radio Transmitting Antennas," *Proc IRE*, Feb 1935.

G. H. Brown, R. F. Lewis and J. Epstein, "Ground Systems as a Factor in Antenna Efficiency," *Proc IRE*, Jun 1937, pp 753-787.

G. H. Brown and O. M. Woodward, Jr., "Experimentally Determined Impedance Characteristics of Cylindrical Antennas," *Proc IRE*, April 1945.

A. Christman, "Elevated Vertical Antenna Systems," *QST*, Aug 1988, pp 35-42.

R. B. Dome, "Increased Radiating Efficiency for Short Antennas," *QST*, Sep 1934, pp 9-12.

A. C. Doty, Jr., J. A. Frey and H. J. Mills, "Characteristics of the Counterpoise and Elevated Ground Screen," Professional Program, Session 9, Southcon '83 (IEEE), Atlanta, GA, Jan 1983.

A. C. Doty, Jr., J. A. Frey and H. J. Mills, "Efficient Ground Systems for Vertical Antennas," *QST*, Feb 1983, pp 20-25.

A. C. Doty, Jr., technical paper presentation, "Capacitive Bottom Loading and Other Aspects of Vertical Antennas," Technical Symposium, Radio Club of America, New York City, Nov 20, 1987.

A. C. Doty, Jr., J. A. Frey and H. J. Mills, "Vertical Antennas: New Design and Construction Data," *The ARRL Antenna Compendium, Volume 2* (Newington: ARRL, 1989), pp 2-9.

R. Fosberg, "Some Notes on Ground Systems for 160 Meters," *QST*, Apr 1965, pp 65-67.

G. Grammer, "More on the Directivity of Horizontal Antennas; Harmonic Operation—Effects of Tilting," *QST*, Mar 1937, pp 38-40, 92, 94, 98.

H. E. Green, "Design Data for Short and Medium Length Yagi-Uda Arrays," *Trans IE Australia*, Vol EE-2, No. 1, Mar 1966.

H. J. Mills, technical paper presentation, "Impedance Transformation Provided by Folded Monopole Antennas," Technical Symposium, Radio Club of America, New York City, Nov 20, 1987.

B. Myers, "The W2PV Four-Element Yagi," *QST*, Oct 1986, pp 15-19.

L. Richard, "Parallel Dipoles of 300-Ohm Ribbon," *QST*, Mar 1957.

J. H. Richmond, "Monopole Antenna on Circular Disc," *IEEE Trans on Antennas and Propagation*, Vol. AP-32, No. 12, Dec 1984.

W. Schulz, "Designing a Vertical Antenna," *QST*, Sep 1978, pp 19- 21.

J. Sevick, "The Ground-Image Vertical Antenna," *QST*, Jul 1971, pp 16-17, 22.

J. Sevick, "The W2FMI 20-Meter Vertical Beam," *QST*, Jun 1972, pp 14-18.

J. Sevick, "The W2FMI Ground-Mounted Short Vertical," *QST*, Mar 1973, pp. 13-18, 41.

J. Sevick, "A High Performance 20-, 40- and 80-Meter Vertical System," *QST*, Dec 1973.

J. Sevick, "Short Ground-Radial Systems for Short Verticals," *QST*, Apr 1978, pp 30-33.

J. Sevick, *Transmission Line Transformers*, 3rd ed. (Tucker, GA: Noble Publishing, 1996).

C. E. Smith and E. M. Johnson, "Performance of Short Antennas," *Proc IRE*, Oct 1947.

J. Stanley, "Optimum Ground Systems for Vertical Antennas," *QST*, Dec 1976, pp 13-15.

R. E. Stephens, "Admittance Matching the Ground-Plane Antenna to Coaxial Transmission Line," Technical Correspondence, *QST*, Apr 1973, pp 55-57.

D. Sumner, "Cushcraft 32-19 'Boomer' and 324-QK Stacking Kit," Product Review, *QST*, Nov 1980, pp 48-49.

W. van B. Roberts, "Input Impedance of a Folded Dipole," *RCA Review*, Jun 1947.

E. M. Williams, "Radiating Characteristics of Short-Wave Loop Aerials," *Proc IRE*, Oct 1940.

TEXTBOOKS ON ANTENNAS

C. A. Balanis, *Antenna Theory, Analysis and Design* (New York: Harper & Row, 1982).

D. S. Bond, *Radio Direction Finders*, 1st ed. (New York: McGraw-Hill Book Co).

W. N. Caron, *Antenna Impedance Matching* (Newington: ARRL, 1989).

K. Davies, *Ionospheric Radio Propagation*—National Bureau of Standards Monograph 80 (Washington, DC: U.S. Government Printing Office, Apr 1, 1965).

R. S. Elliott, *Antenna Theory and Design* (Englewood Cliffs, NJ: Prentice Hall, 1981).

A. E. Harper, *Rhombic Antenna Design* (New York: D. Van Nostrand Co, Inc, 1941).

K. Henney, *Principles of Radio* (New York: John Wiley and Sons, 1938), p 462.

H. Jasik, *Antenna Engineering Handbook*, 1st ed. (New York: McGraw-Hill, 1961).

W. C. Johnson, *Transmission Lines and Networks*, 1st ed. (New York: McGraw-Hill Book Co, 1950).

R. C. Johnson and H. Jasik, *Antenna Engineering Handbook*, 2nd ed. (New York: McGraw-Hill, 1984).

R. C. Johnson, *Antenna Engineering Handbook*, 3rd ed. (New York: McGraw-Hill, 1993).

E. C. Jordan and K. G. Balmain, *Electromagnetic Waves and Radiating Systems*, 2nd ed. (Englewood Cliffs, NJ: Prentice-Hall, Inc, 1968).

R. Keen, *Wireless Direction Finding*, 3rd ed. (London: Wireless World).

R. W. P. King, *Theory of Linear Antennas* (Cambridge, MA: Harvard Univ. Press, 1956).

R. W. P. King, H. R. Mimno and A. H. Wing, *Transmission Lines, Antennas and Waveguides* (New York: Dover Publications, Inc, 1965).

King, Mack and Sandler, *Arrays of Cylindrical Dipoles* (London: Cambridge Univ Press, 1968).

M. G. Knitter, Ed., *Loop Antennas—Design and Theory* (Cambridge, WI: National Radio Club, 1983).

M. G. Knitter, Ed., *Beverage and Long Wire Antennas—Design and Theory* (Cambridge, WI: National Radio Club, 1983).

J. D. Kraus, *Electromagnetics* (New York: McGraw-Hill Book Co).

J. D. Kraus, *Antennas*, 2nd ed. (New York: McGraw-Hill Book Co, 1988).

E. A. Laport, *Radio Antenna Engineering* (New York: McGraw-Hill Book Co, 1952).

J. L. Lawson, *Yagi-Antenna Design*, 1st ed. (Newington: ARRL, 1986).

P. H. Lee, *The Amateur Radio Vertical Antenna Handbook*, 2nd ed. (Port Washington, NY: Cowen Publishing Co., 1984).

A. W. Lowe, *Reflector Antennas* (New York: IEEE Press, 1978).

M. W. Maxwell, *Reflections—Transmission Lines and Antennas* (Newington: ARRL, 1990). Out of print.

M. W. Maxwell, *Reflections II—Transmission Lines and Antennas* (Sacramento: Worldradio Books, 2001).

G. M. Miller, *Modern Electronic Communication* (Englewood Cliffs, NJ: Prentice Hall, 1983).

V. A. Misek, *The Beverage Antenna Handbook* (Hudson, NH: V. A. Misek, 1977).

T. Moreno, *Microwave Transmission Design Data* (New York: McGraw-Hill, 1948).

L. A. Moxon, *HF Antennas for All Locations* (Potters Bar, Herts: Radio Society of Great Britain, 1982), pp 109-111.

Ramo and Whinnery, *Fields and Waves in Modern Radio* (New York: John Wiley & Sons).

V. H. Rumsey, *Frequency Independent Antennas* (New York: Academic Press, 1966).

P. N. Saveskie, *Radio Propagation Handbook* (Blue Ridge Summit, PA: Tab Books, Inc, 1980).

S. A. Schelkunoff, *Advanced Antenna Theory* (New York: John Wiley & Sons, Inc, 1952).

S. A. Schelkunoff and H. T. Friis, *Antennas Theory and Practice* (New York: John Wiley & Sons, Inc, 1952).

J. Sevick, *Transmission Line Transformers* (Atlanta: Noble Publishing, 1996).

H. H. Skilling, *Electric Transmission Lines* (New York: McGraw-Hill Book Co, Inc, 1951).

M. Slurzburg and W. Osterheld, *Electrical Essentials of Radio* (New York: McGraw-Hill Book Co, Inc, 1944).

G. Southworth, *Principles and Applications of Waveguide*

Transmission (New York: D. Van Nostrand Co, 1950).

F. E. Terman, *Radio Engineers' Handbook*, 1st ed. (New York, London: McGraw-Hill Book Co, 1943).

F. E. Terman, *Radio Engineering*, 3rd ed. (New York: McGraw-Hill, 1947).

S. Uda and Y. Mushiake, *Yagi-Uda Antenna* (Sendai, Japan: Sasaki Publishing Co, 1954). [Published in English—Ed.]

P. P. Viezbicke, "*Yagi Antenna Design*," NBS Technical Note 688 (U. S. Dept of Commerce/National Bureau of Standards, Boulder, CO), Dec 1976.

G. B. Welch, *Wave Propagation and Antennas* (New York: D. Van Nostrand Co, 1958), pp 180-182.

The GIANT Book of Amateur Radio Antennas (Blue Ridge Summit, PA: Tab Books, 1979), pp 55-85.

IEEE Standard Dictionary of Electrical and Electronics Terms, 3rd ed. (New York: IEEE, 1984).

Radio Broadcast Ground Systems, available from Smith Electronics, Inc, 8200 Snowville Rd, Cleveland, OH 44141.

Radio Communication Handbook, 5th ed. (London: RSGB, 1976).

Radio Direction Finding, published by the Happy Flyer, 1811 Hillman Ave, Belmont, CA 94002

The Effects of Ground

The ground around and under an antenna is part of the environment in which any actual antenna must operate. Chapter 2, Antenna Fundamentals, dealt mainly with theoretical antennas in free space, completely removed from the influence of the ground. This chapter is devoted to exploring the interactions between antennas and the ground.

The interactions can be analyzed depending on where they occur relative to two areas surrounding the antenna: the *reactive near field* and the *radiating far field*. You will recall that the reactive near field only exists very close to the antenna itself. In this region the antenna acts as though it were a large lumped-constant inductor or capacitor, where energy is stored but very little is actually radiated. The interaction with the ground in this area creates mutual impedances between the antenna and its environment and these interactions not only modify the feed-point impedance of an antenna, but also often increase losses.

In the radiating far field, the presence of ground profoundly influences the radiation pattern of a real antenna. The interaction is different, depending on the antenna's polarization with respect to the ground. For horizontally polarized antennas, the *shape* of the radiated pattern in the elevation plane depends primarily on the antenna's height above ground. For vertically polarized antennas, both the *shape* and the *strength* of the radiated pattern in the elevation plane strongly depend on the nature of the ground itself (its dielectric constant and conductivity at the frequency of operation), as well as on the height of the antenna above ground.

The Effects of Ground in the Reactive Near Field

FEED-POINT IMPEDANCE VERSUS HEIGHT ABOVE GROUND

Waves radiated from the antenna directly downward reflect vertically from the ground and, in passing the antenna on their upward journey, induce a voltage in it. The magnitude and phase of the current resulting from this induced voltage depends on the height of the antenna above the reflecting surface.

The total current in the antenna consists of two components. The amplitude of the first is determined by the power supplied by the transmitter and the free-space feed-point resistance of the antenna. The second component is induced in the antenna by the wave reflected from the ground. This second component of current, while considerably smaller than the first at most useful antenna heights, is by no means insignificant. At some heights, the two components will be in phase, so the total current is larger than is indicated by the free-space feed-point resistance. At other heights, the two components are out of phase, and the total current is the difference between the two components.

Changing the height of the antenna above ground will change the amount of current flow, assuming that the power input to the antenna is constant. A higher current at the same power input means that the effective resistance of the

antenna is lower, and vice versa. In other words, the feed-point resistance of the antenna is affected by the height of the antenna above ground because of mutual coupling between the antenna and the ground beneath it.

The electrical characteristics of the ground affect both the amplitude and the phase of reflected signals. For this reason, the electrical characteristics of the ground under the antenna will have some effect on the impedance of that antenna, the reflected wave having been influenced by the ground. Different impedance values may be encountered when an antenna is erected at identical heights but over different types of earth.

Fig 1 shows the way in which the radiation resistance of horizontal and vertical half-wave antennas varies with height above ground (in λ, wavelengths). The height of the vertical half-wave is the distance from the bottom of the antenna to ground. For horizontally polarized half-wave antennas, the differences between the effects of perfect ground and real earth are negligible if the antenna height is greater than 0.2 λ. At lower heights, the feed-point resistance over perfect ground decreases rapidly as the antenna is brought closer to a theoretically perfect ground, but this does not occur so rapidly for actual ground. Over real earth, the resistance actually begins increasing at heights below about 0.08 λ. The reason for the increasing resistance at very low heights is that more and more of the reactive (induction) field of the

antenna is absorbed by the lossy ground in close proximity. This results in increased loss that is reflected in the increased value of the feedpoint resistance.

For a vertically polarized λ/2-long dipole, differences between the effects of perfect ground and real earth on the feed-point impedance is negligible, as seen in **Fig 1**. The theoretical half-wave antennas on which this chart is based are assumed to have infinitely thin conductors.

GROUND SYSTEMS FOR VERTICAL MONOPOLES

In this section, we'll look at vertical monopoles, which require some sort of ground system in order to make up for the "missing" second half of the antenna and reduce the power lost in the near field. Rudy Severns, N6LF, contributed much of the new material in this chapter.

In Chapter 2, Antenna Fundamentals, and up to this point in this chapter, the discussion about vertical monopoles has mainly been for antennas where *perfect ground* is available. We have also briefly looked at the ground-plane vertical in free space, where the four ground-plane radials form a built-in ground system.

Perfect ground makes a vertical monopole into the functional equivalent of a center-fed dipole, although the feed-point resistance at resonance is half that of the center-fed dipole. But how can we manage to create that elusive perfect ground, or at least a reasonable approximation, for our real vertical antennas?

Simulating a Perfect Ground in the Reactive Near Field

The effect of a perfectly conducting ground (so far as feed-point resistance and losses are concerned) can be simulated under a real antenna by installing a very large metal screen or mesh, such as poultry netting (chicken wire) or hardware cloth, on or near the surface of the ground. The screen (also called a *counterpoise system*, especially if it is elevated off the ground) should extend at least a half wavelength in every direction from the antenna. The feed-point resistance of a quarter-wave long, thin vertical radiator over such a ground screen will approach the theoretical value of 36.6 Ω. Of course on the lower HF bands such a screen is not practical for most amateurs.

Based on the results of a study published in 1937 by Brown, Lewis and Epstein (see Bibliography), a grounding system consisting of 120 wires, each at least λ/2 long, extending radially from the base of the antenna and spaced equally around a circle, is also the practical equivalent of perfectly conducting ground for reactive-field currents. The wires can either be laid directly on the surface of the ground or buried a few inches below.

Another approach to simulating a perfect ground system is to utilize the ground-plane antenna, with its four ground-plane radials elevated well above lossy earth. Heights (between the bottom of the ground-plane and the surface of the ground) greater than λ/8 have proven to yield excellent

Fig 1—Variation in radiation resistance of vertical and horizontal half-wave antennas at various heights above flat ground. Solid lines are for perfectly conducting ground; the broken line is the radiation resistance of horizontal half-wave antennas at low height over real ground.

results. See Chapter 6, Low-Frequency Antennas, for more details on practical ground-plane verticals.

For a vertical antenna, a large ground screen, either made of wire mesh or a multitude of radials, or an elevated system of ground-plane radials will reduce ground losses near the antenna. This is because the screen conductors are solidly bonded to each other and the resistance is much lower than that of the lossy, low-conductivity earth itself. If the ground screen or elevated ground plane were not present, RF currents would be forced to flow through the lossy, low-conductivity earth to return to the base of the radiator. The ground screen or elevated ground plane in effect shield ground-return currents from the lossy earth.

Less-Than-Ideal Ground Systems

Now, what happens when something less than an ideal ground screen is used as the ground plane for a vertical monopole? Typically this will take the form of an on-ground wire radial system. A great deal of mystery and lack of information seems to surround the vertical antenna ground system. In the case of ground-mounted vertical antennas, many general statements such as "the more radials the better" and "lots of short radials are better than a few long ones" have served as rules of thumb, but many questions as to relative performance differences and optimum number for a given length remain unanswered, as is the justification for the rules of thumb. Most of these questions boil down to one: namely, how many radials, and how long, should be used in a given vertical antenna installation?

A ground system with 120 $\lambda/2$ radials is not very practical for many amateur installations, which often must contend with limited space and funding. Unfortunately the ground resistance, R_g, increases rapidly when the number of radials is reduced. To minimize ground loss where a large, optimum ground system is not possible requires that we understand how ground losses occur and how to optimize the design of a ground system that can fit within the space and budget available.

E and H Fields

E and H fields were introduced in Chapter 2, Antenna Fundamentals, to explain some basic concepts concerning antennas. To understand the reasons for ground loss we need to look at the E and H fields in the near field, but we need to have some feeling for what E and H fields are. The following is a brief description of these fields. It is certainly not a rigorous description but should give at least an intuitive feeling for what is happening.

In 1820 Hans Oerstad discovered that a current flowing in a wire would deflect the needle of a nearby compass. We attribute this effect to a *magnetic* or *H-field*, which at any given location is denoted by the bold-faced letter **H**. **H** is a vector, with an amplitude expressed in A/m (Amperes/meter) and a direction. **Fig 2** shows a typical experimental arrangement. The shape of the magnetic field is roughly shown by the distribution of the iron fil-

ings. This field distribution is very similar to that for a vertical antenna.

A compass needle (a small magnet itself) will try to align itself parallel to **H.** As the compass is moved around the conductor, the orientation of the needle changes accordingly. The orientation of the needle gives the direction of **H**. If you attempt to turn the needle away from alignment you will discover a torque trying to restore the needle to its original position. The torque is proportional to the strength of the magnetic field at that point. This is called the *field intensity* or amplitude of **H** at that point. If a larger current flows in the conductor going through the piece of paper holding the iron filings, the amplitude of **H** will be larger. Currents flowing in the conductors of an antenna also generate a magnetic field, one component of the near field.

An antenna will also have an *electric* or *E-field*, which can be visualized using a parallel-plate capacitor, as shown in **Fig 3**. If we connect a battery with a potential V_{dc} across the capacitor plates there will be an electric field **E** established between the plates, as indicated by the lines and directional arrows between the plates. The magnitude of vector **E** is expressed in V/m (volts per meter), so for a potential of V volts and a spacing of d meters, E = V/d V/m. The amplitude of **E** will increase with greater voltage and/or a smaller distance (d). In an antenna, there will be ac potential differences between different parts of the antenna and from the antenna to ground. These ac potential differences establish the electric field associated with the antenna.

Conduction And Displacement Currents

If we replace the dc voltage source in Fig 3 with an ac source, a steady ac current will flow in the circuit. In the

Fig 2—The magnetic lines of force that surround a conductor with an electric current flowing in it are shown by iron filings and small compass needles. The needles point in the direction of the magnetic or H-field. The filings give a general view of the field distribution in the plane perpendicular to the conductor.

conductors between the ac source and the capacitor plates, current (I_c) flows, because of the movement of charge, usually electrons. But in the space between the capacitor plates—particularly in a vacuum—there are no charge carriers available to carry a conduction current. Nonetheless, current still flows in the complete circuit, and we attribute this to a *displacement current* (I_d) flowing between the capacitor plates to account for the continuity of current in the circuit. Displacement and conduction currents are two different phenomena but they both represent current, just two different kinds. Some observers prefer to call conduction currents "currents" and displacement currents "imaginary currents." That terminology is OK, but to account for the current flow in a closed circuit with capacitance you have to keep track of both kinds of current, whatever you call them.

In an antenna over ground, the displacement current represents the current flow from the antenna surface through the air into the ground. The currents flowing in the ground are predominantly conduction currents, but there may also be displacement currents.

Where the dielectric material between the capacitor plates is not a perfect insulator, both conduction and displacement currents can flow between the capacitor plates. A good example of this would be a soil dielectric, which has both resistive and capacitive characteristics. Soil can be represented in the circuit of **Fig 4**, where there is a resistor with a conduction current I_c in parallel with a capacitor with a displacement current I_d. The two currents add up (vectorially) as the total current I_T.

A Closer Look at Verticals

A vertical antenna has two field components that induce currents in the ground around the antenna. **Fig 5** shows in a general way the electric-field component (E_z, in V/m) and magnetic-field component (H_ϕ, in A/m) in the region near a vertical. Because the soil near the antenna usually has relatively high resistance, both of these field components will induce currents (I_V and I_H) in the ground, resulting in losses. While the worms may enjoy the heated ground, power dissipated in the ground is subtracted from the radiated power, weakening your signal.

As shown in Fig 5, the tangential component of the H-field (H_ϕ) induces horizontal currents (I_H) flowing radially. The normal component (perpendicular to the ground surface) of the E-field (E_z) induces vertically flowing currents (I_V). Actually, things are more complex than this but we don't need to thrash through that to understand conceptually what's going on.

When modeling an antenna we account for the radiated power (P_r) by assuming there is a resistor we call the *radiation resistance* (R_r) through which the antenna base current (I_o) flows. The radiated power is then $P_r = I_o^2 R_r$. Similarly, we can account for the power dissipated in the ground (P_g) by adding a loss resistance (R_g) in series with R_r. The ground loss is then $P_g = I_o^2 R_g$. Additional losses due to conductors, loading coils, etc can also be simulated

Fig 3—Example of an electric field, $E=V_{dc}/d$. When the dc source is replaced with an ac source there will be a displacement current (I_d) flowing between the capacitor plates.

Fig 4—When the capacitor dielectric is less than perfect there will be a conduction current (I_c) in addition to the displacement current (I_d). Soil will typically have both resistive and capacitive components. Power loss in the soil is due to the current flowing through the resistive component.

Fig 5—A general view of the fields and ground currents near the base of a vertical antenna. Note that the H-field distribution is equivalent to that shown in Fig 3.

by adding more series loss resistances. Putting aside for the moment these additional losses, the efficiency (η) of a vertical can be expressed as:

$$\eta = \frac{P_r}{P_r + P_g} \qquad \text{(Eq 1)}$$

This can be restated in terms of resistances as:

$$\eta = \frac{R_r}{R_r + R_g} = \frac{1}{1 + \dfrac{R_g}{R_r}} \qquad \text{(Eq 2)}$$

In essence, efficiency is the ratio of the radiated power to the total input power ($P_T = P_r + P_g$). Another way of saying this is that efficiency depends on the ratio of ground loss resistance (R_g) to radiation resistance (R_r), as Eq 2 shows. The smaller we make R_g the more power will be radiated for a given input power. Reducing R_g is the purpose of the ground system.

A sketch of current flow in the antenna and the surrounding ground (due to H-field), near the base of a vertical, is shown in **Fig 6**. I_z represents the total *zone current* flowing radially through a cylindrical zone at a given radius (r) due to the H field, while I_o is the current at the feed point at the base of the antenna. Technically speaking, the cylinder is infinitely deep, with I_z being the total current integrated over the surface of the cylinder at a given radius.

Fig 7 is a graph of the amplitude of I_z for several antenna heights in wavelengths (h) as we move away from the base of the antenna. Fig 7 shows the zone current that would flow in the ground returning to the base of the antenna, assuming a single ground rod is placed at the feed point for the vertical radiator. The heights indicated are the effective electrical heights. For example, if you use some top loading on the vertical, the effective electrical height will be greater than the physical height.

It is important to recognize that simply adding a top hat to a vertical of a given physical height may reduce ground losses. We can see this from the effect of h on ground current amplitude in Fig 7. Increasing h reduces the ground current. Even something as simple as moving a loading coil from the base up to the center of the antenna may reduce ground losses because it reduces ground current amplitude. But we do have to be careful that the loss introduced by the loading coil does not overcome the reduction in ground loss! Both loading-coil and top-hat schemes also increase the radiation resistance R_r, which further improves efficiency.

The currents in Fig 7 have been adjusted for constant radiated power at the base of the antenna by varying I_o to compensate for the change in R_r as we vary h. To maintain constant radiated power as R_r is falling, you must increase I_o. The base feed-point impedance is a strong function of h. For example, for h = 0.25 λ, R_r will be in the neighborhood of 36 Ω. However, for h = 0.1 λ, R_r will be less than 4 Ω. More information on short antennas can be found in Chapter 16, Mobile and Maritime Antennas.

Fig 7 clearly shows the high currents that flow in the ground near the base of a short antenna due to the antenna's H field. Compared to a 0.25-λ vertical, the 0.1-λ vertical has about three times the base current. As you shorten the antenna further, the zone current increases even more quickly. The ground loss is proportional to the square of the ground current ($P_g = I_g^2 R_g$), so the power loss in the immediate

Fig 6—Representation of the zone current near the base of a vertical antenna. Individual i_z components of current flow into a cylinder of soil, with a radius r centered on the base of the vertical. The total current, I_z, thus represents the net current induced in the soil by the H-field for a given radius. (I_z was labeled I_H in Fig 5.)

Fig 7—Plot of zone current (I_z) in amperes near the base of a vertical as a function of height (h) and radius (r) in wavelengths. The current in the base of the 0.25-λ antenna is assumed to be 1 A and the current for other values of h is adjusted to maintain the same radiated power ($P_r = I_o^2 R_r = 37$ W) as the radiation resistance (R_r) changes with h.

Fig 8—Total H-field induced ground loss within a circle of radius r around the base of a vertical for different values of h and constant $P_r = 37$ W. Note how the total loss increases rapidly near the base of the antenna indicating high loss. Beyond r = 0.15 λ, however, the additional loss is much lower and the curves flatten out. Note also how much higher the loss is for shorter antennas.

region of the base is much higher for a short antenna operating with the same input power as for a quarter-wave vertical.

We can calculate the losses induced in the soil by either the E- or H-field intensity. **Fig 8** shows an example of the H-field losses for several different antenna heights, given a constant radiated power of 37 W. Note that the total loss within 0.5 λ of the base for h = 0.25 λ is about 16 W (right side of the graph). This gives $\eta = 37/(37 + 16) = 70\%$. However, for h = 0.1 λ, the total loss is about 94 W. Taking into consideration only the H-field losses, $\eta = 37/(37 + 94) = 28\%$. Note that in both cases the majority of the loss is near ($< 0.1 \lambda$) the antenna, with the rate of increase of total loss decreasing rapidly as we move farther away from the base, where the lines are almost flat.

Fig 9 is a graph of the E-field intensity around a vertical with 1500 W radiated power, for three values of h. The E-field intensity doesn't depend on the exact type of ground system. (You can see this when you consider that the voltage across a capacitor doesn't depend on the size of the capacitor's plates.) Notice that close to the base, the E-field intensity for the 0.1-λ vertical is almost 100 times that for the 0.25-λ vertical. Because loss is proportional to the square of the voltage, the E-field losses close to the base will be ten thousand times larger in the 0.1-λ vertical! At a 1500-W power level the field intensity near the base of a short vertical is high enough to pose some risk of igniting grass and bushes that grow above any radial system close to the vertical's base. The grass should be kept mowed within 0.1 λ of the base.

Fig 10 shows a computation for the E-field losses, again for a constant radiated power of 37 W and several values of h. For the 0.25-λ vertical, the electric field intensity is quite low and so are the losses associated with it, at only 1.5 W.

Fig 9—Electric field intensity near the base of a vertical for different values of h. P_r is held constant at 1500 W.

With any reasonable ground system, the E-field losses for a 0.25-λ vertical will be insignificant.

For shorter or longer verticals, however, the picture is different. This is why we see the very high losses (> 100 W) in Fig 10 for h = 0.1 λ. This loss, when added to the H-field loss, reduces the efficiency of the 0.1-λ vertical to 16% or less without a good ground system. In short antennas the E-field losses cannot be ignored, since they get worse exponentially as the antenna is shortened further.

The presence of a top-loading hat will also increase the E-field intensity in the area below the hat. However, most practical amateur hats will be quite small and the associated E-field loss small. The benefit, however, of reducing I_o because of the addition of the hat—which reduces the field

Fig 10—Total E-field induced ground loss within a circle of radius r around the base of a vertical for different values of h and constant P_r = 37 W. Note how the total loss increases rapidly near the base of the antenna, indicating high loss. Beyond r = 0.05 λ, however, the additional loss is much lower and the curves flatten out. Note again how much higher the loss is for shorter antennas. For h = 0.1 λ the E-field loss is greater than the H-field loss.

Fig 11—Effective ground resistance (R_g) at the base of the vertical as a function of the radius of a ground screen for several different antenna heights. Note how R_g falls as power dissipation in the soil is eliminated by the highly conducting ground screen.

from the vertical part of the antenna—more than compensates for the small additional E-field loss due to the hat.

Verticals taller than 0.25 λ also display increased E-field intensity, but not nearly so severe as short verticals. In verticals both shorter and longer than a 0.25 λ, the critical loss region is within a radius of about 0.05 λ. We can see this in Fig 10, where the power-loss curves for the shorter antennas flatten out by the time we reach a radius of 0.05 λ.

It's not widely known, but while radial wire systems reduce the H-field losses very effectively, Larsen (see Bibliography) has shown that the E-field losses with the same radial system do not fall in the same fashion as H-field losses. For h > 0.15 λ this doesn't matter much because the E-field

loss is so low anyway. However, for short antennas it is very helpful to install either a ground screen or a dense radial system within 0.05 λ of the base.

We can take the data in Figs 8 and 10 and calculate the effective value of the ground resistance R_g. **Fig 11** shows the results of such a computation. Fig 11 assumes a perfect ground screen that varies in radius from 0.001 λ to 0.5 λ. As we would expect, when the ground screen is very small the ground losses are high, meaning R_g is high and the efficiency is low. As we increase the radius of the ground screen, forcing current out of the lossy soil and into the very low-loss screen, R_g drops rapidly and the efficiency increases.

Fig 11 demonstrates why it is desirable to have a good ground system out to at least 0.125 λ, and better yet, even farther. The shorter the antenna, the more important the ground system becomes, especially close to the base. In this example the ground system consists of a highly conductive, bonded ground screen, not always practical for amateur installations. A more typical ground system would consist of a number of individual radial wires. This kind of ground will be inferior to a screen but represents a practical compromise. We'll examine this in more detail shortly.

Note that as we reduce h in Fig 11, R_g actually goes down—even though the ground losses are higher. When h is made smaller the radiation resistance declines rapidly (see Chapter 16, Mobile and Maritime Antennas), so that for a given radiated power I_o must increase. If we measure R_g as we reduce h over a given ground system, we would see that the value for R_g goes down as shown in Fig 11. But because I_o^2 is rising more rapidly than R_g is falling, the power lost in the ground increases and efficiency decreases. The point here is that the value of R_g depends on the ground system, soil characteristics *and* the antenna configuration. You cannot assign an arbitrary value to R_g independent of the antenna system.

Wire Radial Systems

Fig 11 shows R_g for a dense, perfectly conducting ground screen, but what we really need to know is the effect of length and number of individual radials on R_g in a wire radial system. We can calculate the current division between a radial system and the soil and use this to determine R_g. A typical graph of the proportion of the zone current flowing in the radial system, as a function of radius and various numbers of radials (N), is shown in **Fig 12**.

The radial currents decrease as we move away from the base, and the lower the number of radials, the more rapidly the radial current decreases. This means that close to the base of the antenna most of the current is in the radial system, but as we move away from the base the current increasingly flows in the lossy ground. When only a few radials are used, the outer ends of the radials contribute little to reducing ground loss.

Why is this? The problem is that I_z does not go immediately to the nearest radial but may flow for some distance in the soil. This is illustrated in a general way in **Fig 13**. As

we move away from the base of the antenna, adjacent radials are further apart from each other and the current must flow further in the soil before it reaches one of the radials. When we use more radials, the distance between radials is less and more of the total current will be in the radials and less in the soil. This reduces ground loss.

When we know the current distribution in the ground we can calculate the power loss and R_g. A typical example for h = 0.25 λ is given in **Fig 14**. We can learn a lot about radial system design from Fig 14 and similar graphs. If we use only a few radials, the radial current drops off very rapidly. Most of the current is flowing in the soil.

Such a ground system is by nature inefficient—that is, R_g is large. We can also see that if we have only 16 radials, R_g falls an ohm or two as we lengthen the radials, but is essentially flat by 0.1 λ. There is no point in making them longer because there is little current in the outer portions and R_g is essentially constant beyond 0.1 λ. As we increase the number of radials, we gather more current further out, making longer radials more useful. The result is cumulative—more radials allow longer radials to be effective and both together reduce ground loss. We can see this in Fig 14, where the initial value of R_g drops as N increases and flattens out at longer radial lengths. For 128 radials, for example, lengths of 0.25 λ or more are useful.

The example in Fig 14 uses #12 wire for the radials. Compared to soil, the resistance of the radial wires is very small, especially if many radials are used, and does not greatly affect overall losses no matter how small the wire. The effect of changing wire size is to slowly change the current division between ground and the radial system. Larger wire results in only a small decrease in R_g. In principle, very small wire could be used for radials but from a mechanical point of view, #18 or #20 wire is about as small as is practical. Any smaller wire breaks too easily to be buried, and also breaks easily when left on the ground surface and is walked on or driven over.

Fig 13—An example of current entering the ground between the radials and flowing for some distance before being picked up by a radial.

Fig 12—An example of the portion of the zone current flowing in the radial system as you move away from the base of a 0.25 λ vertical for different numbers of radials (N). Note that when more radials are used, more of the zone current flows in the radials and not in the ground, reducing ground loss. The proportion of current in the radial system falls rapidly when only a few radials are used. This leads to high ground loss because most of the zone current is flowing in the ground rather than in the radials.

Fig 14—An example of the variation of R_g with radial length and number of radials (N) for h = 0.25 λ. When only a few radials are used there is little point in making them longer than 0.1 λ. Increasing N reduces R_g at a given radius and also makes longer radials useful, further reducing R_g. R_g for other values of h behave similarly.

On the other hand, wire larger than #12 is expensive. Thousands of feet of #8 wire may be affordable for broadcast stations but not for most hams. Increasing the wire size from #20 to #10 would result in only a small reduction in R_g. Of course, if you happen to have a few thousand feet of old RG-8 cable lying around (the diameter is comparable to #0000 wire) then that might indeed help to reduce R_g, as W9QQ has shown (see Bibliography). You are still better off, however, using many radials with small wire than a few radials with large wire. Radial wire size is usually a mechanical and financial issue, not an electrical one.

If the example in Fig 14 were changed for different ground characteristics, then the curves would have a similar shape but would be shifted either up or down. For example, poorer ground will result in higher R_g but the usable length for the radials for a given N would increase somewhat. For better-quality ground, with higher conductivity, R_g will be lower but the usable length of the radials for a given N will be shorter.

For short antennas, the initial drop in R_g will be more rapid and the curves flatten out sooner. This implies that somewhat shorter radials are useful with short antennas. However, given the high losses, it is still a very good idea to use lots of radials with short antennas. As in the above example, increasing N also increases the usable length.

As you go up in frequency from 160 meters, R_g generally rises slowly and then stabilizes around 7 MHz, depending on the ground characteristics. This effect is related to the change in skin depth with frequency, which is discussed in a later section of this chapter. There is also a small shift in current division between the radials and ground as the frequency increases.

A Word Of Caution

In the preceding discussion we presented a number of graphs and the CD-ROM accompanying this book contains some spreadsheets containing the equations from which these graphs were derived. From these graphs we extracted a number of observations on how to design radial systems. Basic to each graph is the assumption that we know the ground characteristics: conductivity and permitivity. In the real world, we amateurs very rarely have more than a rough idea of the ground characteristics under our antennas. Even when careful measurements are made, the characteristics will vary through the year with rainfall or the lack thereof.

Soils are always stratified vertically and can vary by factors or two or more horizontally over distances comparable to radial length, so that even good ground measurements are at best an average. In addition, there will frequently be constraints on the size and shape of the ground system. As a result, we use the calculated information and the previous graphs for general guidance and preliminary design, but when actually installing a ground system we try to measure—or at least estimate—R_g as we go along.

When R_g stops falling, or our patience and/or money run out, we stop adding ground radials. We can measure the feed-point resistance with an impedance bridge to estimate of R_g. The impedance seen at the feed point of the antenna is the sum of the loss and the radiation resistance. To determine R_g you have to estimate R_r (from the antenna height) and other losses due to loading or conductors, and then subtract that from the total measured input resistance. The remainder is R_g, and R_g should fall as we add radials. When R_g stops falling we probably have as many radials of a given length as will be useful. Further reduction in R_g would require more, longer radials.

Practical Suggestions For Vertical Ground Systems

At least 16 radials should be used if at all possible. Experimental measurements and calculations show that with this number, the loss resistance decreases the antenna efficiency by 30% to 50% for a 0.25 λ vertical, depending on soil characteristics. In general, a large number of radials (even though some or all of them must be short) is preferable to a few long radials for a vertical antenna mounted on the ground. The conductor size is relatively unimportant as mentioned before: #12 to #22 copper wire is suitable.

Table 1 summarizes these conclusions. John Stanley, K4ERO, first presented this material in December 1976 *QST*. Another source of information on ground-system design is *Radio Broadcast Ground Systems* (see the Bibliography at the end of this chapter). Most of the data presented in Table 1 is taken from that source, or derived from the interpolation of data contained therein.

Table 1 is based on the number of radials. For each configuration, there is a corresponding optimum radial length. Each configuration also includes the amount of wire used, expressed in wavelengths. Using radials considerably longer than suggested for a given N or using a lot more radials than suggested for a given length, while not adverse to performance, does not yield significant improvement either. That would represent a non-optimum use of wire and construction time. Each suggested configuration represents an optimum relationship between length and number for the given amount of total wire used. Table 1 leads to these conclusions:

- If you install only 16 radials (in configuration A), they need not be very long—0.1 λ is sufficient. The total length of wire will be 1.6 λ, which is about 875 feet at 1.8 MHz.
- If you have the wire, the space and the patience to lay down 120 radials (optimal configuration F), they should be 0.4 λ long. This radial system will gain about 3 dB over the 16-radial case and you'll use 48 λ of wire, or about 26,000 feet at 1.8 MHz.
- If you install 36 radials that are 0.15 λ long, you will lose 1.5 dB compared to optimal configuration F. You will use 5.4 λ of wire, or almost 3,000 feet at 1.8 MHz.

The loss figures in Table 1 assume h = 0.25 λ. A very rough approximation of loss when using shorter antennas can be obtained by doubling the loss in dB each

Table 1
Optimum Ground-System Configurations

	Configuration	Designation				
	A	B	C	D	E	F
Number of radials	16	24	36	60	90	120
Length of each radial in wavelengths	0.1	0.125	0.15	0.2	0.25	0.4
Spacing of radials in degrees	22.5	15	10	6	4	3
Total length of radial wire installed, in wavelengths	1.6	3	5.4	12	22.5	48
Power loss in dB at low angles with a quarter-wave radiating element	3	2	1.5	1	0.5	0*
Feed-point impedance in ohms with a quarter-wave radiating element	52	46	43	40	37	35

Note: Configuration designations are indicated only for text reference.
*Reference: The loss of this configuration is negligible compared to a perfectly conducting ground.

time the antenna height is halved. For taller antennas the losses decrease, approaching 2 dB for configuration A of Table 1 for a half-wave radiator. Even longer antennas yield correspondingly better performance.

Table 1 is based on average ground conductivity. Variation of the loss values shown can be considerable, especially for configurations using fewer radials. Those building antennas over dry, sandy or rocky ground should expect more loss. On the other hand, higher than average soil conductivity and wet soils would make the compromise configurations (those with the fewest radials) even more attractive.

When antennas are combined into arrays, either parasitic or all-driven types, mutual impedances lower the radiation resistance of the elements. This drastically increases the effects of ground loss because I_o will be higher for the same power level. For instance, an antenna with a 50-Ω feed-point impedance, of which 10 Ω is ground-loss resistance, will have an efficiency of approximately 83%. An array of two similar antennas in a driven array with similar ground losses may have an efficiency of 70% or less.

Special precautions must be taken in such cases to achieve satisfactory operation. Generally speaking, a wide-spaced broadside array presents little problem because R_r is high, but a close-spaced end-fire array should be avoided because R_r is much lower, unless low-loss radial system configurations are used or other precautions taken. Chapter 8, Multielement Arrays, covers the subject of vertical arrays in great detail.

In cases where directivity is desirable or real-estate limitations dictate, longer, more closely spaced radials can be installed in one direction, and shorter, more widely spaced radials in another. Multiband ground systems can be designed using different optimum configurations for different bands. Usually it is most convenient to start at the lowest frequency with fewer radials and add more short radials for better performance on the higher bands.

There is nothing sacred about the exact details of the configurations in Table 1, and small changes in the number of radials and lengths will not cause serious problems. Thus, a configuration with 32 or 40 radials of 0.14 λ or 0.16 λ will work as well as configuration C shown in the table.

If less than 90 radials are contemplated, there is no need to make them a quarter wavelength long. This differs rather dramatically from the case of a ground-plane antenna, where resonant radials are installed above ground. For a ground-mounted antenna, quarter-wave long radials may not be optimum. Because the radials of a ground-mounted vertical are actually on, if not slightly below the surface, they are coupled by capacitance or conduction to the ground, and thus resonance effects are not important. The basic function of radials is to provide a low-loss return path for ground currents.

Radio Broadcast Ground Systems states, "Experiments show that the ground system consisting of only 15 radial wires need not be more than 0.1 wavelength long, while the system consisting of 113 radials is still effective out to 0.5 wavelength." Many graphs in that publication confirm this statement. This is not to say that these two systems will perform equally well; they most certainly will not. However, if 0.1 λ is as long as the radials can be, there is little point in using more than 15 of them unless the vertical radiator's height is also small.

The antenna designer should:
1. Study the cost of various radial configurations versus the gain of each.
2. Compare alternative means of improving transmitted signal and their cost (more power, etc).
3. Consider increasing the physical antenna height (the electrical length) of the vertical radiator, instead of improving the ground system.
4. Use multi-element arrays for directivity and gain, observing the necessary precautions related to mutual impedances discussed in Chapter 8, Multielement Arrays.

The Effect of Ground in the Far Field

The properties of the ground in the far field of an antenna are very important, especially for a vertically polarized antenna, as discussed above. Even if the ground-radial system for a vertical has been optimized to reduce ground-return losses in the reactive near field to an insignificant level, the electrical properties of the ground may still diminish far-field performance to lower levels than "perfect-ground" analyses might lead you to expect. The key is that *ground reflections* from horizontally and vertically polarized waves behave very differently.

Reflections in General

First, let us consider the case of flat ground. Over flat ground, either horizontally or vertically polarized downgoing waves launched from an antenna into the far field strike the surface and are reflected by a process very similar to that by which light waves are reflected from a mirror. As is the case with light waves, the angle of reflection is the same as the angle of incidence, so a wave striking the surface at an angle of, say, 15° is reflected upward from the surface at 15°.

The reflected waves combine with direct waves (those radiated at angles above the horizon) in various ways. Some of the factors that influence this combining process are the height of the antenna, its length, the electrical characteristics of the ground, and as mentioned above, the polarization of the wave. At some elevation angles above the horizon the direct and reflected waves are exactly in phase—that is, the maximum field strengths of both waves are reached at the same time at the same point in space, and the directions of the fields are the same. In such a case, the resultant field strength for that angle is simply the sum of the direct and reflected fields. (This represents a theoretical increase in field strength of 6 dB over the free-space pattern at these angles.)

At other elevation angles the two waves are completely out of phase—that is, the field intensities are equal at the same instant and the directions are opposite. At such angles, the fields cancel each other. At still other angles, the resultant field will have intermediate values. Thus, the effect of the ground is to increase radiation intensity at some elevation angles and to decrease it at others. When you plot the results as an elevation pattern, you will see *lobes* and *nulls*, as described in Chapter 2, Antenna Fundamentals.

The concept of an *image antenna* is often useful to show the effect of reflection. As **Fig 15** shows, the reflected ray has the same path length (AD equals BD) that it would if it originated at a virtual second antenna with the same characteristics as the real antenna, but situated below the ground just as far as the actual antenna is above it.

Now, if we look at the antenna and its image over perfect ground from a remote point on the surface of the ground, we will see that the currents in a horizontally polarized antenna and its image are flowing in opposite directions, or

Fig 15—At any distant point, P, the field strength will be the vector sum of the direct ray and the reflected ray. The reflected ray travels farther than the direct ray by the distance BC, where the reflected ray is considered to originate at the *image* antenna.

in other words, are 180° out of phase. But the currents in a vertically polarized antenna and its image are flowing in the *same* direction—they are *in* phase. This 180° phase difference between the vertically and horizontally polarized reflections off ground is what makes the combinations with direct waves behave so very differently.

FAR-FIELD GROUND REFLECTIONS AND THE VERTICAL ANTENNA

A vertical's azimuthal directivity is omnidirectional. A λ/2 vertical over ideal, perfectly conducting earth has the elevation-plane radiation pattern shown by the solid line in **Fig 16**. Over real earth, however, the pattern looks more like the shaded one in the same diagram. In this case, the low-angle radiation that might be hoped for because of perfect-ground performance is not realized in the real world.

Now look at **Fig 17A**, which compares the computed elevation-angle response for two half-wave dipoles at 14 MHz. One is oriented horizontally over ground at a height of λ/2 and the other is oriented vertically, with its center just over λ/2 high (so that the bottom end of the wire doesn't actually touch the ground). The ground is "average" in dielectric constant (13) and conductivity (0.005 S/m). At a 15° elevation angle, the horizontally polarized dipole has almost 7 dB more gain than its vertical brother. Contrast Fig 17A to the comparison in Fig 17B, where the peak gain of a vertically polarized half-wave dipole over seawater, which is virtually perfect for RF reflections, is quite comparable with the horizontal dipole's response at 15°, and exceeds the horizontally polarized antenna dramatically below 15° elevation.

Fig 16—Vertical-plane radiation pattern for a ground-mounted quarter-wave vertical. The solid line is the pattern for perfect earth. The shaded pattern shows how the response is modified over average earth (k = 13, G = 0.005 S/m) at 14 MHz. ψ is the pseudo-Brewster angle (PBA), in this case 14.8°.

———— λ/2 Vertical Dipole, Bottom Just Above Average Ground
——— λ/2 Horizontal Dipole, λ/2 Over Average Ground

0 dB = 7.41 dBi

Elevation

(A)

14.100 MHz

———— λ/2 Vertical Dipole, Bottom Just Above Seawater
——— λ/2 Horizontal at λ/2 Over Average Ground

0 dB = 7.41 dBi

Elevation

(B)

14.100 MHz

Fig 17—At A, comparison of horizontal and vertical λ/2 dipoles over average ground. Average ground has conductivity of 5 mS/m and dielectric constant of 13. Horizontal dipole is λ/2 high; vertical dipole's bottom wire is just above ground. Horizontal antenna is much less affected by far-field ground losses compared with its vertical counterpart. At B, comparison of 20-meter λ/2 vertical dipole whose bottom wire is just above seawater with λ/2-high horizontal dipole over average ground. Seawater is great for verticals!

To understand in a qualitative fashion why the desired low-angle radiation from a vertical is not delivered when the ground isn't "perfect," examine **Fig 18A**. Radiation from each antenna segment reaches a point P in space by two paths; one directly from the antenna, path AP, and the other by reflection from the earth, path AGP. (Note that P is so far away that the slight difference in angles is insignificant—for practical purposes the waves are parallel to each other at point P.)

If the earth were a perfectly conducting surface, there would be no phase shift of the vertically polarized wave upon reflection at point G. The two waves would add together with some phase difference because of the different path lengths. This difference in path lengths of the two waves is why the free-space radiation pattern differs from the pattern of the same antenna over ground.

Now consider a point P that is close to the horizon, as in Fig 18B. The path lengths AP and AGP are almost the same, so the magnitudes of the two waves add together, producing a maximum at zero angle of radiation. The arrows on the waves point both ways since the process works similarly for transmitting and receiving.

With real earth, however, the reflected wave from a vertically polarized antenna undergoes a change in both *amplitude* and *phase* in the reflection process. Indeed, at a low-enough elevation angle, the phase of the reflected wave will actually change by 180° and its magnitude will then subtract from that of the direct wave. At a zero takeoff angle, it will be almost equal in amplitude, but 180° out of phase with the direct wave.

Note that this is very similar to what happens with horizontally polarized reflected and direct waves at low elevation angles. Virtually complete cancellation will result in a deep null, inhibiting any radiation or reception at 0°. For real-world soils, the vertical loses the theoretical advantage it has at low elevation angles over a horizontal antenna, as Fig 17A so clearly shows.

The degree that a vertical works better than a horizontal antenna at low elevation angles is largely dependent on the characteristics of the ground around the vertical, as we'll next examine.

THE PSEUDO-BREWSTER ANGLE AND THE VERTICAL ANTENNA

Much of the material presented here regarding pseudo-Brewster angle was prepared by Charles J. Michaels, W7XC, and first appeared in July 1987 *QST*, with additional information in *The ARRL Antenna Compendium, Vol 3*. (See the Bibliography at the end of this chapter.)

Most fishermen have noticed that when the sun is low, its light is reflected from the water's surface as glare, obscuring the underwater view. When the sun is high, however, the sunlight penetrates the water and it is possible to see objects below the surface of the water. The angle at which this transition takes place is known as the *Brewster angle*,

Fig 18—The direct wave and the reflected wave combine at point P to form the pattern (P is very far from the antenna). At A the two paths AP and AGP differ appreciably in length, while at B these two path lengths are nearly equal.

named for the Scottish physicist, Sir David Brewster (1781-1868).

A similar situation exists in the case of vertically polarized antennas; the RF energy behaves as the sunlight in the optical system, and the earth under the antenna acts as the water. The *pseudo-Brewster angle* (PBA) is the angle at which the reflected wave is 90° out of phase with respect to the direct wave. "Pseudo" is used here because the RF effect is similar to the optical effect from which the term gets its name. Below this angle, the reflected wave is between 90° and 180° out of phase with the direct wave, so some degree of cancellation takes place. The largest amount of cancellation occurs near 0°, and steadily less cancellation occurs as the PBA is approached from below.

The factors that determine the PBA for a particular location *are not related to the antenna itself, but to the ground around it*. The first of these factors is earth conductivity, G, which is a measure of the ability of the soil to conduct electricity. Conductivity is the inverse of resistance. The second factor is the dielectric constant, k, which is a unitless quan-

tity that corresponds to the capacitive effect of the earth. For both of these quantities, the higher the number, the better is the ground (for vertical antenna purposes). The third factor determining the PBA for a given location is the frequency of operation. The PBA increases with increasing frequency, all other conditions being equal. **Table 2** gives typical values of conductivity and dielectric constant for different types of soil. The map of **Fig 19** shows the approximate conductivity values for different areas in the continental United States.

As the frequency is increased, the role of the dielectric constant in determining the PBA becomes more significant. **Table 3** shows how the PBA varies with changes in ground conductivity, dielectric constant and frequency. The table shows trends in PBA dependency on ground constants and frequency. The constants chosen are not necessarily typical of any geographical area; they are just examples.

At angles below the PBA, the reflected vertically polarized wave subtracts from the direct wave, causing the radiation intensity to fall off rapidly. Similarly, above the PBA, the reflected wave adds to the direct wave, and the radiated pattern approaches the perfect-earth pattern. Fig 16 shows the PBA, usually labeled ψ_B.

When plotting vertical-antenna radiation patterns over real earth, the reflected wave from an antenna segment is multiplied by a factor called the *vertical reflection coefficient*, and the product is then added vectorially to the direct wave to get the resultant. The reflection coefficient consists of an attenuation factor, A, and a phase angle, ϕ, and is usually expressed as $A\angle\phi$. (ϕ is always a negative angle, because the earth acts as a lossy capacitor in this situation.) The following equation can be used to calculate the reflection coefficient for vertically polarized waves, for earth of given conductivity and dielectric constant at any frequency and elevation angle (also called the wave angle in many texts).

Table 2

Conductivities and Dielectric Constants for Common Types of Earth

Surface Type	Dielectric Constant	Conductivity (S/m)	Relative Quality
Fresh water	80	0.001	
Salt water	81	5.0	
Pastoral, low hills, rich soil, typ Dallas, TX, to Lincoln, NE areas	20	0.0303	Very good
Pastoral, low hills, rich soil typ OH and IL	14	0.01	
Flat country, marshy, densely wooded, typ LA near Mississippi River	12	0.0075	
Pastoral, medium hills and forestation, typ MD, PA, NY, (exclusive of mountains and coastline)	13	0.006	
Pastoral, medium hills and forestation, heavy clay soil, typ central VA	13	0.005	Average
Rocky soil, steep hills, typ mountainous	12-14	0.002	Poor
Sandy, dry, flat, coastal	10	0.002	
Cities, industrial areas	5	0.001	Very Poor
Cities, heavy industrial areas, high buildings	3	0.001	Extremely poor

Table 3
Pseudo-Brewster Angle Variation with Frequency, Dielectric Constant, and Conductivity

Frequency (MHz)	Dielectric Constant	Conductivity (S/m)	PBA (degrees)
7	20	0.0303	6.4
	13	0.005	13.3
	13	0.002	15.0
	5	0.001	23.2
	3	0.001	27.8
14	20	0.0303	8.6
	13	0.005	14.8
	13	0.002	15.4
	5	0.001	23.8
	3	0.001	29.5
21	20	0.0303	10.0
	13	0.005	15.2
	13	0.002	15.4
	5	0.001	24.0
	3	0.001	29.8

$$A_{Vert} \angle \phi = \frac{k' \sin \psi - \sqrt{k' - \cos^2 \psi}}{k' \sin \psi + \sqrt{k' - \cos^2 \psi}} \qquad \text{(Eq 3)}$$

where

$A_{Vert} \angle \phi$ = vertical reflection coefficient

ψ = elevation angle

$$k' = k - j \left| \frac{1.8 \times 10^4 \times G}{f} \right|$$

k = dielectric constant of earth (k for air = 1)

G = conductivity of earth in S/m

f = frequency in MHz

j = complex operator ($\sqrt{-1}$)

Solving this equation for several points indicates what effect the earth has on vertically polarized signals at a particular location for a given frequency range. **Fig 20** shows the reflection coefficient as a function of elevation angle at 21 MHz over average earth (G = 0.005 S/m, and k = 13).

Numbers on map represent estimated effective ground conductivity in millisiemens per meter

Conductivity of seawater is not shown on map but is assumed to be 500 millisiemens per meter

0 — 200
Scale in Miles

Estimated Effective
Ground Conductivity
in the United States

Fig 19—Typical average soil conductivities for the continental United States. Numeric values indicate conductivities in millisiemens per meter (mS/m), where 1.0 mS/m = 0.001 S/m.

Fig 20—Reflection coefficient for vertically polarized waves. A and φ are magnitude and angle for wave angles ψ. This case is for average earth, (k = 13, G = 0.005 S/m), at 21 MHz.

Note that as the phase curve, ψ, passes through 90°, the attenuation curve (A) passes through a minimum at the same wave angle ψ. This is the PBA. At this angle, the reflected wave is not only at a phase angle of 90° with respect to the direct wave, but is so low in amplitude that it does not aid the direct wave by a significant amount. In the case illustrated in Fig 20 this elevation angle is about 15°.

Variations in PBA with Earth Quality

From Eq 3, it is quite a task to search for either the 90° phase point or the attenuation curve minimum for a wide variety of earth conditions. Instead, the PBA can be calculated directly from the following equation.

$$\psi_B = \arcsin\sqrt{\frac{k-1+\sqrt{(x^2+k^2)^2(k-1)^2+x^2[(x^2+k^2)^2-1]}}{(x^2+k^2)^2-1}}$$

(Eq 4)

where k, G and f are as defined for Eq 3, and

$$x = \frac{1.8\times10^4\times G}{f}$$

Fig 21 shows curves calculated using Eq 4 for several different earth conditions, at frequencies between 1.8 and 30 MHz. As expected, poorer earths yield higher PBAs. Unfortunately, at the higher frequencies (where low-angle radiation is most important for DX work), the PBAs are highest. The PBA is the same for both transmitting and receiving.

Fig 21—Pseudo-Brewster angle (ψ) for various qualities of earth over the 1.8 to 30-MHz frequency range. Note that the frequency scale is logarithmic. The constants used for each curve are given in Table 2.

Relating PBA to Location and Frequency

Table 2 lists the physical descriptions of various kinds of earth with their respective conductivities and dielectric constants, as mentioned earlier. Note that in general, the dielectric constants and conductivities are higher for better earths. This enables the labeling of the earth characteristics as extremely poor, very poor, poor, average, very good, and so on, without the complications that would result from treating the two parameters independently.

Fresh water and salt water are special cases; in spite of high resistivity, the fresh-water PBA is 6.4°, and is nearly independent of frequency below 30 MHz. Salt water, because of its extremely high conductivity, has a PBA that never exceeds 1° in this frequency range. The extremely low conductivity listed for cities (the last case) in Table 2 results more from the clutter of surrounding buildings and other obstructions than any actual earth characteristic. The PBA at any location can be found for a given frequency from the curves in Fig 21.

FLAT-GROUND REFLECTIONS AND HORIZONTALLY POLARIZED WAVES

The situation for horizontal antennas is different from that of verticals. **Fig 22** shows the reflection coefficient for horizontally polarized waves over average earth at 21 MHz. Note that in this case, the phase-angle departure from 0° never gets very large, and the attenuation factor that causes the most loss for high-angle signals approaches unity for low angles. Attenuation increases with progressively poorer earth types.

In calculating the broadside radiation pattern of a horizontal λ/2 dipole, the perfect-earth image current, equal to the true antenna current but 180° out of phase with it) is multiplied by the horizontal reflection coefficient given by Eq 5 below. The product is then added vectorially to the direct wave to get the resultant at that elevation angle. The

reflection coefficient for horizontally polarized waves can be calculated using the following equation.

$$A_{Horiz} \angle \phi = \frac{\sqrt{k'-\cos^2\psi}-\sin\psi}{\sqrt{k'-\cos^2\psi}+\sin\psi}$$ (Eq 5)

where

$A_{Horiz} \angle \phi$ = horizontal reflection coefficient

ψ = elevation angle

$$k' = k - j\left(\frac{1.8 \times 10^4 \times G}{f}\right)$$

k = dielectric constant of earth
G = conductivity of earth in S/m
f = frequency in MHz
j = complex operator ($\sqrt{-1}$)

For a horizontal antenna near the earth, the resultant pattern is a modification of the free-space pattern of the antenna. **Fig 23** shows how this modification takes place for a horizontal $\lambda/2$ antenna over a perfectly conducting flat surface. The patterns at the left show the relative radiation when one views the antenna from the side; those at the right show the radiation pattern looking at the end of the antenna. Changing the height above ground from $\lambda/4$ to $\lambda/2$ makes a significant difference in the high-angle radiation, moving the main lobe down lower.

Note that for an antenna height of $\lambda/2$ (Fig 23, bottom), the out-of-phase reflection from a perfectly conducting surface creates a null in the pattern at the zenith (90°

elevation angle). Over real earth, however, a *filling in* of this null occurs because of ground losses that prevent perfect reflection of high-angle radiation.

At a 0° elevation angle, horizontally polarized antennas also demonstrate a null, because out-of-phase reflection cancels the direct wave. As the elevation angle departs from 0°, however, there is a slight filling-in effect so that over other-than-perfect earth, radiation at lower angles is enhanced compared to a vertical. A horizontal antenna will often outperform a vertical for low-angle DX work, particularly over lossy types of earth at the higher frequencies.

Reflection coefficients for vertically and horizontally polarized radiation differ considerably at most angles above ground, as can be seen by comparison of Figs 20 and 22. (Both sets of curves were plotted for the same ground constants and at the same frequency, so they may be compared directly.) This is because, as mentioned earlier, the image of a horizontally polarized antenna is out-of-phase with the antenna itself, and the image of a vertical antenna is in-phase with the actual radiator.

The result is that the phase shifts and reflection magnitudes vary greatly at different angles for horizontal and vertical polarization. The magnitude of the reflection coefficient for vertically polarized waves is greatest (near unity) at very low angles, and the phase angle is close to 180°. As mentioned earlier, this cancels nearly all radiation at very low angles. For the same range of angles, the magnitude of the reflection coefficient for horizontally polarized waves is also near unity, but the phase angle is near 0° for the specific conditions shown in Figs 20 and 22. This causes reinforcement of low-angle horizontally polarized waves. At some relatively high angle, the reflection coefficients for

Fig 22—Reflection coefficient for horizontally polarized waves (magnitude A at angle ϕ), at 21 MHz over average earth (k = 13, G = 0.005 S/m).

Fig 23—Effect of the ground on the radiation from a horizontal half-wave dipole antenna, for heights of one-fourth and one-half wavelength. Broken lines show what the pattern would be if there were no reflection from the ground (free space).

horizontally and vertically polarized waves are equal in magnitude and phase. At this angle (approximately 81° for the example case), the effect of ground reflection on vertically and horizontally polarized signals will be the same.

DEPTH OF RF CURRENT PENETRATION

When considering earth characteristics, questions about depth of RF current penetration often arise. For instance, if a given location consists of a 6-foot layer of soil overlying a highly resistive rock strata, which material dominates? The answer depends on the frequency, the soil and rock dielectric constants, and their respective conductivities. The following equation can be used to calculate the current density at any depth.

$$e^{-pd} = \frac{\text{Current Density at Depth d}}{\text{Current Density at Surface}} \qquad \text{(Eq 6)}$$

where

d = depth of penetration in cm
e = natural logarithm base (2.718)

$$p = \left(\frac{X \times B}{2} \times \left(\sqrt{1 + \frac{G^2 \times 10^{-4}}{B^2}} - 1 \right) \right)^{1/2}$$

$X = 0.008 \times \pi^2 \times f$
$B = 5.56 \times 10^{-7} \times k \times f$
k = dielectric constant of earth
f = frequency in MHz
G = conductivity of earth in S/m

After some manipulation of this equation, it can be used to calculate the depth at which the current density is some fraction of that at the surface. The depth at which the current density is 37% (1/e) of that at the surface (often referred to as *skin depth*) is the depth at which the current density would be zero if it were distributed uniformly instead of exponentially. (This 1/e factor appears in many physical situations. For instance, a capacitor charges to within 1/e of full charge within one RC time constant.) At this depth, since the power loss is proportional to the square of the current, approximately 91% of the total power loss has occurred, as has most of the phase shift, and current flow below this level is negligible.

Fig 24 shows the solutions to Eq 6 over the 1.8 to 30-MHz frequency range for various types of earth. For example, in very good earth, substantial RF currents flow down to about 3.3 feet at 14 MHz. This depth goes to 13 feet in average earth and as far as 40 feet in very poor earth. Thus, if the overlying soil is rich, moist loam, the underlying rock stratum is of little concern. However, if the soil is only average, the underlying rock may constitute a major consideration in determining the PBA and the depth to which the RF current will penetrate.

The depth in fresh water is about 156 feet and is nearly independent of frequency in the amateur bands below 30 MHz. In salt water, the depth is about seven inches at

1.8 MHz and decreases rather steadily to about two inches at 30 MHz. Dissolved minerals in moist earth increase its conductivity.

The depth-of-penetration curves in Fig 24 illustrate a noteworthy phenomenon. While skin effect confines RF current flow close to the surface of a conductor, the earth is so lossy that RF current penetrates to much greater depths than in most other media. The depth of RF current penetration is a function of frequency as well as earth type. Thus, the only cases in which most of the current flows near the surface are with very highly conductive media (such as salt water), and at frequencies above 30 MHz.

DIRECTIVE PATTERNS OVER REAL GROUND

As explained in Chapter 2, Antenna Fundamentals, because antenna radiation patterns are three-dimensional, it is helpful in understanding their operation to use a form of representation showing the elevation-plane directional characteristic for different heights. It is possible to show selected elevation-plane patterns oriented in various directions with respect to the antenna axis. In the case of the horizontal half-wave dipole, a plane running in a direction along the axis and another broadside to the antenna will give a good deal of information.

The effect of reflection from the ground can be expressed as a separate *pattern factor*, given in decibels. For any given elevation angle, adding this factor algebraically to the value for that angle from the free-space pattern for that antenna gives the resultant radiation value at that

Fig 24—Depths at which the current density is 37% (1/e) of that at the surface for different qualities of earth over the 1.8- to 30-MHz frequency range. The depth for fresh water, not plotted, is 156 feet and almost independent of frequency below 30 MHz. See text and Table 2 for ground constants.

angle. The limiting conditions are those represented by the direct ray and the reflected ray being exactly in-phase and exactly out-of-phase, when both (assuming there are no ground losses) have equal amplitudes. Thus, the resultant field strength at a distant point may be either 6 dB greater than the free-space pattern (twice the field strength), or zero, in the limiting cases.

Horizontally Polarized Antennas

The way in which pattern factors vary with height for horizontal antennas over flat earth is shown graphically in the plots of **Fig 25**. The solid-line plots are based on perfectly conducting ground, while the shaded plots are based on typical real-earth conditions. These patterns apply to horizontal antennas of any length. While these graphs are, in fact, radiation patterns of horizontal single-wire antennas (dipoles) as viewed from the axis of the wire, it must be remembered that the plots merely represent pattern factors.

Fig 26 shows vertical-plane radiation patterns in the directions off the ends of a horizontal half-wave dipole for various antenna heights. These patterns are scaled so they may be compared directly to those for the appropriate heights in Fig 25. Note that the perfect-earth patterns in Figs 26A and 25B are the same as those in the upper part of Fig 23. Note also that the perfect-earth patterns of Figs 26B and 25D are the same as those in the lower section of Fig 23. The reduction in field strength off the ends of the wire at the lower angles, as compared with the broadside field strength, is quite apparent. It is also clear from Fig 26 that, at some heights, the high-angle radiation off the ends is nearly as great as the broadside radiation, making the antenna essentially an omnidirectional radiator.

A — Antenna 1/8 λ high
B — Antenna 1/4 λ high
C — Antenna 3/8 λ high
D — Antenna 1/2 λ high
E — Antenna 5/8 λ high
F — Antenna 3/4 λ high
G — Antenna 7/8 λ high
H — Antenna 1 λ high
I — Antenna 1−1/4 λ high
J — Antenna 1−1/2 λ high
K — Antenna 1−3/4 λ high
L — Antenna 2 λ high

Fig 25—Reflection factors for horizontal dipole antennas at various heights above flat ground. The solid-line curves are the perfect-earth patterns (broadside to the antenna wire); the shaded curves represent the effects of average earth (k = 13, G = 0.005 S/m) at 14 MHz. Add 7 dB to values shown for absolute gain in dBd referenced to dipole in free space, or 9.15 dB for gain in dBi. For example, peak gain over perfect earth at $^5/_8$ λ height is 7 dBd (or 9.15 dBi) at 25° elevation.

In vertical planes making some intermediate angle between 0° and 90° with the wire axis, the pattern will have a shape intermediate between the broadside and end-on patterns. By visualizing a smooth transition from the end-on pattern to the broadside pattern as the horizontal angle is varied from 0° to 90°, a fairly good mental picture of the actual solid pattern may be formed. An example is shown in **Fig 27**. At A, the elevation-plane pattern of a half-wave dipole at a height of λ/2 is shown through a plane 45° away from the favored direction of the antenna. At B and C, the pattern of the same antenna is shown at heights of 3λ/4 and 1λ (through the same 45° off-axis plane). These patterns are scaled so they may be compared directly with the broadside and end-on patterns for the same antenna (at the appropriate heights) in Figs 25 and 26.

The curves presented in **Fig 28** are useful for determining heights of horizontal antennas that give either maximum or minimum reinforcement at any desired wave angle. For instance, if you want to place an antenna at a height so that it will have a null at 30°, the antenna should be placed where a broken line crosses the 30° line on the horizontal scale. There are two heights (up to 2 λ) that will yield this null angle: 1 λ and 2 λ.

As a second example, you may want to have the ground reflection give maximum reinforcement of the direct ray from a horizontal antenna at a 20° elevation angle. The antenna height should be 0.75 λ. The same height will give a null at 42° and a second lobe at 90°.

Fig 28 is also useful for visualizing the vertical pattern of a horizontal antenna. For example, if an antenna is erected at 1.25 λ, it will have major lobes (solid-line crossings) at 12° and 37°, as well as at 90° (the zenith). The nulls in this pattern (dashed-line crossings) will appear at 24° and 53°.

The Y-axis in Fig 28 plots the wave angle versus the height in wavelength above flat ground on the X-axis. Fig 28 doesn't show the elevation angles required for actual

A—Antenna 1/4 λ high   B—Antenna 1/2 λ high   C—Antenna 3/4 λ high

D—Antenna 1 λ high   E—Antenna 1-1/4 λ high   F—Antenna 1-1/2 λ high

Fig 26—Vertical-plane radiation patterns of horizontal half-wave dipole antennas off the ends of the antenna wire. The solid-line curves are the flat, perfect-earth patterns, and the shaded curves represent the effects of average flat earth (k = 13, G = 0.005 S/m) at 14 MHz. The 0-dB reference in each plot corresponds to the peak of the main lobe in the favored direction of the antenna (the maximum gain). Add 7 dB to values shown for absolute gain in dBd referenced to dipole in free space, or 9.15 dB for gain in dBi.

A—Height 1/2 λ   B—Height 3/4 λ   C—Height 1 λ

Fig 27—Vertical-plane radiation patterns of half-wave horizontal dipole antennas at 45° from the antenna wire over flat ground. The solid-line and shaded curves represent the same conditions as in Figs 25 and 26. These patterns are scaled so they may be compared directly with those of Figs 25 and 26.

Fig 28—Angles at which nulls and maxima (factor = 6 dB) in the ground-reflection factor appear for antenna heights up to two wavelengths over flat ground. The solid lines are maxima, dashed lines nulls, for all horizontal antennas. See text for examples. Values may also be determined from the trigonometric relationship θ = arc sin (A/4h), where θ is the wave angle and h is the antenna height in wavelengths. For the first maximum, A has a value of 1; for the first null A has a value of 2, for the second maximum 3, for the second null 4, and so on.

communications to various target geographic locations of interest. Chapter 23, Radio Wave Propagation, and the CD-ROM in the back of this book give details about the range of angles required for target locations around the world. It is very useful to overlay plots of these angles together with the elevation pattern for horizontally polarized antennas at various heights above flat ground. This will be demonstrated in detail later in this chapter.

Vertically Polarized Antennas

In the case of a vertical λ/2 dipole or a ground-plane antenna, the horizontal directional pattern is simply a circle at any elevation angle (although the actual field strength will vary, at the different elevation angles, with the height above ground). Hence, one vertical pattern is sufficient to give complete information (for a given antenna height) about the antenna in any direction with respect to the wire. A series of such patterns for various heights is given in **Fig 29**. Rotating the plane pattern about the zenith axis of the graph forms the three-dimensional radiation pattern in each case.

The solid-line curves represent the radiation patterns of the λ/2 vertical dipole at different feed-point heights over perfectly conducting ground. The shaded curves in Fig 29 show the patterns produced by the same antennas at the same heights over average ground (G = 0.005 S/m, k = 13) at 14 MHz. The PBA in this case is 14.8°.

In short, far-field losses for vertically polarized antennas are highly dependent on the conductivity and dielectric constant of the earth around the antenna, extending far beyond the ends of any radials used to complete the ground return for the near field. Putting more radials out around the antenna may well decrease ground-return losses in the reactive near field for a vertical monopole, but will not increase radiation at low elevation launch angles in the far field, unless the radials can extend perhaps 100 wavelengths in all directions! Aside from moving to the fabled "salt water swamp on a high hill," there is very little that someone can do to change the character of the ground that affects the far-field pattern of a real vertical. Classical texts

Fig 29—Vertical-plane radiation patterns of a ground-plane antenna above flat ground. The height is that of the ground plane, which consists of four radials in a horizontal plane. Solid lines are perfect-earth patterns; shaded curves show the effects of real earth. The patterns are scaled—that is, they may be directly compared to the solid-line ones for comparison of losses at any wave angle. These patterns were calculated for average ground (k = 13, G = 0.005 S/m) at 14 MHz. The PBA for these conditions is 14.8°. Add 6 dB to values shown for absolute gain in dBd over dipole in free space.

on verticals often show elevation patterns computed over an "infinitely wide, infinitely conducting ground plane." Real ground, with finite conductivity and less than perfect dielectric constant, can severely curtail the low-angle radiation at which verticals are supposed to excel.

While real verticals over real ground are not a sure-fire method to achieve low-angle radiation, cost versus performance and ease of installation are still attributes that can highly recommend verticals to knowledgeable builders. Practical installations for 160 and 80 meters rarely allow amateurs to put up horizontal antenna high enough to radiate effectively at low elevation angles. After all, a half-wave on 1.8 MHz is 273 feet high, and even at such a lofty height the peak radiation would be at a 30° elevation angle.

The Effects of Irregular Local Terrain in the Far Field

The following material is condensed and updated from an article by R. Dean Straw, N6BV, in July 1995 *QEX* magazine. *HFTA* (HF Terrain Assessment) and supporting data files are included on the CD-ROM at the back of this book. *HFTA* is the latest version of the *YT* program included with earlier editions of *The ARRL Antenna Book*.

Choosing a QTH for DXing

The subject of how to choose a QTH for working DX has fascinated hams since the beginning of amateur operations. No doubt, Marconi probably spent a lot of time wandering around Newfoundland looking for a great radio QTH before making the first transAtlantic transmission. Putting together a high-performance HF station for contesting or DXing has always followed some pretty simple rules. First, you need the perfect QTH, preferably on a rural mountaintop or at least on top of a hill. Even better yet, you need a mountaintop surrounded by seawater! Then, after you have found your dream QTH, you put up the biggest antennas you possibly can, on the highest towers you can afford. Then you work all sorts of DX—sunspots willing, of course.

The only trouble with this straightforward formula for success is that it doesn't always work. Hams fortunate enough to be located on mountain tops with really spectacular drop-offs often find that their highest antennas don't do very well, especially on 15 or 10 meters, but often even on 20 meters. When they compare their signals with nearby locals in the flatlands, they sometimes (but not always) come out on the losing end, especially when sunspot activity is high.

On the other hand, when the sunspots drop into the cellar, the high antennas on the mountaintop are usually the ones crunching the pileups—but again, not always. So, the really ambitious contest aficionados, the guys with lots of resources and infinite enthusiasm, have resorted to putting up antennas at all possible heights, on a multitude of towers.

There is a more scientific way to figure out where and how high to put your antennas to optimize your signal during all parts of the 11-year solar cycle. We advocate a *system approach* to HF station design, in which you need to know the following:

1. The range of elevation angles necessary to get from point A to point B
2. The elevation patterns for various types and configurations of antennas
3. The effect of local terrain on elevation patterns for horizontally polarized antennas.

WHAT IS THE RANGE OF ELEVATION ANGLES NEEDED?

Up until 1994, *The ARRL Antenna Book* contained only a limited amount of information about the elevation angles needed for communication throughout the world. In the 1974 edition, Table 1-1 in the Wave Propagation chapter was captioned: "Measured vertical angles of arrival of signals from England at receiving location in New Jersey."

What the caption didn't say was that Table 1-1 was derived from measurements made during 1934 by Bell Labs. The highest frequency data seemed pretty shaky, considering that 1934 was the low point of Cycle 17. Neither was this data applicable to any other path, other than the one from New Jersey to England. Nonetheless, many amateurs located throughout the US tried to use the sparse information in Table 1-1 as the only rational data they had for determining how high to mount their antennas. (If they lived on hills, they made estimates of the effect of the terrain, assuming that the hill was adequately represented by a long, unbroken slope. More on this later.)

In 1993 ARRL HQ embarked on a major project to tabulate the range of elevation angles from all regions of the US to important DX QTHs around the world. This was accomplished by running many thousands of computations using the *IONCAP* computer program. *IONCAP* has been under development for more than 25 years by various agencies of the US government and is considered the standard of comparison for propagation programs by many agencies, including the Voice of America, Radio Free Europe, and more than 100 foreign governments throughout the world. *IONCAP* is a real pain in the neck to use, but it is the standard of comparison.

The calculations were done for all levels of solar activity, for all months of the year, and for all 24 hours of the

day. The results were gathered into some very large databases, from which special custom-written software extracted detailed statistics. The results appeared in summary form in Tables 4 through 13 printed in Chapter 23, Radio Wave Propagation, of the 17th Edition and in more detail on the diskette included with that book. (This book, the 20th Edition, contains even more statistical data, for more areas of the world, on the accompanying CD-ROM.)

Fig 30 shows the full range of elevation angles (represented as vertical bars) for the 20-meter path from New England (centered on Newington, Connecticut) to all of Europe. This is for all openings, in all months, over the entire 11-year solar cycle. The most likely elevation angle occurs at 5° for about 13% of the times when the 20-meter band is open to Europe from New England. From 4° to 6° the band is open a total of about 34% of the times the band is open. There is a secondary peak between 10° to 12°, occurring for a total of about 25% of the times the band is open.

Overlaid on Fig 30 along with the elevation-angle statistics are the elevation-plane responses for three different horizontally polarized Yagi beams, all over flat ground. The first is mounted 140 feet high, 2 λ in terms of wavelength. The second Yagi is mounted 70 feet high (at 1 λ) and the third is 35 feet (0.5 λ). The 140-foot high antenna has a deep null at 15°, but it also has the highest response (13.4 dBi) of the three at the statistical peak elevation angle of 5°. However, at 12°—where the band is open some 9% of the time—the 140-foot high Yagi is

down 4 dB compared to the 70-foot antenna.

The 70-foot high Yagi arguably covers the overall range best, since it has no disastrous nulls in the 1° to 25° range, where most of the action is occurring on 20 meters. At 5°, however, its response is only 8.8 dBi, 4.6 dB down from the 140-foot high antenna at that angle. The 35-foot antenna peaks above 26° in elevation angle, and is down some 10.4 dB compared to the 140-foot antenna at 5°. Obviously, no single antenna covers the complete range of elevation angles needed.

Note that the highest Yagi has a strong *second lobe* peaking at 22°. Let's say that you could select between two antennas, one at 140 and one at 70 feet, and that the incoming angle for a particular distant station is 22°. You might be fooled into thinking that the incoming angle is around 6°, favoring the first peak of the higher antenna, when in truth the angle is relatively high. The 70-foot antenna's response would be lower at 22° than the higher one, but only because the 140-foot antenna is operating on its second lobe. (What would clinch a determination of the correct incoming angle—6° or 22°—would be the response of the 35-foot high Yagi, which would be close to its peak at 22°, while it would be very far down at 6°.)

Now, we must emphasize that these elevation angles are *statistical entities*— in other words, just because 5° is the "statistically most likely angle" for the 20-meter path from New England to Europe doesn't mean that the band will be open at 11° at any particular hour, on a particular day, in a particular month, in any particular year. In fact, however, experience agrees with the *IONCAP* computations: the 20-meter path to Europe usually opens at a low angle in the New England morning hours, rising to about 11° during the afternoon, when the signals remain strongest throughout the afternoon until the evening in New England.

What would happen if we were to feed all three Yagi at 140, 70 and 35 feet in-phase as a stack? **Fig 31** shows this situation, along with a more highly optimized stack at 120, 80 and 40 feet that better covers the overall range of elevation angles from Connecticut to Europe.

Now see **Fig 32**, which uses the same 120/80/40-foot stack of 20-meter antennas as in Fig 31, but this time from Seattle, Washington, to Europe. For comparison, the response of a single 4-element Yagi at 100 feet over flat ground is also shown in Fig 32. Just because 5° is the statistically most prevalent angle (occurring some 13% of the time) from Seattle to Europe on 20 meters, this doesn't mean that the actual angle *at any particular moment in time* might not be 10º, or even 2º. The statistics for W7 to Europe say that 5° is the most likely angle, but 20-meter signals from Europe arrive at angles ranging from 1° to 18º. Note that this range of angles is quite a bit less than from W1 to Europe, which is much closer geographically to Europe than is the Pacific Northwest coast of the US. If you design an antenna system to cover all possible angles needed to talk to Europe from Seattle (or from Seattle to Europe) on 20 meters, you would need to cover the full range from 1° to 18º equally well.

Fig 30—Graph showing 20-meter percentage of all openings from New England to Europe versus elevation angles, together with overlay of elevation patterns over flat ground for three 20-meter antenna systems. The most statistically likely angle at which the band will be open is 5°, although at any particular hour, day, month and year, the actual angle will likely be different. Note the deep null exhibited by the 140-foot high antenna centered at 14°.

120/80/40' Stack

Four-Element Yagi, 8.5 dBi Free-Space Gain

Fig 31—Graph showing results of stacking antennas at different heights on the same tower to cover a wider range of elevation angles, in this case for the path from Connecticut (W1) to all of Europe on 20 meters. The optimized stack at 120/80/40 feet covers the needed range of elevation angles better than the stack at 140/70/35 feet or the single Yagi at 140 feet.

120/80/40' Stack

Four-Element Yagi, 8.5 dBi Free-Space Gain

Fig 33—Graph showing 15-meter percentage of all openings from Chicago to Southern Africa, together with overlay of elevation patterns over flat ground for two 15-meter antenna systems. On this long-distance, low-angle path, higher antennas are again most effective.

120/80/40' Stack

Four-Element Yagi, 8.5 dBi Free-Space Gain

Fig 32—Graph showing 20-meter percentage of all openings, this time from Seattle, WA, to Europe, together with an overlay of elevation patterns over flat ground for two 20-meter antenna systems. The statistically most likely angle on this path is 5°, occurring about 13% of the time when the band is actually open. Higher antennas predominate on this low-angle path.

Similarly, if you wish to cover the full range of elevation angles from Chicago to Southern Africa on 15 meters, you would need to cover 1° to 13°, even though the most statistically likely signals arrive at 1°, for 21% of the time when that the band is open for that path. See **Fig 33**.

It is important to recognize that Figs 30 through 33 are for flat ground. When the antennas are mounted over irregular local terrain, things get much more complicated. First, however, we'll discuss general-purpose antenna modeling programs as they try to model real terrain.

DRAWBACKS OF COMPUTER MODELS FOR ANTENNAS OVER REAL TERRAIN

Modern general-purpose antenna modeling programs such as *NEC* or *MININEC* (or their commercially upgraded equivalents, such as *NEC-Win Plus*, *EZNEC* and *EZNEC ARRL*) can accurately model almost any type of antenna commonly used by radio amateurs. In addition, there are specialized programs specifically designed to model Yagis efficiently, such as *YO* or *YW* (Yagi for Windows, bundled on the CD-ROM with this book) or *YagiMax*. These programs however are all unable to model antennas accurately over anything other than *purely flat ground*.

While both *NEC* and *MININEC* can simulate irregular ground terrain, they do so in a decidedly crude manner, employing step-like concentric rings of height around an antenna. The documentation for *NEC* and *MININEC* both clearly state that diffraction off these steps is not modeled.

Common experience among serious modelers is that the warnings in the manuals are worth heeding.

Although you can analyze and even optimize antenna designs using free-space or flat-earth ground models, it is *diffraction* that makes the real world a very, very complicated place. This should be clarified—diffraction is hard, even tortuous, to analyze properly, but it makes analysis of real world results far more believable than a flat-world reflection model does.

RAY-TRACING OVER UNEVEN LOCAL TERRAIN

The Raytracing Technique

First, let's look at a simple raytracing procedure involving only horizontally polarized reflections, with no diffractions. From a specified height on the tower, an antenna shoots "rays" (just as though they were bullets) in 0.25° increments from +35° above the horizon to –35° below the horizon. Each ray is traced over the foreground terrain to see if it hits the ground at any point on its travels in the direction of interest. If it does hit the ground, the ray is reflected following the classical *law of reflection*. That is, the outgoing angle equals the incoming angle, reflected through the normal to the slope of the surface. Once the rays exit into the ionosphere, the individual contributions are vector-summed to create the overall far-field elevation pattern.

The next step in terrain modeling involves adding *diffractions* as well as reflections. At the Dayton antenna forum in 1994, Jim Breakall, WA3FET, gave a fascinating and tantalizing lecture on the effect of foreground terrain. Later Breakall, Dick Adler, K3CXZ, Joel Young and a group of other researchers published an extremely interesting paper entitled "The Modeling and Measurement of HF Antenna Skywave Radiation Patterns in Irregular Terrain" in July 1994 *IEEE Transactions on Antennas and Propagation*. They described in rather general terms the modifications they made to the *NEC-BSC* program. They showed how the addition of a ray-tracing reflection and diffraction model to the simplistic stair-stepped reflection model in regular *NEC* gave far more realistic results. For validation, they compared actual pattern measurements made on a site in Utah (with an overflying helicopter) to computed patterns made using the modified *NEC* software. However, because the US Navy funded this work the software remained for a long time a military secret.

Thumbnail History of the Uniform Theory of Diffraction

It is instructive to look briefly at the history of how *Geometric Optics* (GO) evolved (and still continues to evolve) into the *Uniform Theory of Diffraction* (UTD). The following is summarized from the historical overview in one book found to be particularly useful and comprehensive on the subject of UTD: *Introduction to the Uniform Geometrical Theory of Diffraction*, by McNamara, Pistorius, and Malherbe.

Many years before the time of Christ, the ancient Greeks studied optics. Euclid is credited with deriving the law of reflection about 300 BC. Other Greeks, such as Ptolemy, were also fascinated with optical phenomena. In the 1600s, a Dutchman named Snell finally figured out the law of refraction, resulting in *Snell's law*. By the early 1800s, the basic world of classical optics was pretty well described from a mathematic point of view, based on the work of a number of individuals.

As its name implies, classical geometric optical theory deals strictly with geometric shapes. Of course, the importance of geometry in optics shouldn't be minimized—after all, we wouldn't have eyeglasses without geometric optics. Mathematical analysis of shapes utilizes a methodology that traces the paths of straight-line *rays* of light. (Note that the paths of rays can also be likened to the straight-line paths of particles.) In classical geometric optics, however, there is no mention of three important quantities: phase, intensity and polarization. Indeed, without phase, intensity or polarization, there is no way to deal properly with the phenomenon of *interference*, or its cousin, *diffraction*. These phenomena require theories that deal with *waves* rather than rays.

Wave theory has also been around for a long time, although not as long as geometry. Workers like Hooke and Grimaldi had recorded their observations of interference and diffraction in the mid 1600s. Huygens had used elements of wave theory in the late 1600s to help explain refraction. By the late 1800s, the work of Lord Rayleigh, Sommerfeld, Fresnel, Maxwell and many others led to the full mathematic characterization of all electromagnetic phenomena, light included.

Unfortunately, ray theory doesn't work for many problems, at least ray theory in the classical optical form. The real world is a lot more jagged, pointy and fuzzy in shape than can be described in a totally rigorous mathematic fashion. Some properties of the real world are most easily explained on the micro level using electrons and protons as conceptual objects, while other macro phenomena (like resonance, for example) are more easily explained in terms of waves. To get a handle on a typical real-world physical situation, a combination of classical ray theory and wave theory was needed.

The breakthrough in the combination of classical geometric optics and wave concepts came from J. B. Keller of Bell Labs in 1953, although he published his work in the early 1960s. In the very simplest of terms, Keller introduced the notion that shooting a ray at a diffraction *wedge* causes wave interference at the tip, with an infinite number of diffracted waves emanating from the diffraction point. Each diffracted wave can be considered to be a point source radiator at the place of generation, the diffraction point. Thereafter, the paths of individual waves can be traced as

though they were individual classical optic rays again. What Keller came up with was a reasonable mathematical description of what happens at the tip of the diffraction wedge.

Fig 34 is a picture of a simple diffraction wedge, with an incoming ray launched at an angle of α_r, referenced to the horizon, impinging on it. The diffraction wedge here is considered to be perfectly conducting, and hence impenetrable by the ray. The wedge generates an infinite number of diffracted waves, going in all directions not blocked by the wedge itself. The amplitudes and phases of the diffracted waves are determined by the interaction at the wedge tip, and this in turn is governed by the various angles associated with the wedge. Shown in Fig 34 are the included angle a of the wedge, the angle ϕ' of the incoming ray (referenced to the incoming surface of the wedge), and the observed angle ϕ of one of the outgoing diffracted waves, also referenced to the wedge surface.

The so-called *shadow boundaries* are also shown in Fig 34. The Reflection-Shadow Boundary (RSB) is the angle beyond which no further reflections can take place for a given incoming angle. The Incident-Shadow Boundary (ISB) is that angle beyond which the wedge's face blocks any incident rays from illuminating the observation point.

Keller derived the amplitude and phase terms by comparing the classical Geometric Optics (GO) solution with the exact mathematical solution calculated by Sommerfeld for a particular case where the boundary conditions were well known—an infinitely long, perfectly conducting wedge illuminated by a plane wave. Simply speaking, whatever was left over had to be diffraction terms. Keller combined these diffraction terms with GO terms to yield the total field everywhere.

Keller's new theory became known as the *Geometric Theory of Diffraction* (abbreviated henceforth as GTD). The beauty of GTD was that in the regions where classical GO predicted zero fields, the GTD "filled in the blanks," so to speak. For example, see **Fig 35**, showing the terrain for a hypothetical case, where a 60-foot high 4-element 15-meter Yagi illuminates a wide, perfectly flat piece of ground. A 10-foot high rock has been placed 400 feet away from the tower base in the direction of outgoing rays. **Fig 36** shows the elevation pattern predicted using reflection-only GO techniques. Due to blockage of the direct wave (A) trying to shoot past the 10-foot high rock, and due to blockage of (B) reflections from the flat ground in front of the rock by the rock, there is a *hole* in the smooth elevation pattern.

Now, doesn't it defy common sense to imagine that a single 10-foot high rock will really have such an effect on a 15-meter signal? Keller's GTD took diffraction effects into account to show that waves do indeed sneak past and over the rock to fill in the pattern. The whole GTD scheme is very clever indeed.

However, GTD wasn't perfect. Keller's GTD predicts some big spikes in the pattern, even though the overall shape of the elevation pattern is much closer to reality than a simple GO reflection analysis would indicate. The region right at the RSB and ISB shadow boundaries is where problems are found. The GO terms go to zero at these points because of blockage by the wedge, while Keller's diffraction terms tend to go to infinity at these very spots. In mathematical terms this is referred to as a *caustic problem*. Nevertheless, despite these nasty problems at the ISB and RSB, the GTD provided a remarkably better solution to diffraction problems than did classical GO.

In the early 1970s, a group at Ohio State University under R. G. Kouyoumjian and P. H. Pathak did some pivotal work to resolve this caustic problem, introducing what amounts to a clever *fudge factor* to compensate for the tendency of the diffraction terms at the shadow boundaries to go to infinity. They introduced what is known as a *transition function*, using a form of Fresnel integral. Most importantly, the Ohio State researchers also created several FORTRAN computer programs to compute the amplitude and phase of diffraction components. Now computer hackers could get to work!

Fig 34—Diagram showing diffraction mechanism of ray launched at angle α_r below the horizon at a diffraction wedge, whose included angle is α. Referenced to the incident face (the *o-face* as it is called in UTD terminology), the incoming angle is ϕ' (phi prime). The wedge creates an infinite number of diffracted waves. Shown is one whose angle referenced to the o-face is ϕ, the so-called *observation angle* in UTD terminology.

Fig 35—Hypothetical terrain exhibiting so-called "10-foot rock effect." The terrain is flat from the tower base out to 400 feet, where a 10-foot high rock is placed. Note that this forms a diffraction wedge, but that it also blocks direct waves trying to shoot through it to the flat surface beyond, as shown by Ray A. Ray B reflects off the flat surface before it reaches the 10-foot rock, but it is blocked by the rock from proceeding further. A simple Geometric Optics (GO) analysis of this terrain without taking diffraction into account will result in the elevation response shown in Fig 36.

Four-Element Yagi, 8.5 dBi Free-Space Gain

Fig 36—Elevation response for rays launched at terrain in Fig 35 from a height of 60 feet using a 4-element Yagi. This was computed using a simple Geometrical Optics (GO) reflection-only analysis. Note the *hole* in the response between 6° to 10° in elevation. It is not reasonable for a 10-foot high rock to create such a disturbance at 21 MHz!

The program that finally resulted is called *HFTA*, standing for "HF Terrain Assessment." (The DOS version of *HFTA* was known as *YT*, standing for "Yagi Terrain.") As the name suggests, *HFTA* analyzes the effect of local terrain on HF propagation through the ionosphere. It is designed for horizontally polarized Yagis, although it will model the effects of a simple flattop dipole also. The accurate appraisal of the effect of terrain on vertically polarized signals is a far more complex problem than for horizontally polarized waves, and *HFTA* doesn't do verticals.

SIMULATION OF REALITY—SOME SIMPLE EXAMPLES FIRST

We want to focus first on some simple results, to show that the computations do make some sense by presenting some simulations over simple terrains. We've already described the "10-foot rock at 400 feet" situation, and showed where a simple GO reflection analysis is inadequate to the task without taking diffraction effects into account.

Now look at the simple case shown in **Fig 37**, where a very long, continuous downslope from the tower base is shown. Note that the scales used for the X and Y axes are different: the Y-axis changes 300 feet in height (from 800 to 1100 feet), while the X-axis goes from 0 to 3000 feet. This exaggerates the apparent steepness of the downwards slope, which is actually a rather gentle slope, at $\tan^{-1}(1000 - 850)/(3000 - 0) = -2.86°$. In other words, the terrain falls 150 feet in height over a range of 3000 feet from the base of the tower.

Fig 38 shows the computed elevation response for this terrain profile, for a 4-element horizontally polarized Yagi

on a 60-foot tower. The response is compared to that of an identical Yagi placed 60 feet above flat ground. Compared to the "flatland" antenna, the hilltop antenna has an elevation response shifted over by almost 3° towards the lower elevation angles. In fact, this shift is directly due to the −2.86° slope of the hill. Reflections off the slope are tilted by the slope. In this situation there is a single diffraction at the bottom of the gentle slope at 3000 feet, where the program assumes that the terrain becomes flat.

Look at **Fig 39**, which shows another simple terrain profile, called a "Hill-Valley" scenario. Here, the 60-foot high tower stands on the edge of a gentle hill overlooking a long valley. Once again the slope of the hill is exaggerated by the different X and Y-axes. **Fig 40** shows the computed elevation response at 21.2 MHz for a 4-element Yagi on a 60-foot high tower at the edge of the slope.

Once again, the pattern is overlaid with that of an identical 60-foot-high Yagi over flat ground. Compared to the flatland antenna, the hilltop antenna's response above 9° in elevation is shifted by almost 3° towards the lower elevation angles. Again, this is due to reflections off the downward slope. From 1° to 9°, the hilltop pattern is enhanced even more compared to the flatland antenna, this time by diffraction occurring at the bottom of the hill.

Now let's see what happens when there is a hill ahead in the direction of interest. **Fig 41** depicts such a situation, labeled "Hill-Ahead." Here, at a height of 400 feet above mean sea level, the land is flat in front of the tower, out to a distance 500 feet, where the hill begins. The hill then rises 100 feet over the range 500 to 1000 feet away

Fig 37—A long, gentle downwards-sloping terrain. This terrain has no explicit diffraction points and can be analyzed using simple GO reflection techniques.

Fig 39—"Hill-Valley" terrain, with reflected and diffracted rays.

Fig 38—Elevation response for terrain shown in Fig 37, using a 4-element 15-meter Yagi, 60-foot high. Note that the shape of the response is essentially shifted towards the left, towards lower elevation angles, by the angle of the sloping ground. For reference, the response for an identical Yagi placed over flat ground is also shown.

Fig 40—Elevation response computed by *HFTA* program for single 4-element 15-meter Yagi at 60 feet above "Hill-Valley" terrain shown in Fig 39. Note that the slope has caused the response in general to be shifted towards lower elevation angles. At 5° elevation, the diffraction components add up to increase the gain slightly above the amount a GO-only analysis would indicate.

from the tower base. After that, the terrain is a plateau, at a constant 500 feet elevation.

Fig 42 shows the computed elevation pattern for a 4-element 21-MHz Yagi 60-feet high on the tower, compared again with an overlay for an identical 60-foot high antenna over flat ground. The hill blocks low-angle waves directly radiated from the antenna from 0° to 2.3°. In addition, waves that would normally be reflected from the ground, and that would normally add in phase from about 2.3° to 12°, are blocked by the hill also. Thus the signal at 8° is down almost 5 dB from the signal over flat ground, all due to the effect of the hill. Diffracted waves start kicking in once the direct wave rises enough above the horizon to illu-

minate the top edge of the hill. These diffracted waves tend to augment elevation angles above about 12°, which reflected waves can't reach.

Is there is any hope for someone in such a lousy QTH for DXing? **Fig 43** shows the elevation response for a truly heroic solution. This involves a stack of four 4element Yagis, mounted at 120, 90, 60 and 30 feet on the tower. Now, the total gain at low angles is just about comparable to that from a single 4-element Yagi mounted over flat ground. Where there's a ham, there is a way!

Fig 41—"Hill-Ahead" terrain, shown with diffracted rays created by illumination of the edge of the plateau at the top of the hill.

Fig 42—Elevation response computed by *HFTA* for "Hill-Ahead" terrain shown in Fig 41. Now the hill blocks direct rays and also precludes possibility of any constructive reflections. Above 10°, diffraction components add up together with direct rays to create the response shown.

At 5° elevation, four diffraction components add up (there are zero reflection components) to achieve the far-field pattern. This seems reasonable, because each of the four antennas is illuminating the diffraction point separately and we know that none of the four antennas can *see over* the hill directly to produce a reflection at a low launch angle.

At an elevation angle of 5°, 15-meter signals arrive from Europe from New England about 13% of the total time when the band is actually open. We can look at this another way. For about two-thirds of the times when the band is open on this path, the incoming angle is between 3° to 12°. For about one-third of the time, signals arrive above 10°, where the "heroic" four-stack is really beginning to come into its own.

Fig 43—Elevation response of "heroic effort" to surmount the difficulties imposed by hill in Fig 41. This effort involves a stack of four 4-element Yagis in a stack starting at 120 feet and spaced at 30-foot increments on the tower. The response is roughly equivalent to a single 4-element Yagi at 60 feet above flat ground, hence the characterization as being a "heroic effort." The elevation-angle statistics from New England to Europe are overlaid on the graph for reference.

A More Complex Terrain

The results for simple terrains look reasonable; let's try a more complicated real-world situation. **Fig 44** shows the terrain from the New Hampshire N6BV/1 QTH towards Japan. The terrain was complex, with 52 different points *HFTA* identifies as diffraction points. **Fig 45** shows a labeled *HFTA* output for three different types of antennas on 20 meters: a stack at 120 and 60 feet, the 120-foot antenna by itself, and then a 120/60-foot stack over flat ground, for reference. The elevation-angle statistics for New England to Japan are overlaid on the graph also, making for a very complicated looking picture—it is a *lot* easier to decipher the lines on the color CRT, by the way than on a black-and-white printer.

Comparison of the same 120/60-foot stacks over irregular terrain and flat ground is useful to show where the terrain itself is affecting the elevation response. The flatland stack has more gain in the region of 3° to 7° than the same stack over the N6BV/1 local terrain towards Japan. On the other hand, the N6BV/1 local terrain boosts signals in the range of 8° to about 12°. This demonstrates the conservation of energy—you may gain a stronger signal at certain elevation angles, but you will lose gain at others. In this case, the N6BV/1 station always felt "weak" towards Japan on 20 meters, because the dominant angles are low.

Examination of the detailed data output from *HFTA* shows that at an elevation angle of 5°, there are 6159

Terrain Profile

Fig 44—Terrain of N6BV in Windham, NH, towards Japan. *HFTA* **identifies 52 different points where diffraction can occur.**

120/60' N6BV/1
120/60' Flat
120' N6BV/1
Four-Element Yagi, 8.5 dBi Free-Space Gain

Fig 45—Elevation responses computed by *HFTA* **for N6BV/1 terrain shown in Fig 44, for a stack of two 4-element 20-meter Yagis at 120 and 60 feet, together with the response for a single Yagi at 120 feet and a 120/60-foot stack over flat ground for reference. The response due to many diffraction and reflection components is quite complicated!**

diffraction components. There are many, many signals bouncing around off the terrain on their trip to Japan! Note that because of blockage of some parts of the terrain, the 60-foot high Yagi cannot illuminate all the diffraction points, while the higher 120-foot Yagi is able to see these diffraction points.

It is fascinating to reflect on the thought that received signals coming down from the ionosphere to the receiver are having encounters with the terrain, but from the opposite direction. It's not surprising, given these kinds of interactions, that transmitting and receiving might not be totally reciprocal.

The 120/60-foot stack in Fig 45 achieves its peak gain of 17.3 dBi at 11° elevation, where it is about 3 dB stronger than the single Yagi at 120 feet. It maintains this 3-dB advantage over most of the range of incoming signals from Japan. This difference in performance between the stack and each antenna by itself was observed many times on the air. Much of the time when comparisons are being made, however, the small differences in signal are difficult to measure meaningfully, especially when the QSB varies signals by 20 dB or so during a typical QSO. It should be noted that the stack usually exhibited less fading compared to each antenna by itself.

USING *HFTA*

Manually Generating a Terrain Profile

The *HFTA* program uses two distinct algorithms to generate the far-field elevation pattern. The first is a simple reflection-only Geometric Optics (GO) algorithm. The second is the diffraction algorithm using the Uniform Theory of Diffraction (UTD). These algorithms work with a digitized representation of the terrain profile for a single azimuthal direction—for example, towards Japan or towards Europe.

You can generate a terrain file manually using a topographic map and a ruler or a pair of dividers. The HFTA.PDF file (accessed by clicking on the **Help** button) and on the accompanying CD-ROM gives complete instructions on how to create a terrain file manually (or automatically). The manual process is simple enough in concept. Mark on your US Geological Survey 7.5-minute map the exact location of your tower. You will find 7.5-minute maps available from some local sources, such as large hardware stores, but the main contact point is the U.S. Geological Survey, Denver, CO 80225 or Reston, VA 22092. Call 1-800-MAPS-USA. Ask for the folder describing the topographic maps available for your geographic area. Many countries outside the USA have topographic charts also. Most are calibrated in meters. To use these with *HFTA*, you will have to convert meters to feet by multiplying meters by 3.28 or else inserting a single line at the very beginning of the disk file, saying "meters" for *HFTA* to recognize meters automatically.

Mark off a pencil line from the tower base, in the azimuthal direction of interest, perhaps 45° from New England to Europe, or 335° to Japan. Then measure the distance from the tower base to each height contour crossed by the pencil line. Enter the data at each distance/height into an ASCII computer file, whose filename extension is "PRO," standing for *profile*.

Fig 46 shows a portion of the USGS paper map for the N6BV QTH in Windham, NH, along with lines scribed in several directions towards various parts of Europe and the Far East. Note that the elevation heights of the intermediate

contour lines are labeled manually in pencil in order to make sense of things. It is very easy to get confused unless you do this!

The terrain model used by *HFTA* assumes that the terrain is represented by flat *plates* connecting the elevation points in the *.PRO file with straight lines. The model is two dimensional, meaning that range and elevation are the only data for a particular azimuth. In effect, *HFTA* assumes that the width of a terrain plate is wide relative to its length. Obviously, the world is three-dimensional. If your shot in a particular direction involves aiming your Yagi down a canyon with steep walls, then it's pretty likely that your actual elevation pattern will be different than what *HFTA* tells you. The signals must careen horizontally from wall to wall, in addition to being affected by the height changes of the terrain. *HFTA* isn't designed to do canyons.

To get a true 3-D picture of the full effects of terrain, a terrain model would have to show azimuth, along with range and elevation, point-by-point for about two miles in every direction around the base of the tower. After you go through the pain of creating a profile for a single azimuth, you'll appreciate the immensity of the process if you were you try to create a full 360° 3D profile manually.

Terrain Data from the Internet

At one time digitized terrain data commonly available from the Internet didn't have sufficient resolution to be accurate enough for *HFTA*. Nowadays, the complete, accurate set of USGS topographic 7.5-minute maps are available at no cost on the Internet. You can use a program called *MicroDEM*, written by Professor Peter Guth at the US Naval Academy, to quickly and easily produce terrain data files suitable for *HFTA* from topographic data files. Dr Guth and the US Naval Academy have graciously allowed ARRL to include the *MicroDEM* program on the CD-ROM accompanying this book. It should be noted that besides automatically creating terrain profiles for *HFTA*, *MicroDEM* is a full-featured mapping program on its own.

Instructions for using *MicroDEM* are in the Help file for *HFTA* (HFTA.PDF), which you can access from the *HFTA* main window by clicking on the **Help** button. **Fig 47** shows a screen capture of the *MicroDEM* program for the N6BV/1 location in New Hampshire for an azimuth of 45° into Europe. The black/white rendering of the screen capture doesn't do justice to the same information in color. The computed terrain profile is plotted in the window at the right of Fig 47 and the data file is shown in the inset window at the top right.

Using *MicroDEM* and on-line USGS topographic map data, you can also automatically create up to 360 terrain profiles with 1° spacing of azimuths in a few seconds. (Specifying a 1° spacing is really overkill; most operator choose to create 72 profiles with 5° spacing.) On a topographic DEM (digital elevation model) map that covers the geographic

Fig 46—A portion of USGS 7.5 minute topographic map, showing N6BV/1 QTH, together with marks in direction of Europe and Japan from tower base. Note that the elevations contours were marked by hand to help eliminate confusion. This required a magnifying glass and a steady hand!

area of interest, you simply specify the latitude and longitude of a tower's location—found using a GPS receiver—and then ask *MicroDEM* for a **Viewshed**. See the *HFTA* **Help** file for the details.

Compare this automated several-second *MicroDEM* process to creating manual profiles on a paper topographic map—It can take up to an hour of meticulous measurements to manually create a single terrain profile!

Algorithm for Ray-Tracing the Terrain

Once a terrain profile is created, there are a number of mechanisms that *HFTA* takes into account as a ray travels over that terrain:

1. Classical ray reflection, with Fresnel ground coefficients.
2. Direct diffraction, where a diffraction point is illuminated directly by an antenna, with no intervening terrain features blocking the direct illumination.
3. When a diffracted ray is subsequently reflected off the terrain.
4. When a reflected ray encounters a diffraction point and causes another series of diffracted rays to be generated.
5. When a diffracted ray hits another diffraction point, generating another whole series of diffractions.

Certain unusual, bowl-shaped terrain profiles, with sheer vertical faces, can conceivably cause signals to reflect or diffract in a backwards direction, only to be reflected back again in the forward direction by the sheer-walled terrain to the rear. *HFTA* does not accommodate these interactions, mainly because to do so would increase the computation time too much. It only evaluates terrain in the forward direction along one azimuth of interest.

Fig 48 shows a portion of an *HFTA* screen capture in the direction towards Europe from the N6BV/1 location in New Hampshire on 21.2 MHz. It compares the results for a 90/60/30-foot stack of TH7DX tribanders to the same stack over flat land, and to a single antenna at 70 feet over flat ground. The 70-foot single antenna represents a pretty typical station on 15 meters. The terrain produces excellent gain at lower elevation angles compared to the same stack over flat ground. The stack is very close to or superior to the single 70-foot high Yagi at all useful elevation angles. Terrain can indeed exhibit a profound effect on the launch of signals into the ionosphere—for good or for bad.

HFTA's Internal Antenna Model

The operator selects the antenna used inside *HFTA* to be anything from a dipole to an 8-element Yagi. The default assumes a simple cosine-squared mathematic response, equivalent to a 4-element Yagi in free space. *HFTA* traces rays only in the forward direction from the tower along the azimuth of interest. This keeps the algorithms reasonably simple and saves computing time.

HFTA considers each antenna in a stack as a separate *point source*. The simulation begins to fall apart if a traveling wave type of antenna like a rhombic is used, particularly if the terrain changes under the antenna—that is, the ground is not flat under the entire antenna. For a typical Yagi, even a long-boom one, the point-source assumption is reasonable. The internal antenna model also assumes that the Yagi is horizontally polarized. *HFTA* does not do vertically polarized antennas, as discussed previously. The documentation for *HFTA* also cautions the user to work with practical spacings between stacked Yagis—0.5 λ or more

Fig 47—A screen-capture of the *MicroDEM* program, showing the topographic map for the same terrain shown in Fig 46, together with the computed terrain profile along an azimuth of 45° on the path towards Europe from the N6BV/1 location in Windham, NH.

Fig 48—The 21-MHz elevation response for a stack of three TH7DX Yagis mounted on a single tower at 90/60/30 feet, at the N6BV/1 QTH for a 45° azimuth towards Europe. The terrain focuses the energy at low elevation angles compared to the same stack over flat ground. This illustrates once again the conservation of energy—Energy squeezed down into low elevation angles is stolen from other, higher, angles.

because *HFTA* doesn't explicitly model mutual coupling between Yagis in a stack.

HFTA compares well with the measurements for the horizontal antennas described earlier by Jim Breakall, WA3FET, using a helicopter in Utah. Breakall's measurements were done with a 15-foot high horizontal dipole.

More Details About *HFTA*
Frequency Coverage

HFTA can be used on frequencies higher than the HF bands, although the graphical resolution is only 0.25°. The patterns above about 100 MHz thus look rather grainy. The UTD is a *high-frequency-asymptotic* solution, so in theory the results become more realistic as the frequency is raised. Keep in mind too that *HFTA* is designed to model launch angles for skywave propagation modes, including E- and F-layer, and even Sporadic-E. Since by definition the ionospheric launch angles include only those above the horizon, direct line-of-sight UHF modes involving negative launch angles are not considered in *HFTA*.

See the HFTA.PDF documentation file for further details on the operation of *HFTA*. This file, as well as sample terrain profiles for some *big-gun* stations, is located on the CD-ROM accompanying this book.

BIBLIOGRAPHY

Source material and more extended discussion of the topics covered in this chapter can be found in the references

listed below and in the textbooks listed at the end of Chapter 2, Antenna Fundamentals.

B. Boothe, "The Minooka Special," *QST*, Dec 1974.

Brown, Lewis and Epstein, "Ground Systems as a Factor in Antenna Efficiency," *Proc. IRE* , Jun 1937.

G. Brown, "The Phase And Magnitude Of Earth Currents Near Radio Transmitting Antennas," *Proc. IRE*, Feb 1935, pp 168-182.

R. Collin and F. Zucker, *Antenna Theory*, Chap 23 by J. Wait, Inter-University Electronics Series (New York: McGraw-Hill, 1969), Vol 7, pp 414-424.

T. Hullick, W9QQ, "A Two-Element Vertical Parasitic Array For 75 Meters," *QST*, Dec 1995, pp 38-41.

R. Jones, "A 7-MHz Vertical Parasitic Array," *QST*, Nov 1973.

T. Larsen, "The E-Field and H-Field Losses Around Antennas With a Radial Ground Wire System," *Journal of Research of the National Bureau of Standards*, D. Radio Propagation, Vol 66D, No. 2, Mar-Apr 1962, pp 189-204.

D. A. McNamara, C. W. I. Pistorius, J. A. G. Malherbe, *Introduction to the Geometrical Theory of Diffraction* (Norwood, MA: Artech House, 1994).

C. J. Michaels, "Some Reflections on Vertical Antennas," *QST*, Jul 1987.

C. J. Michaels, "Horizontal Antennas and the Compound Reflection Coefficient," *The ARRL Antenna Compendium, Vol 3* (Newington: ARRL, 1992).

R. Severns, N6LF, "Verticals, Ground Systems and Some History," *QST*, Jul 2000, pp 38-44.

J. Sevick, "The Ground-Image Vertical Antenna," *QST*, Jul 1971.

J. Sevick, "The W2FMI 20-Meter Vertical Beam," *QST*, Jun 1972.

J. Sevick, "The W2FMI Ground-Mounted Short Vertical," *QST*, Mar 1973.

J. Sevick, "A High Performance 20-, 40- and 80-Meter Vertical System," *QST*, Dec 1973.

J. Sevick, "The Constant-Impedance Trap Vertical," *QST*, Mar 1974.

J. Stanley, "Optimum Ground Systems for Vertical Antennas," *QST*, Dec 1976.

F. E. Terman, *Radio Engineers' Handbook*, 1st ed. (New York, London: McGraw-Hill Book Co, 1943).

Radio Broadcast Ground Systems, available from Smith Electronics, Inc, 8200 Snowville Rd, Cleveland, OH 44141.

The last major study that appeared in the Amateur literature on the subject of local terrain as it affects DX appeared in four *QST* "How's DX" columns, by Clarke Greene, K1JX, from October 1980 to January 1981. Greene's work was an update of a landmark Sep 1966 *QST* article entitled "Station Design for DX," by Paul Rockwell, W3AFM. The long-range profiles of several prominent, indeed legendary, stations in Rockwell's article are fascinating: W3CRA, W4KFC and W6AM.

Chapter 4

Antenna Modeling & System Planning

OVERVIEW:
ANTENNA ANALYSIS BY COMPUTER

As pointed out in Chapter 3, The Effects of Ground, irregular local terrain can have a profound effect on the launch of HF signals into the ionosphere. A *system approach* is needed to create a scientifically planned station. We pointed out in Chapter 3 that antenna modeling programs do not generally take into account the effects of irregular terrain, and by "irregular" we mean any sort of ground that is not flat. Most modeling programs based on *NEC-2* or *MININEC* do model reflections, but they do not model diffractions.

On the other hand, while a ray-tracing program like *HFTA* (HF Terrain Assessment) does take into account diffraction, it doesn't explicitly factor in the mutual impedance between an antenna and the ground. Instead, *HFTA* makes the basic assumption that the antenna is mounted sufficiently high above ground so that the mutual impedance between an antenna and the ground is minimal.

In this chapter we'll look at modeling the antennas themselves on the PC. We'll evaluate some typical antennas over flat ground and also in free space. Once characterized—or even optimized for certain characteristics—these antennas can then be analyzed over real terrain using *HFTA* and the other tools discussed in Chapter 3.

A Short History of Antenna Modeling

With the proliferation of personal computers since the early 1980s, amateurs and professionals alike have made significant strides in computerized antenna system analysis. It is now possible for the amateur with a relatively inexpensive computer to evaluate even complicated antenna systems. Amateurs can obtain a keener grasp of the operation of antenna systems—a subject that has been a great mystery to many in the past. We might add that modern computing tools allow hams to debunk overblown claims made about certain antennas.

The most commonly encountered programs for antenna analysis are those derived from a program developed at US government laboratories called *NEC*, short for "Numerical Electromagnetics Code." *NEC* uses a so-called *Method of Moments* algorithm. This intriguing name derives from a mathematical convention dealing with how "momentous" the accumulated error becomes when certain simplifying assumptions are made about the current distribution along an antenna wire. If you want to delve into details about the method of moments, John Kraus, W8JK, has an excellent chapter in his book *Antennas*, 2nd edition. See also the article "Programs for Antenna Analysis by the Method of Moments," by Bob Haviland, W4MB, in *The ARRL Antenna Compendium, Vol 4*.

The mathematics behind the method-of-moments algorithm are pretty formidable, but the basic principle is simple. An antenna is broken down into a number of straight-line wire *segments*, and the field resulting from the RF current in each segment is evaluated by itself and also with respect to other mutually coupled segments. Finally, the field from each contributing segment is vector-summed to yield the total field, which can be computed for any elevation or azimuth angle desired. The effects of flat-earth ground reflections, including the effect of ground conductivity and dielectric constant, may be evaluated as well.

In the early 1980s, *MININEC* was written in BASIC for use on personal computers. Because of limitations in

memory and speed typical of personal computers of the time, several simplifying assumptions were necessary in *MININEC* and these limited potential accuracy. Perhaps the most significant limitation was that perfect ground was assumed to be directly under the antenna, even though the radiation pattern in the far field did take into account real ground parameters. This meant that antennas modeled closer than approximately 0.2 λ over ground sometimes gave erroneous impedances and inflated gains, especially for horizontal polarization. Despite some limitations, *MININEC* represented a remarkable leap forward in analytical capability. See Roy Lewallen's (W7EL)

"*MININEC*—the Other Edge of the Sword" in Feb 1991 *QST* for an excellent treatment on pitfalls when using *MININEC*.

Because source code was made available when *MININEC* was released to the public, a number of programmers produced some very capable commercial versions for the amateur market, many incorporating exciting graphics showing antenna patterns in 2D or 3D. These programs also simplify the creation of models for popular antenna types, and several come with libraries of sample antennas.

By the end of the 1980s, the speed and capabilities

Commercial Implementations of *MININEC* and *NEC-2* Programs

Ever since the source code for *NEC-2* and *MININEC* came into in the public domain, enterprising programmers have been upgrading, extending and improving these programs. There are a number of "freeware" versions available nowadays, and there are also a variety of commercial implementations.

This sidebar deals only with the most popular commercial versions, programs that many hams use. You should keep in mind that whatever program you choose will require an investment in learning time, if not in dollars. Your time is valuable, of course, and so is the ability to swap modeling files you create with other modelers. Other peoples' modeling files, particularly when you are just starting out, are a great way to learn how the "experts" do their modeling. For example, there are archives of *EZNEC/ELNEC* files available on the Internet, since this popular modeling program has been around for a number of years. (*ELNEC* is the DOS-only, *MININEC*-core predecessor of EZNEC.)

The following table summarizes the main features and the pricing as of 2006 for some popular commercial antenna modeling programs. The programs that use the *NEC-4* core require separate licenses from Lawrence Livermore National Laboratories.

Commercial Implementations of *MININEC* and *NEC 2* programs

Name	EZNEC 4.0 (+ ver.)	EZNEC-M Pro	EZNEC/4	NEC-Win Plus +	NEC-Win Pro	GNEC	Antenna Model
Manufacturer	Roy Lewallen	Roy Lewallen	Roy Lewallen	Nittany Scientific	Nittany Scientific	Nittany Scientific	Teri Software
Core	NEC-2	NEC-2	NEC-4	NEC-2	NEC-2	NEC-2/NEC-4	MININEC
Operating System	Windows 32-bit	Windows 32-bit	Windows 32-bit	Windows 32-bit	Windows 32-bit	Windows 32-bit	Windows 32-bit
Number Segments	500 (1500, + ver.)	20,000	20,000	10,000	10,000	80,000	Limited by memory
NEC-Card Inputs	No	Yes	Yes	Yes	Yes	Yes	No
Other Input	ASCII (NEC, + ver.)	ASCII, NEC	ASCII, NEC	CAD *.DXF	CAD *.DXF	CAD *.DXF	No
Wires by Equation	No	No	No	Yes	Yes	Yes	Yes
Source Setting	By %	By %	By %	By %	By %	By %	By %
Source Type	Current/ Voltage/Split	Current/ Voltage/Split	Current /Voltage/Split	Current/ Voltage/Split	All types	All types	Current/Voltage
R + jX Loads	Yes	Yes	Yes	Yes	Yes	Yes	Yes
RLC Loads	Series, Parallel, Trap	Series, Parallel, Trap	Series, Parallel, Trap	Series, Parallel	Series, Parallel	Series, Parallel	Series, Parallel
True Trap Loads	Yes	Yes	Yes	No	No	No	No
Laplace Loads	Yes	Yes	Yes	Yes	Yes	Yes	No
Conductivity Table	Yes *	Yes *	Yes *	Yes	Yes	Yes	Yes
Average Gain Test	Yes	Yes	Yes	Yes	Yes	Yes	Yes
Transmission Lines	Yes	Yes	Yes	Yes	Yes	Yes	No
View Geometry	Excellent	Excellent	Excellent	Good	Good	Good	Very Good
Geometry Checking	Yes	Yes	Yes	Yes	Yes	Yes	Yes
Easy Height Change	Yes	Yes	Yes	No	No	No	No
Polar Plots	ARRL, linear-dB Az/El, Circ. (+ ver.)	ARRL, linear-dB Az/El, Circ.	ARRL, linear-dB Az/El, Circ.	ARRL, linear-dB Az/El Patterns	ARRL, linear-dB Az/El Patterns	ARRL, linear-dB Az/El Patterns	ARRL, Linear -dB Az/El Patterns
Rectangular Plots	SWR	SWR	SWR	SWR, Zin	SWR, Zin, Az/El, Near/Far Plots, Currents	SWR, Zin, Az/El, Near/Far Plots, Currents	Gain, SWR, F/B, F/R, Rin, Xin
Operating Speed	Fast	Fast	Fast	Very Fast	Very Fast	Very Fast	Slow
Smith Chart	Data for Ext. Smith program	Data for Ext. Smith program	Data for Ext. Smithprogram	No	Yes	Yes	Yes
Near/Far Field Tables	Both	Both	Both	Far	Both	Both	Both
Ground Wave Analysis	No	Yes	Yes	No	Yes	Yes	No
Pricing	$89 Web; $99 CD-ROM, $139 (+ ver.)	$450	$600; must have NEC-4 license	$150	$425	$795	$85

* Wire conductivity is the same for all wires.

Excellent, Very Good, Good ratings done by *Antenna Book* editor.

---

of personal computers had advanced to the point where PC versions of *NEC* became practical, and several versions are now available to amateurs. The most recent public-domain version is *NEC-2* and this is the computational core that we'll use as an example throughout this chapter.

Like *MININEC*, *NEC-2* is a general-purpose modeling package and it can be difficult to use and relatively slow in operation for certain specialized antenna forms. Thus, custom commercial software has been created for more user-friendly and speedier analysis of specific antenna varieties, mainly Yagi arrays. See Chapter 11, HF Yagi Arrays. Also see the sidebar, "Commercial Implementations of *MININEC* and *NEC-2* Programs."

For this edition of *The ARRL Antenna Book*, Roy Lewallen, W7EL, has graciously provided a special version of his *EZNEC 3.0* program, called *EZNEC-ARRL*. This version works with the specific antenna models also bundled on the CD-ROM. Please note that this ARRL-specific version of *EZNEC* is limited to a maximum of 20 segments (we'll explain segments later) for all models except for the special ones included on this CD-ROM. You can find information on how to purchase the full-fledged version of *EZNEC* in the **Help** section of the *EZNEC-ARRL* program.

The following material on antenna modeling is by necessity a summary, since entire books have been written on this subject. Serious modelers would be well-advised to enroll in the online Antenna Modeling course, part of the ARRL Certification and Continuing Education series. L. B. Cebik, W4RNL created the ARRL Antenna Modeling course and it contains a great deal of information, tips and techniques concerning modeling by computer. See: **http://www.arrl.org/news/stories/2002/02/06/2/** for more information. We also strongly recommend that you read the Help files in *EZNEC-ARRL*. There is a wealth of practical information on the finer points of antenna modeling there.

THE BASICS OF ANTENNA MODELING

This chapter will discuss the following antenna-modeling topics for an *NEC-2*-based modeling software, using *EZNEC-ARRL* as an example:
- Program outputs
- Wire geometry
- Segmentation, warnings and limitations
- Source (feed point) placement
- Environment, including ground types and frequency
- Loads and transmission lines
- Testing the adequacy of a model

PROGRAM OUTPUTS

Instruction manuals for software programs traditionally start out describing in detail the input data needed by the program. They then demonstrate the output data the program can generate. We feel it is instructive, however, to turn things around and start out with a brief over-

view of the output from a typical antenna-modeling program.

We'll look at the output from public-domain *NEC-2*. Next, we'll look at the output information available from commercial adaptations of *NEC-2*, using *EZNEC-ARRL* provided by W7EL. After this brief overview of the output data, we'll look in detail at the input data needed to make a modeling program work. In the following discussions it will be very instructive if you to bring up *EZNEC-ARRL* on your computer and open the specific modeling files used in each example. [From now on in this chapter we'll refer merely to *EZNEC* rather than *EZNEC 3.0*, the official name or *EZNEC-ARRL*, a specialized subset of *EZNEC 3.0*. Where there are specific differences between *EZNEC 3.0* and the limited-edition *EZNEC-ARRL* we'll identify them.]

Native *NEC-2*

The native *NEC-2* program produces pages and pages of output formatted for a mainframe "line printer." You may be old enough to remember the stacks of green-and-white, tractor-feed, 132-column computer paper that such a line printer produced. Corporate MIS departments stored untold number of boxes of that paper.

Native *NEC-2* was written in the Fortran language, which stands for *Formula Translation*. Programmers used punched cards to enter the program itself and its accompanying input data into huge mainframe computers. To say that the paper output from *NEC-2* is massive, even intimidating, is putting it mildly. There is a strong distinction between "useful information" and "raw data" and the raw output from native *NEC-2* bombards the user with raw data.

Commercial versions that use the *NEC-2* computational core shield the user from the ugliness of raw line-printer output, as well as punched-card input (or disk surrogates for punched cards). Commercial versions like *EZNEC* do produce output numerical tables where this is useful. These tables show parameters such as the source impedance and SWR at a single frequency, or the characteristics of a load or a transmission line. But as the old saying goes, "One picture is worth a thousand words." This is as true for modeling programs as it is for other endeavors dealing with reams of numbers. Thus, most commercial modeling software packages create *graphs* for the user. *EZNEC* produces the following types of graphs:

- Polar (linear-dB or ARRL-style) graphs of the far-field elevation and azimuth responses.
- 3-D wire-frame graph of the total far-field response.
- Graph of the SWR across a frequency band.
- Graphical display of the RF currents on various conductors in a model.
- Rotatable, zoomable 3-D views of the wires used to make a model.
- Output to programs capable of generating Smith charts.

Fig 1A and 1B shows the computed far-field 2-D elevation and azimuth patterns for a 135-foot long horizontal dipole, mounted in a flattop configuration 50 feet above flat ground. These figures were generated using *EZNEC* at 3.75 MHz. Fig 1C shows a 3-D wire-frame picture of the far-field response, but this time at 14.2 MHz. For comparison, **Table 1** shows a short portion of the line-printer output for the azimuth pattern at 3.75 MHz. The actual printout is many pages long. One picture can indeed replace thousands of numbers!

Fig 2 shows the computed SWR curve over the frequency range 3.0 to 4.0 MHz for this dipole, fed with lossless 50-Ω transmission line. *EZNEC* generated this plot using the "SWR" button. Figs 1 and 2 are typical of the kind of graphical outputs that commercial implementations of the *NEC-2* computing core can produce.

Now, let's get into the details of what kind of input data is required to run a typical method-of-moments antenna-modeling program.

PROGRAM INPUTS: WIRE GEOMETRY
Coordinates in an X, Y and Z World

The most difficult part of using a *NEC*-type of modeling program is setting up the antenna's geometry—you must condition yourself to think in three-dimensional, Cartesian coordinates. Each end point of a wire is represented by three numbers: an x, y and z coordinate. These coordinates represent the distance from the origin (x-axis), the width of an antenna (y-axis), and the height (z-axis).

An example should help sort things out. **Fig 3** shows a simple model of a 135-foot center-fed dipole, made of #14 copper wire placed 50 feet above flat ground. The common term for this antenna is *flattop dipole*. For convenience, the ground is located at the *origin* of the coordinate system, at (0, 0, 0) feet, directly under the center of the dipole. **Fig 4** shows the *EZNEC* spreadsheet-like input data for this antenna. (Use model file: **Ch4-Flattop Dipole.EZ**.) *EZNEC* allows you to specify the type of conductor material from its main window, using the **Wire Loss** button to open a new window. We will click on the **Copper** button for this dipole.

Above the origin, at a height of 50 feet on the z-axis, is the dipole's *feed point*, called a *source* in *NEC* terminology. The width of the dipole goes toward the left (that is, in the "negative-y" direction) one-half the overall length of 135 feet, or −67.5 feet. Toward the right, our dipole's other end is at +67.5 feet. The x-axis dimension of our dipole is zero, meaning that the dipole wire is parallel to and directly above the x-axis. The dipole's ends are thus represented by two points, whose coordinates are (0, −67.5, 50) and (0, 67.5, 50) feet. The use of parentheses with a sequential listing of (x, y, z) coordinates is a common practice among antenna modelers to describe a wire end point.

Fig 3B includes some other useful information about this antenna beyond the wire geometry. Fig 3B overlays the wire geometry, the current distribution along the wire and the far-field azimuth response, in this case at an elevation angle of 30°.

Although not shown specifically in Fig 3, the thickness of the antenna is the diameter of the wire, #14 gauge. Note that native *NEC* programs specify the *radius* of the

Fig 1—At A, far-field elevation-plane pattern for a 135-foot-long horizontal dipole, 50 feet above flat ground, at 3.5 MHz. At B, the far-field azimuth-plane pattern at an elevation angle of 30°.

Fig 2—SWR curve for 135-foot flattop dipole over the frequency range 3.0 to 4.0 MHz for a 50-Ω feed line. This antenna is an example and is not optimized for the amateur band.

a single, straight wire. In fact, all antenna models created for method-of-moment programs are made of combinations of straight wires. This includes even complex antennas, such as helical antennas or round loops. (The mathematical basis for modeling complex antennas is that they can be simulated using straight-wire *polygons*. A circular loop, for example, can be modeled using an octagon.)

Segmentation and Specifying a Source Segment

We've specified the physical geometry of this simple one-wire dipole. Now several more modeling details surface—you must specify the number of *segments* into which the dipole is divided for the method-of-moment analysis and you must somehow feed the antenna. The *NEC-2* guideline for setting the number of segments is to use at least 10 segments per half-wavelength. This is a general rule of thumb, however, and in many models more dense segmentation is mandatory for good accuracy.

In Fig 3, we've specified that the dipole be divided into 11 segments for operation on the 80-meter band. This follows the rule of thumb above, since the 135-foot dipole is about a half-wavelength long at 3.5 MHz.

Setting the Source Segment

The use of 11 segments, an odd rather than an even number such as 10, places the dipole's feed point (the

wire, rather than the diameter, but programs like *EZNEC* use the more intuitive diameter of a wire rather than the radius. *EZNEC* (and other commercial programs) also allows the user to specify the wire as an AWG gauge, such as #14 or #22, for example.

We've represented our simple dipole in Fig 3 using

Table 1
Portion of line-printer output from *NEC-2* for 135-foot dipole.

- - - RADIATION PATTERNS - - -

- - ANGLES - -		- POWER GAINS -			- - - POLARIZATION - - -			- - - E(THETA) - - -		- - - E(PHI) - - -	
Theta Degrees	Phi Degrees	Vert dB	Hor dB	Total dB	Axial Ratio	Tilt Degrees	Sense	Magnitude Volts	Phase Degrees	Magnitude Volts	Phase Degrees
60.00	0.00	−999.99	3.14	3.14	0.00000	90.00	LINEAR	0.00000E+00	0.00	6.62073E-01	−66.87
60.00	1.00	−37.87	3.13	3.14	0.00301	89.52	LEFT	5.89772E-03	−86.64	6.61933E-01	−66.87
60.00	2.00	−31.85	3.13	3.13	0.00603	89.04	LEFT	1.17915E-02	−86.64	6.61512E-01	−66.87
60.00	3.00	−28.33	3.12	3.12	0.00904	88.56	LEFT	1.76776E-02	−86.64	6.60812E-01	−66.87
60.00	4.00	−25.84	3.11	3.11	0.01206	88.08	LEFT	2.35520E-02	−86.64	6.59834E-01	−66.87
60.00	5.00	−23.91	3.09	3.10	0.01508	87.59	LEFT	2.94109E-02	−86.64	6.58577E-01	−66.87
60.00	6.00	−22.34	3.07	3.08	0.01810	87.11	LEFT	3.52504E-02	−86.64	6.57045E-01	−66.87
60.00	7.00	−21.01	3.05	3.06	0.02112	86.62	LEFT	4.10669E-02	−86.63	6.55237E-01	−66.87
60.00	8.00	−19.87	3.02	3.04	0.02415	86.14	LEFT	4.68565E-02	−86.63	6.53158E-01	−66.87
60.00	9.00	−18.86	2.99	3.02	0.02718	85.65	LEFT	5.26156E-02	−86.63	6.50808E-01	−66.87
60.00	10.00	−17.96	2.95	2.99	0.03022	85.15	LEFT	5.83405E-02	−86.63	6.48190E-01	−66.87
60.00	11.00	−17.15	2.91	2.96	0.03327	84.66	LEFT	6.40278E-02	−86.63	6.45308E-01	−66.86
60.00	12.00	−16.42	2.87	2.92	0.03631	84.16	LEFT	6.96739E-02	−86.63	6.42165E-01	−66.86
60.00	13.00	−15.75	2.83	2.89	0.03937	83.66	LEFT	7.52755E-02	−86.63	6.38764E-01	−66.86
60.00	14.00	−15.13	2.78	2.85	0.04243	83.16	LEFT	8.08291E-02	−86.63	6.35108E-01	−66.86
60.00	15.00	−14.56	2.72	2.80	0.04550	82.65	LEFT	8.63317E-02	−86.62	6.31203E-01	−66.86
60.00	16.00	−14.03	2.66	2.76	0.04858	82.14	LEFT	9.17800E-02	−86.62	6.27051E-01	−66.86
60.00	17.00	−13.53	2.60	2.71	0.05166	81.62	LEFT	9.71711E-02	−86.62	6.22657E-01	−66.85
60.00	18.00	−13.07	2.54	2.66	0.05475	81.10	LEFT	1.02502E-01	−86.62	6.18027E-01	−66.85

Fig 3—At A, simple model for a 135-foot long
horizontal dipole, 50 feet above the ground. The dipole
is over the y-axis. The wire has been segmented into 11
segments, with the center of segment number 6 as the
feed point. The left-hand end of the antenna is -67.5
feet from the center feed point and that the right-hand
end is at 67.5 feet from the center. At B, *EZNEC* "View
Antenna" drawing, showing geometry of wire and the x,
y and z axes. Overlaid on the wire geometry drawing
are the current distribution along the wire and the far-
field azimuthal response at an elevation angle of 30°.

Fig 4—*EZNEC* "Wires" spreadsheet for simple flattop
dipole in Fig 3. The numbers shown are in feet, except
for the wire diameter, which *EZNEC* allows you to
specify as an AWG gauge, in this case #14. Note that
83 segments have been specified for this antenna for
analysis over the range from 3.5 to 29.7 MHz.

source in *NEC*-speak, a word choice that can befuddle
beginners) right at the antenna's center, at the center of
segment number six. In concert with the "EZ" in its name,
EZNEC makes choosing the source segment easy by
allowing the user to specify a percentage along the wire,
in this case 50% for center feeding.

At this point you may very well be wondering why
no center insulator is shown in the middle of our center-
fed dipole. After all, a real dipole would have a center
insulator. However, method-of-moment programs assume
that a source generator is placed across an infinitely small
gap in the antenna wire. While this is convenient from a
mathematical point of view, the unstated use of such an
infinitely small gap often confuses newcomers to the
world of antenna modeling. We'll get into more details,
caveats and limitations in source placement later in this

chapter. For now, just trust us that the model we've just
described with 11 segments, fed at segment 6, will work
well over the full amateur band from 3.5 to 4.0 MHz.

Now, let's consider what would happen if we want to
use our 135-foot long dipole on all HF amateur bands from
3.5 to 29.7 MHz, rather than just from 3.5 to 4.0 MHz.
Instead of feeding such an antenna with coax cable, we
would feed it with open-wire line and use an antenna tuner
in the shack to create a 50-Ω load for the transmitter. To
comply with the segmentation rule above, the number of
segments used in the model should vary with frequency—
or at least be segmented at or above the minimum recom-
mended level at the highest frequency used. This is because
a half wavelength at 29.7 MHz is 16.6 feet, while a half
wavelength at 3.5 MHz is 140.6 feet. So the number of
segments for proper operation on 29.7 MHz should be 10
× 135/16.6 = 81. We'll be a little more conservative than
the minimum requirement and specify 83 segments. **Fig 4**
shows the *EZNEC* input spreadsheet for this model. (Use
model file: **Ch4-Multiband Dipole.EZ**.)

The penalty for using more segments in a program
like *NEC* is that the program slows down roughly as the
square of the segments—double the number of segments
and the speed drops to a fourth. If we try to use too few
segments, we'll introduce inaccuracies, particularly in
computing the feed-point impedance. We'll delve into this
area of segmentation density in more detail later when
we discuss testing the adequacy of a model.

Segment Length-to-Wire-Diameter Ratio

Even if you're willing to live with the slowdown in
computing speed for situations involving a large number
of wire segments, you should make sure the ratio between
the segment length and the diameter of any wire is greater
than 1:1. This is to say that the length of each segment is
longer than the diameter of the wire. Doing so stays away
from internal limitations in the *NEC* program.

For the #14 wire specified in this simple 135-foot long
dipole, it's pretty unlikely that you'll bump up against this
limitation for any reasonable level of segmentation. After
all, #14 wire has a diameter of 0.064 inches and 135 feet
is 1620 inches. To keep above a segment length of
0.064 inches, the maximum number of segments is 1620/

0.064 = 25,312. This is a *very* large number of segments and it would take a very long time to compute, assuming that your program can handle that many segments.

Keeping above a 1:1 ratio in segment length to wire diameter can be more challenging at VHF/UHF frequencies, however. This is particularly true for fairly large "wires" made of aluminum tubing. Incidentally, this is another point where newcomers to antenna modeling can be led astray by the terminology. In a *NEC*-type program, all conductors in a model are considered to be *wires*, even if they consist of hollow aluminum or copper tubes. Surface effect keeps the RF current in any conductor confined to the outer surface of that conductor, and thus it doesn't matter whether the conductor is hollow or solid, or even made using a number of stranded wires twisted together.

Let's look at a half-wave dipole at 420 MHz. This would be about 14.1 inches long. If you use $^1/_4$-inch diameter tubing for this dipole, the maximum segment length meeting the 1:1 diameter-to-length ratio requirement is also $^1/_4$ inches long. The maximum number of segments then would be 14.1/0.25 = 56.4, rounded down to 56. From this discussion you should now understand why method-of-moment programs are known for using a "thin-wire approximation." Really fat conductors can get you into trouble, particularly at VHF/UHF.

Some Caveats and Limitations Concerning Geometry

Example: Inverted-V Dipole

Now, let's get a little more complicated and specify another 135-foot-long dipole, but this time configured as an *inverted V*. As shown in **Fig 5**, you must now specify two wires. The two wires join at the top, at (0, 0, 50) feet. (Again, the program doesn't use a center insulator in the model.)

If you are using a native version of *NEC*, you may have to go back to your high-school trigonometry book to figure out how to specify the end points of our "droopy" dipole, with its 120° included angle. Fig 5 shows the details, along with the trigonometric equations needed. *EZNEC* is indeed more "easy" here, since it allows you to tilt the ends of each wire downwards an appropriate number of degrees (in this case –30° at each end of the dipole) to automatically create an inverted-V configuration. **Fig 6A** shows the *EZNEC* spreadsheet describing this inverted-V dipole with a 120° included angle between the two wires.

See the *EZNEC* **Help** section under "Wire Coordinate Shortcuts" for specific instructions on how to use the "elevation rotate end" shortcut "RE–30" to create the sloping wires easily by rotating the end of the wire down 30°. Now the specification of the source becomes a bit more complicated. The easiest way is to specify two sources, one on each end segment at the junction of the two wires. *EZNEC* does this automatically if you specify a so-called *split-source* feed. Fig 6B shows the two

Fig 5—Model for an inverted-V dipole, with an included angle between the two legs of 120°. Sine and cosine functions are used to describe the heights of the end points for the sloping arms of the antenna.

Fig 6—At A, *EZNEC* spreadsheet for inverted-V dipole in Fig 5. Now the ends of the inverted-V dipole are 16.25 feet above ground, instead of 50 feet for the flattop dipole. At B, *EZNEC* "View Antenna" drawing, with overlay of geometry, current distribution and azimuth plot.

sources as two open circles at the top ends of the two wires making up the inverted-V dipole. What *EZNEC* is doing is creating two sources, each on the closest segments on either side of the junction of the two wires. *EZNEC* sums up the two source impedances to provide a single readout.

Navigating in the View Antenna Window

At this point it's worthwhile to explore some of the ways you can see what the wire geometry looks like using the *EZNEC* **View Ant** button on the main window. Bring up the file **Ch4-Inverted V Dipole.EZ** in *EZNEC*, and click on the **View Ant** button. You will see a small inverted-V dipole raised over the (0, 0, 0) origin on the ground directly under the feed point of the inverted-V dipole. First, "rotate" the dipole by holding down the left-mouse button and moving the mouse. You can orient the picture any way you wish.

Let's take a closer look at the junction of the two wires at the feed point. Click the **Center Ant Image** checkbox toward the bottom of the window to anchor the center of the image at the center of the window, and then move the **Zoom** slider upwards to zoom in on the image. At some point the junction of the two slanted wires will move up off the edge of the window, so you will need to click on the left-hand side of the **Z Move Image** slider to bring the junction back into view. Now you should be able to see a zoomed view of the junction, along with the two open circles that represent the location of the split sources in the middle of the segments adjacent to the wire junction.

Now put the mouse cursor over one of the slanted wires and double click the left-mouse button. *EZNEC* will now identify that wire and show its length, as well as the length of each segment on that wire. Pretty slick, isn't it?

Short, Fat Wires and the Acute-Angle Junction

Another possible complication can arise for wires with short, fat segments, particularly ones that have only a small included angle between them. These wire segments can end up inter-penetrating within each other's volumes, leading to problems in a model. Once you think of each wire segment as a thick cylinder, you can appreciate the difficulty in connecting two wires together at their ends. The two wires always inter-penetrate each other's volume to some extent. **Fig 7** depicts this problem graphically for two short, fat wires joined at their ends at an acute angle. A rule of thumb is to avoid creating junctions where more than $1/3$ of the wire volumes inter-penetrate. You can achieve this by using longer segment lengths or thinner wire diameters.

Some Other Practical Antenna Geometries

A Vertical Half-Wave Dipole

If you turn the 135-foot-long horizontal dipole in Fig 1 on its end you will create a vertical half-wave dipole that is above the origin of the x, y and z axes. See **Fig 8**, where the bottom end of the dipole is placed 8 feet off the ground to keep it away from humans and animals for safety, at (0, 0, 8) feet. The top end is thus at 8 + 135 = 143 feet off the ground at (0, 0, 143). Fig 8 also shows the current distribution and the elevation pattern for this

Fig 7—A junction of two short, fat wire segments at an acute angle. This results in inter-penetration of the two wire volumes beyond the middle-1/3 recommended limit.

Fig 8—A vertical half-wave dipole, created by turning the dipole in Fig 3 on its end, with a minimum height at the lower end of 8 feet to keep the antenna away from people and animals. The current distribution and the elevation pattern for this antenna are also shown overlaid on the wire geometry.

antenna. (Use *EZNEC* model file: **Ch4-Vertical Dipole.EZ**.)

A Ground-Plane Antenna

The ground-plane model is more complicated than previous ones because a total of five wires are now needed: one for the vertical radiator and four for the radials. **Fig 9** shows the *EZNEC* view for a 20-meter ground plane mounted 15 feet off the ground (perhaps on a garage roof), with the overlay of both the current distribution and the elevation-plane plot. (Use *EZNEC* model file: **Ch4-GP.EZ**.) Note that the source has been placed at the

Fig 9—A vertical ground-plane antenna. The radials and the bottom of the vertical radiator are located 15 feet off the ground in this model. The current distribution along each wire and the far-field elevation-plane pattern are overlaid on the antenna geometry.

Fig 10—*EZNEC* View Antenna for the ground-plane antenna with its four radials tilted downwards by 40° to improve the SWR at the feed point.

bottom segment of the vertical radiator. Once again, the program needs no bottom insulator, since all five wires are connected together at a common point. *EZNEC* reports that this antenna has a resonant feed-point impedance of about 22 Ω, which would show an SWR of 2.3:1 for a 50-Ω coax feed line if no matching system is used, such as a gamma or hairpin match.

Fig 10 shows the same antenna, except that the radials have now been tilted downwards by 35° to facilitate an almost perfect 50-Ω match (SWR = 1.08:1). In addition, the length of the radiator in this model was shortened by 6 inches to re-resonate the antenna. (Use *EZNEC* model file: **Ch4-Modified GP.EZ**.) The trick of tilting the radials downwards for a ground-plane antenna is an old one, and the modeling programs validates what hams have been doing for years.

A 5-Element Horizontal Yagi

This is a little more challenging modeling exercise. Let's use a 5-element design on a 40-foot boom, but rather than using telescoping aluminum tubing for the elements, we'll use #14 wire. The *SCALE* program included with this book on the CD-ROM converted the aluminum-tubing 520-40.YW to a design using #14 copper wire. **Table 2** shows the element lineup for this antenna. (Later in this chapter we'll see what happens when telescoping aluminum tubing is used in a real-world Yagi design.)

Some explanations of what Table 3 means are in order. First, only one half of each element is shown. The *YW* program (Yagi for Windows), also included on the CD-ROM, computes the other half of the Yagi automatically, essentially mirroring the other half on the opposite side of the boom. Having to enter the dimensions for only half of a real-world Yagi element that uses telescoping aluminum tubing is much easier this way.

Second, the placement of the elements along the boom starts at 0.0 inches for the reflector. The distance between adjacent elements defined in this particular file is the spacing between the element itself and the element just before it. For example, the spacing between the driven element and the reflector is 72 inches, and the spacing between the first director and the driven element is also 72 inches. The spacing between the second director and the first director is 139 inches.

Fig 11A shows the wire geometry for this Yagi array when it is mounted 720 inches (60 feet) above flat ground and Fig 11B shows the *EZNEC* Wires spreadsheet that describes the coordinates. (Use *EZNEC* model file: **Ch4-520-40W.EZ**.) You can see that the x-axis coordinates for the elements have been automatically moved by the *SCALE* program so that the center of the boom is located directly above the origin. This makes it easier to evaluate the effects of stacking different monoband Yagis on a rotating mast in a "Christmas Tree" arrangement. A typical Christmas Tree stack might include 20, 15 and 10-meter monobanders on a single rotating mast sticking out of the top of the tower.

Fig 12 shows the computed azimuth pattern for this Yagi at 14.175 MHz, at an elevation angle of 15°, the angle where the peak of the forward lobe occurs at this

Table 2

520-40W.YW, using #14 wire from 520-40H.YW
14.000 14.174 14.350 MHz
5 elements,   inches
Spacing   .064
0.000   210.923
72.000   200.941
72.000   199.600
139.000   197.502
191.000   190.536

(A)

(B)

Fig 11—At A, geometry for 5-element Yagi on a 40-foot boom, mounted 720 inches (60 feet) above flat ground, with an overlay of current and the azimuth pattern. At B, *EZNEC* Wires spreadsheet for this antenna. This design uses #14 wire for simplicity.

height above flat ground. The antenna exhibits excellent gain at 13.1 dBi, as well as a clean pattern behind the main lobe. The worst-case front-to-rear ratio at any point from 90° to 270° in azimuth is better than 23 dB. *EZNEC* says the feed-point impedance is 25 − *j* 23 Ω, just the right impedance suited for a simple hairpin or gamma match.

A Monoband 2-Element Cubical Quad

Unlike a Yagi, with its elements existing only in the x-y plane, a quad type of beam is a three-dimensional sort of antenna. A quad loop has height in the z-axis, as well as width and length in the x-y plane. Each individual loop for a monoband quad consists of four wires, joined together at the corners. **Fig 13** shows the coordinates for a 2-element 15-meter quad, consisting of a reflector and a driven element on a 10-foot boom.

You can see that the axis of symmetry, the x-axis, runs down the center of this model, meaning that the origin of this particular x, y and z-coordinate scheme is in the center of the reflector. The (0, 0, 0) origin is placed this way for convenience in assigning corner coordinates for each element. For actual placement of the antenna at a particular height above real ground, the heights of all z-axis coordinates are changed accordingly. *EZNEC* has a convenient built-in function to change the height of all wires at a single stroke.

Fig 14 shows the input *EZNEC* spreadsheet for this quad in free space, clearly showing the symmetrical nature of the corner coordinates. (Use *EZNEC* model file: **Ch4-Quad.EZ**.) This is a good place to emphasize that you should enter the wire coordinates in a logical

Max. Gain = 14.34 dBi   Elevation = 15 deg.

Fig 12—*EZNEC* azimuth-plane pattern at an elevation angle of 15° for #14 wire Yagi described in Fig 11.

Fig 13—Wire geometry for a 2-element cubical quad, with a reflector and driven element. The x-axis is the axis of symmetry for this free-space model.

- *MININEC* type ground
- "Fast" type ground
- Sommerfeld-Norton ground.

Wires

No.	End 1				End 2				Diameter	Segs
	X (ft)	Y (ft)	Z (ft)	Conn	X (ft)	Y (ft)	Z (ft)	Conn	(in)	
1	0	-6.083	-6.083	W4E2	0	6.083	-6.083	W2E1	#12	7
2	0	6.083	-6.083	W1E2	0	6.083	6.083	W3E1	#12	7
3	0	6.083	6.083	W2E2	0	-6.083	6.083	W4E1	#12	7
4	0	-6.083	6.083	W3E2	0	-6.083	-6.083	W1E1	#12	7
5	10	-5.917	-5.917	W8E2	10	5.917	-5.917	W6E1	#12	7
6	10	5.917	-5.917	W5E2	10	5.917	5.917	W7E1	#12	7
7	10	5.917	5.917	W6E2	10	-5.917	5.917	W8E1	#12	7
8	10	-5.917	5.917	W7E2	10	-5.917	-5.917	W5E1	#12	7

Fig 14—*EZNEC* Wires spreadsheet showing the coordinates used for the quad in Fig 13. Note how the x-axis describes the position of an element on the 10-foot boom and also is the axis of symmetry for each element. The values for the z-axis and y-axis vary above and below the axis of symmetry.

sequence. The most obvious example in this particular model is that you should group all the wires associated with a particular element together—for example, the four wires associated with the reflector should be in one place. In Fig 14 you can see that all four wires with an x-coordinate of zero represent the reflector.

It's best to follow a convention in entering wires in a loop structure in a logical fashion. The idea to connect the end point of one wire to the starting point of the next wire. For example, in Fig 13 you can see that the left-hand end of Wire 1 is connected to the bottom of Wire 2, and that the top of Wire 2 connects to the left-hand end of Wire 3. In turn, Wire 3 connects to the top of Wire 4, whose bottom end connects to the right-hand end of Wire 1. The pattern is known as "going around the horn" meaning that the connections proceed smoothly in one direction, in this case in a clockwise direction.

You can see that the entry for the wires making up the elements in the 5-element Yagi in Fig 11B also proceeded in an orderly fashion by starting with the reflector, then the driven element, then director 1, then director 2 and finally director 3. This doesn't mean that you couldn't mix things up, say by specifying the driven element first, followed by director 3, and then the reflector, or whatever. But it's a pretty good bet that doing so in this quasi-random fashion will result in some confusion later on when you revisit a model, or when you let another person see your model.

THE MODELING ENVIRONMENT
The Ground

Above, when considering the 135-foot dipole mounted 50 feet above flat earth, we briefly mentioned the most important environmental item in an antenna model—the ground beneath it. Let's examine some of the options available in the *NEC-2* environment in *EZNEC*:

- Free space
- Perfect ground

The free space environment option is pretty self-explanatory—the antenna model is placed in free space away from the influence of any type of ground. This option is useful when you wish to optimize certain characteristics of a particular antenna design. For example, you might wish to optimize the front-to-rear ratio of a Yagi over an entire amateur band and this might entail many calculation runs. The free-space ground will run the fastest among all the ground options.

Perfect ground is useful as a reference case, especially for vertically polarized antennas over real ground. Antenna evaluations over perfect ground are shown in most classical antenna textbooks, so it is useful to compare models for simple antennas over perfect ground to those textbook cases.

MININEC type ground is useful when modeling vertical wires, or horizontal wires that are higher than 0.2 λ above ground. A *MININEC* type ground will compute faster than either a "Fast" ground or a Sommerfeld-Norton type of ground because it assumes that the ground under the antenna is perfect, while still taking into account the far-field reflections for ground using user-specified values of ground conductivity and dielectric constant. The fact that the ground under the antenna is perfect allows the *NEC-2* user of a *MININEC* type ground to specify wires that touch (but don't go below) the ground surface, something that only users of the advanced *NEC-4* program can do with the more accurate Sommerfeld-Norton type of ground described below. (*NEC-4* is presently not in the public domain and is strictly restricted and licensed by the US government.) The ability to model grounded wires is useful with vertical antennas. The modeler must be wary of the feed-point source impedances reported for either horizontally or vertically polarized wires because of the perfect-ground assumption inherent in a *MININEC*-type ground.

The "fast" type of ground is a hybrid type of ground that makes certain simplifying assumptions that allow it to be used provided that horizontal wires are higher than about 0.1 λ above ground. With today's fast computers the Sommerfeld-Norton model is preferred.

The Sommerfeld-Norton ground (referred to in *EZNEC* as the "high accuracy" ground) is preferable to the other ground types because it has essentially no practical limitations for wire height. It has the disadvantage that it can run about four times slower than a *MININEC* type of ground, but today's fast computers make that almost a non-issue. Again, *NEC-2*-based programs cannot model wires that penetrate into the ground (although there are work-arounds described below).

As mentioned above, for any type of ground other than perfect ground or free space, the user must specify the conductivity and dielectric constant of the soil. *EZNEC*

allows the entry by several user-friendly categories, where σ is conductivity in Siemens/meter and ε is dielectric constant:

- Extremely poor: cities, high buildings ($\sigma = 0.001$, $\varepsilon = 3$)
- Very Poor: cities, industrial ($\sigma = 0.001$, $\varepsilon = 5$)
- Sandy, dry ($\sigma = 0.002$, $\varepsilon = 10$)
- Poor: rocky, mountainous ($\sigma = 0.002$, $\varepsilon = 13$)
- Average: pastoral, heavy clay ($\sigma = 0.005$, $\varepsilon = 13$)
- Pastoral: medium hills and forestation ($\sigma = 0.006$, $\varepsilon = 13$)
- Flat, marshy, densely wooded ($\sigma = 0.0075$, $\varepsilon = 12$)
- Pastoral, rich soil, US Midwest ($\sigma = 0.010$, $\varepsilon = 14$)
- Very Good: pastoral, rich, central US ($\sigma = 0.0303$, $\varepsilon = 20$)
- Fresh water ($\sigma = 0.001$, $\varepsilon = 80$)
- Saltwater ($\sigma = 5$, $\varepsilon = 80$)

Let's use *EZNEC*'s ability to overlay one or more plots together on one graph to compare the response of the vertical ground plane antenna in Fig 9 for two different types of ground: Saltwater and Poor. Open the **Ch4-GP.EZ** file in *EZNEC*. Click the **Ground Descrip** button and then right-click anywhere in the Media window that opens up. Choose first the "Poor: rocky, mountainous" option button, click **OK** and then **FF Plot**. When the elevation plot appears, click the **File** menu at the top of the main window, and then **Save As**. Choose an appropriate name for the trace, perhaps "Poor Gnd.PF."

Go back and select saltwater as your **Ground Descrip** and follow the same procedure to compute the far-field plot for saltwater ground. Now, add the Poor Gnd.PF trace, by clicking menu selection **File**, **Add Trace**. **Fig 15** shows this comparison, which greatly favors the saltwater environment, particularly at low elevation angles. At 5° the ground plane mounted over saltwater has about a 10 dB advantage compared to its landlocked cousin.

You might be wondering what happens if we move the ground-plane antenna down closer to the ground. The lower limit to how far the radials can approach the lossy earth is 0.001 λ or twice the diameter of the radial wire. A distance of 0.001 λ at 1.8 MHz is about 6 inches, while it is 0.4 inches at 30 MHz. While *NEC-2*-based programs cannot model wires that penetrate the ground, radial systems just above the ground with more than about eight radial wires can provide a work-around to simulate a direct-ground connection.

Modeling Environment: Frequency

It's always a good idea to evaluate an antenna over a *range of frequencies*, rather than simply at a single spot frequency. Trends that become quite apparent on a frequency sweep are frequently lost when looking simply at a single frequency. Native *NEC-2* has built-in frequency sweep capabilities, but once again the commercial programs make the process easier to use and understand. You

Fig 15—A comparison of the elevation response for the vertical ground plane in Fig 9 over saltwater and over "poor: rocky, mountainous" soil. Saltwater works wonders for verticals, providing excellent low-angle signals.

Fig 16—Frequency sweep of 5-element Yagi described in Fig 11, showing how the azimuth pattern changes with frequency.

saw in the SWR curve in Fig 2 the result of one such frequency sweep using *EZNEC*. **Fig 16** shows a frequency sweep of the azimuth response for the 5-element Yagi in Fig 11 across the 20-meter band, using steps of 117 kHz so there are four evaluation frequencies. At 14.0 MHz this Yagi's gain is down a small amount compared to the gain at 14.351 MHz but the rearward pattern is noticeably degraded, dropping to a front-to-back ratio of just under 20 dB.

EZNEC can save to a series of output plot files a frequency sweep of elevation (or azimuth) patterns. In essence, this automates the process described above for

saving a plot to disk and then overlaying it on another plot. *EZNEC* can save to a text file for later analysis (or perhaps importation into a spreadsheet) the following parameters, chosen by the user:

- Source data
- Load data
- Pattern data
- Current data
- MicroSmith numeric data
- Pattern analysis summary.

Frequency Scaling

EZNEC has a very useful feature that allows you to create new models *scaled* to a new frequency. You invoke the algorithm used to scale a model from one frequency to another by checking the **Rescale** box after you've clicked the **Frequency** button. *EZNEC* will scale all model dimensions (wire length, height and diameter) except for one specific situation—the wire diameter will stay the same at the new frequency if you originally specified wire size by AWG gauge. For example, #14 copper wire for a half-wave 80-meter dipole will stay #14 copper wire for a 20-meter half-wave dipole. If, however, you specified diameter as a floating point number originally, the diameter will be scaled by the ratio of new to old frequency, along with wire length and height.

Start up *EZNEC* and open up the file **Ch4-520-40W.EZ** for the 5-element 20-meter Yagi on a 40-foot boom. Click the **Frequency** box and then check the **Rescale** check box. Now, type in the frequency of 28.4 MHz and click **OK**. You have quickly and easily created a new 5-element 10-meter Yagi, that is mounted 29.9949 feet high, the exact ratio of 28.4 MHz to 14.1739 MHz, the original design frequency on 20 meters. Click the **FF Plot** button to plot the azimuth pattern for this new Yagi. You will see that it closely duplicates the performance of its 20-meter brother. Click **Src Dat** to see that the source impedance is $25.38 - j\,22.19\ \Omega$, again very close to the source data for the 20-meter version.

REVISITING SOURCE SPECIFICATION

Sensitivity to Source Placement

Earlier, we briefly described how to specify a source on a particular segment using *EZNEC*. The sources for the relatively simple dipole, Yagi and quad models investigated so far have been in the center of an easy-to-visualize wire. The placement for the source on the vertical ground plane was at the bottom of the vertical radiator, an eminently logical place. In the other cases we specified the position of the source at 50% of the distance along a wire, given that the wire being fed had an odd number of segments. Please note that in each case so far, the feed point (source) has been placed at a relatively low-impedance point, where the current changes relatively slowly from segment to segment.

Now we're going to examine some subtler source-placement problems. *NEC-2* is well-known as being very sensitive to source placement. Significant errors can result from a haphazard choice of the source segment and the segments surrounding it.

Let's return to the inverted-V dipole in Fig 5. The first time we evaluated this antenna (**Ch4-Inverted V Dipole.EZ**) we specified a split source in *EZNEC*. This function uses two sources, one on each of the segments immediately adjacent to the junction of the two downward slanting wires.

Another common method to create a source at the junction of two wires that meet at an angle is to separate these two slanted wires by a short distance and bridge that gap with a short straight wire, which is fed at its center. **Fig 17** shows a close-up of this scheme. In Fig 17 the length of the segments surrounding the short middle wire are purposely made equal to the length of the middle wire. The segmentation for the short middle wire is set to one. **Table 3** lists the source impedance and the maximum gain the *EZNEC* computes for three different models:

1. **Ch4-Inverted V Dipole.EZ** (the original model)
2. **Ch4-Inverted V Dipole Triple Segmentation.EZ**
3. **Ch4-Modified Inverted V Dipole.EZ** (as shown in Fig 17, for the middle wire set to be 2 feet long)
4. **Ch4-Mod Inverted V Poor Segmentation.EZ** (where the number of segments on the two slanted wires have been increased to 200)

Fig 17—Model of inverted-V dipole using a short center wire on which the source is placed.

Table 3
135-Foot Inverted-V Dipole at 3.75 MHz

Case	Segments	Source Impedance Ω	Max. Gain dBi
1	82	72.64 + j 128.2	4.82
2	246	73.19 + j 128.9	4.82
3	67	73.06 + j 129.1	4.85
4	401	76.21 + j 135.2	4.67

Case 2 shows the effect of tripling the number of segments in Case 1. This is a check on the segmentation, to see that the results are stable at a lower level compared to a higher level of segmentation (which theoretically is better, although slower in computation). We purposely set up Case 4 so that the lengths of the segments on either side of the single-segment middle wire are significantly different (0.33 feet) compared to the 2-foot length of the middle wire.

The feed-point and gain figures for the first three models are close to each other. But you can see that the figures for the fourth model are beginning to diverge from the first three, with about a 5% overall change in the reactance and resistance compared to the average values, and about a 3% change in the maximum gain. This illustrates that it is best to keep the segments surrounding the source equal or at least close to equal in length. We'll soon examine a figure of merit called the *Average Gain* test, but it bears mentioning here that the average gain test is very close for the first three models and begins to diverge for the fourth model.

Things get more interesting if the source is placed at a high-impedance point on an antenna—for example, in the center of a full-wave dipole—the value computed for the source impedance will be high, and things will be quite sensitive to the segment lengths. We'll repeat the computations for the same inverted-V models, but this time at twice the operating frequency, at 7.5 MHz.

Table 4 summarizes the results. The impedance is high, as expected. Note that the resistance term varies quite a bit for all four models, a range of about 23% around the average value. Interestingly, the poorly segmented model's resistance falls in between the other three. The reactive terms are closer for all four models but still cover a range of 4% around the average value. The maximum gain shows the same tendency to be somewhat lower in the fourth model compared to the first three and thus looks as potentially untrustworthy at 7.5 MHz as it does at 3.75 MHz.

This is, of course, but a small sampling of segmentation schemes, and caution dictates that you shouldn't take these results as being representative of all possibilities. Nevertheless, the lesson to be learned here is that the feed-point (source) impedance can vary significantly at a point where the current is changing rapidly, as it does where a high impedance feed is involved. Another general conclusion that can be drawn from Table 5 is that more segments, particularly if they surround the source segment improperly, is not necessarily better.

Voltage and Current Sources

Before we leave the topic of sources, you should be aware that programs like *EZNEC* and others have the ability to simulate both voltage sources and current sources. Although native *NEC-2* has several source types, voltage sources are the most commonly used by hams. Native *NEC-2* doesn't have a current source, but a current source is nothing more than a voltage source delivering current through a high impedance. Basic network theory says that every Thevenin voltage source has a Norton current source equivalent. Various commercial implementations of *NEC-2* approach the creation of a current source in slightly different fashions. Some use a high value of inductive reactance as a series impedance, while others use a high value of series resistance.

Why would we want to use a current source instead of a voltage source in a model? The general-purpose answer is that models containing a single source at a single feed point can use a voltage source with no problems. Models that employ multiple sources, usually with different amplitudes and different phase shifts, do best with current sources.

For example, *phased arrays* feed RF currents at different amplitudes and phase shifts into two or more elements. The impedances seen at each element may be very different—some impedances might even have negative values of resistance, indicating that power is flowing out of that element into the feed system due to mutual coupling to other elements. Having the ability to specify the amplitude and phase of the current, rather than a feed voltage, at a feed point in a program like *EZNEC* is a valuable tool.

Next, we examine one more important aspect of building a model, setting up loads. After that, we'll look into two tests for the potential accuracy of a model. These tests can help identify source placement, as well as other problems.

LOADS

Many ham antennas, in particular electrically short ones, employ some sort of *loading* to resonate the system. Sometimes loading takes the form of *capacitance hats*, but these can and should be modeled as wires connected to the top of a vertical radiator. A capacitance hat is not the type of loading we'll explore in this section.

Here, the term *loads* refers to discrete inductances, capacitances and resistances that are placed at some point (or points) in an antenna system to achieve certain effects. One fairly common form of a load is a *loading coil* used to resonate an electrically short antenna. Another form of load often seen in ham antennas is a *trap*. *EZNEC* has

Table 4
135-Foot Inverted-V Dipole at 7.5 MHz

Case	Segments	Source Impedance Ω	Max. Gain dBi
1	82	2297 – j 2668	5.67
2	246	1822 – j 2553	5.66
3	67	1960 – j 2583	5.66
4	401	2031 – j 2688	5.48

a special built-in function to evaluate parallel-resonant traps, even at different frequencies beyond their main parallel resonance.

Just for reference, a more subtle type of load is a *distributed* material load. We encountered just such a load in our first model antenna, the 135-foot long flattop dipole—although we didn't identify it specifically as a load at that time. Instead, it was identified as a "wire loss" associated with copper.

The *NEC-2* core program has the capability of simulating a number of built-in loads, including distributed material and discrete loads. *EZNEC* implements the following discrete loads:

- Series R $\pm$ *j* X loads.
- Series R-L-C loads, specified in Ω of resistance, μH of inductance and pF of capacitance.
- Parallel R-L-C loads, specified in Ω of resistance, μH of inductance and pF of capacitance.
- Trap loads, specified in Ω of resistance in series with μH of inductance, shunted by pF of capacitance, at a specific frequency.
- Laplace loads, specified as mathematical Laplace coefficients (sometimes used in older modeling programs and left in *EZNEC* for backwards compatibility).

It is important to recognize that the discrete loads in an antenna modeling program *do not radiate* and they have zero size. The *NEC-2* discrete loads are described by L. B. Cebik in his antenna modeling course as being *mathematical loads*. The fact that *NEC-2* loads do not radiate means that the popular mobile antennas that use helical loading coils wound over a length of fiberglass whip cannot be modeled with *NEC-2*, because such coils do radiate.

Let's say that we want to put a air-wound loading coil with an unloaded Q of 400 at the center of a 40-foot long, 50-foot high, flattop dipole so that it is resonant at 7.1 MHz. The schematic of this antenna is shown in **Fig 18**. Examine the modeling file **Ch4-Loaded Dipole.EZ** to see how a discrete series RL load is used to resonate this short dipole at 7.1 MHz, with a feed-point (source) impedance of 25.3 Ω. This requires a series resistance of 1.854 Ω and an inductive reactance of +741.5 Ω. Note that we again used a single wire to model this antenna, and that we placed the load at a point 50% along the length of the wire.

This load represents a 16.62 μH coil with an unloaded Q of 741.5/1.854 = 400, just what we wanted. Let's assume for now that we use a perfect transformer to transform the 25.3-Ω source impedance to 50 Ω. If we now attempt to run a frequency sweep over the whole 40-meter band from 7.0 to 7.3 MHz, the load reactance and resistance will not change, since we specified fixed values for reactance and resistance. Hence, the source impedance will be correct only at the frequency where the reactance and resistance are specified, since the reactance changes with frequency.

Fig 18—Schematic diagram of a 40-foot long flattop dipole with a loading coil placed at the center. This coil has an unloaded Q of 400 at 7.1 MHz.

Fig 19—SWR graph of the loaded 40-foot long flattop dipole shown in Fig 18.

So let's use another load capability and substitute a 16.62 μH coil with a series 1.854-Ω resistance at 7.1 MHz. We'll let *EZNEC* take care of the details of computing both the reactance and the changing series resistance at various frequencies. The degree that both reactance and series loss resistance of the coil change with frequency may be viewed using the **Load Dat** button from the main *EZNEC* window.

Fig 19 shows the computed SWR curve for a 25.3-Ω **Alt SWR Z0** reference resistance. The 2:1 SWR bandwidth is about 120 kHz. As could be expected, the antenna has a rather narrow bandwidth because it is electrically short.

ACCURACY TESTS

There are two tests that can help identify accuracy problems in a model:

- The Convergence test.
- The Average Gain test.

Convergence Test

The idea behind the *Convergence* test is simple: If you increase the segmentation in a particular model and the results changes more than you'd like, then you increase the segmentation until the computations converge

to a level that is suitable to you. This process has the potential for being subjective, but simple antenna models do converge quickly. In this section, we'll review several more of the antennas discussed previously to see how they converge.

Let's go back to the simple dipole in Fig 3. The original segmentation was 11 segments, but we'll start with a very low value of segmentation of three, well below the minimum recommended level. **Table 5** shows how the source impedance and gain change with increase in segmentation at 3.75 MHz. For this simple antenna, the gain levels off at 6.50 dBi by the time the segmentation has reached 11 segments. Going to ten times the minimum-recommended level (to 111 segments) results in an increase of only 0.01 dBi in the gain.

Arguably, the impedance has also stabilized by the time we reach a segmentation level of 11 segments, although purists may opt for 23 segments. The tradeoff is a slowdown in computational speed.

Let's see how the 5-element Yagi model converges with changes in segmentation level. **Table 6** shows how the source impedance, gain, 180° front-to-back ratio and worst-case front-to-rear ratio change with segmentation density. By the time the segmentation has reached 11 segments per wire, the impedance and gain have stabilized quite nicely, as has the F/R. The 180° F/B is still increasing with segmentation level until about 25 segments, but a relatively small shift in frequency will change the maximum F/B level greatly. For example, with 11 segments per wire, shifting the frequency to 14.1 MHz—a shift of only 0.5%— will change the maximum 180° F/B from almost 50 dB down to 27 dB. For this reason the F/R is considered a more reliable indicator of the adequacy of the segmentation level than is F/B.

Average Gain Test

The theory behind the *Average Gain* test is a little more involved. Basically, if you remove all intentional losses in a model, and if you place the antenna either in free space or over perfect ground, then all the power fed to the antenna should be radiated by it. Internally, the program runs a full 3-D analysis, adding up the power in all directions and then dividing that sum by the total power fed to the antenna. Since *NEC-2* is very sensitive about source placement, as mentioned before, the Average Gain test is a good indicator that something is wrong with the specification of the source.

Various commercial versions of *NEC-2* handle the Average Gain test in different ways. *EZNEC* requires the operator to turn off all distributed losses in wires or set to zero any discrete resistive losses in loads. Next you set the ground environment to free space (or perfect ground) and request a 3-D pattern plot. *EZNEC* will then report the average gain, which will be 1.000 if the model has no problems. The average gain can be lower or higher than 1.000, but if it falls within the range 0.95 to 1.05 it

Table 5
135-Foot Flattop Dipole at 3.75 MHz

Segments	Source Impedance Ω	Max. Gain dBi
3	85.9 + j 128.0	6.34
5	86.3 + j 128.3	6.45
7	86.8 + j 128.8	6.48
11	87.9 + j 129.5	6.50
23	88.5 + j 130.3	6.51
45	89.0 + j 130.8	6.51
101	89.4 + j 131.1	6.51

Table 6
5-element Wire Yagi at 14.1739 MHz

Segments	Source Impedance Ω	Max. Gain dBi	180° F/B dB	F/R dB
3	28.5 − j 30.6	12.79	23.2	22.4
5	26.3 − j 25.6	13.02	30.5	23.1
7	25.6 − j 24.0	13.07	34.8	23.1
11	25.1 − j 22.9	13.09	39.9	23.1
25	24.9 − j 22.0	13.10	43.7	23.1
99	24.7 − j 21.5	13.10	44.2	23.1

is usually considered adequate.

As L. B. Cebik, W4RNL, stated in his ARRL Certification and Continuing Education Course on antenna modeling: "Like the convergence test, the average gain test is a necessary but not a sufficient condition of model reliability." Pass both tests, however, and you can be pretty well sure that your model represents reality. Pass only one test, and you have reason to worry about how well your model represents reality.

Once again, open the model file **Ch4-Mod Inverted V Poor Segmentation.EZ** and set **Wire Loss** to zero, **Ground Type** to Free Space and **Plot Type** to 3-Dimensional. Click on the **FF Plot** button. *EZNEC* will report that the Average Gain is 0.955 = −0.2 dB. This is very close to the lower limit of 0.95 considered valid for excellent accuracy. This is a direct result of forcing the segment lengths adjacent to the source segment to be considerably shorter than the source segment's length. The gain reported using this test would be approximately −0.2 dB from what it should be—just what Table 4 alludes to also.

Now, let's revisit the basic model **Ch4-Inverted V Dipole.EZ** and look at Case 2 in Table 4. Case 2 amounts to a Convergence test for the basic inverted-V model. Since the impedance and gain changes were small comparing the basic model to the one using three times the number of segments, the model passed the Convergence test. The Average Gain test for the basic model yields a value of 0.991, well within the limits for good accuracy. This model has thus passed both tests and can be considered accurate.

Running the Average Gain test for the 5-element Yagi (using 11 segments per wire and whose convergence we examined in Table 6) yields a value of 0.996, again well within the bounds indicating a good model. And the simple flattop dipole with 11 segments at 3.75 MHz yields an Average Gain result of 0.997, again indicating a very accurate model.

OTHER POSSIBLE MODEL LIMITATIONS

Programs based on the *NEC-2* core computational code have several well-documented limitations that you should know about. Some limitations have been removed in the restricted-access *NEC-4* core (which is not generally available to users), but other limitations still exist, even in *NEC-4*.

Closely Spaced Wires

If wires are spaced too close to each other, the *NEC-2* core can run into problems. If the segments are not carefully aligned, there also can be problems with accuracy. The worst-case situation is where two wires are so close together that their volumes actually merge into each other. This can happen where wires are thick, parallel to each other and close together. You should keep parallel wires separated by at least several diameters.

For example, #14 wire is 0.064 inches in diameter. The rule then is to keep parallel #14 wires separated by more than $2 \times 0.064 = 0.128$ inches. And you should run the Convergence test to assure yourself that the solution is indeed converging when you have closely spaced wires, especially if the two wires have different diameters. To model antennas containing closely spaced wires, very often you will need many more segments than usual and you must also carefully ensure that the segments line up with each other.

Things can get a little more tricky when wires cross over or under each other, simply because such crossings are sometimes difficult to visualize. Again, the rule is to keep crossing wires separated by more than two diameters from each other. And if you intend to join two wires together, make sure you do so at the ends of the two wires, using identical end coordinates. When any or all of these rules are violated, the Convergence and Average Gain tests will usually warn you of potential inaccuracies.

Parallel-Wire Transmission Lines and LPDAs

A common example of problems with closely spaced wires is when someone attempts to model a parallel-wire transmission line. *NEC-2*-based programs usually do not work as well in such situations as do *MININEC*-based programs. The problems are compounded if the diameters are different for the two wires simulating a parallel-wire transmission line. In *NEC-2* programs, it is usually better to use the built-in "perfect transmission line" function than to try to model closely spaced parallel wires as a transmission line.

For example, a Log Periodic Dipole Array (LPDA) is composed of a series of elements fed using a transmission line that reverses the phase 180° at each element. In other words, the elements are connected to a transmission line that reverses connections left-to-right at each element. It is cumbersome to do so, but you could model such a transmission line using separate wires in *EZNEC*, but it is a potentially confusing and a definitely painstaking process. Further, the accuracy of the resulting model is usually suspect, as shown by the Average Gain test.

It is far easier to use the **Trans Lines** function from the *EZNEC* main window to accurately model an LPDA. See **Fig 20**, which shows the **Trans Lines** window for the **9302A.EZ** 16-element LPDA. There are 15 transmission lines connecting the 16 elements, placed at the 50% point on each element, with a 200-Ω characteristic impedance and with Reversed connections.

Fat Wires Connected to Skinny Wires

Another inherent limitation in the *NEC-2* computational core shows up when modeling several popular ham-radio antennas: many Yagis and some quads.

Tapered Elements

As mentioned before, many Yagis are built using telescoping aluminum tubing. This technique saves weight and makes for a more flexible and usually stronger element, one that can survive wind and ice loading better than a "monotaper" element design. Many vertical antennas are also constructed using telescoping aluminum tubing.

Unfortunately, native *NEC-2* doesn't model accurately such *tapered elements*, as they are commonly called. There is, however, a sophisticated and accurate work-around for such elements, called the *Leeson corrections*. The Leeson corrections, derived by Dave Leeson, W6NL, from pioneering work by Schelkunoff at Bell Labs, compute the diameter and length of an element that is electrically equivalent to a tapered element. This monotaper element is much easier to use in a pro-

Fig 20—Transmission-line window for the 9302A.EZ 16-element LPDA. Note that the transmission lines going between elements are "reversed," meaning that they are 180° out-of-phase at each element, a requirement for properly feeding an LPDA.

Table 7
5-element Yagi at 14.1739 MHz with Telescoping Aluminum Elements

Freq. MHz	With Leeson Corrections Source Impedance Ω	Gain dBi	F/R dB	Without Leeson Corrections Source Impedance Ω	Gain dBi	F/R dB
14.0	23.2 – j 26.5	14.82	23.3	22.4 – j 12.7	14.92	23.1
14.1	22.7 – j 20.5	14.87	22.8	18.6 – j 12.5	14.70	21.6
14.2	22.8 – j 14.8	14.87	22.7	6.6 – j 4.6	14.01	16.2
14.3	22.5 – j 11.9	14.76	21.5	1.9 + j 10.6	10.61	3.1
14.4	14.5 – j 10.5	14.45	19.9	1.6 + j 23.7	11.15	−11.4

gram like *NEC-2*. See Chapter 2, Antenna Fundamentals, for more information on the Leeson corrections.

EZNEC and other *NEC-2* programs can automatically invoke the Leeson corrections, providing that some basic conditions are met—and happily, these conditions are true for the telescoping aluminum-tubing elements commonly used as Yagi elements. *EZNEC* gives you the ability to disable or enable Leeson corrections, under the **Option** menu, under **Stepped Diameter Correction**, *EZNEC*'s name for the Leeson corrections. Open the modeling file **520-40H.EZ**, which contains tapered aluminum tubing elements and compare the results using and without using the Leeson corrections.

Table 7 lists the differences over the 20-meter band, with the 5-element Yagi at a height of 70 feet above flat ground. You can see that the non-Leeson corrected figures are very different from the corrected ones. At 14.3 MHz, the pattern for the non-corrected Yagi has degenerated to a F/R of 3.1 db, while at 14.4 MHz, just outside the top of the Amateur band, the pattern for the non-corrected antenna actually has reversed. Even at 14.2 MHz, the non-corrected antenna shows a low source impedance, while the corrected version exhibits smooth variations in gain, F/R and impedance across the whole band, just as the actual antenna exhibits.

Some Quads

Some types of cubical quads are made using a combination of aluminum tubing and wire elements, particularly in Europe where the "Swiss" quad has a wide following. Again, *NEC-2*-based programs don't handle such tubing/wire elements well. It is best to avoid modeling this type of antenna, although there are some ways to attempt to get around the limitations, ways that are beyond the scope of this chapter.

NEAR-FIELD OUTPUTS

FCC regulations set limits on the maximum permissible exposure (MPE) allowed from the operation of radio transmitters. These limits are expressed in terms of the electric (V/m) and magnetic fields (A/m) close to an antenna. *NEC-2*-based programs can compute the electric and magnetic *near fields* and the FCC accepts such computations to demonstrate that an installation meets their regulatory requirements. See Chapter 1, Safety, in this book.

Table 8
E- and H-Field Intensities for 1500 W into 5-Element Yagi at 70 Feet on 14.2 MHz

Height Feet	H-Field (A/m)	E-Field (V/m)
0	0.04	4.1
10	0.03	13.8
20	0.04	20.6
30	0.06	22.6
40	0.08	25.8
50	0.10	33.8
60	0.12	41.5
70	0.12	44.3

We'll continue to use the 5-element Yagi at 70 feet to demonstrate a near-field computation. Open **Ch4-520-40H.EZ** in *EZNEC* and choose **Setups** and then **Near Field** from the menu at the top of the main window. Let's calculate the E-field and H-field intensity for a power level of 1500 W (chosen using the **Options**, **Power Level** choices from the main menu) in the main beam at a fixed distance, say 50 feet, from the tower base. We'll do this at various heights, using 10-foot increments of height, in order to see the lobe structure of the Yagi at 70 feet height.

Table 8 summarizes the total H- and E-field intensities as a function of height. As you might expect, the fields are strongest directly in line with the antenna at a height of 70 feet. At ground level, the total fields are well within the FCC limits for rf exposure for both fields. In fact, the fields are within the FCC limits if someone were to stand at the tower base, directly under the antenna.

ANTENNA MODELING SUMMARY

This section on antenna modeling is by necessity only a brief introduction to the science of antenna modeling. The subject is partly art as well as science because there are usually several ways of creating a model for a particular antenna or antennas.

Indeed, the presence of other wires surrounding a particular antenna can affect the performance of that antenna. Finally, there are the practical aspects of putting a actual antenna up in the real world. We'll explore this next.

Practical Aspects, Designing Your Antenna System

The most important time spent in putting together an antenna system is the time spent in planning. In Chapter 3, The Effects of Ground, we outlined the steps needed to evaluate how your local terrain can affect HF communications. There we emphasized that you need to compare the patterns resulting from your own terrain to the statistically relevant elevation angles needed for coverage of various geographic areas. (The elevation-angle statistics were developed in Chapter 23, Radio Wave Propagation and are located on the CD-ROM included with this book, as is the terrain-assessment program *HFTA*.)

The implicit assumptions in Chapter 3 are (1) that you know where you want to talk to, and (2) that you'd like the most effective system possible. At the start of such a theoretical analysis, cost is no object. Practical matters, like cost or the desires of your spouse, can come later! After all, you're just checking out all the possibilities. If nothing else, you will use the methodology in Chapter 3 to evaluate any property you are considering buying so that you can build your "dream station."

Next, in the first part of this chapter we described modeling tools used to evaluate different types of antennas. These modeling tools can help you evaluate what type of antenna might be suitable to your own particular style of operating. Do you want a Yagi with a lot of rejection of received signals from the rear? Let's say that terrain analysis shows that you need an antenna at least 50 feet high. Do you really need a steel tower, or would a simple dipole in the trees serve your communication needs just fine? How about a vertical in your backyard? Would that be inconspicuous enough to suit your neighbors and your own family, yet still get you on the air?

In short, using the techniques and tools we've presented in Chapters 3, 23 and here in Chapter 4, you can scientifically plan an antenna *system* that will be best suited for your own particular conditions. Now, however, you have to get practical. Thinking through and planning the installation can save a lot of time, money and frustration. While no one can tell you the exact steps you should take in developing your own master plan, this section, prepared originally by Chuck Hutchinson, K8CH, should help you with some ideas.

WHAT DO YOU REALLY WANT?

Begin planning by spelling out your communications *desires*. What bands are you interested in? Who (or where) do you want to talk to? When do you operate? How much time and money are you willing to spend on an antenna system? What physical limitations affect your master plan?

From the answers to the above questions, begin to formulate *goals*—short, intermediate and long range. Be realistic about those goals. Remember that there are three station effectiveness factors that are under your control. These are: operator skill, equipment in the shack, and the antenna system. There is no substitute for developing operating skills. Some tradeoffs are possible between shack equipment and antennas. For example, a high-power amplifier can compensate for a less than optimum antenna. By contrast, a better antenna has advantages for receiving as well as for transmitting.

Consider your *limitations*. Are there regulatory restrictions on antennas in your community? Are there any deed restrictions or covenants that apply to your property? Do other factors (finances, family considerations, other interests, and so forth) limit the type or height of antennas that you can erect? All of these factors must be investigated because they play a major role determining the type of antennas you erect.

Chances are that you won't be able to immediately do all you desire. Think about how you can budget your resources over a period of time. Your resources are your money, your time available to work, materials you may have on hand, friends that are willing to help, etc. One way to budget is to concentrate your initial efforts on a given band or two. If your major interest is in chasing DX, you might want to start with a very good antenna for the 14-MHz band. A simple multiband antenna could initially serve for other frequencies. Later you can add better antennas for those other bands.

SITE PLANNING

A map of your property or proposed antenna site can be of great help as you begin to consider alternative antennas. You'll need to know the size and location of buildings, trees and other major objects in the area. Be sure to note compass directions on your map. Graph or quadrille paper (or a simple CAD program) can be very useful for this purpose. See **Fig 21** for an example. It's a good idea to make a few photocopies of your *site map* so you can mark on the copies as you work on your plans.

Use your map to plan antenna layouts and locations of any supporting towers or masts. If your plan calls for more than one tower or mast, think about using them as supports for wire antennas. As you work on a layout, be sure to think in three dimensions even though the map shows only two.

Be sensitive to your neighbors. A 70-foot guyed tower in the front yard of a house in a residential neighborhood is not a good idea (and probably won't comply with local ordinances!). You probably will want to locate that tower in the back yard.

ANALYSIS

Use the information earlier in this chapter and in Chapters 3 and 23 to analyze antenna patterns in both

Fig 21—A site map such this one is a useful tool for planning your antenna installation.

horizontal and vertical planes towards geographic areas of interest. If you want to work DX, you'll want antennas that radiate energy at low as well as intermediate angles. An antenna pattern is greatly affected by the presence of ground and by the local topography of the ground. Therefore, be sure to consider what effect ground will have on the antenna pattern at the height you are considering. A 70-foot high antenna is approximately $^1/_2$, 1, $1^1/_2$ and 2 wavelengths (λ) high on 7, 14, 21 and 28 MHz respectively. Those heights are useful for long-distance communications. The same 70-foot height represents only $\lambda/4$ at 3.5 MHz, however. Most of the radiated energy from a dipole at that height would be concentrated straight up. This condition is not great for long-distance communication, but can still be useful for some DX work and excellent for short-range communications.

Lower heights can be useful for communications. However, it is generally true that "the higher, the better" as far as communications effectiveness is concerned. This general rule of thumb, of course, should be tempered by an exact analysis of your local terrain. Being located at the top of a steep hill can mean that you can use lower tower heights to achieve good coverage.

There may be cases where it is not possible to install low-frequency dipoles at $\lambda/4$ or more above the ground.

A vertical antenna with many radials is a good choice for long-distance communications. You may want to install both a dipole and a vertical for the 3.5- or 7-MHz bands. On the 1.8-MHz band, unless extremely tall supports are available, a vertical antenna is likely to be the most useful for DXing. You can then choose the antenna that performs best for a given set of conditions. A low dipole will generally work better for shorter-range communications, while the vertical will generally be the better performer over longer distances.

Consider the azimuthal pattern of fixed antennas. You'll want to orient any fixed antennas to favor the directions of greatest interest to you.

BUILDING THE SYSTEM

When the planning is completed, it is time to begin construction of the antenna system. Chances are that you can divide that construction into a series of *phases* or steps. Say, for example, that you have lots of room and that your long-range plan calls for a pair of towers, one 100-feet high, and the other 70-feet high, to support monoband Yagi antennas. The towers will also support a horizontal 3.5-MHz dipole, for DX work. On your map you've located them so the 80-meter dipole will be broadside to Europe. You decide to build the 70-foot tower with a "triband" beam and 80- and 40-meter inverted-V dipoles to begin the project.

In your master plan you design the guys, anchors and all hardware for the 70-foot tower to support the load of stacked 4-element 10- and 15-meter monobanders Yagis. So you make sure you buy a heavy-duty rotator and the stout mast needed for the monoband antennas later. Thus you avoid having to buy, and then sell, a medium-duty rotator and lighter weight tower equipment later on when you upgrade the station. You could have saved money in the long run by putting up a monoband beam for your favorite band, but you decided that for now it is more important to have a beam on 14, 21 and 28 MHz, so you choose a commercial triband Yagi.

The second step of your plan calls for installing the second tower and stacking a 2-element 40-meter and a 4-element 20-meter monoband Yagi on it. You also plan to replace the tribander on the 70-foot tower with stacked 4-element 10- and 15-meter monoband Yagis. Although this is still a "dream system" you can now apply some of the modeling techniques discussed earlier in this chapter to determine the overall system performance.

Modeling Interactions at Your Dream Station

In this analysis we're going to assume that you have sufficient real estate to separate the 70- and 100-foot towers by 150 feet so that you can easily support an 80-meter dipole between them. We'll also assume that you want the 80-meter dipole to have its maximum response at a heading of 45° into Europe from your location in Newington, Connecticut. The dipole will also have a lobe

Max. Gain = 14.04 dBi   Freq. = 21.225 MHz

Fig 22—Layout for two-tower antenna system, at 70 and 100 feet high and 150 feet apart. The 70-foot tower has a 4-element 10-meter Yagi at 80 feet on a 10-foot rotating mast and a 4-element 15-meter Yagi at 70 feet. An 80-meter dipole goes from the 70-foot tower to the 100-foot tower, which holds a 2-element 40-meter Yagi at 110 feet and a 4-element 20-meter Yagi at 100 feet. In this figure all the rotatable Yagis are facing the direction of Europe and the currents on the 15-meter Yagi are shown. Note the significant amount of current re-radiated by the nearby 80-meter dipole.

Fig 23—An overlay of azimuth patterns. The solid line is the radiation pattern for the 15-meter Yagi all by itself. The dashed line is the pattern for the 15-meter Yagi, as affected by all the other antennas. The dotted line is the pattern for the 15-meter Yagi when it is pointed toward the Caribbean, with the Yagis on the 100-foot tower pointed toward the 70-foot tower. The peak response of the 15-meter Yagi has dropped by about 1.5 dB.

facing 225° towards the USA and New Zealand, making it a good antenna for both domestic contacts and DX work.

Let's examine the interactions that occur between the rotatable Yagis for 10, 15, 20 and 40 meters. See **Fig 22**, which purposely exaggerates the magnitude of the currents on the 4-element 15-meter Yagi mounted at 70 feet. Here, both sets of Yagis have been rotated so that they are pointing into Europe. There is a small amount of current radiated onto the 10-meter antenna but virtually no current is radiated onto the 40- and 20-meter Yagis. This is good.

However, significant current is radiated onto, and then re-radiated, by the 80-meter dipole. This undesired current affects the radiation pattern of the 15-meter antenna, as shown in **Fig 23**, which overlays the pattern of the 4-element 15-meter Yagi by itself with that of the Yagi interacting with the other antennas. You can see "ripples" in the azimuthal response of the 15-meter Yagi due to the effects of the 80-meter dipole's re-radiation. The magnitude of the ripples is about 1 dB at worst, so they don't seriously affect the forward pattern (into Europe), but the rearward lobes are degraded somewhat, to just below 20 dB.

Fig 23 also shows the worst-case situation for the 15-meter Yagi. Here, the 15- and 10-meter stack has been turned clockwise 90°, facing the Caribbean, while the 40-

Fig 24—The layout and 15-meter currents when the Yagis on the 100-foot tower are pointed toward the 70-foot tower. The 15-meter Yagi has been rotated to face the direction of the 100-foot tower (toward the Caribbean).

and 20-meter Yagis on the 100-foot tower have been turned counter-clockwise 90° (in the direction of Japan) to face the 70-foot tower holding the 10/15-meter Yagis. You can see the layout and the currents in **Fig 24**. Now the 40- and 20-meter Yagis re-radiate some 15-meter

Max. Gain = 14.21 dBi   Freq. = 28.4 MHz

Fig 25—The radiation patterns for the 10-meter Yagi. The solid line is the 10-meter Yagi by itself. The dashed line is for the same Yagi, with all other antenna interactions. The dotted line shows the worst-case pattern, with the stacked Yagis on the 100-foot tower facing the 70-foot tower and the 10-meter Yagi pointed toward the Caribbean. Again, the peak response of the 10-meter Yagi has dropped about 1.5 dB in the worst-case situation.

energy and reduce the maximum gain by about 1.5 dB. Note that in this direction the 80-meter dipole no longer has 15-meter energy radiated onto it by the 15-meter Yagi.

The shape of the patterns will change depending on whether you specify "current" or "voltage" sources in the models for the other antennas, since this effectively opens up or shorts the feed points at the other antennas so far as 15-meter energy is concerned. In practice, this means that the interaction between antennas will vary somewhat depending on the length of the feed lines going to each antenna and whether each feed line is open-circuited or short-circuited when it is not in use.

You can now see that interactions between various antennas pointing in different directions can be significant in a real-world antenna system. In general, higher-frequency antennas are affected by re-radiation from lower-frequency antennas, rather than the other way around. Thus the presence of a 10- or 15-meter stack does not affect the 20-meter Yagi at all.

Modeling can also help determine the minimum stacking distance required between monoband Yagis on the same rotating mast. In this case, stacking the 10- and 15-meter monobanders 10 feet apart holds down interaction between them so that the pattern and gain of the

10-meter Yagi is not impacted adversely. **Fig 25** demonstrates this in the European direction, where the patterns for the 10-meter beam by itself looks very clean compared to the same Yagi separated by 10 feet from the 15-meter Yagi below it. The worst-case situation is pointing towards the Caribbean, when the 40- and 20-meter stack is facing the 70-foot tower. This drops the 10-meter gain down about 1.5 dB from maximum, indicating significant interaction is occurring.

In this situation you might find it best to place the 70-foot tower in the direction closest to the Caribbean if this direction is very important to you. Doing so will, however, cause the pattern in the direction of the Far East to be affected on 10 and 15 meters. You have the modeling tools necessary to evaluate various configurations to achieve whatever is most important to you.

COMPROMISES

Because of limitations, most amateurs are never able to build their dream antenna system. This means that some compromises must be made. Do not, under any circumstances, compromise the *safety* of an antenna installation. Follow the manufacturer's recommendations for tower assembly, installation and accessories. Make sure that all hardware is being used within its ratings.

Guyed towers are frequently used by radio amateurs because they cost less than more complicated unguyed or freestanding towers with similar ratings. Guyed towers are fine for those who can climb, or those with a friend who is willing to climb. But you may want to consider an antenna tower that folds over, or one that cranks up (and down). Some towers crank up (and down) and fold over too. See **Fig 26**. That makes for convenient access to antennas for adjustments and maintenance without climbing. Crank-up towers also offer another advantage. They allow antennas to be lowered during periods of no operation, such as for aesthetic reasons or during periods of high winds.

A well-designed monoband Yagi should outperform a multiband Yagi. In a monoband design the best adjustments can be made for gain, front-to-rear ratio (F/R) and matching, *but only for a single band*. In a multiband design, there are always tradeoffs in these properties for the ability to operate on more than one band. Nevertheless, a multiband antenna has many advantages over two or more single band antennas. A multiband antenna requires less heavy-duty hardware, requires only one feed line, takes up less space and it costs less.

Apartment dwellers face much greater limitations in their choice of antennas. For most, the possibility of a tower is only a dream. (One enterprising ham made arrangements to purchase a top-floor condominium from a developer. The arrangements were made before construction began, and the plans were altered to include a roof-top tower installation.) For apartment and condominium dwellers, the situation is still far from hopeless. A later section presents ideas for consideration.

Fig 26—Alternatives to a guyed tower are shown here. At A, the crank-up tower permits working on antennas at reduced height. It also allows antennas to be lowered during periods of no operation. Motor-driven versions are available. The fold-over tower at B and the combination at C permit working on antennas at ground level.

EXAMPLES

You can follow the procedure previously outlined to put together modest or very large antenna systems. What might a ham put together for antennas when he or she wants to try a little of everything, and has a modest budget? Let's suppose that the goals are (1) low cost, (2) no tower, (3) coverage of all HF bands and the repeater portion of one VHF band, and (4) the possibility of working some DX.

After studying the pages of this book, the station owner decides to first put up a 135-foot center-fed antenna. High trees in the back yard will serve as supports to about 50 feet. This antenna will cover all the HF bands by using a balanced feeder and an antenna tuner. It should be good for DX contacts on 10 MHz and above, and will probably work okay for DX contacts on the lower bands. However, her plan calls for a vertical for 3.5 and 7 MHz to enhance the DX possibilities on those bands. For VHF, a chimney-mounted vertical is included.

ANOTHER EXAMPLE

A licensed couple has bigger ambitions. Goals for their station are (1) a good setup for DX on 14, 21 and 28 MHz, (2) moderate cost, (3) one tower, (4) ability to work some DX on 1.8, 3.5 and 7 MHz, and (5) no need to cover the CW portion of the bands.

After considering the options, the couple decides to install a 65-foot guyed tower. A large commercial triband Yagi will be mounted on top of the tower. The center of a trap dipole tuned for the phone portion of the 3.5- and 7-MHz bands will be supported by a wooden yardarm installed at the 60-foot level of the tower, with ends drooping down to form an inverted V. An inverted L for 1.8 MHz starts near ground level and goes up to a similar yardarm on the opposite side of the tower. The horizontal portion of the inverted L runs away from the tower at right angles to the trap dipole. Later, the husband will experiment with sloping antennas for 3.5 MHz. If those experiments are not successful, a $\lambda/4$ vertical will be used on that band.

Apartment Possibilities

A complete and accurate assessment of antenna types, antenna placement and feed-line placement is very important for the apartment dweller. Among the many possibilities for types are balcony antennas, *invisible* ones (made of fine wire), vertical antennas disguised as flag poles or as masts with a TV antenna on top, and indoor antennas.

A number of amateurs have been successful negotiating with the apartment owner or manager for permission to install a short mast on the roof of the building. Coaxial lines and rotator control cables might be routed through conduit troughs or through ductwork. If you live in one of the upper stories of the building, routing the cables over the edge of the roof and in through a window might be the way to go. There is a story about one amateur who owns a triband beam mounted on a 10-foot mast. But even with such a short mast, he is the envy of all his amateur friends because of his superb antenna height. His mast stands on top of a 22-story apartment building.

Usually the challenge is to find ways to install antennas that are unobtrusive. That means searching out antenna locations such as balconies, eaves, nearby trees, etc. For example, a simple but effective balcony antenna is a dangling vertical. Attach a thin wire to the tip of a mobile whip or a length of metal rod or tubing. Then mount the rigid part of the antenna horizontally on the balcony rail, dangling the wire over the edge. The antenna is operated against the balcony railing or other metallic framework. A matching network is usually required at the antenna feed point. Metal in the building will likely give a directivity effect, but this may be of little conse-quence and perhaps even an advantage. The antenna may be removed and stored when not in use.

Frequently, the task of finding an inconspicuous route for a feed line is more difficult than the antenna installation itself. When Al Francisco, K7NHV, lived in an apartment, he used a tree-mounted vertical antenna. The coax feeder exited his apartment through a window and ran down the wall to the ground. Al buried the section of line that went from under the window to a nearby tree. At the tree, a section of enameled wire was connected to the coax center conductor. He ran the wire up the side of the tree away from foot traffic. A few short radials completed the installation. The antenna worked fine, and was never noticed by the neighbors.

See Chapters 6, Low-Frequency Antennas, and Chapter 15, Portable Antennas, for ideas about low-frequency and portable antennas that might fit into your available space. Your options are limited as much by your imagination and ingenuity as by your pocketbook. Another option for apartment dwellers is to operate away from home. Some hams concentrate on mobile operation as an alternative to a fixed station. It is possible to make a lot of contacts on HF mobile. Some have worked DXCC that way.

Suppose that you like VHF contests. Because of other activities, you are not particularly interested in operating VHF outside the contests. Why not take your equipment and antennas to a hilltop for the contests? Many hams combine a love for camping or hiking with their interest in radio.

Antennas for Limited Space

It is not always practical to erect full-size antennas for the HF bands. Those who live in apartment buildings may be restricted to the use of minuscule radiators because of house rules, or simply because the required space for full-size antennas is unavailable. Other amateurs may desire small antennas for aesthetic reasons, perhaps to keep peace with neighbors who do not share their enthusiasm about high towers and big antennas. There are many reasons why some amateurs prefer to use physically-shortened antennas. This section discusses proven designs and various ways of building and using them effectively. You will find that modeling antennas by computer, even compromised "stealth antennas," can help you determine the most practical system possible for your particular circumstances—before you go through the effort of stringing up wires.

Few compromise antennas are capable of delivering the performance you can expect from the full-size variety. But the patient and skillful operator can often do as well as some who are equipped with high power and full-size antennas. Someone with a reduced-size antenna may not be able to "bore a hole" in the bands as often and with the commanding dispatch enjoyed by those who are better equipped, but DX can be worked successfully when band conditions are suitable.

INVISIBLE ANTENNAS

We amateurs don't regard our antennas as eyesores; in fact, we almost always regard them as works of art! But there are occasions when having an outdoor or visible antenna can present problems.

When we are confronted with restrictions—self-imposed or otherwise—we can take advantage of a number of options toward getting on the air and radiating at least a moderately effective signal. In this context, a poor antenna is certainly better than no antenna at all! This section describes a number of techniques that enable us to use indoor antennas or "invisible" antennas outdoors.

Fig 27—The clothesline antenna is more than it appears to be.

Fig 28—The "invisible" end-fed antenna.

Many of these systems will yield good-to-excellent results for local and DX contacts, depending on band conditions at any given time. *The most important consideration is that of not erecting any antenna that can present a hazard (physical or electrical) to humans, animals and buildings. Safety first!*

Clothesline Antenna

Clotheslines are sometimes attached to pulleys (**Fig 27**) so that the user can load the line and retrieve the laundry from a back porch. Laundry lines of this variety are accepted parts of the neighborhood "scenery," and can be used handily as amateur antennas by simply insulating the pulleys from their support points. This calls for the use of a conducting type of clothesline, such as heavy gauge stranded electrical wire with Teflon or vinyl insulation. A high quality, flexible steel cable (stranded) is suitable as a substitute if you don't mind cleaning it before clothing is hung on it.

A jumper wire can be brought from one end of the line to the ham shack when the station is being operated. If a good electrical connection exists between the wire clothesline and the pulley, a permanent connection can be made by connecting the lead-in wire between the pul-

ley and its insulator. An antenna tuner can be used to match the "invisible" random-length wire to the transmitter and receiver.

Invisible Long Wire

A wire antenna is not actually a "long wire" unless it is one wavelength or greater in length. Yet many amateurs refer to (relatively) long physical spans of conductor as *long wires*. For the purpose of this discussion we will assume we have a fairly long span of wire, and refer to it as an *end-fed* wire antenna.

If we use small-diameter enameled wire for our end-fed antenna, chances are that it will be very difficult to see against the sky and neighborhood scenery. The smaller the wire, the more invisible the antenna will be. The limiting factor with small wire is fragility. A good compromise is #24 or #26 magnet wire for spans up to 130 feet; lighter-gauge wire can be used for shorter spans, such as 30 or 60 feet. The major threat to the longevity of fine wire is icing. Also, birds may fly into the wire and break it. Therefore, this style of antenna may require frequent service or replacement.

Fig 28 illustrates how you might install an invisible end-fed wire. It is important that the insulators also be lacking in prominence. Tiny Plexiglas blocks perform this function well. Small-diameter clear plastic medical vials are suitable also. Some amateurs simply use rubber bands for end insulators, but they will deteriorate rapidly from sun and air pollutants. They are entirely adequate for short-term operation with an invisible antenna, however.

Rain Gutter and TV Antennas

A great number of amateurs have taken advantage of standard house fixtures when contriving inconspicuous antennas. A very old technique is the use of the gutter and downspout system on the building. This is shown in **Fig 29**, where a lead wire is routed to the operating room

Fig 29—Rain gutters and TV antenna installations can be used as inconspicuous Amateur Radio antennas.

from one end of the gutter trough. We must assume that the wood to which the gutter is affixed is dry and of good quality to provide reasonable electrical insulation. The rain gutter antenna may perform quite poorly during wet weather or when there is ice and snow on it and the house roof.

All joints between gutter and downspout sections must be bonded electrically with straps of braid or flashing copper to provide good continuity in the system. Poor joints can permit rectification of RF and subsequently cause TVI and other harmonic interference. Also, it is prudent to insert a section of plastic downspout about 8 feet above ground to prevent RF shocks or burns to passersby while the antenna is being used. Improved performance may result if you join the front and back gutters of the house with a jumper wire to increase the area of the antenna.

Fig 29 also shows a TV or FM antenna that can be employed as an invisible amateur antenna. Many of these antennas can be modified easily to accommodate the 144- or 222-MHz bands, thereby permitting the use of the 300-Ω line as a feeder system. Some FM antennas can be used on 6 meters by adding #10 bus wire extensions to the ends of the elements, and adjusting the match for an SWR of 1:1. If 300-Ω line is used it will require a balun or antenna tuner to interface the line with the station equipment.

For operation in the HF bands, the TV or FM antenna feeders can be tied together at the transmitter end of the span and the system treated as a random length wire. If this is done, the 300-Ω line will have to be on TV standoff insulators and spaced well away from phone and power company service entrance lines. Naturally, the TV or FM radio must be disconnected from the system when it is used for amateur work! Similarly, masthead amplifiers and splitters must be removed from the line if the system is to be used for amateur operation. If the system is mostly vertical, a good RF ground system with many radials around the base of the house should be used to improve performance.

A very nice top-loaded vertical can be made from a length of TV mast with a large TV antenna on the top. Radials can be placed on the roof or at ground level with the TV "feed line" acting as part of the vertical. There is an extensive discussion of loaded verticals and radial systems in Chapter 6, Low-Frequency Antennas.

Flagpole Antennas

We can exhibit our patriotism and have an invisible amateur antenna at the same time by disguising our antenna as shown in **Fig 30**. The vertical antenna is a wire that has been placed inside a plastic or fiberglass pole.

The flagpole antenna shown is structured for a single amateur band, and it is assumed that the height of the pole corresponds to a quarter wavelength for the chosen band. The radials and feed line can be buried in the ground

Fig 30—A flagpole antenna.

as shown. In a practical installation, the sealed end of the coax cable would protrude slightly into the lower end of the plastic pole.

If a large-diameter fiberglass pole were available, a multiband trap vertical may be concealed inside it. Or you might use a metal pole and bury a water-tight box at its base, containing fixed-tuned matching networks for the bands of interest. The networks could then be selected remotely by means of relays inside the box. A 30-foot flagpole would provide good results in this kind of system, provided it was used in conjunction with a buried radial system.

Still another technique is one that employs a wooden flagpole. A small diameter wire can be stapled to the pole and routed to the coax feeder or matching network. The halyard could by itself constitute the antenna wire if it were made from heavy-duty insulated hookup wire. There are countless variations for this type of antenna, and they are limited only by the imagination of the amateur.

Other Invisible Antennas

Some amateurs have used the metal fence on apartment verandas as antennas, and have had good results on the upper HF bands (14, 21 and 28 MHz). We must presume that the fences were not connected to the steel framework of the building, but rather were insulated by the concrete floor to which they were affixed. These verandah fences have also been used effectively as ground systems (counterpoises) for HF-band vertical antennas put in place temporarily after dark.

One amateur in New York City uses the fire escape on his apartment building as a 7-MHz antenna, and he reports good success working DX stations with it. Another

apartment dweller makes use of the aluminum frame on his living room picture window as an antenna for 21 and 28 MHz. He works it against the metal conductors of the baseboard heater in the same room.

Many jokes have been told over the years about *bedspring antennas*. The idea is by no means absurd. Bedsprings and metal end boards have been used to advantage as antennas by many apartment dwellers as 14, 21 and 28 MHz radiators. A counterpoise ground can be routed along the baseboard of the room and used in combination with the bedspring. It is important to remember that any independent (insulated) metal object of reasonable size can serve as an antenna if the transmitter can be matched to it. An amateur in Detroit once used his Shopsmith craft machine (about 5 feet tall) as a 28 MHz antenna. He worked a number of DX stations with it when band conditions were good.

A number of operators have used metal curtain rods and window screens for VHF work, and found them to be acceptable for local communications. Best results with any of these makeshift antennas will be had when the "antennas" are kept well away from house wiring and other conductive objects.

INDOOR ANTENNAS

Without question, the best place for your antenna is outdoors, and as high and in the clear as possible. Some of us, however, for legal, social, neighborhood, family or landlord reasons, are restricted to indoor antennas. Having to settle for an indoor antenna is certainly a handicap for the amateur seeking effective radio communication, but that is not enough reason to abandon all operation in despair.

First, we should be aware of the reasons why indoor antennas do not work well. Principal faults are:

- Low height above ground—the antenna cannot be placed higher than the highest peak of the roof, a point usually low in terms of wavelength at HF
- The antenna must function in a lossy RF environment involving close coupling to electrical wiring, guttering, plumbing and other parasitic conductors, besides dielectric losses in such nonconductors as wood, plaster and masonry
- Sometimes the antenna must be made small in terms of a wavelength
- Usually it cannot be rotated.

These are appreciable handicaps. Nevertheless, global communication with an indoor antenna is still possible, although you must be sure that you are not exposing anyone in your family or nearby neighbors to excessive radiation. See Chapter 1, Safety, in this book.

Some practical points in favor of the indoor antenna include:

- Freedom from weathering effects and damage caused by wind, ice, rain and sunlight (the SWR of an attic antenna, however, can be affected somewhat by a wet or snow-covered roof).
- Indoor antennas can be made from materials that would be altogether impractical outdoors, such as aluminum foil and thread (the antenna need support only its own weight).
- The supporting structure is already in place, eliminating the need for antenna masts.
- The antenna is readily accessible in all weather conditions, simplifying pruning or tuning, which can be accomplished without climbing or tilting over a tower.

Empiricism

A typical house or apartment presents such a complex electromagnetic environment that it is impossible to predict theoretically which location or orientation of the indoor antenna will work best. This is where good old fashioned cut-and-try, use-what-works-best *empiricism* pays off. But to properly determine what really is most suitable requires an understanding of some antenna measuring fundamentals.

Unfortunately, many amateurs do not know how to evaluate performance scientifically or compare one antenna with another. Typically, they will put up one antenna and try it out on the air to see how it "gets out" in comparison with a previous antenna. This is obviously a very poor evaluation method because there is no way to know if the better or worse reports are caused by changing band conditions, different S-meter characteristics or any of several other factors that could influence the reports received.

Many times the difference between two antennas or between two different locations for identical antennas amounts to only a few decibels, a difference that is hard to discern unless instantaneous switching between the two is possible. Those few decibels are not important under strong signal conditions, of course, but when the going gets rough, as is often the case with an indoor antenna, a few dB can make the difference between solid copy and no possibility of real communication.

Very little in the way of test equipment is needed for casual antenna evaluation, other than a communications receiver. You can even do a qualitative comparison by ear, if you can switch antennas instantaneously. Differences of less than 2 dB, however, are still hard to discern. The same is true of S-meters. Signal strength differences of less than a decibel are usually difficult to see. If you want to measure that last fraction of a decibel, you should use a good ac voltmeter at the receiver audio output (with the AGC turned off).

In order to compare two antennas, switching the coaxial transmission line from one to the other is necessary. No elaborate coaxial switch is needed; even a simple double-throw toggle or slide switch will provide more than 40 dB of isolation at HF. See **Fig 31**. Switching by means of manually connecting and disconnecting coaxial lines is not recommended because that takes too long.

Fig 31—When antennas are compared on fading signals, the time delay involved in disconnecting and reconnecting coaxial cables is too long for accurate measurements. A simple slide switch will do well for switching coaxial lines at HF. The four components can be mounted in a tin can or any small metal box. Leads should be short and direct. J1 through J3 are coaxial connectors.

Fading can cause signal-strength changes during the changeover interval.

Whatever difference shows up in the strength of the received signal will be the difference in performance between the two antennas in the direction of that signal. For this test to be valid, both antennas must have nearly the same feed-point impedance, a condition that is reasonably well met if the SWR is below 2:1 on both antennas.

On ionospheric propagated signals (sky wave) there will be constant fading, and for a valid comparison it will be necessary to take an average of the difference between the two antennas. Occasionally, the inferior antenna will deliver a stronger signal to the receiver, but in the long run the law of averages will put the better antenna ahead.

Of course with a ground-wave signal, such as that from a station across town, there will be no fading problems. A ground-wave signal will enable the operator to properly evaluate the antenna under test in the direction of the source. The results will be valid for ionospheric-propagated signals at low elevation angles in that direction. On 28 MHz, all sky-wave signals arrive and leave at low angles. But on the lower bands, particularly 3.5 and 7 MHz, we often use signals propagated at high elevation angles, almost up to the zenith. For these angles a ground-wave test between local stations may not provide a proper evaluation of the antenna, and use of sky wave signals becomes necessary.

Dipoles

At HF the most practical indoor antenna is usually the dipole. Attempts to get more gain with parasitic elements will usually fail because of close proximity to the ground or coupling to house wiring. Beam antenna dimensions determined outdoors will not usually be valid for an attic antenna because the roof structure will cause dielectric loading of the parasitic elements. It is usually more worthwhile to spend time optimizing the location

and performance of a dipole than to try to improve results with parasitic elements.

Most attics are not long enough to accommodate half-wave dipoles for 7 MHz and below. If this is the case, some folding of the dipole will be necessary. The final shape of the antenna will depend on the dimensions and configuration of the attic. Remember that the center of the dipole carries the most current and therefore does most of the radiating. This part should be as high and unfolded as possible. Because the dipole ends radiate less energy than the center, their orientation is not as important. They do carry the maximum voltage, nevertheless, so care should be taken to position the ends far enough from other conductors to avoid arcing.

The dipole may end up being L-shaped, Z-shaped, U-shaped or some indescribable corkscrew shape, depending on what space is available, but reasonable performance can often be had even with such a non-straight arrangement. **Fig 32** shows some possible configurations. Multiband operation is possible with the use of open-wire feeders and an antenna tuner.

One alternative not shown here is the aluminum-foil dipole, which was conceived by Rudy Stork, KA5FSB. He suggests mounting the dipole behind wallpaper or in the attic, with portability, ease of construction and adjustment, and economy in design among its desirable features. This antenna should also display reasonably good bandwidth resulting from the large area of its conductor material. If coaxial feed is used, some pruning of an attic antenna to establish minimum SWR at the band center will be required. Tuning the antenna outdoors and then installing it inside is usually not feasible since the behavior of the antenna will not be the same when placed in the attic. Resonance will be affected somewhat if the antenna is bent.

Even if the antenna is placed in a straight line, parasitic conductors and dielectric loading by nearby wood structures can affect the impedance. Trap and loaded dipoles are shorter than the full-sized versions, but are comparable performers. Trap dipoles are discussed in Chapter 7, Multiband Antennas, and loaded dipoles in Chapter 6, Low-Frequency Antennas.

Dipole Orientation

Theoretically a vertical dipole is most effective at low radiation angles, but practical experience shows that the horizontal dipole is usually a better indoor antenna. A high horizontal dipole does exhibit directional effects at low radiation angles, but you will not be likely to see much, if any, directivity with an attic-mounted dipole. Some operators place two dipoles at right angles to each other with provisions at the operating position for switching between the two. Their reasoning is the radiation patterns will inevitably be distorted in an unpredictable manner by nearby parasitic conductors. There will be little coupling between the dipoles if they are oriented a right

Fig 32—Various configurations for small indoor antennas. See text for discussion.

Fig 33—Ways to orient a pair of perpendicular dipoles. The orientation at A and B will result in no mutual coupling between the two dipoles, but there will be some coupling in the configuration shown at C. End (El) and center (Cl) insulators are shown.

angles to each other as shown in **Figs 33A** and 33B. There will be some coupling with the arrangement shown in Fig 33C, but even this orientation is preferable to a single dipole.

With two antennas mounted 90° apart, you may find that one dipole is consistently better in nearly all directions, in which case you will want to remove the inferior dipole, perhaps placing it someplace else. In this manner the best spots in the house or attic can be determined experimentally.

Parasitic Conductors

Inevitably, any conductor in your house near a quarter wave in length or longer at the operating frequency will be parasitically coupled to your antenna. The word *parasitic* is particularly appropriate in this case because these conductors usually introduce losses and leave less energy for radiation into space. Unlike the parasitic elements in a beam antenna, conductors such as house wiring and plumbing are usually connected to lossy objects such as earth, electrical appliances, masonry or other objects that dissipate energy. Even where this energy is reradiated, it is not likely to be in the right phase in the desired direction; it is, in fact, likely to be a source of RFI.

There are, however, some things that can be done about parasitic conductors. The most obvious is to reroute them at right angles to the antenna or close to the ground, or even underground—procedures that are usually not feasible in a finished home. Where these conductors cannot be rerouted, other measures can be taken. Electrical wiring can be broken up with RF chokes to prevent the flow of radio-frequency currents while permitting 60-Hz current (or audio, in the case of telephone wires) to flow unimpeded. A typical RF choke for a power line can be 100 turns of #10 insulated wire close wound on a length of 1-inch diameter plastic pipe. Of course one choke will be needed for each conductor. A three-wire line calls for three chokes. The chokes can be simplified by winding them bifilar or trifilar on a single coil form.

THE RESONANT BREAKER

Obviously, RF chokes cannot be used on conductors such as metal conduit or water pipes. But it is still possible, surprising as it may seem, to obstruct RF currents on such conductors without breaking the metal. The resonant breaker was first described by Fred Brown, W6HPH, in Oct 1979 *QST*.

Fig 34—A "resonant breaker" such as shown here can be used to obstruct radio-frequency currents in a conductor without the need to break the conductor physically. A vernier dial is recommended for use with the variable capacitor because tuning is quite sharp. The 100-pF capacitor is in series with the loop. This resonant breaker tunes from 14 through 29.7 MHz. Larger models may be constructed for the lower frequency bands.

Fig 34 shows a method of accomplishing this. A figure-eight loop is inductively coupled to the parasitic conductor and is resonated to the desired frequency with a variable capacitor. The result is a very high impedance induced in series with the pipe, conduit or wire. This impedance will block the flow of radio-frequency currents. The figure-eight coil can be thought of as two turns of an air-core toroid and since the parasitic conductor threads through the hole of this core, there will be tight coupling between the two. Inasmuch as the figure-eight coil is parallel resonated, transformer action will reflect a high impedance in series with the linear conductor.

Before you bother with a *resonant breaker* of this type, be sure that there is a significant amount of RF current flowing in the parasitic conductor, and that you will therefore benefit from installing one. The relative magnitude of this current can be determined with an RF current probe of the type described in Chapter 27, Antenna and Transmission-Line Measurements. According to the rule of thumb regarding parasitic conductor current, if it measures less than $1/10$ of that measured near the center of the dipole, the parasitic current is generally not large enough to be of concern.

The current probe is also needed for resonating the breaker after it is installed. Normally, the resonant breaker will be placed on the parasitic conductor near the point of maximum current. When it is tuned through resonance, there will be a sharp dip in RF current, as indicated by the current probe. Of course, the resonant breaker will be effective only on one band. You will need one for each band where there is significant current indicated by the probe.

Power-Handling Capability

So far, our discussion have not considered the full power-handling capability of an indoor antenna. Any tendency to flash over must be determined by running full power or, preferably, somewhat more than the peak power you intend to use in regular operation. The antenna should be carefully checked for arcing or RF heating before you do any operating. Bear in mind that attics are indeed vulnerable to fire hazards. A potential of several hundred volts exists at the ends of a dipole fed by the typical Amateur Radio transmitter. If a power amplifier is used, there could be a few thousand volts at the ends of the dipole. Keep your antenna elements well away from other objects. *Safety first*!

Construction Details and Practical Considerations

Ultimately the success of an antenna project depends on the details of how the antenna is fabricated. A great deal of construction information is given in other chapters of this book. For example the construction of HF Yagis is discussed in Chapter 11, Quad arrays in Chapter 12, VHF antennas in Chapter 18, and in Chapter 20 there is an excellent discussion of antenna materials, particularly wire and tubing for elements. Here is still more helpful antenna construction information.

END EFFECT

If the standard expression $\lambda/2 \approx 491.8/f$ (MHz) is used for the length of a $\lambda/2$ wire antenna, the antenna will resonate at a somewhat lower frequency than is desired. The reason is that in addition to the effect of the conductor diameter and ground effects (Chapter 3, The Effects of Ground) an additional "loading" effect is caused by the insulators used at the ends of the wires to support the antenna. The insulators and the wire loops that tie the insulators to the antenna add a small amount of capacitance to the system. This capacitance helps to tune the antenna to a slightly lower frequency, in much the same way that additional capacitance in any tuned circuit lowers the resonant frequency. In an antenna this is called *end effect*. The current at the ends of the antenna does not quite reach zero because of the end effect, as there is some current flowing into the end capacitance. Note that the computations used to create Figs 2 through 7 in Chapter 2, Antenna Fundamentals, did not take into account any end effect.

End effect increases with frequency and varies slightly with different installations. However, at frequencies up to 30 MHz (the frequency range over which wire antennas are most commonly used), experience shows that the length of a practical $\lambda/2$ antenna, including the effect of diameter and end effect, is on the order of 5% less than the length of a half wave in space. As an average, then, the physical length of a resonant $\lambda/2$ wire antenna can be found from:

$$\lambda = \frac{491.8 \times 0.95}{f\,(\text{MHz})} \approx \frac{468}{f\,(\text{MHz})} \qquad \text{(Eq 1)}$$

Eq 1 is reasonably accurate for finding the physical length of a $\lambda/2$ antenna for a given frequency, but does not apply to antennas longer than a half wave in length. In the practical case, if the antenna length must be adjusted to exact frequency (not all antenna systems require it) the length should be "pruned" to resonance. Note that the use of plastic-insulated wire will typically lower the resonant frequency of a half-wave dipole about 3%.

INSULATORS

Wire antennas must be insulated at the ends. Com-

Fig 35—Some ideas for homemade antenna insulators.

mercially available insulators are made from ceramic, glass or plastic. Insulators are available from many Amateur Radio dealers. RadioShack and local hardware stores are other possible sources. Acceptable homemade insulators may be fashioned from a variety of material including (but not limited to) acrylic sheet or rod, PVC tubing, wood, fiberglass rod or even stiff plastic from a discarded container. **Fig 35** shows some homemade insulators. Ceramic or glass insulators will usually outlast the wire, so they are highly recommended for a safe, reliable, permanent installation. Other materials may tear under stress or break down in the presence of sunlight. Many types of plastic do not weather well.

INSTALLING TRANSMISSION LINES

Many wire antennas require an insulator at the feed point. Although there are many ways to connect the feed line, there are a few things to keep in mind. If you feed your antenna with coaxial cable, you have two choices. You can install an SO-239 connector on the center insu-

Fig 36—Some homemade dipole center insulators. The one in the center includes a built-in SO-239 connector. Others are designed for direct connection to the feed line.

(A)

(B)

Fig 37—Details of dipole antenna construction. At A, the end insulator connection is shown. At B, the completed antenna is shown. A balun (not shown) is often used at the feed point, since this is a balanced antenna.

lator, as shown by the center example in **Fig 36,** and use a PL-259 on the end of your coax, or you can separate the center conductor from the braid and connect the feed line directly to the antenna wire as shown in the other two examples in Fig 36 and the example in **Fig 37**. Although it costs less to connect direct, the use of connectors offers several advantages. Coaxial cable braid soaks up water like a sponge unless it is very well waterproofed. If you do not adequately seal the antenna end of the feed line, water will find its way into the braid. Water in the feed line will lead to contamination, rendering the coax useless long before its normal lifetime is up. Many hams waterproof the coax, first with vinyl electrical tape, and then using a paint-on material called "PlastiDip," which is sold by RadioShack (part number 910-5166 for the white variety).

It is not uncommon for water to drip from the end of the coax inside the shack after a year or so of service if the antenna connection is not properly waterproofed. Use of a PL-259/SO-239 combination (or connector of your choice) makes the task of waterproofing connections much easier. Another advantage to using the PL-259/SO-239 combination is that feed-line replacement is much easier, should that become necessary.

Whether you use coaxial cable, ladder line, or twin lead to feed your antenna, an often overlooked consideration is the mechanical strength of the connection. Wire antennas and feed lines tend to move a lot in the breeze, and

Fig 38—A piece of cut Plexiglas can be used as a center insulator and to support a ladder-line feeder. The Plexiglas acts to reduce the flexing of the wires where they connect to the antenna. Use thick Plexiglas in areas subject to high winds.

unless the feed line is attached securely, the connection will weaken with time. The resulting failure can range from a frustrating intermittent electrical connection to a complete separation of feed line and antenna. Fig 37 and **Fig 38** illustrate different ways of attaching either coax or ladder line to the antenna securely.

When open-wire feed line is used, the conductors of the line should be anchored to the insulator by threading them through the eyes of the insulator two or three times, and twisting the wire back on itself before soldering. A slack tie wire should then be used between the feeder conductor and the antenna, as shown in Fig 38. (The tie wires may be extensions of the line conductors themselves.) When window-type line is suspended from an antenna in a manner such as that shown in Fig 38, the line should be twisted—at several twists per foot—to prevent stress hardening of the wire because of constant flexing in the wind.

When using plastic-insulated open-wire line, the tendency of the line to twist and short out close to the antenna can be counteracted by making the center insulator of the antenna longer than the spacing of the line, as shown in Fig 38. In severe wind areas, it may be necessary to use ¼-inch thick Plexiglas for the center insulator rather than thinner material.

RUNNING THE FEED LINE FROM THE ANTENNA TO THE STATION

Chapter 24, Transmission Lines, contains some general guidelines for installing feed lines. More detailed information is contained in this section. Whenever possible, the transmission line should be lead away from the antenna at a 90° angle to minimize coupling from the antenna to the transmission line. This coupling can cause unequal currents on the transmission line, which will then radiate and it can detune the antenna.

Except for the portion of the line in close proximity to the antenna, coaxial cable requires no particular care in running from the antenna to the station entrance, other than protection from mechanical damage. If the antenna is not supported at the center, the line should be fastened to a post more than head high located under the center of the antenna, allowing enough slack between the post and the antenna to take care of any movement of the antenna in the wind. If the antenna feed point is supported by a tower or mast, the cable can be taped to the mast at intervals or to one leg of the tower.

Coaxial cable rated for direct burial can be buried a few inches in the ground to make the run from the antenna to the station. A deep slit can be cut by pushing a square-end spade full depth into the ground and moving the handle back and forth to widen the slit before removing the spade. After the cable has been pushed into the slit with a piece of 1-inch board 3 or 4 inches wide, the slit can be tamped closed. Many hams run coax cables through PVC pipe buried in the ground deeper than the frost line

Fig 39—A support for open-wire line. The support at the antenna end of the line must be sufficiently rigid to stand the tension of the line.

and slanted downwards slightly so that water will drain, rather than pooling inside the length of the pipe.

Solid ribbon or the newer *window* types of line should be kept reasonably well spaced from other conductors running parallel to it for more than a few feet. TV-type standoff insulators with strap clamp mountings can be used for running this type of line down a mast or tower leg. Similar insulators of the screw-in type can be used in supporting the line on wooden poles for a long run.

Open-wire lines with bare conductors require frequent supports to keep the lines from twisting and shorting out, as well as to relieve the mechanical strain. One method of supporting a long horizontal run of heavy open-wire line is shown in **Fig 39**. The line must be anchored securely at a point under the feed point of the antenna. Window-type line can be supported similarly with wire links fastened to the insulators or with black cable ties (ones not affected by UV radiation from the sun).

To keep the line clear of pedestrians and vehicles, it is usually desirable to anchor the feed line at the eaves or rafter line of the station building (see **Fig 40**), and then drop it vertically to the point of entrance. The points of anchorage and entrance should be chosen to permit the vertical drop without crossing windows for aesthetic reasons.

If the station is located in a room on the ground floor, one way of bringing coax transmission line into the house is to go through the outside wall below floor level, feed it through the basement or crawl space and then up to the station through a hole in the floor. When making the entrance hole in the side of the building, suitable measurements should be made in advance to be sure the hole will go through the sill 2 or 3 inches above the foundation line (and between joists if the bore is parallel to the joists). The line should be allowed to sag below the entrance hole level outside the building to allow rain water to drip off.

Open-wire line can be fed in a similar manner, although it will require a separate hole for each conductor. Each hole should be insulated with a length of polystyrene or Lucite tubing. If available, ceramic tubes salvaged from old-fashioned *knob and tube* electrical

Fig 40—Anchoring open-wire line at the station end. The springs are especially desirable if the line is not supported between the antenna and the anchoring point.

Fig 41—An adjustable window lead-in panel made up of two sheets of Lucite or Plexiglas. A feedthrough connector for coax line can be made as shown in Fig 28. Ceramic feedthrough insulators are suitable for open-wire line. (W1RVE)

installations, work very well for this purpose. Drill the holes with a slight downward slant toward the outside of the building to prevent rain seepage. With window ladder line, it will be necessary to remove a few of the spreader insulators, cut the line before passing through the holes (allowing enough length to reach the inside) and splice the remainder on the inside.

Fig 42—Feedthrough connector for coax line. An Amphenol 83-1J (PL-258) connector, the type used to splice sections of coax line together, is soldered into a hole cut in a brass mounting flange. An Amphenol bulkhead adapter 83-1F may be used instead.

If the station is located above ground level, or if there is other objection to the procedure described above, entrance can be made at a window, using the arrangement shown in **Fig 41**. An Amphenol type 83-1F (UG-363) connector can be used as shown in **Fig 42**; ceramic feedthrough insulators can be used for open-wire line. Ribbon line can be run through clearance holes in the panel, and secured by a winding of tape on either side of the panel, or by cutting the retaining rings and insulators from a pair of TV standoff insulators and clamping one on each side of the panel.

LIGHTNING PROTECTION

Two or three types of lightning arresters for coaxial cable are available on the market. If the antenna feed point is at the top of a well-grounded tower, the arrester can be fastened securely to the top of the tower for grounding purposes. A short length of cable, terminated in a coaxial plug, is then run from the antenna feed point to one receptacle of the arrester, while the transmission line is run from the other arrester receptacle to the station. Such arresters may also be placed at the entrance point to the station, if a suitable ground connection is available at that point (or arresters may be placed at both points for added insurance).

Fig 43—A simple lightning arrester for open-wire line made from three standoff or feedthrough insulators and sections of ¹/₈ × ¹/₂-inch brass or copper strap. It should be installed in the line at the point where the line enters the station. The heavy ground lead should be as short and as direct as possible. The gap setting should be adjusted to the minimum width that will prohibit arcing when the transmitter is operated.

Fig 44—The lightning arrester of Fig 39 may be used with 300-Ω ribbon line in the manner shown here. The TV standoffs support the line an inch or so away from the grounded center member of the arrester

The construction of a homemade arrester for open-wire line is shown in **Fig 43**. This type of arrester can be adapted to ribbon line an inch or so away from the center member of the arrester, as shown in **Fig 44**. Sufficient insulation should be removed from the line where it crosses the arrester to permit soldering the arrester connecting leads.

Lightning Grounds

Lightning-ground connecting leads should be of conductor size equivalent to at least #10 wire. The #8 aluminum wire used for TV-antenna grounds is satisfactory. Copper braid ³/₄-inch wide (Belden 8662-10) is also suitable. The conductor should run in a straight line to the grounding point. The ground connection may be made to a water pipe system (if the pipe is not plastic), the grounded metal frame of a building, or to one or more ⁵/₈-inch ground rods driven to a depth of at least 8 feet. More detailed information on lightning protection is contained in Chapter 1, Safety.

A central grounding panel for coax cables coming into the house is highly recommended. See **Fig 45** for a photo of the homemade grounding panel installed by Chuck Hutchinson, K8CH, at his Michigan home. The coax cables screwed into dual-female feed-through UHF connectors. K8CH installed this aluminum panel under the outside grill for a duct that provided combustion air to an unused fireplace. He used ground strap to connect to ground rods located under the panel. See the ARRL

Fig 45—K8CH's coax entry panel mounted on exterior wall (later covered by grill that provides combustion to an unused fireplace). The ground braid goes to a ground rod located beneath the panel. (Photo courtesy: *Simple and Fun Antennas for Hams*)

book *Simple and Fun Antennas* for more information about ground panels.

Before a lightning storm approaches, a prudent ham will disconnect all feed lines, rotor lines and control lines inside the shack to prevent damage to sensitive electronics. When lightning is crashing about outside, you certainly don't want that lightning inside your shack!

Loop Antennas

A loop antenna is a closed-circuit antenna—that is, one in which a conductor is formed into one or more turns so its two ends are close together. Loops can be divided into two general classes, those in which both the total conductor length and the maximum linear dimension of a turn are very small compared with the wavelength, and those in which both the conductor length and the loop dimensions begin to be comparable with the wavelength.

A "small" loop can be considered to be simply a rather large coil, and the current distribution in such a loop is the same as in a coil. That is, the current has the same phase and the same amplitude in every part of the loop. To meet this condition, the total length of conductor in the loop must not exceed about 0.1 λ. Small loops are discussed later in this chapter, and further in Chapter 14, Direction Finding Antennas.

A "large" loop is one in which the current is not the same either in amplitude or phase in every part of the loop. This change in current distribution gives rise to entirely different properties compared with a small loop.

Half-Wave Loops

The smallest size of "large" loop generally used is one having a conductor length of $^1/_2$ λ. The conductor is usually formed into a square, as shown in **Fig 1**, making each side $^1/_8$ λ long. When fed at the center of one side, the current flows in a closed loop as shown in Fig 1A. The current distribution is approximately the same as on a $^1/_2$ λ wire, and so is maximum at the center of the side opposite the terminals X-Y, and minimum at the terminals themselves. This current distribution causes the field strength to be maximum in the plane of the loop and in the direction looking from the low-current side to the high-current side. If the side opposite the terminals is

opened at the center as shown in Fig 1B (strictly speaking, it is then no longer a loop because it is no longer a closed circuit), the direction of current flow remains unchanged but the maximum current flow occurs at the terminals. This reverses the direction of maximum radiation.

The radiation resistance at a current antinode (which is also the resistance at X-Y in Fig 1B) is on the order of 50 Ω. The impedance at the terminals in Fig 1A is a few thousand ohms. This can be reduced by using two identical loops side by side with a few inches spacing between them and applying power between terminal X on one loop and terminal Y on the other.

Unlike a $^1/_2$ λ dipole or a small loop, there is no direction in which the radiation from a loop of the type shown in Fig 1 is zero. There is appreciable radiation in the direction perpendicular to the plane of the loop, as well as to the "rear"—the opposite direction to the arrows shown. The front-to-back (F/B) ratio is approximately 4 to 6 dB. The small size and the shape of the directive pattern result in a loss of about 1 dB when the field strength in the optimum direction from such a

Fig 1—Half-wave loops, consisting of a single turn having a total length of $^1/_2$ λ.

loop is compared with the field from a $^1/_2$ λ dipole in its optimum direction.

The ratio of the forward radiation to the backward radiation can be increased, and the field strength likewise increased at the same time to give a gain of about 1 dB over a dipole, by using inductive reactances to "load" the sides joining the front and back of the loop. This is shown in **Fig 2**. The reactances, which should have a value of approximately 360 Ω, decrease the current in the sides in which they are inserted and increase it in the side having terminals. This increases the directivity and thus increases the efficiency of the loop as a radiator. Lossy coils can reduce this advantage greatly.

One-Wavelength Loops

Loops in which the conductor length is 1 λ have different characteristics than $^1/_2$-λ loops. Three forms of 1 λ loops are shown in **Fig 3**. At A and B the sides of the squares are equal to $^1/_4$ λ, the difference being in the point at which the terminals are inserted. At C the sides of the triangle are equal to $^1/_3$ λ. The relative direction of current flow is as shown in the drawings. This direction reverses halfway around the perimeter of the loop, as such reversals always occur at the junction of each $^1/_2$-λ section of wire.

The directional characteristics of loops of this type are opposite in sense to those of a small loop. That is, the radiation is maximum perpendicular to the plane of the loop and is minimum in either direction in the plane containing the loop. If the three loops shown in Fig 3 are mounted in a vertical plane with the terminals at the bottom, the radiation is horizontally polarized. When the terminals are moved to the center of one vertical side in Fig 3A, or to a side corner in B, the radiation is vertically polarized. If the terminals are moved to a side corner in C, the polarization will be diagonal, containing both vertical and horizontal components.

In contrast to straight-wire antennas, the electrical length of the circumference of a 1-λ loop is shorter than the actual length. For a loop made of bare #18 wire and operating at a frequency of 14 MHz, where the ratio of conductor length to wire diameter is large, the loop will be close to resonance when

$$\text{Length}_{\text{feet}} = \frac{1032}{f_{\text{MHz}}}$$

The radiation resistance of a resonant 1 λ loop is approximately 120 Ω, under these conditions. Since the loop dimensions are larger than those of a $^1/_2$-λ dipole, the radiation efficiency is high.

Fig 2—Inductive loading in the sides of a $^1/_2$-λ loop to increase the directivity and gain. Maximum radiation or response is in the plane of the loop, in the direction shown by the arrow.

Fig 3—At A and B, loops having sides $^1/_4$ λ long, and at C having sides $^1/_3$ λ long (total conductor length 1 λ). The polarization depends on the orientation of the loop and on the position of the feed point (terminals X-Y) around the perimeter of the loop.

In the direction of maximum radiation (that is, broadside to the plane of the loop, regardless of the point at which it is fed) the 1-λ loop will show a small gain over a $^1/_2$-λ dipole. Theoretically, this gain is about 1 dB, and measurements have confirmed that it is of this order.

The 1-λ loop is more frequently used as an element of a directive antenna array (the quad and delta-loop antennas described in Chapter 12, Quad Arrays) than singly, although there is no reason why it cannot be used alone. In the quad and delta loop, it is nearly always driven so that the polarization is horizontal.

Small Loop Antennas

The electrically small loop antenna has existed in various forms for many years. Probably the most familiar form of this antenna is the ferrite *loopstick* found in portable AM broadcast-band receivers. Amateur applications of the small loop include direction finding, low-noise directional receiving antennas for 1.8 and 3.5 MHz, and small transmitting antennas. Because the design of transmitting and receiving loops requires some different considerations, the two situations are examined separately in this section. This information was written by Domenic M. Mallozzi, N1DM.

The Basic Loop

What is and what is not a small loop antenna? By definition, the loop is considered to be electrically small when its total conductor length is less than 0.1 λ—0.085 is the number used in this section. This size is based on the fact that the current around the perimeter of the loop must be in phase. When the winding conductor is more than about 0.085 λ long, this is no longer true. This constraint results in a very predictable figure-eight radiation pattern, shown in **Fig 4**.

The simplest loop is a 1-turn untuned loop with a load connected to a pair of terminals located in the center of one of the sides, as shown in **Fig 5**. How its pattern is developed is easily pictured if we look at some "snapshots" of the antenna relative to a signal source. **Fig 6** represents a loop from above, and shows the instantaneous radiated voltage wave. Note that points A and B of the loop are receiving the same instantaneous voltage. This means that no current will flow through the loop, because there is no current flow between points of equal potential. A similar analysis of **Fig 7**, with the loop turned 90° from the position represented in Fig 6, shows that this position of the loop provides maximum response. Of course, the voltage derived from the passing wave is small because of the small physical size of the loop. Fig 4 shows the ideal radiation pattern for a small loop.

The voltage across the loop terminals is given by

$$V = \frac{2 \pi A N E \cos \theta}{\lambda} \qquad \text{(Eq 1)}$$

where

- V = voltage across the loop terminals
- A = area of loop in square meters
- N = number of turns in the loop
- E = RF field strength in volts per meter
- θ = angle between the plane of the loop and the signal source (transmitting station)
- λ = wavelength of operation in meters

Fig 5—Simple untuned small loop antenna.

Fig 4—Calculated small loop antenna radiation pattern.

Fig 6—Example of orientation of loop antenna that does not respond to a signal source (null in pattern).

Fig 7—Example of orientation of loop antenna for maximum response.

This equation comes from a term called *effective height*. The effective height refers to the height (length) of a vertical piece of wire above ground that would deliver the same voltage to the receiver. The equation for effective height is

$$h = \frac{2\pi N A}{\lambda} \qquad \text{(Eq 2)}$$

where h is in meters and the other terms are as for Eq 1.

A few minutes with a calculator will show that, with the constraints previously stated, the loop antenna will have a very small effective height. This means it will deliver a relatively small voltage to the receiver, even with a large transmitted signal.

TUNED LOOPS

We can tune the loop by placing a capacitor across the antenna terminals. This causes a larger voltage to appear across the loop terminals because of the Q of the parallel resonant circuit that is formed.

The voltage across the loop terminals is now given by

$$V = \frac{2\pi A N E Q \cos\theta}{\lambda} \qquad \text{(Eq 3)}$$

where Q is the loaded Q of the tuned circuit, and the other terms are as defined above.

Most amateur loops are of the tuned variety. For this reason, all comments that follow are based on tuned-loop antennas, consisting of one or more turns. The tuned-loop antenna has some particular advantages. For example, it puts high selectivity up at the "front" of a receiving system, where it can significantly help factors such as dynamic range. Loaded Q values of 100 or greater are easy to obtain with careful loop construction.

Consider a situation where the inherent selectivity of the loop is helpful. Assume we have a loop with a Q of 100 at 1.805 MHz. We are working a DX station on 1.805 MHz and are suffering strong interference from a local station 10 kHz away. Switching from a dipole to a small loop will reduce the strength of the off-frequency signal by 6 dB (approximately one S unit). This, in effect, increases the dynamic range of the receiver. In fact, if the off-frequency station were further off frequency, the attenuation would be greater.

Another way the loop can help is by using the nulls in its pattern to null out on-frequency (or slightly off-frequency) interference. For example, say we are working a DX station to the north, and just 1 kHz away is another local station engaged in a contact. The local station is to our west. We can simply rotate our loop to put its null to the west, and now the DX station should be readable while the local will be knocked down by 60 or more dB. This obviously is quite a noticeable difference. Loop nulls are very sharp and are generally noticeable only on ground-wave signals (more on this later).

Of course, this method of nulling will be effective only if the interfering station and the station being worked are not in the same direction (or in exact opposite directions) from our location. If the two stations were on the same line from our location, both the station being worked and the undesired station would be nulled out. Luckily the nulls are very sharp, so as long as the stations are at least 10° off axis from each other, the loop null will be usable.

A similar use of the nulling capability is to eliminate local noise interference, such as that from a light dimmer in a neighbor's house. Just put the null on the offending light dimmer, and the noise should disappear.

Now that we have seen some possible uses of the small loop, let us look at a bit of detail about its design. First, the loop forms an inductor having a very small ratio of winding length to diameter. The equations for finding inductance given in most radio handbooks assume that the inductor coil is longer than its diameter. However, F. W. Grover of the US National Bureau of Standards has provided equations for inductors of common cross-sectional shapes and small length-to-diameter ratios. (See the Bibliography at the end of this chapter.) Grover's equations are shown in **Table 1**. Their use will yield relatively accurate numbers; results are easily worked out with a scientific calculator or home computer.

The value of a tuning capacitor for a loop is easy to calculate from the standard resonance equations. The only matter to consider before calculating this is the value of distributed capacitance of the loop winding. This capacitance shows up between adjacent turns of the coil because of their slight difference in potential. This causes each turn to appear as a charge plate. As with all other capacitances, the value of the distributed capacitance is based on the physical dimensions of the coil. An exact mathematical analysis of its value is a complex problem. A simple approximation is given by Medhurst (see Bibliography) as:

$$C = HD \qquad \text{(Eq 4)}$$

where
  C = distributed capacitance in pF
  H = a constant related to the length-to-diameter ratio of the coil (**Table 2** gives H values for length-to-diameter ratios used in loop antenna work.)
  D = diameter of the winding in cm

Medhurst's work was with coils of round cross section. For loops of square cross section the distributed capacitance is given by Bramslev (see Bibliography) as

$$C = 60S \qquad\qquad (Eq\ 5)$$

where
  C = the distributed capacitance in pF
  S = the length of the side in meters

If you convert the length in this equation to centimeters, you will find Bramslev's equation gives results in the same order of magnitude as Medhurst's equation.

This distributed capacitance appears as if it were a capacitor across the loop terminals. Therefore, when determining the value of the tuning capacitor, the distributed capacitance must be subtracted from the total capacitance required to resonate the loop. The distributed capacitance also determines the highest frequency at which a particular loop can be used, because it is the minimum capacitance obtainable.

Electrostatically Shielded Loops

Over the years, many loop antennas have incorporated an electrostatic shield. This shield generally takes the form of a tube around the winding, made of a conductive but non-magnetic material (such as copper or aluminum). Its purpose is to maintain loop balance with respect to ground, by forcing the capacitance between all portions of the loop and ground to be identical. This is illustrated in **Fig 8**. It is necessary to maintain electrical loop balance to eliminate what is referred to as the *antenna effect*. When the antenna becomes unbalanced it appears to act partially as a small vertical antenna. This vertical pattern gets superimposed on the ideal figure-eight pattern, distorting the pattern and filling in the nulls. The type of pattern that results is shown in **Fig 9**.

Adding the shield has the effect of somewhat reducing the pickup of the loop, but this loss is generally offset by the increase in null depth of the loops. Proper balance of the loop antenna requires that the load on the loop also be balanced. This is usually accomplished by use of a balun transformer or a balanced input preamplifier. One important point regarding the shield is that it cannot form a continuous electrical path around the loop perimeter, or it will appear as a shorted coil turn. Usually the insulated break is located opposite the feed point to maintain symmetry. Another point to be considered is that the shield should be of a much larger diameter than the loop winding, or it will lower the Q of the loop.

Various construction techniques have been used in

Table 1
Inductance Equations for Short Coils (Loop Antennas)

Triangle:

$$L\,(\mu H) = 0.006 N^2\, s$$
$$\left[\ln\left(\frac{1.1547\,s\,N}{(N+1)\,\ell} \right) + 0.65533 + \frac{0.1348\,(N+1)\,\ell}{s\,N} \right]$$

Square:

$$L\,(\mu H) = 0.008 N^2\, s$$
$$\left[\ln\left(\frac{1.4142\,s\,N}{(N+1)\,\ell} \right) + 0.37942 + \frac{0.3333\,(N+1)\,\ell}{s\,N} \right]$$

Hexagon:

$$L\,(\mu H) = 0.012 N^2\, s$$
$$\left[\ln\left(\frac{2\,s\,N}{(N+1)\,\ell} \right) + 0.65533 + \frac{0.1348\,(N+1)\,\ell}{s\,N} \right]$$

Octagon:

$$L\,(\mu H) = 0.016 N^2$$
$$\left[\ln\left(\frac{2.613\,s\,N}{(N+1)\,\ell} \right) + 0.75143 + \frac{0.07153\,(N+1)\,\ell}{s\,N} \right]$$

where
  N = number of turns
  s = side length in cm
  ℓ = coil length in cm

Note: In the case of single-turn coils, the diameter of the conductor should be used for ℓ.

Table 2
Values of the Constant H for Distributed Capacitance

Length to Diameter Ratio	H
0.10	0.96
0.15	0.79
0.20	0.78
0.25	0.64
0.30	0.60
0.35	0.57
0.40	0.54
0.50	0.50
1.00	0.46

Fig 8—At A, the loop is unbalanced by capacitance to its surroundings. At B, the use of an electrostatic shield overcomes this effect.

Fig 9—Distortion in loop pattern resulting from antenna effect.

making shielded loops. Genaille located his loop winding inside aluminum conduit, while True constructed an aluminum shield can around his winding. Others have used pieces of Hardline to form a loop, using the outer conductor as a shield. DeMaw used flexible coax with the shield broken at the center of the loop conductor in a multiturn loop for 1.8 MHz. Goldman uses another shielding method for broadcast receiver loops. His shield is in the form of a barrel made of hardware cloth, with the loop in its center. (See Bibliography for above references.) All these methods provide sufficient shielding to maintain the balance. It is possible, as Nelson shows, to construct an unshielded loop with good nulls (60 dB or better) by paying great care to symmetry.

LOOP Q

As previously mentioned, Q is an important consideration in loop performance because it determines both the

loop bandwidth and its terminal voltage for a given field strength. The loaded Q of a loop is based on four major factors. These are (1) the intrinsic Q of the loop winding, (2) the effect of the load, (3) the effect of the electrostatic shield, and (4) the Q of the tuning capacitor.

The major factor is the Q of the winding of the loop itself. The ac resistance of the conductor caused by skin effect is the major consideration. The ac resistance for copper conductors may be determined from

$$R = \frac{0.996 \times 10^{-6} \sqrt{f}}{d} \qquad \text{(Eq 6)}$$

where

R = resistance in ohms per foot
f = frequency, Hz
d = conductor diameter, inches

The Q of the inductor is then easily determined by taking the reactance of the inductor and dividing it by the ac resistance. If you are using a multiturn loop and are a perfectionist, you might also want to include the loss from conductor proximity effect. This effect is described in detail later in this chapter, in the section on transmitting loops.

Improvement in Q can be obtained in some cases by the use of Litz wire (short for *Litzendraht*). Litz wire consists of strands of individual insulated wires that are woven into bundles in such a manner that each conductor occupies each location in the bundle with equal frequency. Litz wire results in improved Q over solid or stranded wire of equivalent size, up to about 3 MHz.

Also, the Q of the tuned circuit of the loop antenna is determined by the Q of the capacitors used to resonate it. In the case of air variables or dipped micas this is not usually a problem. But if variable-capacitance diodes are used to remotely tune the loop, pay particular attention to the manufacturer's specification for Q of the diode at the frequency of operation. The tuning diodes can have a significant effect on circuit Q.

Now we consider the effect of load impedance on loop Q. In the case of a directly coupled loop (as in Fig 5), the load is connected directly across the loop terminals, causing it to be treated as a parallel resistance in a parallel-tuned RLC circuit. Obviously, if the load is of a low value, the Q of the loop will be low. A simple way to correct this is to use a transformer to step up the load impedance that appears across the loop terminals. In fact, if we make this transformer a balun, it also allows us to use our unbalanced receivers with the loop and maintain loop symmetry. Another solution is to use what is referred to as an inductively coupled loop, such as DeMaw's four turn electrostatically shielded loop. A one-turn link is connected to the receiver. This turn is wound with the four-turn loop. In effect, this builds the transformer into the antenna.

Another solution to the problem of load impedance on loop Q is to use an active preamplifier with a high imped-

ance balanced input and unbalanced output. This method also has the advantage of amplifying the low-level output voltage of the loop to where it can be used with a receiver of even mediocre sensitivity. In fact, the Q of the loop when used with a balanced preamplifier having high input impedance may be so high as to be unusable in certain applications. An example of this situation would occur where a loop is being used to receive a 5 kHz wide AM signal at a frequency where the bandwidth of the loop is only 1.5 kHz. In this case the detected audio might be very distorted. The solution to this is to put a Q-degrading resistor across the loop terminals.

FERRITE-CORE LOOP ANTENNAS

The ferrite-core loop antenna is a special case of the air-core receiving loops considered up to now. Because of its use in every AM broadcast-band portable radio, the ferrite-core loop is, by quantity, the most popular form of the loop antenna. But broadcast-band reception is far from its only use; it is commonly found in radio-direction-finding equipment and low-frequency-receiving systems (below 500 kHz) for time and frequency standard systems. In recent years, design information on these types of antennas has been a bit sparse in the amateur literature, so the next few paragraphs are devoted to providing some details.

Ferrite-loop antennas are characteristically very small compared to the frequency of use. For example, a 3.5-MHz version may be in the range of 15 to 30 cm long and about 1.25 cm in diameter. Earlier in this chapter, effective height was introduced as a measure of loop sensitivity. The effective height of an air-core loop antenna is given by Eq 2.

Fig 10—At A, an air-core loop has no effect on nearby field lines. B illustrates the effect of a ferrite core on nearby field lines. The field is altered by the reluctance of the ferrite material.

If an air-core loop is placed in a field, in essence it cuts the lines of flux without disturbing them (**Fig 10A**). On the other hand, when a ferrite (magnetic) core is placed in the field, the nearby field lines are redirected into the loop (Fig 10B). This is because the reluctance of the ferrite material is less than that of the surrounding air, so the nearby flux lines tend to flow through the loop rather than passing it by. (Reluctance is the magnetic analogy of resistance, while flux is analogous to current.) The reluctance is inversely proportional to the permeability of the rod core, μ_{rod}. (In some texts the rod permeability is referred to as effective permeability, μ_{eff}). This effect modifies the equation for effective height of a ferrite-core loop to

$$h = \frac{2\pi N A \mu_{rod}}{\lambda} \qquad \text{(Eq 7)}$$

where

    h = effective height (length) in meters
    N = number of turns in the loop
    A = area of loop in square meters
    μ_{rod} = permeability of the ferrite rod
    λ = wavelength of operation in meters

This obviously is a large increase in "collected" signal. If the rod permeability were 90, this would be the same as making the loop area 90 times larger with the same number of turns. For example, a 1.25-cm diameter ferrite-core loop would have an effective height equal to an air-core loop 22.5 cm in diameter (with the same number of turns).

By now you might have noticed we have been very careful to refer to rod permeability. There is a very important reason for this. The permeability that a rod of ferrite exhibits is a combination of the material permeability or μ, the shape of the rod, and the dimensions of the rod. In ferrite rods, μ is sometimes referred to as initial permeability, μ_i, or toroidal permeability, μ_{tor}. Because most amateur ferrite loops are in the form of rods, we will discuss only this shape.

The reason that μ_{rod} is different from μ is a very complex physics problem that is well beyond the scope of this book. For those interested in the details, books by Polydoroff and by Snelling cover this subject in considerable detail. (See Bibliography.) For our purposes a simple explanation will suffice. The rod is in fact not a perfect director of flux, as is illustrated in **Fig 11**. Note that some lines impinge on the sides of the core and also exit from the sides. These lines therefore would not pass through all the turns of the coil if it were wound from one end of the core to the other. These flux lines are referred to as *leakage flux*, or sometimes as flux leakage.

Leakage flux causes the flux density in the core to be nonuniform along its length. From Fig 11 it can be seen that the flux has a maximum at the geometric center of the length of the core, and decreases as the ends of the core are approached. This causes some noticeable effects. As a short

coil is placed at different locations along a long core, its inductance will change. The maximum inductance exists when the coil is centered on the rod. The Q of a short coil on a long rod is greatest at the center. On the other hand, if you require a higher Q than this, it is recommended that you spread the coil turns along the whole length of the core, even though this will result in a lower value of inductance. (The inductance can be increased to the original value by adding turns.) **Fig 12** gives the relationship of rod permeability to material permeability for a variety of values.

The change in μ over the length of the rod results in an adjustment in the term μ_{rod} for its so called "free ends" (those not covered by the winding). This adjustment factor is given by

$$\mu' = \mu_{rod} \sqrt[3]{\frac{a}{b}} \qquad \text{(Eq 8)}$$

where

μ' = the corrected permeability
a = the length of the core
b = the length of the coil

This value of μ' should be used in place of μ_{rod} in Eq 7 to obtain the most accurate value of effective height.

All these variables make the calculation of ferrite loop antenna inductance somewhat less accurate than for the air-core version. The inductance of a ferrite loop is given by

$$L = \frac{4\pi N^2 A \mu_{rod} \times 10^{-4}}{\ell} \qquad \text{(Eq 9)}$$

where

L = inductance in μH
N = number of turns
A = cross-sectional area of the core in square mm
ℓ = magnetic length of core in mm

Experiments indicate that the winding diameter should be as close to that of the rod diameter as practical in order to maximize both inductance value and Q. By using all this information, we may determine the voltage at the loop ter-minals and its signal-to-noise ratio (SNR). The voltage may be determined from

$$V = \frac{2\pi A N \mu' Q E}{\lambda} \qquad \text{(Eq 10)}$$

where

V = output voltage across the loop terminals
A = loop area in square meters
N = number of turns in the loop winding
μ' = corrected rod permeability
Q = loaded Q of the loop
E = RF field strength in volts per meter
λ = wavelength of operation in meters

Lankford's equation for the sensitivity of the loop for a 10 dB SNR is

$$E = \frac{1.09 \times 10^{-10} \lambda \sqrt{f \, L \, b}}{A N \mu' \sqrt{Q}} \qquad \text{(Eq 11)}$$

where

f = operating frequency in Hz
L = loop inductance in henrys
b = receiver bandwidth in Hz

ANT0138

Fig 12—Rod permeability, μ_{rod}, versus material permeability, μ, for different rod length-to-diameter ratios.

ANT0137

Fig 11—Example of magnetic field lines near a practical ferrite rod, showing leakage flux.

Similarly, Belrose gives the SNR of a tuned loop antenna as

$$SNR = \frac{66.3\,N\,A\,\mu_{rod}\,E}{\sqrt{b}}\sqrt{\frac{Q\,f}{L}} \qquad \text{(Eq 12)}$$

From this, if the field strength E, μ_{rod}, b, and A are fixed, then Q or N must increase (or L decrease) to yield a better SNR. Higher sensitivity can also be obtained (especially at frequencies below 500 kHz) by bunching ferrite cores together to increase the loop area over that which would be possible with a single rod. High sensitivity is important because loop antennas are not the most efficient collectors of signals, but they do offer improvement over other receiving antennas in terms of SNR. For this reason, you should attempt to maximize the SNR when using a small loop receiving antenna. In some cases there may be physical constraints that limit how large you can make a ferrite-core loop.

After working through Eq 11 or 12, you might find you still require some increase in antenna system gain to effectively use your loop. In these cases the addition of a low noise preamplifier may be quite valuable even on the lower frequency bands where they are not commonly used. Chapter 14 contains information on such preamplifiers.

The electrostatic shield discussed earlier with reference to air-core loops can be used effectively with ferrite-core loops. (Construction examples are presented in Chapter 14.) As in the air-core loop, a shield will reduce electrical noise and improve loop balance.

PROPAGATION EFFECTS ON NULL DEPTH

After building a balanced loop you may find it does not approach the theoretical performance in the null depth. This problem may result from propagation effects. Tilting the loop away from a vertical plane may improve performance under some propagation conditions, to account for the vertical angle of arrival. Basically, the loop performs as described above only when the signal is arriving perpendicular to the axis of rotation of the loop. At incidence angles other than perpendicular, the position and depth of the nulls deteriorate.

The problem can be even further influenced by the fact that if the loop is situated over less than perfectly conductive ground, the wave front will appear to tilt or bend. (This bending is not always detrimental; in the case of Beverage antennas, sites are chosen to take advantage of this effect.)

Another cause of apparent poor performance in the null depth can be from polarization error. If the polarization of the signal is not completely linear, the nulls will not be sharp. In fact, for circularly polarized signals, the loop might appear to have almost no nulls. Propagation effects are discussed further in Chapter 14.

SITING EFFECTS ON THE LOOP

The location of the loop has an influence on its performance that at times may become quite noticeable. For ideal performance the loop should be located outdoors and clear of any large conductors, such as metallic downspouts and towers. A VLF loop, when mounted this way, will show good sharp nulls spaced 180° apart if the loop is well balanced. This is because the major propagation mode at VLF is by ground wave. At frequencies in the HF region, a significant portion of the signals is propagated by sky wave, and nulls are often only partial.

Most hams locate their loop antennas near their operating position. If you choose to locate a small loop indoors, its performance may show nulls of less than the expected depth, and some skewing of the pattern. For precision direction finding there may be some errors associated with wiring, plumbing, and other metallic construction members in the building. Also, a strong local signal may be reradiated from the surrounding conductors so that it cannot be nulled with any positioning of the loop. There appears to be no known method of curing this type of problem. All this should not discourage you from locating a loop indoors; this information is presented here only to give you an idea of some pitfalls. Many hams have reported excellent results with indoor mounted loops, in spite of some of the problems.

Locating a receiving loop in the field of a transmitting antenna may cause a large voltage to appear at the receiver antenna terminals. This may be sufficient to destroy sensitive RF amplifier transistors or front-end protection diodes. This can be solved by disconnecting your loop from the receiver during transmit periods. This can obviously be done automatically with a relay that opens when the transmitter is activated.

LOOP ANTENNA ARRAYS

Arrays of loop antennas, both in combination with each other and with other antenna types, have been used for many years. The arrays are generally used to cure some "deficiency" in the basic loop for a particular application, such as a 180° ambiguity in the null direction, low sensitivity, and so forth.

A Sensing Element

For direction-finding applications the single loop suffers the problem of having two nulls that are 180° apart. This leads to an ambiguity of 180° when trying to find the direction to a transmitting station from a given location. A sensing element (often called a *sense antenna*) may be added to the loop, causing the overall antenna to have a cardioid pattern and only one null. The sensing element is a small vertical antenna whose height is equal to or greater than the loop effective height. This vertical is physically close to the loop, and when its omnidirectional pattern is adjusted so that its amplitude and phase are equal to one of the loop

lobes, the patterns combine to form a cardioid. This antenna can be made quite compact by use of a ferrite loop to form a portable DF antenna for HF direction finding. Chapter 14 contains additional information and construction projects using sensing elements.

Arrays of Loops

A more advanced array that can develop more diverse patterns consists of two or more loops. Their outputs are combined through appropriate phasing lines and combiners to form a phased array. Two loops can also be formed into an array that can be rotated without physically turning the loops themselves. This method was developed by Bellini and Tosi in 1907 and performs this apparently contradictory feat by use of a special transformer called a *goniometer*. The goniometer is described in Chapter 14.

Aperiodic Arrays

The aperiodic loop array is a wide-band antenna. This type of array is useful over at least a decade of frequency, such as 2 to 20 MHz. Unlike most of the loops discussed up to now, the loop elements in an aperiodic array are untuned. Such arrays have been used commercially for many years. One loop used in such an array is shown in **Fig 13**. This loop is quite different from all the loops discussed so far in this chapter because its pattern is not the familiar figure eight. Rather, it is omnidirectional.

The antenna is omnidirectional because it is purposely unbalanced, and also because the isolating resistor causes the antenna to appear as two closely spaced short monopoles. The loop maintains the omnidirectional characteristics over a frequency range of at least four or five to one. These loops, when combined into end-fire or broadside phased arrays, can provide quite impressive performance. A commercially made end-fire array of this type consisting of four loops equally spaced along a 25-meter baseline can provide gains in excess of 5 dBi over a range of 2 to 30 MHz. Over a considerable portion of this frequency range, the array can maintain F/B ratios of 10 dB. Even though the commercial version is very expensive, an amateur version can be constructed using the information provided by Lambert. One interesting feature of this type of array is that, with the proper combination of hybrids and combiners, the antenna can simultaneously feed two receivers with signals from different directions, as shown in **Fig 14**. This antenna may be especially interesting to one wanting a directional receiving array for two or more adjacent amateur bands.

SMALL TRANSMITTING LOOP ANTENNAS

The electrically small transmitting-loop antenna involves some different design considerations compared to receiving loops. Unlike receiving loops, the size limitations of the antenna are not as clearly defined. For most purposes, any transmitting loop whose physical circumference is less than ¼ λ can be considered "small." In most cases, as a consequence of their relatively large size (when compared to a receiving loop), transmitting loops have a nonuniform current distribution along their circumference. This leads to some performance changes from a receiving loop.

The transmitting loop is a parallel-tuned circuit with a large inductor acting as the radiator. As with the receiving

Fig 13—A single wide-band loop antenna used in an aperiodic array.

Fig 14—Block diagram of a four-loop broadside array with dual beams separated by 60° in azimuth.

Table 3
Transmitting Loop Equations

$$X_L = 2\pi f L \text{ ohms}$$

$$Q = \frac{f}{\Delta f} = \frac{X_L}{2(R_R + R_L)}$$

$$R_R = 3.12 \times 10^4 \left[\frac{NA}{\lambda^2}\right]^2 \text{ ohms}$$

$$V_C = \sqrt{P X_L Q}$$

$$I_L = \sqrt{\frac{PQ}{X_L}}$$

where

    X_L = inductive reactance, ohms
    f = frequency, Hz
    Δf = bandwidth, Hz
    R_R = radiation resistance, ohms
    R_L = loss resistance, ohms (see text)
    N = number of turns
    A = area enclosed by loop, square meters
    λ = wavelength at operating frequency, meters
    V_C = voltage across capacitor
    P = power, watts
    I_L = resonant circulating current in loop

loop, the calculation of the transmitting-loop inductance may be carried out with the equations in Table 1. Avoid equations for long solenoids found in most texts. Other fundamental equations for transmitting loops are given in **Table 3**.

In the March 1968 *QST*, Lew McCoy, W1ICP, introduced the so-called "Army Loop" to radio amateurs. This was an amateur version of a loop designed for portable use in Southeast Asia by Patterson of the US Army and described in 1967. The Army Loop is diagrammed in **Fig 15A**, showing that this is a parallel tuned circuit fed by a tapped-capacitance impedance-matching network.

The Hart "high-efficiency" loop was introduced in the June 1986 *QST* by Ted Hart, W5QJR. It is shown schematically in Fig 15B and has the series-tuning capacitor separate from the matching network. The Hart matching network is basically a form of gamma match. Other designs have used a smaller loop connected to the transmission line to couple into the larger transmitting loop.

The approximate radiation resistance of a loop in ohms is given by

$$R_R = 3.12 \times 10^4 \left(\frac{NA}{\lambda^2}\right)^2 \qquad \text{(Eq 13)}$$

where

    N = number of turns
    A = area of loop in square meters
    λ = wavelength of operation in meters

Fig 15—At A, a simplified diagram of the Army Loop. At B, the W5QJR loop, which is described in more detail later in this chapter.

The radiation resistance of a small transmitting loop is usually very small. For example, a 1-meter diameter, single-turn circular loop has a radius of 0.5 meters and an enclosed area of $\pi \times 0.5^2 = 0.785$ m^2. Operated at 14.0 MHz, the free-space wavelength is 21.4 meters and this leads to a computed radiation resistance of only $3.12 \times 10^{-4} (0.785/21.4^2)^2 = 0.092$ Ω.

Unfortunately the loop also has losses, both ohmic and from skin effect. By using this information, the radiation efficiency of a loop can be calculated from

$$\eta = \frac{R_R}{R_R + R_L} \qquad \text{(Eq 14)}$$

where

η = antenna efficiency, %
R_R = radiation resistance, Ω
R_L = loss resistance, Ω, which includes the loop's conductor loss plus the loss in the series-tuning capacitor.

A simple ratio of R_R versus R_L shows the effects on the efficiency, as can be seen from **Fig 16**. The loss resistance is primarily the ac resistance of the conductor. This can be calculated from Eq 6. A transmitting loop generally requires the use of copper conductors of at least ¾ inch in diameter in order to obtain reasonable efficiency. Tubing is as useful as a solid conductor because high-frequency currents flow only along a very small depth of the surface of the conductor; the center of the conductor has almost no effect on current flow.

Note that the R_L term above also includes the effect of the tuning capacitor's loss. Normally, the unloaded Q of a capacitor can be considered to be so high that any loss in the tuning capacitor can be neglected. For example, a very high-quality tuning capacitor with no mechanical wiping contacts, such as a vacuum-variable or a transmitting butterfly capacitor, might have an unloaded Q of about 5000. This implies a series loss resistance of less than about 0.02 Ω for a capacitive reactance of 100 Ω. This relatively tiny loss resistance can become significant, however, when the radiation resistance of the loop is only on the order of

0.1 Ω! Practical details for curbing capacitor losses are covered later in this chapter.

In the case of multiturn loops there is an additional loss related to a term called *proximity effect*. The proximity effect occurs in cases where the turns are closely spaced (such as being spaced one wire diameter apart). As these current-carrying conductors are brought close to each other, the current density around the circumference of each conductor gets redistributed. The result is that more current per square meter is flowing at the surfaces adjacent to other conductors. This means that the loss is higher than a simple skin-effect analysis would indicate, because the current is bunched so it flows through a smaller cross section of the conductor than if the other turns were not present.

As the efficiency of a loop approaches 90%, the proximity effect is less serious. But unfortunately, the less efficient the loop, the worse the effect. For example, an 8-turn transmitting loop with an efficiency of 10% (calculated by the skin-effect method) actually only has an efficiency of 3% because of the additional losses introduced by the proximity effect. If you are contemplating construction of a multiturn transmitting loop, you might want to consider spreading the conductors apart to reduce this effect. G. S. Smith includes graphs that detail this effect in his 1972 IEEE paper.

The components in a resonated transmitting loop are subject to both high currents and voltages as a result of the large circulating currents found in the high-Q tuned circuit formed by the antenna. This makes it important that any fixed capacitors have a high RF current rating, such as transmitting micas or the Centralab 850 series. Be aware that even a 100-W transmitter can develop currents in the tens of amperes, and voltages across the tuning capacitor in excess of 10,000 V. This consideration also applies to any conductors used to connect the loop to the capacitors. A piece of #14 wire may have more resistance than the rest of the loop conductor!

It is therefore best to use copper strips or the braid from a piece of large coax cable to make any connections. Make the best electrical connection possible, using soldered or welded joints. Using nuts and bolts should be avoided, because at RF these joints generally have high resistance, especially after being subjected to weathering.

An unfortunate consequence of having a small but high-efficiency transmitting loop is high loaded Q, and therefore limited bandwidth. This type of antenna may require retuning for frequency changes as little as 5 kHz. If you are using any wide-band mode such as AM or FM, this might cause fidelity problems and you might wish to sacrifice a little efficiency to obtain the required bandwidth.

A special case of the transmitting loop is that of the ferrite-loaded loop. This is a logical extension of the transmitting loop if we consider the improvement that a ferrite core makes in receiving loops. The use of ferrites in a transmitting loop is still under development. (See the Bibliography reference for DeVore and Bohley.)

ANT0142

Fig 16—Effect of ratio of R_R/R_L on loop efficiency.

PRACTICAL COMPACT TRANSMITTING LOOPS

The ideal small transmitting antenna would have performance equal to a large antenna. A small loop antenna can approach that performance except for a reduction in bandwidth, but that effect can be overcome by retuning. This section is adapted and updated from material written by Robert T. (Ted) Hart, W5QJR.

As pointed out above, small antennas are characterized by low radiation resistance. For a typical small antenna, such as a short dipole, loading coils are often added to achieve resonance. However, the loss inherent in the coils can result in an antenna with low efficiency. If instead of coils a large, low-loss capacitor is added to a low-loss conductor to achieve resonance, and if the antenna conductor is bent to connect the ends to the capacitor, a loop is formed.

Based on this concept, the small loop is capable of relatively high efficiency, compared to its coil-loaded cousin. In addition, the small loop, when mounted vertically, can radiate efficiently over the wide range of elevation angles required on the lower frequency bands. This is because it has both high-angle and low-angle response. See **Fig 17**, which shows the elevation response for a compact transmitting loop only 16.2 inches wide at 14.2 MHz. This loop is

vertically polarized and its bottom is 8 feet above average ground, which has a conductivity of 5 mS/m and a dielectric constant of 13. For comparison, Fig 17 also shows the responses of three other reference antennas—the same small loop flipped sideways at a height of 30 feet to produce horizontal radiation, a full-sized $\frac{1}{4}$-λ ground plane antenna mounted 8 feet above average ground using two tuned radials, and finally a simple $\frac{1}{2}$ λ flattop dipole mounted 30 feet above flat ground. The considerably smaller transmitting loop comes to within 3 dB of the larger $\frac{1}{4}$-λ vertical at a 10° elevation angle, and it is far stronger for high elevation angles because it does not have the null at high elevation angles that the ground plane has. Of course, this characteristic does make it more susceptible to strong signals received at high elevation angles. Incidentally, just in case you were wondering, adding more radials to the $\lambda/4$ ground plane doesn't materially improve its performance when mounted at an 8-foot height on 20 meters.

The simple horizontal dipole in Fig 17 would be the clear winner in any shootout because its horizontally polarized radiation does not suffer as much attenuation at reflection from ground as does a vertically polarized wave. The case is not quite so clear-cut, however, for the small loop mounted horizontally at 30 feet. While it does have increased gain at medium elevation angles, it may not be worth the effort needed to mount it on a mast, considering the slight loss at low angles compared to its twin mounted vertically only 8 feet above ground.

A physically small antenna like the 16.2-inch-wide vertically polarized loop does put out an impressive signal compared to far larger competing antennas. Though somewhat ungainly, it is a substantially better performer than most mobile whips, for example. The main deficiency in a compact transmitting loop is its narrow bandwidth—it must be accurately tuned to the operating frequency. The use of a remote motor drive allows the loop to be tuned over a wide frequency range.

For example, for fixed-station use, two loops could be constructed to provide continuous frequency coverage from 3.5 to 30 MHz. A loop with an 8.5 foot circumference, 16 inches wide, could cover 10 through 30 MHz and a loop with a 20-foot circumference, 72 inches wide, could cover 3.5 to 10.1 MHz.

Table 4 presents summary data for various size loop antennas for the HF amateur bands. Through computer analysis, the optimum size conductor was determined to be $\frac{3}{4}$-inch rigid copper water pipe, considering both performance and cost. Performance will be compromised, but only slightly, if $\frac{5}{8}$-inch flexible copper tubing is used. This tubing can easily be bent to any desired shape, even a circle. The rigid $\frac{3}{4}$-inch copper pipe is best used with 45° elbows to make an octagon.

The loop circumference should be between $\frac{1}{4}$ and $\frac{1}{8}$ λ at the operating frequency. It will become self-resonant above $\frac{1}{4}$ λ, and efficiency drops rapidly below $\frac{1}{8}$ λ. In the frequency ranges shown in Table 4, the high fre-

Fig 17—Elevation-plane plot at 14.2 MHz, showing response of an 8.5-foot circumference octagonal copper loop (width of 16.2 inches), compared to a full-sized λ/4 ground-plane vertical with two elevated λ/4 radials, the same small loop flipped horizontally at a height of 30 feet, and lastly, a λ/2 flattop dipole also at a height of 30 feet. Both the λ/4 ground-plane vertical and the vertically polarized loop are elevated 8 feet above typical ground, with σ = 5 mS/m and ε = 13. The low vertically polarized loop is surprisingly competitive, only down about 2.5 dB compared to the far larger ground plane at low elevation angles. Note that the vertical loop has both high-angle as well as low-angle radiation, and hence would be better at working close-in local stations than the ground-plane vertical, with its deep nulls at higher angles. The simple flattop dipole, however, is better than either vertical because of the poor ground reflection for a vertically polarized compared to a horizontally polarized signal.

Table 4

Design Data for Loops

Loop Circumference = 8.5' (Width = 32.4"), Vertically Polarized

Frequency, MHz	10.1	14.2	21.2	29.0
Max Gain, dBi	−4.47	−1.42	+1.34	+2.97
Max Elevation Angle	40°	30°	22°	90°
Gain, dBi @10°	−8.40	−4.61	−0.87	+0.40
Total Capacitance, pF	145	70	29	13
Peak Capacitor kV	23	27	30	30

Loop Circumference = 8.5' (Width = 32.4"), Horizontally Polarized, @30'

Frequency, MHz	10.1	14.2	21.2	29.0
Max Gain, dBi	−3.06	+1.71	+5.43	+6.60
Max Elevation Angle	34°	28°	20°	16°
Gain, dBi @10°	−9.25	−3.11	+2.61	+5.34
Total Capacitance, pF	145	70	29	13
Peak Capacitor kV	23	27	30	30

Loop Circumference = 20' (Width = 6'), Vertically Polarized

Frequency, MHz	3.5	4.0	7.2	10.1
Max Gain, dBi	−7.40	−6.07	−1.69	−0.34
Max Elevation Angle	68°	60°	38°	30°
Gain, dBi @10°	−11.46	−10.12	−5.27	−3.33
Capacitance, pF	379	286	85	38
Peak Capacitor kV	22	24	26	30

Loop Circumference = 20' (Width = 6'), Horizontally Polarized, @30'

Frequency, MHz	3.5	4.0	7.2	10.1
Max Gain, dBi	−13.32	−10.60	−0.20	+3.20
Max Elevation Angle	42°	42°	38°	34°
Gain, dBi @10°	−21.62	−18.79	−7.51	−3.22
Capacitance, pF	379	286	85	38
Peak Capacitor kV	22	24	26	30

Loop Circumference = 38' (Width = 11.5'), Vertically Polarized

Frequency, MHz	3.5	4.0	7.2
Max Gain, dBi	−2.93	−2.20	−0.05
Max Elevation Angle	46°	42°	28°
Gain, dBi @10°	−6.48	−5.69	−2.80
Capacitance, pF	165	123	29
Peak Capacitor kV	26	27	33

Notes: These loops are octagonal in shape, constructed with ¾-inch copper water pipe and soldered 45° copper elbows. The gain figures assume a capacitor unloaded Q_C = 5000, typical for vacuum-variable type of tuning capacitor. The bottom of the loop is assumed to be 8 feet high for safety and the ground constants are "typical" at conductivity = 5 mS/m and dielectric constant = 13. Transmitter power is 1500 W. The voltage across the tuning capacitor for lower powers goes down with a multiplier of $\sqrt{\dfrac{P}{1500}}$. For example, at 100 W using the 38-foot-circumference loop at 7.2 MHz, the peak voltage would be $33\ \text{kV} \times \sqrt{\dfrac{100}{1500}} = 8.5\ \text{kV}$.

quency is tuned with a minimum capacitance of about 29 pF—including stray capacitance.

The low frequency listed in Table 4 is that where the loop response is down about 10 dB from that of a full-sized elevated ground plane at low elevation angles suitable for DX work. **Fig 18** shows an overlay at 3.5 MHz of the elevation responses for two loops: one with an 8.5-foot circumference and one with a 20-foot circumference, together with the response for a full-sized 80-meter ground plane elevated 8 feet off average ground with 2 tuned radials. The 20-foot circumference loop holds its own well compared to the full-sized ground plane.

Controlling Losses

Contrary to earlier reports, adding quarter-wave ground radials underneath a vertically polarized transmitting loop doesn't materially increase loop efficiency. The size of the conductor used for a transmitting loop, however, does directly affect several interrelated aspects of loop performance.

Data for Table 4 was computed for ¾-inch copper water pipe (nominal OD of 0.9 inch). Note that the efficiency is higher and the Q is lower for loops having a circumference near ¼ λ. Larger pipe size will reduce the loss resistance, but the Q increases. Therefore the bandwidth decreases, and the voltage across the tuning capacitor increases. The voltage across the tuning capacitor for high-power operation can become very impressive, as shown in Table 4. Rigid ¾-inch copper water pipe is a good electrical compromise and can also help make a small-diameter loop mechanically sturdy.

The equivalent electrical circuit for the loop is a parallel resonant circuit with a very high Q, and therefore a narrow bandwidth. The efficiency is a function of radiation resistance divided by the sum of the radiation plus loss resistances. The radiation resistance is much less than 1 Ω, so it is necessary to minimize the loss resistance, which is largely the skin-effect loss of the conductor, assuming that the tuning capacitor has very low loss. Poor construction techniques must be avoided. All joints in the

loop must be brazed or soldered.

However, if the system loss is too low, for example by using even larger diameter tubing, the Q may become excessive and the bandwidth may become too narrow for practical use. These reasons dictate the need for a complete analysis to be performed before proceeding with the construction of a loop.

There is another source of additional loss in a completed loop antenna besides the conductor and capacitor losses. If the loop is mounted near lossy metallic conductors, the large magnetic field produced will induce currents into those conductors and be reflected as losses in the loop. Therefore the loop should be as far from other conductors as possible. If you use the loop inside a building constructed with large amounts of iron or near ferrous materials, you will simply have to live with the loss if the loop cannot otherwise be relocated.

The Tuning Capacitor

Fig 19 demonstrates the selection of loop size versus tuning capacitance for any desired operating frequency range for the HF amateur bands. This is for octagonal-shaped loops using ¾-inch copper water pipe with 45° copper elbows. For example, a capacitor that varies from 5 to 50 pF, used with a loop 10 feet in circumference, tunes from 13 to 27 MHz (represented by the left dark vertical bar). A 25 to 150-pF capacitor with a 13.5-foot loop circumference covers the 7 to 14.4-MHz range, represented by the right vertical bar.

Fig 20 illustrates how the 29-MHz elevation pattern becomes distorted and rather bulbous-looking for the 10-foot circumference loop, although the response at low elevation angles is still better than that of a full-sized ground-plane antenna.

Air Variable Capacitors

Special care must be taken with the tuning capacitor if an air-variable type is used. The use of a split-stator capacitor eliminates the resistance of wiper contacts, resistance that is inherent in a single-section capacitor. The ends of the loop are connected to the stators, and the rotor forms the variable coupling path between the stators. With this arrangement the value of capacitance is divided by two, but the voltage rating is doubled.

Fig 19—Frequency tuning range of an octagon-shaped loop using ³/₄-inch copper water pipe, for various values of tuning capacitance and loop circumference.

Fig 18—Elevation-plane response of three antennas at 3.5 MHz—a 20-foot circumference octagonal copper loop, a 38-foot circumference copper loop and a full-sized λ/4 ground plane with two elevated radials. The bottom of each antenna is mounted 8 feet above ground for safety. The 38-foot circumference loop (which has a "wingspan" of 11.5 feet) is fairly competitive with the much large ground-plane, being down only about 4 dB at low elevation angles. The 20-foot circumference loop is much more lossy, but with its top only about 14 feet off the ground is very much of a "stealth" antenna.

Fig 20—Elevation-plane plot for a 16.2-inch wingspan octagonal copper loop at 29 MHz, compared to a λ/4 ground-plane antenna with two resonant elevated radials. The gains at low angles are almost identical, but the loop exhibits more gain at medium and high elevation angles. Again, the bottom of each antenna is located 8 feet above ground for safety.

You must carefully select a variable capacitor for transmitting-loop application—that is, all contacts must be welded, and no mechanical wiping contacts are allowed. For example, if the spacers between plates are not welded to the plates, there will be loss at each joint, and thus degraded loop efficiency. (Earlier transmitting loops exhibited poor efficiency because capacitors with wiping contacts were used.)

There are several suitable types of capacitors for this application. A vacuum variable is an excellent choice, provided one is selected with an adequate voltage rating. Unfortunately, those capacitors are very expensive.

W5QJR used a specially modified air-variable capacitor in his designs. This had up to 340 pF maximum per section, with $1/4$-inch spacing, resulting in 170 pF when both sections were in series as a butterfly capacitor. Another alternative is to obtain a large air variable, remove the aluminum plates, and replace them with copper or double-sided PC board material to reduce losses. Connect all plates together on the rotor and on the stators. Solder copper straps to the capacitor for soldering to the loop itself.

The spacing between plates in an air-variable capacitor determines the voltage-handling capability, rated at 75,000 V per inch. For other power ratings, multiply the spacing (and voltage) by the square root of the ratio of your power to 1000 W. For example, for 100 W, the ratio would be = 0.316.

A Teflon-Insulated Trombone Variable Capacitor

Another type of variable capacitor discussed in the amateur literature for use with a compact transmitting loop is the so-called "trombone" type of capacitor. **Fig 21** shows a practical trombone capacitor created by Bill Jones, KD7S, for Nov 1994 *QST*. This capacitor uses downward pointing extensions of the two $3/4$-inch OD main conductor copper pipes, with a Teflon-insulated trombone section made of $1/2$-inch ID copper pipe. The trombone telescopes into the main pipes, driven by a lead screw and a 180-rpm gear-head motor. Like the butterfly air variable capacitor, the trombone works without lossy wiper contacts. Jones' capacitor varied from 12 pF (including strays) to almost 60 pF, making it suitable to tune his 3-foot circumference loop from 14 to 30 MHz at the 100-W level.

KD7S used 5-mil (0.005 inch) thick Teflon sheet as an insulator. Since Teflon is conservatively rated at more than 1 kV per mil of thickness, the voltage breakdown capability of this capacitor is well in excess of 5 kV. The parts list is given in **Table 5**.

Table 5
KD7S Loop-Tuning Capacitor Parts List for Nominal 50-pF Capacitor

Qty	Description
2	10-inch length of ¾-inch-ID type M copper water pipe
2	10-inch length of ½-inch-ID type M copper water pipe
1	3-inch length of ½-inch-ID type M copper water pipe
2	½-inch, 90° copper elbows
2	¾-inch, 90° copper elbows
2	10 × 22-inch piece of 0.005-inch-thick Teflon sheet plastic
1	12-inch length of #8-32 threaded brass rod
1	#8-32 brass shoulder nut
2	22 × 5½ × ¼-inch ABS plastic sheet (top and bottom covers)
3	1 × 5½ × ¼-inch ABS plastic sheet (end pieces and center) brace/guide
2	1 × 22 × ¼-inch ABS plastic sheet (side rails)
1	50 to 200-rpm gear-head dc motor
1	DPDT center-off toggle switch (up/down control)
2	SPDT microswitches (limit switches)
50 feet	3-conductor control cable
1	Enclosure for control switch

Fig 21—A practical trombone capacitor designed by Bill Jones, KD7S, for his compact transmitting loop. This capacitor has a tuning range from 12 to almost 60 pF, and can withstand at least 5 kV peak. The 10-inch ½-inch ID tubes are covered with Teflon-sheet insulation and slide into the ¾-inch ID copper pipes.

A short length of plastic tubing connects the threaded brass rod to the motor. The tubing acts as an insulator and a flexible coupling to smooth out minor shaft-alignment errors. The other end of the rod is threaded into a brass nut soldered to the crossbar holding the $^1/_2$-inch pipes together. Jones used a 12-V motor rated at 180 rpm, but it has sufficient torque to work with as little as 4 V applied. Instead of a sophisticated variable duty-cycle speed control circuit, he used an LM327 adjustable voltage regulator to vary the motor-control voltage from 4 to 12 V. Tuning speeds ranged from 11 seconds per inch at 12 V to 40 seconds per inch at 4 V. The higher speed is necessary to jump from band to band in a reasonable length of time. The lower speed makes it easy to fine-tune the capacitor to any desired frequency within a band.

When building the capacitor, keep in mind that the smaller tubes must telescope in and out of the larger tubes with silky smoothness. Any binding will cause erratic tuning. For the same reason, the #8-32 brass threaded rod must be straight and properly aligned with the brass nut. *Take your time with this part of the project.*

Perhaps the easiest way to form the insulator is to pre-cut a length of Teflon sheet to the proper size. Place a lengthwise strip of double-sided tape on the tube to secure one end of the Teflon sheet. Begin wrapping the Teflon around the tube while keeping it as tight as possible. *Don't allow wrinkles or ridges to form.* Secure the other end with another piece of tape. Once both tubes are covered, ensure they are just short of being a snug fit inside the larger tubes. Confirm that the insulation completely overlaps the open end of the small tubes. If not, the capacitor is certain to arc internally with more than a few watts of power applied to it.

Route the motor wiring inside the antenna pipes to minimize the amount of metal within the field of the antenna. Bring the wires out next to the coaxial connector. A three-wire system allows the use of limit switches to restrict the movement of the trombone section. Be sure to solder together all metal parts of the capacitor. Use a small propane torch, a good quality flux and 50/50 solid solder. Do not use acid-core solder! Clean all parts to be joined with steel wool prior to coating them with flux.

A Cookie-Sheet and Picture-Frame-Glass Variable Capacitor

In Vol 2 of *The ARRL Antenna Compendium* series, Richard Plasencia, WØRPV, described a clever high-voltage variable capacitor he constructed using readily available materials. See **Fig 22**, which shows Plasencia's homebrew high-voltage variable capacitor, along with the coil and other parts used in his homemade antenna coupler. This capacitor could be varied from 16 to 542 pF and tested at a breakdown of 12,000 V.

The capacitor sits on four PVC pillars and consists of two $4^1/_2 \times 4^1/_2$-inch aluminum plates separated by a piece of window glass that is $8^1/_2 \times 5^1/_2$ inches in size. The lower plate is epoxied to the glass. The upper plate is free to move in a wooden track epoxied to the upper surface of the glass. The motor is reversible and moves the upper capacitor plate by rotating a threaded rod in a wing nut pinned to a tab on the capacitor plate. The four pillars are cut from PVC pipe to insulate the capacitor from the chassis and to elevate it into alignment with the motor shaft.

WØRPV used a piece of 0.063-inch thick single-weight glass that exhibited a dielectric constant of 8. He removed the glass from a dime-store picture frame. In time-honored ham fashion, he improvised his wooden tracks for the upper capacitor plate from a single wooden paint stirrer, and for the capacitor plates, he used aluminum cookie sheets.

The wooden track for the upper plate is made by splitting the wooden paint stirrer with a knife into one narrow and one wide strip. The narrow strip is cemented on top and overhangs the movable plate, creating a slotted track. Since the wood is supported by the glass plate, its insulating qualities are of no importance.

The principle of operation is simple. The reversible motor turns a threaded $^1/_4$-inch rod with a pitch of 20 threads to the inch. This rod engages a wing nut attached to the movable capacitor plate. Although WØRPV grounded his capacitor's movable plate with a braid, an insulator similar to that used in the trombone capacitor above should be used to isolate the lead-screw mechanism. Several pieces of braid made from RG-8 coax shield should be used to connect to the ends of the compact transmitting loop conductors to form low-loss connections.

WØRPV used a 90-rpm motor from a surplus vending machine. It moved his variable capacitor plate $4^1/_2$ inches, taking about a minute to travel from one end to the other. Since he wished to eliminate the complexity and dubious reliability of limit switches when used outdoors, he monitored the motor's dc current through two 3 Ω, 2W resistors

Fig 22—The picture-frame-glass variable capacitor design of Richard Plasencia, WØRPV. Two aluminum plates separated by a piece of glass scavenged from a picture frame create a variable capacitor that can withstand 12,000 V, with a variable range from 16 to 542 pF.

placed in series with each lead of the motor and shunted by red LEDs at the control box. When the motor stalled by jamming up against the PVC limit stop or against the inside of the plastic mounting box, the increased motor current caused one or the other of the LEDs to light up.

TYPICAL LOOP CONSTRUCTION

After you select the electrical design for your loop application, you must consider how to mount it and how to feed it. If you wish to cover only the upper HF bands of 20 through 10 meters, you will probably choose a loop that has a circumference of about 8.5 feet. You can make a reasonably sturdy loop using 1-inch diameter PVC pipe and ⅝-inch flexible copper tubing bent into the shape of a circle. Robert Capon, WA3ULH, did this for a QRP-level transmitting loop described in May 1994 *QST*. **Fig 23** shows a picture of his loop, with PVC H-frame stand.

Fig 23—Photo of compact transmitting loop designed by Robert Capon, WA3ULH. This uses a 1-inch PVC H-frame to support the loop made of flexible ⅝-inch copper tubing. The small coupling loop made of RG-8 coax braid couples the loop to the coax feed line. The tuning capacitor and drive motor are at the top of the loop, shown here in the ARRL Laboratory during testing.

This loop design used a 20-inch long coupling loop made of RG-8 coax to magnetically couple into the transmitting loop rather than the gamma-match arrangement used by W5QJR in his loop designs. The coupling loop was fastened to the PVC pipe frame using 2-inch long #8 bolts that also held the main loop to the mast.

A more rugged loop can be constructed using rigid ¾-inch copper water pipe, as shown in the W5QJR design in **Fig 24**. While a round loop is theoretically a bit more efficient, an octagonal shape is much easier to construct. The values presented in Table 4 are for octagons.

For a given loop circumference, divide the circumference by 8 and cut eight equal-length pieces of ¾ inch copper water pipe. Join the pieces with 45° elbows to form the octagon. With the loop lying on the ground on scraps of 2 × 4 lumber, braze or solder all joints.

W5QJR made a box from clear plastic to house his air-variable capacitor and drive motor at the top of the loop. The side of the box that mounts to the loop and the capacitor should be at least ¼-inch thick, preferably ⅜-inch. The remainder of the box can be ⅛-inch plastic sheet. He mounted the loop to the plastic using ¼-inch bolts (two on either side of center) after cutting out a section of pipe 2 inches wide in the center. On the motor side of the capacitor, he cut the pipe and installed a copper T for the motor wiring.

W5QJR's next step was to solder copper straps to the loop ends and to the capacitor stators, then he remounted the loop to the plastic. If you insert wood dowels, the pipe will remain round when you tighten the bolts. Next he installed the motor drive cable through the loop and connected it to the motor. Antenna rotator cable is a good choice for this cable. He completed the plastic box using short pieces of aluminum angle and small sheet-metal screws to join the pieces.

The loop was then ready to raise to the vertical position. Remember, no metal is allowed near the loop. W5QJR made a pole of 2 × 4-inch lumber with 1 × 4-inch boards on either side to form an I section. He held the boards together with ¼-inch bolts, 2 feet apart and tied rope guys to the top. This made an excellent mast up to 50 feet high. The pole height should be one foot greater than the loop diameter, to allow room for cutting grass or weeds at the bottom of the loop. W5QJR installed a pulley at the top so that his loop could be raised, supported by rope. He supported the bottom of the loop by tying it to the pole and tied guy ropes to the sides of the loop to keep it from rotating in the wind. By moving the anchor points, he could rotate his loop in the azimuth plane.

W5QJR used a gamma-matching arrangement made of flexible ¼-inch copper tubing to couple the loop to the transmission line. In the center of one leg, he cut the pipe and installed a copper T. Adjacent to the T, he installed a mount for the coax connector. He made the mount from copper strap, which can be obtained by splitting a short piece of pipe and hammering it flat.

While the loop was in the vertical position he cut a piece of ¼-inch flexible copper tubing the length of one

Fig 24—Octagonal loop construction details. Table 4 gives loop design data for various frequency ranges.

of the straight sides of the loop. He then flattened one end and soldered a piece of flexible wire to the other. He wrapped the tubing with electrical tape for insulation and connected the flexible wire to the coax connector. He then installed the tubing against the inside of the loop, held temporarily in place with tape. He soldered the flat part to the loop, ending up with a form of gamma match, but without reactive components. This simple feed provided better than 1.7:1 SWR over a 2:1 frequency range. For safety, he installed a good ground rod under the loop and connected it to the strap for the coax connector, using large flexible wire.

TUNE-UP PROCEDURE

The resonant frequency of the loop can be readily found by setting the receiver to a desired frequency and rotating the capacitor (by remote control) until signals peak. The peak will be very sharp because of the high Q of the loop.

Turn on the transmitter in the tune mode and adjust either the transmitter frequency or the loop capacitor for maximum signal on a field-strength meter, or for maximum forward signal on an SWR bridge. Adjust the matching network for minimum SWR by bending the matching line. Normally a small hump in the $1/4$-inch tubing line, as shown in Fig 24, will give the desired results. For a loop that covers two or more bands, adjust the feed to give equally low SWR at each end of the tubing range.

The SWR will be very low in the center of the tuning range but will rise at each end.

If there is metal near the loop, the additional loss will reduce the Q and therefore the impedance of the loop. In those cases it will be necessary to increase the length of the matching line and tap higher up on the loop to obtain a 50-Ω match.

PERFORMANCE COMPARISON

As previously indicated, a compact transmitting loop can provide performance approaching full-size dipoles and verticals. To illustrate one case, a loop 100 feet in circumference would be 30 feet high for 1.8 MHz. However, a good dipole would be 240 feet ($1/2 \lambda$) in length and at least 120 feet high ($1/4 \lambda$). A $1/4$-λ vertical would be 120 feet tall with a large number of radials on the ground, each 120 feet in length. The smaller loop could replace both of those antennas with only a moderate degradation in performance and a requirement for a high-voltage variable capacitor.

On the higher frequencies, the same ratios apply, but full-size antennas are less dramatic. However, very few city dwellers can erect good verticals even on 7 MHz with a full-size counterpoise. Even on 14 MHz a loop about 3 feet high can work the world.

Other than trading small size for narrow bandwidth and a high-voltage capacitor, the compact transmitting loop is an excellent antenna and should find use where large antennas are not practical.

The Loop Skywire

Are you looking for a multiband HF antenna that is easy to construct, costs nearly nothing and yet works well? You might want to try this one. The *Loop Skywire* antenna is a full-sized horizontal loop. Early proponents suggested that the antenna could be fed with coaxial cable with little concern for losses, but later analysis proved that this was a bit of wishful thinking—the relatively low values for SWR across multiple bands indicate that cable losses were part and parcel of performance. The best way to feed this versatile antenna is with open-wire ladder line, with an antenna tuner in the shack to present the transmitter with a low value of SWR.

THE DESIGN

The Loop Skywire is shown in **Fig 25**. The antenna has one wavelength of wire in its perimeter at the design or fundamental frequency. If you choose to calculate L_{total} in feet, the following equation should be used:

$$L_{total} = \frac{1005}{f}$$

where f equals the frequency in MHz.

Given any length of wire, the maximum possible area the antenna can enclose is with the wire in the shape of a circle. Since it takes an infinite number of supports to hang a circular loop, the square loop (four supports) is the most practical. Further reducing the area enclosed by the wire loop (fewer supports) brings the antenna closer to the properties of the folded dipole, and both harmonic-impedance and feed-line voltage problems can result. Loop geometries other than a square are thus possible, but remember the two fundamental requirements for the Loop Skywire—its horizontal position and maximum enclosed area.

There is another great advantage to this antenna system. It can be operated as a vertical antenna with top-hat loading on other bands as well. This is accomplished by simply keeping the feed line run from the antenna to the shack as vertical as possible and clear of objects. Both feed-line conductors are then tied together, and the antenna is fed against a good ground.

CONSTRUCTION

Antenna construction is simple. Although the loop can be made for any band or frequency of operation, the following two Loop Skywires are good performers. The 10-MHz band can also be operated on both.

L/4   L/4

L/4   L/4

3.5 MHz Loop Skywire - L=287'
7 MHz Loop Skywire - L=142'

Open-wire Line

Height About 40'

Ham Shack

ANT0149

Fig 25—A complete view of the Loop Skywire. The square loop is erected horizontal to the earth.

3.5-MHz Loop Skywire
  (3.5-28 MHz loop and 1.8-MHz vertical)
  Total loop perimeter: 272 feet
  Square side length: 68 feet

7-MHz Loop Skywire
  (7-28 MHz loop and 3.5-MHz vertical)
  Total loop perimeter: 142 feet
  Square side length: 35.5 feet

The actual total length can vary from the above by a few feet, as the length is not at all critical. Do not worry about tuning and pruning the loop to resonance. No signal difference will be detected on the other end when that method is used.

Bare #14 copper wire is used in the loop. **Fig 26** shows the placement of the insulators at the loop corners. Two common methods are used to attach the insulators. Either lock or tie the insulator in place with a loop wire tie, as shown in Fig 26A, or leave the insulator free to "float" or slide along the wire, Fig 26B. Most loop users float at least two insulators. This allows pulling the slack out of the loop once it is in the air, and eliminates the need to have all the supports exactly placed for proper tension in each leg. Floating two opposite corners is recommended.

Fig 27A shows the azimuth-plane performance on 7.2 MHz of a 142-foot long, 7-MHz Loop Skywire, 40 feet high at an elevation angle of 10º, compared to a regular flattop $1/2$-λ dipole at a height of 30 feet. The loop comes into its own at higher frequencies. Fig 27B shows the response at 14.2 MHz, compared again to a $1/2$–λ 14.2-MHz

Fig 26—Two methods of installing the insulators at the loop corners.

Fig 27—At A, azimuth-plane response of 142-foot long, 7-MHz Loop Skywire, 40 feet in the air at 7.2 MHz, compared with ½-λ dipole 30 feet in the air. At B, response of same Loop Skywire at 14.2 MHz, compared with ½-λ 14.2-MHz dipole 30 feet in the air. Now the loop has some advantage in certain directions. At C, response of the same Loop Skywire at 21.2 MHz compared to a 21.2-MHz dipole at 30 feet. Here, the Loop Skywire has more gain in almost all directions than the simple dipole. All azimuth-plane patterns were made at 10° elevation.

dipole at a height of 30 feet. Now the loop has several lobes that are stronger than the dipole. Fig 27C shows the response at 21.2 MHz, compared to a dipole. Now the loop has superior gain compared to the $^1/_2$-λ dipole at almost any azimuth. In its favored direction on 21.2 MHz, the loop is 8 dB stronger than the dipole.

The feed point can be positioned anywhere along the loop that you wish. However, most users feed the Skywire at a corner. **Fig 28** depicts a method of doing this, using a piece of plexiglass to provide insulation as well as strain relief for the open-wire ladder line. It is advantageous to keep the feed-point mechanicals away from the corner support. Feeding a foot or so from one corner allows the feed line to exit more freely. This method keeps the feed line free from the loop support.

Generally a minimum of four supports is required. If trees are used for supports, then at least two of the ropes or guys used to support the insulators should be counterweighted and allowed to move freely. The feed-line corner is almost always tied down, however. Very little tension is needed to support the loop (far less than that for a dipole). Thus, counterweights are light. Several such loops have been constructed with bungie cords tied to three of the four insulators. This eliminates the need for counterweighting.

Recommended height for the antenna is 40 feet or more. The higher the better, especially if you wish to use the loop in the vertical mode. However, successful local and DX operation has been reported in several cases with the antenna at 20 feet. **Fig 29** shows the feed arrangement for using the Loop Skywire as a top-loaded vertical fed against ground on the lower bands.

Because the loop is high in the air and has considerable electrical exposure to the elements, proper methods should be employed to eliminate the chance of induced or direct lightning hazard to the shack and operator. Some users simply completely disconnect the antenna from the antenna tuner and rig and shack during periods of possible lightning activity.

ANT0152

Fig 28—Most users feed the Skywire at a corner. A high-impedance weather-resistant insulator should be used for the feed-point insulator.

ANT0153

Fig 29—The feed arrangement for operating the 7-MHz Loop Skywire as a vertical antenna.

7-MHz Loop

An effective but simple 7MHz antenna that has a theoretical gain of approximately 1 dB over a dipole is a full-wave, closed vertical loop. Such a loop need not be square, as illustrated in **Fig 30A**. It can be trapezoidal, rectangular, circular, or some distorted configuration in between those shapes. For best results, however, you should attempt to make the loop as square as possible. The more rectangular the shape, the greater the cancellation of energy in the system, and the less effective it will be. In the limiting case, the antenna loses its identity as a loop and becomes a folded dipole.

You can feed the loop in the center of one of the vertical sides if you want vertical polarization. For horizontal polarization, you feed either of the horizontal sides at the center. Since optimum directivity occurs at right angles to the plane of the loop (or in more simple terms, broadside to the loop), you should hang the loop to radiate the maximum amount in some favored direction.

Fig 31A shows the azimuthal response at a takeoff angle of 15°, a typical angle for 40-meter DX, for vertical and horizontal feed systems over ground with "average" con-

ductivity and dielectric constant. Fig 31A includes, for reference, the response of a flattop dipole 50 feet high. For DX work on 40 meters, the vertically polarized loop can perform as well as or substantially better than either a horizontally polarized loop or a flattop dipole, particularly in the azimuthal nulls of the dipole.

For the low elevation angles that favor DX work, the optimal feed point is at the center of one of the vertical wires. Feeding the loop at one of the corners at the bottom gives a

Fig 30—At A, details of the rectangular full-wave loop. The dimensions given are for operation at 7.05 MHz. The height above ground was 7 feet in this instance, although improved performance should result if the builder can install the loop higher above ground without sacrificing length on the vertical sides. At B, illustration how a single supporting structure can be used to hold the loop in a diamond-shaped configuration. Feeding the diamond at the lower tip provides radiation in the horizontal plane. Feeding the system at either side will result in vertical polarization of the radiated signal.

Fig 31—At A, azimuthal plane responses for the vertically and horizontally polarized 7-MHz loop, compared to a flattop 50-foot high dipole, all at a takeoff angle of 15° for DX work. The solid line is for feeding the loop horizontally at the bottom; the dashed line is for feeding the loop vertically at a side, and the dotted line is for a simple flattop horizontal dipole at 50 feet in height. For DX work, the vertically polarized loop is an excellent performer.

compromise result for both local and DX work. The actual impedance is roughly the same at each point: bottom horizontal center, corner or vertical side center.

Fig 31B demonstrates how the gain for vertical polarization changes over different type of grounds: saltwater, very poor ground (conductivity = 1 mS/m, dielectric constant = 5) very good (conductivity = 30 mS/m, dielectric constant = 20) and average ground (conductivity = 5 mS/m, dielectric constant = 13). Again, for reference a 50-foot high flattop dipole's elevation response is included. As has been mentioned previously in other chapters, a seaside location is a wonderful environment for verticals!

Just how you erect such a loop will depend on what is available in your backyard. Trees are always handy for supporting loop antennas. A disadvantage to the rectangular loop shown in Fig 30A is that two 34-foot high supports are needed, although in many instances your house may be high enough to serve as one of these supports. If you have a tower higher than about 50 feet, Fig 30B demonstrates how you can use it to support a diamond-shaped loop for 40 meters. The elevation and azimuthal responses are almost the same for either loop configuration, rectangular- or diamond-shaped.

The overall length of the wire used in a loop is determined in feet from the formula 1005/f (MHz). Hence, for operation at 7.125 MHz the overall wire length will be 141 feet. The matching transformer, an electrical $^1/_4 \lambda$ of 75Ω coax cable, can be computed by dividing 246 by the operating frequency in MHz, then multiplying that number by the velocity factor of the cable being used. Thus, for operation at 7.125 MHz, 246/7.125 MHz = 34.53 feet. If coax with solid polyethylene insulation is used, a velocity factor of 0.66 must be employed. Foam-polyethylene coax has a velocity factor of 0.80. Assum-

Fig 32—Elevation-plane response of 7-MHz loop used on 14.2 MHz. This is for a feed point at the center of one of the two vertical wires. The dashed line is the response of a flattop 20-meter dipole at 30 feet in height for comparison.

ing RG-59 is used, the length of the matching transformer becomes 34.53 (feet) × 0.66 = 22.79 feet, or 22 feet, 9$^1/_2$ inches.

This same loop antenna in Fig 30A fed vertically may be used on the 14 and 21MHz bands, although its pattern will not be as good as that on its fundamental frequency and you will have to use an open-wire transmission line to feed the loop for multiband use. **Fig 32** shows the response at the peak lobe of the loop, at a 45° angle to the plane of the loop, compared to the peak response for a simple halfwave 20-meter dipole, 30 feet high. The gain from a simple flattop dipole, mounted at 30 feet, will be superior to the loop operated on a harmonic frequency.

A Receiving Loop for 1.8 MHz

You can use a small shielded-loop antenna to improve reception under certain conditions, especially at the lower amateur frequencies. This is particularly true when high levels of man-made noise are prevalent, when the second-harmonic energy from a nearby broadcast station falls in the 1.8MHz band, or when interference exists from some other amateur station in the immediate area. A properly constructed and tuned small loop will exhibit approximately 30 dB of front-to-side response, the minimum response being at right angles to the plane of the loop. Therefore, noise and interference can be reduced significantly or completely nulled out, by rotating the loop so that it is sideways to the interference-causing source.

Generally speaking, small shielded loops are far less responsive to man-made noise than are the larger antennas used for transmitting and receiving. But a trade-off in performance must be accepted when using the loop, for the strength of received signals will be 10 or 15 dB less than when using a full-size resonant antenna. This condition is not a handicap on 1.8 or 3.5 MHz, provided the station receiver has normal sensitivity and overall gain. Because a front-to-side ratio of 30 dB may be expected, a shielded loop can be used to eliminate a variety of receiving problems if made rotatable, as shown in **Fig 33**.

To obtain the sharp bidirectional pattern of a small loop, the overall length of the conductor must not exceed 0.1 λ. The loop of **Fig 34** has a conductor length of 20 feet. At 1.81 MHz, 20 feet is 0.037 λ. With this style of loop, 0.037 λ is about the maximum practical dimension if you want to tune the element to resonance. This limitation results from the distributed capacitance between the shield and inner conductor of the loop. RG-59 was used for the loop element in this example. The capacitance per foot for this cable is 21 pF, resulting in a total distributed

Fig 33—Jean DeMaw, W1CKK, tests the 1.8-MHz shielded loop. Bamboo cross arms are used to support the antenna.

Fig 34—Schematic diagram of the loop antenna. The dimensions are not critical provided overall length of the loop element does not exceed approximately 0.1 λ. Small loops which are one half or less the size of this one will prove useful where limited space is a consideration.

capacitance of 420 pF. An additional 100 pF was needed to resonate the loop at 1.810 MHz.

Therefore, the approximate inductance of the loop is 15 μH. The effect of the capacitance becomes less pronounced at the higher end of the HF spectrum, provided the same percentage of a wavelength is used in computing the conductor length. The ratio between the distributed capacitance and the lumped capacitance used at the feed point becomes greater at resonance. These facts should be contemplated when scaling the loop to those bands above 1.8 MHz.

There will not be a major difference in the construction requirements of the loop if coaxial cables other than RG-59 are used. The line impedance is not significant with respect to the loop element. Various types of coaxial line exhibit different amounts of capacitance per foot, however, thereby requiring more or less capacitance across the feed point to establish resonance.

Shielded loops are not affected noticeably by nearby objects, and therefore they can be installed indoors or out after being tuned to resonance. Moving them from one place to another does not significantly affect the tuning.

You can see in the model shown in Fig 33 that a supporting structure was fashioned from bamboo poles. The X frame is held together at the center with two U bolts. The loop element is taped to the cross-arms to form a square. You could likely use metal cross arms without seriously

degrading the antenna performance. Alternatively, wood can be used for the supporting frame.

A Minibox was used at the feed point of the loop to hold the resonating variable capacitor. In this model a 50 to 400-pF compression trimmer was used to establish resonance. You must weatherproof the box for outdoor installations.

Remove the shield braid of the loop coax for one inch directly opposite the feed point. You should treat the exposed areas with a sealing compound once this is done.

In operation this receiving loop has proven very effective for nulling out second-harmonic energy from local broadcast stations. During DX and contest operations on 1.8 MHz it helped prevent receiver overloading from nearby 1.8-MHz stations that share the band. The marked reduction in response to noise has made the loop a valuable station accessory when receiving weak signals. It is not used all of the time, but is available when needed by connecting it to the receiver through an antenna selector switch. Reception of European stations with the loop has been possible from New England at times when other antennas were totally ineffective because of noise.

It was also discovered that the effects of approaching storms (with attendant atmospheric noise) could be nullified considerably by rotating the loop away from the storm front. It should be said that the loop does not exhibit meaningful directivity when receiving sky-wave signals. The directivity characteristics relate primarily to ground-wave signals. This is a bonus feature in disguise, for when nulling out local noise or interference, one is still able to copy sky-wave signals from all compass points!

For receiving applications it is not necessary to match the feed line to the loop, though doing so may enhance the performance somewhat. If no attempt is made to obtain an SWR of 1, the builder can use 50 or 75-Ω coax for a feeder, and no difference in performance will be observed. The Q of this loop is sufficiently low to allow the operator to peak it for resonance at 1.9 MHz and use it across the entire 1.8MHz band. The degradation in performance at 1.8 and 2 MHz will be so slight that it will be difficult to discern.

An Indoor Stealth Loop

Ted Phelps, W8TP, wrote an article in *The ARRL Antenna Compendium, Vol 7* describing his attic-mounted wire loop antenna, fed with an automatic antenna tuner. Here is a shortened version of that article.

If you drive down my street in Whitechapel Village in Newark, DE, trying to find my ham location by looking for my antenna, you wouldn't find it. Even if you pulled up in front of my condo, you wouldn't notice any telltale signs, because my multiband antenna is completely hidden. It's in the attic of my two-bedroom condominium in a small retirement community completed in 1999.

Before the move, I had given considerable thought to what type of antenna I might use, if any. I already knew that permanent outdoor types were out of the question, due to restrictive real estate and condo association rules. So I planned a clause for any sales contract I might sign, specifically mentioning amateur radio and my desire to set up a station in my new living quarters. I decided I would not move where my lifelong hobby would be severely restricted or prohibited.

That meant that to be reasonably sure I could continue enjoying Amateur Radio as before, I would have to install an indoor antenna that could perform as well as a typical outdoor system. What kind? In Ohio, I had tried a horizontally polarized attic dipole made with #14 wire. It didn't work very well—it was just too low to the ground.

I learned about a high-tech method of remote antenna tuning using an antenna coupler which contains a microprocessor. I found this kind of automatic tuner available from two American manufacturers and within a reasonable price range. Although our move was still a few months ahead, I purchased a model SG-230 antenna coupler made by SGC Inc, Bellevue, WA, for use in Delaware.

Fig 35 shows the final dimensions of my hidden loop, which is a single-turn rectangular loop, erected in a north-south vertical plane and made from nearly 78 feet of #6 stranded, aircraft primary wire in a PVC jacket, held taut at the lower corners and supported by a pulley and guy rope at each upper corner. Because it's vertically polarized, it supports low-angle radiation reasonably well. By the way, if you're wondering why I used such a relatively large-gauge wire as #6 for the loop antenna, it was readily available from my son-in-law!

Fig 36 shows my completed condo unit. Note the doghouse dormer on the roof about 12 feet above ground at the attic floor. This is the level of my hidden loop's base leg.

In constructing my system I had to overcome RFI problems on my own premises. Each condo unit has its own electronic security panel on an upper shelf in a closet. As soon as I applied moderate power to my radio and loop, the Fire Alarm sounded and firefighters came to my door! The burglar/intrusion signal was triggered a couple of times, too. Working with a security installation technician, I found that *there was no ground wire connected to my security panel.* "We don't bother with that," said the tech, and then, reacting to my surprise, connected a #14 ground between the security panel and the house water-pipe ground. I then installed a ferrite bead on each lead entering the security panel. I also placed ferrite beads on keyer-paddle leads, GFCI electrical outlets, etc. Those

ANT0158

Fig 35—Diagram showing layout of W8TP's indoor hidden loop antenna.

Fig 36—Can you see W8TP's antenna in this photograph? Of course you can't—it's hidden from view inside his attic!

ANT0159

Max. Gain = 5.48 dBi   Freq. = 14.2 MHz

(A)

Loop ———   Dipole at 23' – – – –

Max. Gain = 3.13 dBi   Freq. = 14.2 MHz

(B)

Fig 37—At A, computed elevation pattern at 14.2 MHz for W8TP's hidden loop (solid line), compared to a 20-meter dipole (dashed line) at a height of 23 feet. At B, a comparison of the azimuth patterns at a 20°-elevation angle for W8TP's loop (solid line) and the same 20-meter dipole (dashed line). The loop has a slightly asymmetrical response because it is fed at a corner, but its performance is competitive to an outdoor dipole. In fact, it has superior low-angle performance, typical of a vertically polarized antenna compared to a low horizontal antenna.

measures seem to have eliminated my RFI problems.

When we moved into our condo, I took the obvious precaution of not using a linear amplifier. I took extra care to establish a single-point ground for my station equipment by connecting all equipment grounds to the cover plate of the dedicated metallic outlet box behind the operating position, and thence to a separate ground rod in our front yard. I use a 1-kW RL Drake low-pass filter in the transceiver-antenna feed line.

Is this indoor antenna system safe? I believe so. In the attic it is not at all close to our living space. It is fixed firmly in place and unlike most amateur antennas it is *out of the weather*! I therefore do not use a quick-grounding system for times when a thunderstorm approaches.

Fig 37 shows the computed elevation and azimuth patterns on 20 meters. The tuner is able to hold the SWR down low enough so that my JRC-245 transceiver can operate through its internal antenna tuner.

BIBLIOGRAPHY

Source material and more extended discussion of topics covered in this chapter can be found in the references given below and in the textbooks listed at the end of Chapter 2.

C. F. W. Anderson, "A Crossed-Loop/Goniometer DF Antenna for 160 Meters," *The ARRL Antenna Compendium, Vol 1* (Newington: ARRL, 1985), pp 127-132.

J. S. Belrose, "Ferromagnetic Loop Aerials," *Wireless Engineer*, Feb 1955, pp 41-46.

J. S. Belrose, "An Update on Compact Transmitting Loops," *QST*, Nov 1993, pp 37-40.

D. S. Bond, *Radio Direction Finders*, 1st ed. (New York: McGraw-Hill Book Co, 1944).

G. Bramslev, "Loop Aerial Reception," *Wireless World*, Nov 1952, pp 469-472.

R. W. Burhans, "Experimental Loop Antennas for 60 kHz to 200 kHz," *Technical Memorandum (NASA) 71*, (Athens, OH: Ohio Univ, Dept of Electrical Engr), Dec 1979.

R. W. Burhans, "Loop Antennas for VLF-LF," *Radio-Electronics*, Jun 1983, pp 83-87.

D. DeMaw, "Beat the Noise with a Scoop Loop," *QST*, Jul 1977, pp 30-34.

M. F. DeMaw, *Ferromagnetic-Core Design and Application Handbook* (Englewood Cliffs, NJ: Prentice-Hall Inc, 1981).

D. DeMaw and L. Aurick, "The Full-Wave Delta Loop at Low Height," *QST*, Oct 1984, pp 24-26.

R. Devore and P. Bohley, "The Electrically Small Magnetically Loaded Multiturn Loop Antenna," *IEEE Trans on Ant and Prop*, Jul 1977, pp 496-505.

T. Dorbuck, "Radio Direction-Finding Techniques," *QST*, Aug 1975, pp 30-36.

R. G. Fenwick, "A Loop Array for 160 Meters," *CQ*, Apr 1986, pp 25-29.

D. Fischer, "The Loop Skywire," *QST*, Nov 1985, pp 20-22. Also "Feedback," *QST*, Dec 1985, p 53.

R. A. Genaille, "V.L.F. Loop Antenna," *Electronics World*, Jan 1963, pp 49-52.

G. Gercke, "Radio Direction/Range Finder," *73*, Dec 1971, pp 29-30.

R. S. Glasgow, *Principles of Radio Engineering* (New York: McGraw-Hill Book Co, Inc, 1936).

S. Goldman, "A Shielded Loop for Low Noise Broadcast Reception," *Electronics*, Oct 1938, pp 20-22.

F. W. Grover, *Inductance Calculation-Working Formulas and Tables* (New York: D. VanNostrand Co, Inc, 1946).

J. V. Hagan, "A Large Aperture Ferrite Core Loop Antenna for Long and Medium Wave Reception," *Loop Antennas Design and Theory*, M.G. Knitter, Ed. (Cambridge, WI: National Radio Club, 1983), pp 37-49.

T. Hart, "Small, High-Efficiency Loop Antennas," *QST*, Jun 1986, pp 33-36.

T. Hart, *Small High Efficiency Antennas Alias The Loop* (Melbourne, FL: W5QJR Antenna Products, 1985)

H. Hawkins, "A Low Budget, Rotatable 17 Meter Loop," *QST*, Nov 1997, p 35.

F. M. Howes and F. M. Wood, "Note on the Bearing Error and Sensitivity of a Loop Antenna in an Abnormally Polarized Field," *Proc IRE*, Apr 1944, pp 231-233.

B. Jones, KD7S, "You Can Build: A Compact Loop Antenna for 30 Through 12 Meters," Nov 1994 *QST*, pp 33-36.

J. A. Lambert, "A Directional Active Loop Receiving Antenna System," *Radio Communication*, Nov 1982, pp 944-949.

D. Lankford, "Loop Antennas, Theory and Practice," *Loop Antennas Design and Theory*, M. G. Knitter, Ed. (Cambridge, WI: National Radio Club, 1983), pp 10-22.

D. Lankford, "Multi-Rod Ferrite Loop Antennas," *Loop Antennas Design and Theory*, M. G. Knitter, Ed. (Cambridge, WI: National Radio Club, 1983), pp 53-56.

G. Levy, "Loop Antennas for Aircraft," *Proc IRE*, Feb 1943, pp 56-66. Also see correction, *Proc IRE*, Jul 1943, p 384.

J. Malone, "Can a 7 foot 40m Antenna Work?" *73*, Mar 1975, pp 33-38.

R. Q. Marris, "An In-Room 80-Meter Transmitting Multiturn Loop Antenna," *QST*, Feb 1996, pp 43-45. Feedback. *QST*, May 1996, p 48.

L. G. McCoy, "The Army Loop in Ham Communications," *QST*, Mar 1968, pp 17, 18, 150, 152. (See also Technical Correspondence, *QST*, May 1968, pp 49-51 and Nov 1968, pp 46-47.)

R. G. Medhurst, "HF Resistance and Self Capacitance of Single Layer Solenoids," *Wireless Engineer*, Feb 1947, pp 35-43, and Mar 1947, pp 80-92.

G. P. Nelson, "The NRC FET Altazimuth Loop Antenna," *N.R.C. Antenna Reference Manual Vol. 1,* 4th ed., R. J. Edmunds, Ed. (Cambridge, WI: National Radio Club, 1982), pp 2-18.

K. H. Patterson, "Down-To-Earth Army Antenna," *Electronics*, Aug 21, 1967, pp 111-114.

R. C. Pettengill, H. T. Garland and J. D. Meindl, "Receiving Antenna Design for Miniature Receivers," *IEEE Trans on Ant and Prop*, Jul 1977, pp 528-530.

T. Phelps, W8TP, "A Hidden Loop Antenna," *The ARRL Antenna Compendium, Vol 7* (Newington: ARRL, 2002), pp 160-162.

R. Z. Plasencia, WØRPV, "Remotely Controlled Antenna Coupler," *The ARRL Antenna Compendium, Vol 2* (Newington: ARRL, 1989), pp 182-186.

W. J. Polydoroff, *High Frequency Magnetic Materials—Their Characteristics and Principal Applications* (New York: John Wiley and Sons, Inc, 1960).

E. Robberson, "QRM? Get Looped," *Radio and Television News*, Aug 1955, pp 52-54, 126.

G. S. Smith, "Radiation Efficiency of Electrically Small Multiturn Loop Antennas," *IEEE Trans on Ant and Prop*, Sep 1972, pp 656-657.

E. C. Snelling, *Soft Ferrites—Properties and Applications* (Cleveland, OH: CRC Press, 1969).

G. Thomas, "The Hot Rod—An Inexpensive Ferrite Booster Antenna," *Loop Antennas Theory and Design*, M. G. Knitter, Ed. (Cambridge, WI: National Radio Club, 1983), pp 57-62.

J. R. True, "Low-Frequency Loop Antennas," *Ham Radio*, Dec 1976, pp 18-24.

E. G. VonWald, "Small-Loop Antennas," *Ham Radio*, May 1972, pp 36-41.

"An FET Loop Amplifier with Coaxial Output," *N.R.C. Antenna Reference Manual, Vol 2*, 1st ed., R. J. Edmunds, Ed. (Cambridge, WI: National Radio Club, Oct 1982), pp 17-20.

Aperiodic Loop Antenna Arrays (Hermes Electronics Ltd, Nov 1973).

Reference Data for Radio Engineers, 6th ed. (Indianapolis: Howard W. Sams & Co, subsidiary of ITT, 1977).

Fig 43—A simple lightning arrester for open-wire line made from three standoff or feedthrough insulators and sections of $^1/_8 \times {}^1/_2$-inch brass or copper strap. It should be installed in the line at the point where the line enters the station. The heavy ground lead should be as short and as direct as possible. The gap setting should be adjusted to the minimum width that will prohibit arcing when the transmitter is operated.

Fig 44—The lightning arrester of Fig 39 may be used with 300-Ω ribbon line in the manner shown here. The TV standoffs support the line an inch or so away from the grounded center member of the arrester

The construction of a homemade arrester for open-wire line is shown in **Fig 43**. This type of arrester can be adapted to ribbon line an inch or so away from the center member of the arrester, as shown in **Fig 44**. Sufficient insulation should be removed from the line where it crosses the arrester to permit soldering the arrester connecting leads.

Lightning Grounds

Lightning-ground connecting leads should be of conductor size equivalent to at least #10 wire. The #8 aluminum wire used for TV-antenna grounds is satisfactory. Copper braid $^3/_4$-inch wide (Belden 8662-10) is also suitable. The conductor should run in a straight line to the grounding point. The ground connection may be made to a water pipe system (if the pipe is not plastic), the grounded metal frame of a building, or to one or more $^5/_8$-inch ground rods driven to a depth of at least 8 feet. More detailed information on lightning protection is contained in Chapter 1, Safety.

A central grounding panel for coax cables coming into the house is highly recommended. See **Fig 45** for a photo of the homemade grounding panel installed by Chuck Hutchinson, K8CH, at his Michigan home. The coax cables screwed into dual-female feed-through UHF connectors. K8CH installed this aluminum panel under the outside grill for a duct that provided combustion air to an unused fireplace. He used ground strap to connect to ground rods located under the panel. See the ARRL

Fig 45—K8CH's coax entry panel mounted on exterior wall (later covered by grill that provides combustion to an unused fireplace). The ground braid goes to a ground rod located beneath the panel. (Photo courtesy: *Simple and Fun Antennas for Hams*)

book *Simple and Fun Antennas* for more information about ground panels.

Before a lightning storm approaches, a prudent ham will disconnect all feed lines, rotor lines and control lines inside the shack to prevent damage to sensitive electronics. When lightning is crashing about outside, you certainly don't want that lightning inside your shack!

Chapter 6

Low-Frequency Antennas

In theory there is no difference between antennas at 10 MHz and up and those for lower frequencies. In reality however, there are often important differences. It is the size of the antennas, which increases as frequency is decreased, that creates practical limits on what can be realized physically at reasonable cost.

At 7.3 MHz, 1λ = 133 feet and by the time we get to 1.8 MHz, 1 λ = 547 feet. Even a λ/2 dipole is very long on 160 meters. The result is that the average antenna for these bands is quite different from the higher bands, where Yagis and other relatively complex antennas dominate. In addition, vertical antennas can be more useful at low frequencies than they are on 20 meters and above because of the low heights (in wavelengths) usually available for horizontal antennas on the low bands. Much of the effort on the low bands is focused on how to build simple but effective antennas with limited resources. This section is devoted to antennas for use on amateur bands between 1.8 to 7 MHz.

The Importance of Low Angles for Low-Band DXing

In Chapter 3, The Effects of Ground, we emphasized the importance of matching the elevation response of your antennas as closely as possible to the range of elevation angles needed for communication with desired geographic areas. **Fig 1** shows the statistical 40-meter elevation angles needed over the entire 11-year solar cycle to cover the path from Boston, Massachusetts, to all of Europe. These angles range from 1° (at 9.6% of the time when the 40-meter band is open to Europe) to 28° (at 0.3% of the time).

Fig 1 also overlays the elevation pattern response of a 100-foot high flattop dipole on the elevation-angle statistics, illustrating that even at this height the coverage is hardly optimum to cover all the necessary elevation angles. While Fig 1 is dramatic in its own right, the data can be viewed in another way that emphasizes even more the importance of low elevation angles. **Fig 2** plots the the *cumulative distribution function*, the total percentage of time 40 meters is open from Boston to Europe, at or below each elevation angle. For example, Fig 2 says that 40 meters is open to Europe from Boston 50% of the time at an elevation angle of 9° or less. The band is open 90%

Fig 1—Screen capture from *HFTA* (HF Terrain Assessment) program showing elevation response for 100-foot high dipole over flat ground on 7.1 MHz, with bar-graph overlay of the statistical elevation angles needed over the whole 11-year solar cycle from New England (Boston) to all of Europe. Even a 100-foot high antenna cannot cover all the necessary angles.

Percentage of Time 40 Meters is Open, At or Below Each Elevation Angle
Boston to Europe

Fig 2—Another way of looking at the elevation statistics from Fig 1. This shows the percentage of time the 40-meter band is open, at or below each elevation angle, on the path from Boston to Europe. For example, the band is open 50% of the time at an angle of 9° or lower. It is open 90% of the time at an angle of 19° or lower.

Percentage of Time 40 Meters is Open, At or Below Each Elevation Angle
Boston to World

Europe	———————	Japan	— — — — —
So. America	—— — ——	Oceana	··············
Africa	—·—·—··	So. Asia	—— ·· ——

Fig 3—The percentage of time the 40-meter band is open, at or below each elevation angle, for various DX paths from Boston: to Europe, South America, southern Africa, Japan, Oceania and south Asias. The angles are predominantly quite low. For example, on the path from Boston to Japan, 90% of the time when the 40-meter band is open, it is open at elevation angles less than or equal to 10°. Achieving good performance at these low takeoff angles requires very high horizontally polarized antennas, or efficient vertically polarized antennas.

Percentage of Time 40 Meters is Open, At or Below Each Elevation Angle
San Francisco to World

Europe	———————	Japan	— — — — —
So. America	—— — ——	Oceania	··············
Africa	—·—·—··	So. Asia	—— ·· ——

Fig 4—The 40-meter statistics from the West Coast: from San Francisco to the rest of the DX world. Here, 90% of the time the path to Europe is open, it is at takeoff angles less than or equal to 11°. No wonder the hams living on mountain tops do best into Europe from the West Coast.

Percentage of Time 80 Meters is Open, At or Below Each Elevation Angle
Boston to World

Europe	———————	Japan	— — — — —
So. America	—— — ——	Oceania	··············
Africa	—·—·—··	So. Asia	—— ·· ——

Fig 5—The situation on 80 meters from Boston to the rest of the DX world. Into Europe, 90% of the time the elevation angle is less than or equal to 20°. Into Japan from Boston, 90% of the time the angle is less than or equal to 12°.

of the time at an elevation angle of 19° or less.

Fig 3 plots the 40-meter elevation-angle data for six major geographic areas around the world from Boston. In general, the overall range of elevation angles for far-distant locations is smaller, and the angles are lower than for closer-in areas. For example, from Boston to southern Asia (India), 50% of the time the takeoff angles are 4° or less. On the path

to Japan from Boston, the takeoff angles is less than or equal to 6° about 70% of the time. These are low angles indeed.

Fig 4 shows similar data for the 40-meter band from San Francisco, California, to the rest of the world. The path to southern Africa from the US West Coast is a very long-distance path, open some 65% of the time it is open at angles of 2° or less! The 40-meter path to Japan involves takeoff angles of 10° or less more than 50% of the time. If you are

Fig 6—From San Francisco to the rest of the world on 80 meters: 90% of the time on the path to Japan, the takeoff angle is less than or equal to 17°; 50% of the time the angle is less than or equal to 10°; 25% of the time the angle is less than or equal to 6°. A horizontally polarized antenna would have to be 600 feet above flat ground to be optimum at 6°!

fortunate enough to have a 100-foot high flattop dipole for 40 meters, at a takeoff angle of 10° the response would be down about 3 dB from its peak level at 20°. At an elevation angle of 5° the response would be about 8 dB down from peak. You can see why the California stations located on mountain tops do best on 40 meters for DXing.

Fig 5 shows the same percentage-of-time data for the 80-meter band from Boston to the world. Into Europe from Boston, the 80-meter elevation angle is 13° or less more than 50% of the time. Into Japan from Boston, 90% of the time the band is open is at a takeoff angle of 13° or less. (Note that these elevation statistics are computed for "undisturbed" ionospheric conditions. There are times when the incoming angles are affected by geomagnetic storms, and generally speaking the elevation angles rise under these conditions.)

Fig 6 shows the 80-meter data from San Francisco to the world. Low elevation angles dominate in this graph and high horizontal antennas would be necessary to optimal coverage. In fact, 50% of the time for all paths, the elevation angle is less than 10°.

In the rest of this chapter, we'll often compare horizontally polarized antennas at practical heights with vertically polarized antennas, usually at takeoff angles of 5° or 10°, angles useful for DX work. But first, let us look at situations where *high* takeoff angles are most useful.

Short/Medium-Range Communications

Not all hams are interested in working stations thousands of miles from them. Traffic handlers and rag chewers may, in fact, only be interested in *nearby* communications—perhaps out to 600 miles from their location.

For example, a ham in Boston may want to talk with his brother-in-law in Cleveland, OH, a path that is just over 550 miles away. Or an operator in Buffalo, NY, may be the net control station (NCS) for a regional net involving the states of New York and New Jersey. She needs to cover distances up to about 300 miles away.

Depending on the time of day, the most appropriate ham frequencies needed for nearby communications are the 40 and 80/75-meter bands, with 160 meters also a possibility during the night hours, particularly during low portions of the sunspot cycle. The elevation angles involved in such nearby distances are usually high, even almost directly overhead for distances beyond ground-wave coverage (which may be as short as a few miles on 40 meters). For example, the distance between the Massachusetts cities of Boston and Worchester is about 40 miles. On 40 meters, 40 miles is beyond ground-wave coverage. So you will need sky-wave signals that use the ionosphere to communicate between these two cities, where the elevation angle is 83°—very nearly straight up.

Hams using vertical antennas for communications with nearby stations may well find that their signals will be below the noise level typical on the lower bands, especially

if they aren't running maximum legal power. Such relatively short-range paths involve so-called *NVIS*, "Near Vertical Incidence Skywave," a fancy name for HF communication systems covering nearby geographic areas. The US military discusses NVIS out to about 500 miles, encompassing the territory a brigade might cover. Elevation angles needed to cover distances from 0 to 500 miles range from about 40° to 90°. This also covers the circumstances involved in amateur communications, particularly in emergency situations.

The following section is adopted from the article "What's the Deal About NVIS?" that appeared in December 2005 *QST*. This article used an example of a hypothetical earthquake in San Francisco to analyze HF emergency communication requirements.

HAM RADIO RESPONSE IN NATURAL DISASTERS

One of San Francisco's somewhat less endearing nicknames is "the city that waits to die." When the *Big Earthquake* does come, you can be assured that all the cell phones and the land-line telephones will be totally jammed, making calling in or out of the San Francisco Bay Area virtually impossible. The same thing occurred in Manhattan on September 11, 2001. The Internet will also be severely affected throughout northern California because of its trunking via the facilities of the telephone network. Commercial electricity will be out

in wide areas because power lines will be down. It's virtually certain that water mains will be out of commission too.

If the repeaters on the hills around the San Francisco Bay Area haven't been damaged by the shaking itself, there will be some ham VHF/UHF voice coverage in the intermediate area, at least until the backup batteries run down. But connecting to the dysfunctional telephone system will be difficult at best through amateur repeaters.

With little or no telephone coverage, an obvious need for ham radio communications to aid disaster relief would be from San Francisco to Sacramento, the state capital. Sacramento is 75 miles northeast of the Bay Area, well outside VHF/UHF coverage, so amateur HF will be required on this radio circuit. On-the-ground communications directly between emergency personnel (including the armed-forces personnel who will be brought into the rescue and rebuilding effort) will often be difficult on VHF/UHF since San Francisco is a hilly place. So HF will probably be needed even for short distance, operator-to-operator or operator-to-com-

munications center work. Throughout the city, portable HF stations will have to be quickly set up and staffed to provide such communications.

Hams used to half jokingly call short range HF communications on 40 and 80 meters "cloud warming." This is an apt description, because the takeoff angles needed to launch HF signals up into the ionosphere and then down again to a nearby station are almost directly upwards. **Table 1** lists the distance and takeoff angles from San Francisco to various cities around the western part of the USA. The distance between San Francisco and Sacramento is about 75 miles, and the optimum takeoff angle is about 78°. Launching such a high-angle signal is best done using horizontally polarized antennas mounted relatively close to the ground.

GEOGRAPHIC COVERAGE FOR NVIS

Figure 7A shows the geographic area coverage around San Francisco for a 100-W, 7.2-MHz station using an inverted V dipole. The center of this antenna is 20 feet above flat

Table 1
Average Elevation Angles for Target Destinations from San Francisco

Location	Distance Miles	Average Elevation Angle, Degrees
San Jose, CA	43	80
Sacramento, CA	75	78
Fresno, CA	160	63
Reno, NV	185	60
Los Angeles	350	44
San Diego	450	42
Portland, OR	530	30
Denver, CO	950	18
Dallas, TX	1500	8

Fig 8—Layout for two band inverted V dipoles for 40 and 80 meters. The two dipoles are fed together at the center and are laid out at right angles to each other to minimize interaction between them. Each end of both dipoles is kept 8 feet above ground for personnel safety.

Fig 7—At A, Predicted 40 meter geographic coverage plot for a 100 W transmitter in December at 0000 UTC (near sunset), for a SSN (Smoothed Sunspot Number) of 20. The antennas used are 20 foot-high inverted V dipoles. At B, 40 meter coverage for same date and time, but for 100 foot-high flattop dipoles. Most of California is well covered with S9 signals in both cases, but there is more susceptibility in the higher dipole case to thunderstorm crashes coming from outside California, for example from Arizona or even Texas. Such noise can interfere with communications inside California.

40 Meter Antenna Responses, Flat, Average Ground

QS0512-Straw03

Fig 9—Elevation plots for different 40 meter antennas above flat ground with average ground characteristics (5 mS/m conductivity and dielectric constant of 13). The 10 foot-high flattop dipole and the 20 foot-high inverted V dipoles both have close to the same characteristics. Note that there is a null in the response of the 100 foot-high flattop dipole at a 42° elevation angle. The gain there is roughly that of a 2 foot-high dipole!

Fig 10—The distribution of lightning strikes across the USA for August 10, 2005 from 2200 to 0000 UTC, in the afternoon California time. There are lots of lightning strikes in the US during the summer—60,898 of them in this two-hour period! (*Courtesy Vaisala Lightning Explorer.*)

ground and the ends are 8 feet high. An actual implementation of such an antenna could be as an 80-meter inverted V, fed in parallel with a 40-meter inverted V dipole at a 90° angle. See **Fig 8**. The 8-foot height puts the ends high enough to prevent RF burns to humans (or most animals). The low height of the antenna above ground means that the azimuthal pattern is omnidirectional for high elevation angles.

Fig 7 was generated using the *VOAAREA* program, part of the *VOACAP* propagation-prediction suite, for the month of December. This was for 0000 UTC, close to sundown, for

a low period of solar activity (Smoothed Sunspot Number, SSN of 20). The receiving stations were also assumed to be using identical inverted-V dipoles.

You can see that almost the whole state of California is covered with S9 signals, minus only a thin slice of land near the Mexican border in the southeast portion of the state, where the signal drops to S7. Signals from Texas are predicted to be only S5 or less in strength. Signals (or thunderstorm static) coming from, say, Louisiana would be several S units weaker than signals from central Texas.

Now take a look at Fig 7B. Here, the date, time and solar conditions remain the same, but now the antennas are 100-foot high flattop dipoles. California is still blanketed with S9 signals, save for an interesting crescent-shaped slice near Los Angeles, where the signal drops down to S7. Close investigation of this intriguing drop in signal strength reveals that the necessary elevation angle, 44°, from San Francisco to this part of southern California falls in the first null of the 100-foot high antenna's elevation pattern. See **Fig 9**, which shows the elevation patterns for five 40-meter antennas at different heights. In the null at a 44° takeoff angle, the 100-foot high dipole is just about equal to a 2-foot high dipole. We'll discuss 2-foot high dipoles in more detail later.

For most of California, the problem with 100-foot high 40-meter antennas is that interfering signals from Texas, Colorado or Washington State will *also* be S9 in San Francisco. So will static crashes coming from thunderstorms all over the West and much of the Gulf Coast. (Ed Farmer, AA6ZM, joked once that the Army doesn't have any problem with interfering signals—they just call in an airstrike. We hams don't generally have this ability, although we occasionally call in the FCC.) See **Fig 10**, which shows a typical distribution of thunderstorms across the US in the late afternoon, California time, in mid-August. There certainly are a lot of thunderstorms raging around the country in the summer.

The signal-to-noise and signal-to-interference ratios for a 20-foot high inverted V dipole will be superior for medium-

NVIS Signals, San Francisco to Los Angeles
December, SSN = Low, 10' Dipoles Average Ground, 100 W

80m SSN=20
40m SSN=20

MUF drops below 7 MHz

D-Layer Absorbtion

Darkness

Sunlight

Signal Strength ("10"=S9 +)

UTC Hours

QS0512-Straw05A

Fig 11—VOACAP calculations for a 350 mile path from San Francisco to Los Angeles, using 10 foot-high flattop dipoles. This plot shows the signal strength in S Units ("S10" = S9+10) for a worst-case month/SSN combination—winter solstice, in December, for a low level of solar activity (SSN = 20). The 40-meter signal drops to a very low level during the night because the MUF drops well below 7.2 MHz. The 80-meter signal drops in the afternoon because of D-layer absorption. For 24-hour communications on this path, the rule of thumb is to select 40 meters during the day and 80 meters during the night.

NVIS Signals, San Francisco to Los Angeles
June, SSN = High, 10' Dipoles Average Ground, 100 W

80m SSN=120
40m SSN=120

MUF stays above 7 MHz

D-Layer Absorbtion

Darkness

Sunlight

Signal Strength ("10"=S9 +)

UTC Hours

QS0512-Straw06A

Fig 12—Signal strengths for the San Francisco to Los Angeles path for a worst-case month/ SSN combination—summer solstice, in June, for a high level of solar activity (SSN = 120). Now 80 meters drops out more dramatically during the daylight hours, due to increased D-layer absorption. At this high level of solar activity, 40 meters remains open 24 hours with reasonable signal levels. However, the NVIS rule-of-thumb still holds: Use 40 meters during the day; 80 meters at night.

range distances, say out to 500 miles from the center, compared to a 100-foot high antenna. The 20-foot high antenna can discriminate against medium-angle thunderstorm noise in the late afternoon coming from the Arizona desert, although it wouldn't help much for thunderstorms in the Sierra Nevada in central Nevada, which are arriving in San Francisco at high angles, along with the desired NVIS signals.

This is the essence of what NVIS means. NVIS exploits the difference in elevation pattern responses of low horizontally polarized antennas compared to higher horizontal antennas, or even verticals. Over the years, many hams have been lead to believe that higher is always better. This is not quite so true for consistent coverage of medium or short distance signals!

If NVIS only involved putting up a low horizontally polarized antenna on 40 meters the story would end here.

However, real cloud warming is more complicated. It also involves the intelligent choice of more than just one operating frequency to achieve reliable all day, all-night communications coverage.

Fig 11 shows the signal strength predicted using *VOACAP* for the 350-mile path from San Francisco to Los Angeles for the month of December for a period of low solar activity (SSN of 20). The antennas used in this case are 10-foot high dipoles, just for some variety. These act almost like 20-foot high Inverted V dipoles. December at a low SSN was chosen as a worst-case scenario because the *winter solstice* occurs on December 21. This is the day that has the fewest hours of daylight in the year. (Contrast this with the *summer solstice*, on June 21, which has the most hours of daylight in the year.) Note that the upper signal limit in Fig 11 is "S10"—a fictitious quantity that allows easier graphing.

S10 is equivalent to S9+, or at least S9+10 dB.

The 40-meter curve in Fig 11 shows that the MUF (maximum usable frequency) actually drops below the 7.2 MHz amateur band after sunset. The signal becomes quite weak for about 14 hours during the night, from about 0300 to 1700 UTC. In a period of low solar activity the 40-meter band thus becomes strictly a *daytime band* on this medium-distance path.

The 80-meter curve in Fig 11 shows strong signals after dusk, through the night and up until about an hour after sunrise. After sunrise, 80 meters starts to suffer absorption in the D layer of the ionosphere and hence the signal strength drops. Here, 80 meters is a true *nighttime band*.

Let's see what happens from San Francisco to Los Angeles during a period of high solar activity (SSN of 120) during the summer solstice in June. **Fig 12** shows that 40 meters now stays open all hours of the day due to the greater number of hours of sunlight in June and because the ionosphere becomes more highly ionized by higher solar activity. Meanwhile, 80 meters still remains a nighttime band during these conditions on this path.

Now, let's look at a shorter-distance path—our 75-mile emergency communications path from San Francisco to Sacramento. We'll again use June during the summer solstice, at a high level of solar activity (SSN of 120) because this represents another worst-case scenario. **Fig 13** shows that 40 meters remains open on this path all day, dropping to a lower signal level just before sunrise. At sunrise, the MUF drops close to 7.2 MHz. 80 meters is still mainly a nighttime band to Sacramento, even though it does yield workable signal levels even during the daylight hours. However, 40 meters is better from 1200 to 0400 UTC, so 40 would be still the right daytime band for this path during the day.

CHOOSING THE RIGHT NVIS FREQUENCY

You can see that a pattern is developing here for efficient NVIS short/medium-distance communications out to 500 miles:

- You should pick a frequency on 40 meters during the day.
- You should pick a frequency on 80 meters during the night.
- You should choose an antenna that emphasizes moderate to high elevation angles, from 40° to almost directly overhead at 90°.

"What about 60 meters?" you might ask. The characteristics on 60 meters fall in-between 40 and 80 meters, although it resembles 40 meters more closely. With characteristics close to that of 40, but with only five channels available and a 50-W power limit, the 60-meter band is of low utility for serious NVIS use.

What about 160 meters? For 100-W level radios, even at the worst-case month or during low solar activity, the critical frequency doesn't fall below 3.8 MHz often enough to destroy the ability to communicate, even for short distances. That is a relief, considering that installing a 160-meter half-wave dipole involves a 255-foot wingspan, and it would need to be elevated at least 30 feet in the center. A short loaded vertical such as a 160-meter mobile whip would have poor response at the high elevation angles needed for NVIS. You could probably put a monster 160-meter horizontal dipole up at a permanent location, but hauling such a thing around in the field would not be an easy task.

SOME OTHER OBSERVATIONS ABOUT NVIS—STRATEGY

You could pose the question about whether NVIS is an operating *mode* or whether it is actually an operating *strategy*. We maintain that NVIS is a strategy. It involves choosing both appropriate frequencies and then appropriate antennas for those frequencies. Fig 13 does show that on short-distance

Fig 13—Signal strengths for a 75 mile path—San Francisco to Sacramento. This is for June and SSN = 120. Either band could be used successfully over the full 24-hour period because signal levels are always higher than S6. But the simple NVIS rule-of-thumb still holds: Use 40 meters during the day; 80 meters at night. This simplifies giving instructions to operators unaccustomed to the use of HF.

paths, such as between San Francisco and Sacramento, you could stay on 80 meters all day and night. But if you have to give a single rule-of-thumb to operators who are not very experienced at operating HF, we would tell them to operate on the higher frequency band during the day and on the lower frequency band at night.

SOME OTHER OBSERVATIONS ABOUT NVIS—ANTENNA HEIGHT

Some NVIS aficionados have advocated placing dipoles only a few feet over ground, something akin to saying, "If low is good for NVIS, then lower must be even better." Now we are not claiming that a very low antenna *won't* work in specific instances—for example, covering a small state such as Rhode Island or even just the San Francisco Bay Area.

It certainly is convenient to mount a 40-meter dipole

on some 2-foot high red traffic cones! You should be very skeptical, however, about the ability of such antennas to cover all of a large state, such as California or Texas, especially on 80 meters. **Fig 14** shows the computed elevation responses for a number of 80-meter antennas, including a 2-foot-high dipole.

Fig 15B shows the 80 meter geographic coverage plot for 2-foot-high flattop dipoles, compared with the plot in Fig 15A for 20-foot-high inverted V dipoles on both ends of the path. The 2-foot-high dipoles produce about two S-units less signal across all of California than the 20-foot-high inverted V dipoles, at 0300 UTC in December, with an SSN of 20. The reason is that a low dipole will suffer more losses in the ground under it.

The differential between California signals and possible interfering signals from, say, New Mexico, is predicted to be four S-units, the same as it is for the higher inverted V dipole

Fig 14—Elevation response patterns for 80 meter antennas over average soil. The shapes track each other rather well, remaining parallel for heights from 2 to 66 feet over flat ground. The 2 foot dipole is substantially down, about 9 dB, from the 20 foot inverted V dipole at all angles.

Fig 15—Geographic coverage plots for December, SSN = 20, 0300 UTC. At A, antennas are 20 foot-high inverted V dipoles over Average soil. At B, antennas are 2-foot-high flattop dipoles over Average soil. The response for the 2-foot-high antennas is down about 2 S Units, 8 to 12 dB for a typical communications receiver.

at 20 feet. Thus there is no real advantage in terms of signal-to-interference ratio or signal-to-noise ratio (for thunderstorm static crashes) for either height. This is because the shape of all the response curves in Fig 14 below 20 feet essentially track each other in parallel.

However, the lower the antenna, the lower the transmitted signal strength. Physics remain physics. And if you are in an emergency situation operating on batteries, you could reduce power from 100 W to 10 W with a 20-foot high inverted-V antenna and still maintain the same signal strength as a 2-foot high dipole at 100W.

LOW NVIS ANTENNAS AND LOCAL POWERLINE NOISE

Some advocates of really low antennas have stated that the received noise is much lower than that received from higher antennas, and this therefore leads to better signal-to-noise ratios (SNR). How much this is true depends on the source of the noise. If the noise comes from distant thunderstorms, then the SNR advantage going to a 2-foot antenna from a 20-foot-high one is insignificant, as Fig 15 indicates.

If noise is from an arcing insulator on a HV power line half a mile away, that noise will arrive at the antenna as a ground-wave signal. We calculate that the 2-foot antenna receives 4.4 dB less noise by groundwave than a 20-foot-high inverted V dipole. However, at an incoming elevation angle of 45º—suitable for a signal going from Los Angeles to San Francisco—the signal would be down 7.1 dB on the low dipole compared to the higher antenna. The net loss in SNR for the 2-foot-high dipole is thus 7.1– 4.4 or 2.7 dB. Close, but no cigar. Summarizing about really low NVIS antennas:

- A 2-foot-high dipole yields weaker signals, but without an SNR advantage compared to its more elevated brethren.
- A 2-foot-high dipole is a lot easier to trip over at night. We would call this a "knee biter" (or maybe an "ankle biter" if you're really tall).
- You (and your dog) can easily get RF burns from an antenna that is only 2 feet off the ground.

This is not a winning strategy to make friends or QSOs, it seems. But still, a really low dipole may serve your short-range communication needs just fine. But remember, that just as "higher is better" isn't universally true for NVIS (or even longer range) applications, "lower is better" isn't a panacea either.

ELEVATION ANGLES FOR MODERATE DISTANCES ON 75/80 METERS

Fig 16 shows the elevation angles statistics for a 75-meter, 550-mile path from Boston to Cleveland, together with overlays of the elevation patterns for several different types of antennas. These elevation statistics cover all parts of the 11-year solar cycle for this path. The responses for the popular G5RV antenna (described later in this chapter) are shown for two different heights above flat ground: 50 and 100 feet. An 80-meter half-wave sloper ("full sloper") and an 80-meter ground-plane antenna are also shown. All

Fig 16—80/75-meter elevation statistics for all portions of the 11-year solar cycle for the path from Cleveland, Ohio, to Boston, Massachusetts, together with the elevation responses for four different multiband antennas. The 100-foot high horizontally polarized G5RV performs well over the entire range of necessary takeoff elevation angles.

antenna patterns are for "average ground" constants of 5 mS/m conductivity and a dielectric constant of 13.

At the statistically most significant takeoff angles around 50°, the two horizontally polarized G5RV antennas are about equal. At the second-highest elevation peak near 30°, the 100-foot G5RV has about a 4-dB advantage over its lower counterpart. The full sloper has comparable performance to the 100-foot high G5RV from 1° to about 20° and then gradually rises to its peak at angles higher than 70°. The full sloper is superior to the 50-foot horizontal G5RV at low takeoff elevation angles. The 80-meter ground plane has a deep null directly overhead. At an elevation angle of 70° it is down some 16 dB compared to the 50-foot high horizontal G5RV.

The advantage of antennas suitable for high-angle radiation was vividly demonstrated during a 75-meter QSO one fall evening between N6BV/1 in southern New Hampshire and W1WEF in central Connecticut. This involved a distance of about 100 miles and W1WEF was using his Four Square vertical array. Although W1WEF's signal was S9 on the Four Square, N6BV/1 suggested an experiment. Instead of connecting the so-called "dump power" connector on his Comtek ACB-4 hybrid phasing coupler to a 50-Ω dummy load (the normal configuration), W1WEF switched the dump power to his 100-foot high 80-meter horizontal dipole. W1WEF's signal came up more than 20 dB! The approximately 100-W of power that would otherwise be "wasted" in the dummy load was converted to useful signal.

ELEVATION ANGLES FOR MODERATE DISTANCES ON 40 METERS

Fig 17 shows the situation for the 40-meter band, from Boston to Cleveland, together with the same antennas used for 80 meters in Fig 16. Note that the 100-foot high horizontally

40 Meters, Cleveland to Boston, Comparison of Antennas

Legend:
- 40m Stats
- G5RV 100'
- G5RV 50'
- 40m Full Sloper
- 40m GP Ave.

Fig 17—40-meter elevation statistics for the Cleveland to Boston path, together with elevation patterns for four antennas. Here, the 100-foot high horizontally polarized G5RV would have a null in the middle of the range of elevation angles needed for consistent performance on this path. For multiband use on this path to relatively nearby stations, the 50-foot high horizontal antenna would be a better choice than the 100-foot high antenna.

polarized G5RV has about a 16-dB null at an elevation angle of 43°. This doesn't affect things for low elevation angles, but it certainly has a profound effect on signals arriving between about 30° to 60°, especially when compared to the 50-foot high horizontal G5RV. The 40-meter full sloper beats out the high horizontal antenna from about 35° to 50°. And the

ground plane is obviously not the antenna of choice for this moderate-range path from Boston to Cleveland, although it is still a good performer on longer-distance paths, with their low takeoff angles.

A 100-foot high multiband dipole is about ⅜-λ high on 75/80 meters. It is an excellent antenna for general-purpose local and DXing operation. But the same dipole used on 40 meters becomes ¾-λ high. At that height, the nulls in its elevation pattern give large holes in coverage for nearby 40-meter contacts. Many operators have found that a 40- to 50-foot high dipole on 40 meters gives them far superior performance for close-in QSOs, when compared to a high dipole, or even a high 2-element 40-meter Yagi.

NVIS SUMMARY

The use of NVIS strategies to cover close-in and intermediate distance communications within about 600 miles involves the intelligent choice of low HF frequencies. As a rule-of-thumb for ham band NVIS, 40 meters is recommended for use during the day; 80 meters during the night.

NVIS involves the choice of antennas suitable for this strategy. Horizontally polarized dual-band 80 and 40-meter flattop dipoles that are mounted higher than about 10 feet high will work adequately for portable operations. Dual-band 80 and 40-meter inverted V dipoles supported 20 feet above the ground at the center can also work well in portable operations.

Single-band 40-meter flattop antennas about 30 feet high and 80-meter flattop antennas about 60 feet high can do a good job for fixed locations.

Horizontal Antennas for the Low Bands

As shown in Chapter 3, The Effects of Ground, and here, radiation angles from horizontal antennas are a very strong function of the height above ground in wavelengths. Typically for DX work heights of λ/2 to 1 λ are considered to be a minimum. As we go down in frequency these heights become harder to realize. For example, a 160-meter dipole at 70 feet is only 0.14 λ high. This antenna will be very effective for local and short distance QSOs but not very good for DX work. Despite this limitation, horizontal antennas are very popular on the lower bands because the low frequencies are often used for short range communications, local nets and rag chewing. Also horizontal antennas do not require extensive ground systems to be efficient.

DIPOLE ANTENNAS

Half-wave dipoles and variations of these can be a very good choice for a low band antenna. A variety of possibilities are shown in **Fig 18**. An untuned or "flat" feed line is a logical choice on any band because the losses are low, but this generally limits the use of the antenna to one band. Where only single-band operation is wanted, the λ/2 antenna fed

with open-wire line is one of the most popular systems on the 3.5 and 7-MHz bands.

If the antenna is a single-wire affair, its impedance is in the vicinity of 60 Ω, depending on the height and the ground characteristics. The most common way to feed the antenna is with 50- or 75-Ω coaxial line. Heavy coaxial lines present support problems because they are a concentrated weight at the center of the antenna, tending to pull the center of the antenna down. This can be overcome by using an auxiliary pole to take at least some of the weight of the line. The line should come away from the antenna at right angles, and it can be of any length.

Folded Dipoles

A folded dipole (Fig 18B and C) has an impedance of about 300 Ω, and can be fed directly with any length of 300-Ω line. The folded dipole can be made of ordinary wire spaced by lightweight wooden or plastic spacers, 4 or 6 inches long, or a piece of 300 or 450-Ω twin-lead or ladder line.

A folded dipole can be fed with a 600-Ω open wire line with only a 2:1 SWR, but a nearly perfect match can be ob-

$$\frac{468}{f\,(MHz)}$$

72 Ω Twin—lead
or Coaxial Lines
Any Length

C

(A)

$$\frac{468}{f\,(MHz)}$$

Two #12 or #14 Wires,
Spaced 4 to 6 Inches

300 Ω Twin—Lead
Any Length

C

(B)

$$\frac{468}{f\,(MHz)}$$

300 Ω
Twin -Lead

Weatherproof Seal

300 Ω Twin -Lead
Any Length

C

(C)

$$\frac{468}{f\,(MHz)}$$

Three #12 or #14 Wires,
Spaced 4 to 6 Inches with
Wood or Plastic Spacers

#14 Spaced 5 Inches
or #12 Spaced 6 Inches

C

(D)

Fig 18—Half-wavelength antennas for single band operation. The multiwire types shown in B, C and D offer a better match to the feeder over a somewhat wider range of frequencies but otherwise the performances are identical. The feeder should run away from the antenna at a right angle for as great a distance as possible. In the coupling circuits shown, tuned circuits should resonate to the operating frequency. In the series-tuned circuits of A, B, and C, high L and low C are recommended, and in D the inductance and capacitance should be similar to the output-amplifier tank, with the feeders tapped across at least ½ the coil. The tapped-coil matching circuit shown in Chapter 25 can be substituted in each case.

tained with a three-wire dipole fed with either 450-Ω ladder line or 600-Ω open wire line. One advantage of the two- and three-wire antennas over the single wire is that they offer a better match over a wider band. This is particularly important if full coverage of the 3.5-MHz band is contemplated.

Inverted-V Dipole

The halves of a dipole may be sloped to form an in-

verted V, as shown in **Fig 19**. This has the advantages of requiring only a single high support and less horizontal space. There will be some difference in performance between a normal horizontal dipole and the inverted V as shown by the radiation patterns in **Fig 20**. There is small loss in peak gain and the pattern is less directional.

Sloping of the wires results in a raising of the resonant frequency and a decrease in feed-point impedance and

Fig 19—The inverted-V dipole. The length and apex angle should be adjusted as described in the text.

bandwidth. Thus, for the same frequency, the length of the dipole must be increased somewhat. The angle at the apex is not critical, although it should probably be made no smaller than 90°. Because of the lower impedance, a 50-Ω line should be used. For those who are dissatisfied with anything but a perfect match, the usual procedure is to adjust the angle for lowest SWR while keeping the dipole resonant by adjustment of length. Bandwidth may be increased by using multiconductor elements, such as a cage configuration.

PHASED HORIZONTAL ARRAYS

Phased arrays with horizontal elements, which provide some directional gain, can be used to advantage at 7 MHz, if they can be placed at least 40 feet above ground. At 3.5 MHz heights of 70 feet or more are needed for any real advantage.

Fig 20—At A, elevation and at B, azimuthal radiation patterns comparing a normal 80-meter dipole and an inverted-V dipole. The center of both dipoles is at 65 feet and the ends of the inverted V are at 20 feet. The frequency is 3.750 MHz.

Fig 21—Directional antennas for 7 MHz. To realize any advantage from these antennas, they should be at least 40 feet high. At A, system is bidirectional. At B, system is unidirectional in a direction depending upon the tuning conditions of the parasitic element. The length of the elements in either antenna should be exactly the same, but any length from 60 to 150 feet can be used.
If the length of the antenna at A is between 60 and 80 feet, the antenna will be bidirectional along the same line on both 7 and 14 MHz. The system at B can be made to work on 7 and 14 MHz in the same way, by keeping the length between 60 and 80 feet.

Many of the driven arrays discussed in Chapter 8 and even some of the Yagis discussed in Chapter 11 can be used as fixed directional antennas. If a bidirectional characteristic is desired, the W8JK array, shown in **Fig 21A**, is a good one. If a unidirectional characteristic is required, two elements can be mounted about 20 feet apart and provision included for tuning one of the elements as either a director or reflector, as shown in Fig 21B.

The parasitic element is tuned at the end of its feed line with a series or parallel-tuned circuit (whichever would normally be required to couple power into the line), and the proper tuning condition can be found by using the system for receiving and listening to distant stations along the line to the rear of the antenna. Tuning the feeder to the parasitic element can minimize the received signals from the back of the antenna. This is in effect adjusting the antenna for maximum front-to-back ratio. Maximum front-to-back does not occur at the same point as maximum forward gain but the loss in forward gain is very small. Adjusting the antenna for maximum forward gain (peaking received signals in the forward direction) may increase the forward gain slightly but will almost certainly result in relatively poor front-to-back ratio.

A MODIFIED EXTENDED DOUBLE ZEPP

If the distance between the available supports is greater than λ/2 then a very simple form of a single wire collinear array can be used to achieve significant gain. The *extended double Zepp* antenna has long been used by amateurs and is discussed in Chapter 8, Multielement Arrays. A simple variation of this antenna with substantially improved bandwidth can be very useful on 3.5 and 7.0 MHz. The following material has been taken from an article by Rudy Severns, N6LF, in *The ARRL Antenna Compendium Vol 4*.

The key to improving the characteristics of a standard double-extended Zepp is to modify the current distribution. One of the simplest ways to do this is to insert a reactance(s) in series with the wire. This could either be an inductor(s) or a capacitor(s). In general, a series capacitor will have a higher Q and therefore less loss. With either choice it is desirable to use as few components as possible.

As an initial trial at 7 MHz, only two capacitors, one on each side of the antenna, were used. The value and position of the capacitors was varied to see what would happen. It quickly became clear that the reactance at the feed point could be tuned out by adjusting the capacitor value, making the antenna look essentially like a resistor over the entire band. The value of the feed-point resistance could be varied from less than 150 Ω to over 1500 Ω by changing the location of the capacitors and adjusting their values to resonate the antenna.

A number of interesting combinations were created. The one ultimately selected is shown in **Fig 22**. The antenna is 170 feet in length. Two 9.1 pF capacitors are located 25 feet out each side of the center. The antenna is fed with 450-Ω transmission line and a 9:1 three-core Guanella balun used

Fig 22—Schematic for modified N6LF Double Extended Zepp. Overall length is 170 feet, with 9.1 pF capacitors placed 25 feet each side of center.

26° Elevation
0 dB=9.05 dBd

7.150 MHz

Fig 23—Azimuth pattern for N6LF Double Extended Zepp (solid line), compared to classic Double Extended Zepp (dashed line). The main lobe for the modified antenna is slightly broader than that of the classic model, and the sidelobes are suppressed better.

at the transmitter to convert to 50 Ω. The transmission line can be any convenient length and it operates with a very low SWR.

That's all there is to it. The radiation pattern, overlaid with that for a standard DEZepp for comparison, is shown in **Fig 23**. The sidelobes are now reduced to below 20 dB. The main lobe is now 43° wide at the 3-dB points, as opposed to 35° for the original DEZepp. The antenna has gain over a dipole for > 50° now and the gain of the main lobe has dropped only 0.2 dB below the original DEZepp.

Experimental Results

The antenna was made from #14 wire and the capacitors were made from 3.5-inch sections of RG-213, shown in **Fig 24A**. Note that great care should be taken to seal out moisture in these capacitors. The voltage across the capacitor for 1.5 kW will be about 2000 V so any corona will quickly destroy the capacitor.

A silicon sealant was used and then both ends covered

Fig 24—Construction details for series capacitor made from RG-213 coaxial cable. At A, the method used by N6LF is illustrated. At B, a suggested method to seal capacitor better against weather is shown, using a section of PVC pipe with end caps.

Fig 25—Measured SWR curve across 40-meter band for N6LF DEZepp.

Fig 26—75/80-meter modified Double Extended Zepp, designed using *NEC Wires*. At A, a schematic is shown for antenna. At B, SWR curve is shown across 75/80-meter band. Solid line shows measured curve for W7ISV antenna, which was pruned to place SWR minimum higher in the band. The dashed curve shows the computed response when SWR minimum is set to 3.8 MHz.

with coax seal, finally wrapping it with plastic tape. The solder balls indicated on the drawing are to prevent wicking of moisture through the braid and the stranded center conductor. This is a small but important point if long service out in the weather is expected. An even better way to protect the capacitor would be to enclose it in a short piece of PVC pipe with end caps, as shown in Fig 24B.

Note that all RG-8 type cables do not have exactly the same capacitance per foot and there will also be some end effect adding to the capacitance. If possible the capacitor should be trimmed with a capacitance meter. It isn't necessary to be too exact—the effect of varying the capacitance ±10% was checked and the antenna still worked fine.

The results proved to be close to those predicted by the computer model. **Fig 25** shows the measured value for SWR across the band. These measurements were made with a Bird directional wattmeter. The worst SWR is 1.35:1 at the low end of the band.

Dick Ives, W7ISV, erected an 80-meter version of the antenna, shown in **Fig 26A**. The series capacitors are 17 pF. Since he isn't interested in CW, Dick adjusted the length for the lowest SWR at the high end of the band, as shown in the SWR curve (Fig 26B). The antenna could have been tuned somewhat lower in frequency and would then provide an SWR < 2:1 over the entire band, as indicated by the dashed line.

This antenna provides wide bandwidth and moderate gain over the entire 75/80-meter band. Not many antennas will give you that with a simple wire structure.

Vertical Antennas

On the low bands quarter-wave high vertical antennas become increasingly attractive, especially for DX work, because they provide a means for lowering the radiation angle. This is especially true where practical heights for horizontally polarized antennas are too low. In addition, verticals can be very simple and unobtrusive structures. For example, it is very easy to disguise a vertical as a flagpole. In fact an actual flagpole may be used as a vertical. Performance of a vertical is determined by several factors:

- Height of the vertical portion of the radiator
- The ground or counterpoise system efficiency, if one is used
- Ground characteristics in the near- and far-field regions
- The efficiency of loading elements and matching networks

THE HALF-WAVE VERTICAL DIPOLE (HVD)

The simplest form of vertical is that of a half-wave vertical dipole, an HVD. This is a horizontal dipole turned 90° so that it is perpendicular to the ground under it. Of course, the top end of such an antenna must be at least a half wave above the ground or else it would be touching the ground. This poses quite a construction challenge if the builder wants a free-standing low-frequency antenna. Hams fortunate enough to have tall trees on their property can suspend wire HVDs from these trees. Similarly, hams with two tall towers can run rope catenaries between them to hold up an HVD.

A vertical half-wave dipole has some operational advantages compared to a more-commonly used vertical configuration—the quarter-wave vertical used with some sort of above-ground counterpoise or an on-ground radial system. See **Fig 27** and 27B, which shows the two configurations discussed here. In each case, the lowest part of each antenna is 8 feet above ground, to prevent passersby from being able to touch any live wire. Each antenna is assumed to be made of #14 wire resonant on 80 meters.

Feeding a Half-Wave Vertical Dipole

Fig 28 compares elevation patterns for the two antennas for "average ground." You can see that the half-wave vertical dipole has about 1.5 dB higher peak gain, since it compresses the vertical elevation pattern down somewhat closer to the horizon than does the quarter-wave ground plane. Another advantage to using a half-wave radiator besides higher gain is that less horizontal "real estate" is needed compared to a quarter-wave vertical with its horizontal radials.

The obvious disadvantage to an HVD is that it is taller than a quarter-wave ground plane. This requires a higher support (such as a taller tree) if you make it from wire, or a longer element if you make it from telescoping aluminum tubing.

Another problem is that theory says you must dress the feed line so that it is perpendicular to the half-wave radiator. This means you must support the coax feed line above ground for some distance before bringing the coax down to ground level. A question immediately arises: How far must you go out horizontally with the feed line before going to ground level to eliminate common-mode currents that are radiated onto the coax shield? Such common-mode currents will affect the feed-point impedance as well as the radiation pattern for the antenna system. Quite a bit of distortion in the azimuthal pattern can be created if common-mode currents aren't suppressed, usually by using a common-mode choke, also known as a current balun.

Fig 27—At A, a 80-meter half-wave vertical dipole elevated 8 feet above the ground. The feed line is run perpendicularly away from the dipole. At B, a "ground plane" type of quarter-wave vertical, with four elevated resonant radials. Both antennas are mounted 8 feet above the ground to keep them away from passersby.

Fig 28—A comparison of the elevation patterns for the two antennas in Fig 27. The peak gain of the HVD is about 1.5 dB higher than that for the quarter-wave ground-plane radiator with radials.

Fig 29—A 20-meter HVD whose bottom is 8 feet above ground. This is fed with a λ/2 of RG-213 coax. This system uses a common-mode choke at the feed point and another λ/4 down the line. The resulting azimuthal radiation pattern is within 0.4 dB of being perfectly circular. The "wingspan" of this antenna system is 27 feet from the radiator to the point where the coax comes to ground level.

Constructing such a common-mode choke is very simple: Three large ferrite beads are slipped over the coax (before the connectors are soldered on or else they won't fit!) and taped in place. The only problem with this scheme is that an additional support (some sort of "skyhook") is required to support the coax horizontally. Let's try to simplify the installation, by slanting the feed-line coax down to ground from the feed point at a fairly steep angle of about 30° from vertical. See **Fig 29**.

Note that the bottom end of the coax in Fig 29 is grounded to a ground rod. This serves several purposes—this serves as a mechanical connection to hold the coax in place and it provides some protection against lightning strikes. Now, as a purely practical matter, just how picky are we being here? What if we skip the second common-mode choke and just use one at the feed point? The computer models predicts that there will be some distortion in the azimuthal pattern—about 1.1 dB worth. Whether this is serious is up to you. However, you may find other problems with common-mode currents on the coax shield—problems such as RF in the shack or variable SWR readings depending on the way coax is routed in the shack. The addition of three extra ferrite beads to suppress the common-mode currents is cheap insurance.

Later in this chapter we'll discuss shortened vertical antennas, ones arranged both as vertical dipoles and as vertical monopoles with radial systems.

MONOPOLE VERTICALS WITH GROUND PLANE RADIALS

For best performance the vertical portion of a ground-plane type of antenna should be λ/4 or more, but this is not an absolute requirement. With proper design, antennas as short as 0.1 λ or even less can be efficient and effective. Antennas shorter than λ/4 will be reactive and some form of loading and perhaps a matching network will be required.

If the radiator is made of wire supported by nonconducting material, the approximate length for λ/4 resonance can be found from:

$$\ell_{feet} = \frac{234}{f_{MHz}} \qquad \text{(Eq 1)}$$

For tubing, the length for resonance must be shorter than given by the above equation, as the length-to-diameter ratio is lower than for wire (see Chapter 2, Antenna Fundamentals). For a tower, the resonant length will be shorter still. In any case, after installation the antenna length (height) can be adjusted for resonance at the desired frequency.

The effect of ground characteristics on losses and elevation pattern is discussed in detail in Chapter 3, The Effects of Ground. The most important points made in that discussion are the effect of ground characteristics on the radiation pattern and the means for achieving low ground-loss resistance in a buried ground system. As ground conductivity increases, low-angle radiation improves. This makes a vertical very attractive to those who live in areas with good ground conductivity. If your QTH is on a saltwater beach, then a vertical would be very effective, even when compared to horizontal antennas at great height.

When a buried-radial ground system is used, the efficiency of the antenna will be limited by the loss resistance of the ground system. The ground can be a number of radial wires extending out from the base of the antenna for about λ/4. Driven ground rods, while satisfactory for electrical safety and for lightning protection, are of little value as an RF ground for a vertical antenna, except perhaps in marshy or beach areas. As pointed out in Chapter 3, many long radials are desirable. In general, however, a large number of short radials are preferable to only a few long radials, although the best system would have 60 or more radials longer than λ/4. An elevated system of radials or a ground screen (*counterpoise*) may be used instead of buried radials, and can result in an efficient antenna.

ELEVATED RADIALS AND COUNTERPOISES

Elevated radials, isolated from ground, can be used in place of an extensive buried radial system. Work by Al Christman, K3LC (ex-KB8I), has shown that 4 to 8 elevated radials can provide performance comparable to a 120 λ/4-long buried wires. This is especially important for the low bands, where such a buried ground system is very large and impractical for most amateurs. An elevated ground system is sometimes referred to as a *ground plane* or *counterpoise*. **Fig 30** compares buried and elevated ground systems, showing the difference in current flow in the two systems.

An elevated ground can take several forms. A number of wires arranged with radial symmetry around the base of the antenna is shown in Fig 30B. Four radials are normally

Fig 30—How earth currents affect the losses in a short vertical antenna system. At A, the current through the combination of C_E and R_E may be appreciable if C_E is much greater than C_W, the capacitance of the vertical to the ground wires. This ratio can be improved (up to a point) by using more radials. By raising the entire antenna system off the ground, C_E (which consists of the series combination of C_{E1} and C_{E2}) is decreased while C_W stays the same. The radial system shown at B is sometimes called a *counterpoise*.

used, but as few as two, or as many as eight, can be used. For a given height of vertical, the length of the radials can be adjusted to resonate the antenna. For a $\lambda/4$ vertical, the radials are normally $\lambda/4$ long.

In the case of a multiband vertical, two or more sets of radials, with different lengths, may be interleaved. The radials associated with each band are adjusted for resonance on their associated band.

A counterpoise is most commonly a system of elevated radials, where the radial wires are interconnected with jumpers, as shown in **Fig 31**. As illustrated in Fig 30, the purpose of the elevated-ground system is to provide a return path for the displacement currents flowing in the vicinity of the antenna. The idea is to minimize the current flowing through the ground itself, which is usually very lossy. By raising the radials above ground most of the current will flow in the radials, which are good conductors. This allows a simple radial system to provide a very efficient ground. However, there is a price to be paid for this.

The ground system now has a direct effect on the feedpoint impedance, introducing reactance as well as resistance, and is relatively narrow band. For a given vertical height, the

Fig 31—Counterpoise, showing the radial wires connected together by cross wires. The length of the perimeter of the individual meshes should be < $\lambda/4$ to prevent undesired resonances. Sometimes the center portion of the counterpoise is made from wire mesh.

Table 2

Illustration of the effect of variable vertical height (L$_1$) on elevated radial length (L2) and R$_R$.
#12 wire, elevated 5 feet over average ground at 3.525 MHz.

L$_1$ (λ)	L$_1$ (feet)	L$_2$ (feet)	R$_R$ (Ω)
0.225	62.8	94	28.8
0.25	69.8	67	38.4
0.27	75.0	45	51.0
0.3	83.7	24	75.9

Fig 32—The ground-plane antenna. Power is applied between the base of the vertical radiator and the center of the ground plane, as indicated in the drawing. Decoupling from the transmission line and any conductive support structure is highly desirable.

radial length must be adjusted to resonate the antenna. The length of the radials must be readjusted for each band if a multiband vertical is used. As pointed out above, this usually means the installation of a set of radials for each band. To minimize current flowing in the ground, the antenna, ground plane and feed line must be isolated from ground for RF. More on this later.

The height of the vertical does not have to be exactly λ/4. Other lengths may be used and the antenna may be resonated by adjusting the length of the radials. **Table 2** gives a comparison between three different vertical lengths in an antenna using four elevated radials at 3.525 MHz.

An important feature of Table 2 is the dramatic reduction in radial length (L$_2$) with even a small increase in vertical height (L$_1$). For example, increasing the height by 5 feet reduces the radial length by 22 feet on 80 meters. On the other hand even a small decrease in L$_1$ can cause a substantial increase in L$_2$. This would be very undesirable, since the area required by the radials is already considerable. Notice also that the small increase in height raises R$_R$ to 51 Ω. This trick of increasing the height slightly to reduce the size of the elevated ground system and to increase the input resistance can be very useful. In a following section the use of *top loading* for short antennas will be discussed. Top loading can also be used on a λ/4 vertical to achieve the same effect

as increasing the height—the ability to use shorter radials and a better match.

GROUND-PLANE ANTENNAS

The ground-plane antenna is a λ/4 vertical with four radials, as shown in **Fig 32**. The entire antenna is elevated above ground. A practical example of a 7-MHz ground-plane antenna is given in **Fig 33**. As explained earlier, elevating the antenna reduces the ground loss and lowers the radiation angle somewhat. The radials are sloped downward to make the feed-point impedance closer to 50 Ω.

The feed-point impedance of the antenna varies with the height above ground, and to a lesser extent varies with the ground characteristics. **Fig 34** is a graph of feed-point resistance (R$_R$) for a ground-plane antenna with the radials parallel to the ground. R$_R$ is plotted as a function of height above ground. Notice that the difference between perfect ground and average ground (ε=13 and σ = 0.005 S/m) is small, except when quite close to ground. Near ground R$_R$ is between 36 and 40 Ω. This is a reasonable match for 50-Ω feed line but as the antenna is raised above ground R$_R$ drops to approximately 22 Ω, which is not a very good match. The feed-point resistance can be increased by sloping the radials downward, away from the vertical section.

The effect of sloping the radials is shown in **Fig 35**. The

Fig 33—A ground-plane antenna is effective for DX work on 7 MHz. Although its base can be any height above ground, losses in the ground underneath will be reduced by keeping the bottom of the antenna and the ground plane as high above ground as possible. Feeding the antenna directly with 50-Ω coaxial cable will result in a low SWR. The vertical radiator and the radials are all λ/4 long electrically. Contrary to popular myth, the radials need not necessarily be 5% longer than the radiator. Their physical length will depend on their length-to-diameter ratios, the height over ground and the length of the vertical radiator, as discussed in text.

Fig 34—Radiation resistance of a 4-radial ground-plane antenna as a function of height over ground. Perfect and average ground are shown. Frequency is 3.525 MHz. Radial angle (θ) is 0°.

Fig 35—Radiation resistance and resonant length for a 4-radial ground-plane antenna > 0.3 λ above ground as a function of radial droop angle (θ).

Fig 36—Radiation resistance and resonant length for a 4-radial ground-plane antenna for various heights above average ground for radial droop angle θ = 45°.

graph is for an antenna well above ground (> 0.3 λ). Notice that $R_R = 50 \, \Omega$ when the radials are sloped downward at an angle of 45°, a convenient value. The resonant length of the antenna will vary slightly with the angle. In addition, the resonant length will vary a small amount with height above the ground. It is for these reasons, as well as the effect of conductor diameter, that some adjustment of the radial lengths is usually required. When the ground-plane antenna is used on the higher HF bands and at VHF, the height above ground is usually such that a radial sloping angle of 45° will give a good match to 50-Ω feed line.

The effect of height on R_R with a radial angle of 45° is shown in **Fig 36**. At 7 MHz and lower, it is seldom possible to elevate the antenna a significant portion of a wavelength and the radial angle required to match to 50-Ω line is usually of the order of 10° to 20°. To make the vertical portion of the antenna

Fig 37—The folded monopole antenna. Shown here is a ground plane of four λ/4 radials. The folded element may be operated over an extensive counterpoise system or mounted on the ground and worked against buried radials and the earth. As with the folded dipole antenna, the feed-point impedance depends on the ratios of the radiator conductor sizes and their spacing.

Fig 38—A choke balun with sufficient impedance to isolate the antenna properly can be made by winding coaxial cable around a section of plastic pipe. Suitable dimensions are given in the text.

as long as possible, it may be better to accept a slightly poorer match and keep the radials parallel to ground.

The principles of the folded dipole (Fig 18) can also be applied to the ground-plane antenna, as shown in **Fig 37**. This is the *folded monopole* antenna. The feed-point resistance can be controlled by the number of parallel vertical conductors and the ratios of their diameters.

As mentioned earlier, it is important in most installations to isolate the antenna from the feed line and any conductive supporting structure. This is done to minimize the return current conducted through the ground. A return current on the feed line itself or the support structure can drastically alter the radiation pattern, usually for the worse. For these reasons, a balun (see Chapter 26, Coupling the Line to the Antenna) or other isolation scheme must be used. 1:1 baluns are effective for the higher bands but at 3.5 and 1.8 MHz commercial baluns often have too low a shunt inductance to provide adequate isolation. It is very easy to recognize when the isolation is inadequate. When the antenna is being adjusted while watching an isolated impedance or SWR meter, adjustments may be sensitive to your touching the instrument. After adjustment and after the feed line is attached, the SWR may be drastically different. When the feed line is inadequately isolated, the apparent resonant frequency or the length of the radials required for resonance may also be significantly different from what you expect.

In general, an isolation choke inductance of 50 to 100 μH will be needed for 3.5 and 1.8-MHz ground-plane antennas. One of the easiest ways to make the required isolation choke is to wind a length of coaxial cable into a coil as shown in **Fig 38**. For 1.8 MHz, 30 turns of RG-213 wound on a 14-inch length of 8-inch diameter PVC pipe, will make a very good isolation choke that can handle full legal power continuously. A smaller choke could be wound on 4-inch diameter plastic drain pipe using RG-8X or a Teflon insulated cable. The important point here is to isolate or decouple the antenna from the feed line and support structure.

A full-size ground-plane antenna is often a little impractical for 3.5-MHz and quite impractical for 1.8 MHz, but it can be used at 7 MHz to good advantage, particularly for DX work. Smaller versions can be very useful on 3.5 and 1.8 MHz.

EXAMPLES OF VERTICALS

There are many possible ways to build a vertical antenna—the limits are set by your ingenuity. The primary problem is creating the vertical portion of the antenna with sufficient height. Some of the more common means are:

- A dedicated tower
- Using an existing tower with an HF Yagi on top
- A wire suspended from a tree limb or the side of a building
- A vertical wire supported by a line between two trees or other supports
- A tall pole supporting a conductor
- Flagpoles
- Light standards
- Irrigation pipe
- TV masts

If you have the space and the resources, the most straightforward means is to erect a dedicated tower for a vertical. While this is certainly an effective approach, many amateurs do not have the space or the funds to do this, especially if they already have a tower with an HF antenna on the top. The existing tower can be used as a top-loaded vertical, using shunt feed and a ground radial system. A system like this is shown in **Fig 39B**.

For those who live in an area with tall trees, it may be possible to install a support rope between two trees, or between a tree and an existing tower. (Under no circumstances should you use an active utility pole!) The vertical portion of the antenna can be a wire suspended from the support line to ground, as shown in Fig 39C. If top loading is needed, some or all of the support line can be made part of the antenna.

Your local utility company will periodically have older power poles that they no longer wish to keep in service. These are sometimes available at little or no expense. If you see a power line under reconstruction or repair in your area you might stop and speak with the crew foreman. Sometimes they will have removed older poles they will not use again and will have to haul them back to their shop for disposal. Your offer for local "disposal" may well be accepted. Such a pole can be used in conjunction with a tubing or whip extension such as that shown in Fig 39A. Power poles are not your only option. In some areas of the US, such as the southeast or northwest, tall poles made directly from small conifers are available.

Freestanding (unguyed) flagpoles and roadway illumination standards are available in heights exceeding 100 feet. These are made of fiberglass, aluminum or galvanized steel. All of these are candidates for verticals. Flagpole suppliers are listed under "Flags and Banners" in your Yellow Pages. For lighting standards (lamp posts), you can contact a local electrical hardware distributor. Like a wooden pole, a fiberglass flagpole does not require a base insulator, but metal poles do. Guy wires will be needed.

One option to avoid the use of guys and a base insulator is to mount the pole directly into the ground as originally intended and then use shunt feed. If you want to keep the pole grounded but would like to use elevated radials, you can attach a cage of wires (four to six) at the top as shown in Fig 39D. The cage surrounds the pole and allows the pole (or tower for that matter) to be grounded while allowing elevated radials to be used. The use of a cage of wires surrounding the pole or tower is a very good way to increase the effective diameter. This reduces the Q of the antenna, thereby increasing the bandwidth. It can also reduce the conductor loss, especially if the pole is galvanized steel, which is not a very good RF conductor.

Aluminum irrigation tubing, which comes in diameters of 3 and 4 inches and in lengths of 20 to 40 feet, is widely available in rural areas. One or two lengths of tubing con-

Fig 39—Vertical antennas are effective for 3.5- or 7-MHz work. The λ/4 antenna shown at A is fed directly with 50-Ω coaxial line, and the resulting SWR is usually less than 1.5 to 1, depending on the ground resistance. If a grounded antenna is used as at B, the antenna can be shunt fed with either 50- or 75-Ω coaxial line. The tap for best match and the value of C will have to be found by experiment. The line running up the side of the antenna should be spaced 6 to 12 inches from the antenna. If tall trees are available the antenna can be supported from a line suspended between the trees, as shown in C. If the vertical section is not long enough then the horizontal support section can be made of wire and act as top loading. A pole or even a grounded tower can be used with elevated radials if a cage of four to six wires is provided as shown in D. The cage surrounds the pole which may be wood or a grounded conductor.

nected together can make a very good vertical when guyed with non-conducting line. It is also very lightweight and relatively easy to erect. A variety of TV masts are available which can also be used for verticals.

1.8 TO 3.5-MHz VERTICAL USING AN EXISTING TOWER

A tower can be used as a vertical antenna, provided that a good ground system is available. The shunt-fed tower is at its best on 1.8 MHz, where a full λ/4 vertical antenna is rarely possible. Almost any tower height can be used. If the beam structure provides some top loading, so much the

better, but anything can be made to radiate—if it is fed properly. W5RTQ (now K6SE) uses a self-supporting, aluminum, crank-up, tilt-over tower, with a TH6DXX tribander mounted at 70 feet. Measurements showed that the entire structure has about the same properties as a 125-foot vertical. It thus works quite well as an antenna on 1.8 and 3.5 MHz for DX work requiring low-angle radiation.

Preparing the Structure

Usually some work on the tower system must be done before shunt-feeding is tried. If present, metallic guys should be broken up with insulators. They can be made to simulate

top loading, if needed, by judicious placement of the first insulators. Don't overdo it; there is no need to "tune the radiator to resonance" in this way since a shunt feed is employed. If the tower is fastened to a house at a point more than about one-fourth of the height of the tower, it may be desirable to insulate the tower from the building. Plexiglas sheet, ¼-inch or more thick, can be bent to any desired shape for this purpose, if it is heated in an oven and bent while hot.

All cables should be taped tightly to the tower, on the inside, and run down to the ground level. It is not necessary to bond shielded cables to the tower electrically, but there should be no exceptions to the down-to-the-ground rule.

A good system of buried radials is very desirable. The ideal would be 120 radials, each 250 feet long, but fewer and shorter ones must often suffice. You can lay them around corners of houses, along fences or sidewalks, wherever they can be put a few inches under the surface, or even on the earth's surface. Aluminum clothesline wire may be used extensively in areas where it will not be subject to corrosion. Neoprene-covered aluminum wire will be better in highly acid soils. Contact with the soil is not important. Deep-driven ground rods and connection to underground copper water pipes may be helpful, if available, especially to provide some protection from lightning.

Installing the Shunt Feed

Principal details of the shunt-fed tower for 1.8 and 3.5 MHz are shown in **Fig 40**. Rigid rod or tubing can be used for the feed portion, but heavy gauge aluminum or copper wire is easier to work with. Flexible stranded #8 copper wire is used at W5RTQ (now K6SE) for the 1.8-MHz feed, because when the tower is cranked down, the feed wire must come down with it. Connection is made at the top, 68 feet, through a 4-foot length of aluminum tubing clamped to the top of the tower, horizontally. The wire is clamped to the tubing at the outer end, and runs down vertically through standoff insulators. These are made by fitting 12-inch lengths of PVC plastic water pipe over 3-foot lengths of aluminum tubing. These are clamped to the tower at 15- to 20-foot intervals, with the bottom clamp about 3 feet above ground. These lengths allow for adjustment of the tower-to-wire spacing over a range of about 12 to 36 inches, for impedance matching.

The gamma-match capacitor for 1.8 MHz is a 250-pF variable with about ⅙-inch plate spacing. This is adequate for power levels up to about 200 W. A large transmitting or a vacuum-variable capacitor should be used for high-power applications.

Tuning Procedure

The 1.8-MHz feed wire should be connected to the top of the structure if it is 75 feet tall or less. Mount the standoff insulators so as to have a spacing of about 24 inches between wire and tower. Pull the wire taut and clamp it in place at the bottom insulator. Leave a little slack below to permit adjustment of the wire spacing, if necessary.

Adjust the series capacitor in the 1.8-MHz line for

minimum reflected power, as indicated on an SWR meter connected between the coax and the connector on the capacitor housing. Make this adjustment at a frequency near the middle of your expected operating range. If a high SWR is indicated, try moving the wire closer to the tower. Just the

Fig 40—Principal details of the shunt-fed tower at W5RTQ (now K6SE). The 1.8-MHz feed, left side, connects to the top of the tower through a horizontal arm of 1-inch diameter aluminum tubing. The other arms have standoff insulators at their outer ends, made of 1-foot lengths of plastic water pipe. The connection for 3.5-4 MHz, right, is made similarly, at 28 feet, but two variable capacitors are used to permit adjustment of matching with large changes in frequency.

lower part of the wire need be moved for an indication as to whether reduced spacing is needed. If the SWR drops, move all insulators closer to the tower, and try again.

If the SWR goes up, increase the spacing. There will be a practical range of about 12 to 36 inches. If going down to 12 inches does not give a low SWR, try connecting the top a bit farther down the tower. If wide spacing does not make it, the omega match shown for 3.5-MHz work should be tried. No adjustment of spacing is needed with the latter arrangement, which may be necessary with short towers or installations having little or no top loading.

The two-capacitor arrangement in the omega match is also useful for working in more than one 25-kHz segment of the 1.8-MHz band. Tune up on the highest frequency, say 1990 kHz, using the single capacitor, making the settings of wire spacing and connection point permanent for this frequency. To move to the lower frequency, say 1810 kHz, connect the second capacitor into the circuit and adjust it for the new frequency. Switching the second capacitor in and out then allows changing from one segment to the other, with no more than a slight retuning of the first capacitor.

SIMPLE, EFFECTIVE, ELEVATED GROUND-PLANE ANTENNAS

This section describes a simple and effective means of using a grounded tower, with or without top-mounted antennas, as an elevated ground-plane antenna for 80 and 160 meters. It first appeared in a June 1994 *QST* article by Thomas Russell, N4KG.

From Sloper to Vertical

Recall the quarter-wavelength sloper, also known as the *half sloper*. [The half sloper is covered later in this chapter in more detail.—*Ed.*] It consists of an isolated quarter wavelength of wire, sloping from an elevated feed point on a grounded tower. Best results are usually obtained when the feed point is somewhere below a top-mounted Yagi antenna. You feed a sloper by attaching the center conductor of a coaxial cable to the wire and the braid of the cable to the tower leg. Now, imagine four (or more) slopers, but instead of feeding each individually, connect them together to the center conductor of a single feed line. Voilà! Instant elevated ground plane.

Now, all you need to do is determine how to tune the antenna to resonance. With no antennas on the top of the tower, the tower can be thought of as a fat conductor and should be approximately 4% shorter than a quarter wavelength in free space. Calculate this length and attach four insulated quarter-wavelength radials at this distance from the top of the tower. For 80 meters, a feed point 65 feet below the top of an unloaded tower is called for. The tower guys must be broken up with insulators for all such installations. For 160 meters, 130 feet of tower above the feed point is needed.

What can be done with a typical grounded-tower-and-Yagi installation? A top-mounted Yagi acts as a large capacitance hat, top loading the tower. Fortunately, top loading is the most efficient means of loading a vertical antenna.

The examples in **Table 3** should give us an idea of how much top loading might be expected from typical amateur antennas. The values listed in the *Equivalent Loading* column tell us the approximate vertical height replaced by the antennas listed in a top-loaded vertical antenna. To arrive at the remaining amount of tower needed for resonance, subtract these numbers from the non-loaded tower height needed for resonance. Note that for all but the 10-meter antennas, the equivalent loading equals or exceeds a quarter wavelength on 40 meters. For typical HF Yagis, this method is best used only on 80 and 160 meters.

Construction Examples

Consider this example: A TH7 triband Yagi mounted on a 40-foot tower. The TH7 has approximately the same overall dimensions as a full-sized 3-element 20-meter beam, but has more interlaced elements. Its equivalent loading is estimated to be 40 feet. At 3.6 MHz, 65 feet of tower is needed without loading. Subtracting 40 feet of equivalent loading, the feed point should be 25 feet below the TH7 antenna.

Ten quarter-wavelength (65-foot) radials were run from a nylon rope tied between tower legs at the 15-foot level, to various supports 10 feet high. Nylon cord was tied to the insulated, stranded, #18 wire, without using insulators. The radials are all connected together and to the center of an exact half wavelength (at 3.6 MHz) of RG-213 coax, which will repeat the antenna feed impedance at the other end. **Fig 41** is a drawing of the installation. The author used a Hewlett-Packard low-frequency impedance analyzer to measure the input impedance across the 80-meter band. An exact resonance (zero reactance) was seen at 3.6 MHz, just as predicted. The radiation resistance was found to be 17 Ω. The next question is, how to feed and match the antenna.

One good approach to 80-meter antennas is to tune them to the low end of the band, use a low-loss transmission line, and switch an antenna tuner in line for operation in the higher portions of the band. With a 50-Ω line, the 17-Ω radiation resistance represents a 3:1 SWR, meaning that an antenna tuner should be in-line for all frequencies. For short runs, it

Table 3
Effective Loading of Common Yagi Antennas

Antenna	Boom Length (feet)	S (area, ft²)	Equivalent Loading (feet)
3L 20	24	768	39
5L 15	26	624	35
4L 15	20	480	31
3L 15	16	384	28
5L 10	24	384	28
4L 10	18	288	24
3L 10	12	192	20
TH7	24	—	40 (estimated)
TH3	14	—	27 (estimated)

Fig 41—At A, an 80-meter top-loaded, reverse-fed elevated ground plane, using a 40-foot tower carrying a TH7 triband Yagi antenna. At B, dimensions of the 3.6-MHz matching network, made from RG-59.

Fig 42—A 160-meter antenna using a 75-foot tower carrying stacked triband Yagis.

would be permissible to use RG-8 or RG-213 directly to the tuner. If you have a plentiful supply of low-loss 75-Ω CATV rigid coax, you can take another approach.

Make a quarter-wave (70 feet × 0.66 velocity factor = 46 feet) 37-Ω matching line by paralleling two pieces of RG-59 and connecting them between the feed point and a run of the rigid coax to the transmitter. The magic of quarter-wave matching transformers is that the input impedance (R_i) and output impedance (R_o) are related by:

$$Z_0{}^2 = R_i \times R_o \qquad (Eq\ 2)$$

For $R_i = 17\ \Omega$ and $Z_0 = 37\ \Omega$, $R_o = 80\ \Omega$, an almost perfect match for the 75-Ω CATV coax. The resulting 1.6:1 SWR at the transmitter is good enough for CW operation without a tuner.

160-Meter Operation

On the 160-meter band, a resonant quarter-wavelength requires 130 feet of tower above the radials. That's a pretty tall order. Subtracting 40 feet of top loading for a 3-element 20-meter or TH7 antenna brings us to a more reasonable 90 feet above the radials. Additional top loading in the form

of more antennas will reduce that even more.

Another installation, using stacked TH6s on a 75-foot tower, is shown in **Fig 42**. The radials are 10 feet off the ground.

PHASED VERTICALS

Two or more vertical antennas spaced apart can be operated as a single antenna system to obtain additional gain and a directional pattern. There is an extensive discussion of phased arrays in Chapter 8, Multielement Arrays. Much of the material in Chapter 8 is useful for low-band antennas.

The Half-Square Antenna

The *half-square* antenna is a very simple form of vertical two-element phased array that can be very effective on the low bands. The following section was originally presented in *The ARRL Antenna Compendium Vol 5*, by Rudy Severns, N6LF.

A simple modification to a standard dipole is to add two λ/4 vertical wires, one at each end, as shown in **Fig 43**. This makes a *half-square antenna*. The antenna can be fed at one corner (low-impedance, current fed) or at the lower end of one of the vertical wires (high-impedance, voltage fed).

Fig 43—Typical 80-meter half-square, with λ/4-high vertical legs and a λ/2-long horizontal leg. The antenna may be fed at the bottom or at a corner. When fed at a corner, the feed point is a low-impedance, current-feed. When fed at the bottom of one of the wires against a small ground counterpoise, the feed point is a high-impedance, voltage-feed.

Other feed arrangements are also possible.

The "classical" dimensions for this antenna are λ/2 (131 feet at 3.75 MHz) for the top wire and λ/4 (65.5 feet) for the vertical wires. However, there is nothing sacred about these dimensions! They can vary over a wide range and still obtain nearly the same performance.

This antenna is two λ/4 verticals, spaced λ/2, fed in-phase by the top wire. The current maximums are at the top corners. The theoretical gain over a single vertical is 3.8 dB. An important advantage of this antenna is that it does not require the extensive ground system and feed arrangements that a conventional pair of phased λ/4 verticals would.

Comparison to a Dipole

In the past, one of the things that has turned off potential users of the half-square on 80 and 160 meters is the perceived need for λ/4 vertical sections. This forces the height to be > 65 feet on 80 meters and > 130 feet on 160 meters. That's not really a problem. If you don't have the height there are several things you can do. For example, just fold the ends in, as shown in **Fig 44**. This compromises the performance surprisingly little.

It is helpful to compare the examples given in Figs 43 and 44 to dipoles at the same height. Two heights, 40 and 80 feet, and average, very good and sea water grounds, were used for this comparison. It is also assumed that the lower end of the vertical wires had to be a minimum of 5 feet above ground.

At 40 feet the half-square is really mangled, with only 35-foot long (≈ λ/8) vertical sections. The elevation-plane comparison between this antenna and a dipole of the same height is shown in **Fig 45**. Over average ground the half-square is superior below 32° and at 15° is almost 5 dB better. That is a worthwhile improvement. If you have very good soil conductivity, like parts of the lower Midwest and South, then the half-square will be superior below 38° and at 15° will be nearly 8 dB better. For those fortunate few with saltwater frontal property the advantage at 15° is 11 dB! Notice also that above 35°, the response drops off rapidly. This is great for DX but is not good for local work.

Fig 44—An 80-meter half-square configured for 40-foot high supports. The ends have been bent inward to reresonate the antenna. The performance is compromised surprisingly little.

Fig 45—Comparison of 80-meter elevation response of 40-foot high, horizontally polarized dipole over average ground and a 40-foot high, vertically polarized half-square, over three types of ground: average (conductivity σ = 5 mS/m, dielectric constant ε = 13), very good (σ = 30 mS/m, ε = 20) and salt water (σ = 5000 mS/m, ε = 80). The quality of the ground clearly has a profound effect on the low-angle performance of the half-square. Even over average ground, the half-square outperforms the low dipole below about 32°.

Fig 46—80-meter azimuth patterns for shortened half-square antenna (solid line) shown in Fig 44, compared with flattop dipole (dashed line) at 100 feet height. Average ground is assumed for these cases.

Fig 46 shows the azimuthal-plane pattern for the 80-meter half-square antenna in Fig 44, but this time compared with the response of a flattop horizontal dipole that is 100 feet high. These comparisons are for average ground and are for an elevation angle of 5°. The message here is that the lower your dipole and the better your ground, the more you have to gain by switching from a dipole to a half-square. The half-square antenna looks like a good bet for DXing.

Changing the Shape of the Half Square

Just how flexible is the shape? There are several common distortions of practical importance. Some have very little effect but a few are fatal to the gain. Suppose you have either more height and less width than called for in the standard version or more width and less height, as shown in **Fig 47A**.

The effect on gain from this type of dimensional variation is given in **Table 4**. For a top length (L_T) varying between 110 and 150 feet, where the vertical wire lengths (L_V) readjusted to resonate the antenna, the gain changes only by 0.6 dB. For a 1-dB change the range of L_T is 100 to 155 feet, a pretty wide range.

Another variation results if we vary the length of the horizontal top wire and readjust the vertical wires for resonance, while keeping the top at a constant height. See Fig 47B. **Table 5** shows the effect of this variation on the peak gain. For a range of $L_T = 110$ to 145 feet, the gain changes only 0.65 dB.

The effect of bending the ends into a V shape, as shown in Fig 47C, is given in **Table 6**. The bottom of the antenna is kept at a height of 5 feet and the top height (H) is either 40 or 60 feet. Even this gross deformation has only a relatively small effect on the gain. Sloping the ends outward as shown in Fig 47D and varying the top length also has only a small effect on the gain. While this is good news because it allows you dimension the antenna to fit different QTHs, not all distortions are so benign.

Fig 47—Varying the horizontal and vertical lengths of a half-square. At A, both the horizontal and vertical legs are varied, while keeping the antenna resonant. At B, the height of the horizontal wire is kept constant, while its length and that of the vertical legs is varied to keep the antenna resonant. At C, the length of the horizontal wire is varied and the legs are bent inwards in the shape of "vees." At D, the ends are sloped outward and the length of the flattop portion is varied. All these symmetrical forms of distortion of the basic half-square shape result in small performance losses. At E, a "halfwave vertical dipole" (HVD) with the feed coax isolated with common-mode choke baluns to keep RF current off the coax shield.

Table 4
Variation in Gain with Change in Horizontal Length, with Vertical Height Readjusted for Resonance (see Fig 47A)

L_T (feet)	L_V (feet)	Gain (dBi)
100	85.4	2.65
110	79.5	3.15
120	73.7	3.55
130	67.8	3.75
140	61.8	3.65
150	56	3.05
155	53	2.65

Table 5
Variation in Gain with Change in Horizontal Length, with Vertical Length Readjusted for Resonance, but Horizontal Wire Kept at Constant Height (see Fig 47B)

L_T (feet)	L_V (feet)	Gain (dBi)
110	78.7	3.15
120	73.9	3.55
130	68	3.75
140	63	3.35
145	60.7	3.05

Table 6
Gain for Half-Square Antenna, Where Ends Are Bent Into V-Shape (see Fig 47 C)

Height ⇒ L_T (feet)	H=40 feet L_e (feet)	H=40 feet Gain (dBi)	H=60 feet L_e (feet)	H=60 feet Gain (dBi)
40	57.6	3.25	52.0	2.75
60	51.4	3.75	45.4	3.35
80	45.2	3.95	76.4	3.65
100	38.6	3.75	61.4	3.85
120	31.7	3.05	44.4	3.65
140	—	—	23	3.05

Fig 48—An asymmetrical distortion of the half-square antenna, where the bottom of one leg is purposely made 20 feet higher than the other. This type of distortion does affect the pattern!

Fig 49—Elevation pattern for the asymmetrical half-square shown in Fig 48, compared with pattern for a 50-foot high dipole. This is over average ground, with a conductivity of 5 mS/m and a dielectric constant of 13. Note that the zenith-angle null has filled in and the peak gain is lower compared to conventional half-square shown in Fig 43 over the same kind of ground.

Suppose the two ends are not of the same height, as illustrated in **Fig 48**, where one end of the half-square is 20 feet higher than the other. The elevation-plane radiation pattern for this antenna is shown in **Fig 49** compared to a dipole at 50 feet. This type of distortion does affect the pattern. The gain drops somewhat and the zenith null goes away. The nulls off the end of the antenna also go away, so that there

is some end-fire radiation. In this example the difference in height is fairly extreme at 20 feet. Small differences of 1 to 5 feet do not affect the pattern seriously.

If the top height is the same at both ends but the length of the vertical wires is not the same, then a similar pattern distortion can occur. The antenna is very tolerant of symmetrical distortions but it is much less accepting of asymmetrical distortion.

What if the length of the wires is such that the antenna is not resonant? Depending on the feed arrangement, that may or may not matter. We will look at that issue later on, in the section on patterns versus frequency. The half-square antenna, like the dipole, is very flexible in its proportions.

Half-Square Feed-Point Impedance

There are many different ways to feed the half-square. Traditionally the antenna has been fed either at the end of one of the vertical sections, against ground, or at one of the upper corners as shown in Fig 43.

For voltage feed at the bottom against ground, the impedance is very high, on the order of several thousand ohms. For current feed at a corner, the impedance is much lower and is usually close to 50 Ω. This is very convenient for direct feed with coax.

The half-square is a relatively high-Q antenna (Q ≈ 17). **Fig 50** shows the SWR variation with frequency for this feed arrangement. An 80-meter dipole is not particularly wideband either, but a dipole will have less extreme variation in SWR than the half-square.

Patterns Versus Frequency

Impedance is not the only issue when defining the bandwidth of an antenna. The effect on the radiation pattern of changing frequency is also a concern. For a voltage-fed half-square, the current distribution changes with frequency. For an antenna resonant near 3.75 MHz, the current distribution is nearly symmetrical. However, above and below resonance the current distribution increasingly becomes asymmetrical. In effect, the open end of the antenna is constrained to be a voltage maximum but the feed point can behave less as a voltage point and more like a current maxima. This allows the current distribution to become asymmetrical.

The effect is to reduce the gain by −0.4 dB at 3.5 MHz and by −0.6 dB at 4 MHz. The depth of the zenith null is reduced from −20 dB to −10 dB. The side nulls are also reduced. Note that this is exactly what happened when the antenna was made physically asymmetrical. Whether the asymmetry is due to current distribution or mechanical arrangements, the antenna pattern will suffer.

When current-feed at a corner is used, the asymmetry introduced by off-resonance operation is much less, since both ends of the antenna are open circuits and constrained to be voltage maximums. The resulting gain reduction is only −0.1 dB. It is interesting that the sensitivity of the pattern to changing frequency depends on the feed scheme used.

Of more concern for corner feed is the effect of the transmission line. The usual instruction is to simply feed

Fig 50—Variation of SWR with frequency for current-fed half-square antenna. The SWR band-width is quite narrow.

Fig 51—Typical matching networks used for voltage-feeding a half-square antenna.

the antenna using coax, with the shield connected to vertical wire and the center conductor to the top wire. Since the shield of the coax is a conductor, more or less parallel with the radiator, and is in the immediate field of the antenna, you might expect the pattern to be seriously distorted by this practice. This arrangement seems to have very little effect on the pattern. The greatest effect is when the feed line length was near a multiple of $\lambda/2$. Such lengths should be avoided.

Of course, you may use a choke balun at the feed point if you desire. This might reduce the coupling to the feed line even further but it doesn't appear to be worth the trouble. In fact, if you use an antenna tuner in the shack to operate away from resonance with a very high SWR on the transmission line, a balun at the feed point would take a beating.

Voltage-Feed at One End of Antenna: Matching Schemes

Several straightforward means are available for narrow-band matching. However, broadband matching over the full 80-meter band is much more challenging. Voltage feed with a parallel-resonant circuit and a modest local ground, as shown in **Fig 51**, is the traditional matching scheme for this antenna. Matching is achieved by resonating the circuit at the desired frequency and tapping down on the inductor in Fig 51A or using a capacitive divider (Fig 51B). It is also possible to use a $\lambda/4$ transmission-line matching scheme, as shown in Fig 51C.

If the matching network shown in Fig 51B is used, typical values for the components would be: L = 15 µH, C1 = 125 pF and C2 = 855 pF. At any single point the SWR can be made very close to 1:1 but the bandwidth for SWR < 2:1 will be very narrow at <100 kHz. Altering the L-C ratio doesn't make very much difference. The half-square antenna has a well-earned reputation for being narrow-band.

Short Vertical Antennas

On the lower frequencies it becomes increasingly difficult to accommodate a full λ/4 vertical height and full-sized λ/4 radials, or even worse, a full-sized half-wave vertical dipole (HVD). In fact, it is not absolutely necessary to make the antenna full size, whether it is an HVD, a grounded monopole antenna or a ground-plane type of monopole antenna. The size of the antenna can be reduced by half or even more and still retain high efficiency and the desired radiation pattern. This requires careful design, however. And if high efficiency is maintained, the operating bandwidth of the shortened antenna will be reduced because the shortened antenna will have a higher Q.

This translates into a more rapid increase of reactance away from resonance. The effect can be mitigated to some extent by using larger-diameter conductors. Even doing this however, bandwidth will be a problem, particularly on the 3.5 to 4-MHz band, which is very wide in proportion to the center frequency.

If we take a vertical monopole with a diameter of 2 inches and a frequency of 3.525 MHz and progressively shorten it from λ/4 in length, the feed-point impedance and efficiency (using an inductor at the base to tune out the capacitive reactance) will vary as shown in **Table 7**. In this example perfect ground and conductor are assumed. Real ground will not make a great difference in the impedance but will introduce ground loss, which will reduce the efficiency further. Conductor loss will also reduce efficiency. In general, higher R_R will result in better efficiency.

The important point of Table 7 is the drastic reduction in radiation resistance R_R as the antenna gets shorter. This combined with the increasing loss resistance of the inductor (R_L) used to tune out the increasing base reactance (X_C) reduces the efficiency.

BASE LOADING A SHORT VERTICAL ANTENNA

The base of the antenna is a convenient point at which

to add a loading inductor, but it is usually not the lowest loss point at which an inductor, of a given Q, could be placed. There is an extensive discussion of the optimum location of the loading in a short vertical as a function of ground loss and inductor Q in Chapter 16 for mobile antennas, which by necessity are electrically and physically short. This information should be reviewed before using inductive loading.

On the accompanying CD-ROM is a copy of the program *MOBILE.EXE*. This is an excellent tool for designing short, inductively loaded antennas. In most cases, where top loading (discussed below) is not used, the optimum point is near or a little above the middle of the vertical section. Moving the loading coil from the base to the middle of the vertical antenna can make an important difference, increasing R_R and reducing the inductor loss. For example, in an antenna operating at 3.525 MHz, if we make $L_1 = 34.9$ feet (0.125 λ) the amount of loading inductor placed at the center is 25.2 μH. This resonates the antenna. In this configuration R_R will increase from 6.8 Ω (base loading) to 13.5 Ω (center loading). This substantially increases the efficiency of the antenna, depending on the ground loss and conductor resistances.

Instead of a lumped inductance being inserted at some point in the antenna, it is also possible to use "continuous loading," where the entire radiator is wound as a small diameter coil. The effect is to distribute the inductive loading all along the radiator. In this version of inductive loading the coil is the radiator. An example of a short vertical using this principle is given later in this chapter.

OTHER WAYS OF LOADING A SHORT ANTENNA FOR RESONANCE

Inductive loading is not the only, or even the best, way to compensate for reduced antenna height. *Capacitive top loading* can also be used as indicated in **Fig 52** to bring a vertical monopole to resonance. **Table 8** gives information on a shortened 3.525-MHz vertical using top loading. The vertical portion (L_1) is made from 2-inch tubing. The top loading is also 2-inch tubing extending across the top like a T. The length of the top loading T ($\pm L_2$) is adjusted to resonate the

Table 7

Effect of Shortening a Vertical Radiator Below λ/4 Using Inductive Base Loading.

Frequency is 3.525 MHz and for the Inductor $Q_L = 200$. Ground and conductor losses are omitted.

Length (feet)	Length (λ)	R_R (Ω)	X_C (Ω)	R_L (Ω)	Efficiency (%)	Loss (dB)
14	0.050	0.96	−761	3.8	20	−7.0
20.9	0.075	2.2	−533	2.7	45	−3.5
27.9	0.100	4.2	−395	2.0	68	−1.7
34.9	0.125	6.8	−298	1.5	82	−0.86
41.9	0.150	10.4	−220	1.1	90	−0.44
48.9	0.175	15.1	−153	0.77	95	−0.22
55.8	0.200	21.4	−92	0.46	98	−0.09
62.8	0.225	29.7	−34	0.17	99	−0.02

Table 8

Effect of Shortening a Vertical Using Top Loading

L_1 (feet)	L_2 (feet)	Length (λ)	R_R (Ω)
14.0	48.8	0.050	4.0
20.9	38.6	0.075	8.5
27.9	30.1	0.100	14.0
34.9	22.8	0.125	19.9
41.9	17.3	0.150	25.5
48.9	11.9	0.175	30.4
55.8	7.0	0.200	33.9
62.8	2.4	0.225	35.7

antenna. Again, the ground and the conductors are assumed to be perfect in Table 8.

For a given vertical height, resonating the antenna with top loading results in much higher radiation resistance R_R—2 to 4 times. In addition, the loss associated with the loading element will be smaller. The result is a more efficient antenna for low heights. A comparison of R_R for both capacitive top loading and inductive base loading is given in **Fig 53**. For heights below 0.15 λ the length of the top-loading elements becomes impractical but there are other, potentially more useful, top-loading schemes.

A multiwire system such as the one shown in **Fig 54** has more capacitance than the single-conductor arrangement, and thus does not need to be as long to resonate at a given frequency. This design does, however, require extra supports for the additional wires. Ideally, an arrangement of this sort should be in the form of a cross, but parallel wires separated by several feet give a considerable increase in capacitance

Fig 54—Multiple top wires can increase the effective capacitance substantially. This allows the use of shorter top wires to achieve resonance.

Fig 55—A close-up view of the capacitance hat for a 7-MHz vertical antenna. The ½-in. diameter radial arms terminate in a loop of copper wire.

Fig 52—Horizontal wire used to top load a short vertical.

Fig 53—Comparison of top (capacitive) and base (inductive) loading for short verticals. Sufficient loading is used to resonate the antenna.

Fig 56—Capacitance of sphere, disc and cylinder as a function of their diameters. The cylinder length is assumed equal to its diameter.

over a single wire.

The top loading can be supplied by a variety of metallic structures large enough to have the necessary self-capacitance. For example, as shown in **Fig 55**, a multi-spoked structure with the ends connected together can be used. One simple way to make a capacitance hat is to take four to six 8-foot fiberglass CB mobile whips, arrange them like spokes in a wagon wheel and connect the ends with a peripheral wire. This arrangement will produce a 16-foot diameter hat that is economical and very durable, even when loaded with ice. Practically any sufficiently large metallic structure can be used for this purpose, but simple geometric forms such as the sphere, cylinder and disc are preferred because of the relative ease with which their capacitance can be calculated.

The capacitance of three geometric forms can be estimated from the curves of **Fig 56** as a function of their size. For the cylinder, the length is specified equal to the diameter. The sphere, disc and cylinder can be constructed from sheet metal, if such construction is feasible, but the capacitance will be practically the same in each if a "skeleton" type of construction with screening or networks of wire or tubing are used.

Finding Capacitance Hat Size

The required size of a capacitance hat may be determined from the following procedure. The information in this section is based on a September 1978 *QST* article by Walter Schulz, K3OQF. The physical length of a shortened antenna can be found from:

$$h_{inches} = \frac{11808}{F_{MHz}} \qquad \text{(Eq 3)}$$

where h = length in inches.

Thus, using an example of 7 MHz and a shortened length of 0.167 λ, h = 11808/7 × 0.167 = 282 inches, equivalent to 23.48 feet.

Consider the vertical radiator as an open-ended transmission line, so the impedance and top loading may be determined. The characteristic impedance of a vertical antenna can be found from

$$Z_0 = 60 \left(\ln\left(\frac{4h}{d}\right) - 1 \right) \qquad \text{(Eq 4)}$$

where

    ln = natural logarithm
    h = length (height) of vertical radiator in inches (as above)
    d = diameter of radiator in inches

The vertical radiator for this example has a diameter of 1 inch. Thus, for this example,

$$Z_0 = 60 \left(\ln\left(\frac{4 \times 281}{1}\right) - 1 \right) = 361 \ \Omega$$

The capacitive reactance required for the amount of top loading can be found from

$$Z_0 = 60 \ \ln\left(\frac{4 \times 281}{1}\right) - 1 = 361 \ \Omega \qquad \text{(Eq 5)}$$

where

    X = capacitive reactance, ohms
    Z_0 = characteristic impedance of antenna (from Eq 4)
    θ = amount of electrical loading, degrees.

This value for a 30° hat is 361/tan 30° = 625 Ω. This capacitive reactance may be converted to capacitance with the following equation,

$$C = \frac{10^6}{2\pi f X_C} \qquad \text{(Eq 6)}$$

where

    C = capacitance in pF
    f = frequency, MHz
    X_C = capacitive reactance, ohms (from above).

For this example, the required C = 10^6/(2 π × 7 × 625) = 36.4 pF, which may be rounded to 36 pF. A disc capacitor is used in this example. The appropriate diameter for 36 pF of hat capacitance can be found from Fig 56. The disc diameter that yields 36 pF of capacitance is 40 inches.

The skeleton disc shown in Fig 55 is fashioned into a wagonwheel configuration. Six 20-inch lengths of ½-inch OD aluminum tubing are used as spokes. Each is connected to the hub at equidistant intervals. The outer ends of the spokes terminate in a loop made of #14 copper wire. Note that the loop increases the hat capacitance slightly, making a better approximation of a solid disc. The addition of this hat at the top of a 23.4-foot radiator makes it quarter-wave resonant at 7 MHz.

After construction, some slight adjustment in the radiator length or the hat size may be required if resonance at a specific frequency is desired. From Fig 53, the radiation resistance of a 0.167-λ high radiator is seen to be about 13 Ω without top loading. With top loading Rr ≈ 25 Ω or almost double.

THE COMPACT VERTICAL DIPOLE

A variation on the HVD (half-wave vertical dipole) theme is the *compact vertical dipole*, or CVD. The CVD uses capacitance-hat loading on each end of a shortened vertical radiator, as shown in **Fig 57C**. Some call this "top hat" and "bottom hat" loading. Les Moxon, G6XN, called this method of loading a shortened antenna simply "end loading." The vertical wire for his 40-meter CVD is 25 feet high, with 15-foot long horizontal loading wires on each side, top and bottom.

K8CH Compact Vertical Dipole

The top loading wires needn't be perpendicular to the vertical radiator, although that is convenient if you construct the antenna from aluminum tubing. K8CH described a wire 30-meter CVD in the 2006 Edition of *The ARRL Handbook*. This used #14 wire throughout, with sloping top loading wires. It was designed to be suspended from a tree at least

(A)

Ant0206

(B)

(C)

(D)

(E)

Fig 57—Progression of end-loaded-vertical dipole designs. At A, the HVD (half-wave vertical dipole), with no end loading. At B, an HVD whose bottom half has been replaced with a set of four ground-plane radials, making it into the familiar ground-plane vertical. At C, G6XN-style dipole with end loading of two wires at both top and bottom. At D, end-loaded dipole with four shorter wires at top and bottom. At E, K8CH end-loaded dipole with asymmetric loading wires. The four top wires are slanted down to the ground using extension insulating strings that also hold up the bottom horizontal end-loading wires. See Fig 58.

32 feet high to keep all wires 8 feet or more above humans and animals. The vertical radiating wire is 24 feet long, and the eight top and bottom end-loading wires are all 5 feet 9 inches long. See Fig 57E and **Table 9**, CVD 1.

The top loading wires slant at an angle of 45° down to the ground, using insulating strings that also support the ends of the bottom loading wires, holding them out so that they are horizontal. See **Fig 58**. There is a small loss of gain

because of the "umbrella" shape of the top loading wires, and the 2:1 SWR bandwidth is diminished slightly from the horizontal case. This isn't a problem on a narrow band like 30 meters.

A 40-meter version of this antenna, CVD 6, also uses a 24-foot long vertical radiator, 8 feet high at its bottom. It uses 11.3-foot long radial wires made of #14 wire, again with the top four slanted down at 45°. This CVD has a 2:1

Fig 58—Layout of CVD made using #14 wire suspended from a tree branch.

SWR bandwidth of 250 kHz. It is directly fed with 50-Ω coax with ferrite-core common-mode choke baluns in the middle of the vertical radiator. An additional choke balun is used where the coax reaches ground level in order to knock down common-mode currents that might otherwise radiate onto the coax shield.

You should note the comparison of 40-meter ground-plane vertical antennas in Table 9. GP 1 is for horizontal radials that are 8 feet off the ground, while GP 2 has its radials only 2 feet high. There is some loss in gain because of the proximity of the lossy ground. The 40-meter CVD 1 and CVD 2 cases illustrate the same effect of being close to the lossy ground.

Some of the cases in Table 9 require Center Load coils to bring the antenna to resonance. Where the loading coil inductance is equal to the "Hairpin Coil" inductance, the loading coil also serves as a hairpin matching coil. Where the amount of Hairpin Coil inductance is less than the Load Coil inductance, a match is achieved by tapping the Center Load Coil symmetrically out from the center.

80-Meter CVD

The size of a CVD becomes a real challenge on 80 meters, requiring either very tall support structures or multiple loading methods to keep the vertical radiator to a reasonable length. The CVD 2 design in Table 9 shows a K8CH-style CVD wire antenna whose vertical radiator is 46.5 feet long. It requires a 54.5-foot high tree to keep the bottom end of the vertical radiator 8 feet above ground for safety. Compare this to an HVD that requires a 143-foot support of some sort to keep it 8 feet off the ground at the bottom. The CVD 2 sacrifices some 0.7 dB in gain for this difference in size, and about 75 kHz in 2:1 SWR bandwidth.

The CVD 2 would require retuning when going from

Table 9
Variations on a Vertical Center-Fed Dipole

Name	Style Fig 57	Vertical Length feet	Spoke Length feet	Min. Ht feet	Max. Gain dBi	2:1 SWR kHz	Hairpin Coil μH	Center Load μH
20 Meters								
GP	B	17.53	16.53	8	0.29	400	—	—
CVD 1	C	13	7.57	8	0.12	625	—	—
CVD 2	D	12	5.1	8	0.00	550	0.68	0.68
CVD 3	E	12.15	5.6	8	−0.01	450	0.5	0.5
30 Meters								
GP	B	24.54	23.14	8	0.04	400	—	—
CVD 1	E	24	5.33	8	−0.2	500	—	—
CVD 2	E	17	7.60	8	−0.36	400	0.82	0.82
40 Meters								
HVD	A	66	—	8	0.13	450	—	—
GP 1	B	35	33	8	−0.12	325	—	—
GP 2	B	34.5	33	2	−0.37	400	—	—
CVD 1	C	25	15	8	−0.42	450	—	—
CVD 2	C	24	15	2	−1.09	400	—	—
CVD 3	D	24	10	8	−0.55	425	—	0.25
CVD 4	D	24	5	8	−0.85	225	—	8.7
CVD 5	D	16	8	8	−1.18	175	0.94	6.8
CVD 6	E	24	11.3	8	−0.59	250	—	—
80 Meters								
HVD	A	135	—	8	0.19	225	—	—
GP	B	65.5	61	8	0.11	200	—	—
CVD 1	C	48.3	30	8	−0.27	200	—	—
CVD 2	E	46.5	21.9	8	−0.50	150	—	—

CW to phone, probably by changing the length of the four bottom horizontal wires equally.

LINEAR LOADING

Another alternative to inductive loading is *linear loading*. This little-understood method of shortening radiators can be applied to almost any antenna configuration—including parasitic arrays. Although commercial antenna manufacturers make use of linear loading in their HF antennas, relatively few hams have used it in their own designs. Linear loading can be used to advantage in many antennas because it introduces relatively little loss, does not degrade directivity patterns, and has low enough Q to allow reasonably good bandwidth. Some

Fig 59—Some examples of linear loading. The small circles indicate the feed points of the antennas.

Fig 60—Wire dipole antennas. The ratio f/f_0 is the measured resonant frequency divided by frequency f_0 of a standard dipole of same length. R is radiation resistance in ohms. At A, standard single-wire dipole. At B, two-wire linear-loaded dipole, similar to folded dipole except that side opposite feed line is open. At C, three-wire linear-loaded dipole.

examples of linear-loaded antennas are shown in **Fig 59**.

Since the dimensions and spacing of linear-loading devices vary greatly from one antenna installation to another, the best way to employ this technique is to try a length of conductor 10% to 20% longer than the difference between the shortened antenna and the full-size dimension for the linear-loading device. Then use the "cut-and-try" method, varying both the spacing and length of the loading device to optimize the match. A hairpin at the feed point can be useful in achieving a 1:1 SWR at resonance.

Linear-Loaded Short Wire Antennas

More detail on linear loading is provided in this section, which was originally presented in *The ARRL Antenna Compendium Vol 5* by John Stanford, NNØF. Linear loading can significantly reduce the required length for resonant antennas. For example, it is easy to make a resonant antenna that is as much as 30 to 40% shorter than an ordinary dipole for a given band. The shorter overall lengths come from bending back some of the wire. The increased self-coupling lowers the resonant frequency. These ideas are applicable to short antennas for restricted space or portable use.

Experiments

The results of the measurements are shown in **Fig 60** and are also consistent with values given by Rashed and Tai from an earlier paper. This shows several simple wire antenna configurations, with resonant frequencies and impedance (radiation resistance). The reference dipole has a resonant frequency f_0 and resistance R = 72 Ω. The f/f_0 values give the effective reduced frequency obtained with the linear loading in each case. For example, the two-wire linear-loaded dipole has its resonant frequency lowered to about 0.67 to 0.70 that of the simple reference dipole of the same length.

The three-wire linear-loaded dipole has its frequency reduced to 0.55 to 0.60 of the simple dipole of the same length. As you will see later, these values will vary with conductor diameter and spacing.

The two-wire linear-loaded dipole (Fig 60B) looks almost like a folded dipole but, unlike a folded dipole, it is open in the middle of the side opposite where the feed line is attached. Measurements show that this antenna structure has a resonant frequency lowered to about two-thirds that of the reference dipole, and R equal to about 35 Ω. A three-wire linear-loaded dipole (Fig 60C) has even lower resonant frequency and R about 25 to 30 Ω.

Linear-loaded monopoles (one half of the dipoles in Fig 60) working against a radial ground plane have similar resonant frequencies, but with only half the radiation resistance shown for the dipoles.

A Ladder-Line Linear-Loaded Dipole

Based on these results, NNØF next constructed a linear loaded dipole as in Fig 60B, using 24 feet of 1-inch ladder line (the black, 450-Ω plastic kind widely available) for the dipole length. He hung the system from a tree using nylon

fishing line, about 4 feet from the tree at the top, and about 8 feet from the ground on the bottom end. It was slanted at about a 60° angle to the ground. This antenna resonated at 12.8 MHz and had a measured resistance of about 35 Ω. After the resonance measurements, he fed it with 1-inch ladder open-wire line (a total of about 100 feet to the shack).

For brevity, this is called a vertical *LLSD* (linear-loaded short dipole). A tuner resonated the system nicely on 20 and 30 meters. On these bands the performance of the vertical LLSD seemed comparable to his 120-foot long, horizontal center-fed Zepp, 30 feet above ground. In some directions where the horizontal, all-band Zepp has nulls, such as toward Siberia, the vertical LLSD was definitely superior. This system also resonates on 17 and 40 meters. However, from listening to various signals, NNØF had the impression that this length LLSD is not as good on 17 and 40 meters as the horizontal 120-foot antenna.

Using Capacitance End Hats

He also experimented with an even shorter resonant length by trying an LLSD with capacitance end-hats. The hats, as expected, increased the radiation resistance and lowered the resonant frequency. Six-foot long, single-wire hats were used on each end of the previous 24-foot LLSD, as shown in **Fig 61**. The antenna was supported in the same way as the previous vertical dipole, but the bottom-end hat wire was only inches from the grass. This system resonated at 10.6 MHz with a measured resistance of 50 Ω.

If the dipole section were lengthened slightly, by a foot or so, to about 25 feet, it should hit the 10.1-MHz band and be a good match for 50-Ω coax. It would be suitable for a restricted space, shortened 30-meter antenna. Note that this antenna is only about half the length of a conventional 30-meter dipole, needs no tuner, and has no losses due to traps. It does have the loss of the extra wire, but this is essentially negligible.

Any of the linear-loaded dipole antennas can be mounted either horizontally or vertically. The vertical version can be used for longer skip contacts—beyond 600 miles or so—unless you have rather tall supports for horizontal antennas to give a low elevation angle. Using different diameter conductors in linear-loaded antenna configurations yields different results, depending on whether the larger or small diameter conductor is fed. NNØF experimented with a vertical ground-plane antenna using a 10-foot piece of electrical conduit pipe (⅝ inch OD) and #12 copper house wire.

Fig 62 shows the configuration. The radial ground system was buried a couple of inches under the soil and is not shown. Note that this is not a folded monopole, which would have either A or B grounded.

The two conductors were separated by 2 inches, using plastic spreaders held onto the pipe by stainless-steel hose clamps obtained from the local hardware store. Hose clamps intertwined at right angles were also used to clamp the pipe on electric fence stand-off insulators on a short 2×4 post set vertically in the ground.

The two different diameter conductors make the antenna characteristics change, depending on how they are configured. With the antenna bridge connected to the larger diameter conductor (point A in Fig 62), and point B unconnected, the system resonated at 16.8 MHz and had R = 35 Ω. With the bridge at B (the smaller conductor), and point A left unconnected, the resonance lowered to 12.4 MHz and R was found to be about 24 Ω.

The resonant frequency of the system in Fig 62 can be adjusted by changing the overall height, or for increasing the frequency, by reducing the length of the wire. Note that a 3.8-MHz resonant ground plane can be made with height only about half that of the usual 67 feet required, if the smaller conductor is fed (point B in Fig 62). In this case, the pipe would be left unconnected electrically. The lengths given above can be scaled to determine a first-try attempt for your favorite band. Resonant lengths will, however, depend on the conductor diameters and spacing.

Fig 61—Two-wire linear-loaded dipole with capacitance end hats. Main dipole length was constructed from 24 feet of "windowed" ladder line. The end-hat elements were stiff wires 6 feet long. The antenna was strung at about a 60° angle from a tree limb using monofilament fishing line. Measured resonant frequency and radiation resistance were 10.6 MHz and 50 Ω.

Fig 62—Vertical ground-plane antenna with a 10-foot pipe and #12 wire as the linear-loaded element. Resonant frequency and radiation resistance depend on which side (A or B) is fed. The other side (B or A) is *not* grounded. See text for details.

The same ideas hold for a dipole, except that the lengths should be doubled from those of the ground plane in Fig 62. The resistance will be twice that of the ground plane. Say, how about a shortened 40-meter horizontal beam to enhance your signal?!

COMBINED LOADING

As an antenna is shortened further the size of the top loading device will become larger and at some point will be impractical. In this situation inductive loading, usually placed directly between the capacitance "hat" and the top of the antenna, can be added to resonate the antenna. An alternative would be to use linear loading in place of inductive loading. The previous section contained an example of end loading combined with linear loading.

SHORTENING THE RADIALS

Very often the space required by full-length radials is simply not available. Like the vertical portion of the antenna, the radials can also be shortened and loaded in very much the same way. An example of end loaded radials is given in **Fig 63A**. Radials half the usual length can be used with little reduction in efficiency but, as in the case of top loading, the antenna Q will be higher and the bandwidth reduced. As shown in Fig 63B**,** inductive loading can also be used. As long as they are not made too short (down to 0.1λ) loaded radials can be efficient—with careful design.

GENERAL RULES

The steps in designing an efficient short vertical antenna system are:

- Make the vertical section as long as possible.
- Make the diameter of the vertical section as large as possible. Tubing or a cage of smaller wires will work well.
- Provide as much top and/or bottom loading as possible.
- If the top/bottom loading is insufficient, resonate the antenna with a high-Q inductor placed between the hat and the top of the antenna.
- For buried-ground systems, use as many radials ($> 0.2 \lambda$) as possible. 40 or more is best.
- If an elevated ground plane is used, use 4 to 8 radials, 5 or more feet above ground.
- If shortened radials must be used then capacitive loading is preferable to inductive loading.

EXAMPLES OF SHORT VERTICALS

A 6-Foot-High 7-MHz Vertical Antenna

Figs 64 through 67 give details for building short, effective vertical quarter-wavelength radiators. This information was originally presented by Jerry Sevick, W2FMI.

A short vertical antenna, properly designed and installed, approaches the efficiency of a full-size resonant quarter-wave antenna. Even a 6-foot vertical on 7 MHz can

Fig 63—Radials may be shortened by using either capacitive (A) or inductive (B) loading. In extreme cases both may be used but the operating bandwidth will be limited.

produce an exceptional signal. Theory tells us that this should be possible, but the practical achievement of such a result requires an understanding of the problems of ground losses, loading, and impedance matching.

The key to success with shortened vertical antennas lies in the efficiency of the ground system with which the antenna is used. A system of at least 60 radial wires is rec-

Fig 64—Jerry Sevick, W2FMI, adjusts the 6-foot high, 40-meter vertical.

ommended for best results, although the builder may elect to reduce the number at the expense of some performance. The radials can be tensioned and pinned at the far ends to permit on-the-ground installation, which will enable the amateur to mow the lawn without the wires becoming entangled in the mower blades. Alternatively, the wires can be buried in the ground, where they will not be visible. There is nothing critical about the wire size for the radials. Radials made of 28, 22, or even 16-gauge wire, will provide the same results. The radials should be at least 0.2 λ long (27 feet or greater on 7 MHz).

A top hat is formed as illustrated in **Fig 65**. The diameter is 7 feet, and a continuous length of wire is connected to the spokes around the outer circumference of the wheel. A load-

Fig 65—Construction details for the top hat. For a diameter of 7 feet, ½-in. aluminum tubing is used. The hose clamp is made of stainless steel and is available at Sears. The rest of the hardware is aluminum.

Fig 66—Standing-wave ratio of the 6-foot vertical using a 7-foot top hat and 14 turns of loading 6 inches below the top hat.

ing coil consisting of 14 turns of B&W 3029 Miniductor stock (2½-inch dia, 6 TPI, #12 wire) is installed 6 inches below the top hat (see Fig 65). This antenna exhibits a feed-point impedance of 3.5 Ω at 7.21 MHz. For operation above or below this frequency, the number of coil turns must be decreased or increased, respectively. Matching is accomplished by increasing the feed-point impedance to 14 Ω through addition of a 4:1-transformer, then matching 14 Ω to 50 Ω (feeder impedance) by means of a pi network. The 2:1 SWR bandwidth for this antenna is approximately 100 kHz.

More than 200 contacts with the 6-foot antenna have indicated the efficiency and capability of a short vertical. Invariably at distances greater than 500 or 600 miles, the short vertical yields excellent signals. Similar antennas can be scaled and constructed for bands other than 7 MHz. The 7-foot-diameter-top hat was tried on a 3.5-MHz vertical, with an antenna height of 22 feet. The loading coil had 24 turns and was placed 2 feet below the top hat. On-the-air results duplicated those on 40-meters. The bandwidth was 65 kHz.

Short verticals such as these have the ability to radiate and receive almost as well as a full-size quarter-wave. Trade-offs are in lowered input impedances and bandwidths. However, with a good radial system and a proper design, these trade-offs can be made entirely acceptable.

Short Continuously Loaded Verticals

While there is the option of using lumped inductance to achieve resonance in a short antenna, the antenna can also be helically wound to provide the required inductance. This is shown in **Fig 68**. Shortened quarter-wavelength vertical antennas can be made by forming a helix on a long cylindrical insulator. The diameter of the helix must be small in terms of λ to prevent the antenna from radiating in the axial mode.

Acceptable form diameters for HF-band operation are from 1 inch to 10 inches when the practical aspects of antenna construction are considered. Insulating poles of fiberglass, PVC tubing, treated bamboo or wood, or phenolic are suitable for use in building helically wound radiators. If wood or bamboo is used the builder should treat the material with at least two coats of exterior spar varnish prior to winding the antenna element. The completed structure should be given two more coats of varnish, regardless of the material used for the coil form. Application of the varnish will help weatherproof the antenna and prevent the coil turns from changing position.

No strict rule has been established concerning how short a helically wound vertical can be before a significant drop in performance is experienced. Generally, one should use the greatest amount of length consistent with available space. A guideline might be to maintain an element length of 0.05 wavelength or more for antennas which are electrically a quarter wavelength long. Thus, use 13 feet or more of stock for an 80-meter antenna, 7 feet for 40 meters, and so on.

A quarter-wavelength helically wound vertical can be used in the same manner as a full-size vertical. That is, it can be worked against an above-ground wire radial system (four or more radials), or it can be ground-mounted with

Fig 67—Base of the vertical antenna showing the 60 radial wires. The aluminum disc is 15 inches in diameter and ¼ inches thick. Sixty tapped holes for ¼-20 aluminum hex-head bolts form the outer ring and 20 form the inner ring. The inner bolts were used for performance comparisons with more than 60 radials. The insulator is polystyrene material (phenolic or Plexiglas suitable) with a 1-inch diameter. Also shown is the impedance bridge used for measuring input resistance.

Fig 68—Helically wound ground-plane vertical. Performance from this type of antenna is comparable to that of many full-size λ/4 vertical antennas. The major design trade-off is usable bandwidth. All shortened antennas of this variety are narrow-band devices. At 7 MHz, in the example illustrated here, the bandwidth between the 2:1 SWR points will be on the order of 50 kHz, half that amount on 80 meters, and twice that amount on 20 meters. Therefore, the antenna should be adjusted for operation in the center of the frequency band of interest.

radials buried or lying on the ground. Some operators have reported good results when using antennas of this kind with four helically wound radials cut for resonance at the operating frequency. The latter technique should capture the attention of those persons who must use indoor antennas.

Winding Information

There is no hard-and-fast formula for determining the amount of wire needed to establish resonance in a helical antenna. The relationship between the length of wire needed for resonance and a full quarter wave at the desired frequency depends on several factors. Some of these are wire size, diameter of the turns, and the dielectric properties of the form material, to name a few. Experience has indicated that a section of wire approximately one half wavelength long, wound on an insulating form with a linear pitch (equal spacing between turns) will come close to yielding a resonant quarter wavelength. Therefore, an antenna for use on 160 meters would require approximately 260 feet of wire, spirally wound on the support.

No specific rule exists concerning the size or type of wire one should use in making a helix. Larger wire sizes are, of course, preferable in the interest of minimizing I^2R losses in the system. For power levels up to 1000 W it is wise to use a wire size of #16 or larger. Aluminum clothesline wire is suitable for use in systems where the spacing between turns is greater than the wire diameter. Antennas requiring close-spaced turns can be made from enameled magnet wire or #14 vinyl jacketed, single-conductor house wiring stock. Every effort should be made to keep the turn spacing as large as is practical to maximize efficiency.

A short rod or metal disc should be made for the top or high-impedance end of the vertical. This is a necessary part of the installation to assure reduction in antenna Q. This broadens the bandwidth of the system and helps prevent extremely high amounts of RF voltage from being developed at the top of the radiator. (Some helical antennas act like Tesla coils when used with high-power transmitters, and can actually catch fire at the high-impedance end when a stub or disc is not used.) Since the Q-lowering device exhibits some additional capacitance in the system, it must be in place before the antenna is tuned.

Tuning and Matching

Once the element is wound it should be mounted where it will be used, with the ground system installed. The feed end of the radiator can be connected temporarily to the ground system. Use a dip meter to check the antenna for resonance by coupling the dipper to the last few turns near the ground end of the radiator. Add or remove turns until the vertical is resonant at the desired operating frequency.

It is impossible to predict the absolute value of feed impedance for a helically wound vertical. The value will depend upon the length and diameter of the element, the ground system used with the antenna, and the size of the disc or stub atop the radiator. Generally speaking, the radiation resistance will be very low—approximately 3 to 10 Ω. An L

network of the kind shown in Fig 68 can be used to increase the impedance to 50 Ω. The Q_L (loaded Q) of the network inductors is low to provide reasonable bandwidth, consistent with the bandwidth of the antenna. Network values for other operating bands and frequencies can be determined by using the reactance values listed below. The design center for the network is based on a radiation resistance of 5 Ω. If the exact feed impedance is known, the following equations can be used to determine precise component values for the matching network. (See Chapter 25, Coupling the Transmitter to the Line, for additional information on L-network matching.)

$$X_A \quad QR_L \tag{Eq 7}$$

$$X_{C2} = 50\sqrt{\frac{R_L}{50 - R_L}} \tag{Eq 8}$$

$$X_{L1} = X_{C1} + \frac{R_L 50}{X_{C2}} \tag{Eq 9}$$

where

X_{C1} = capacitive reactance of C1
X_{C2} = capacitive reactance of C2
X_{L1} = inductive reactance of L1
Q = loaded Q of network
R_L = radiation resistance of antenna

Example: Find the network constants for a helical antenna with a feed impedance of 5 Ω at 7 MHz, Q = 3:

$$X_{C1} = 3 \times 5 = 15$$

$$X_{C2} = \sqrt{\frac{5}{50 - 5}} = 16.666$$

$$X_{L1} = 15 + \frac{250}{16.666} = 30$$

Therefore, C1 = 1500 pF, C2 = 1350 pF, and L1 = 0.7 μH. The capacitors can be made from parallel or series combinations of transmitting micas. L_1 can be a few turns of large Miniductor stock. At RF power levels of 100 W or less, large compression trimmers can be used at C1 and C2 because the maximum RMS voltage at 100 W (across 50 Ω) will be 50 V. At, say, 800 W there will be approximately 220 V RMS developed across 50 Ω. This suggests the use of small transmitting variables at C1 and C2, possibly connected in parallel with fixed values of capacitance to constitute the required amount of capacitance for the network.

By making some part of the network variable, it will be possible to adjust the circuit for an SWR of 1:1 without knowing precisely what the antenna feed impedance is. Actually, C1 is not required as part of the matching network. It is included here to bring the necessary value for L1 into a practical range.

Fig 68 illustrates the practical form a typical helically wound ground-plane vertical might take. Performance from this type antenna is comparable to that of many full-size quarter-wavelength vertical antennas. The major design trade-off is in usable bandwidth. All shortened antennas of this variety are narrow-band devices. At 7 MHz, in the example illustrated here, the bandwidth between the 2:1 SWR points will be on the order of 50 kHz, half that amount on 80 meters, and twice that amount on 20 meters. Therefore, the antenna should be adjusted for operation in the center of the frequency spread of interest.

SHORTENED DIPOLES

As shown in preceding sections, there are a number of ways to load antennas so they may be reduced in size without severe reductions in effectiveness. Loading is always a compromise; the best method is determined by the amount of space available and the band(s) to be worked.

The simplest way to shorten a dipole is shown in **Fig 69**. If you do not have sufficient length between the supports, simply hang as much of the center of the antenna as possible between the supports and let the ends hang down. The ends can be straight down or may be at an angle as indicated but in either case should be secured so that they do not move in the wind. As long as the center portion between the supports is at least ¼, the radiation pattern will be very nearly the same

Fig 69—When space is limited, the ends may be bent downward as shown at A, or back on the radiator as shown at B. The bent dipole ends may come straight down or be led off at an angle away from the center of the antenna. An inverted V at C can be erected with the ends bent parallel to the ground when the support structure is not high enough.

Off-Center-Loaded Dipole

(A)

D = Diameter, Inches

Inductively and Capacitively
Loaded Dipole

Wooden Spreader

(B)

Fan Dipole

(C)

Fig 70—At A is a dipole antenna lengthened electrically with off-center loading coils. For a fixed dimension A, greater efficiency will be realized with greater distance B, but as B is increased, L must be larger in value to maintain resonance. If the two coils are placed at the ends of the antenna, in theory they must be infinite in size to maintain resonance. At B, capacitive loading of the ends, either through proximity of the antenna to other objects or through the addition of capacitance hats, will reduce the required value of the coils. At C, a fan dipole provides some electrical lengthening as well as broadbanding.

as a full-length dipole.

The resonant length of the wire will be somewhat shorter than a full-length dipole and can best be determined by experimentally adjusting the length of ends, which may be conveniently near ground. Keep in mind that there can be very high potentials at the ends of the wires and for safety the ends should be kept out of reach. Letting the ends hang down as shown is a form of capacitive end loading. While it is efficient, it will also reduce the matching bandwidth—as does any form of loading.

The most serious drawback associated with inductive loading is high loss in the coils themselves. It is important that you use inductors made from reasonably large wire or tubing to minimize this problem. Close winding of turns should also be avoided if possible. A good compromise is to use some off-center inductive loading in combination with capacitive end loading, keeping the inductor losses small and the efficiency as high as possible.

Some examples of off-center coil loading and capacitive-end loading are shown in **Fig 70**. This technique was described by Jerry Hall, K1TD in Sep 1974 *QST*. In the equation below, the diameter D is that of the wire used for the antenna, in inches. The frequency f is expressed in MHz.

Fig 71—Chart for determining approximate inductance values for off-center-loaded dipoles. See Fig 70A. At the intersection of the appropriate curve from the body of the chart for dimension A and proper value for the coil position from the horizontal scale at the bottom of the chart, read the required inductive reactance for resonance from the scale at the left. Dimension A is expressed as percent length of the shortened antenna with respect to the length of a half-wave dipole of the same conductor material. Dimension B is expressed as the percentage of coil distance from the feed point to the end of the antenna. For example, a shortened antenna, which is 50% or half the size of a half-wave dipole (one-quarter wavelength overall) with loading coils positioned midway between the feed point and each end (50% out), would require coils having an inductive reactance of approximately 950 Ω at the operating frequency for antenna resonance.

Fig 72—The WØSVM "Shorty Forty" center-loaded antenna. Dimensions given are for 7.0 MHz. The loading coil is 5 inches long and 2½ inches diameter. It has a total of 30 turns of #12 wire wound at 6 turns per inch (Miniductor 3029 stock).

For the antennas shown, the longer the overall length (dimension A, Fig 70A, in feet) and the farther the loading coils are from the center of the antenna (dimension B, also in feet), the greater the efficiency of the antenna. As dimension B is increased, however, the inductance required to resonate the antenna at the desired frequency increases.

Approximate inductive reactances for single-band resonance (for the antenna in Fig 70A only) may be determined with the aid of **Fig 71** or from Eq 10 below. The final values will depend on the proximity of surrounding objects in individual installations and must be determined experimentally. The use of high-Q low-loss coils is important for maximum efficiency.

A dip meter or SWR indicator is recommended for use during adjustment of the system. Note that the minimum inductance required is for a center-loaded dipole. If the inductive reactance is read from Fig 66 for a dimension B of zero, one coil having approximately twice this reactance can be used near the center of the dipole. **Fig 72** illustrates this idea. This antenna was conceived by Jack Sobel, WØSVM, who dubbed the 7-MHz version the "Shorty Forty."

$$X_L = \frac{10^6}{34\pi f} \left(\frac{\ln\dfrac{24\left(\dfrac{234}{f}\right)-B}{D}-1\left(\left(1-\dfrac{fB}{234}\right)^2-1\right)}{\dfrac{234}{f}-B} - \frac{\ln\dfrac{24\left(\dfrac{A}{2}-B\right)}{D}-1\left(\dfrac{\dfrac{fA}{2}-fB}{234}\right)^2-1}{\dfrac{A}{2}-B} \right) \quad \text{(Eq 10)}$$

Inverted-L Antennas

The antenna shown in **Fig 73** is called an *inverted-L* antenna. It is simple and easy to construct and is a good antenna for the beginner or the experienced 1.8-MHz DXer. Because the overall electrical length is made somewhat greater than λ/4, the feed-point resistance is on the order of 50 Ω, with an inductive reactance. That reactance is canceled by a series capacitor as indicated in the figure. For a vertical section length of 60 feet and a horizontal section length of 115 feet, the input impedance is ≈ 40 + *j* 300 Ω. Longer vertical or horizontal sections would increase the input impedance. The azimuthal radiation pattern is slightly asymmetrical with ≈1 to 2-dB increase in the direction opposite to the horizontal wire. This antenna requires a good buried ground system or elevated radials and will have a 2:1 SWR bandwidth of about 50 kHz.

This antenna is a form of top-loaded vertical, where the top loading is asymmetrical. This results in both vertical and horizontal polarization because the currents in the top wire do not cancel like they would in a symmetrical-T vertical. This is not necessarily a bad thing because it eliminates the zenith null present in a true vertical. This allows for good communication at short ranges as well as for DX.

A yardarm attached to a tower or a tree limb can be used to support the vertical section. As with any vertical, for best results the vertical section should be as long as possible. A good ground system is necessary for good results—the better the ground, the better the results.

If you don't have the space for the inverted L shown in Fig 73 (with its 115-foot horizontal section) and if you don't have a second tall supporting structure to make the top

Fig 73—The 1.8-MHz inverted L. Overall wire length is 165 to 175 feet. The variable capacitor has a capacitance range from 100 to 800 pF, at 3 kV or more. Adjust antenna length and variable capacitor for lowest SWR.

Fig 74—Sketch showing a modified 160-meter inverted L, with a single supporting 60-foot high tower and a 79-foot long slanted top-loading wire. The feed-point impedance is about 12 Ω in this system, requiring a quarter-wave matching transformer made of paralleled 50-Ω coaxes.

Max. Gain = 0.85 dBi   Freq. = 1.83 MHz

Fig 75—Overlay of the elevation responses for the inverted-L antennas in Fig 73 (solid line) and Fig 74 (dashed line). The gains are very close for these two setups, provided that the ground radial system for the antenna in Fig 74 is extensive enough to keep ground losses low.

Fig 76—A single elevated radial can be used for the inverted-L. This changes the directivity slightly. The series tuning capacitor is approximately 175 pF for this system.

Max. Gain = -1.87 dBi   Elevation = 10 deg.
                               Freq. = 1.83 MHz

Fig 77—Azimuthal pattern comparison for inverted-L antennas shown in Fig 73 (solid line) and the compromise, single-radial system in Fig 76 (dashed line). This is for a takeoff angle of 10°.

wire horizontal, consider sloping the top wire down towards ground. **Fig 74** illustrates such a setup, with a 60-foot high vertical section and a 79-foot sloping wire. As always, you will have to adjust the length of the sloping wire to fine-tune the resonant frequency. For a good ground radial system, the feed-point impedance is about 12 Ω, which may be transformed to 50 Ω with a 25-Ω quarter-wave transformer consisting of two paralleled 50-Ω quarter-wave coaxes. The peak gain will decrease about 1 dB compared to the inverted L shown in Fig 73. **Fig 75** overlays the elevation responses for average ground conditions. The 2:1 SWR bandwidth will be about 30 kHz, narrower than the larger system in Fig 73.

If the ground system suggested for Figs 73 and 74 is not practical, you can use a single elevated radial as shown in **Fig 76**. For the dimensions shown in the figure $Z_i = 50 + j\,498$ Ω, requiring a 175-pF series resonating capacitor. The azimuthal radiation pattern is shown in **Fig 77** compared to

Fig 78—Azimuthal pattern at a takeoff angle of 5° for an 80-meter version of the inverted L (solid line) in Fig 73, compared to the response for a 100-foot high flattop dipole (dashed line).

Fig 79—Details and dimensions for gamma-match feeding a 50-foot tower as a 1.8-MHz vertical antenna. The rotator cable and coaxial feed line for the 14-MHz beam is taped to the tower legs and run into the shack from ground level. No decoupling networks are necessary.

the inverted L in Fig 68. Note that the 1 to 2-dB asymmetry is now in the direction of the horizontal wires, just the opposite of that for a symmetrical ground system. The 2:1 SWR bandwidth is about 40 kHz, assuming that the series capacitor is adjusted at 1.83 MHz for minimum SWR.

Fig 78 shows the azimuthal response at a 5° elevation angle for an 80-meter version of the inverted L in Fig 73. The peak response occurs at an azimuth directly behind the direction in which the horizontal portion of the inverted L points. For comparison, the response for a 100-foot high flattop dipole is also shown. The top wire of this antenna is only 40 feet high and the 2:1 SWR bandwidth is about 150 kHz wide with a good, low-loss ground-radial system.

Fig 78 illustrates that the azimuth response of an inverted L is nearly omnidirectional. This gives such an antenna an advantage in certain directions compared to a flattop dipole, which is constrained by its supporting mounts (such as trees or towers) to favor fixed directions. For example, the flattop dipole in Fig 78 is at its weakest at azimuths of 90° and 270°, where it is down about 12 dB compared to

the inverted L. Hams who are fortunate enough to have high rotary dipoles or rotatable low-band Yagis have found them to be very effective antennas indeed.

A DIFFERENT APPROACH

Fig 79 shows the method used by Doug DeMaw, W1FB, to gamma match his self-supporting 50-foot tower operating as an inverted L. A wire cage simulates a gamma rod of the proper diameter. The tuning capacitor is fashioned from telescoping sections of 1½ and 1½-inch aluminum tubing with polyethylene tubing serving as the dielectric. This capacitor is more than adequate for power levels of 100 W. The horizontal wire connected to the top of the tower provides the additional top loading.

Sloper Antennas

Sloping dipoles and λ/2 dipoles can be very useful antennas on the low bands. These antennas can have one end attached to a tower, tree or other structure and the other end near ground level, elevated high enough so that passersby can't contact them, of course. The following section gives a number of examples of these types of antennas.

THE HALF-WAVE SLOPING DIPOLE

If you have a sufficiently high support, you can install a halfwave dipole sloping downwards toward ground to provide

vertical as well as horizontal polarization. This antenna is popularly known as a *sloper* or a *halfwave sloper*. The amount of slope from horizontal can vary from 0°, where the dipole is in a flattop configuration, all the way to 90°, where the dipole becomes fully vertical. The latter configuration is sometimes called a *Halfwave Vertical Dipole* (HVD).

The question arises when contemplating a vertical half-wave dipole or a halfwave sloping dipole about how to treat the feed line to make sure it doesn't accidentally become part of the radiating system. The ideal situation would be to bring the feed line out perpendicular to the vertical or sloping wire for an infinite distance. Obviously, that isn't very practical because the feed line eventually has to be connected to a transmitter located near the ground. An intensive modeling study on feeding an HVD was done for the book *Simple and Fun Antennas for Hams*. This study indicated that a slant angle down to the ground of as little as 30° from a vertical radiator can work with only minor interaction, provided that common-mode decoupling chokes were employed at the feed point and a quarter-wavelength down the line from the feed point. These common-mode chokes can consist of either discrete ferrite beads placed over the outer jacket of the coaxial line or multiple turns of the coax itself to form a choke.

Fig 80A compares the 40-meter azimuthal patterns at a DX takeoff angle of 5° for three configurations: a flattop dipole, a dipole tilted down 45° and an HVD (halfwave vertical dipole). These are computed for ground with average conductivity and dielectric constant, and for a maximum height of 80 feet in each configuration. The sloping halfwave dipole exhibits about 5 dB of front-to-back ratio, although even at its most favored direction it doesn't quite have the same maximum gain as the HVD or the flattop dipole.

The reason why the maximum gain for the sloper is less than the other two configurations, even while still exhibiting some front-to-back pattern, is shown in Fig 80A, which shows the elevation-plane patterns for the same antennas, each at the azimuth of maximum gain. The halfwave sloper distributes much of its energy higher in elevation than the HVD, lowering the peak-gain potential of the sloper.

You can also see from Fig 80B that the 80-foot high horizontal dipole would perform much better than either the HVD or halfwave sloper for close-in local contacts, which occur at high elevation angles. On the other hand, except for the greater gain exhibited in the flattop dipole's most favored directions, the HVD has more gain than the other antennas at low elevation angles. While the HVD's omnidirectional pattern is a plus for transmitting, it may be a problem for receiving, where local noise may be coming from specific directions (such as power lines) and may also be predominantly vertically polarized. In such cases, a horizontally polarized flattop dipole may be a considerably better receiving antenna than a vertically polarized antenna of any sort. We've already mentioned the fact that a rotary flattop dipole high in the air can be a very effective antenna on the low bands.

Fig 80—At A, the azimuthal responses for a flattop dipole (solid line), a dipole whose end has been tilted down 45° (dashed line), and a HVD (halfwave vertical dipole, dotted line). All these were modeled over average ground, with a conductivity of 5 mS/m and a dielectric constant of 13. Note that the tilted dipole exhibits about 5 dB front-to-back ratio, although its maximum gain is less than either the HVD or flattop dipole. At B, the elevation-plane patterns for the same antennas. Note that the tilted halfwave dipole (dashed line) has more energy at higher elevation angles than either the flattop dipole or HVD.

THE QUARTER-WAVELENGTH "HALF SLOPER"

Perhaps one of the easiest antennas to install is the λ/4 sloper shown in **Fig 81**. As pointed out above, a sloping λ/2 dipole is known among radio amateurs as a *sloper* or sometimes as a *full sloper*. If only one half of it is used, it becomes a *half sloper*. The performance of the two types of sloping antennas is similar—They exhibit some directivity in the direction of the slope and radiate vertically polarized energy at low angles respective to the horizon. The amount of directivity will range from 3 to 6 dB, depending upon the individual installation, and will be observed in the slope direction.

The main advantage of the half sloper over the full half-wave-long sloping dipole is that its supporting tower needn't be as high. Both the half sloper and the full sloper place the feed point (the point of maximum current) high above lossy ground. But the half-sloper only needs half as much wire to build the antenna for a given amateur band. The disadvantage of the half sloper is that it is sometimes difficult or even impossible to obtain a low SWR when using coaxial-cable feed, especially without a good isolating choke balun. (See the section above on isolating ground-plane antennas.)

Other factors that affect the feed impedance are tower height, height of the attachment point, enclosed angle between the sloper and the tower, and what is mounted atop the tower (HF or VHF beams). Further, the quality of the ground under the tower (ground conductivity, radials, etc) has a marked effect on the antenna performance. The final SWR can vary (after optimization) from 1:1 to as high as 6:1. Generally speaking, the closer the low end of the slope wire is to ground, the more difficult it will be to obtain a good match.

Basic Recommendations for a Half Sloper

The half sloper can be an excellent DX type of antenna. Hams usually install theirs on a metal supporting structure such as a mast or tower. The support needs to be grounded at the lower end, preferably to a buried or on-ground radial system. If a nonconductive support is used, the outside of the coax braid becomes the return circuit and should be grounded at the base of the support. As a starting point you can attach the sloper so the feed point is approximately λ/4 above ground. If the tower is not high enough to permit this, the antenna should be fastened as high on the supporting structure as possible. Start with an enclosed angle of approximately 45°, as indicated in Fig 81. Cut the wire to the length determined from

$$\ell = \frac{260}{f_{MHz}} \qquad \text{(Eq 11)}$$

This will allow sufficient extra length for pruning the wire for the lowest SWR. A metal tower or mast becomes an operating part of the half sloper system. In effect, it and the slope wire function somewhat like an inverted-V dipole antenna. In other words, the tower operates as the missing half of the dipole. Hence its height and the top loading (beams) play a significant role.

Detailed modeling indicates that a sufficiently large

Fig 81—The λ/4 "half sloper" antenna.

Max. Gain = -5.7 dBi

Elevation Angle = 5 deg
Freq. = 3.8 MHz

Fig 82—Radiation pattern for a typical half sloper (solid line) mounted on a 50-foot high tower with a large 5-element 20-meter beam on the top compared to that for a flattop dipole (dashed line) at 100 feet. At a 5° takeoff angle typical for DX work on 80 meters, the two antennas are pretty comparable in the directions favored by the high dipole. In other directions, the half sloper has an advantage of more than 10 dB.

Fig 83—Comparison of elevation patterns for a full-sized halfwave sloper (solid line) on a 100-foot tower and a half sloper (dashed line) on a 50-foot tower with a 5-element 20-meter Yagi acting as a top counterpoise. The performance is quite comparable for these two systems.

Fig 84—Comparing the azimuthal response of a half sloper (solid line) on a 50-foot tower with a 3-element 20-meter Yagi on top to that of a flattop dipole (dashed line) at 100 feet. The two are again quite comparable at a 5° takeoff angle.

mass of metal (that is, a large, "Plumber's Delight" Yagi) connected to the top of the tower acts like enough of a "top counterpoise" that the tower may be removed from the model with little change in the essential characteristics of the half-sloper system. Consider an installation using a freestanding 50-foot tower with a large 5-element 20-meter Yagi on top. This Yagi is assumed to have a 40-foot boom oriented 90° to the direction of the slanted 80-meter half-sloper wire. The best SWR that could be reached by changing the length and slant angle for this sloper is 1.67:1, representing a feed-point impedance of 30.1 – j 2.7 Ω. The peak gain at 3.8 MHz is 0.97 dBi at an elevation angle of 70°. **Fig 82** shows the azimuth-plane pattern for this half sloper, compared to a 100-foot high flattop dipole for reference, at an elevation angle of 5°.

Removing the tower from the model resulted in a feed-point impedance of 30.1 – j 1.5 Ω and a peak gain of 1.17 dBi. The tower is obviously not contributing much in this setup, since the mass of the large 20-meter Yagi is acting like an elevated counterpoise all by itself. It's interesting to rotate the boom of the model Yagi and observe the change in SWR that occurs on the half-sloper antenna. With the boom turned 90°, the SWR falls to 1.38:1. This level of SWR change could be measured with amateur-type instrumentation.

On the other hand, substituting a smaller 3-element 20-meter Yagi with an 18-foot boom in the model does result in significant change in feed-point impedance and gain when the tower is removed from the model, indicating that the "counterpoise effect" of the smaller beam is insufficient by itself. Interestingly enough, the best SWR for the half sloper/tower and the 3-element Yagi (with its boom inline with the half sloper is 1.33:1), changing to 1.27:1 with the boom turned 90°. Such a small change in SWR would be difficult to measure using typical amateur instrumentation.

In any case, the 50-Ω transmission line feeding a half sloper should be taped to the tower leg at frequent intervals to make it secure. The best method is to bring it to earth level,

then route it to the operating position along the surface of the ground if it can't be buried. This will ensure adequate RF decoupling, which will help prevent RF energy from affecting the equipment in the station. Rotator cable and other feed lines on the tower or mast should be treated in a similar manner.

Adjustment of the half sloper is done with an SWR indicator in the 50-Ω transmission line. A compromise can usually be found between the enclosed angle and wire length, providing the lowest SWR attainable in the center of the chosen part of an amateur band. If the SWR "bottoms out" at 2:1 or lower, the system will work fine without using an antenna tuner, provided the transmitter can work into the load. Typical optimum values of SWR for 3.5 or 7-MHz half slopers are between 1.3:1 and 2:1. A 100-kHz bandwidth is normal on 3.5 MHz, with 200 kHz being typical at 7 MHz.

If the lowest SWR possible is greater than 2:1, the attachment point can be raised or lowered to improve the match. Readjustment of the wire length and enclosed angle may be necessary when the feed-point height is changed. If the tower is guyed, the guy wires will need to be insulated from the tower and broken up with additional insulators to prevent resonance.

At this point you may be curious about which antenna is better—a full sloper or a half sloper. The peak gain for each antenna is very nearly identical. **Fig 83** overlays the elevation-plane pattern for the full-sized halfwave sloper on a 100-foot tower and for the half sloper shown in Fig 81 on a 50-foot tower with a 5-element 20-meter Yagi on top. The

Fig 85—The W1CF half sloper for 160 meters is arranged in this manner. Three monoband antennas atop the tower provide capacitive loading.

Relay Switch Box

45°

130'

92' Tower

Guy Wires

Guy Wires

15'

Tower Ground

Guy Wires

Ground Anchor

52 Ω
Transmission Line

Ground Anchor

full-sized halfwave sloper has more front-to-back ratio, but it is only a few dB more than the half sloper. **Fig 84** compares the azimuthal patterns at a 5° takeoff angle for a 100-foot high flattop dipole and a half-sloper system on a 50-foot tower with a 3-element 20-meter Yagi on top.

Despite the frustration some have experienced trying to achieve a low SWR with some half-sloper installations, many operators have found the half sloper to be an effective and low-cost antenna for DX work.

1.8-MHz ANTENNA SYSTEMS USING TOWERS

The half sloper discussed above for 80 or 40-meter operation will also perform well on 1.8 MHz where vertically polarized radiators can achieve the low takeoff angles needed on Topband. Prominent 1.8-MHz operators who have had success with the half sloper antenna suggest a minimum tower height of 50 feet. Dana Atchley, W1CF (SK), used the configuration sketched in **Fig 85**. He reported that the uninsulated guy wires act as an effective counterpoise for the sloping wire. In **Fig 86** is the feed system used by Doug

Insulator

Aluminum Clamp

λ/4 Radiator

Shield Braid Under Clamp

Seal With Epoxy

Tower Leg

Insulator

Tape

to Station

Fig 86—Feed system used by W1FB for 1.8 MHz half sloper on a 50-foot self-supporting tower.

DeMaw, W1FB (SK), on a 50-foot self-supporting tower. The ground for the W1FB system is provided by buried radials connected to the tower base.

As described previously, a tower can also be used as a true vertical antenna, provided a good ground system is used. The shunt-fed tower is at its best on 1.8 MHz, where a full λ/4 vertical antenna is rarely possible. Almost any tower height can be used. An HF beam at the top provides some top loading.

THE K1WA 7-MHz "SLOPER SYSTEM"

One of the more popular antennas for 3.5 and 7 MHz is the half-wave long sloping dipole described previously. David Pietraszewski, K1WA, made an extensive study of sloping dipoles at different heights with reflectors at the 3-GHz frequency range. From his experiments, he developed the novel 7-MHz antenna system described here. With several sloping dipoles supported by a single mast and a switching network, an antenna with directional characteristics and forward gain can be simply constructed. This 7-MHz system uses several "slopers" equally spaced around a common center support. Each dipole is cut to λ/2 and fed at the center with 50-Ω coax. The length of each feed line is 36 feet.

All of the feed lines go to a common point on the support (tower) where the switching takes place. The line length of 36 feet is just over 3λ/8, which provides a useful quality. At 7 MHz, the coax looks inductive to the antenna when the end at the switching box is open circuited. This has the effect of adding inductance at the center of the sloping dipole element, which electrically lengthens the element. The 36-foot length of feed line serves to increase the length of the element about 5%. This makes any unused element appear to be a reflector.

The array is simple and effective. By selecting one of the slopers through a relay box located at the tower, the system becomes a parasitic array that can be electrically rotated. All but the driven element of the array become reflectors.

The physical layout is shown in **Fig 87**, and the basic materials required for the sloper system are shown in **Fig 88**. The height of the support point should be about 70 feet, but can be less and still give reasonable results. The upper portion of the sloper is 5 feet from the tower, suspended by rope. The wire makes an angle of 60° with the ground.

Fig 88—The basic materials required for the sloper system. The control box appears at the left, and the relay box at the right.

Fig 87—Five sloping dipoles suspended from one support. Directivity and forward gain can be obtained from this simple array. The top view shows how the elements should be spaced around the support.

Fig 89—Inside view of relay box. Four relays provide control over five antennas. See text. The relays pictured here are Potter and Brumfeld type MR11D.

In **Fig 89**, the switch box is shown containing all the necessary relays to select the proper feed line for the desired direction. One feed line is selected at a time and the feed lines of those remaining are opened, **Fig 90**. In this way the array is electrically rotated. These relays are controlled from inside the shack with an appropriate power supply and rotary switch. For safety reasons and simplicity, 12-volt dc relays are used. The control line consists of a five conductor cable, one wire used as a common connection; the others go to the four relays. By using diodes in series with the relays and a dual-polarity power supply, the number of control wires can be reduced, as shown in Fig 90B.

Measurements indicate that this sloper array provides up to 20 dB front-to-back ratio and forward gain of about 4 dB over a single half-wave sloper. **Fig 91** shows the azimuthal pattern (at a 5° takeoff angle) for the K1WA array, compared to a 100-foot high flattop dipole and a full sloper suspended from a 50-foot tower. These patterns were calculated for average ground conditions. Just for fun, look at

Fig 90—Schematic diagram for sloper control system. All relays are 12-volt dc, DPDT, with 8-A contact ratings. At A, the basic layout, excluding control cable and antennas. Note that the braid of the coax is also open-circuited when not in use. Each relay is bypassed with 0.001-μF capacitors. The power supply is a low current type. At B, diodes are used to reduce the number of control wires when using dc relays. See text.

Fig 91—Azimuth pattern for K1WA 40-meter sloper array (solid line), compared to a flattop dipole (dashed line) at 100 feet and a halfwave full sloper on a 50-foot tower (dotted line). The K1WA array has an excellent front-to-back ratio and almost as much gain as the high flattop dipole. These patterns are for average ground.

Fig 92, which shows a comparison between a 100-foot high flattop dipole and a K1WA array placed over saltwater. Now that's a real barnburner at low takeoff angles! Such a seaside system would be very competitive with a rotatable 2-element "shorty-40" type of Yagi.

   If one direction is the only concern, the switching system can be eliminated and the reflectors should be cut 5% longer than the resonant frequency. The feature worth noting is the good F/B ratio. By arranging the system properly, a null can be placed in an unwanted direction, thus making it an effective receiving antenna. In the tests conducted with this antenna, the number of reflectors used were as few as one and as many as five. The optimum combination appeared to occur with four reflectors and one driven element. No tests were conducted with more than five reflectors. This same array can be scaled to 3.5 MHz for similar results.

BIBLIOGRAPHY

   Source material and more extended discussion of topics covered in this chapter can be found in the references given below.

D. Atchley, Jr., "Putting the Quarter-Wave Sloper to Work on 160," *QST*, Jul 1979, pp 19-20.

J. Belrose, "Transmission Line Low Profile Antennas," *QST*, Dec 1975, pp 19-25.

L. Braskamp, AA6GL, "*MOBILE*, a Computer Program for Short HF Verticals," *The ARRL Antenna Compendium Vol 4*, pp 92-96.

G. H. Brown, "The Phase and Magnitude of Earth Currents Near Radio Transmitting Antennas," *Proc. IRE*.

G. H. Brown, R. F. Lewis and J. Epstein, "Ground Systems as a Factor in Antenna Efficiency," *Proc. IRE* , Jun 1937, pp 753-787.

P. Carr, N4PC, "A Two Band Half-Square Antenna With Coaxial Feed," *CQ*, Sep 1992, pp 40-45.

P. Carr, N4PC, "A DX Antenna For 40 Meters," *CQ*, Sep 1994, pp 40-43.

A. Christman, KB8I, "Elevated Vertical Antennas for the Low Bands," *The ARRL Antenna Compendium Vol 5*, pp 11-18.

Curry Communications, PO Box 1884, Burbank, CA 91507, a kit manufacturer of lowfer CW transceivers.

D. DeMaw, "Additional Notes on the Half Sloper," *QST*, Jul 1979, p 20.

Fig 92—The K1WA 40-meter sloper array over saltwater, compared to a 100-foot high flattop dipole. At A, azimuth patterns. At B, elevation patterns. Now the sloper array really comes into its own!

P. Dodd, *The LF Experimenter's Source Book* (RSGB, 1996).

A. C. Doty, Jr., J. A. Frey and H. J. Mills, "Efficient Ground Systems for Vertical Antennas," *QST*, Feb 1983, pp 9-12.

S. Ford, "*Low*fing on 1750 Meters," *QST*, Oct 1993, pp 67-68.

R. Fosberg, "Some Notes on Ground Systems for 160 Meters," *QST*, Apr 1965, pp 65-67.

J. Hall, "Off-Center-Loaded Dipole Antennas," *QST*, Sep 1974, pp 28-34.

G. Hubbell, "Feeding Grounded Towers as Radiators," *QST*, pp 32-33, 140, 142.

C. Hutchinson and R. D. Straw, *Simple and Fun Antennas for Hams* (Newington, Ct: ARRL, 2002).

P. H. Lee, *The Amateur Radio Vertical Antenna Handbook*, 1st edition (Port Washington, NY: Cowan Publishing Corp., 1974).

C. J. Michaels, "Some Reflections on Vertical Antennas," *QST*, July 1987, pp 15-19; feedback *QST*, Aug 1987, p 39.

Rashed and C. Tai, "A New Class of Wire Antennas," 1982 International Symposium Digest, *Antennas and Propagation*, Vol 2, IEEE.

T. Russell, N4KG, "Simple, Effective, Elevated Ground-Plane Antennas," *QST*, June 1994, pp 45-46

F. J. Schnell, "The Flagpole Deluxe," *QST*, Mar 1978, pp 29-32.

R. Severns, N6LF, "Using the Half-Square Antenna for Low-Band Dxing," *The ARRL Antenna Compendium Vol 5*, pp 35-42.

R. Severns, N6LF, "Broadbanding the Half-Square Antenna For 80-meter Dxing," *The ARRL Antenna Compendium Vol 5*, pp 43-44.

R. Severns, N6LF, "An Improved Double Extended Zepp," *The ARRL Antenna Compendium Vol 4*, pp 78-80.

J. Sevick, "The Ground-Image Vertical Antenna," *QST*, Jul 1971, pp 16-19, 22.

J. Sevick, "The W2FMI Ground-Mounted Short Vertical," *QST*, Mar 1973, pp 13-18, 41.

J. Sevick, "The Constant-Impedance Trap Vertical," *QST* , Mar 1974, pp 29-34.

J. Sevick, "Short Ground-Radial Systems for Short Verticals," *QST*, Apr 1978, pp 30-33.

J. Sevick, W2FMI, *Transmission Line Transformers* (Noble Publishing, Atlanta, 1996).

W. Smith, W6BCX, "Bet My Money On A Bobtail Beam," *CQ*, Mar 1948, pp 21-23, 92.

J. Stanford, NNØF, "Linear-Loaded Short Wire Antennas," *The ARRL Antenna Compendium Vol 5*, pp 105-107.

J. Swank, W8HXR, "The S-Meter Bender," *73*, Jun 1978, pp 170-173.

J. Tyskewicz, "The Heli-Rope Antenna," *QST*, Jun 1971.

B. Vester, K3BC, "The Half-Square Antenna," *QST*, Mar 1974, pp 11-14.

A. D. Watt, *VLF Radio Engineering* (Pergamon Press, 1967) (out of print).

Prediction of Sky-wave Field Strength at Frequencies Between About 150 and 1700 kHz, ITU Doc 3/14, Radiocommunication Study Groups, Feb 1995.

Multiband Antennas

For operation in a number of bands, such as those between 3.5 and 30 MHz, it would be impractical for most amateurs to put up a separate antenna for each band. But this is not necessary—a dipole, cut for the lowest frequency band to be used, can be operated readily on higher frequencies. To do so, one must be willing to accept the fact that such harmonic-type operation leads to a change in the directional pattern of the antenna, both in the azimuth and the elevation planes (see Chapter 2, Antenna Fundamentals, and Chapter 3, The Effects of Ground).

You can see from discussions in Chapter 6, Low-Frequency Antennas, that you should carefully plan the height at which you install a multiband horizontally polarized antenna. This is one aspect of multiband antennas. Another important thing to consider is that you should be willing to use so-called *tuned feeders*. A center-fed single-wire antenna can be made to accept power and radiate it with high efficiency on any frequency higher than its fundamental resonant frequency and, with a reduction in efficiency and bandwidth, on frequencies as low as one half the fundamental.

In fact, it is not necessary for an antenna to be a full half-wavelength long at the lowest frequency. An antenna can be considerably shorter than ½ λ, even as short as ¼ λ, and still be a very efficient radiator. The use of such short antennas results in stresses, however, on other parts of the system, for example the antenna tuner and the transmission line. This will be discussed in some detail in this chapter.

Methods have been devised for making a single antenna structure operate on a number of bands while still offering a good match to a transmission line, usually of the coaxial type. It should be understood, however, that a multiband antenna is not *necessarily* one that will match a given line on all bands on which you intend to use it. Even a relatively short whip type of antenna can be operated as a multiband antenna with suitable loading for each band. Such loading may be in the form of a coil at the base of the antenna on those frequencies where loading is needed, or it may be incorporated in the tuned feeders running from the transmitter to the base of the antenna.

This chapter describes a number of systems that can be used on two or more bands. Beam antennas, such as Yagis or quads, are treated separately in later chapters.

Simple Wire Antennas

The simplest multiband antenna is a random length of #12 or #14 wire. Power can be fed to the wire on practically any frequency using one or the other of the methods shown in **Fig 1**. If the wire is made either 67 or 135 feet long, it can also be fed through a tuned circuit, as in **Fig 2**. It is advantageous to use an SWR bridge or other indicator in the coax line at the point marked "X."

If you have installed a 28- or 50-MHz rotary beam, in many cases it may be possible to use the beam's feed line as an antenna on the lower frequencies. Connecting the two wires of the feeder together at the station end will give a random-length wire that can be conveniently coupled to the transmitter as in Fig 1. The rotary system at the far end will serve only to *end-load* the wire and will not have much other effect.

Fig 1—At A, a random-length wire driven directly from the pi-network output of a transmitter. At B, an L network for use in cases where sufficient loading cannot be obtained with the arrangement at A. C1 should have about the same plate spacing as the final tank capacitor in a vacuum-tube type of transmitter; a maximum capacitance of 100 pF is sufficient if L1 is 20 to 25 μH. A suitable coil would consist of 30 turns of #12 wire, 2½ inches diameter, 6 turns per inch. Bare wire should be used so the tap can be placed as required for loading the transmitter.

Fig 2—If the antenna length is 137 feet, a parallel-tuned coupling circuit can be used on each amateur band from 3.5 through 30 MHz, with the possible exception of the WARC 10-, 18- and 24-MHz bands. C1 should duplicate the final tank tuning capacitor and L1 should have the same dimensions as the final tank inductor on the band being used. If the wire is 67 feet long, series tuning can be used on 3.5 MHz as shown at the left; parallel tuning will be required on 7 MHz and higher frequency bands. C2 and L2 will in general duplicate the final tank tuning capacitor and inductor, the same as with parallel tuning. The L network shown in Fig 1B is also suitable for these antenna lengths.

One disadvantage of all such directly fed systems is that part of the antenna is practically within the station, and there is a good chance that you will have some trouble with RF feedback. RF within the station can often be minimized by choosing a length of wire so that the low feed-point impedance at a current loop occurs at or near the transmitter. This means using a wire length of $\lambda/4$ (65 feet at 3.6 MHz, 33 feet at 7.1 MHz), or an odd multiple of $\lambda/4$ (¾-λ is 195 feet at 3.6 MHz, 100 feet at 7.1 MHz). Obviously, this can be done for only one band in the case of even harmonically related bands, since the wire length that presents a current loop at the transmitter will present a voltage loop at two (or four) times that frequency.

When you operate with a random-length wire antenna, as in Figs 1 and 2, you should try different types of grounds on the various bands, to see what gives you the best results. In many cases it will be satisfactory to return to the transmitter chassis for the ground, or directly to a convenient metallic water pipe. If neither of these works well (or the metallic water pipe is not available), a length of #12 or #14 wire (approximately $\lambda/4$ long) can often be used to good advantage. Connect the wire at the point in the circuit that is shown grounded, and run it out and down the side of the house, or support it a few feet above the ground if the station is on the first floor or in the basement. It should not be connected to actual ground at any point.

END-FED ANTENNAS

When a straight-wire antenna is fed at one end with a two-wire transmission line, the length of the antenna portion becomes critical if radiation from the line is to be held to a minimum. Such an antenna system for multiband operation is the *end-fed Zepp* or *Zepp-fed* antenna shown in **Fig 3**. The antenna length is made $\lambda/2$ long at the lowest operating frequency. (This name came about because the first documented use of this sort of antennas was on the *Zeppelin* airships.) The feeder length can be anything that is convenient, but feeder lengths that are multiples of $\lambda/4$ generally give trouble with parallel currents and radiation from the feeder portion of the system. The feeder can be an open-wire line of #14 solid

Fig 3—An end-fed Zepp antenna for multiband use.

copper wire spaced 4 or 6 inches with ceramic or plastic spacers. Open-wire TV line (not the type with a solid web of dielectric) is a convenient type to use. This type of line is available in approximately 300- and 450-Ω characteristic impedances.

If you have room for only a 67-foot flat top and yet want to operate in the 3.5-MHz band, the two feeder wires can be tied together at the transmitter end and the entire system treated as a random-length wire fed directly, as in Fig 1. The simplest precaution against parallel currents that could cause feed-line radiation is to use a feeder length that is not a multiple of λ/4. An antenna tuner can be used to provide multiband coverage with an end-fed antenna with any length of open-wire feed line, as shown in Fig 3.

CENTER-FED ANTENNAS

The simplest and most flexible (and also least expensive) all-band antennas are those using open-wire parallel-conductor feeders to the center of the antenna, as in **Fig 4**. Because each half of the flat top is the same length, the feeder currents will be balanced at all frequencies unless, of course, unbalance is introduced by one half of the antenna being closer to ground (or a grounded object) than the other. For best results and to maintain feed-current balance, the feeder should run away at right angles to the antenna, preferably for at least λ/4.

Center feed is not only more desirable than end feed because of inherently better balance, but generally also results in a lower standing wave ratio on the transmission line, provided a parallel-conductor line having a characteristic impedance of 450 to 600 Ω is used. TV-type open-wire line is satisfactory for all but possibly high power installations (over 500 W), where heavier wire and wider spacing is desirable to handle the larger currents and voltages.

The length of the antenna is not critical, nor is the length of the line. As mentioned earlier, the length of the antenna can be considerably less than λ/2 and still be very effective. If the overall length is at least λ/4 at the lowest frequency, a quite usable system will result. The only difficulty that may exist with this type of system is the matter of coupling the antenna-system load to the transmitter. Most modern transmitters are designed to work into a 50-Ω coaxial load. With this type of antenna system a coupling network (an antenna tuner) is required.

Feed-Line Radiation

The preceding sections have pointed out means of reducing or eliminating feed-line radiation. However, it should be emphasized that any radiation from a transmission line is not "lost" energy and is not necessarily harmful. Whether or not feed-line radiation is important depends entirely on the antenna system being used. For example, feed-line radiation is not desirable when a directive array is being used. Such feed-line radiation can distort the desired pattern of such an array, producing responses in unwanted directions. In other words, you want radiation only from the directive array,

Fig 4—A center-fed antenna system for multiband use.

rather than from the directive array and the feed line. See Chapter 26, Coupling the Line to the Antenna, for a detailed discussion of this topic.

On the other hand, in the case of a multiband dipole where general coverage is desired, if the feed line happens to radiate, such energy could actually have a desirable effect. Antenna purists may dispute such a premise, but from a practical standpoint where you are not concerned with a directive pattern, much time and labor can be saved by ignoring possible transmission-line radiation.

THE 135-FOOT, 80 TO 10-METER DIPOLE

As mentioned previously, one of the most versatile antennas around is a simple dipole, center-fed with open-wire transmission line and used with an antenna tuner in the shack. A 135-foot long dipole hung horizontally between two trees or towers at a height of 50 feet or higher works very well on 80 through 10 meters. Such an antenna system has significant gain at the higher frequencies.

Flattop or Inverted-V Configuration?

There is no denying that the inverted-V mounting configuration (sometimes called a *drooping dipole*) is very convenient, since it requires only a single support. The flattop configuration, however, where the dipole is mounted horizontally, gives more gain at the higher frequencies. **Fig 5** shows the 80-meter azimuth and elevation patterns for two 135-foot long dipoles. The first is mounted as a flattop at a height of 50 feet over flat ground with a conductivity of 5 mS/m and a dielectric constant of 13, typical for average soil. The second dipole uses the same length of wire, with the center apex at 50 feet and the ends drooped down to be suspended 10 feet off the ground. This height is sufficient so that there is no danger to passersby from RF burns.

At 3.8 MHz, the flattop dipole about 4 dB more peak gain than its drooping cousin. On the other hand, the inverted-V configuration gives a pattern that is more omnidirectional than the flattop dipole, which has nulls off the

ends of the wire. Omnidirectional coverage may be more important to net operators, for example, than maximum gain.

Fig 6 shows the azimuth and elevation patterns for the same two antenna configurations, but this time at 14.2 MHz. The flattop dipole has developed four distinct lobes at a 10° elevation angle, an angle typical for 20-meter skywave communication. The peak elevation angle gain of 9.4 dBi occurs at about 17° for a height of 50 feet above flat ground for the flattop dipole. The inverted-V configuration is again nominally more omnidirectional, but the peak gain is down some 6 dB from the flattop.

The situation gets even worse in terms of peak gain at 28.4 MHz for the inverted-V configuration. Here the peak gain is down about 8 dB from that produced by the flattop dipole, which exhibits eight lobes at this frequency with a maximum gain of 10.5 dBi at about 7° elevation. See the comparisons in **Fig 7**.

Whatever configuration you choose to mount the 135-foot dipole, you will want to feed it with some sort of low-loss open-wire transmission line. So-called *window* 450-Ω ladder line is popular for this application. Be sure to twist the line about three or four turns per foot to keep it from twisting excessively in the wind. Make sure also that you provide some mechanical support for the line at the junction with the dipole

20° Elevation
0 dB=0.57 dBi
(A)
3.800 MHz

0 dB=6.62 dBi
Elevation
(B)
3.800 MHz

- - - - Inv. V Configuration
——— Flattop Configuration

Fig 5—Patterns on 80 meters for 135-foot, center-fed dipole erected as a horizontal flattop dipole at 50 feet, compared with the same dipole installed as an inverted V with the apex at 50 feet and the ends at 10 feet. The azimuth pattern is shown at A, where the dipole wire lies in the 90° to 270° plane. At B, the elevation pattern, the dipole wire comes out of the paper at a right angle. On 80 meters, the patterns are not markedly different for either flattop or inverted-V configuration.

10° Elevation
0 dB=6.95 dBi
(A)
14.100 MHz

Elevation
At Azimuths for Max. Gain
0 dB=9.40 dBi
(B)
14.100 MHz

- - - - Inv. V Configuration
——— Flattop Configuration

Fig 6—Patterns on 20 meters for two 135-foot dipoles. One is mounted horizontally as a flattop and the other as an inverted V with 120° included angle between the legs. The azimuth pattern is shown in A and the elevation pattern is shown in B. The inverted V has about 6 dB less gain at the peak azimuths, but has a more uniform, almost omnidirectional, azimuthal pattern. In the elevation plane, the inverted V has a fat lobe overhead, making it a somewhat better antenna for local communication, but not quite so good for DX contacts at low elevation angles.

5° Elevation
0 dB=8.01 dBi   28.400 MHz

(A)

Elevation
At Azimuths for Max. Gain
0 dB=10.50 dBi   28.400 MHz

(B)

- - - - Inv. V Configuration
——— Flattop Configuration

Fig 7—Patterns on 10 meters for same antenna configurations as in Figs 7 and 8. Once again, the inverted-V configuration yields a more omnidirectional pattern, but at the expense of almost 8 dB less gain than the flattop configuration at its strongest lobes.

wires. This will prevent flexing of the transmission-line wire, since excessive flexing will result in breakage.

THE G5RV MULTIBAND ANTENNA

A multiband antenna that does not require a lot of space, is simple to construct, and is low in cost is the G5RV. Designed in England by Louis Varney (G5RV) some years ago, it has become quite popular in the US. The G5RV design is shown in **Fig 8**. The antenna may be used from 3.5 through 30 MHz. Although some amateurs claim it may be fed directly with 50-Ω coax on several amateur bands with a low SWR, Varney himself recommended the use of an antenna tuner on bands other than 14 MHz (see Bibliography). In fact, an analysis of the G5RV feed-point impedance shows there

Fig 8—The G5RV multiband antenna covers 3.5 through 30 MHz. Although many amateurs claim it may be fed directly with 50-Ω coax on several amateur bands, Louis Varney, its originator, recommends the use of a matching network on bands other than 14 MHz.

Max. Gain = 1.72 dBi

Elevation = 5 deg.
Freq. = 14.175 MHz

——— G5RV @ 50'   - - - - 132' Center - Fed Dipole @ 50'   ········· Dipole @ 50'

Fig 9—Azimuth pattern at a 5° takeoff angle for a 102-foot long, 50-foot high G5RV dipole (solid line). For comparison, the response for a 132-foot long, center-fed dipole at 50 feet height (dashed line) and a 33-foot long half wave 20-meter dipole at 50 feet (dotted line) are also shown. The longest antenna exhibits about 0.5 dB more gain than the G5RV, although the response is more omnidirectional for the G5RV—an advantage for a wire antenna that is not usually rotatable.

is *no* length of balanced line of *any* characteristic impedance that will transform the terminal impedance to the 50 to 75-Ω range on all bands. (Low SWR indication with coax feed and no matching network on bands other than 14 MHz may indicate excessive losses in the coaxial line.)

Fig 9 shows the 20-meter azimuthal pattern for a G5RV at a height of 50 feet over flat ground, at an elevation angle of 5° that is suitable for DX work. For comparison, the response for two other antennas is also shown in Fig 9—a standard half wave 20-meter dipole at 50 feet and a 132-foot long center-fed

dipole at 50 feet. The G5RV on 20 meters is, of course, longer than a standard half wave dipole and it exhibits about 2 dB more gain compared to that dipole. With four lobes making it look rather like a four-leaf clover, the azimuth pattern is more omnidirectional than the two-lobed dipole. The 132-foot center-fed dipole is longer than the G5RV and it has about 0.5 dB more gain than the G5RV, also exhibiting four major lobes, along with two strong minor lobes in the plane of the wire. Overall, the azimuthal response for the G5RV is more omnidirectional than the comparison antennas.

The G5RV patterns for other frequencies are similar to those shown for the 135-foot dipole previously for other frequencies. Incidentally, you may be wondering why a 132-foot dipole is shown in Fig 9, rather than the 135-foot dipole described earlier. The 132-foot overall length describes another antenna that we'll discus in the next section on Windom antennas.

The portion of the G5RV antenna shown as horizontal in Fig 8 may also be installed in an inverted-V dipole arrangement, subject to the same loss of peak gain mentioned above for the 135-foot dipole. Or instead, up to $\frac{1}{6}$ of the total length of the antenna at each end may be dropped vertically, semi-vertically, or bent at a convenient angle to the main axis of the antenna, to cut down on the requirements for real estate.

THE WINDOM ANTENNA

An antenna that enjoyed popularity in the 1930s and into the 1940s was what we now call the *Windom*. It was known at the time as a "single-feeder Hertz" antenna, after being described in Sep 1929 *QST* by Loren G. Windom, W8GZ (see Bibliography).

The Windom antenna, shown in **Fig 10**, is fed with a single wire, attached approximately 14% off center. In theory, this location provides a match for the single-wire transmission line, which is worked against an earth ground. Because the single-wire feed line is not inherently well balanced and because it is brought to the operating position, "RF in the shack" and a potential radiation hazard may be experienced with this antenna.

Fig 10—The Windom antenna, cut for a fundamental frequency of 3.75 MHz. The single-wire feeder, connected 14% off center, is brought into the station and the system is fed against ground. The antenna is also effective on its harmonics.

Later variations of the off-center fed Windom moved the attachment point slightly to accommodate balanced 300-Ω ribbon line. One relatively recent variation is called the "Carolina Windom," apparently because two of the designers, Edgar Lambert, WA4LVB, and Joe Wright, W4UEB, lived in coastal North Carolina (the third, Jim Wilkie, WY4R, lived

Fig 11—Layout for flattop "Carolina Windom" antenna.

Max. Gain = 1.72 dBi

Elevation = 5 deg.
Freq. = 14.15 MHz

——— 132' Carolina Windom @ 50', Saltwater

- - - - 132' Center - Fed Dipole @ 50'

Fig 12—20-meter azimuth patterns for a 132-foot long off-center fed Carolina Windom and a 132-foot long center-fed flattop dipole on 20 meters, both at a height of 50 feet above saltwater. The response for the Carolina Windom is more omnidirectional because the vertically polarized radiation from the 22-foot long vertical RG-8X coax fills in the deep nulls.

in nearby Norfolk, Virginia). One of the interesting parts about the Carolina Windom is that it turns a potential disadvantage—feed line radiation—into a potential advantage.

Fig 11 is a diagram of a flattop Carolina Windom, which uses a 50-foot wire joined with an 83-foot wire at the feed-point insulator. This resembles the layout shown in Fig 10 for the original W8GZ Windom. The "Vertical Radiator" for the Carolina Windom is a 22-foot piece of RG-8X coax, with a "Line Isolator" (current-type choke balun) at the bottom end and a 4:1 "Matching Unit" at the top. The system takes advantage of the asymmetry of the horizontal wires to induce current onto the braid of the vertical coax section. Note that the matching unit is a voltage-type balun transformer, which purposely does not act like a common-mode current choking balun. You must use an antenna tuner with this system to present a 1:1 SWR to the transmitter on the amateur bands from 80 through 10 meters.

The radiation resulting from current induced onto the 22-foot vertical coax section tends to fill in the deep nulls that would be present if the 132-feet of horizontal wire were symmetrically center fed. Over saltwater, the vertical radiator can give significant gain at the low elevation angles needed for DX work. Indeed, field reports for the Carolina Windom are most impressive for stations located near or on saltwater. Over average soil the advantage of the additional vertically polarized component is not quite so evident. **Fig 12** compares a 50-foot high Carolina Windom on 14 MHz over saltwater to a 50-foot high, 132-foot long, flattop center-fed dipole. The

Carolina Windom has a more omnidirectional azimuthal pattern, a desirable characteristic in a 132-foot long wire antenna that is not normally rotated to favor different directions.

Another advantage of the Carolina Windom over a traditional Windom is that the coax feed line hanging below the common-mode current choke does not radiate, meaning that there will be less "RF in the shack." Since the feed line is not always operating at a low SWR on various ham bands, use the minimum length of feed coax possible to hold down losses in the coax.

Fig 13 shows the azimuth responses for a 50-foot long flattop Carolina Windom on 28.4 MHz over saltwater and over average soil. The pattern for a 50-foot high, flattop 20-meter dipole operated on 28.4 MHz is also shown, since this 20-meter dipole can also be used as a multiband antenna, when fed with open-wire transmission line rather than with coax. Again, the Carolina Windom exhibits a more omnidirectional pattern, even if the pattern is somewhat lopsided at the bottom.

MULTIPLE-DIPOLE ANTENNAS

The antenna system shown in **Fig 14** consists of a group of center-fed dipoles, all connected in parallel at the point where the transmission line joins them. The dipole elements are *stagger-tuned*. That is, they are individually cut to be $\lambda/2$ at different frequencies. Chapter 9, Broadband Antenna Matching, discusses stagger tuning of dipole antennas to attain a low SWR across a broad range of frequencies. An extension of the stagger tuning idea is to construct multiwire dipoles cut for different bands.

In theory, the 4-wire antenna of Fig 14 can be used with a coaxial feeder on five bands. The four wires are prepared as parallel-fed dipoles for 3.5, 7, 14, and 28 MHz. The 7-MHz dipole can be operated on its 3rd harmonic for 21-MHz operation to cover a fifth band. However, in practice it has been found difficult to get a good match to coaxial line

Max. Gain = 6.35 dBi

Elevation = 5 deg.
Freq. = 28.4 MHz

——— 132' Carolina Windom @ 50' Saltwater

– – – 132' Carolina Windom @ 50' Above Ground

········· 20 m Dipole @ 50' on 10 m

Fig 13—10-meter azimuthal responses for a 132-foot long, 50-foot high Carolina Windom over saltwater (solid line) and over average ground (dashed line), compared to that for a 20-meter half-wave dipole at 50 feet (dotted line).

Fig 14—Multiband antenna using paralleled dipoles all connected to a common low-impedance transmission line. The half-wave dimensions may be either for the centers of the various bands or selected to fit favorite frequencies in each band. The length of a half wave in feet is 468/ frequency in MHz, but because of interaction among the various elements, some pruning for resonance may be needed on each band.

on all bands. The λ/2 resonant length of any one dipole in the presence of the others is not the same as for a dipole by itself due to interaction, and attempts to optimize all four lengths can become a frustrating procedure. The problem is compounded because the optimum tuning changes in a different antenna environment, so what works for one amateur may not work for another. Even so, many amateurs with limited antenna space are willing to accept the mismatch on some bands just so they can operate on those frequencies using a single coax feed line.

Since this antenna system is balanced, it is desirable to use a balanced transmission line to feed it. The most desirable type of line is 75-Ω transmitting twin-lead. However, either 52-Ω or 75-Ω coaxial line can be used. Coax line introduces some unbalance, but this is tolerable on the lower frequencies. An alternative is to use a balun at the feed point, fed with coaxial cable.

The separation between the dipoles for the various frequencies does not seem to be especially critical. One set of wires can be suspended from the next larger set, using insulating spreaders (of the type used for feeder spreaders) to give a separation of a few inches. Users of this antenna often run some of the dipoles at right angles to each other to help reduce interaction. Some operators use inverted-V-mounted dipoles as guy wires for the mast that supports the antenna system.

An interesting method of construction used successfully by Louis Richard, ON4UF, is shown in **Fig 15**. The antenna has four dipoles (for 7, 14, 21 and 28 MHz) constructed from 300-Ω ribbon transmission line. A single length of ribbon makes two dipoles. Thus, two lengths, as shown in the sketch, serve to make dipoles for four bands. Ribbon with copper-clad steel conductors (Amphenol type 14-022) should be used because all of the weight, including that of the feed line, must be supported by the uppermost wire.

Two pieces of ribbon are first cut to a length suitable for the two halves of the longest dipole. Then one of the conductors in each piece is cut to proper length for the next band higher in frequency. The excess wire and insulation is stripped away. A second pair of lengths is prepared in the same manner, except that the lengths are appropriate for the next two higher frequency bands.

A piece of thick polystyrene sheet drilled with holes for anchoring each wire serves as the central insulator. The shorter pair of dipoles is suspended the width of the ribbon below the longer pair by clamps also made of poly sheet. Intermediate spacers are made by sawing slots in pieces of poly sheet so they will fit the ribbon snugly.

The multiple-dipole principle can also be applied to vertical antennas. Parallel or fanned λ/4 elements of wire or tubing can be worked against ground or tuned radials from a common feed point.

OFF-CENTER-FED DIPOLES

Fig 16 shows an off-center-fed or *OCF* dipole. Because it is similar in appearance to the Windom of Fig 12, this antenna is often mistakenly called a "Windom," or sometimes a "coax-fed Windom." The two antennas are not the same, since the Windom is worked against its image in the ground, while one leg is worked against the other in the OCF dipole.

It is not necessary to feed a dipole antenna at its center, although doing so will allow it to be operated with a relatively low feed-point impedance on its fundamental and *odd* harmonics. (For example, a 7-MHz center-fed half-wave dipole can also be used for 21-MHz operation.) By contrast, the OCF dipole of Fig 16, fed ⅓ of its length from one end, may be used on its fundamental and *even* harmonics. Its free-space antenna-terminal impedance at 3.5, 7 and 14 MHz is on the order of 150 to 200 Ω. A 1:4 step-up transformer at the feed point should offer a reasonably good match to 50- or 75-Ω line, although some commercially made OCF dipoles use a 1:6 transformer.

At the 6th harmonic, 21 MHz, the antenna is three wavelengths long and fed at a voltage loop (maximum), instead of a current loop. The feed-point impedance at this frequency

Fig 15—Sketch showing how the twin-lead multiple-dipole antenna system is assembled. The excess wire and insulation are stripped away.

Fig 16—The off-center-fed (OCF) dipole for 3.5, 7 and 14 MHz. A 1:4 or 1:6 step-up current balun is used at the feed point.

is high, a few thousand ohms, so the antenna is unsuitable for use on this band.

Balun Requirements

Because the OCF dipole is not fed at the center of the radiator, the RF impedance paths of the two wires at the feed point are unequal. If the antenna is fed directly with coax (or a balanced line), or if a voltage step-up transformer is used, then voltages of equal magnitude (but opposite polarity) are applied to the wires at the feed point. Because of unequal impedances, the resulting antenna currents flowing in the two wires will not be equal. This also means that antenna current can flow on the feeder—on the *outside* of a coaxial line. (You may recall that this is how the Carolina Windom works, actually inducing current onto a carefully chosen length of coax, choked at its bottom end, so that it acts as a vertical radiator.)

How much current flows on the coax shield depends on the impedance of the RF current path down the outside of the feed line. In general, this is not a desirable situation. To prevent radiation, equal *currents* are required at the feed point, with the same current flowing in and out of the short leg as in and out of the long leg of the radiator. A *current* or *choke* type of balun provides just such operation. (Current baluns are discussed in detail in Chapter 26, Coupling the Line to the Antenna.)

Trap Antennas

By using tuned circuits of appropriate design strategically placed in a dipole, the antenna can be made to show what is essentially fundamental resonance at a number of different frequencies. The general principle is illustrated by **Fig 17**.

Even though a trap-antenna arrangement is a simple one, an explanation of how a trap antenna works can be elusive. For some designs, traps are resonated in our amateur bands, and for others (especially commercially made antennas) the traps are resonant far outside any amateur band.

A trap in an antenna system can perform either of two functions, depending on whether or not it is resonant at the operating frequency. A familiar case is where the trap is parallel-resonant in an amateur band. For the moment, let us assume that dimension A in Fig 17 is 32 feet and that each L/C combination is resonant in the 7-MHz band. Because of its parallel resonance, the trap presents a high impedance at that point in the antenna system. The electrical effect at 7 MHz is that the trap behaves as an insulator. It serves to divorce the outside ends, the B sections, from the antenna. The result is easy to visualize—we have an antenna system that is resonant

in the 7-MHz band. Each 33-foot section (labeled A in the drawing) represents λ/4, and the trap behaves as an insulator. We therefore have a full-size 7-MHz antenna.

The second function of a trap, obtained when the frequency of operation is *not* the resonant frequency of the trap, is one of electrical loading. If the operating frequency is below that of trap resonance, the trap behaves as an inductor; if above, as a capacitor. Inductive loading will electrically lengthen the antenna, and capacitive loading will electrically shorten the antenna.

Let's carry our assumption a bit further and try using the antenna we just considered at 3.5 MHz. With the traps resonant in the 7-MHz band, they will behave as inductors when operation takes place at 3.5 MHz, electrically lengthening the antenna. This means that the total length of sections A and B (plus the length of the inductor) may be something less than a physical λ/4 for resonance at 3.5 MHz. Thus, we have a two-band antenna that is shorter than full size on the lower frequency band. But with the electrical loading provided by the traps, the overall electrical length is λ/2. The total antenna length needed for resonance in the 3.5-MHz band will depend on the L/C ratio of the trap elements.

The key to trap operation off resonance is its L/C ratio, the ratio of the value of L to the value of C. At resonance, however, within practical limitations the L/C ratio is immaterial as far as electrical operation goes. For example, in the antenna we've been discussing, it would make no difference for 7-MHz operation whether the inductor were 1 μH and the capacitor were 500 pF (the reactances would be just below 45 Ω at 7.1 MHz), or whether the inductor were 5 μH and the capacitor 100 pF (reactances of approximately 224 Ω at 7.1 MHz). But the choice of these values will make a significant difference in the antenna size for resonance at 3.5 MHz. In the first case, where the L/C ratio is 2000, the necessary length of section B of the antenna for resonance at 3.75 MHz would be approximately 28.25 feet. In the second case, where the L/C ratio is 50,000, this length need be only 24.0 feet, a difference of more than 15%.

The above example concerns a two-band antenna with

Fig 17—A trap dipole antenna. This antenna may be fed with 50-Ω coaxial line. Depending on the L/C ratio of the trap elements and the lengths chosen for dimensions A and B, the traps may be resonant either in an amateur band or at a frequency far removed from an amateur band for proper two-band antenna operation.

trap resonance at one of the two frequencies of operation. On each of the two bands, each half of the dipole operates as an electrical λ/4. However, the same band coverage can be obtained with a trap resonant at, say, 5 MHz, a frequency quite removed from either amateur band. With proper selection of the L/C ratio and the dimensions for A and B, the trap will act to shorten the antenna electrically at 7 MHz and lengthen it electrically at 3.5 MHz. Thus, an antenna that is intermediate in physical length between being full size on 3.5 MHz and full size on 7 MHz can cover both bands, even though the trap is not resonant at either frequency. Again, the antenna operates with electrical λ/4 sections. Note that such non-resonant traps have less RF current flowing in the trap components, and hence trap losses are less than for resonant traps.

Additional traps may be added in an antenna section to cover three or more bands. Or a judicious choice of dimensions and the L/C ratio may permit operation on three or more bands with just a pair of identical traps in the dipole.

An important point to remember about traps is this. If the operating frequency is below that of trap resonance, the trap behaves as an inductor; if above, as a capacitor. The above discussion is based on dipoles that operate electrically as λ/2 antennas. This is not a requirement, however. Elements may be operated as electrical 3/2 λ, or even 5/2 λ, and still present a reasonable impedance to a coaxial feeder. In trap antennas covering several HF bands, using electrical lengths that are odd multiples of λ/2 is often done at the higher frequencies.

To further aid in understanding trap operation, let's now choose trap L and C components that each have a reactance of 20 Ω at 7 MHz. Inductive reactance is directly proportional to frequency, and capacitive reactance is inversely proportional. When we shift operation to the 3.5-MHz band, the inductive reactance becomes 10 Ω, and the capacitive reactance becomes 40 Ω. At first thought, it may seem that the trap would become capacitive at 3.5 MHz with a higher capacitive reactance, and that the extra capacitive reactance would make the antenna electrically shorter yet. Fortunately, this is not the case. The inductor and the capacitor are connected in parallel with each other.

$$Z = \frac{-jX_L X_C}{X_L + X_C} \qquad \text{(Eq 1)}$$

where j indicates a reactive impedance component, rather than resistive. A positive result indicates inductive reactance, and a negative result indicates capacitive. In this 3.5-MHz case, with 40 Ω of capacitive reactance and 10 Ω of inductive, the equivalent series reactance is 13.3 Ω inductive. This inductive loading lengthens the antenna to an electrical λ/2 overall at 3.5 MHz, assuming the B end sections in Fig 17 are of the proper length.

With the above reactance values providing resonance at 7-MHz, X_L equals X_C, and the theoretical series equivalent is infinity. This provides the insulator effect, divorcing the ends.

At 14 MHz, where $X_L = 40$ Ω and $X_C = 10$ Ω, the re-

sultant series equivalent trap reactance is 13.3 Ω capacitive. If the total physical antenna length is slightly longer than 3/2 λ at 14 MHz, this trap reactance at 14 MHz can be used to shorten the antenna to an electrical 3/2 λ. In this way, 3-band operation is obtained for 3.5, 7 and 14 MHz with just one pair of identical traps. The design of such a system is not straightforward, however, for any chosen L/C ratio for a given total length affects the resonant frequency of the antenna on both the 3.5 and 14-MHz bands.

Trap Losses

Since the tuned circuits have some inherent losses, the efficiency of a trap system depends on the unloaded Q values of the tuned circuits. Low-loss (high-Q) coils should be used, and the capacitor losses likewise should be kept as low as possible. With tuned circuits that are good in this respect—comparable with the low-loss components used in transmitter tank circuits, for example—the reduction in efficiency compared with the efficiency of a simple dipole is small, but tuned circuits of low unloaded Q can lose an appreciable portion of the power supplied to the antenna.

The commentary above applies to traps assembled from conventional components. The important function of a trap that is resonant in an amateur band is to provide a high isolating impedance, and this impedance is directly proportional to Q. Unfortunately, high Q restricts the antenna bandwidth, because the traps provide maximum isolation only at trap resonance.

FIVE-BAND W3DZZ TRAP ANTENNA

C. L. Buchanan, W3DZZ, created one of the first trap antennas for the five pre-1979 WARC amateur bands from 3.5 to 30 MHz. Dimensions are given in **Fig 18**. Only one set of traps is used, resonant at 7 MHz to isolate the inner (7-MHz) dipole from the outer sections. This causes the overall system to be resonant in the 3.5-MHz band. On 14, 21 and 28 MHz the antenna works on the capacitive-reactance principle just outlined. With a 75-Ω twin-lead feeder, the SWR with this antenna is under 2:1 throughout the three highest frequency

Fig 18—Five-band (3.5, 7, 14, 21 and 28 MHz) trap dipole for operation with 75-Ω feeder at low SWR (C. L. Buchanan, W3DZZ). The balanced (parallel-conductor) line indicated is desirable, but 75-Ω coax can be substituted with some sacrifice of symmetry in the system. Dimensions given are for resonance (lowest SWR) at 3.75, 7.2, 14.15 and 29.5 MHz. Resonance is very broad on the 21-MHz band, with SWR less than 2:1 throughout the band.

bands, and the SWR is comparable with that obtained with similarly fed simple dipoles on 3.5 and 7 MHz.

Trap Construction

Traps frequently are built with coaxial aluminum tubes (usually with polystyrene tubing in-between them for insulation) for the capacitor, with the coil either self-supporting or wound on a form of larger diameter than the tubular capacitor. The coil is then mounted coaxially with the capacitor to form a unit assembly that can be supported at each end by the antenna wires. In another type of trap devised by William J. Lattin, W4JRW (see Bibliography at the end of this chapter), the coil is supported inside an aluminum tube and the trap capacitor is obtained in the form of capacitance between the coil and the outer tube. This type of trap is inherently weatherproof.

A simpler type of trap, easily assembled from readily

Fig 19—Easily constructed trap for wire antennas (A. Greenburg, W2LH). The ceramic insulator is 4¼ inches long (Birnback 688). The clamps are small service connectors available from electrical supply and hardware stores (Burndy KS90 servits).

Fig 20—Layout of multiband antenna using traps constructed as shown in Fig 21. The capacitors are 100 pF each, transmitting type, 5000-volt dc rating (Centralab 850SL-100N). Coils are 9 turns of #12 wire, 2½ inches diameter, 6 turns per inch (B&W 3029) with end turns spread as necessary to resonate the traps to 7.2 MHz. These traps, with the wire dimensions shown, resonate the antenna at approximately the following frequencies on each band: 3.9, 7.25, 14.1, 21.5 and 29.9 MHz (based on measurements by W9YJH).

available components, is shown in **Fig 19**. A small transmitting-type ceramic "doorknob" capacitor is used, together with a length of commercially available coil material, these being supported by an ordinary antenna strain insulator. The circuit constants and antenna dimensions differ slightly from those of Fig 18, in order to bring the antenna resonance points closer to the centers of the various phone bands. Construction data are given in **Fig 20**. If a 10-turn length of inductor is used, a half turn from each end may be used to slip through the anchor holes in the insulator to act as leads.

The components used in these traps are sufficiently weatherproof in themselves so that no additional weatherproofing has been found necessary. However, if it is desired to protect them from the accumulation of snow or ice, a plastic cover can be made by cutting two discs of polystyrene slightly larger in diameter than the coil, drilling at the center to pass the antenna wires, and cementing a plastic cylinder on the edges of the discs. The cylinder can be made by wrapping two turns or so of 0.02-inch poly or Lucite sheet around the discs, if no suitable ready-made tubing is available. Plastic drinking glasses and 2-liter soft-drink plastic bottles are easily adaptable for use as impromptu trap covers.

TWO W8NX MULTIBAND, COAX-TRAP DIPOLES

Over the last 60 or 70 years, amateurs have used many kinds of multiband antennas to cover the traditional HF bands. The availability of the 30, 17 and 12-meter bands has expanded our need for multiband antenna coverage.

Two different antennas are described here. The first covers the traditional 80, 40, 20, 15 and 10-meter bands, and the second covers 80, 40, 17 and 12 meters. Each uses the same type of W8NX trap—connected for different modes of operation—and a pair of short capacitive stubs to enhance coverage. The W8NX coaxial-cable traps have two different modes: a high- and a low-impedance mode. The inner-conductor windings and shield windings of the traps are connected in series for both modes. However, either the low- or high-impedance point can be used as the trap's output terminal. For low-impedance trap operation, only the center conductor turns of the trap windings are used. For high-impedance operation, all turns are used, in the conventional manner for a trap. The short stubs on each antenna are strategically sized and located to permit more flexibility in adjusting the resonant frequencies of the antenna.

80, 40, 20, 15 and 10-Meter Dipole

Fig 21 shows the configuration of the 80, 40, 20, 15 and 10-meter antenna. The radiating elements are made of #14

Fig 21—A W8NX multiband dipole for 80, 40, 20, 15 and 10 meters. The values shown (123 pF and 4 μH) for the coaxial-cable traps are for parallel resonance at 7.15 MHz. The low-impedance output of each trap is used for this antenna.

stranded copper wire. The element lengths are the wire span lengths in feet. These lengths do not include the lengths of the pigtails at the balun, traps and insulators. The 32.3-foot-long inner 40-meter segments are measured from the eyelet of the input balun to the tension-relief hole in the trap coil form. The 4.9-foot segment length is measured from the tension-relief hole in the trap to the 6-foot stub. The 16.1-foot outer-segment span is measured from the stub to the eyelet of the end insulator.

The coaxial-cable traps are wound on PVC pipe coil forms and use the low-impedance output connection. The stubs are 6-foot lengths of ⅛-inch stiffened aluminum or copper rod hanging perpendicular to the radiating elements. The first inch of their length is bent 90° to permit attachment to the radiating elements by large-diameter copper crimp connectors. Ordinary #14 wire may be used for the stubs, but it has a tendency to curl up and may tangle unless weighed down at the end. You should feed the antenna with 75-Ω coax cable using a good 1:1 balun.

This antenna may be thought of as a modified W3DZZ antenna due to the addition of the capacitive stubs. The length and location of the stub give the antenna designer two extra degrees of freedom to place the resonant frequencies within the amateur bands. This additional flexibility is particularly helpful to bring the 15 and 10-meter resonant frequencies to more desirable locations in these bands. The actual 10-meter resonant frequency of the original W3DZZ antenna is somewhat above 30 MHz, pretty remote from the more desirable low frequency end of 10 meters.

80, 40, 17 and 12-Meter Dipole

Fig 22 shows the configuration of the 80, 40, 17 and 12-meter antenna. Notice that the capacitive stubs are attached immediately outboard after the traps and are 6.5 feet long, ½ foot longer than those used in the other antenna. The traps are the same as those of the other antenna, but are connected for the high-impedance parallel-resonant output mode. Since only four bands are covered by this antenna, it is easier to fine tune it to precisely the desired frequency on all bands. The 12.4-foot tips can he pruned to a particular 17-meter frequency with little effect on the 12-meter frequency. The stub lengths can be pruned to a particular 12-meter frequency with little effect on the 17-meter frequency. Both such pruning adjustments slightly alter the 80-meter resonant frequency. However, the bandwidths of the antennas are so broad on 17 and 12 meters that little need for such pruning exists. The 40-meter frequency is nearly independent of adjustments to

the capacitive stubs and outer radiating tip elements. Like the first antennas, this dipole is fed with a 75-Ω balun and feed line.

Fig 23 shows the schematic diagram of the traps. It explains the difference between the low and high-impedance modes of the traps. Notice that the high-impedance terminal is the output configuration used in most conventional trap applications. The low-impedance connection is made across only the inner conductor turns, corresponding to one-half of the total turns of the trap. This mode steps the trap's impedance down to approximately one-fourth of that of the high-impedance level. This is what allows a single trap design to be used for two different multiband antennas.

Fig 24 is a drawing of a cross-section of the coax trap shown through the long axis of the trap. Notice that the traps are conventional coaxial-cable traps, except for the added low-impedance output terminal. The traps are 8¾ close-spaced turns of RG-59 (Belden 8241) on a 2⅜-inch-OD PVC pipe (schedule 40 pipe with a 2-inch ID) coil form. The forms are 4⅛ inches long. Trap resonant frequency is very sensitive to the outer diameter of the coil form, so check it carefully. Unfortunately, not all PVC pipe is made with the same wall thickness. The trap frequencies should be checked with a dip meter and general-coverage receiver and adjusted to within 50 kHz of the 7150 kHz resonant frequency before installation. One inch is left over at each end of the coil forms to allow for the coax feed-through holes and holes for tension-relief attachment of the antenna radiating elements to the traps. Be sure to seal the ends of the trap coax cable with RTV sealant to prevent moisture from entering the coaxial cable.

Also, be sure that you connect the 32.3-foot wire element at the start of the inner conductor winding of the trap. This avoids detuning the antenna by the stray capacitance of the coaxial-cable shield. The trap output terminal (which has the shield stray capacitance) should be at the outboard side of

Fig 23—Schematic for the W8NX coaxial-cable trap. RG-59 is wound on a 2⅜-inch OD PVC pipe.

Fig 22—A W8NX multiband dipole for 80, 40, 17 and 12 meters. For this antenna, the high-impedance output is used on each trap. The resonant frequency of the traps is 7.15 MHz.

Fig 24—Construction details of the W8NX coaxial-cable trap.

the trap. Reversing the input and output terminals of the trap will lower the 40-meter frequency by approximately 50 kHz, but there will be negligible effect on the other bands.

Fig 25 shows a coaxial-cable trap. Further details of the trap installation are shown in **Fig 26**. This drawing applies specifically to the 80, 40, 20, 15 and l0-meter antenna, which uses the low-impedance trap connections. Notice the lengths of the trap pigtails: 3 to 4 inches at each terminal of the trap. If you use a different arrangement, you must modify the span lengths accordingly. All connections can be made using crimp connectors rather than by soldering. Access to the trap's interior is attained more easily with a crimping tool than with a soldering iron.

Performance

The performance of both antennas has been very satisfactory. W8NX uses the 80, 40, 17 and 12-meter version because it covers 17 and 12 meters. (He has a tribander for 20, 15 and 10 meters.) The radiation pattern on 17 meters is that of a ³⁄₂-wave dipole. On 12 meters, the pattern is that of a ⁵⁄₂-wave dipole. At his location in Akron, Ohio, the antenna runs essentially east and west. It is installed as an inverted V, 40 feet high at the center, with a $120°$ included angle between the legs. Since the stubs are very short, they

radiate little power and make only minor contributions to the radiation patterns. In theory, the pattern has four major lobes on 17 meters, with maxima to the northeast, southeast, southwest and northwest. These provide low-angle radiation into Europe, Africa, South Pacific, Japan and Alaska. A narrow pair of minor broadside lobes provides north and south coverage into Central America, South America and the polar regions.

There are four major lobes on 12 meters, giving nearly end-fire radiation and good low-angle east and west coverage. There are also three pairs of very narrow, nearly broadside, minor lobes on 12 meters, down about 6 dB from the major end-fire lobes. On 80 and 40 meters, the antenna has the usual figure-8 patterns of a half-wave-length dipole.

Both antennas function as electrical half-wave dipoles on 80 and 40 meters with a low SWR. They both function as odd-harmonic current-fed dipoles on their other operating frequencies, with higher, but still acceptable, SWR. The presence of the stubs can either raise or lower the input impedance of the antenna from those of the usual third and fifth harmonic dipoles. Again W8NX recommends that 75-Ω,

Fig 25—Other views of a W8NX coax-cable trap.

Fig 26—Additional construction details for the W8NX coaxial-cable trap.

rather than 50-Ω, feed line be used because of the generally higher input impedances at the harmonic operating frequencies of the antennas.

The SWR curves of both antennas were carefully measured using a 75 to 50-Ω transformer from Palomar Engineers inserted at the junction of the 75-Ω coax feed line and a 50-Ω SWR bridge. The transformer is required for accurate SWR measurement if a 50-Ω SWR bridge is used with a 75-Ω line. Most 50-Ω rigs operate satisfactorily with a 75-Ω line, although this requires different tuning and load settings in the final output stage of the rig or antenna tuner. The author uses the 75 to 50-Ω transformer only when making SWR measure-

Fig 27—Measured SWR curves for an 80, 40, 20, 15 and 10-meter antenna, installed as an inverted-V with 40-ft apex and 120° included angle between legs.

Fig 28—Measured SWR curves for an 80, 40, 17 and 12-meter antenna, installed as an inverted-V with 40-ft apex and 120° included angle between legs.

ments and at low power levels. The transformer is rated for 100 W, and when he runs his 1-kW PEP linear amplifier the transformer is taken out of the line.

Fig 27 gives the SWR curves of the 80, 40, 20, 15 and 10-meter antenna. Minimum SWR is nearly 1:1 on 80 meters, 1.5:1 on 40 meters, 1.6:1 on 20 meters, and 1.5:1 on 10 meters. The minimum SWR is slightly below 3:1 on 15 meters. On 15 meters, the stub capacitive reactance combines with the inductive reactance of the outer segment of the antenna to produce a resonant rise that raises the antenna input resistance to about 220 Ω, higher than that of the usual 3/2-wavelength dipole. An antenna tuner may be required on this band to keep a solid-state final output stage happy under these load conditions.

Fig 28 shows the SWR curves of the 80, 40, 17 and 12-meter antenna. Notice the excellent 80-meter performance with a nearly unity minimum SWR in the middle of the band. The performance approaches that of a full-size 80-meter wire dipole. The short stubs and the low-inductance traps shorten the antenna somewhat on 80 meters. Also observe the good 17-meter performance, with the SWR being only a little above 2:1 across the band.

But notice the 12-meter SWR curve of this antenna, which shows 4:1 SWR across the band. The antenna input resistance approaches 300 Ω on this band because the capacitive reactance of the stubs combines with the inductive reactance of the outer antenna segments to give resonant rises in impedance. These are reflected back to the input terminals. These stub-induced resonant impedance rises are similar to those on the other antenna on 15 meters, but are even more pronounced.

Too much concern must not be given to SWR on the feed line. Even if the SWR is as high as 9:1 *no destructively high voltages will exist on the transmission line.* Recall that transmission-line voltages increase as the square root of the SWR in the line. Thus, 1 kW of RF power in 75-Ω line corresponds to 274 V line voltage for a 1:1 SWR. Raising the SWR to 9:1 merely triples the maximum voltage that the line must withstand to 822 V. This voltage is well below the 3700-V rating of RG-11, or the 1700-V rating of RG-59, the two most popular 75-Ω coax lines. Voltage breakdown in the traps is also very unlikely. As will be pointed out later, the operating power levels of these antennas are limited by RF power dissipation in the traps, not trap voltage breakdown or feed-line SWR.

Trap Losses and Power Rating

Table 1 presents the results of trap Q measurements and extrapolation by a two-frequency method to higher frequencies above resonance. W8NX employed an old, but recently calibrated, Boonton Q meter for the measurements. Extrapolation to higher-frequency bands assumes that trap resistance losses rise with skin effect according to the square root of frequency, and that trap dielectric loses rise directly with frequency. Systematic measurement errors are not increased by frequency extrapolation. However, random measurement

Table 1

Trap Q

Frequency (MHz)	3.8	7.15	14.18	18.1	21.3	24.9	28.6
High Z out (Ω)	101	124	139	165	73	179	186
Low Z out (Ω)	83	103	125	137	44	149	155

Table 2

Trap Loss Analysis: 80, 40, 20, 15, 10-Meter Antenna

Frequency (MHz)	3.8	7.15	14.18	21.3	28.6
Radiation Efficiency (%)	96.4	70.8	99.4	99.9	100.0
Trap Losses (dB)	0.16	1.5	0.02	0.01	0.003

Table 3

Trap Loss Analysis: 80, 40, 17, 12-Meter Antenna

Frequency (MHz)	3.8	7.15	18.1	24.9
Radiation Efficiency (%)	89.5	90.5	99.3	99.8
Trap Losses (dB)	0.5	0.4	0.03	0.006

errors increase in magnitude with upward frequency extrapolation. Results are believed to be accurate within 4% on 80 and 40 meters, but only within l0 to 15% at 10 meters. Trap Q is shown at both the high- and low-impedance trap terminals. The Q at the low-impedance output terminals is 15 to 20% lower than the Q at the high-impedance output terminals.

W8NX computer-analyzed trap losses for both antennas in free space. Antenna-input resistances at resonance were first calculated, assuming lossless, infinite-Q traps. They were again calculated using the Q values in Table 1. The radiation efficiencies were also converted into equivalent trap losses in decibels. **Table 2** summarizes the trap-loss analysis for the 80, 40, 20, 15 and 10-meter antenna and **Table 3** for the 80, 40,17 and 12-meter antenna.

The loss analysis shows radiation efficiencies of 90% or more for both antennas on all bands except for the 80, 40, 20, 15 and 10-meter antenna when used on 40 meters. Here, the radiation efficiency falls to 70.8%. A 1-kW power level at 90% radiation efficiency corresponds to 50-W dissipation per trap. In W8NX's experience, this is the trap's survival limit for extended key-down operation. SSB power levels of 1 kW PEP would dissipate 25 W or less in each trap. This is well within the dissipation capability of the traps.

When the 80, 40, 20, 15 and 10-meter antenna is operated on 40 meters, the radiation efficiency of 70.8% corresponds to a dissipation of 146 W in each trap when 1 kW is delivered to the antenna. This is sure to burn out the traps—even if sustained for only a short time. Thus, the power should be limited to leas than 300 W when this antenna is operated on 40 meters under prolonged key-down conditions. A 50% CW duty cycle would correspond to a 600-W power limit for normal 40-meter CW operation. Likewise, a 50% duty cycle for 40-meter SSB corresponds to a 600-W PEP power limit for the antenna.

The author knows of no analysis where the burnout wattage rating of traps has been rigorously determined. Operating experience seems to be the best way to determine trap burnout ratings. In his own experience with these antennas, he's had no traps burn out, even though he operated the 80, 40, 20, 15 and 10-meter antenna on the critical 40-meter band using his AL-80A linear amplifier at the 600-W PEP output level. He did not make a continuous, key-down, CW operating test at full power purposely trying to destroy the traps!

Some hams may suggest using a different type of coaxial cable for the traps. The dc resistance of 40.7 Ω per 1000 feet of RG-59 coax seems rather high. However, W8NX has found no coax other than RG-59 that has the necessary inductance-to-capacitance ratio to create the trap characteristic reactance required for the 80, 40, 20, 15 and 10-meter antenna. Conventional traps with wide-spaced, open-air inductors and appropriate fixed-value capacitors could be substituted for the coax traps, but the convenience, weatherproof configuration and ease of fabrication of coaxial-cable traps is hard to beat.

Multiband Vertical Antennas

There are two basic types of vertical antennas; either type can be used in multiband configurations. The first is the ground-mounted vertical and the second, the ground plane. These antennas are described in detail in Chapter 6, Low-Frequency Antennas.

The efficiency of any ground-mounted vertical depends a great deal on near-field earth losses. As pointed out in Chapter 3, The Effects of Ground, these near-field losses can be reduced or eliminated with an adequate radial system. Considerable experimentation has been conducted on this subject by Jerry Sevick, W2FMI, and several important results were obtained. It was determined that a radial system consisting of 40 to 50 radials, 0.2 λ long, would reduce the earth losses to about 2 Ω when a λ/4 radiator was being used. These radials should be on the earth's surface, or if buried, placed not more than an inch or so below ground. Otherwise, the RF current would have to travel through the lossy earth before reaching the radials. In a multiband vertical system, the radials should be 0.2 λ long for the lowest band, that is, 55 feet long for 3.5-MHz operation. Any wire size may be used for the radials. The radials should fan out in a circle, radiating from the base of the antenna. A metal plate, such as a piece of sheet copper, can be used at the center connection.

The other common type of vertical is the ground-plane antenna. Normally, this antenna is mounted above ground with the radials fanning out from the base of the antenna. The vertical portion of the antenna is usually an electrical λ/4, as is each of the radials. In this type of antenna, the system of radials acts somewhat like an RF choke, to prevent RF currents from flowing in the supporting structure, so the number of radials is not as important a factor as it is with a ground-mounted vertical system. From a practical standpoint, the customary number of radials is four or five. In a multiband configuration, λ/4 radials are required for each band of operation with the ground-plane antenna.

This is not so with the ground-mounted vertical antenna, where the ground plane is relied upon to provide an image of the radiating section. Note that even quarter-wave-long radials are greatly detuned by their proximity to ground—radial resonance is not necessary or even possible. In the ground-mounted case, so long as the ground-screen radials are approximately 0.2 λ long at the lowest frequency, the length will be more than adequate for the higher frequency bands.

Short Vertical Antennas

A short vertical antenna can be operated on several bands by loading it at the base, the general arrangement being similar to Figs 1 and 2. That is, for multiband work the vertical can be handled by the same methods that are used for random-length wires.

A vertical antenna should not be longer than about ¾ λ at the highest frequency to be used, however, if low-angle radiation is wanted. If the antenna is to be used on 28 MHz and lower frequencies, therefore, it should not be more than approximately 25 feet high, and the shortest possible ground lead should be used.

Another method of feeding is shown in **Fig 29**. L1 is a loading coil, tapped to resonate the antenna on the desired band. A second tap permits using the coil as a transformer for matching a coax line to the transmitter. C1 is not strictly necessary, but may be helpful on the lower frequencies, 3.5 and 7 MHz, if the antenna is quite short. In that case C1 makes it possible to tune the system to resonance with a coil of reasonable dimensions at L1. C1 may also be useful on other bands as well, if the system cannot be matched to the feed line with a coil alone.

The coil and capacitor should preferably be installed at the base of the antenna, but if this cannot be done a wire can be run from the antenna base to the nearest convenient location for mounting L1 and C1. The extra wire will of course be a part of the antenna, and since it may have to run through unfavorable surroundings it is best to avoid using it if at all possible.

This system is best adjusted with the help of an SWR indicator. Connect the coax line across a few turns of L1 and take trial positions of the shorting tap until the SWR reaches its lowest value. Then vary the line tap similarly; this should bring the SWR down to a low value. Small adjustments of both taps then should reduce the SWR to close to 1:1. If not, try adding C1 and go through the same procedure, varying C1 each time a tap position is changed.

Fig 29—Multiband vertical antenna system using base loading for resonating on 3.5 to 28 MHz. L1 should be wound with bare wire so it can be tapped at every turn, using #12 wire. A convenient size is 2½ inches diameter, 6 turns per inch (such as B&W 3029). Number of turns required depends on antenna and ground lead length, more turns being required as the antenna and ground lead are made shorter. For a 25-foot antenna and a ground lead of the order of 5 feet, L1 should have about 30 turns. The use of C1 is explained in the text. The smallest capacitance that will permit matching the coax cable should be used; a maximum capacitance of 100 to 150 pF will be sufficient in any case.

Trap Verticals

The trap principle described in Fig 17 for center-fed dipoles also can be used for vertical antennas. There are two principal differences. Only one half of the dipole is used, the ground connection taking the place of the missing half, and the feed-point impedance is one half the feed-point impedance of a dipole. Thus it is in the vicinity of 30 Ω (plus the ground-connection resistance), so 52-Ω cable should be used since it is the commonly available type that comes closest to matching.

A TRAP VERTICAL FOR 21 AND 28 MHZ

Simple antennas covering the upper HF bands can be quite compact and inexpensive. The two-band vertical ground plane described here is highly effective for long-distance communication when installed in the clear.

Figs 30, **31** and **32** show the important assembly details. The vertical section of the antenna is mounted on a ¾-inch thick piece of plywood board that measures 7 × 10 inches. Several coats of exterior varnish or similar material will help protect the wood from inclement weather. Both the mast and the radiator are mounted on the piece of wood by means of TV U-bolt hardware. The vertical is electrically isolated from the wood with a piece of 1-inch diameter PVC tubing. A piece approximately 8 inches long is required, and it is of the schedule-80 variety. To prepare the tubing, you must slit it along the entire length on one side. A hacksaw will work quite well. The PVC fits rather snugly on the aluminum tubing and

Fig 31—A close-up view of a trap. The coil is 3 inches in diameter. The leads from the coaxial-cable capacitor should be soldered directly to the pigtails of the coil. These connections should be coated with varnish after they have been secured under the hose clamps.

Fig 32—The base assembly of the 21- and 28-MHz vertical. The SO-239 coaxial connector and hood can be seen in the center of the aluminum L bracket. The U bolts are TV-type antenna hardware. The plywood should be coated with varnish or similar material.

Fig 30—Constructional details of the 21- and 28-MHz dual-band antenna system.

will have to be "persuaded" with the aid of a hammer. Mount the mast directly on the wood with no insulation.

Use an SO-239 coaxial connector and four solder lugs on an L-shaped bracket made from a piece of aluminum sheet. Solder a short length of test probe wire, or inner conductor of RG-58 cable, to the inner terminal of the connector. A UG-106 connector hood is then slid over the wire and onto the coaxial connector. Then bolt the hood and connector to the aluminum bracket. Two wood screws are used to secure the aluminum bracket to the plywood, as shown in the drawing and photograph. Solder the free end of the wire coming from the connector to a lug mounted on the bottom of the vertical radiator. Fill any space between the wire and where it passes through the hood with GE silicone sealant or similar material to keep moisture out. The eight radials, four for each band, are soldered to the four lugs on the aluminum bracket. Separate the two sections of the vertical member with a piece of clear acrylic rod. Approximately 8 inches of ⅞-inch OD material is required. You must slit the aluminum tubing lengthwise for several inches so the acrylic rod may be inserted. The two pieces of aluminum tubing are separated by 2¼ inches.

The trap capacitor is made from RG-8 coaxial cable and is 30.5 inches long. RG-8 cable has 29.5 pF of capacitance per foot and RG-58 has 28.5 pF per foot. RG-8 cable is recommended over RG-58 because of its higher breakdown-voltage capability. The braid should be pulled back 2 inches on one end of the cable, and the center conductor soldered to one end of the coil. Solder the braid to the other end of the coil. Compression type hose clamps are placed over the capacitor/coil leads and put in position at the edges of the aluminum tubing. When tightened securely, the clamps serve a two-fold purpose—they keep the trap in contact with the vertical members and prevent the aluminum tubing from slipping off the acrylic rod. The coaxial-cable capacitor runs upward along the top section of the antenna. This is the side of the antenna to which the braid of the capacitor is connected. Place a cork or plastic cap in the very top of the antenna to keep moisture out.

Installation and Operation

The antenna may be mounted in position using a TV-type tripod, chimney, wall or vent mount. Alternatively, a telescoping mast or ordinary steel TV mast may be used, in which case the radials may be used as guys for the structure. The 28-MHz radials are 8 feet 5 inches long, and the 21-MHz radials are 11 feet 7 inches.

Any length of 50-Ω cable may be used to feed the antenna. The SWR at resonance should be on the order of 1.2:1 to 1.5:1 on both bands. The reason the SWR is not 1:1 is that the feed-point resistance is something other than 50 Ω —closer to 35 or 40 Ω.

The Open-Sleeve Antenna

Although only recently adapted for the HF and VHF amateur bands, the open-sleeve antenna has been around since 1946. The antenna was invented by Dr J. T. Bolljahn, of Stanford Research Institute. This section on sleeve antennas was written by Roger A. Cox, WBØDGF.

The basic form of the open-sleeve monopole is shown in **Fig 33**. The open-sleeve monopole consists of a base-fed central monopole with two parallel closely spaced parasitics, one on each side of the central element, and grounded at each base. The lengths of the parasitics are roughly one half that of the central monopole.

Impedance

The operation of the open sleeve can be divided into two modes, an antenna-mode and a transmission-line mode. This is shown in **Fig 34**.

The antenna-mode impedance, Z_A, is determined by the length and diameter of the central monopole. For sleeve lengths less than that of the monopole, this impedance is essentially independent of the sleeve dimensions.

The transmission-line mode impedance, Z_T, is determined by the characteristic impedance, end impedance, and length of the 3-wire transmission line formed by the central monopole and the two sleeve elements. The characteristic impedance, Z_c, can be determined by the element diameters and spacing if all element diameters are equal, and is found from

$$Z_c = 207 \log 1.59 \, (D/d) \qquad \text{(Eq 2)}$$

where

D = spacing between the center of each sleeve element and the center of the driven element

d = diameter of each element

This is shown graphically in **Fig 35**. However, since the end impedance is usually unknown, there is little need to know the characteristic impedance. The transmission-line mode impedance, Z_T, is usually determined by an educated guess and experimentation.

As an example, let us consider the case where the central monopole is $\lambda/4$ at 14 MHz. It would have an antenna mode impedance, Z_A, of approximately 52 Ω, depending upon the ground conductivity and number of radials. If two sleeve elements were added on either side of the central monopole, with each approximately half the height of the monopole and at a distance equal to their height, there would be very little

Fig 33—Diagram of an open-sleeve monopole.

Fig 35—Characteristic impedance of transmission-line mode in an open-sleeve antenna.

$$Z_C = 207 \; LOG_{10} \; 1.59 \, D/d$$

Fig 34—Equivalent circuit of an open-sleeve antenna.

effect on the antenna mode impedance, Z_A, at 14 MHz.

Also, Z_T at 14 MHz would be the end impedance transformed through a $\lambda/8$ section of a very high characteristic impedance transmission line. Therefore, Z_T would be on the order of 500-2000 Ω resistive plus a large capacitive reactance component. This high impedance in parallel with 52 Ω would still give a resultant impedance close to 52 Ω.

At a frequency of 28 MHz, however, Z_A is that of an end-fed half-wave antenna, and is on the order of 1000-5000 Ω resistive. Also, Z_T at 28 MHz would be on the order of 1000 to 5000 Ω resistive, since it is the end impedance of the sleeve elements transformed through a quarter-wave section of a very high characteristic impedance 3-wire transmission line. Therefore, the parallel combination of Z_A and Z_T would still be on the order of 500 to 2500 Ω resistive.

If the sleeve elements were brought closer to the central monopole such that the ratio of the spacing to element diameter was less than 10:1, then the characteristic imped-

ance of the 3-wire transmission line would drop to less than 250 Ω. At 28 MHz, Z_A remains essentially unchanged, while Z_T begins to edge closer to 52 Ω as the spacing is reduced. At some particular spacing the characteristic impedance, as determined by the D/d ratio, is just right to transform the end impedance to exactly 52 Ω at some frequency. Also, as the spacing is decreased, the frequency where the impedance is purely resistive gradually increases.

The actual impedance plots of a 14/28-MHz open-sleeve monopole appear in **Figs 36** and **37**. The length of the central monopole is 195.5 inches, and of the sleeve elements 89.5 inches. The element diameters range from 1.25 inches at the bases to 0.875 inch at each tip. The measured impedance of the 14-MHz monopole alone, curve A of Fig 36, is quite high. This is probably because of a very poor ground plane under the antenna. The addition of the sleeve elements raises this impedance slightly, curves B, C and D.

As curves A and B in Fig 37 show, an 8-inch sleeve spacing gives a resonance near 27.8 MHz at 70 Ω, while a 6-inch spacing gives a resonance near 28.5 MHz at 42 Ω. Closer spacings give lower impedances and higher resonances. The optimum spacing for this particular antenna would be somewhere between 6 and 8 inches. Once the spacing is found, the lengths of the sleeve elements can be tweaked slightly for a choice of resonant frequency.

In other frequency combinations such as 10/21, 10/24, 14/21 and 14/24-MHz, spacings in the 6 to 10-inch range work very well with element diameters in the 0.5 to 1.25-inch range.

Fig 36—Impedance of an open-sleeve monopole for the frequency range 13.5-15 MHz. Curve A is for a 14 MHz monopole alone. For curves B, C and D, the respective spacings from the central monopole to the sleeve elements are 8, 6 and 4 inches. See text for other dimensions.

Fig 37—Impedance of the open-sleeve monopole for the range 25-30 MHz. For curves A, B and C the spacings from the central monopole to the sleeve elements are 8, 6 and 4 inches, respectively.

Bandwidth

The open-sleeve antenna, when used as a multiband antenna, does not exhibit broad SWR bandwidths unless, of course, the two bands are very close together. For example, **Fig 38** shows the return loss and SWR of a single 10-MHz vertical antenna. Its 2:1 SWR bandwidth is 1.5 MHz, from 9.8 to 11.3 MHz. Return loss and SWR are related as given by the following equation.

$$SWR = \frac{1+k}{1-k}$$ (Eq 3)

where

$$k = 10^{\frac{R_L}{20}}$$

RL = return loss, dB

When sleeve elements are added for a resonance near 22 MHz, the 2:1 SWR bandwidth at 10 MHz is still nearly 1.5 MHz, as shown in **Fig 39**. The total amount of spectrum under 2:1 SWR increases, of course, because of the additional band, but the individual bandwidths of each resonance are virtually unaffected.

The open-sleeve antenna, however, can be used as a broadband structure, if the resonances are close enough to overlap. With the proper choices of resonant frequencies, sleeve and driven element diameters and sleeve spacing, the SWR "hump" between resonances can be reduced to a value less than 3:1. This is shown in **Fig 40**.

Current Distribution

According to H. B. Barkley (see Bibliography at the end of this chapter), the total current flowing into the base of the open-sleeve antenna may be broken down into two components, that contributed by the antenna mode, I_A, and that contributed by the transmission-line mode, I_T. Assuming that the sleeves are approximately half the height of the central monopole, the impedance of the antenna mode, Z_A, is very low at the resonant frequency of the central monopole, and

Fig 38—Return loss and SWR of a 10 MHz vertical antenna. A return loss of 0 dB represents an SWR of infinity. The text contains an equation for converting return loss to an SWR value.

Fig 39—Return loss and SWR of a 10/22 MHz open-sleeve vertical antenna.

Fig 40—SWR response of an open-sleeve dipole and a conventional dipole.

Fig 41—Current distribution in the transmission-line mode. The amplitude of the current induced in each sleeve element equals that of the current in the central element but the phases are opposite, as shown.

Fig 42—Total current distribution with $\lambda = L/2$.

the impedance of the transmission-line mode, Z_T, is very high. This allows almost all of the current to flow in the antenna mode, and I_A is very much greater than I_T. Therefore, the current on the central $\lambda/4$ monopole assumes the standard sinusoidal variation, and the radiation and gain characteristics are much like those of a normal $\lambda/4$ vertical antenna.

However, at the resonant frequency of the sleeves, the impedance of the central monopole is that of an end fed half-wave monopole and is very high. Therefore I_A is small. If proper element diameters and spacings have been used to match the transmission line mode impedance, Z_T, to 52 Ω, then I_T, the transmission line mode current, is high compared to I_A.

This means that very little current flows in the central monopole above the tops of the sleeve elements, and the radiation is mostly from the transmission-line mode current, I_T, in all three elements below the tops of the sleeve elements. The resulting current distribution is shown in **Figs 41** and **42** for this case.

Radiation Pattern and Gain

The current distribution of the open-sleeve antenna where all three elements are nearly equal in length is nearly that of a single monopole antenna. If, at a particular frequency, the elements are approximately $\lambda/4$ long, the current distribution is sinusoidal.

If, for this and other length ratios, the chosen diameters and spacings are such that the two sleeve elements approach

an interelement spacing of $\lambda/8$, the azimuthal pattern will show directivity typical of two in-phase vertical radiators, approximately $\lambda/8$ apart. If a bi-directional pattern is needed, then this is one way to achieve it.

Spacings closer than this will produce nearly circular azimuthal radiation patterns. Practical designs in the 10 to 30 MHz range using 0.5 to 1.5-inch diameter elements will produce azimuthal patterns that vary less than ±1 dB.

If the ratio of the length of the central monopole to the length of the sleeves approaches 2:1, then the elevation pattern of the open-sleeve vertical antenna at the resonant frequency of the sleeves becomes slightly compressed. This is because of the in-phase contribution of radiation from the $\lambda/2$ central monopole.

As shown in **Fig 43**, the 10/21-Mhz open-sleeve vertical antenna produces a lower angle of radiation at 21.2 MHz with a corresponding increase in gain of 0.66 dB over that of the 10-MHz vertical alone. At length ratios approaching 3:1, the

Fig 43—Vertical-plane radiation patterns of a 10/21-MHz open-sleeve vertical antenna on a perfect ground plane. At 10.1 MHz the maximum gain is 5.09 dBi, and 5.75 dBi at 21.2 MHz.

antenna mode and transmission-line mode impedance become nearly equal again, and the central monopole again carries a significant portion of the antenna current. The radiation from the top λ/2 combines constructively with the radiation from the λ/4 sleeve elements to produce gains of up to 3 dB more than just a quarter-wave vertical element alone.

Length ratios in excess of 3.2:1 produce higher level sidelobes and less gain on the horizon, except for narrow spots near the even ratios of 4:1, 6:1, 8:1, etc. These are where the central monopole is an even multiple of a half-wave, and the antenna-mode impedance is too high to allow much

antenna-mode current.

Up to this point, it has been assumed that only λ/4 resonance could be used on the sleeve elements. The third, fifth, and seventh-order resonances of the sleeve elements and the central monopole element can be used, but their radiation patterns normally consist of high-elevation lobes, and the gain on the horizon is less than that of a λ/4 vertical.

Practical Construction and Evaluation

The open-sleeve antenna lends itself very easily to home construction. For the open-sleeve vertical antenna, only a feed-point insulator and a good supply of aluminum tubing are needed. No special traps or matching networks are required. The open-sleeve vertical can produce up to 3 dB more gain than a conventional λ/4 vertical. Further, there is no reduction in bandwidth, because there are no loading coils.

The open-sleeve design can also be adapted to horizontal dipole and beam antennas for HF, VHF and UHF. A good example of this is Telex/Hy-Gain's Explorer 14 triband beam which utilizes an open sleeve for the 10/15-meter driven element. The open-sleeve antenna is also very easy to model in computer programs such as *NEC* and *MININEC*, because of the open tubular construction and lack of traps or other intricate structures.

In conclusion, the open-sleeve antenna is an antenna experimenters delight. It is not difficult to match or construct, and it makes an ideal broadband or multiband antenna.

The Coupled-Resonator Dipole

A variation of the open-sleeve system above is the coupled-resonator system described by Gary Breed, K9AY, in an article in *The ARRL Antenna Compendium, Vol 5*, entitled "The Coupled-Resonator Principle: A Flexible Method for Multiband Antennas." The following is condensed from that article.

In 1995, *QST* published two antenna designs that use an interesting technique to get multiband coverage in one antenna. Rudy Severns, N6LF, described a wideband 80 and 75-meter dipole using this technique, and Robert Wilson, AL7KK, showed us how to make a three-band vertical. Both of these antennas achieve multi-frequency operation by placing resonant conductors very close to a driven dipole or vertical—with no physical connection.

The Coupled-Resonator Principle

As we all know, nearby conductors can interact with an antenna. Our dipoles, verticals and beams can be affected by nearby power lines, rain gutters, guy wires and other metallic materials. The antennas designed by Severns and Wilson use this interaction intentionally, to combine the resonances of several conductors at a single feed point. While other names

have been used, I call the behavior that makes these antennas work the *coupled-resonator* (C-R) principle.

Take a look at **Fig 44**, which illustrates the general idea. Each figure shows the SWR at the feed point of a dipole, over a range of frequencies. When this dipole is all alone, it will have a very low SWR at its half-wave resonant frequency (Fig 44A). Next, if we take another wire or tubing conductor and start bringing it close to the dipole, we will see a "bump" in the dipole's SWR at the resonant frequency of this new wire. See Fig 44B. We are beginning to the see the effects of interaction between the two conductors. As we bring this new conductor closer, we reach a point where the SWR "bump" has grown to a very deep dip—a low SWR. We now have a good match at both the original dipole's resonant frequency and the frequency of the new conductor, as illustrated in Fig 44C.

We can repeat this process for several more conductors at other frequencies to get a dipole with three, four, five, six, or more resonant frequencies. The principle also applies to verticals, so any reference to a dipole can be considered to be valid for a vertical, as well.

We can write a definition of the C-R principle this

Fig 44—At A, the SWR of a dipole over a wide frequency range. At B, a nearby conductor is just close enough to interact with the dipole. At C, when the second conductor is at the optimum spacing, the combination is matched at both frequencies.

way: *Given a dipole (or vertical) at one frequency and an additional conductor resonant at another frequency, there is an optimum distance between them that results in the resonance of the additional conductor being imposed upon the original dipole, resulting in a low SWR at both resonant frequencies.*

Some History

In the late 1940s, the *coaxial sleeve* antenna was developed (**Fig 45A**), covering two frequencies by surrounding a dipole or monopole with a cylindrical tube resonant at the higher of the desired frequencies. In the 1950s, Gonset briefly marketed a two-band antenna based on this design. Other experimenters soon determined that two conductors

Fig 45—Evolution of coupled-resonator antennas: At A, the *coaxial-sleeve* dipole; at B, the *open-sleeve* dipole; and at C, a *coupled-resonator* dipole, the most universal configuration.

at the second frequency, placed on either side of the main dipole or monopole, would make a skeleton representation of a cylinder (Fig 45B). This is called the *open-sleeve* antenna. The Hy-Gain Explorer tribander uses this method in its driven element to obtain resonance in the 10-meter band. Later on, a few antenna developers finally figured out that these extra conductors did not need to be added in pairs, and that a single conductor at each frequency could add the extra resonances (Fig 45C). This is the method used by Force 12 in some of their multiband antennas.

This is a perfect example of how science works. A specific idea is discovered, with later developments leading to an underlying general principle. The original coaxial-sleeve configuration is the most specific, being limited to two frequencies and requiring a particular construction method. The open-sleeve antenna is an intermediate step, showing that the sleeve idea is not limited to one configuration.

Finally, we have the coupled-resonator concept, which is the general principle, applicable in many different antenna configurations, for many different frequency combinations. Severns' antenna uses it with a folded dipole, and Wilson uses it with a main vertical that is off-center fed. The author K9AY used it with conventional dipoles and quarter-wave verticals. Other designers have used the principle more subtly, like putting the first director in a Yagi very close to the driven element, broadening the SWR bandwidth the same way Severns' design does with a dipole.

In the past, most antennas built with this single-conductor technique have also been called *open-sleeve* (or *multiple-open-sleeve*) antennas, a term taken from the history of their development. However, the term *sleeve* implies that one conductor must surround another. This is not really a physical or electrical description of the antenna's operation, therefore, K9AY suggests using the term *coupled-resonator,* which is the most accurate description of the general principle.

A Little Math

The interaction that makes the C-R principle work is not random. It behaves in a predictable, regular manner. K9AY

derived an equation that shows the relationship between the driven element and the additional resonators for ordinary dipoles and verticals:

$$\frac{\log_{10} d}{\log_{10}(D/4)} = 0.54 \qquad \text{(Eq 4)}$$

where

> d = distance between conductors, measured in wavelengths at the frequency of the chosen additional resonator
>
> D = the diameter of the conductors, also in wavelengths at the frequency of the additional resonator.

Eq 4 assumes they are both the same diameter and that the feed point impedance at both frequencies is the same as a dipole in free space (72 Ω) or a quarter-wave monopole over perfect ground (36 Ω).

The equation only describes the impedance due to the additional resonator. The main dipole element is always part of the antenna, and it may have a fairly low impedance at the additional frequency. This is the case when the frequencies are close together, or when the main element is operating at its third harmonic. At these frequencies, the spacing distance must be adjusted so that the parallel combination of dipole and resonator results in the desired feed-point impedance.

K9AY worked out two correction factors, one to cover a range of impedances and another for frequencies close together. These can be included in the basic equation, which is rearranged below to solve for the distance between the conductors:

$$d = 10^{0.54 \log_{10}(D/4)} \times \frac{Z_0 + 35.5}{109} \times [1 + e^{-[((F_2/F_1)-1.1)\times 11.3)+0.1)]}] \qquad \text{(Eq 5)}$$

where

> d and D are the same as above.
>
> Z_0 = the desired feed point impedance at the frequency of the additional resonator (between 20 and 120 Ω). For a vertical, multiply the desired impedance by two to get Z_0. If you want a 50-Ω feed, use 100 Ω for Z_0.
>
> F_1 = the resonant frequency of the main dipole or vertical.
>
> F_2 = the resonant frequency of the additional conductor. The ratio F_2/F_1 is more than 1.1.
>
> e = 2.7183, the base of natural logarithms.

Eq 5 does not directly allow for conductors of unequal diameters, but it can be used as a starting point if you use the diameter of the driven dipole or vertical element for D in the equation.

Characteristics of C-R Antennas

Here's the important stuff—what's different about C-R antennas, what are they good for and what are their drawbacks? The key points are:

• Multiband operation without traps, stubs or tuners

K9AY's Eq 5 above does indeed yield a good "first-cut" value for the spacing between coupled-resonator elements. **Fig A** shows the spacing, in inches, plotted against the ratio of frequencies, for two coupled resonator elements with different diameters, again expressed in inches. This is for an upper frequency of 28.4 MHz. Beyond a frequency ratio of about 1.5:1 (28.4:18.1 MHz), the spacing flattens out to a fixed distance between elements for each element diameter. For example, if $1/_2$-inch elements are used at 28.4 and 18.1 MHz, the spacing between the elements is about 3.75 inches.

EZNEC verifies Eq 5's computations. Note that a large number of segments are necessary for each element when they are closely spaced from each other, and the segments on the elements must be closely aligned with each other. Be sure to run the Average Gain test, as well as Segmentation tests. The modeler should also be aware that if mutually coupled resonators are placed along a horizontal boom (as they would be on multiband Yagis using coupled resonators), the higher-frequency elements will act like retrograde directors, producing some gain (or lack of gain, depending on the azimuth being investigated).

For example, in the *EZNEC* file **K9AY C-R 28-21-14 MHz 1 In.EZ**, using 1-inch diameter elements spaced 6 inches apart, if the 28-MHz element is placed 6 inches behind the 14-MHz driven element (with the 21-MHz element placed 6 inches ahead), on 28 MHz the system will have a F/B of 2.6 dB, favoring the rearward direc-

Fig A—Graph of the spacing versus frequency ratio for two Coupled-Resonator elements at 28.4 MHz, for 50-Ω feed-point impedance.

tion. On 21 MHz, the system will exhibit a F/B of 1.6 dB, favoring the forward direction. Of course, there are systems where gain and F/B due to the C-R configuration may be put to good use, such as the multiband Yagis mentioned above. However, if the elements are spaced above/below the 14-MHz driven element there is no distortion of the dipole patterns.

- Flexible impedance matching at each frequency
- Independent fine-tuning at each frequency (little interaction)
- Easily modeled using *MININEC* or *NEC*-based programs
- Pruning process same as a simple dipole
- Can accommodate many frequencies (seven or more)
- Virtually lossless coupling (high efficiency)
- Requires a separate wire or tubing conductor at each frequency
- Mechanical assembly requires a number of insulated supports
- Narrower bandwidth than equivalent dipole
- Capacitance requires slight lengthening of conductors

To begin with, the most obvious characteristic is that this principle can be used to add multiple resonant frequencies to an ordinary dipole or vertical, using additional conductors that are not physically connected. This gives us three variable factors: (1) the diameter of the conductor, (2) its length, and (3) its position relative to the main element.

Having the freedom to control these factors gives us the advantage of *flexibility*; we have a wide range of control over the impedance at each added frequency. Another advantage is that the behavior at each frequency is quite *independent*, once the basic design is in place. In other words, making fine-tuning adjustments at one frequency doesn't change the resonance or impedance at the other frequencies. A final advantage is *efficiency*. With conductors close together, and with a resonant target conductor, coupling is very efficient. Traps, stubs, and compensating networks found on other multiband antennas all introduce lossy reactive components.

There are two main disadvantages of C-R antennas. The first is the relative *complexity* of construction. Several conductors are needed, installed with some type of insulating spacers. Other multiband antennas have their complexities as well (such as traps that need to be mounted and tuned), but C-R antennas will usually be bulkier. The larger size generally means greater windload, which is a disadvantage to some hams.

The other significant disadvantage is *narrower bandwidth*, particularly at the highest of the operating frequencies. We can partially overcome this problem with large conductors that are naturally broad in bandwidth, and in some cases we might even use an extra conductor to put two resonances in one band. It is interesting to note that the pattern is opposite that of trapped antennas. The C-R antenna gets narrower at the highest frequencies of operation, while trap antennas generally have narrowest bandwidth at their lowest frequencies.

There are two special situations that should be noted. First, when the antenna has a resonance near the frequency where the driven dipole is 3/2 λ long (3/4 λ for a vertical), the dipole has a fairly low impedance. The spacing of the C-R element needs to be increased to raise its impedance so that the parallel combination of the main element and C-R element equals the desired impedance (usually 50 Ω). There is also significant antenna current in the part of the main dipole extending beyond the C-R section, contributing to the total radiation pattern. As a result, this particular arrangement radiates as three λ/2 sections in phase, and has about 3 dB gain and a narrower directional pattern compared to a dipole (**Fig 46**). This might be an advantage for antennas covering bands with a frequency ratio of about three, such as 3.5 and 10.1 MHz, 7 and 21 MHz, or 144 and 430 MHz.

The other special situation is when we want to add a new frequency very close to the resonant frequency of the main dipole. An antenna for 80 and 75 meters would be an example of this. Again, the driven dipole has a fairly low impedance at the new frequency. Add the fact that coupling is very strong between these similar conductors and we find that a wide spacing is required to make the antenna work. A dipole resonant at 3.5 MHz and another wire resonant at 3.8 MHz will need to be 3 or 4 feet apart, while a 3.5 MHz and 7 MHz combination might only need to be spaced 4 or 5 inches.

Another useful characteristic of C-R antennas is that they are easily and accurately modeled by computer programs based on either *MININEC* or *NEC*, as long as you stay within each program's limitations. For example, Severns points out that *MININEC* does not handle folded dipoles very well, and *NEC* modeling is required. With ease of computer modeling, a precise answer isn't needed for the design equation given above. An approximate solution will provide a starting point that can quickly be adjusted for optimum dimensions.

The added resonators have an effect on the lengths of all conductors, due to the capacitance between the conductors. Capacitance causes antennas to look electrically shorter, so

Fig 46—Radiation pattern for the special case of a C-R antenna with the additional frequency at the third harmonic of the main dipole resonant frequency.

each element needs to be about 1% or 2% longer than a simple dipole at the same frequency. As a rule of thumb, use 477/f (in feet) instead of the usual 468/f when calculating dipole length, and 239/f instead of 234/f for a λ/4 vertical.

A 30/17/12-Meter Dipole

To show how a C-R antenna is designed, let's build a dipole to cover all three WARC bands. We'll use #12 wire, which has a diameter of 0.08 inches, and the main dipole will be cut for the 10.1 MHz band. From the equation above, the spacing between the main dipole and the 18-MHz resonator should be 2.4 inches for 72 Ω, or 1.875 inches for 50 Ω. At 24.9 MHz, the spacing to the resonator for that band should be 2.0 inches for 72 Ω, or 1.62 inches for 50 Ω. Of course, this antenna will be installed over real ground, not in free space, so these spacing distances may not be exact. Plugging these numbers into your favorite antenna-modeling program will let you optimize the dimensions for installation at the height you choose.

For those of you who like to work with real antennas, not computer-generated ones, the predicted spacing is accurate enough to build an antenna with minimum trial-and-error. You should use a nice round number just larger than the calculated spacing for 50 Ω. For this antenna, K9AY decided that the right spacing for the desired height would be 2 inches for the 18 MHz resonator and 1.8 inches for the 24.9 MHz resonator. For simplicity of construction, he just used 2 inches for both, figuring that the worst he would get is a 1.2:1 SWR if the numbers were a little bit off. Like all dipoles, the impedance varies with height above ground, but the 2-inch spacing results in an excellent match on the two additional bands, at heights of more than 25 feet.

The final dimensions of the dipole for 10.1, 18.068 and 24.89 MHz are shown in **Fig 47**. These are the final pruned lengths for a straight dipole installed at a height of about 40 feet. If you put up the antenna as an inverted V, you will need each wire to be a bit longer. Pruning this type of antenna is just like a dipole—if it's resonant too low in frequency, it's too long and the appropriate wire needs to be shortened. So, you can cut the wires just a little long to start with and easily prune them to resonance.

A final note: if you want to duplicate this antenna design, remember that the 2-inch spacing is just for #12 wire! The required spacing for a C-R antenna is related to the conductor diameter. This same antenna built with #14 wire needs under 1½-inch spacing, while a 1-inch aluminum-tubing version requires about 7-inch spacing.

Fig 47—Dimensions of a C-R dipole for the 30, 17 and 12-meter bands.

Summary

The coupled-resonator principle is one more weapon in the antenna designer's arsenal. It's not the perfect method for all multiband antennas, but what the C-R principle offers is an alternative to traps and tuners, in exchange for using more wire or aluminum. Although a C-R antenna requires more complicated construction, its main attraction is in making a multiband antenna that can be built with no compromise in matching or efficiency.

HF Discone Antennas

The material in this section is adapted from an article by Daniel A. Krupp, W8NWF, in *The ARRL Antenna Compendium, Vol 5*. The name *discone* is a contraction of the words disc and cone. Although people often describe a discone by its design-center frequency (for example, a "20-meter discone"), it works very well over a wide frequency range, as much as several octaves. **Fig 48** shows a typical discone, constructed of sheet metal for UHF use. On lower frequencies, the sheet metal may be replaced with closely spaced wires and/or aluminum tubing.

The dimensions of a discone are determined by the lowest frequency of use. The antenna produces a vertically polarized signal at a low-elevation angle and it presents a good match for 50-Ω coax over its operating range. One advantage of the discone is that its maximum current area is near the top of the antenna, where it can radiate away from ground clutter. The cone-like skirt of the discone radiates the signal—radiation from the disc on top is minimal. This is because the currents flowing in the skirt wires essentially all go in the same direction, while the currents in the disc elements oppose each other and cancel out. The discone's omnidirectional characteristics make it ideal for roundtable QSOs or for a Net Control station.

Electrical operation of this antenna is very stable, with no changes due to rain or accumulated ice. It is a self-contained antenna—unlike a traditional ground-mounted vertical radiator, the discone does not rely on a ground-radial system for efficient operation. However, just like any other vertical

Fig 48—Diagram of VHF/UHF discone, using a sheet-metal disc and cone. It is fed directly with 50-Ω coax line. The dimensions L and D, together with the spacing S between the disc and cone, determine the frequency characteristics of the antenna. L = 246 / f_{MHz} for the lowest frequency to be used. Diameter D should be from 0.67 to 0.70 of dimension L. The diameter at the bottom of the cone B is equal to L. The space S between disc and cone can be 2 to 12 inches, with the wider spacing appropriate for larger antennas.

antenna, the quality of the ground in the Fresnel area will affect the discone's far-field pattern.

Both the disc and cone are inherently balanced for wind loading, so torque caused by the wind is minimal. The entire cone and metal mast or tower can be connected directly to ground for lightning protection.

Unlike a trap vertical or a triband beam, discone antennas are not adjusted to resonate at a particular frequency in a ham band or a group of ham bands. Instead, a discone functions as a sort of high-pass filter, efficiently radiating RF all the way from the low-frequency design cutoff to the high-frequency limits imposed by the physical design.

While VHF discones have been available out-of-the-box for many years, HF discones are rare indeed. Some articles have dealt with HF discones, where the number of disc elements and cone wires was minimized to cut costs or to simplify construction. While the minimalist approach is fine if the sought-after results really are obtained, W8NWF believes in building his discones without compromise.

History of the Discone

The July 1949 and July 1950 issues of *CQ* magazine both contained excellent articles on discones. The first article, by Joseph M. Boyer, W6UYH, said that the discone was developed and used by the military during World War II. (See Bibliography.) The exact configuration of the top disc and cone was the brainchild of Armig G. Kandonian. Boyer described three VHF models, plus information on how to build them, radiation patterns, and most importantly, a detailed description of how they work. He referred to the

discone as a type of "coaxial taper transformer."

The July 1950 article was by Mack Seybold, W2RYI. He described an 11-MHz version he built on his garage roof. The mast actually fit through the roof to allow lowering the antenna for service. Seybold stated that his 11-MHz discone would load up on 2 meters but that performance was down 10 dB compared to his 100-MHz Birdcage discone. He commented that this was caused by the relatively large spacing between the disc and cone. Actually, the performance degradation he found was caused by the wave angle lifting upward at high frequencies. The cone wires were electrically long, causing them to act like long wire antennas. See **Fig 49**.

W8NWF's First Discone: the A-Frame Discone

The first discone was one designed to cover 20 through 10 meters without requiring an antenna tuner. The cone assembly uses 18-foot long wires, with a 60° included apex angle and a 12-foot diameter disc assembly. See **Fig 50** and **Fig 51**. The whole thing was assembled on the ground, with the feed coax and all guys attached. Then with the aid of some friends, it was pulled up into position.

The author used a 40-foot tall wooden "A-frame" mast, made of three 22-foot-long 2 × 4s. He primed the mast with sealer and then gave it two coats of red barn paint to make it look nice and last a long time. The disc hub was a 12-inch length of 3-inch schedule-40 PVC plumbing pipe. The PVC is very tough, slightly ductile, and easy to drill and cut. PVC is well suited for RF power at the feed point of the antenna.

Three 12-foot by 0.375-inch OD pieces of 6061 aluminum, with 0.058-inch wall thickness, were used for the 12-foot diameter top disc. These were cut in half to make the center portions of the six telescoping spreaders. Four twelve foot by 0.250-inch OD (0.035-inch wall thickness) tubes were cut into 12 pieces, each 40 inches long. This gave extension tips for each end of the six spreaders.

See **Fig 52** for details on the disc hub assembly. W8NWF started by drilling six holes straight through the PVC for the six spreaders, accurately and squarely, starting

Fig49—Computed elevation plot over average ground for W8NWF's small discone at 146 MHz, ten times its design frequency range. The cone wires are acting as long-wire antennas, distorting severely the low-elevation angle response, even though the feed-point impedance is close to 50 Ω.

Fig 50—Photo of W8NWF's original A-frame mounted HF discone.

12' dia. disc — 12 aluminum spreaders connected tip to tip with 18 ga. wire

45 cone wires 18' long 60° apex angle

Aluminum strap 1"x 1/8"x 55' 6–1/2" See text

Six nylon or black Dacron cone guy lines

All stakes 23' 1–1/2" from center of mast

40' mast made of wooden 2x4 s

Mast guy wires 2 sets of 3 with egg insulators

Fig 51—Detailed drawing of the A-frame discone for 14 to 30 MHz. The disc assembly at the top of the A-frame is 12 feet in diameter. There are 45 cone wires, each 18 feet long, making a 60° included angle of the cone. This antenna works very well over the design frequency range.

about two inches down from the top and spaced radially every 30°. Each hole is 0.375 inches below the plane of the previous one. Take great care in drilling—a poor job now will look bad from the ground up for a long time! It's a good idea to make up a paper template beforehand. Tape this to the PVC hub and then drill the holes, which should make for a close fit with the elements. If you goof, start over with a new piece of PVC—it's cheap.

Each six-foot spreader tube was secured exactly in the center to clear a 6-32 threaded brass rod that secured the elements mechanically and electrically. A two-foot long by ¼-inch OD wooden dowel was inserted into the middle of each six-foot length of tubing. The dowel added strength and also prevented crushing the element when the nuts on the threaded rod were tightened.

Insert the 40-inch long extensions four inches into each end of the six-foot spreaders. Mark and drill holes to pin the telescoping tips, plus holes big enough to clear #18 soft-drawn copper wire. This was for the inner circumferential wire for the disc. Drill a single hole for #18 wire about ¼ inch from each extension element tip, through which passes the outer circumferential wire. Finally, insert all 6-foot elements into the PVC hub and line up the holes in the center so the brass rod could be inserted through the middle to secure the elements.

The next step is to "chisel to fit" the top of my wooden mast to allow the PVC to slide down on it about six or seven inches. For convenience, place the whole mast assembly in a horizontal position on top of two clothesline poles and one stepladder.

Place the disc head assembly over the top of the mast, but don't secure it yet. This allows for rotation while adding the disc spreader extensions. A tip for safety: tie white pieces of cloth to the ends of elements near eye level. Just remember to remove them before raising the antenna.

For a long-lasting installation, use an anti-corrosion compound, such as Penetrox, when assembling the aluminum antenna elements. As the extensions are added, secure them in the innermost of the two holes with a short piece of #18 wire. Then run a wire through the remaining holes looping each element as you go. This gives added support laterally to the elements. Next add a #18 wire to the tips of the extensions in the same fashion. This provides even more

PVC Rain Cap

Brass Nuts, Washers, and Threaded Rod

3/8" OD aluminum disc through the PVC pipe. 2' long wooden dowel inside each one.

Center Lead of Coax

PVC pipe, 3"ID, 12" long

Shielded Braid of Coax

Brass hardware

Cone wires

Loop of 12 ga. stranded wire for connecting cone wires

Top end of 2x4 of 40' wooden mast. Snug fit inside PVC, corners trimmed to fit

50−Ω coax feed line

Fig 52—Details of the top hub for the A-frame discone. The three-inch PVC pipe was drilled to hold the six spreaders making up the top disc. Connections for the shield of the feed coax were made to the disc. The coax center conductor was connected to the cone-wire assembly by means of a loop of #12 stranded wire encircling the outside of the PVC hub.

physical stability as well as making electrical connections.

Next, pin the PVC disk hub to the wooden mast with a ⅜-inch threaded rod. This is also the point where the cone wires are attached, using a loop of #12 stranded copper wire around the PVC. Solder each cone wire to this loop, together with the coax shield braid. Make sure the loop of #12 wire is large enough to make soldering possible without burning the PVC with the soldering iron.

Connect the coax center conductor to the disc assembly by securing it with the same 6-32 threaded rod that ties all the disc elements together. Make sure to use coax-seal compound to keep moisture out of the coax. The coax is then fed down the mast and secured in a few places to provide strain relief and to keep it out of the way of the cone wires.

Use two sets of three guy wires. Break these up with egg insulators, just to be sure there won't be any interaction with the antenna. Use 45 wires of #18 soft-drawn copper wire

for the cone, 18 feet long each. Cut them a little long so they can be soldered to the connecting loop.

A difficult task is now at hand—keeping all the cone wires from getting tangled! Solder each of the 45 cone wires to the loop of #12 wire, spacing each wire about ¼ inch from the last one for an even distribution all the way around.

The cone base is 18 feet in diameter to provide a 60° included angle. At the base of the cone, use five 12-foot long aluminum straps, 1 inch wide by ⅛ inch thick, overlapping 8¼ inches and fastened together with aluminum rivets. Drill holes along the strap every 15 inches to secure the cone wires.

Make sure to handle the aluminum strap carefully while fastening the cone wire ends; too sharp of a bend could possibly break it. Fasten six small-diameter nylon lines to the cone-base aluminum strap to stabilize the cone. These cone-guys share the same guy stakes as the mast guy lines.

After cutting the nylon lines, heat the frayed ends of each with a small flame to prevent unraveling. Apply several coats of clear protective spray to the disk head assembly, after checking that all hardware is tight. A rain cap at the top of the PVC disc hub completes construction.

Putting It All Up

You are going to need a lot of help now to raise this antenna. Have the whole process fully thought out before trying to raise it. You should have the spot selected for the base of the mast and some pipes driven into the ground to prevent the mast from slipping sideways as it is being pulled up. The three guy stakes should be in place, 23 feet, 1½ inches from mast center. Of course, the guys should have been cut to the correct length, with some extra. Be sure the coax transmission line will come off the mast where it should. A long length of rope to an upper and lower guy line is used to pull up the whole works.

The author used an old trick of standing an extension ladder vertically near the antenna base with the pull lines looped over the top rung to get a good lift angle. The weight added to the mast from the antenna disc assembly and cone wires is about 26 pounds, most of it from the cone assembly. Use two strong people to pull up the antenna slowly so that the other helpers on the guy wires and cone guy lines have time to move about as required. As the antenna rises to the vertical position, if there are no snafus, the guy lines can be secured. Then tie the six cone lines to stakes.

A Really Big Discone

When an opportunity arose to buy a 64-foot self-supporting TV tower, the author jumped at the chance to implement a full 7 to 30-MHz discone. His new tower had eight sections, each eight feet long. Counting the overlap between sections, the cone wires would come off the tower at about the 61.5-foot mark.

W8NWF took some liberties with the design of this larger discone compared to the first one, which he had done strictly "by the book." The first change was to make the cone wires 70 feet long, even though the formula said they should be 38 feet long. Further, the cone wires would not be connected together at the bottom. With the longer cone wires, he felt that 75 and 80-meter operation might be a possibility.

Fig 53—The large W8NWF discone, designed for operation from 7 to 14 MHz, but useable with a tuning network in the shack for 3.8 MHz.

The second major change was to widen the apex angle out from 60° to about 78°. Modeling said this should produce a flatter SWR over the frequency spectrum and would also give a better guy system for the tower.

The topside disc assembly would be 27 feet in diameter and have 16 radial spreaders, using telescoping aluminum tubing tapering from ⅝ to ½ to ⅜ inches OD. All spreaders were made from 0.058-inch wall thickness 6063-T832 aluminum tubing, available from Texas Towers. A section of 10-inch PVC plumbing pipe would be used as the hub for construction of the disc assembly.

Construction Details for the Large Discone.

While installing the tower, the author had left the top section on the ground. This allowed him to fit the disc head assembly precisely to it. **Fig 53** shows the overall plan for the large discone. The 10-inch diameter PVC hub was designed to slip over the tower top section, but was a little too large. So a set of shims was installed on the three legs at the top of the tower for a just-right fit. Drilling the PVC pipe for the eight ⅝-inch OD elements was started about an inch down from the top. W8NWF purposely staggered the drilled holes in the same fashion as the hub for the smaller antenna. See **Fig 54**.

Again, three-foot sections of ½-inch wooden dowel were used to strengthen the ⅝-inch center portion of each spreader. Instead of using a loop of #12 wire for connecting the cone wires, as had been done on the smaller discone, he drilled 36 holes in the PVC hub. These holes are small enough so

Fig 54—Photo showing details of the hub assembly for the large discone, including the threaded brass rod that connects the radial spreaders together. The 10-inch PVC pipe is drilled to accommodate the radial spreaders. Each spreader is reinforced with a three-foot long wooden dowel inside for crush resistance. Note the row of holes drilled below the lowest spreader. Each of the 36 cone wire passes through one of these holes.

Fig 55—Details of the copper pipe slipped over the feed coax. The coax shield has been folded back over the copper pipe and secured with two stainless-steel hose clamps. The cone wires are also laid against the copper pipe and secured with additional hose clamps.

that the PVC hub would not be weakened appreciably. He drilled the circles of holes for the cone wires about 6 inches below the disc spreaders.

He prepared a three-foot long piece of RG-213 coax, permanently fastened on one end to the antenna, with a female type-N connector at the other end. Type-N fittings were used because of their superior waterproofing abilities. The coax center lead was connected with a terminal lug under a nut on the brass threaded rod securing the disc spreaders. The coax shield braid was folded back over a six-inch long copper pipe and clamped to it with a stainless-steel hose clamp. See **Fig 55** for details.

The plan was that after the top disc assembly had been hoisted up and attached at the top of the tower, individual cone wires would be fed, one at a time, through the small holes drilled in the PVC. They were to be laid against the copper pipe and secured with stainless-steel hose clamps.

The ½ and ⅜-inch OD spreader extension tips were secured in place with two aluminum pop-rivets at each joint. Again, the author used anti-oxidant compound on all spreader junctions. He drilled a hole horizontally near the tip of each ⅜-inch tip all around the perimeter to allow a #8 aluminum wire to circle the entire disc. A small stainless-steel sheet-metal screw was threaded into the end of each element to secure the wire.

In parallel with the aluminum wire, a length of small-diameter black Dacron line was run, securing it in a couple of places between each set of spreaders with UV-resistant plastic tie-wraps. The reason for doing this was to hold the aluminum wire in position and to prevent it from dangling, in case it should break some years in the future. Two coats of clear protective spray were applied for protection.

A truss system helps prevent the disc from sagging due to its own weight. See **Fig 56** for details. This shows the completed disk assembly mounted on the

Fig 56—Photo of the spreader hub assembly, showing the truss ropes above and below the radial spreaders. This is a very rugged assembly!

Fig 57—Photo showing some of the fence posts used to hold individual cone wires to keep them off the ground and out of harm's way. The truck in the background is carting away the A-frame discone for installation at KA8UNO's QTH.

top of the tower. A 3-foot length of 2-inch PVC pipe was used for a truss mast above the disc assembly, notching the bottom of the pipe so that it would form a saddle over the top couple of spreaders. This gave a good foothold. He cut a circle of thin sheet aluminum to fit over the 10-inch PVC to serve as a rain cap. The cap has a hole in the center for the two-inch PVC truss mast to pass through, thereby holding it down tight. The author sprayed a few light coats of paint over the PVC for protection from ultraviolet radiation from the sun.

Sixteen small-diameter black Dacron ropes were connected at the top of the truss support mast, with the other ends fastened to the disc spreaders, halfway out. Another rain cap was added to the top of the two-inch PVC truss mast. Eight lengths of the same small diameter Dacron rope were added halfway out the length of every other spreader. These ropes are meant to be tied back to the tower, to prevent updrafts from blowing the disc assembly upwards. Small egg insulators were used near the spot where the eight bottom trusses were tied to the disc spreaders, just to be sure there would be no RF leakage in rainy weather.

Hoisting the completed disc assembly to the top of the tower can be done easily, with the assistance of at least two others. The trickiest part is to get the disc assembly from its position sitting flat on the ground to the vertical position needed for hoisting it up the tower without damaging it. The disc assembly weighs about 35 pounds. Someone at the top of the tower will receive the disc as it is hoisted up by gin pole, and can mount it on the tower top.

You should prepare three 6-foot long metal braces going over the outside of the PVC to fasten to the tower legs. They really beef things up.

In plastic irrigation pipe buried between the house and tower base, the author ran 100 feet of 9086 low-loss coax to the shack. For cone wires, he was able to obtain some #18 copperclad steel wire, with heavy black insulation that looked a lot like neoprene. The cone system takes a lot of

wire: 36 × 70 feet = 2520 feet, plus some extra at each end for termination. You'd be well advised to look around at hamfests to save money.

As each cone wire was connected at the top of the tower, a helper should place the other end at its proper spot below. The lower end of each cone wire is secured to an insulator screwed into a fencepost. See **Fig 57**. There are 36 treated-pine fenceposts, each standing about 5½ feet tall, 45 feet from the tower base to hold the lower end of the cone wires. This makes mowing the grass easier and the cone wires are less likely to be tripped over too.

On the final trip down the tower, the eight Dacron downward-truss lines were tied back to the tower about 6 feet below the disc assembly. The author's tower has three ground rods driven near the base, connected with heavy copper wire to the three tower legs.

Fig 58—Computed patterns showing elevation response of small discone at 28.5 MHz compared to that of the larger discone at 28.5 MHz. The cone wires are clearly too long for efficient operation on 10 meters, producing unwanted high-angle lobes that rob power from the desirable low-elevation angles.

Performance Tests

On the air tests proved to be very satisfying. Loading up on 40 meters was easy—the SWR was 1:1 across the entire band. W8NWF can work all directions very well and receives excellent signal reports from DX stations. When he switches to his long (333 foot) center-fed dipole for comparison, he finds the dipole is much noisier and that received signals are weaker. During the daytime, nearby stations (less than about 300 to 500 miles) can be louder with the dipole, but the discone can work them just fine also.

The author happily reports that this antenna even works well on 75 meters. As you might expect, it doesn't present a 1:1 match. However, the SWR is between 3.5:1 and 5.5:1 across the band. W8NWF uses an antenna tuner to operate the discone on 75. It seems to get out as well on 75 as it does on 40 meters.

The SWR on 30 meters is about 1.1:1. On 20 meters the SWR runs from 1.05:1 at 14.0 MHz to 1.4:1 at 14.3 MHz. The SWR on the 17, 15, 12 and 10-meter bands varies, going up to a high of 3.5:1 on 12 meters.

Radiation Patterns for the Discones

From modeling using *NEC/Wires* by K6STI, W8NWF verified that the low-angle performance for the bigger antenna is worse than that for the smaller discone on the upper frequencies. See **Fig 58** for an elevation-pattern comparison on 10 meters for both antennas, with average ground constants. The azimuth patterns are simply circles. Radiation patterns produced by antenna modeling programs are very helpful to determine what to expect from an antenna.

The smaller discone, which was built by the book, displays good, low-angle lobes on 20 through 10 meters. The frequency range of 14 through 28 MHz is an octave's worth of coverage. It met his expectations in every way by covering this frequency span with low SWR and a low angle of radiation.

The bigger discone, with a modified cone suitable for use on 75 meters, presents a little different story. The low-angle lobe on 40 meters works well, and 75-meter performance also is good, although an antenna tuner is necessary on this band. The 30-meter band has a good low-angle lobe

Fig 59—Computed elevation-response patterns for the larger W8NWF discone for 3.8, 7.2 and 21.2 MHz operation. Again, as in Fig 58, the pattern degrades at 21.2 MHz, although it is still reasonably efficient, if not optimal.

but secondary high-angle lobes are starting to hurt performance. Note that 30 meters is roughly three times the design frequency of the cone. On 20 and 17 meters there still are good low-angle lobes but more and more power is wasted in high-angle lobes.

The operation on 15, 12, and 10 meters continues to worsen for the larger discone. The message here is that although a discone may have a decent SWR as high as 10 times the design frequency, its radiation pattern is not necessarily good for low-angle communications. See **Fig 59** for a comparison of elevation patterns for 3.8, 7.2 and 21.2 MHz on the larger discone.

A discone antenna built according to formula will work predictably and without any adjustments. One can modify the antenna's cone length and apex angle without fear of rendering it useless. The broadband feature of the discone makes it attractive to use on the HF bands. The low angle of radiation makes DX a real possibility, and the discone is also much less noisy on receive than a dipole.

Probably the biggest drawback to an HF discone is its bulky size. There is no disguising this antenna! However, if you live in the countryside you should be able to put up a nice one.

Harmonic Radiation from Multiband Antennas

Since a multiband antenna is intentionally designed for operation on a number of different frequencies, any harmonics or spurious frequencies that happen to coincide with one of the antenna resonant frequencies will be radiated with very little, if any, attenuation. Particular care should be exercised, therefore, to prevent such harmonics from reaching the antenna.

Multiband antennas using tuned feeders have a certain inherent amount of built-in protection against such radiation, since it is nearly always necessary to use a tuned coupling circuit (antenna tuner) between the transmitter and the feeder. This adds considerable selectivity to the system and helps to discriminate against frequencies other than the desired one.

Multiple dipoles and trap antennas do not have this feature, since the objective in design is to make the antenna show as nearly as possible the same resistive impedance in all the amateur bands the antenna is intended to cover. It is advisable to conduct tests with other amateur stations to determine whether harmonics of the transmitting frequency can be heard at a distance of, say, a mile or so. If they can, more selectivity should be added to the system since a harmonic that is heard locally, even if weak, may be quite strong at a distance because of propagation conditions.

BIBLIOGRAPHY

Source material and more extended discussion of topics covered in this chapter can be found in the references given below and in the textbooks listed at the end of Chapter 2, Antenna Fundamentals.

H. B. Barkley, *The Open-Sleeve As A Broadband Antenna*, Technical Report No. 14, U.S. Naval Postgraduate School, Monterey, CA, Jun 1955.

W. M. Bell, "A Trap Collinear Antenna," *QST*, Aug 1963, pp 30-31.

J. S. Belrose, "The HF Discone Antenna," *QST*, Jul 1975, pp 11-14, 56.

J. Belrose and P. Bouliane, "The Off-Center-Fed Dipole Revisited: A Broadband, Multiband Antenna," *QST*, Oct 1990, p 40.

H. J. Berg, "Multiband Operation with Paralleled Dipoles," *QST*, Jul 1956.

E. L. Bock, J. A. Nelson and A. Dorne, "Sleeve Antennas," *Very High Frequency Techniques*, H. J. Reich, ed. (New York: McGraw-Hill, 1947), Chap 5.

J. T. Bolljahn and J. V. N. Granger, "Omnidirectional VHF and UHF Antennas," *Antenna Engineering Handbook*, H. Jasik, ed. (New York: McGraw-Hill, 1961) pp 27-32 through 27-34.

J. M. Boyer, W6UYH, "Discone--40 to 500 Mc Skywire," *CQ*, July 1949, p 11.

G. A. Breed, K9AY, "Multi-Frequency Antenna Technique Uses Closely-Coupled Resonators," *RF Design*, November 1994. US Patent 5,489,914, "Method of Constructing Multiple-Frequency Dipole or Monopole Antenna Elements Using Closely-Coupled Resonators," Gary A. Breed, Feb 6, 1996.

G. H. Brown, "The Phase and Magnitude of Earth Currents Near Radio Transmitting Antennas," *Proc. IRE*, Feb 1935.

G. H. Brown, R. F. Lewis and J. Epstein, "Ground Systems as a Factor in Antenna Efficiency," *Proc. IRE*, Jun 1937, pp 753-787.

C. L. Buchanan, "The Multimatch Antenna System," *QST*, Mar 1955.

R. A. Cox, "The Open-Sleeve Antenna," *CQ*, Aug 1983, pp 13-19.

D. DeMaw, "Lightweight Trap Antennas—Some Thoughts," *QST*, Jun 1983, p 15.

W. C. Gann, "A Center-Fed 'Zepp' for 80 and 40," *QST*, May 1966.

D. Geiser, "An Inexpensive Multiband VHF Antenna," *QST*, Dec 1978, pp 28-29.

A. Greenberg, "Simple Trap Construction for the Multiband Antenna," *QST*, Oct 1956.

G. L. Hall, "Trap Antennas," Technical Correspondence, *QST*, Nov 1981, pp 49-50.

W. Hayward, "Designing Trap Antennas," Technical Correspondence, *QST*, Aug 1976, p 38.

R. H. Johns, "Dual-Frequency Antenna Traps," *QST*, Nov 1983, p 27.

A. G. Kandoian, "Three New Antenna Types and Their Applications," *Proc IEE*, Vol 34, Feb 1946, pp 70W-75W.

R. W. P. King, *Theory of Linear Antennas* (Cambridge, MA: Harvard Univ Press, 1956), pp 407-427.

W. J. Lattin, "Multiband Antennas Using Decoupling Stubs," *QST*, Dec 1960.

W. J. Lattin, "Antenna Traps of Spiral Delay Line," *QST*, Nov 1972, pp 13-15.

M. A. Logan, "Coaxial-Cable Traps," Technical Correspondence, *QST*, Aug 1985, p 43.

J. R. Mathison, "Inexpensive Traps for Wire Antennas," *QST*, Aug 1977, p 18.

L. McCoy, "An Easy-to-Make Coax-Fed Multiband Trap Dipole," *QST*, Dec 1964.

M. Mims, "The Mims Signal Squirter," *QST*, Dec 1939, p 12.

G. E. O'Neil, "Trapping the Mysteries of Trapped Antennas," *Ham Radio*, Oct 1981, pp 10-16.

B. Orr, W6SAI, "Radio FUNdamentals," The Open-Sleeve Dipole, *CQ*, February 1995.

E. W. Pappenfus, "The Conical Monopole Antenna," *QST*, Nov 1966, pp 21-24.

L. Richard, "Parallel Dipoles of 300-Ohm Ribbon," *QST*, Mar 1957.

R. Severns, N6LF, "A Wideband 80-Meter Dipole," *QST*, July 1995.

R. R. Shellenback, "Try the 'TJ'," *QST*, Jun 1982, p 18.

R. R. Shellenback, "The JF Array," *QST*, Nov 1982, p 26.

H. Scholle and R. Steins, "Eine Doppel-Windom Antenna fur Acht Bander," *cq-DL*, Sep 1983, p 427. (In English: *QST*, Aug 1990, pp 33-34.)

T. H. Schiller, N6BT, President, Force 12, US Patent 5,995,061, "No loss, multi-band, adaptable antenna," Nov 30, 1999.

M. Seybold, W2RYI, "The Low-Frequency Discone," *CQ*, July 1950, p 13.

D. P. Shafer, "Four-Band Dipole with Traps," *QST*, Oct 1958.

R. C. Sommer, "Optimizing Coaxial-Cable Traps," *QST*, Dec 1984, p 37.

L. Varney, "The G5RV Multiband Antenna . . . Up-to-Date," *The ARRL Antenna Compendium, Vol 1* (Newington: ARRL, 1985), pp 86.

R. Wilson, AL7KK, "The Offset Multiband Trapless Antenna (OMTA)," *QST*, October 1995.

L. G. Windom, "Notes on Ethereal Antennas," *QST*, Sep 1929, pp 19-22, 84.

W. I. Orr, W6SAI, editor, "The Low-Frequency Discone," *RADIO Handbook*, 14th Edition, (Editors and Engineers, 1956), p 369.

Multielement Arrays

The gain and directivity offered by an array of elements represents a worthwhile improvement both in transmitting and receiving. *Power gain* in an antenna is the same as an equivalent increase in the transmitter power. But unlike increasing the power of your own transmitter, antenna gain works equally well on signals received from the favored direction. In addition, the directivity reduces the strength of signals coming from the directions not favored, and so helps discriminate against interference.

One common method of obtaining gain and directivity is to combine the radiation from a group of λ/2 dipoles to concentrate it in a desired direction. A few words of explanation may help make it clear how power gain is obtained.

In **Fig 1**, imagine that the four circles, A, B, C and D, represent four dipoles so far separated from each other that the coupling between them is negligible. Also imagine that point P is so far away from the dipoles that the distance from P to each one is exactly the same (obviously P would have to be much farther away than it is shown in this drawing). Under these conditions the fields from all the dipoles will add up at P if all four are fed RF currents in the same phase.

Let us say that a certain current, I, in dipole A will produce a certain value of field strength, E, at the distant point P. The same current in any of the other dipoles will produce the same field at P. Thus, if only dipoles A and B are operating, each with a current I, the field at P will be 2E.

With A, B and C operating, the field will be 3E, and with all four operating with the same I, the field will be 4E. Since the power received at P is proportional to the square of the field strength, the relative power received at P is 1, 4, 9 or 16, depending on whether one, two, three or four dipoles are operating.

Now, since all four dipoles are alike and there is no coupling between them, the same power must be put into each in order to cause the current I to flow. For two dipoles the relative power input is 2, for three dipoles it is 3, for four dipoles 4, and so on. The actual gain in each case is the relative received (or output) power divided by the relative input power. Thus we have the results shown in **Table 1**. The power ratio is directly proportional to the number of elements used.

It is well to have clearly in mind the conditions under which this relationship is true:

1) The fields from the separate antenna elements must be in-phase at the receiving point.

2) The elements are identical, with equal currents in all elements.

3) The elements must be separated in such a way that the current induced in one by another is negligible; that is, the radiation resistance of each element must be the same as it would be if the other elements were not there.

Very few antenna arrays meet all these conditions exactly. However, the power gain of a directive array using dipole elements with optimum values of element spacing is approximately proportional to the number of elements.

Fig 1—Fields from separate antennas combine at a distant point, P, to produce a field strength that exceeds the field produced by the same power in a single antenna.

ANT0296

Table 1

Comparison of Dipoles with Negligible Coupling (See Fig 1)

Dipoles	Relative Output Power	Relative Input Power	Power Gain	Gain in dB
A only	1	1	1	0
A and B	4	2	2	3
A, B and C	9	3	3	4.8
A, B, C and D	16	4	4	6

Another way to say this is that a gain of approximately 3 dB will be obtained each time the number of elements is doubled, assuming the proper element spacing is maintained. It is possible, though, for an estimate based on this rule to be in error by a ratio factor of two or more (gain error of 3 dB or more), especially if mutual coupling is *not* negligible.

DEFINITIONS

An *element* in a multi-element directive array is usually a λ/2 radiator or a λ/4 vertical element above ground. The length is not always an exact electrical half or quarter wavelength, because in some types of arrays it is desirable that the element show either inductive or capacitive reactance. However, the departure in length from resonance is ordinarily small (not more than 5% in the usual case) and so has no appreciable effect on the radiating properties of the element.

Antenna elements in multi-element arrays of the type considered in this chapter are always either *parallel*, as in **Fig 2A** , or *collinear* (end-to-end), as in Fig 2B. Fig 2C shows an array combining both parallel and collinear elements. The elements can be either horizontal or vertical, depending on whether horizontal or vertical polarization is desired. Except for space communications, there is seldom any reason for mixing polarization, so arrays are customarily constructed with all elements similarly polarized.

A *driven element* is one supplied power from the transmitter, usually through a transmission line. A *parasitic element* is one that obtains power solely through coupling to another element in the array because of its proximity to such an element.

A *driven array* is one in which all the elements are driven elements. A *parasitic array* is one in which one or more of the elements are parasitic elements. At least one element must be a driven element, since you must somehow introduce power into the array.

A *broadside array* is one in which the principal direction of radiation is perpendicular to the axis of the array and to the plane containing the elements, as shown in **Fig 3**. The elements of a broadside array may be collinear, as in Fig 3A, or parallel (two views in Fig 3B).

An *end-fire array* is one in which the principal direction of radiation coincides with the direction of the array axis. This definition is illustrated in **Fig 4**. An end-fire array must consist of parallel elements. They cannot be collinear, as λ/2 elements do not radiate straight off their ends. A Yagi is a familiar form of an end-fire array.

A *bidirectional array* is one that radiates equally well in either direction along the line of maximum radiation. A bidirectional pattern is shown in **Fig 5A**. A *unidirectional array* is one that has only one principal direction of radiation, as the pattern in Fig 5B shows.

The *major lobes* of the directive pattern are those in which the radiation is maximum. Lobes of lesser radiation intensity are called *minor lobes*. The *beamwidth* of a directive antenna is the width, in degrees, of the major lobe between the two directions at which the relative radiated power is equal to one half its value at the peak of the lobe. At these *half-power points* the field intensity is equal to 0.707 times its maximum value, or in other words, is down 3 dB from the maximum. **Fig 6** shows a lobe having a beamwidth of 30°.

Unless specified otherwise, the term *gain* as used in this

Fig 3—Representative broadside arrays. At A, collinear elements, with parallel elements at B.

Fig 4—An end-fire array. Practical arrays may combine both broadside directivity (Fig 3) and end-fire directivity, including both parallel and collinear elements.

Fig 2—At A, parallel and at B, collinear antenna elements. The array shown at C combines both parallel and collinear elements.

section is the power gain over an isotropic radiator in free space. The gain can also be compared with a λ/2 dipole of the same orientation and height as the array under discussion and having the same power input. Gain may either be measured experimentally or determined by calculation. Experimental measurement is difficult and often subject to considerable error, for two reasons. First, errors normally occur in measurement because the accuracy of simple RF measuring

equipment is relatively poor—even high-quality instruments suffer in accuracy compared with their low-frequency and dc counterparts. And second, the accuracy depends considerably on conditions—the antenna site, including height, terrain characteristics, and surroundings—under which the measurements are made.

Calculations are frequently based on the measured or theoretical directive patterns of the antenna (see Chapter 2). The theoretical gain of an array may be determined approximately from:

$$G = 10 \ \log \ \frac{41{,}253}{\theta_H \ \theta_V} \hspace{2cm} \text{(Eq 1)}$$

where

G = decibel gain over a dipole in its favored direction
θ_H = horizontal half-power beamwidth in degrees
θ_V = vertical half-power beamwidth in degrees.

This equation, strictly speaking, applies only to lossless antennas having approximately equal and narrow E- and H-plane beam widths—up to about 20°—and no large minor lobes. The E and H planes are discussed in Chapter 2. The error may be considerable when the formula is applied to simple directive antennas having relatively large beam widths. The error is in the direction of making the calculated gain larger than the actual gain.

Front-to-back ratio (F/B) is the ratio of the power radiated in the favored direction to the power radiated in the opposite direction. See Chapter 11 for a discussion of front-to-back ratio, and its close cousin, *worst-case front-to-rear ratio*.

Fig 5—At A, typical bidirectional pattern and at B, unidirectional directive pattern. These drawings also illustrate the application of the terms *major* and *minor* to the pattern lobes.

Fig 6—The width of a beam is the angular distance between the directions at which the received or transmitted power is half the maximum power (–3 dB). Each angular division of the pattern grid is 5°.

Phase

The term *phase* has the same meaning when used in connection with the currents flowing in antenna elements as it does in ordinary circuit work. For example, two currents are in-phase when they reach their maximum values, flowing in the same direction, at the same instant. The direction of current flow depends on the way in which power is applied to the element.

This is illustrated in **Fig 7**. Assume that by some means an identical voltage is applied to each of the elements at the ends marked A. Assume also that the coupling between the elements is negligible, and that the instantaneous polarity of the voltage is such that the current is flowing away from the point at which the voltage is applied. The arrows show the assumed current directions. Then the currents in elements 1 and 2 are in-phase, since they are flowing in the same direction in space and are caused by the same voltage. However, the current in element 3 is flowing in the *opposite* direction in space because the voltage is applied to the opposite end of the element. The current in element 3 is therefore 180° out-of-phase with the currents in elements 1 and 2.

The phasing of driven elements depends on the direction of the element, the phase of the applied voltage, and the point at which the voltage is applied. In many systems used by amateurs, the voltages applied to the elements are exactly

Fig 7—This drawing illustrates the phase of currents in antenna elements, represented by the arrows. The currents in elements 1 and 2 are in phase, while that in element 3 is 180° out of phase with 1 and 2.

in or exactly out-of-phase with each other. Also, the axes of the elements are nearly always in the same direction, since parallel or collinear elements are invariably used. The currents in driven elements in such systems therefore are usually either exactly in or exactly out-of-phase with the currents in other elements.

It is possible to use phase differences of less than 180° in driven arrays. One important case is where the current in one set of elements differs by 90° from the current in another set. However, making provision for proper phasing in such systems is considerably more complex than in the case of simple 0° or 180° phasing, as described in a later section of this chapter.

In parasitic arrays the phase of the currents in the parasitic elements depends on the spacing and tuning, as described later.

Ground Effects

The effect of the ground is the same with a directive antenna as it is with a simple dipole antenna. The reflection factors discussed in Chapter 3 may therefore be applied to the vertical pattern of an array, subject to the same modifications mentioned in that chapter. In cases where the array elements are not all at the same height, the reflection factor for the mean height of the array may be used for a close approximation. The mean height is the average of the heights measured from the ground to the centers of the lowest and highest elements.

MUTUAL IMPEDANCE

Consider two λ/2 elements that are fairly close to each other. Assume that power is applied to only one element, causing current to flow. This creates an electromagnetic field,

which induces a voltage in the second element and causes current to flow in it as well. The current flowing in element 2 will in turn induce a voltage in element 1, causing additional current to flow there. The total current in 1 is then the sum (taking phase into account) of the original current and the induced current.

With element 2 present, the amplitude and phase of the resulting current in element 1 will be different than if element 2 were not there. This indicates that the presence of the second element has changed the impedance of the first. This effect is called *mutual coupling*. Mutual coupling results in a *mutual impedance* between the two elements. The mutual impedance has both resistive and reactive components. The actual impedance of an antenna element is the sum of its self-impedance (the impedance with no other antennas present) and its mutual impedances with all other antennas in the vicinity.

The magnitude and nature of the feed-point impedance of the first antenna depends on the amplitude of the current induced in it by the second, and on the phase relationship between the original and induced currents. The amplitude and phase of the induced current depend on the spacing between the antennas and whether or not the second antenna is tuned to resonance.

In the discussion of the several preceding paragraphs, power is applied to only one of the two elements. Do not interpret this to mean that mutual coupling exists only in parasitic arrays! It is important to remember that mutual coupling exists between any two conductors that are located near one another.

Amplitude of Induced Current

The induced current will be largest when the two antennas are close together and are parallel. Under these conditions the voltage induced in the second antenna by the first, and in the first by the second, has its greatest value and causes the largest current flow. The coupling decreases as the parallel antennas are moved farther apart.

The coupling between collinear antennas is comparatively small, and so the mutual impedance between such antennas is likewise small. It is not negligible, however.

Phase Relationships

When the separation between two antennas is an appreciable fraction of a wavelength, a measurable period of time elapses before the field from antenna 1 reaches antenna 2. There is a similar time lapse before the field set up by the current in number 2 gets back to induce a current in number 1. Hence the current induced in antenna 1 by antenna 2 will have a phase relationship with the original current in antenna 1 that depends on the spacing between the two antennas.

The induced current can range all the way from being completely in-phase with the original current to being completely out-of-phase with it. If the currents are in-phase, the total current is larger than the original current and the antenna feed-point impedance is reduced. If the currents are out-of-phase, the total current is smaller and the impedance

is increased. At intermediate phase relationships the impedance will be lowered or raised depending on whether the induced current is mostly in or mostly out-of-phase with the original current.

Except in the special cases when the induced current is exactly in or out-of-phase with the original current, the induced current causes the phase of the total current to shift with respect to the applied voltage. Consequently, the presence of a second antenna nearby may cause the impedance of an antenna to be reactive—that is, the antenna will be detuned from resonance—even though its self-impedance is entirely resistive. The amount of detuning depends on the magnitude and phase of the induced current.

Tuning Conditions

A third factor that affects the impedance of antenna 1 when antenna 2 is present is the tuning of number 2. If antenna 2 is not exactly resonant, the current that flows in it as a result of the induced voltage will either lead or lag the phase it would have if the antenna were resonant. This causes an additional phase advance or delay that affects the phase of the current induced back in antenna 1. Such a phase lag has an effect similar to a change in the spacing between self-resonant antennas. However, a change in tuning is not exactly equivalent to a change in spacing because the two methods do not have the same effect on the amplitude of the induced current.

MUTUAL IMPEDANCE AND GAIN

The mutual coupling between antennas is important because it can have a significant effect on the amount of current that will flow for a given amount of power supplied. And it is the amount of *current* flowing that determines the field strength from the antenna. Other things being equal, if the mutual coupling between two antennas is such that the currents are greater for the same total power than would be the case if the two antennas were not coupled, the power gain will be greater than that shown in Table 1.

On the other hand, if the mutual coupling is such as to reduce the current, the gain will be less than if the antennas were not coupled. The term *mutual coupling*, as used in this paragraph, assumes that the mutual impedance between elements is taken into account, along with the added effects of propagation delay because of element spacing and element tuning or phasing.

The calculation of mutual impedance between antennas is a complex problem. Data for two simple but important cases are graphed in Figs 8 and 9. These graphs do not show the mutual impedance, but instead show a more useful quantity—the feed-point resistance measured at the center of an antenna as it is affected by the spacing between two antennas.

As shown by the solid curve in **Fig 8**, the feed-point resistance at the center of either antenna, when the two are self-resonant, parallel, and operated in-phase, decreases as the spacing between them is increased until the spacing is about 0.7 λ. This is a broadside array. The maximum gain

Fig 8—Feed-point resistance measured at the center of one element as a function of the spacing between two parallel ½-λ self-resonant antenna elements. For ground-mounted ¼-λ vertical elements, divide these resistances by two.

is achieved from a pair of such elements when the spacing is in this region, because the current is larger for the same power and the fields from the two arrive in-phase at a distant point placed on a line perpendicular to the line joining the two antennas.

The dashed line in Fig 8, representing two antennas operated 180° out-of-phase (end-fire), cannot be interpreted quite so simply. The feed-point resistance decreases with spacing decreasing less than about 0.6 λ in this case. However, for the range of spacings considered, only when the spacing is 0.5 λ do the fields from the two antennas add up exactly in phase at a distant point in the favored direction. At smaller spacings the fields become increasingly out-of-phase, so the total field is less than the simple sum of the two. Smaller spacings thus decrease the gain at the same time that

Fig 9—Feed-point resistance measured at the center of one element as a function of the spacing between the ends of two collinear self-resonant ½-λ antenna elements operated in phase.

the reduction in feed-point resistance is increasing it. For a lossless antenna, the gain goes through a maximum when the spacing is in the region of ⅛ λ.

The feed-point resistance curve for two collinear elements in-phase, **Fig 9**, shows that the feed-point resistance decreases and goes through a broad minimum in the region of 0.4 to 0.6-λ spacing between the adjacent ends of the antennas. As the minimum is not significantly less than the feed-point resistance of an isolated antenna, the gain will not exceed the gain calculated on the basis of uncoupled antennas. That is, the best that two collinear elements will give, even with optimum spacing, is a power gain of about 2 (3 dB). When the separation between the ends is very small—the usual method of operation—the gain is reduced.

GAIN AND ARRAY DIMENSIONS

The gain of an array is principally determined by the dimensions of the array, so long as there are a minimum number of elements. A good example of this is the relationship between boom length, gain and number of elements for an array such as a Yagi. **Fig 10** compares the gain versus boom length for Yagis with different numbers of elements. For given number of elements, notice that the gain increases as the boom length increases, up to a maximum. Beyond this point, longer boom lengths result in less gain for a given number of elements. This observation does not mean that it is always desirable to use only the minimum number of elements. Other considerations of array performance, such as front-to-back ratio, minor lobe amplitudes or operating bandwidth, may make it advantageous to use more than the minimum number of elements for a given array length. A specific example of this is presented in a later section in a comparison between a half-square, a bobtail curtain and a Bruce array.

In a broadside array the gain is a function of both the length and width of the array. The gain can be increased by adding more elements (with additional spacing) or by using longer elements (>λ/2), although the use of longer elements requires proper attention to current phase in the elements. In general, in a broadside array the element spacing that gives maximum gain for a minimum number of elements, is in the range of 0.5 to 0.7 λ. Broadside arrays with elements spaced

Fig 10—Yagi gain for 3, 4, 5, 6 and 7-element beams as a function of boom length. (From *Yagi Antenna Design*, J. Lawson, W2PV.)

for maximum gain will frequently have significant side lobes and associated narrowing of the main lobe beamwidth. Side lobes can be reduced by using more than the minimum number of elements, spaced closer than the maximum gain distance.

Additional gain can be obtained by expanding the array into a third dimension. An example of this is the stacking of endfire arrays in a broadside configuration. In the case of stacked short endfire arrays, maximum gain occurs with spacings in the region of 0.5 to 0.7 λ. However, for longer higher-gain end-fire arrays, larger spacing is required to achieve maximum gain. This is important in VHF and UHF arrays, which often use long-boom Yagis.

PARASITIC ARRAYS

The foregoing applies to multi-element arrays of both types, driven and parasitic. However, there are special considerations for driven arrays that do not necessarily apply to parasitic arrays, and vice versa. Such considerations for Yagi and quad parasitic arrays are presented in Chapters 11 and 12. The remainder of this chapter is devoted to driven arrays.

Driven Arrays

Driven arrays in general are either broadside or end-fire, and may consist of collinear elements, parallel elements, or a combination of both. From a practical standpoint, the maximum number of usable elements depends on the frequency and the space available for the antenna. Fairly elaborate arrays, using as many as 16 or even 32 elements, can be installed in a rather small space when the operating frequency is in the VHF range, and more at UHF. At lower frequencies the construction of antennas with a large number of elements is impractical for most amateurs.

Of course the simplest of driven arrays is one with just two elements. If the elements are collinear, they are always fed in-phase. The effects of mutual coupling are not great, as illustrated in Fig 9. Therefore, feeding power to each element in the presence of the other presents no significant problems. This may not be the case when the elements are parallel to each other. However, because the combination of spacing and phasing arrangements for parallel elements is infinite, the number of possible radiation patterns is endless.

This is illustrated in **Fig 11**. When the elements are fed

in-phase, a broadside pattern always results. At spacings of less than ⅝ λ with the elements fed 180° out-of-phase, an end-fire pattern always results. With intermediate amounts of phase difference, the results cannot be so simply stated. Patterns evolve that are not symmetrical in all four quadrants.

Because of the effects of mutual coupling between the two driven elements, for a given power input greater or lesser currents will flow in each element with changes in spacing and phasing, as described earlier. This, in turn, affects the gain of the array in a way that cannot be shown merely by plotting the *shapes* of the patterns, as has been done in Fig 11. Therefore, supplemental gain information is also shown in Fig 11, adjacent to the pattern plot for each combination of spacing and phasing. The gain figures shown are referenced to a single element. For example, a pair of elements fed 90° apart at a spacing of λ/4 will have a gain in the direction of maximum radiation of 3.1 dB over a single element.

Current Distribution in Phased Arrays

In the plots of Fig 11, the two elements are assumed to be identical and self-resonant. In addition, currents of equal amplitude are assumed to be flowing at the feed point of each element, a condition that most often will not exist in practice without devoting special consideration to the feeder system. Such considerations are discussed in the next section of this chapter.

Most literature for radio amateurs concerning phased arrays is based on the assumption that if all elements in the array are identical, the *current distribution* in all the elements will be identical. This distribution is presumed to be that of a single, isolated element, or nearly sinusoidal. However, information published in the professional literature as early as the 1940s indicates the existence of dissimilar current distributions among the elements of phased arrays. (See Harrison and King references in the Bibliography.) Lewallen, in July 1990 *QST*, pointed out the causes and effects of dissimilar current distributions.

In essence, even though the two elements in a phased array may be identical and have exactly equal currents of the desired phase flowing *at the feed point*, the amplitude and phase relationships degenerate with departure from the feed point. This happens any time the phase relationship is not 0° or 180°. Thus, the field strengths produced at a distant point by the individual elements may differ. This is because the field from each element is determined by the *distribution* of the current, as well as its magnitude and phase.

The effects are minimal with shortened elements—verticals less than λ/4 or dipoles less than λ/2 long. The effects on radiation patterns begin to show at the above resonant lengths, and become profound with longer elements—λ/2 or longer verticals and 1 λ or longer center-fed elements. These effects are less pronounced with thin elements. The amplitude and phase degeneration takes place because the currents in the array elements are not sinusoidal. Even in two-element arrays with phasing of 0° or 180°, the currents are not sinusoidal, but in these two special cases they do remain identical.

The pattern plots of Fig 11 take element current distributions into account. The visible results of dissimilar distributions are incomplete nulls in some patterns and the development of very small minor lobes in others. For example, the pattern for a phased array with 90° spacing and 90° phasing has traditionally been published in amateur literature as a cardioid with a perfect null in the rear direction. Fig 11, calculated for 7.15-MHz self-resonant dipoles of #12 wire in free space, shows a minor lobe at the rear and only a 33-dB front-to-back ratio.

It is characteristic of broadside arrays that the power gain is proportional to the length of the array but is substantially independent of the number of elements used, provided the optimum element spacing is not exceeded. This means, for example, that a five-element array and a six-element array will have the same gain, provided the elements in both are spaced so the overall array length is the same. Although this principle is seldom used for the purpose of reducing the number of elements because of complications introduced in feeding power to each element in the proper phase, it does illustrate the fact that there is nothing to be gained, in terms of more gain, by increasing the number of elements if the space occupied by the antenna is not increased proportionally.

Generally speaking, the maximum gain in the smallest linear dimensions will result when the antenna combines both broadside and end-fire directivity and uses both parallel and collinear elements. In this way the antenna is spread over a greater volume of space, which has the same effect as extending its length to a much greater extent in one linear direction.

Fig 11—H-plane patterns of two identical parallel driven elements, spaced and phased as indicated (S = spacing, φ = phasing). The elements are aligned with the vertical (0°-180°) axis, and the element nearer the 0° direction (top of page) is of lagging phase at angles other than 0°. The two elements are assumed to be thin and self-resonant, with equal-amplitude currents flowing at the feed point. See text regarding current distributions. The gain figure associated with

| S = 5/8 λ | S = 3/4 λ | S = 7/8 λ | S = 1 λ | ANT0306 |

φ = 0°
G = 4.8 dB G = 4.6 dB G = 3.7 dB G = 2.8 dB

φ = 45°
G = 4.2 dB G = 4.1 dB G = 3.5 dB G = 2.8 dB

φ = 90°
G = 3.0 dB G = 3.0 dB G = 3.0 dB G = 3.0 dB

φ = 135°
G = 2.1 dB G = 2.2 dB G = 2.6 dB G = 3.2 dB

φ = 180°
G = 1.8 dB G = 1.8 dB G = 2.4 dB G = 3.3 dB

each pattern indicates that of the array over a single element. The plots represent the horizontal or azimuth pattern at a 0° elevation angle of two ¼-λ vertical elements over a perfect conductor, or the free-space vertical or elevation pattern of two horizontal ½-λ elements when viewed on end, with one element above the other. (Patterns computed with *ELNEC*—see Bibliography.)

Phased Array Techniques

Phased antenna arrays have become increasingly popular for amateur use, particularly on the lower frequency bands, where they provide one of the few practical methods to obtain substantial gain and directivity. This section on phased-array techniques was written by Roy Lewallen, W7EL.

The operation and limitations of phased arrays, how to design feed systems to make them work properly and how to make necessary tests and adjustments are discussed in the pages that follow. The examples deal primarily with vertical HF arrays, but the principles apply to VHF/UHF arrays and arrays made from other element types as well.

OVERVIEW

Much of this chapter is devoted to techniques for feeding phased arrays. Many people who have a limited acquaintance with phased array techniques believe this is a simple problem, consisting only of connecting array elements through "phasing lines" consisting of transmission lines of the desired electrical lengths. Unfortunately, except for a very few special cases, this approach won't achieve the desired array pattern.

Other proposed universal solutions, such as hybrid couplers or Wilkinson or other power dividers, also usually fail to achieve the necessary phasing. These approaches sometimes produce—often more by accident than design—results good enough to mislead the user into believing that the simple approach is working as planned. Confusion can result when an approach fails to work in different circumstances. This section will explain why the simple solutions don't work as often thought, and how to design feed systems that do consistently produce the desired results.

Very briefly, the reason why the simple phasing-line approach fails is that the delay of current or voltage in a transmission line equals the line's electrical length only if the line is terminated in its characteristic impedance. And in phased arrays, element feed-point impedances are profoundly affected by mutual coupling.

Consequently, even if each element has the correct impedance when isolated, it won't when all elements are excited. Furthermore, transmission lines that are not terminated in their characteristic impedance will transform both the voltage and current magnitude. The net result is that the array elements will have neither the correct magnitudes nor phases of current necessary for proper operation except in a few special cases. This isn't a minor effect of concern only to perfectionists, but often a major one that causes significant pattern distortion and poor or mislocated nulls. The problem is examined in greater depth later.

Power dividers and hybrid couplers also fail to achieve the desired result for different reasons, which will be discussed below, although in one common application hybrid couplers fortuitously provide results that are acceptable to many users. This chapter will show how to design array feed systems that *will* produce predicted element currents

and array patterns.

Various *EZNEC* models are provided to illustrate concepts presented in this chapter. They can all be viewed with the *EZNEC-ARRL* software furnished on the CD included with this book. Step-by-step instructions for the examples are given in **Appendix A**.

FUNDAMENTALS OF PHASED ARRAYS

The performance of a phased array is determined by several factors. Most significant among these are the characteristics of a single element, reinforcement or cancellation of the fields from the elements and the effects of mutual coupling. To understand the operation of phased arrays, it is first necessary to understand the operation of a single antenna element.

Of primary importance is the strength of the field produced by the element. The field radiated from a linear (straight) element, such as a dipole or vertical monopole, is proportional to the sum of the elementary currents flowing in each part of the antenna element. For this discussion it is important to understand what determines the current in a single element.

The amount of current flowing at the base of a ground mounted vertical or ground-plane antenna is given by the familiar formula

$$I = \sqrt{\frac{P}{R}} \qquad \text{(Eq 2)}$$

where

P is the power supplied to the antenna
R is the feed-point resistance.

R consists of two parts, the loss resistance and the radiation resistance. The loss resistance, R_L, includes losses in the conductor, in the matching and loading components and dominantly (in the case of ground-mounted verticals) in ground losses. The power "dissipated" in the radiation resistance, R_R, is actually the power that is radiated, so maximizing the power dissipated by the radiation resistance is desirable. However, the power dissipated in the loss resistance truly is lost as heat, so resistive losses should be made as small as possible.

The radiation resistance of an element can be derived from electromagnetic field theory, being a function of antenna length, diameter and geometry. Graphs of radiation resistance versus antenna length are given in Chapter 2. The radiation resistance of a thin resonant $\lambda/4$ ground-mounted vertical is about 36 Ω. A resonant $\lambda/2$ dipole in free space has a radiation resistance of twice this amount, about 73 Ω. Reducing the antenna lengths by one half drops the radiation resistances to approximately 7 and 14 Ω, respectively.

The radiation resistance of a large variety of antennas can easily be determined by using *EZNEC-ARRL*, which is included on the CD in the back of this book. The radiation

Fig 12—Simplified equivalent circuit for a single-element resonant antenna. R_R represents the radiation resistance, and R_L the ohmic losses in the total antenna system.

resistance is simply the feed-point resistance (the resistive part of the feed-point impedance) when all losses have been set to zero.

Radiation Efficiency

To generate a stronger field from a given radiator, it is necessary to increase the power P (the brute-force solution), decrease the loss resistance R_L (by putting in a more elaborate ground system for a vertical, for instance) or to somehow decrease the radiation resistance R_R so more current will flow with a given power input. This can be seen by expanding the formula for base current as

$$I = \sqrt{\frac{P}{R_R + R_L}} \qquad \text{(Eq 3)}$$

Splitting the feed-point resistance into components R_R and R_L easily leads to an understanding of element efficiency. The efficiency of an element is the proportion of the total power that is actually radiated. The roles of R_R and R_L in determining efficiency can be seen by analyzing a simple equivalent circuit, shown in **Fig 12**.

The power dissipated in R_R (the radiated power) equals $I^2 R_R$. The total power supplied to the antenna system is

$$P = I^2 (R_R + R_L) \qquad \text{(Eq 4)}$$

so the efficiency (the fraction of supplied power that is actually radiated) is

$$Eff = \frac{I^2 R_R}{I^2 (R_R + R_L)} = \frac{R_R}{R_R + R_L} \qquad \text{(Eq 5)}$$

Efficiency is frequently expressed in percent, but expressing it in decibels relative to a 100%-efficient radiator gives a better idea of what to expect in the way of signal strength. The field strength of an element relative to a lossless but otherwise identical element, in dB, is

$$FSG = 10 \log \frac{R_R}{R_R + R_L} \qquad \text{(Eq 6)}$$

where FSG = field strength gain, dB.

For example, information presented by Sevick in March 1973 *QST* shows that a $\lambda/4$ ground-mounted vertical antenna with four 0.2-λ radials has a feed-point resistance of about 65 Ω (see the Bibliography at the end of this chapter). The efficiency of such a system is $36/65 = 55.4\%$. It is rather disheartening to think that, of 100 W fed to the antenna, only 55 W is being radiated, with the remainder literally warming up the ground. Yet the signal will be only 10 log (36/65) = –2.57 dB relative to the same vertical with a perfect ground system. In view of this information, trading a small reduction in signal strength for lower cost and greater simplicity may become an attractive consideration.

So far, only the current at the base of a resonant antenna has been discussed, but the field is proportional to the sum of currents in each tiny part of the antenna. The field is a function of not only the magnitude of current flowing at the feed point, but also the distribution of current along the radiator and the length of the radiator. Nothing can be done at the feed point to change the current distribution, so for a given element the field strength is proportional to the feed point current. However, changing the radiator length or loading it at some point other than the feed point will change the current distribution.

More information on shortened or loaded radiators may be found in Chapters 2 and 6 and in the Bibliography references of this chapter. The current distribution is also changed by mutual coupling to other array elements, although for most arrays this has only a minor effect on the pattern. This is discussed later in more detail. A few other important facts follow.

1) If there is no loss, the field from even an infinitesimally short radiator is less than ½ dB weaker than the field from a half-wave dipole or quarter-wave vertical. Without loss, all the supplied power is radiated regardless of the antenna length, so the only factor influencing gain is the slight difference in the patterns of very short and $\lambda/2$ antennas. The small pattern difference arises from different current distributions. A short antenna has a very low radiation resistance, resulting in a heavy current flow over its short length. In the absence of loss, this generates a field strength comparable to that of a longer antenna. Where loss is present—that is, in practical antennas—shorter radiators usually don't do so well, since the low radiation resistance leads to lower efficiency for a given loss resistance. If care is taken, reasonably short antennas can achieve good efficiency.

2) Care has to be taken in calculating the efficiency of folded antennas. (See Chapter 6.) Folding transforms both the radiation resistance and loss resistance by the same factor, so their ratio and therefore the efficiency remains the same. It's easy to show that in a ground-mounted vertical array, folding reduces the current flowing from the feed line to the ground system by a factor of two due to the impedance transformation. However, the folded antenna has an additional connection to ground, which also carries half the original ground current. The result is that the same amount of current flows

into the ground system, whether unfolded or folded, resulting in the same ground system loss. Analyses purporting to show otherwise invariably transform the radiation resistance but neglect to also transform the loss resistance and reach an incorrect conclusion.

3) The current flowing in an element with a given power input can be increased or decreased by mutual coupling to other elements. The effect is equivalent to changing the element radiation resistance. Mutual coupling is sometimes thought of as a minor effect, but often it is not minor!

Field Reinforcement and Cancellation

The mechanism by which phased arrays produce gain, and the role of mutual coupling in determining gain, were covered earlier in this chapter. One important point that can't be emphasized enough is that all antennas must abide by the law of *conservation of energy*. No antenna can radiate more power than supplied to it. The total amount of power it radiates is the amount it's supplied, less the amount lost as heat. This is true of all antennas, from the smallest "rubber ducky" to the most gigantic array.

Gain

Gain is strictly a relative measure, so the term is completely meaningless unless accompanied by a statement of just what it is relative to. One useful measure for phased array gain is *gain relative to a single similar element*. This is the increase in signal strength that would be obtained by replacing a single element by an array made from elements just like it. In some instances, such as investigating what happens to array performance when *all* elements become more lossy, it's useful to state gain relative to a more absolute, although unattainable standard: a lossless element.

And the most universal reference for gain is another unattainable standard, the *isotropic radiator*. This fictional antenna radiates absolutely equally in all directions. It's very useful because the field strength resulting from any power input is readily calculated, so if the gain relative to this standard is known, the field strength is also known for any radiated power. Gain relative to this reference is referred to as dBi, and it's the standard used by most modeling programs including *EZNEC-ARRL*. To find the gain of an array relative to a single element or other reference antenna such as a dipole, model both the array and the single element or other reference antenna in the same environment and subtract their dBi gains. Don't rely on some assumption about the gain of a single element—many people assume values that can be very wrong.

Nulls

Pattern nulls are very often more important to users of phased arrays than gain because of their importance in reducing both man-made and natural interference when receiving. Consequently, a good deal of emphasis is, and should be, placed on achieving good pattern nulls. Unfortunately, good nulls are much more difficult to achieve than gain and they are much more sensitive to array and feed-system imperfections.

As an illustration, consider two elements that each produce a field strength of, say, exactly 1 millivolt per meter (mV/m) at some distance many wavelengths from the array. In the direction in which the fields from the elements are in-phase, a total field of 2 mV/m results. In the direction in which they're out-of-phase, zero field results. The ratio of maximum to minimum field strength of this array is 2/0, or infinity.

Now suppose, instead, that one field is 10% high and the other 10% low—1.1 and 0.9 mV/m, respectively. In the forward direction, the field strength is still 2 mV/m, but in the canceling direction, the field will be 0.2 mV/m. The front-to-back ratio has dropped from infinity to 2/0.2, or 20 dB. (Actually, slightly more power is required to redistribute the field strengths this way, so the forward gain is reduced—but by only a small amount, less than 0.1 dB.) For most arrays, unequal fields from the elements have a minor effect on forward gain, but a major effect on pattern nulls. This is illustrated by *EZNEC* Example: Nulls in Appendix A.

Even with perfect current balance, deep nulls aren't assured. **Fig 13** shows the minimum spacing required for total field reinforcement or cancellation. If the element spacing isn't adequate, there may be no direction in which the fields are completely out-of-phase (see curve B of Fig 13). Slight physical and environmental differences between elements will invariably affect null depths, and null depths will also vary with elevation angle.

However, a properly designed and fed array can produce very impressive nulls. The key to producing good nulls, like producing gain, is controlling the strengths and phases of the fields from the elements. Just how to accomplish that is the subject of most of the remainder of this section. But be sure to keep in mind that producing good nulls is generally a much more difficult task than producing approximately the predicted gain.

Fig 13—Minimum element spacing required for total field reinforcement, curve A, or total field cancellation, curve B. Total cancellation results in pattern nulls in one or more directions. Total reinforcement does not necessarily mean there is gain over a single element, as the effects of loss and mutual coupling must also be considered.

Mutual Coupling

Mutual coupling was discussed briefly earlier in this chapter. Because it has an important and profound effect on both the performance and feed system design of phased arrays, it will be covered in greater depth here.

Mutual coupling refers to the effects which the elements in an array have on each other. Mutual coupling can occur intentionally or entirely unintentionally. People with multiple antennas on a small lot (or car top) often discover that a better description of their system is a single antenna with multiple feed points. Current is induced in conductors in various antennas by mutual coupling, causing them to act like parasitic elements, which re-radiate and distort the antenna's pattern. The effects of mutual coupling are present whether or not the elements are driven.

Suppose that two driven elements are many wavelengths from each other. Each has some voltage and current at its feed point. For each element, the ratio of this voltage to current is the element self-impedance. If the elements are brought close to each other, the current in each element will change in magnitude and phase because of coupling with the field from the other element. The field from the first element changes the current in the second. This changes the field from the second, which alters the current in the first, and so forth until an equilibrium condition is reached in which the currents in all elements (hence, their fields) are totally interdependent.

The feed-point impedances of all elements also are changed from their values when far apart, and all are dependent on each other. In a driven array, the changes in feed-point impedances can cause additional changes in element currents, because the operation of many feed systems depends on the element feed-point impedances. Significant mutual coupling occurs at spacings as great as a wavelength or more.

Connecting the elements to a feed system to form a driven array does not eliminate the effects of mutual coupling. In fact, in many driven arrays the mutual coupling has a greater effect on antenna operation than the feed system does. All feed-system designs must account for the impedance changes caused by mutual coupling if the desired current balance and phasing are to be achieved.

Several general statements can be made regarding the effects of mutual coupling on phased-array systems.

1) The resistances and reactances of all elements of an array generally will be substantially different from the values when the elements are isolated (that is, very distant from other elements).

2) If the elements of a two-element array are identical and have equal currents that are in-phase or 180° out-of-phase, the feed-point impedances of the two elements will be equal. But they will be different than for an isolated element. If the two elements are part of a larger array, their impedances can be very different from each other.

3) If the elements of a two-element array have currents that are neither in-phase (0°) nor out-of-phase (180°), their feed-point impedances will not be equal. The difference will be considerable in typical amateur arrays.

4) The feed-point resistances of the elements in a closely spaced, 180° out-of-phase array will be very low, resulting in poor efficiency due to ohmic losses unless care is taken to minimize loss. This is also true for any other closely spaced array with significant predicted gain.

It's essential to realize that this is *not* a minor effect and one that can be overlooked or ignored. See ***EZNEC*** **Example—Mutual Coupling** in Appendix A for an illustration of these phenomena.

Loss Resistance, Mutual Coupling and Antenna Gain

Loss reduces the effects of mutual coupling because the feed-point impedance change resulting from mutual coupling is effectively in series with loss resistance. If the loss is great enough, two important results occur. First, the feed-point impedance becomes independent of the presence of nearby current-carrying elements. This greatly simplifies feed system design—the simple "phasing-line" or hybrid-coupler feed system described below is adequate *provided that all elements are physically identical and the feed point of each element is matched to the Z_0 of the feed line and, if used, the hybrid coupler.*

The impedance matching restrictions are necessary to insure that the phasing line or hybrid coupler performs as expected. Identical elements are needed so that equal element currents will result in equal fields from the elements.

In the absence of mutual coupling effects, the maximum gain of an array of identical elements relative to a single (similarly lossy) element is simply 10 log(N), where N is the number of elements—providing that spacing is adequate for the fields to fully reinforce in some direction. If spacing is less, maximum gain will also be less. Of course, the array gain relative to a single *lossless* element will be very low, most likely a sizeable negative number when expressed in dB. So intentionally introducing loss isn't a wise idea for a transmitting array. It is sometimes an advantageous thing to do for a receiving array, however, as explained in the following section.

High-gain close-spaced arrays, such as the W8JK phased array (see *EZNEC-ARRL* example file **ARRL_W8JK.EZ** and accompanying Antenna Notes file), and most parasitic arrays depend heavily on mutual coupling to achieve their gain. Introduction of any loss to these arrays, which reduces the mutual coupling effects, has a profound effect on the gain. Consequently, parasitic or close-spaced driven arrays often produce disappointing results when made from grounded vertical elements unless each has a fairly elaborate (and therefore very low-loss) ground system.

If you place two low-loss elements very close together and feed them in-phase, mutual coupling reduces the array gain to essentially that of a single element, so there's no advantage to this configuration over a single element. However, if you have a single lossy element, for example a short vertical having a relatively poor ground system, you can improve the gain by up to 3 dB by adding a second, close spaced, element and ground system and feeding the two in-phase. Another

way to look at this technique is that you're putting two equal ground system resistances in parallel, which effectively cuts the loss in half. The gain you can realize in practice depends on such things as the ground system overlap, but it might be a practical way to improve transmitting array performance in some situations.

FEEDING PHASED ARRAYS

The previous section explains why the fields from the elements must be very close to the ratios required by the array design. Since the field strengths are proportional to the currents in the elements, controlling the fields requires controlling the element currents. Since the desired current ratio is 1:1 for virtually all two-element and for most (but not all) larger amateur arrays, special attention is paid to methods of assuring equal element currents. But we will examine other current ratios also.

The Role of Element Currents

The field from a conductor is proportional to the current flowing on it. So if we're to control the relative strengths and phases of the fields from the elements, we have to control their currents. We usually do this by controlling the currents at the element feed points. But because the field from an element depends on the current everywhere along the element, elements having identical feed-point currents will produce different fields if they have different current distributions—that is, if the way the current varies along the lengths of the elements is different.

A previous section explained that mutual coupling alters the current distribution, so in many arrays the current distributions will be different on the elements and consequently the relationship between the overall fields won't be the same as that between the feed-point currents. Fortunately, this effect is relatively minor in thin, $\lambda/4$ monopole or $\lambda/2$ dipole elements. The most common arrays are made from elements in this category, so we can generally get very nearly the desired ratio of fields by effecting the same ratio of feed point currents. Exceptions are detailed immediately below.

Feed-point vs Element Current

For most antennas, environmental factors are likely to cause greater performance anomalies than current distribution differences, and both can be corrected with minor feed system adjustments. The difference between field and feed-point current ratios can become very significant, however, if the elements are very fat and/or close to $\lambda/2$ (monopole) or 1 λ (dipole) long. In those cases, most of the feed systems described here won't produce the desired field ratios without major adjustment or modification, except in the special cases of 2-element arrays with identical elements having feed point currents in-phase or 180° out-of-phase. In those special cases, the element current distributions are the same for the same reason the feed-point impedances are equal. This is explained later in the feed system sections.

To get an idea of just how large an element must be to disturb the pattern of an array with correct feed-point currents,

a two-element cardioid array of quarter wave vertical elements was modeled at 10 MHz. With thin, 0.1-inch diameter elements, the front/back ratio was 35 dB, the very small reverse lobe caused by slightly unequal element current distributions. Increasing the element diameter to 20 inches decreased the front/back ratio to 20 dB. Returning the front/back ratio of the array of 20-inch elements to >35 dB required changing the feed-point current ratio from the nominal value of 1.0 at an angle of 90° to 0.88 at 83°.

The same array was first modeled with 0.1 inch diameter elements, where it has a front/back ratio of 35 dB, then the elements were lengthened. The front/back ratio dropped to 20 dB at an element length of 36 feet, or about 0.37 λ. In that case, adjustment of the feed-point current ratio to about 0.9 at about 83° restored a good front/back ratio.

In the discussion and development which follow, the assumption is made that the fields will be very nearly proportional to the feed-point currents. If the elements are fat or long enough to make this assumption untrue, some adjustment of feed-point current ratio will be necessary to achieve the desired pattern, particularly nulls. Most feed systems can be designed for any current ratio. Modeling will reveal the ratio required for the desired pattern, and then the feed system can be designed accordingly.

COMMON PHASED-ARRAY FEED SYSTEMS

This section will first describe several popular approaches to feeding phased arrays that often don't produce the desired results. It will describe why they don't work as well as hoped. It also briefly discusses systems that could be used, but that often aren't appropriate or optimum for amateur arrays.

This will be followed in the next section by detailed descriptions of array feed systems that *do* produce the predicted element current ratios and array patterns.

The "Phasing-Line" Approach

For an array to produce the desired pattern, the element currents must have the required magnitude and the required phase relationship. As explained above, this can generally be achieved well enough by causing the feed point currents to have that same relationship.

On the surface, this sounds easy—just make sure that the difference in electrical lengths of the feed lines to the elements equals the desired phase angle. Unfortunately, this approach doesn't necessarily achieve the desired result. The first problem is that the phase shift through the line is not equal to its electrical length. The current (or, for that matter, voltage) delay in a transmission line is equal to its electrical length in only a few special cases—cases which don't exist in most amateur arrays! The impedance of an element in an array is frequently very different from the impedance of an isolated element and the impedances of all the elements in an array can be different from each other.

See the *EZNEC Example—Mutual Coupling* in Appen-

dix A for a graphic illustration of the effect of mutual coupling on feed-point impedance. Also look at the Four-Square array example in the **Phased Array Design Examples** section. The array in that example has one element with a *negative* feed-point resistance, if ground loss is low. Without mutual coupling, the resistance of that same element would be about 36 Ω plus ground loss.

Because of mutual coupling, the elements seldom provide a matched load for the element feed lines. The effect of mismatch on phase shift can be seen in **Fig 14**. Observe what happens to the phase of the current and voltage on a line terminated by a purely resistive impedance that is lower than the characteristic impedance of the line (Fig 14A). At a point 45° from the load the current has advanced less than 45°, and the voltage more than 45°. At 90° from the load both are advanced 90°. At 135° the current has advanced more and the voltage less than 135°. This apparent slowing down and speeding up of the current and voltage waves is caused by interference between the forward and reflected waves. It occurs on any line that is not terminated with a pure resistance equal to its characteristic impedance. If the load resistance is greater than the characteristic impedance of the line, as shown in Fig 14B, the voltage and current exchange angles. Adding reactance to the load causes additional phase shift. The *only cases in which the current (or voltage) delay is equal to the electrical length of the line are*

1) When the line is flat; that is, terminated in a purely

resistive load equal to its characteristic impedance;

2) When the line length is an integral number of half wavelengths;

3) When the line length is an odd number of quarter wavelengths and the load is purely resistive; and

4) When other specific lengths are used for specific load impedances.

Just how much phase error can be expected if two feed lines are simply hooked up to form an array? There is no simple answer. Some casually designed feed systems might deliver satisfactory results, but most will not. See the ***EZNEC Example—"Phasing-Line" Feed*** in Appendix A for the typical consequences of using this sort of feed system.

A second problem with simply connecting feed lines of different lengths to the elements is that the lines will change the *magnitudes* of the currents. The magnitude of the current (or voltage) out of a line does not equal the magnitude into that line, except in cases 1, 2 and 4 above. The feed systems presented later in this chapter assure currents that are correct in both magnitude and phase.

The elementary phasing-line approach *will* work in three very special but common situations. If the array consists of only two identical elements and those elements are fed in-phase, mutual coupling will modify the element impedances, but both will be modified exactly the same amount. Consequently, if the two elements are fed through equal-length transmission lines, the lines will transform and delay the currents by the same amount and result in equal, in-phase currents at the element feed points.

Similarly, an array of two identical elements fed 180° out-of-phase will have the same feed-point impedances and can be fed with two lines of any length so long as one line is an electrical half wavelength longer than the other. But this can't be extended to any two elements in a larger array, since mutual coupling to the other elements can result in different feed-point impedances. Methods will be described later which do assure a correct current ratio in this situation.

The third application in which the phasing-line approach works is in receiving arrays where the elements are very short in terms of wavelength and/or very lossy. In either of these cases, mutual coupling between elements is much less than an element's self-impedance. This allows the elements to be individually matched to the feed lines, with no significant change taking place when the elements are formed into an array. Under those conditions, the transmission lines can be matched and the lines used as simple delay lines with easily predictable phase shift and with no transformation of current or voltage magnitude other than cable loss. This is discussed in the later section on receiving antennas.

Many arrays *can* be correctly fed with a feed system consisting of only transmission lines, but the technique requires knowledge of the element feed-point impedances in a correctly fed array. Line lengths can then be computed that provide the correct ratio of currents into those particular load impedances. The line lengths generally differ by amount that's considerably different from the element phase angle

Fig 14—Resultant voltages and currents along a mismatched line. At A, R less than Z_0, and at B, R greater than Z_0.

difference, and appropriate line lengths can't always be found for all arrays. This technique is described more fully in the **"The Simplest Phased Array Feed System—That Works"** section later in the chapter and illustrated in the examples in **Phased Array Design Examples**.

The Wilkinson Divider

The *Wilkinson divider*, sometimes called the *Wilkinson power divider*, was once heavily promoted as a means to distribute power among the elements of a phased array. While it's a very useful device for other purposes, it won't produce the desired current ratios in antenna elements. In most phased arrays, element feed-point resistances are different and therefore require different amounts of power to achieve the desired equal magnitude currents. (See the section on mutual coupling above.) A Wilkinson divider is intended to deliver equal powers, not currents, to multiple loads. And it won't even do that when the load impedances are different.

The Hybrid Coupler

Hybrid couplers are promoted as solving the problem of achieving equal magnitude currents with a 90° phase difference between elements. Unfortunately, they provide equal magnitude, quadrature (90° phased) currents only when the load impedances are equal and correct. And this simply isn't true of arrays with quadrature-fed elements, except for arrays consisting of short and/or lossy elements, usually suitable only for receiving. In those arrays, the hybrid coupler can be useful for the same reasons as the phasing-line approach, discussed in an earlier section.

At the time of this writing, hybrid couplers are being used in a popular commercial product for phasing at least one type of array. Reports are that it works satisfactorily. However, this shouldn't be taken as proof that the hybrid coupler forces equal magnitude 90° phased currents in loads of arbitrary impedances. No passive network, including the hybrid coupler, is capable of doing that. See **The "Magic Bullet"** below for more information.

Large Array Feed Systems

The author once worked on a radar system where the transmit array consisted of over 5,000 separate dipole elements and the receive array over 4,000 pairs of crossed dipoles, all over a metal reflecting plane, which was the sloping side of a 140 foot high building. In such large arrays, each element is in essentially the same environment as every other element except near the array edges, so almost all elements have very nearly the same feed-point impedance. While producing the phase shifts and magnitude tapers is a considerable mathematical challenge, the problem of unequal element feed-point impedances can largely be ignored. Consequently, feed methods for these large arrays are generally not suitable for typical amateur arrays of a few elements.

The Broadcast Approach

Networks can be designed to transform the element base impedances from their values in an excited array to, say, 50 Ω resistive. Then another network can be inserted at the junction of the feed lines to properly divide the power among the elements (not necessarily equally!). And finally, additional networks must be added to correct for the phase shifts and magnitude transformations of the other networks. This general approach is used by the broadcast industry, in installations that are typically adjusted only once for a particular frequency and pattern.

Although this technique can be used to correctly feed any type of array, design is difficult and adjustment is tedious, since all adjustments interact. When the relative currents and phasings are adjusted, the feed-point impedances change, which in turn affect the element currents and phasings, and so on. A further disadvantage of using this method is that switching the array direction is generally impossible. Information on applying this technique to amateur arrays can be found in Paul Lee's book, listed in the Bibliography.

The "Magic Bullet"

For about 15 years prior to this writing, this *Antenna Book* section has contained a specification for a hypothetical passive circuit that would provide equal-magnitude, 90° phased currents into two loads without respect to the load impedances. This would be a circuit to which we could connect any two elements and guarantee that they'd have exactly the correct currents.

Along with the specifcation was a request that any person knowing of such a circuit would contact the author (Roy Lewallen, W7EL) or the book editors. During this time, only a single response was received, in 1996. It was from Kevin Schmidt, W9CF, who has formulated a mathematical proof that such a circuit—in fact, one resulting in any relative phase other than 0° or 180°—*cannot exist* if restricted to reciprocal elements. (That is, it can't exist unless directional components such as ferrite circulators are used.) This means that, in order to design a network to feed elements at any other phase angle other than 0 or 180°, we *must* know the impedance of at least one element, and correct feed system operation depends on that impedance. There's no way around this requirement. At the time of this writing, Schmidt's proof can be found at **fermi.la.asu.edu/w9cf/articles/magic/index.html**.

RECOMMENDED FEED METHODS FOR AMATEUR ARRAYS

The following feed methods are able to produce element feed-point currents having a desired magnitude and phase relationship, resulting in desirable and predictable patterns. Most methods require knowing the feed-point impedance of one or more array elements *when the array element currents are the correct values*. This isn't possible to measure directly, because if the element currents were correct, the feed system would already be working properly and no further design would be necessary.

By far the easiest way to get this information, if possible, is by computer modeling. Modeling programs such as *EZNEC-ARRL* (included on the CD in the back of this book)

allow you to construct an ideal array with perfect element currents, then look at the resulting feed-point impedances. Because of its simplicity and versatility, this approach is highly recommended and it's the one used for the array design examples in this chapter.

Some feed systems allow adjustment, so even an approximate result provides an adequate starting point on which to base the feed-system design. There are several other alternatives to computer modeling. One is to first eliminate the effects of coupling of the element to be measured from all other elements, usually by open circuiting the feed points of the other elements. Then the feed-point impedance of the element is measured. Next, the impedance change due to mutual coupling from all other elements has to be calculated, based on the intended currents in the other elements, their lengths and their distances from the element being measured. Mutual impedance (which is not the same as the impedance *change* due to mutual coupling) between each pair of elements must be known for this calculation and it can be determined by measurement, calculation or from a graph.

The latter two methods are possible only for the simplest element types and measurement is very difficult to do accurately because it involves resolving very small differences between two relatively large values. Accuracy of a calculated result will be reduced if any elements are relatively fat (that is, they have a large diameter, because this impacts the current distribution) or they aren't perfectly straight and parallel.

So the only situations where you're likely to get good results from approaches other than modeling are the very easiest ones to model! And modeling allows determination of the feed-point impedances of many antennas that areimpossible to calculate by manual or graphical methods. Therefore, the manual approach isn't discussed or used here. Appendix B, on the CD, contains equations and manual techniques from previous editions of *The ARRL Antenna Book*, for those who are interested. You can also find a great deal of additional information in many of the texts listed in the Bibliography, particularly Jasik and Johnson.

Current Forcing with λ/4 Lines—Elements In-Phase or 180° Out-of-Phase

The feed method introduced here has been used in its simplest form to feed television receiving antennas and other arrays, as presented by Jasik, pages 2-12 and 24-10 or Johnson, on his page 2-14. However, until first presented in *The ARRL Antenna Book*, this feed method was not widely applied to amateur arrays.

The method takes advantage of an interesting property of λ/4 transmission lines. (All references to lengths of lines are electrical length and lines are assumed to have negligible loss.) See **Fig 15**. The magnitude of the *current out* of a λ/4 transmission line is equal to the *input voltage* divided by the characteristic impedance of the line. This is independent of the load impedance. In addition, the phase of the output current lags the phase of the input voltage by 90°, also independent of the load impedance. These properties can be

Fig 15—A useful property of λ/4 transmission lines; see text. This property is utilized in the "current-forcing" method of feeding an array of coupled elements.

used to advantage in feeding arrays with certain phase angles between elements.

If any number of loads are connected to a common driving point through λ/4 lines of equal impedance, the currents in the loads will be *forced* to be equal and in-phase, regardless of the load impedances. So any number of in-phase elements can be correctly fed using this method, regardless of how their impedances might have been changed by mutual coupling. Arrays that require unequal currents can be fed through λ/4 lines of unequal impedances to achieve other current ratios.

The properties of λ/2 lines also are useful. Since the current out of a λ/2 line equals the input current shifted 180°, regardless of the load impedance, any number of half wavelengths of line may be added to the basic λ/4, and the current and phase forcing property will be preserved. For example, if one element is fed through a λ/4 line and another element is fed from the same point through a 3λ/4 line of the same characteristic impedance, the currents in the two elements will be forced to be equal in magnitude and 180° out-of-phase, regardless of the feed-point impedances of the elements.

If an array of two, and only two, identical elements is fed in-phase or 180° out-of-phase with equal magnitude currents, both elements have the same feed-point impedance. The reason is that each element sees exactly the same thing when looking at the other. In an in-phase array, each sees another element with an identical current; in an out-of-phase array, each sees another element with an equal magnitude current that's 180° out-of-phase, the same distance away in both cases. This isn't true in something like a 90° fed array, where one element sees another with a current leading its current by 90°, while the other sees another element with a lagging current.

With arrays fed in-phase or 180° out-of-phase, feeding the elements through equal lengths of feed line (in-phase) or lengths differing by 180° (out-of-phase) will lead to the correct current magnitude ratio and phase difference, regardless of the line length and regardless of how much the element feed-point impedances depart from the lines' Z_0.

Unless the feed-point impedances equal the line Z_0 or the lines are an integral number of half wavelengths long, the magnitudes of the currents out of the lines will not be equal

to the input magnitudes, and the phase will not be shifted an amount equal to the electrical lengths of the lines. But both lines will produce the same transformation and phase shift because their load impedances are equal, resulting in a properly fed array. In practice, however, feed-point impedances of elements frequently are different even in these arrays, because of such things as different ground systems (for ground mounted vertical elements), proximity to buildings or other antennas, or different heights above ground (for horizontal or elevated vertical elements).

In many larger arrays, two or more elements must be fed either in-phase or out-of-phase with equal currents, but coupling to other elements can cause their impedances to change unequally—sometimes extremely so. Using the current-forcing method allows the feed system designer to ignore all these effects, while guaranteeing equal and correctly phased currents in any combination and number of 0° and 180° fed elements.

This method is used to develop feed systems for the Four Square and 4-element rectangular arrays in the **Practical Array Design** section. The front and rear elements of a Four-Square antenna provide a good example of elements having very different feed-point impedances that are forced to have equal out-of-phase currents.

"The Simplest Phased Array Feed System— That Works"

This is the title of an article in *The ARRL Antenna Compendium*, *Vol 2*, which describes how arrays can be fed with a feed system consisting of only transmission lines. (The article is available for viewing at **eznec.com/Amateur/Articles/Simpfeed.pdf** and is also on the CD included in the back of this book, along with the program *Arrayfeed1*, which solves the equations presented in the article.)

As explained earlier in the Phasing Line section, this method requires knowing what the element feed-point impedances will be in a correctly fed array. Feed-line lengths can then be computed, for most but not all arrays. These lengths will produce the desired current ratio in array elements that do present those feed-point impedances. If you know the load impedances connected to transmission lines whose inputs are connected to a common source, it's simple to calculate the resulting load currents for any transmission line lengths. However, the reverse problem is much more difficult; that is, given the load impedances and desired currents to calculate the required cable lengths.

One way to solve the problem is to choose some feed-line lengths, solve for the currents, examine the answer, adjust the feed-line lengths, and try again until the desired currents are obtained. The author used this iterative approach, using first a programmable calculator and later a computer, for some time before developing a direct way of solving for the transmission-line lengths. The direct solution method is described briefly in the *Compendium* article.

Fig 16 shows the basic so-called "simplest" system applied to a two element array. Although it resembles an

Fig 16—"Simplest" feed system for 2-element array. No matching or phasing network is used here, only transmission lines.

elementary phasing-line system as described earlier, the critical difference is that the lengths of Lines 1 and 2 are calculated to provide the correct current relative magnitude transformation and phase shift when terminated with the actual feed-point impedances.

The advantage to using this "simplest" feed system is indeed its simplicity. It's no more complicated than the elementary phasing-line approach but actually works as planned. The disadvantage over some other methods is that there's no convenient adjustment to compensate for environment factors, array imperfections or inaccurately known feed-point impedances.

Also, while unusual, it's possible that no suitable feedline lengths can be found for some arrays, or at least none with practical feed-line characteristic impedances. The difference in electrical feed-line lengths almost never equals the difference in phase angles between element currents. This is because of the different line delays resulting from different feed-point impedances.

Program *Arrayfeed1*, included on the CD included with this book, can do the calculations for any two elements (alone or in a larger array), a Four-Square array or a rectangular array in which two in-phase elements are driven at any current magnitude and phase relative to the other two in-phase elements. These possibilities cover a large number of common arrays.

Arrayfeed1 can also be applied to other types of arrays

using the method described in the **Feeding Larger Arrays** section in Appendix B (on the CD). The required knowledge of element feed-point impedances in a correctly fed array can be obtained using *EZNEC-ARRL*, also included on the CD. Examples of the design of a "simplest" feed system for several different arrays using *EZNEC-ARRL* and *Arrayfeed1* can be found in the **Phased Array Design Examples** section.

When a solution is possible for a given choice of line characteristic impedances, a second solution with different lengths is always available. See the comments in the introductory part of the **Phased Arrray Design Examples** section about choosing the solution to use.

An Adjustable L-Network Feed System

Adjustment of the current ratio of any two elements requires varying two independent quantities; for example the magnitude and phase of the current ratio. Two degrees of freedom—adjustments that are at least partially independent—are required. The "simplest" all-transmission line feed system described earlier adjusts the lengths of the two transmission lines to achieve the correct ratio.

But if the antenna characteristics aren't well known—for example, if the ground resistance isn't known even approximately—then the initial "simplest" design won't be optimum and adjustment can be difficult and tedious. The current-forcing method produces correct currents independently of the element characteristics, so it doesn't require adjustment as long as the elements are identical. But it's suitable only for feeding elements in-phase or 180° out-of-phase and a few fixed current-magnitude ratios.

The addition of a simple network as shown in **Fig 17** allows you to easily adjust feeding of element pairs at other relative phase angles and/or magnitude ratios. Any desired current ratio (magnitude and phase) can be obtained with two elements fed with any lengths of wire, equal or unequal, by adding a network.

However, calculations for the general case are complex. The problem becomes much simpler if the transmission lines are restricted to lengths of odd multiples of $\lambda/4$, forming a modified "forcing" system that includes an added network. There are at least three additional advantages of this scheme. One is that a $\lambda/4$ line is easy to measure, even if the velocity factor isn't known. This is described in the **Practical Aspects of Phased Array Design** section.

Second is that the feed system becomes completely insensitive to the feed-point impedance of one of the two elements. And the third is that the transmission lines of "forcing" systems feeding groups of elements in larger arrays can be used in place of the normal $\lambda/4$ lines. This greatly simplifies both the design of feed systems for larger arrays and the feed systems themselves. Note that both lines can be changed to $3\lambda/4$ if necessary to span the physical distance between elements, but *both* lines must be the same $3\lambda/4$ length.

This basic feed method can be used for any pair of elements, or for two groups of elements having forced equal currents. (See **Feeding Four Element and Larger Arrays**

Fig 17— The addition of a simple L-network to Fig 16 allows you to easily adjust feeding of element pairs at other relative phase angles and/or magnitude ratios.

below.) Many networks can accomplish the desired function, but a simple L network is adequate for most feed systems. The network can be designed to produce a phase lead or phase lag. The basic two-element L-network feed system is shown in Fig 17. Many variations of this general method can be used, but the equations, program, and method to be discussed here apply only to the feed system shown.

If the phase angle of I_2/I_1 is negative (element 2 is lagging element 1), the L network will usually resemble a low-pass network (X_{ser} is an inductor and X_{sh} is a capacitor). But if the phase angle is positive (element 2 lagging element 1), the L network will resemble a high-pass network (X_{ser} is a capacitor and X_{sh} is an inductor). However, some current ratios and feed-point impedances could result in both components being inductors or both being capacitors.

If it's desired to maintain symmetry in the feed system, X_{ser} can be divided into two components, each being inserted in series with a transmission line conductor. If X_{ser} is an inductor, the new components will each have half the value of the original X_{ser}, as shown in **Fig 18**. If X_{ser} is a capacitor, each of the new components will be twice the original value of X_{ser}.

Because of the current-forcing properties of $\lambda/4$ lines, we need to make the ratio of *voltages* at the inputs of the lines equal to the desired ratio of *currents* at the output ends of the lines; that is, at the element feed points. The job of the L network is to provide the desired voltage transformation. If the output-to-input voltage ratio of the network is, say, 2.0 at an angle of –60°, then the ratio of element currents (I_2/I_1)

Fig 18—Symmetrical feed system similar to Fig 17, where feed network is split into two symmetrical parts.

will be 2.0 at an angle of –60°. The voltage transformation of the network is affected by the impedance of element 2, but not by the impedance of element 1. So only the impedance of element 2 must be known to design the feed system.

Equations for designing the L network are given in Appendix B, but the program *Arrayfeed1* is included on the CD to make it unnecessary to solve them. The feed-point impedance of the lagging element or group of elements must be known in order to design the network. This can best be determined by modeling the array with *EZNEC-ARRL*. The impedance can be manually calculated for some simple element and array types by using the equations in Appendix B, but those same types of element and array are simple to model.

Examples of the design of L-network feed systems for several different arrays using *EZNEC-ARRL* and *Arrayfeed1* can be found in the **Phased Array Design Examples** section. A similar application of this feed system and a spreadsheet program for calculation was developed by Robye Lahlum, W1MK, and described in *Low-Band DXing* (see the Bibliography). *Arrayfeed1* can be used for the applications of the feed system described in that book if desired.

Additional Considerations
Feeding 4-Element and Larger Arrays

Both the simplest and L-network feed systems described above can be extended to feeding larger arrays having two groups of elements in which all the elements in a group are in-phase or 180° out-of-phase with each other—basically, any group that can be fed with the current-forcing method.

The elements in each group are connected to a common point with λ/4 or 3λ/4 lines to force the currents to be in the correct ratio within the group. Then the "simplest" or L-network feed system can be used to produce the correct phasing between the two groups, just as it does between two individual elements.

Two common arrays that fit this description are the Four Square and the 4-element rectangular array. But more elaborate arrays could be constructed and fed using this method, such as a pair of binomial arrays. (A single binomial array is described in the **Phased Array Design Example** section below.) The *Arrayfeed1* program incorporates additional calculations necessary for designing Four Square and 4-element rectangular arrays. The general procedure for adapting the feed methods to other larger arrays can be found in Appendix B.

What If the Elements Aren't Identical?

Getting the desired pattern requires getting the correct relative magnitude and phase of the *fields* from the elements. If the elements are identical, which we've generally assumed up to this point, then producing currents of the desired magnitude and phase will create the desired fields (neglecting mutual coupling current distribution effects, discussed elsewhere).

But what if the elements aren't identical? Fortunately, the feed systems described here can still be used for any 2-element array and some more complex arrays, provided that the system can be accurately modeled. But a slightly different approach is required than for identical elements.

The first step is to model the array with a current source at the feed point of each element. Next, the magnitudes and phases of the model source currents are varied until the desired pattern is achieved. Then the ratio of feed-point (source) currents is calculated and this value, along with the feed-point impedances reported by the model, are used for the feed system design. The feed system will produce the same ratio of currents as the model, resulting in the same pattern.

In general, this approach won't work with shunt fed towers or gamma-fed elements because of the difficulty of accurately modeling those structures. See **Shunt and Gamma Fed Towers and Elements** for more information.

Shunt and Gamma Fed Towers and Elements

In a shunt, gamma, or similarly fed tower or element, the feed-point current isn't the same as the main current flowing in the element. The ratio between the feed-point current and element current isn't a constant, but depends on a number of factors. The ratio of currents in shunt or gamma fed elements are typically different—often vastly different—from the currents at the feed points. This complicates the design of feed systems for arrays of these elements.

An even more limiting problem is that the feed-point impedances are difficult to determine. The feed-point impedances of one or more elements in a properly fed array must be known in order to design a feed system for anything but

2-element in-phase or 180° out-of-phase arrays.

The only practical way to get this information for a shunt or gamma fed array is by modeling an array having the desired element currents. But Cebik has pointed out ("Two Limitations of NEC-4"—see the Bibliography) that many common antenna analysis programs, including *EZNEC-ARRL*, have difficulty accurately modeling folded dipoles with unequal diameter wires. The same problem applies to shunt and gamma-fed elements when the element diameter is significantly different from the diameter of the shunt or gamma feed wire. Without accurate feed-point impedances, feed systems can't be designed to work without adjustment. It might be possible to get reasonably accurate results from a *MININEC*-based modeling program, but there are a number of issues which must be given great care when using one. (See Lewallen, "*MININEC*—The Other Edge of the Sword," listed in the Bibliography.)

If such a *MININEC* program is available, you would have to model the complete array including feed system, with sources at the normal feed points in the shunt or gamma wires. Next, you would have to adjust the magnitudes and phases of the sources to produce the desired pattern. The reported source impedances and currents would be the ones you would use to design the feed system. It's likely that some adjustment would be necessary, so an adjustable system such as the L-network feed system described later would be best.

Loading, Matching and Other Networks

Adding a component such as a loading inductor in series with an element or element feed point won't change the ratio of element current to feed-point current. As a result, a feed system designed to produce a particular ratio of element currents will still function properly if the elements contain series components. The extra feed-point impedance introduced by the loading component(s) must be considered when designing the feed system, however. Similarly, end or top loading won't alter the relationship between feed-point and element current, provided that the current distribution in the elements is essentially the same. (See **Feed-point vs Element Current** in a previous section.)

However, insertion of any *shunt* component, or a network containing a shunt component, *will* alter the relationship between feed-point and element current because it will divert part of the feed-line current that would otherwise flow into the antenna. As a result, a feed system designed to deliver correct currents at the feed points will produce incorrect element currents and therefore an incorrect pattern. Therefore, any components or networks other than a series loading component should be avoided at any place in the feed system on the antenna side of the point at which the feed system splits to go to the various elements.

There are a few exceptions to this rule. If the feed-point impedances of the elements when in the excited array are equal, then identical networks with or without shunt components can be put at the feed points of the elements and the proper element current ratio maintained—so long as the feed system is designed to deliver the proper feed-point current ratio with the networks in place. Equal element impedances occur in arrays having only two identical elements fed in-phase or 180° out-of-phase, or arrays of any number of elements where the elements are electrically short and/or very lossy.

Baluns in Phased Arrays

For purposes of achieving the correct array pattern, baluns aren't usually required when feeding grounded vertical elements with coaxial cable feed lines. However, a balun might be desirable if current induced onto the outside of the feed line by mutual coupling to the elements is causing RF in the shack. And with arrays of dipole or other elevated elements, baluns can be important to achieve the proper element current ratio, as explained below.

First, however, the general rules for using baluns in phased arrays will be stated. Here, "main feed line" means the feedline going from the transmitter or receiver to the common point where the system splits to feed the various elements. "Phasing-system lines" means any transmission lines between that common point and any element. The rules:

•**Rule 1:** A balun or baluns (more specifically, a current, sometimes called a choke balun) should be used as necessary to suppress unbalanced current on the main feed line. This usually isn't required when feeding grounded elements with coaxial feed line from an unbalanced rig or tuner. Unbalanced current can occur on either coax or parallel-conductor line.

"Baluns: What They Do and How They Do It", listed in the Bibliography, describes conducted-imbalance (common-mode) currents. Imbalance can also be caused by mutual coupling to the array elements. Common-mode currents have at least two undesirable effects on array performance. First, the imbalance current can flow from the main feed line to the phasing system lines, not necessarily splitting in the right proportion to maintain the correct element current ratio. This can affect the array pattern. In practice, however, this effect is likely to be small unless the common-mode current is unusually large. Even a small common-mode current, however, results in main feed-line radiation, and even a small amount of radiation can significantly degrade array pattern nulls. Any type of current balun can be used on the main feed line, at any place along the line, without any effect on the array pattern except to the extent that it reduces common mode current.

•**Rule 2:** No balun or any other component or network should be inserted in any phasing system line that will alter the line length or characteristic impedance. This means that baluns in phasing system lines must be of a type made from the phasing line itself. Options are the W2DU type balun, consisting of ferrite cores placed along the outside of the feed line; an air-core balun made by winding part of the line into an approximately self-resonant or otherwise high-impedance coil; or winding part of the line onto a ferrite core or rod to make a several-turn winding. When coaxial cable is used, the feed system characteristics are dictated by the inside of the cable. Any cores or winding of the outside prevents common-

mode current on the outside, but otherwise have no effect on the phasing performance. This rule applies equally to parallel wire line, where the balun affects only common-mode current (equivalent to current on the outside of coax) while the phasing performance depends on differential mode current (equivalent to the current on the inside of coax).

Baluns are important when feeding dipole or other elevated arrays, unless a fully balanced tuner is used. This is because common-mode current represents a diversion of some of the current that should be going to the array elements. The presence of common-mode current means that the element currents are being altered from the desired ratio and therefore the pattern won't as intended. A balun should be placed wherever a path for current exists other than along a parallel-line conductor or on the inside of a coaxial line. Such a path exists, for example, where a coaxial cable connects to a dipole, as shown in Fig 1 of the balun article referenced above. Or a path can exist where a parallel-conductor transmission line connects to an unbalanced tuner or to a coaxial line, as shown in Fig 2 of that article. In both those cases, a path exists for a common-mode current to flow on the outside of the coax cable. A balun creates a high impedance to this current, thereby reducing its magnitude. But remember that all baluns must conform to the rules above.

Fig19 shows recommended balun locations for a coax-fed dipole array using an L-network feed system.

Receiving Arrays

While it might not be entirely intuitive, an array designed for a particular gain and pattern for transmitting that considers mutual coupling, element currents, field reinforcement and cancellation, and so forth, will perform exactly the same when receiving. So a receiving array can be designed by approaching the problem as though the array were to be used for transmitting.

However, at HF and below, the system requirements for transmitting and receiving antennas are different, so receiving-only arrays can be designed that aren't suitable for transmitting but are perfectly adequate for receiving in that frequency range. The reason, described in more detail in Chapter 13 of this book, is that at HF and below atmospheric noise is typically much greater than a receiver's internally generated noise. Lowering a receiving antenna's gain and efficiency reduces the signal and atmospheric noise both by the same factor. Because the overall noise is for practical purposes all atmospheric noise, the signal/noise ratio isn't

Fig 19—Adding choke baluns to a two-dipole feed system to get rid of common-mode currents radiated onto the coax shields.

affected by antenna efficiency.

Of course, a point can be reached where the atmospheric noise is so reduced by inefficiency that the receiver itself becomes the dominant source of noise, but this typically doesn't happen until the antenna is extremely inefficient. When transmitting, reduced efficiency lowers the transmitted signal, but it has no effect on the receiving station's noise. So reduced efficiency of a transmitting antenna results in a reduced signal/noise ratio at the receiving end, and consequently should be avoided.

Mutual coupling effects can be minimized by increasing the loss (and therefore reducing the efficiency) of the elements, or by reducing the element sizes to a small fraction of a wavelength. Doing the second without the first isn't usually a good idea because the feed-point impedance tends to change rapidly with frequency for very small elements, making an antenna that works well over only a narrow bandwidth. But increasing loss broadens the bandwidth, even for small elements, as well as reducing mutual coupling effects. So this approach is often taken for designing a receiving-only array. With mutual coupling effects minimized because of loss, feed-system design becomes relatively simple, provided a few simple rules are followed. See **Loss Resistance, Mutual Coupling, and Antenna Gain**, above.

Phased Array Design Examples

This section, also written by Roy Lewallen, W7EL, presents examples of feed-system design for several kinds of array using the design principles given in previous sections. All but the last example array are assumed to be made of $\lambda/4$ vertical elements. The last example is for a halfwave-dipole array, which illustrates that exactly the same method can be used for arrays of any shape of elements, including dipole, square (quad) and triangular. Likewise, the methods shown here apply equally well to VHF and UHF arrays. The first example includes more detail than the remaining ones, so you should read it before the others.

General Array Design Considerations

If either the "simplest" feed system (Fig 16) or L-network feed system (Fig 17) is used, the feed-point impedance of one or more elements—*when the array elements all have the correct currents*—must be known. By far the best way to determine this is by modeling. If accurate modeling isn't practical for some reason, an estimation should be made from an approximate model, and you should expect to have to adjust the feed system after building and installing it.

Manual calculation methods for some simple configurations are given in Appendix B (on the CD), but calculation is tedious and, as stated earlier, the configurations for which this method works are the very ones which are easiest to model. *EZNEC-ARRL* (also included on the CD) is used in the following examples to determine feed-point impedance. Space doesn't permit detailed instructions here on creating the models, so they are included in complete form. They should provide a convenient starting point for any variations you might like to try. See the *EZNEC-ARRL* manual (accessed by clicking **Help/Contents** in the main *EZNEC-ARRL* window) for help in using this program.

In the following examples, vertical elements are close to $\lambda/4$ high and dipole elements close to $\lambda/2$, and their lengths have been adjusted for resonance when all other elements are absent or open circuited. There's actually no need in practice to make the elements self-resonant—it's simply used as a convenient reference point for these examples. You'll also find it interesting to see how much reactance is present at the feed points of the elements when in the arrays, knowing that it's very nearly zero when only one element is present.

In any real grounded vertical array, there is ground loss associated with each element. The amount of loss depends on the length and number of ground radials, and on the type and wetness of the ground under and around the antenna. This resistance becomes part of the feed-point resistance, so it must be included in the model used to determine feed-point impedance. The 90° Fed, 90° Spaced Array example below discusses how this is done. **Fig 20** gives resistance values for typical ground systems, based on measurements by Sevick (July 1971 and March 1973 *QST*). The values of feed system components based on Fig 20 will be reasonably close to correct, even if the ground characteristics are

Fig 20—Approximate ground system loss resistance of a resonant $\lambda/4$ ground-mounted vertical element versus the number of radials, based on measurements by Jerry Sevick, W2FMI. Moderate length radials (0.2 to 0.4 λ) were used for the measurements. The exact resistance, especially for only a few radials, will depend on the nature of the soil under the antenna. Add 36 Ω for the approximate feed-point resistance of a thin resonant $\lambda/4$ vertical.

somewhat different than Sevick's.

Feed systems for the design example arrays to follow are based on the resistance values given below.

Number of Radials	Loss Resistance, Ω
4	29
8	18
16	9
Infinite	0

Elevated radial systems also have some ground loss, although it can be considerably less than a system with the same number of buried radials. This loss will be automatically included in the feed-point impedance of a model which includes the elevated radials, so no further estimation is required. Be sure to use Perfect, High-Accuracy ground type when modeling an elevated radial system with *EZNEC-ARRL*. In other *NEC-2* based programs, this might be referred to as Sommerfeld type ground. More information can be found in the *EZNEC-ARRL* manual.

The matter of matching the array for the best SWR on the feed line to the station is not dealt with here, since it's a separate problem from that of the main topic, which is designing feed systems to produce a desired pattern. Some of the simpler arrays provide a match that is close to 50 or 75 Ω, so no further matching is required. However, as shown by program *Arrayfeed1*, many larger arrays present a less favorable impedance for direct connection and will require matching if a low SWR on the main feedline is required. If matching is necessary, the appropriate network should be

placed in the single feed line running to the station. Attempts to improve the match by adjustment of the phasing L network, individual element lengths, matching at the element feed points or individual element feeder lengths will usually ruin the current balance of the array. Program *TLW*, included on the CD, can be used for designing an appropriate matching network. Additional information on impedance matching may be found in Chapters 25 and 26 of this book.

Choosing Arrayfeed1 Solutions

When designing a feed system for a two element array, *Arrayfeed1* program allows you to choose the characteristic impedances of the two transmission lines going to the elements, which don't have to be equal, so you have your choice of more than one solution. However, directional array switching is much more difficult if the lines have different impedances, so in general you should use the same characteristic impedances.

For larger arrays, *Arrayfeed1* requires the feed lines to all elements to have the same impedance. In choosing the transmission line impedance values, usually you can simply use convenient impedances. But in general, you should avoid solutions where component reactance (X) values are vastly different (say, more than three times or less than one third as large) as the line characteristic impedances. Such networks will become more critical to adjust, and both the impedance and pattern will change more rapidly with changes in frequency. You can usually avoid this situation by choosing feed-line impedances that are in the same ballpark as the element feed-point impedances. The last example in the Practical Array Design section illustrates this problem and its solution.

When designing a "simplest" feed system, the most broadbanded and least critical system is usually one where the difference in electrical feed-line lengths is closest to the relative element phase angle. Here, "broadbanded" means that the pattern changes less with frequency, not necessarily that the SWR changes less. However, an array that's broadbanded in the pattern sense is usually also relatively broadbanded with respect to SWR.

Arrayfeed1 reports the impedance seen at the main array feed point. While it might be tempting to choose the solution producing the lowest SWR on the main feedline, you'll end up with a less critical and more broadbanded system if you base your choice on the criteria given above, and provide separate impedance matching at the array's main feed point when necessary.

90° Fed, 90° Spaced Vertical Array

This example illustrates the design of both "simplest" and L-network feed systems for a 2-element, 90° spaced and fed vertical array. The first task when using either feed system is to determine the feed-point impedances of the elements when placed in an array having the desired element currents. The "simplest" feed system method requires knowledge of both element impedances, while the L-network system

requires you to know only one. Actually, it's equally easy to determine both as it is to find just one, using *EZNEC-ARRL*. (Appendix B contains equations for those interested in manual methods or for more insight as to how the impedances come about.) The first step is to specify the antenna we want. For this example, we'll specify:

- Frequency: 7.15 MHz.
- Two identical, one inch (2.54 cm) diameter, 33 feet (10.06 meter) long elements spaced 90 electrical degrees, with element currents equal in magnitude and 90° apart in-phase.
- 8 buried radial wires, 0.3 λ long, under each element.

A model of this antenna has been created and furnished with *EZNEC-ARRL*. So the next step is to start *EZNEC-ARRL*, click the **Open** button, enter **ARRL_Cardioid_Example** in the text box (or double-click it in the file list) to open example file **ARRL_Cardioid_Example.EZ**.

This *EZNEC* example model uses a *MININEC*-type ground, which is the same as perfect ground when calculating antenna currents and impedances. A real antenna would have some additional resistive loss due to the finite conductivity of the ground system. The only way to model a buried radial ground system with an *NEC-2* based program like *EZNEC* is to create radial wires just above the ground (using the Real, High-Accuracy ground type), because *NEC-2* can't handle buried conductors.

This provides only a moderate approximation of a buried system. Another way to estimate ground-system resistance is to measure the feed-point impedance of a single element, then subtract from that the resistance reported for a model of that element over perfect (or *MININEC*-type) ground. For most uses, however, an adequate approximation can be made by simply referring to the graph of Fig 20. As stated previously, the feed system design depends on the feed-point impedances of the elements, which in turn depend on the ground system resistance. So the ground system resistance must be known, approximately anyway, before designing the feed system. At the end of this example we'll investigate the effect of changes in the ground system or errors in estimating the resistance on the pattern.

For 8 radials, Fig 20 shows the ground system resistance to be about 18 Ω. This is included in the example model as a simple resistive load at the feed point of each element. Click the **Src Dat** button to see the feed-point impedances of the two elements. In this model, Source 1 is at the base of Wire 1 (element 1), and Source 2 is at the base of Wire 2 (element 2). Notice in the **Source Data** display that the Source 1 current has been specified at 1 amp at 0°, and Source 2 is 1 amp at –90°. So the Source 2 element is the lagging element. You should see impedances of 37.53 – j19.1 Ω for element 1 and 68.97 + j18.5 Ω for element 2. These are the feed-point impedances resulting when the array is ideally fed, with equal magnitude and 90° phased currents. Record these values for use in *Arrayfeed1*.

Click the **FF Plot** button to generate a plot of the azimuth pattern at an elevation angle of 10°. In the 2D Plot Window,

open the **File** menu and select **Save Trace As**. Enter **Cardioid_Ideal Feed** in the **File Name** box, then click **Save**. This saves the cardioid pattern plot so you can compare it later to the pattern you get with the transmission line feed system.

Now it's time to design the feed system. Refer to the appropriate subheading below for the design of each of the two kinds of feed systems. Both systems use program *Arrayfeed1* program.

"Simplest" (Transmission Line Only) Feed System

Start *Arrayfeed1*. In the **Array Type** frame, select **Two Element**. In Feed System Type, select **"Simplest."** In the **Inputs** frame, enter the following values:

Frequency MHz = 7.15; Feed-point impedances – Leading Element: R ohms = 37.53, X ohms = −19.1; Lagging Element: R ohms = 68.97, X ohms = 18.5 (these are the element R and X values from *EZNEC-ARRL*). We'll be discussing the array input impedance, so check the **Calc Zin** box near the lower left corner of the main window if it's not already checked.

We're free to choose any transmission-line characteristic impedances we want, so long as we can get cables with those impedances. And the two cables don't have to have the same characteristic impedances. Each choice will lead to a different set of solutions. But sometimes a solution isn't possible, which then requires choosing different line impedances. Let's try 50 Ω for both lines. Enter **50** in both **Z0** boxes.

Finally, enter **1** for the lagging:leading **I Mag**, and **–90** for the **Phase**. Click **Find Solutions**. The result is no solution! So enter **75** into both the line impedance boxes and click **Find Solutions** again. You should now see two sets of results in the **Solutions** frame, electrical lengths of 68.80° and 156.03° for the first solution and 131.69° and 185.00° for the second. (Notice that the difference in length between the two lines isn't 90° for either solution, although the first solution is quite close. It's normal for the feed-line length difference to be different than the phase difference, due to the unequal element feed-point impedances caused by mutual coupling.)

The solution with a line length difference closest to the element phase difference is usually preferable. Also, all else being equal, the solution with shortest lines is better providing that the lines will physically reach the elements. This is because the current magnitude and phase will change less with frequency than for a longer-length solution. However, there might be some cases where the change with frequency luckily compensates for the changing electrical distance between elements, so it's not a bad idea to model both solutions unless you plan on using the antenna over only a narrow frequency range.

In this case, the first solution looks best in all respects. The sum of the two lines in the first solution is about 225 electrical degrees. Assuming the lines have a velocity factor of 0.66, the total length of the lines will be more than 148 physical degrees. Since our two elements are spaced 90 physical degrees apart, the lines will comfortably reach. If they

didn't, we could either use the second solution's lengths, use cable with a higher velocity factor or add a half wavelength to both the line lengths in the first solution.

The impedance **Zin** shown by *Arrayfeed1* is the impedance at the input to the feed system, so it's the impedance that will be seen by the main feed line. The second solution provides nearly a perfect match for a 50-Ω transmission line. But the first solution is good for nearly all applications. Also a 50-Ω line connected to the first solution's feed system would have an SWR of only 1.65:1, which wouldn't require any matching under most circumstances. Normal line loss would reduce the SWR even more at the transmitter end of the feed coax.

To find the required physical line lengths, enter the cable velocity factor and make your choice of units in the **Physical Lengths** frame. The design is now complete; all you have to do is cut two lines to the specified lengths and connect one from a common feed point to each element as shown in Fig 16, or the screen capture from *Arrayfeed1* shown in **Fig 21**.

Next, we'll design an L-network feed system for the same array.

L Network Feed System

In *Arrayfeed1*, select **L Network** in the **Feed System Type** frame. The program doesn't need to know the leading element impedance to calculate the L-network values, but it does need it to calculate the array input impedance. If you want to know the impedance, check the **Zin** box at the lower left corner of the main window, otherwise you can uncheck it and the input box for the leading element Z will disappear. The values from the "Simplest" analysis should still be present in the appropriate boxes; if not, refer to the "Simplest" feed system design above and re-enter the values. Again, we'll use 75 Ω for the line impedances, since that gave us a

ANT0992

Fig 21—Screen capture from *Arrayfeed1* program for "Simplest" 2-element phased array shown in Fig 16 and whose feed-point impedances are modeled by *EZNEC-ARRL*.

ANT0993

Fig 22—Screen capture from *Arrayfeed1* program for L-network feed system using "current-forcing" properties of λ/4 feed lines.

solution for the "Simplest" feed system. This feed system is more versatile, though, so we could use 50-Ω lines with this feed system if desired.

Click **Find Solution** and see the results in the **Solution** frame. See screen capture in **Fig 22**. With 75-Ω lines, the L network consists of a series inductor of 1.815 µH and a shunt capacitor of 199.7 pF, connected as shown in the diagram in the left part of the program window. To find the physical length of the λ/4 lines, enter the velocity factor and choice of units in the **Physical Lengths** frame.

The main feed-point impedance of 31.37 + *j*25.94 Ω would result in about a 2.2:1 SWR on a 50-Ω feed line, which would be acceptable for many applications. It could easily be reduced to 1.6:1 by the simple addition of a series capacitor of 25.94 Ω reactance (858 pF) at the main feed point or, of course, reduced to 1:1 with a simple L network or other matching system designed with the *TLW* program.

Pattern Verification and Effect of Loss Resistance— "Simplest" System

EZNEC-ARRL doesn't have the capability to model an L-network, so *EZNEC-ARRL* verification of the pattern and the effect of various modifications can be done only for the "simplest" feed system.

EZNEC model **ARRL_Cardioid_TL_Example.EZ** has been created to model the "simplest" feed system just designed. Open it with *EZNEC-ARRL*. In the View Antenna Display, you can see the transmission lines connecting to the source midway between the antennas. In *EZNEC*, the physical locations of the ends of transmission line models don't have to be the same as the physical locations, so the view isn't a precise representation of what the actual setup would look like. (You can find more about this in **ARRL_Cardioid_TL_Example.txt**, the Antenna Notes file that accompanies

example file **ARRL_Cardioid_TL_Example.EZ**.)

Click **FF Plot** to generate a 2D pattern of the antenna. In the 2D Plot Window, open the **File** menu and select **Add Trace**. Select **Cardioid—Ideal Feed** (which you saved earlier) and click **Open**. The added plot overlays perfectly, indicating that the pattern using this feed system is identical to the pattern we got with perfect current sources at each feed point.

To check the feed-point currents, click the **Currents** button. In the resulting table, you can see that **Wire 1 Segment 1** current is 0.56467 A at a phase of –56.73° and **Wire 2 Segment 1** current is 0.56467 A at –146.7°. (If you get the correct phase angles but wrong magnitudes, open the main window **Options** menu, select **Power level**, and make sure the **Absolute V, I sources** box is checked.) The ratio is 1.0000 at an angle of –89.97°, which is within normal error bounds for the desired 1 at –90°.

As a check on *Arrayfeed1*, click the **Src Dat** button to find the impedance seen by the source. This would be the impedance at the main feedline connection in the real array. *EZNEC-ARRL* reports 33.96 + *j*13.11 Ω, very close to the 33.94 + *j*13.13 Ω given by *Arrayfeed1* in Fig 21. Small differences of this order are normal and to be expected. This provides a further check that the *EZNEC-ARRL* model is correctly analyzing the *Arrayfeed1* feed system.

This *EZNEC-ARRL* model uses lossless transmission lines of a fixed physical length rather than a fixed electrical length (number of degrees), so they'll behave like real lines as the frequency is changed. By changing the *EZNEC* frequency and re-running the 2D plot, you can see that the front-to-back ratio degrades at 7.0 and 7.3 MHz. A slight adjustment of one or more line lengths, or a new *Arrayfeed1* solution at a slightly different frequency might produce a better compromise for some uses.

Other things you can try are to evaluate the second *Arrayfeed1* solution, or to try using different line impedances. (Keep the two line impedances equal if you anticipate doing array direction switching.) The effect of varying ground system resistance can also be evaluated by clicking the **Loads** line in the main window and changing the load resistance values. For example, if the ground system resistance were 9 Ω instead of the 18 Ω we have assumed, the front/back ratio would drop from about 32 to about 20 dB. Note that changing the *EZNEC* ground conductivity in this model has no effect on the feed-point current ratio. With a *MININEC* type ground, it's used only for pattern calculation—the ground is assumed perfect during impedance and current calculations, and the only ground system loss resistance in the model is what we've specifically put in as loads.

Not surprisingly, the forward gain is affected very little by changes in frequency or ground system loss. To find the gain relative to a single element, compare the reported dBi gain of **ARRL_Cardioid_Example** with the same model with one of the elements deleted. You'll find it's very close to 3.0 dB. The 90° fed, 90° spaced array is a special case of array where the effects of mutual coupling on the two ele-

ments are opposite and cancel, resulting in the same gain as if mutual coupling didn't exist. But mutual coupling most certainly does exist!

The second solution presented a more favorable main feed-point impedance, so it would be tempting to use that one instead of the first solution. Replacing the feed-line lengths with the second solution lengths to model the second solution shows that the front/back ratio deteriorates more at the band edges when the second solution is used. This might be tolerable if restricted frequency use is anticipated. But it does illustrate that the solution with shorter lines is generally more broadbanded and that the choice of solution shouldn't in general be based on the one giving the most favorable impedance.

A Three-Element Binomial Broadside Array

An array of three in-line elements spaced $\lambda/2$ apart and fed in-phase gives a pattern that is generally bidirectional. If the element currents are equal, the resulting pattern has a forward gain of 5.7 dB (for lossless elements) compared to a single element, but it has substantial side lobes. If the currents are tapered in a binomial coefficient 1:2:1 ratio (twice the current in the center element as in the two end elements), the gain drops slightly to just under 5.3 dB, the main lobes widen and the side lobes disappear.

The array is shown in **Fig 23**, and an *EZNEC-ARRL* model of the antenna over perfect ground to show the ideal pattern is provided as **ARRL_Binomial_Example.EZ**. To obtain a 1:2:1 current ratio in the elements, each end element is fed

through a $3\lambda/4$ line of impedance Z_0. Line lengths of $3\lambda/4$ are chosen because $\lambda/4$ lines will not physically reach. The center element is fed from the same point through two parallel $3\lambda/4$ lines of the same characteristic impedance. This is equivalent to feeding it through a line of impedance $Z_0/2$. The currents are thus forced to be in-phase and to have the correct ratio. **ARRL_Binomial_TL_Example.EZ** is an *EZNEC-ARRL* model that shows this feed system with lossless transmission lines. The reader is encouraged to experiment with this model to see the effect of changes in frequency, the addition of loss resistance (as resistive loads at the element feed points) and other alterations on the array pattern and gain. You should also replace the perfect ground with *MININEC* type of ground to show how radiation patterns over real ground differ from the theoretical perfect-ground pattern.

A "Four Square" Array

Several types of feed system are used for feeding this popular array, and most share a common problem—they don't provide the correct element current ratio—although a number of them produce a workable approximation. The feed systems described here are capable of producing exactly the correct current ratio. The only significant variable is the element feed-point impedances, so the quality of the result depends on your ability to model the feed-point impedances of a correctly fed array. As in the examples above, *EZNEC-ARRL* will be used for that purpose and *Arrayfeed1* for the design of the feed system itself.

In this array (see **Fig 24**), four elements are placed in a square with $\lambda/4$ sides. (A variation of the Four Square uses wider spacing.) The rear and front elements (1 and 4) are 180° out-of-phase with each other. The side elements (2 and 3) are in phase with each other and 90° delayed from the front ele-

Fig 23—Feed system for the three element 1:2:1 binomial array. All feed lines are ¾ electrical wavelength long and have the same characteristic impedance.

Fig 24—Pattern and layout of the four-element Four-Square array. Gain is referenced to a single similar element; add 5.5 dB to the scale values shown.

ment. The magnitudes of the currents in all four elements are equal. The front and rear elements can be forced to be 180° out-of-phase and to have equal currents by using the current-forcing method described earlier. One element is connected to a line that is either λ/4 or 3λ/4 long, the other to a line that is λ/2 longer, and the two lines to a common point.

Likewise, the two side element currents are forced to be equal by connecting them to a common point via λ/4 or 3λ/4 lines. **Fig 25** shows the basic current-forcing system.

If the pattern is to be electrically rotated, it is necessary to bring lines from all four elements to a common location. If solid-polyethylene dielectric coaxial cable, which has a dielectric constant of 0.66, is used, λ/4 lines won't reach the center of the array. So 3λ/4 lines must be used. Alternatively, you can use λ/4 lines with foam or other dielectric having a velocity factor of more than about 0.71 (plus a little extra margin). These will reach to the center. Whatever your choice, three of the lines must be the same length and the fourth must be λ/2 longer.

In this array, the side elements (2 and 3) have equal impedances, but the rear and front (1 and 4) are different from each other, and both are different from the side elements. We

have to know the feed-point impedances of the front, rear and side elements in order to design the "simplest" feed system, but only the side element impedances are needed to design the L-network system. Knowledge of all feed-point impedances is necessary if the array main feedpoint impedance **Zin** is to be calculated. *EZNEC-ARRL* model **4Square_Example.EZ** shows a 40-meter Four Square array with 18 Ω of loss resistance at each element, to approximate an 8-radial per element ground system. (See the cardioid array example above for more information about modeling ground system loss.) Opening the file in *EZNEC-ARRL* and clicking the **Src Dat** button gives the following impedances:

Source 1: $16.4 - j15.85$ Ω
Sources 2 and 3: $57.47 - j19.44$ Ω
Source 4: $77.81 + j54.8$ Ω

It's interesting to note that the resistive part of source 1 is less than the 18 Ω of loss resistance we intentionally added to simulate ground system loss. That means that the element 1 feed-point resistance would be negative if the ground resistance were less than about an ohm and a half. This isn't uncommon in phased arrays and simply means that the element is feeding power *into* the feed system. This power is coming via mutual coupling from the other elements.

"Simplest" (Transmission Line Only) Feed System

To design a "simplest" feed system, start *Arrayfeed1*. In the **Array Type** frame, select **4 Square**, and select **"Simplest"** in the **Feed System Type** frame. In the **Inputs** frame, enter the frequency and the impedances from *EZNEC-ARRL*:

Frequency = 7.15 MHz
Leading Element: R = 16.4, X = −15.85
Side elements: R = 57.47, X = −19.44
Lagging Element: R = 77.81, X = 54.8

We'll try using 50 Ω for all lines, so enter **50** into the next three boxes.

Enter **1** for the lagging:leading I magnitude and **–90** for the phase.

Click **Find Solutions**.

The result is shown in the **Solutions** frame, shown in **Fig 26**. As always when any solution exists, there are two to choose from. The one with the shortest lines is generally preferable, so we'll choose it. For this example, we'll use λ/4 lines with velocity factor of 0.82. So enter **0.82** in the **Velocity Factor** box in the **Physical Lengths** frame, and read the physical lengths from the bottom of that frame. The λ/4 lines (marked in the *Arrayfeed1* diagram with an asterisk) are 28.2 feet, line 1 is 7.483 feet and line 2 is 51.668 feet. The "simplest" feed system is shown in Fig 26, and the complete feed system consists of this connected to the array of Fig 25.

EZNEC-ARRL model **ARRL_4Square_TL_Example.EZ** is simulates the array fed with this system. Comparison of the pattern plot to one from ideal-current model **ARRL_4Square_Example.EZ** and examination of

Fig 25—"Simplest" feed system for the Four-Square array in Fig 24. Grounds and cable shields have been omitted for clarity.

Fig 26—Screen capture from *Arrayfeed1* for "Simplest" feed system for Four Square feed system shown in Fig 25.

Fig 27—L-network setup for Four-Square array in Fig 25, fed with λ/4 (or 3λ/4) current-forcing feed system.

the element currents verify that the feed system is producing the desired pattern and element currents. You can use **ARRL_4Square_Example.EZ** to investigate the effect of frequency change, ground loss and other changes on the array gain and pattern.

L-Network Feed System

To design the L-network feed system, simply change the **Feed System Type** to **L Network** and click **Find Solutions**. The results you should see are a 0.484 μH inductor for the series component X_{ser}, and a 1369.6 pF capacitor for the shunt component X_{sh}. The L-network feed system is shown in **Fig 27**, and the complete feed system consists of this L network connected to the array of Fig 25.

EZNEC-ARRL doesn't have the ability to directly model

Fig 28—Pattern and layout of the four-element rectangular array. Gain is referenced to a single similar element; add 6.8 dB to the scale values shown.

the L network, so it's unable to model the complete system. However, the system has been modeled using the network capability of *EZNEC v.5* and found to work as designed. Arrays have also been built using this feed system and the element currents measured, with exactly the expected results.

This array is more sensitive to adjustment than the 2-element 90° fed, 90° spaced array. Adjustment procedures and a method of remotely switching the direction of this array are described in the **Practical Aspects of Phased Array Design** section that follows.

A 4-Element Rectangular Array

The 4-element rectangule array shown with its pattern in **Fig 28** has appeared numerous times in amateur publications. However, many of the accompanying feed systems fail to deliver currents in the proper amounts and phases to the various elements. The array can be correctly fed using the principles discussed in this chapter and the design methods that follow.

Elements 1 and 2 can be forced to be in-phase and to have equal currents by feeding them through 3λ/4 lines. (As in the binomial and Four Square array examples, 3λ/4 lines are chosen because λ/4 lines won't physically reach.) The currents in elements 3 and 4 can similarly be forced to be equal and in-phase. **Fig 29** shows the "current-forcing" feed system. Elements 3 and 4 are made to have currents of equal magnitude but of 90° phase difference from elements 1 and 2 by use of either a "simplest" all-transmission line feed system or an L-network feed system. Both will be designed in this example.

Multielement Arrays   8-29

Fig 29—"Simplest" feed system for four-element rectangular array, using four equal-length λ/4 (or 3λ/4) cables.

For this array, we have to know the feed-point impedances of two elements (one of each pair) in order to design either type of feed system. *EZNEC-ARRL* model **Rectangular_Example.EZ** shows a 20-meter rectangular array with 18 Ω of loss resistance at each element, again to approximate an 8-radial per element ground system. (See the cardioid array example above for more information about modeling ground system loss.) Open the file in *EZNEC-ARRL* and click the **Src Dat** button to find the following feed-point impedances:

Sources 1 and 2: $21.44 - j21.29$ Ω
Sources 3 and 4: $70.81 - j5.232$ Ω

"Simplest" (Transmission- Line Only) Feed System

To design a "simplest" feed system, start program *Arrayfeed1*. In the **Array Type** frame, select **4 Element Rectangle**, and select **"Simplest"** in the **Feed System Type** frame. In the **Inputs** frame, enter the frequency and the impedances from *EZNEC-ARRL*:

Frequency = 14.15 MHz
Leading Elements R = 21.44, X = –21.29
Lagging Elements R = 70.81, X = –5.232

We'll use 50 Ω for all lines, so enter **50** into the next three boxes.

Enter **1** for the lagging:leading I magnitude and **–90** for the phase.

Click Find Solutions.

The result is "No Solution"—This combination of line impedances can't be used. Several other combinations also

produce this result, but making lines 1 and 2 each 75 Ω and the 3λ/4 lines 50 Ω does produce a solution. Enter **75** into the **Line 1 Z0** and **Line 2 Z0** boxes, and leave **50** in the **Choose Z0 of ¼ or ¾ wavelength lines** box, then click the Find Solutions button. There won't be any problem making lines 1 and 2 reach, so we'll choose the first solution because the lines are shorter. The physical lengths of all the lines are shown in the **Physical Lengths** frame when the velocity factor is entered in the appropriate box. Assuming that we use coax with a velocity factor of 0.66 (and the example frequency of 14.15 MHz), the lengths are:

Line 1: 4.982 feet
Line 2: 20.153 feet
3λ/4 lines (marked with an asterisk in the *Arrayfeed1* diagram): 34.408 feet

The lines are connected following the diagram in the upper left part of the *Arrayfeed1* window. This completes the "simplest" feed system design. *EZNEC-ARRL* model **Rectangular_TL_Example.EZ** simulates an array fed with this system.

Comparison of the pattern plot to one from ideal-current **Rectangular_Example.EZ**, and examination of the element currents verify that the feed system is producing the desired pattern and element currents.

L-Network Feed System

To design the L-network feed system using *Arrayfeed1*, change the **Feed System Type** to **L Network** and click **Find Solutions**. The resulting L-network values are a 0.484 µH inductor for the series component X_{ser} and a 1369.6 pF capacitor for the shunt component X_{sh}.

120° Fed, 60° Spaced Dipole Array

This example shows the design of "simplest" and L network feed systems for a 2-element 20- meter dipole array, rather than a vertical array. No special accommodation is required for the array made from dipoles rather than vertical elements—the same methods can be used regardless of element shape. This example also shows that both the "simplest" and L-network feed systems can readily be applied to elements that use phase angles other than 90°.

Any 2-element array made with identical elements spaced λ/2 or closer and having equal magnitude currents with a relative phase angle of 180° minus the spacing will produce a unidirectional pattern with a good null to the rear. In practice, very close spacings lead to very low feed-point resistances, with consequent losses and very narrowband characteristics. But this 60° spaced array is well within the range of practical realization. File **ARRL_Dipole_Array_Example.EZ** is a model created for this array, with ideal element currents. Open this file in *EZNEC-ARRL* and click **FF Plot** to show the pattern at an elevation angle of 10°. You can save this pattern for later comparison to the pattern with a "simplest" feed system by opening the **File** menu in the **2D Plot** window, selecting **Save Trace As**, entering a name for the trace file and clicking **Save**.

Following the same procedure as in the previous examples, we begin the array design by finding the element feed-point impedances in the ideally fed array using *EZNEC-ARRL* numbers. Having already opened **ARRL_Dipole_Array_Example.EZ**, all that's needed is to click **Src Dat**. The results are:

Leading element (source 1) : 36.16 – j46.05 Ω
Lagging element (source 2) : 49.56 + j51.47 Ω

"Simplest" (Transmission Line Only) Feed System

Select **Two Element** for the **Array Type** in *Arrayfeed1* and **"Simplest"** for the **Feed System Type**. Enter the frequency of 14.15 MHz and enter the element feed-point impedances from *EZNEC-ARRL* into the appropriate boxes in the **Inputs** frame. For line impedances, the section describing the "simplest" feed system recommends against choosing one which is very different from the element feed-point impedances, but for fun let's try 300 Ω for the two lines and see what happens. Enter **300** in the **Line 1 Z0** and **Line 2 Z0** boxes. Finally, enter the **lagging:leading I mag, phase** of **1** for **Mag** and **–120** for **Phase**.

Click **Find Solutions**. For this example we'll assume that TV type twinlead with a velocity factor of 0.8 is being used. So enter **0.8** for the **Velocity Factor** and read the physical line lengths in the **Physical Lengths** frame. A model of the array using the first solution has been created as **ARRL_Dipole_Array_TL_Example.EZ**. Open this file in *EZNEC-ARRL* and click **FF Tab**. You should see that the plot is virtually identical to the one saved earlier from the ideal-current model. Note the gain and front/back ratio or 8.79 dBi and 31.01 dB respectively reported in the data box below the 2D plot.

Don't subtract 2.15 dB to find the gain relative to a single element! This isn't a free-space model, and the gain of a single dipole over ground is much greater than 2.15 dBi. Instead, delete one of the elements in **ARRL_Dipole_Array_Example.EZ** to find the gain of a single element and subtract that value from the array gain. You can use the undo feature or re-open the file to restore the array.

Now, go back to the model with the "simplest" feed system in *EZNEC-ARRL* and change the Frequency to **14.0** MHz. Click **FF Tab** again. The gain has decreased a little, to 8.54 dBi and the front/back ratio has also decreased, to 21.8 dB. At 14.3 MHz, the gain is slightly higher, 9.04 dBi, but the front/back is again worse, down to 18.64 dB. But this isn't bad overall.

Let's take a look at the second solution. Click the **Trans Lines** line in the main *EZNEC-ARRL* window to open the Transmission Lines Window. Change the length of the first line to **26.856** feet, the second to **28.356** feet, and press the **Enter** key to complete the change. Change the **Frequency** back to **14.15** MHz and click **FF Tab**. You should see exactly the same pattern as for both the first solution and for the ideal current model. But now change the **Frequency** to **14.0** MHz, click FF Tab, and look at the pattern.

What happened? The gain has dropped to 5.95 dBi and the front/back to only 3.1 dB. The array is now nearly bi-directional! It's almost as bad at 14.3 MHz. So we've created a terribly touchy system. The chance of its working correctly even at the design frequency is slim, because there are inevitably some differences between the model and real antenna.

We did have a clue this might happen. As stated in the section describing the "simplest" feed system, the best choices for line Z_0 and for the resulting solution give a difference in electrical line lengths about equal to the desired phase delay of the current. The difference in electrical line lengths for the first solution was about 152°—not as close to the 120° current phase difference as we'd like, but much better than the mere 9.7° difference of the lines for the second solution. While the 300-Ω line Z_0 is quite different from the element feed-point impedances, the first solution result is quite good. If desired, you can try other line impedance values into *Arrayfeed1* and evaluate the results with *EZNEC-ARRL*.

Please see the information about baluns in the **Baluns in Phased Arrays** section. Baluns are placed the same as in Fig 19, which shows the L-network feed system.

L-Network Feed System

To design an L network feed system, change the *Arrayfeed1* **Feed System Type** to **L Network** and click **Find Solutions**. The results aren't good ones to use. The component reactance magnitudes of about 1573 and 2619 Ω are more than five times the 300-Ω Z_0 of the feed lines. As explained in the section describing the L-network feed system, it's undesirable to have such a large ratio of component reactance to line Z_0. Among other problems, the inductor and capacitor values are quite extreme and capacitor stray inductance and inductor capacitance would have a significant impact on performance.

The problem occurs because the feed-line impedance we chose is much larger than the element feed-point impedances, so the λ/4 lines transform the feed-point impedances to much higher values at the L network and main feed point. This feed system would be extremely critical, narrowbanded and difficult to adjust. We can do better by choosing feed-line impedances that aren't too drastically different than the element feed-point impedances. In this case, 50 or 75 Ω would be a much better choice than 300. Let's try 75.

In *Arrayfeed1*, change the **Line 1 Z0** and **Line 2 Z0** impedances from **300** to **75** and click **Find Solutions**. L-network component reactance magnitudes are now about 98 and 164 Ω, much better than before. This will be a relatively uncritical and broadbanded feed system.

Again, be sure to read the information about baluns in the **Baluns in Phased Arrays** section. Fig 19 shows the completed feed system including baluns.

PRACTICAL ASPECTS OF PHASED ARRAY DESIGN

With almost any type of antenna system, there is much that can be learned from experimenting with, testing and using

various array configurations. In this section, Roy Lewallen, W7EL, shares the benefit of years of his experience from actually building, adjusting and using phased arrays. There is much more work to be done in most of the areas covered here, and Roy encourages the reader to build on this work.

Adjusting Phased Array Feed Systems

If a phased array is constructed only to achieve forward gain, adjusting it is seldom worthwhile. This is because the forward gain of most arrays is quite insensitive to either the magnitude or phase of the relative currents flowing in the elements. If, however, good rejection of unwanted signals is desired, adjustment may be required. And achieving very deep nulls will almost surely require some adjustment.

The in-phase and 180° out-of-phase current-forcing method supplies very well-balanced and well-phased currents to elements without adjustment. If the pattern of an array fed using this method is unsatisfactory, it's generally the result of environmental differences—where the elements, even though furnished with correct currents, aren't generating the correct fields. Such an array can be optimized in a single direction, but a more general approach than the current-forcing method must be taken. Some possibilities are described by Paul Lee and Forrest Gehrke (see Bibliography).

Unlike the current-forcing method, the "simplest" and L-network feed systems described earlier in this chapter are dependent on the self and mutual impedance of one or more elements. The required transmission-line lengths or L-network component values can be computed to a high level of precision, but the results are only as good as the knowledge of the relevant feed-point impedances.

While the simplest feed system doesn't readily lend itself to adjustment, the components of an L network can easily be made adjustable or can be experimentally changed in increments. A practical approach is to model the array as accurately as possible, design and build the feed system based on the model results and then adjust the network for the best performance.

Simple arrays such as the two-element 90° fed and spaced array can be adjusted as follows. Place a low-power signal source at a distance from the array (preferably several wavelengths), in the direction a null should be. While listening to the signal on a receiver connected to the array, alternately adjust the two L-network components for the best rejection of the signal.

This has proved to be a very good way to adjust 2-element arrays. However, variable results were obtained when a Four-Square array was adjusted using this technique. The probable reason is that more than one combination of current balance and phasing can produce a null in a given direction but each produces a different overall pattern. So a different method must be used for adjusting more complex arrays. This involves actually measuring the element currents in some way, and adjusting the network until the currents are correct. After adjusting the currents, small adjustments can be made to deepen the null(s) if desired.

Measuring Element Currents

You can measure the element currents two ways. One way is to measure them directly at the element feed points, as shown in **Fig 30**. A dual-channel oscilloscope is required to monitor the currents. This method is the most accurate and it provides a direct indication of the actual relative magnitudes and phases of the element currents. The current probe is shown in **Fig 31**.

Instead of measuring the element currents directly, you could measure them indirectly by measuring the voltages on the feed lines an electrical $\lambda/4$ or $3\lambda/4$ distance from the array. The voltages at these points are directly proportional to the element currents. This introduces additional variables that can reduce the accuracy of the result, but the method generally produces adequate performance. The 2-element arrays fed with the L-network system and all the four element arrays presented earlier have $\lambda/4$ or $3\lambda/4$ lines from all elements to a common location, making this second measurement method convenient. The voltages can be observed with a dual-channel oscilloscope, or, to adjust for equal-magnitude currents and 90° phasing, you can use the test circuit shown in **Fig 32**.

The test circuit is connected to the feed lines of two elements that are to be adjusted for 90° phasing (such as elements 1 and 2, or 2 and 4 of the Four-Square array of Figs 24 and 25). Adjust the L-network components alternately until both meters read zero. Proper operation of the test circuit can be verified by disconnecting one of the inputs. The *phase* output

Fig 30—One method of measuring element currents in a phased array. Details of the current probe are given in Fig 31. Caution: Do not run high power to the antenna system for this measurement, or damage to the test equipment may result.

Fig 31—The current probe for use in the test setup of Fig 30. The ferrite core is of type 72 material, and may be any size. The coax line must be terminated at the opposite end with a resistor equal to its characteristic impedance. You should build this probe in a plastic or metal box to provide mechanical ruggedness.

Fig 32—Quadrature test circuit. All diodes are germanium, such as 1N34A, 1N270, or equiv. Hot carrier or silicon diodes can be used at higher power levels. All resistors are ¼ or ½ W, 5% tolerance. Capacitors are ceramic. Alligator clips are convenient for making the input and ground connections to the array.
T1—7 trifilar turns on an Amidon FT-37-43, -75, -77, or equivalent ferrite toroid core.

should remain close to zero. If not, there is an undesirable imbalance in the circuit, which must be corrected. Another means of verification is to first adjust the L network so the tester indicates correct phasing (zero volts at the *phase* output). Then reverse the tester input connections to the elements. The *phase* output should remain close to zero.

Directional Switching of Arrays

One ideal directional-switching method would take the entire feed system, including the lines to the elements and physically rotate it. The smallest possible increment of rotation would depend on the symmetry of the array—the feed system would need to rotate until the array again *looks* the same to it. For example, any 2-element array can be rotated 180° (although that wouldn't accomplish anything if the array is bidirectional to begin with). The 4-element rectangular array of Figs 28 and 29 can also be reversed, and the Four-Square array of Figs 24 and 25 can be switched in 90° increments.

Smaller switching increments can be accomplished only by reconfiguring the feed system, including any network if used, effectively creating a different kind of array. Switching in smaller increments than dictated by symmetry will create a different pattern in some directions than in others, and must be thoughtfully done to maintain equal and properly phased element currents. The methods illustrated here will deal only with switching in increments related to the array symmetry, except for one: a 2-element broadside/end-fire array.

In all arrays, the success of directional switching depends on the elements and ground systems being identical so that equal element currents result in equal fields. It's even more important in arrays fed with any method other than current forcing, because the effectiveness of those methods depends on the element feed-point impedances. Few of us

can afford the luxury of having an array many wavelengths away from all other conductors, so an array will nearly always perform somewhat differently in each direction. The array should be adjusted when steered in the direction requiring the most signal rejection in the nulls. Forward gain will, for all practical purposes, be equal in all the switched directions, since gain is much more tolerant of error than are nulls.

Basic Switching Methods

Following is a discussion of basic switching methods, how to power relays through the main feed line and other practical considerations. In diagrams, grounds are frequently omitted to aid clarity, but connections of the ground conductors must be carefully made. In fact, it is recommended that the ground conductors be switched just as the center conductors are, as explained in more detail in **Improving Array Switching Systems** below. In all cases, interconnecting lines must be very short.

A pair of elements spaced λ/2 apart can readily be switched between broadside and end-fire bidirectional pat-

Fig 33—Two-element broadside/end-fire switching. All lines must have the same characteristic impedance. Grounds and cable shields have been omitted for clarity.

Fig 35—Directional switching for 90°, 90° spaced 2-element array fed with an L-network, current-forcing feed system.

Fig 34—Directional switching for 90°, 90° spaced 2-element array fed with a "simplest" feed system.

Fig 36—Directional switching of a four-element rectangular array. All interconnections must be very short. As usual, grounds and cable shields have been omitted for clarity.

terns, using the current-forcing properties of λ/4 lines. The method is shown in **Fig 33**. The switching device can be a relay powered via a separate cable or by dc sent along the main feed line.

Fig 34 shows directional switching of a 90° fed, 90° spaced array fed with a "simplest" feed system, where L1 and L2 are the required lengths of the two feed lines. **Fig 35** shows how to switch the same array when fed with an L-network, current-forcing system.

The rectangular array of Fig 28 can be switched in a similar manner, as shown in **Fig 36**. To switch a "simplest" fed rectangular array, use the switching circuit of Fig 34, but connect the two equal length lines to points A and B of

Fig 29 in place of the two elements shown in Fig 34.

Switching the direction of an array in increments of 90°, when permitted by symmetry, requires at least two relays. A method of 90° switching of the Four-Square array with L-network feed is shown in **Fig 37**.

Powering Relays Through Feed Lines

All of the above switching methods can be implemented without additional wires to the switch box. A single-relay system is shown in **Fig 38A**, and a two-relay system in

Fig 38B. Small 12 or 24-V dc power relays can be used in either system at power levels up to at least a few hundred watts. Do not attempt to change directions while transmitting, however. Blocking capacitors C1 and C2 should be good quality ceramic or transmitting mica units of 0.01 to 0.1 µF. No problems have been encountered using 0.1 µF, 300-V monolithic ceramic units at RF output levels up to 300 W. C2 may be omitted if the antenna system is an open circuit at dc. C3 and C4 should be ceramic, 0.001 µF or larger.

In Fig 38B, capacitors C5 through C8 should be selected with the ratings of their counterparts in Fig 38A, as given above. Electrolytic capacitors across the relay coils, C9 and C10 in Fig 38B, should be large enough to prevent the relays from buzzing, but not so large as to make relay operation too slow. Final values for most relays will be in the range from 10 to 100 µF. They should have a voltage rating of at least double the relay coil voltage. Some relays do not require this capacitor. All diodes are 1N4001 or similar. A rotary switch may be used in place of the two toggle switches in the two-relay system to switch the relays in the desired sequence.

Improving Array-Switching Systems

The extra circuitry involved in switching arrays can degrade array performance by altering the relative currents fed to each element. One common cause is current sharing in common ground conductors, even when connections are kept very short. The author has seen a 30° phase shift in voltage along a 4-inch piece of #12 wire in a 40-meter array feed system.

When the two conductors of a feedline are physically separated from each other, the impedance increases. This is especially true when the main lines are coaxial cables. If currents from two elements share the ground conductor of a split line, a relatively large voltage drop results. Voltage changes λ/4 from the elements translate to current changes at the elements. Although keeping all leads extremely short is sometimes adequate, the best way to reduce current sharing problems is to keep the two conductors of each transmission line as close together as possible, and switch both conductors of each line rather than just a single or "hot" conductor.

An example of a carefully designed switching system is shown in **Fig 39**. It avoids the problem of shared ground conductor currents, as well as another common problem, namely that effective line lengths are often different along different switching paths. Notice how the path from the main feed point travels through a single line to each element with no common ground connections to other lines except at the

Fig 38—Remote switching of relays. See text for component information. A one-relay system is shown at A, and a two-relay system at B. In B, S1 activates K1, and S2 activates K2.

Fig 37—Directional switching of the four-square array. All interconnections must be very short.

Pattern Maximum in Direction of Element No.	Relays K 1	K 2
1	In	Out
2	In	In
3	Out	In
4	Out	Out

Both Relays Shown " Out "

ANT0331

main feed point. Notice also that the distance doesn't change as the direction is switched. The λ/4 lines going to the two elements must be shortened by the length ℓ of the lines on the feed side of the relays, so that the total line length from the main feed point to each element is λ/4 (or 3λ/4).

You can see that in either relay position, there's an open ended stub of length ℓ connected at the main feed point and another at the output end of the L network. These will add capacitance at those points. Extra C at the main feed point will alter the overall impedance seen by a transmitter, but won't otherwise have any effect on the array or its performance. The one at the output of the L network will, however, change the transformation and phase shift properties of the network. But it's easy to compensate—the value of the shunt capacitor element is simply reduced by the amount of the C added by the stub. The amount of C for any kind of transmission line can be calculated from:

$$C(pf/ft) = \frac{1017}{Z_0 VF}$$

or

$$C(pf/m) = \frac{3336}{Z_0 VF}$$

where Z_0 = the characteristic impedance of the line and VF = the velocity factor. This works out to 31 pF/foot or 101 pF/meter for 50-Ω solid polyethylene insulated coax, which has a velocity factor of 0.66.

The general principles illustrated in Fig 39 can be extended to other switching systems. If switching the ground conductors as described above isn't practical, use of a metal box for the switching circuitry is recommended, so that the relatively large surface area of the box can be used for the common ground conductors, minimizing their inductance. Always keep leads extremely short.

Measuring the Electrical Length of Feed Lines

When using the feed methods described earlier the feed lines must be very close to the correct length. For best results, they should be correct within 1% or so. This means that a line that is intended to be, say, λ/4 at 7 MHz, should actually be λ/4 at some frequency within 70 kHz of 7 MHz. A simple but accurate method to determine at what frequency a line is λ/4 or λ/2 is shown in **Fig 40A**. The far end of the line is short circuited with a very short connection. A signal is applied to the input and the frequency is swept until the impedance at the input is a minimum. This is the frequency at which the

Fig 39—A carefully designed L-network, current-forcing switching system that switches both hot and shield conductors in feed coaxes.

Fig 40—At A, the setup for measurement of the electrical length of a transmission line. The receiver may be used in place of the frequency counter to determine the frequency of the signal generator. The signal generator output must be free of harmonics; the half-wave harmonic filter at B may be used outboard if there is any doubt. It must be constructed for the frequency band of operation. Connect the filter between the signal generator and the attenuator pad.
C1, C3—Value to have a capacitive reactance = R_{IN}.
C2—Value to have a capacitive reactance = ½ R_{IN}.
L1, L2—Value to have an inductive reactance = R_{IN}.

line is λ/2. Either the frequency counter or the receiver may be used to determine this frequency. The line is, of course, λ/4 at one half the measured frequency.

The detector can be a simple diode detector or an oscilloscope may be used if available. A 6 to 10 dB attenuator pad is included to prevent the signal generator from looking into a short circuit at the measurement frequency. The signal generator output must be free of harmonics. If there is any doubt, an outboard low-pass filter, such as a half-wave harmonic filter, should be used. The half-wave filter circuit is shown in Fig 40B, and must be constructed for the frequency band of operation.

Another satisfactory method is to use a noise or resistance bridge or antenna analyzer at the input of the line, again looking for a low impedance at the input while the output is short circuited. Simple resistance bridges are described in Chapter 27.

Dip oscillators have been found to be unsatisfactory.

The required coupling loop has too great an effect on measurements.

Measuring Element Self and Mutual Impedances

The need for measuring element self and mutual impedances has been made largely unnecessary with the ready availability of modeling software. Few amateurs appreciate the considerable difficulty of making accurate impedance measurements and accurate mutual impedance measurements are very difficult even with professional test equipment and skills. Despite the limitations of computer modeling, results very often are better than measured values because of the multiple factors affecting measurement accuracy.

Those who are interested in measuring self and mutual impedances can find more detailed information about doing so in Appendix B. The information there is from earlier editions of *The ARRL Antenna Book*.

Broadside Arrays

Broadside arrays can be made up of collinear or parallel elements or combinations of the two. This section was contributed by Rudy Severns, N6LF.

COLLINEAR ARRAYS

Collinear arrays are always operated with the elements in-phase. (If alternate elements in such an array are out-of-phase, the system simply becomes a harmonic type of antenna.) A collinear array is a broadside radiator, the direction of maximum radiation being at right angles to the line of the antenna.

POWER GAIN

Because of the nature of the mutual impedance between collinear elements, the feed-point resistance (compared to a single element, which is ≈73 Ω) is increased as shown earlier in this chapter (Fig 9). For this reason the power gain does not increase in direct proportion to the number of elements. The gain with two elements, as the spacing between them is varied, is shown by **Fig 41**. Although the gain is greatest when

the end-to-end spacing is in the region of 0.4 to 0.6 λ, the use of spacings of this order is inconvenient constructionally and introduces problems in feeding the two elements. As a result, collinear elements are almost always operated with their ends

Fig 41—Gain of two collinear λ/2 elements as a function of spacing between the adjacent ends.

quite close together—in wire antennas, usually with just a strain insulator between.

With very small spacing between the ends of adjacent elements the theoretical power gain of collinear arrays, assuming the use of #12 copper wire, is approximately as follows over a dipole in free space:

2 collinear elements—1.6 dB
3 collinear elements—3.1 dB
4 collinear elements—3.9 dB

More than four elements are rarely used.

DIRECTIVITY

The directivity of a collinear array, in a plane containing the axis of the array, increases with its length. Small secondary lobes appear in the pattern when more than two elements are used, but the amplitudes of these lobes are low enough so that they are usually not important. In a plane at right angles to the array the directive diagram is a circle, no matter what the number of elements. Collinear operation, therefore, affects only E-plane directivity, the plane containing the antenna.

When a collinear array is mounted with the elements vertical, the antenna radiates equally well in all geographical directions. An array of such *stacked* collinear elements tends to confine the radiation to low vertical angles.

If a collinear array is mounted horizontally, the directive pattern in the vertical plane at right angles to the array is the same as the vertical pattern of a simple $\lambda/2$ antenna at the same height (Chapter 3).

TWO-ELEMENT ARRAYS

The simplest and most popular collinear array is one using two elements, as shown in **Fig 42**. This system is commonly known as *two half-waves in phase*. The directive pattern in a plane containing the wire axis is shown in **Fig 43**,

Fig 43—Free-space E-plane directive diagram for dipole, 2, 3 and 4-element collinear arrays. The solid line is a 4-element collinear; the dashed line is for a 3-element collinear; the dotted line is for a 2-element collinear and the dashed-dotted line is for a $\lambda/2$ dipole.

which shows superimposed patterns for a dipole and 2, 3 and 4-element collinear arrays. Depending on the conductor size, height, and similar factors, the impedance at the feed point can be expected to be in the range of 4 to 6 kΩ, for wire antennas. If the elements are made of tubing having a low λ/dia (wavelength to diameter) ratio, values as low as 1 kΩ are representative. The system can be fed through an open-wire tuned line with negligible loss for ordinary line lengths, or a matching section may be used if desired.

A number of arrangements for matching the feed line to this antenna are described in Chapter 26. If elements somewhat shorter than $\lambda/2$ are used, then additional matching schemes can be employed at the expense of a slight reduction in gain. When the elements are shortened two things happen—the impedance at the feed-point drops and the impedance has inductive reactance that can be tuned out with simple series capacitors, as shown in Fig 42B.

Note that these capacitors must be suitable for the power level. Small *doorknob* capacitors such as those frequently used in power amplifiers, are suitable. By way of an example, if each side of a 40-meter 2-element array is shortened from 67 to 58 feet, the feed-point impedance drops from nearly 6000 Ω to about 1012 Ω with an inductive reactance of 1800 Ω. The reactance can be tuned out by inserting 25 pF capacitors at the feed-point. The 1012 Ω resistance can be transformed to 200 Ω using a $\lambda/4$ matching section made of 450-Ω ladder line and then transformed to 50 Ω with a 4:1 balun. Shortening the array as suggested reduces the gain by about 0.5 dB.

Another scheme that preserves the gain is to use a 450-Ω

Fig 42—At A, two-element collinear array (two half-waves in phase). The transmission line shown would operate as a tuned line. A matching section can be substituted and a nonresonant line used if desired, as shown at B, where the matching section is two series capacitors.

Fig 44—Layouts for 3- and 4-element collinear arrays. Alternative methods of feeding a 3-element array are shown at A and B. These drawings also show the current distribution on the antenna elements and phasing stubs. A matched transmission line can be substituted for the tuned line by using a suitable matching section.

λ/4 matching section and shorten the antenna only slightly to have a resistance of 4 kΩ. The impedance at the input of the matching section is then near 50 Ω and a simple 1:1 balun can be used. Many other schemes are possible. The free-space E-plane response for a 2-element collinear array is shown in Fig 43, compared with the responses for more elaborate collinear arrays described below.

THREE- AND FOUR-ELEMENT ARRAYS

In a long wire the direction of current flow reverses in each λ/2 section. Consequently, collinear elements cannot simply be connected end to end; there must be some means for making the current flow in the same direction in all elements. When more than two collinear elements are used it is necessary to connect *phasing* stubs between adjacent elements in order to bring the currents in all elements in-phase. In **Fig 44A** the direction of current flow is correct in the two left-hand elements because the shorted λ/4 transmission line (*stub*) is connected between them. This stub may be looked upon simply as the alternate λ/2 section of a long-wire antenna folded

back on itself to cancel its radiation. In Fig 44A the part to the right of the transmission line has a total length of three half wavelengths, the center half wave being folded back to form a λ/4 phase-reversing stub. No data are available on the impedance at the feed point in this arrangement, but various considerations indicate that it should be over 1 kΩ.

An alternative method of feeding three collinear elements is shown in Fig 44B. In this case power is applied at the center of the middle element and phase-reversing stubs are used between this element and both of the outer elements. The impedance at the feed point in this case is somewhat over 300 Ω and provides a close match to 300 Ω line. The SWR will be less than 2:1 when 600-Ω line is used. Center feed of this type is somewhat preferable to the arrangement in Fig 44A because the system as a whole is balanced. This assures more uniform power distribution among the elements. In Fig 44A, the right-hand element is likely to receive somewhat less power than the other two because a portion of the input power is radiated by the middle element before it can reach the element located at the extreme right.

A four-element array is shown in Fig 44C. The system is symmetrical when fed between the two center elements as shown. As in the three-element case, no data are available on the impedance at the feed point. However, the SWR with a 600 Ω line should not be much over 2:1.

Fig 43 compares the directive patterns of 2, 3 and 4-element arrays. Collinear arrays can be extended to more than four elements. However, the simple 2-element collinear array is the type most frequently used, as it lends itself well to multi-band operation. More than two collinear elements are seldom used because more gain can be obtained from other types of arrays.

ADJUSTMENT

In any of the collinear systems described, the lengths of the radiating elements in feet can be found from the formula $468/f_{MHz}$. The lengths of the phasing stubs can be found from the equations given in Chapter 26 for the type of line used. If the stub is open-wire line (500 to 600 Ω impedance) you may assume a velocity factor of 0.975 in the formula for a $\lambda/4$ line. On-site adjustment is, in general, an unnecessary refinement. If desired, however, the following procedure may be used when the system has more than two elements.

Disconnect all stubs and all elements except those directly connected to the transmission line (in the case of feed such as is shown in Fig 44B leave only the center element connected to the line). Adjust the elements to resonance, using the still-connected element. When the proper length is determined, cut all other elements to the same length. Make the phasing stubs slightly long and use a shorting bar to adjust their length. Connect the elements to the stubs and adjust the stubs to resonance, as indicated by maximum current in the shorting bars or by the SWR on the transmission line. If more than three or four elements are used it is best to add elements two at a time (one at each end of the array), resonating the system each time before a new pair is added.

THE EXTENDED DOUBLE ZEPP

One method to obtain higher gain that goes with wider spacing in a simple system of two collinear elements is to make the elements somewhat longer than $\lambda/2$. As shown in **Fig 45**, this increases the spacing between the two in-phase

Fig 45—The extended double Zepp. This system gives somewhat more gain than two λ-sized collinear elements.

Fig 46—E-plane pattern for the extended double Zepp of Fig 45. This is also the horizontal directional pattern when the elements are horizontal. The axis of the elements lies along the 90°-270° line. The free-space array gain is approximately 4.95 dBi.

Fig 47—Resistive and reactive feed-point impedance of a 40-meter extended double Zepp in free space.

$\lambda/2$ sections at the ends of the wires. The section in the center carries a current of opposite phase, but if this section is short the current will be small; it represents only the outer ends of a $\lambda/2$ antenna section. Because of the small current and short length, the radiation from the center is small. The optimum length for each element is 0.64 λ. At greater lengths the system tends to act as a long-wire antenna, and the gain decreases.

This system is known as the *extended double Zepp*. The gain over a $\lambda/2$ dipole is approximately 3 dB, as compared with about 1.6 dB for two collinear $\lambda/2$ dipoles. The directional pattern in the plane containing the axis of the antenna

is shown in **Fig 46**. As in the case of all other collinear arrays, the free-space pattern in the plane at right angles to the antenna elements is the same as that of a λ/2 antenna—circular.

This antenna is not resonant at the operating frequency so that the feed-point impedance is complex (R ± jX). A typical example of the variation of the feed-point impedance over the band for a 40-meter double-extended Zepp is shown in **Fig 47**. This antenna is normally fed with open-wire transmission line to an antenna tuner.

Fig 48—Typical Sterba array, an 8-element version.

Other matching arrangements are, of course, possible. A method for transforming the feed-point impedance to 450 Ω and eliminating the minor lobes is given in Chapter 6.

THE STERBA ARRAY

Two collinear arrays can be combined to form the *Sterba array*, often called the *Sterba curtain*. An 8-element example of a Sterba array is shown in **Fig 48**. The four λ/4 elements joined on the ends are equivalent to two λ/2 elements. The two collinear arrays are spaced λ/2 and the λ/4 phasing lines connected together to provide λ/2 phasing lines. This arrangement has the advantage of increasing the gain for a given length and also increasing the E-plane directivity, which is no longer circular. An additional advantage of this array is that the wire forms a closed loop. For installations where icing is a problem a low voltage dc or low frequency (50 or 60 Hz) ac current can be passed through the wire to heat it for deicing. The heating current is isolated from RF by decoupling chokes. This is standard practice in commercial installations.

The number of sections in a Sterba array can be extended as far as desired but more than four or five are rarely used because of the slow increase in gain with extra elements, the narrow H-plane directivity and the appearance of multiple sidelobes. When fed at the point indicated the impedance is about 600 Ω. The antenna can also be fed at the point marked X. The impedance at this point will be about 1 kΩ. The gain of the 8-element array in Fig 48 will be between 7 to 8 dB over a single element.

Parallel Broadside Arrays

To obtain broadside directivity with parallel elements the currents in the elements must all be in-phase. At a distant point lying on a line perpendicular to the axis of the array and also perpendicular to the plane containing the elements, the fields from all elements add up in phase. The situation is like that pictured in Fig 1 in this chapter, where four parallel λ/2 dipoles were fed together a broadside array.

Broadside arrays of this type theoretically can have any number of elements. However, practical limitations of construction and available space usually limit the number of broadside parallel elements.

POWER GAIN

The power gain of a parallel-element broadside array depends on the spacing between elements as well as on the number of elements. The way in which the gain of a two-element array varies with spacing is shown in **Fig 49**. The greatest gain is obtained when the spacing is in the vicinity of 0.67 λ.

The theoretical gains of broadside arrays having more than two elements are approximately as follows:

No. of Parallel Elements	dB Gain with λ/2 Spacing	dB Gain with 3λ/4 Spacing
3	5.7	7.2
4	7.1	8.5
5	8.1	9.4
6	8.9	10.4

Fig 49—Gain as a function of the spacing between two parallel elements operated in-phase (broadside).

The elements must, of course, all lie in the same plane and all must be fed in-phase.

DIRECTIVITY

The sharpness of the directive pattern depends on spacing between elements and number of elements. Larger element spacing will sharpen the main lobe, for a given number of elements, up to a point as was shown in Fig 41. The two-element array has no minor lobes when the spacing is λ/2, but small minor lobes appear at greater spacings. When three or more elements are used the pattern always has minor lobes.

Other Forms Of Broadside Arrays

For those who have the available room, multi-element arrays based on the broadside concept have something to offer. The antennas are large but of simple design and non-critical dimensions; they are also very economical in terms of gain per unit of cost.

Large arrays can often be fed at several different points. However, the pattern symmetry may be sensitive to the choice of feed point within the array. Non-symmetrical feed points will result in small asymmetries in the pattern but these are not usually of great concern.

Arrays of three and four elements are shown in **Fig 50**. In the 3-element array with λ/2 spacing at A, the array is fed at the center. This is the most desirable point in that it tends to keep the power distribution among the elements uniform. However, the transmission line could alternatively be connected at either point B or C of Fig 50A, with only slight skewing of the radiation pattern.

When the spacing is greater than λ/2, the phasing lines must be 1 λ long and are not transposed between elements. This is shown Fig 50B. With this arrangement, any element spacing up to 1 λ can be used, if the phasing lines can be folded as suggested in the drawing.

The 2-element array at C is fed at the center of the system to make the power distribution among elements as uniform as possible. However, the transmission line could be connected at either point B, C, D or E. In this case the section of phasing line between B and D must be transposed to make the currents flow in the same direction in all elements. The 4-element array at C and the 3-element array at B have approximately the same gain when the element spacing in the array at B is 3λ/4.

An alternative feeding method is shown in Fig 50D. This system can also be applied to the 3-element arrays, and will result in better symmetry in any case. It is necessary only to move the phasing line to the center of each element, making connection to both sides of the line instead of one only.

The free-space pattern for a 4-element array with λ/2 spacing is shown in **Fig 51**. This is also approximately the pattern for a 3-element array with 3λ/4 spacing.

Larger arrays can be designed and constructed by following the phasing principles shown in the drawings. No accurate figures are available for the impedances at the various feed points indicated in Fig 50. You can estimate it to be in the vicinity of 1 kΩ when the feed point is at a junction between the phasing line and a λ/2 element, becoming smaller as the number of elements in the array is increased. When the feed point is midway between end-fed elements as in Fig 50C, the feed-point impedance of a 4-element array is in the vicinity of 200 to 300 Ω, with 600-Ω open-wire phasing lines. The impedance at the feed point with the antenna shown at D should be about 1.5 kΩ.

Fig 50—Methods of feeding 3- and 4-element broadside arrays with parallel elements.

Max. Gain = 8.95 dBi   ANT0344

Fig 51—Free-space E-plane pattern of a 4-element broadside array using parallel elements (Fig 50). This corresponds to the horizontal directive pattern at low wave angles for a vertically polarized array over ground. The axis of the elements lies along the 90°-270° line.

NON-UNIFORM ELEMENT CURRENTS

The pattern for a 4-element broadside array shown in Fig 51 has substantial side lobes. This is typical for arrays more than $\lambda/2$ wide when equal currents flow in each element. Sidelobe amplitude can be reduced by using non-uniform current distribution among the elements. Many possible current amplitude distributions have been suggested. All of them have reduced current in the outer elements and greater current in the inner elements. This reduces the gain somewhat but can produce a more desirable pattern. One of the common current distributions is called *binomial current grading*. In this scheme the ratio of element currents is set equal to the coefficients of a polynomial. For example:

$$1 \, x + 1, \quad \Rightarrow \quad 1, 1$$
$$(x+1)^2 = 1x^2 + 2x + 1, \quad \Rightarrow \quad 1, 2, 1$$
$$(x+1)^3 = 1x^3 + 3x^2 + 3x + 1, \quad \Rightarrow \quad 1, 3, 3, 1 \qquad \text{(Eq 7)}$$
$$(x+1)^4 = 1x^4 + 4x^3 + 6x^2 + 6x + 1, \quad \Rightarrow \quad 1, 4, 6, 4, 1$$

In a 2-element array the currents are equal, in a 3-element array the current in the center element is twice that in the outer elements, and so on.

HALF-SQUARE ANTENNA

On the low-frequency bands (40, 80 and 160 meters) it becomes increasingly difficult to use $\lambda/2$ elements because of their size. The half-square antenna is a 2-element broadside

Fig 52—Layout for the half-square antenna.

Max. Gain = 8.95 dBi   ANT0346

Fig 53—Free-space E-plane directive pattern for the half-square antenna.

array with $\lambda/4$-high vertical elements and $\lambda/2$ horizontal spacing. See **Fig 52**. The free-space H-plane pattern for this array is shown in **Fig 53**. The antenna gives modest (4.2 dBi) but useful gain and has the advantage of only $\lambda/4$ height. Like all vertically polarized antennas, real-world performance depends directly on the characteristics of the ground surrounding it.

The half-square can be fed either at the point indicated or at the bottom end of one of the vertical elements using a voltage-feed scheme, such as that shown in **Fig 54** for the bobtail curtain. The feed-point impedance is in the region of 50 Ω when fed at a corner as shown in Fig 52. A typical SWR plot is shown in **Fig 55**. Chapter 6 has a detailed discussion of the half-square antenna with several variations, together with practical considerations.

Fig 54—The bobtail curtain is an excellent low-angle radiator having broadside bidirectional characteristics. Current distribution is represented by the arrows. Dimensions A and B (in feet, for wire antennas) can be determined from the equations.

$$A \text{ (Feet)} = \frac{492}{f \text{ (MHz)}}$$

$$B \text{ (Feet)} = \frac{234}{f \text{ (MHz)}}$$

Fig 56—Calculated free-space E-plane directive diagram of the bobtail curtain shown in Fig 54. The array lies along the 90°-270° axis.

Fig 55—Typical SWR plot for a 40-meter half-square antenna fed at one corner. Antenna in free space.

Fig 57—Typical SWR plot for an 80-meter bobtail curtain in free space. This is a narrow-band antenna.

BOBTAIL CURTAIN

The antenna system in Fig 54 uses the principles of co-phased verticals to produce a broadside, bidirectional pattern providing approximately 5.1 dB of gain over a single $\lambda/4$ element. The antenna performs as three in-phase, top-fed vertical radiators approximately $\lambda/4$ in height and spaced approximately $\lambda/2$. It is most effective for low-angle signals and makes an excellent long-distance antenna for 1.8, 3.5 or 7 MHz.

The three vertical sections are the actual radiating components, but only the center element is fed directly. The two horizontal parts, A, act as phasing lines and contribute very little to the radiation pattern. Because the current in the center element must be divided between the end sections, the current distribution approaches a binomial 1:2:1 ratio. The radiation pattern is shown in **Fig 56**.

The vertical elements should be as vertical as possible. The height for the horizontal portion should be slightly greater than B, as shown in Fig 54. The tuning network is resonant at the operating frequency. The L/C ratio should be fairly low to provide good loading characteristics. As a starting point, a maximum capacitor value of 75 to 150 pF is recommended, and the inductor value is determined by C and the operating frequency. The network is first tuned to resonance and then the

tap point is adjusted for the best match. A slight readjustment of C may be necessary. A link coil consisting of a few turns can also be used to feed the antenna.

A feeling for the matching bandwidth of this antenna can be obtained by looking at a feed point located at the top end of the center element. The impedance at this point will be approximately 32 Ω. An SWR plot (for $Z_0 = 32$ Ω) for an 80-meter bobtail curtain at this feed-point is shown in **Fig 57**. However, it is not advisable to actually connect a feed line at this point since it would detune the array and alter the pattern. This antenna is relatively narrow band. When fed at the bottom of the center element as shown in Fig 54, the SWR can be adjusted to be 1:1 at one frequency but the operating bandwidth for SWR < 2:1 may be even narrower than Fig 57 shows. For 80-meters, where operation is often desired in the CW DX window (3.510 MHz) and in the phone DX window (3.790 MHz), it will be necessary to retune the matching network as you change frequency. This can be done by switching a capacitor in or out, manually or remotely with a relay.

While the match bandwidth is quite narrow, the radiation pattern changes more slowly with frequency. **Fig 58** shows the variation in the pattern over the entire band (3.5 to 4.0 MHz). As would be expected, the gain increases with frequency because the antenna is larger in terms of wavelengths. The general shape of the pattern, however, is quite stable.

THE BRUCE ARRAY

Four variations of the Bruce array are shown in **Fig 59**. The Bruce is simply a wire folded so that the vertical sections carry large in-phase currents, while the horizontal sections carry small currents flowing in opposite directions with respect to the center of a section (indicated by dots). The radiation is vertically polarized. The gain is proportional to the length of the array but is somewhat smaller than you can obtain from a broadside array of λ/2 elements of the same length. This is because the radiating portion of the elements is only λ/4.

The Bruce array has a number of advantages:

1) The array is only λ/4 high. This is especially helpful on 80 and 160 meters, where the height of λ/2 supports becomes impractical for most amateurs.

2) The array is very simple. It is just a single piece of wire folded to form the array.

3) The dimensions of the array are very flexible. Depending on the available distance between supports, any number of elements can be used. The longer the array, the greater the gain.

4) The shape of the array does not have to be exactly 1.05 λ/4 squares. If the available height is short but the array can be made longer, then shorter vertical sections and longer horizontal sections can be used to maintain gain and resonance. Conversely, if more height is available but width is restricted then longer vertical sections can be used with shorter horizontal sections.

5) The array can be fed at other points more convenient for a particular installation.

6) The antenna is relatively low Q, so that the feed-point impedance changes slowly with frequency. This is very helpful on 80 meters, for example, where the antenna can be relatively broadband.

7) The radiation pattern and gain is stable over the width of an amateur band.

Note that the nominal dimensions of the array in Fig 59 call for section lengths = 1.05 λ/4. The need to use slightly longer elements to achieve resonance is common in large wire arrays. A quad loop behaves in the same manner. This is quite different from wire dipoles, which are typically *shortened* by 2-5% to achieve resonance.

Fig 60 shows the variations in gain and pattern for 2 to 5-element 80-meter Bruce arrays. **Table 2** lists the gain over a vertical λ/2 dipole, a 4-radial ground-plane vertical and the size of the array. The gain and impedance parameters listed are for free space. Over real ground the patterns and gain will depend on the height above ground and the ground characteristics. Copper loss using #12 conductors in included.

Worthwhile gain can be obtained from these arrays, especially on 80 and 160 meters, where any gain is hard to come by. The feed-point impedance is for the center of a vertical section. From the patterns in Fig 60 you can see that sidelobes start to appear as the length of the array is increased beyond 3λ/4. This is typical for arrays using equal currents in the elements.

It is interesting to compare the bobtail curtain (Fig 54) with a 4-element Bruce array. **Fig 61** compares the radiation patterns for these two antennas. Even though the Bruce is shorter (3λ/4) than the bobtail (1 λ), it has slightly more

Max. Gain = 6.94 dBi

4.0 MHz
3.75 MHz
3.5 MHz

ANT0351

Fig 58—80-meter bobtail curtain's free-space E-plane pattern variation over the 80-meter band.

1.05 λ/8

2 – Element

1.05 λ/4

(A)

3 – Element

(B)

4 – Element

(C)

5 – Element

(D)

ANT0352

Fig 59—Various Bruce arrays: 2, 3, 4 and 5-element versions.

Table 2

Bruce array length, impedance and gain as a function of number of elements

Number Elements	Gain Over λ/2 Vertical Dipole	Gain over λ/4 Ground-Plane	Array Length Wavelengths	Approx. Feed Z, Ω
2	1.2 dB	1.9 dB	¼	130
3	2.8 dB	3.6 dB	½	200
4	4.3 dB	5.1 dB	¾	250
5	5.3 dB	6.1 dB	1	300

gain. The matching bandwidth is illustrated by the SWR curve in **Fig 62**. The 4-element Bruce has over twice the match bandwidth (200 kHz) than does the bobtail (75 kHz in Fig 57). Part of the gain difference is due to the binomial current distribution—the center element has twice the current

as the outer elements in the bobtail. This reduces the gain slightly so that the 4-element Bruce becomes competitive. This is a good example of using more than the minimum number of elements to improve performance or to reduce size. On 160 meters the 4-element Bruce will be 140 feet shorter than the bobtail, a significant reduction. If additional space is available for the bobtail (1 λ) then a 5-element Bruce could

Fig 60—80-meter free-space E-plane directive patterns for the Bruce arrays shown in Fig 59. The 5-element's pattern is a solid line; the 4-element is a dashed line; the 3-element is a dotted line, and the 2-element version is a dashed-dotted line.

Fig 62—Typical SWR curve for a 4-element 80-meter Bruce array.

Fig 61—Comparison of free space patterns of a 4-element Bruce array (solid line) and a 3-element bobtail curtain (dashed line).

Fig 63—Alternate feed arrangements for the Bruce array. At A, the antenna is driven against a ground system and at B, it uses a two-wire counterpoise.

Multielement Arrays   8-47

be used, with a small increase in gain but also introducing some sidelobes.

The 2-element Bruce and the half-square antennas are both 2-element arrays. However, since the spacing between radiators is greater in the half-square ($\lambda/2$) the gain of the half-square is about 1 dB greater. If space is available, the half-square would be a better choice. If there is not room for a half-square then the Bruce, which is only half as long ($\lambda/4$), may be a good alternative. The 3-element Bruce, which has the same length ($\lambda/2$) as the half-square, has about 0.6 dB more gain than the half-square and will have a wider match bandwidth.

The Bruce antenna can be fed at many different points and in different ways. In addition to the feed points indicated in Fig 59, you may connect the feed line at the center of any of the vertical sections. In longer Bruce arrays, feeding at one end will result in some current imbalance among the elements but the resulting pattern distortion is small. Actually, the feed-point can be anywhere along a vertical section. One very convenient point is at an outside corner. The feed-point impedance will be higher (about 600 Ω). A good match for 450-Ω ladder-line can usually be found somewhere on the vertical section. It is important to recognize that feeding the antenna at a voltage node (dots in Fig 59) by breaking the wire and inserting an insulator, completely changes the current distribution. This will be discussed in the section on endfire arrays.

A Bruce can be fed unbalanced against ground or against a counterpoise as shown in **Fig 63**. Because it is a vertically polarized antenna, the better the ground system, the better the performance. As few as two elevated radials can be used as shown in Fig 63B, but more radials can also be used to improve the performance, depending on local ground constants. The original development of the Bruce array in the late 1920s used this feed arrangement.

FOUR-ELEMENT BROADSIDE ARRAY

The 4-element array shown in **Fig 64** is commonly known as the *lazy H*. It consists of a set of two collinear elements and a set of two parallel elements, all operated in-phase to give broadside directivity. The gain and directivity will depend on the spacing, as in the case of a simple parallel-element broadside array. The spacing may be chosen between the limits shown on the drawing, but spacings below $3\lambda/8$ are not worthwhile because the gain is small. Estimated gains compared to a single element are:

$3\lambda/8$ spacing—4.2 dB
$\lambda/2$ spacing—5.8 dB
$5\lambda/8$ spacing—6.7 dB
$3\lambda/4$ spacing—6.3 dB

Half-wave spacing is generally used. Directive patterns for this spacing are given in **Figs 65** and **66**. With $\lambda/2$ spacing between parallel elements, the impedance at the junction of the phasing line and transmission line is resistive and in the vicinity of 100 Ω. With larger or smaller spacing the impedance at this junction will be reactive as well as

Fig 64—Four-element broadside array ("lazy H") using collinear and parallel elements.

resistive. Matching stubs are recommended in cases where a non-resonant line is to be used. They may be calculated and adjusted as described in Chapter 26.

The system shown in Fig 64 may be used on two bands having a 2-to-1 frequency relationship. It should be designed for the higher of the two frequencies, using $3\lambda/4$ spacing between parallel elements. It will then operate on the lower frequency as a simple broadside array with $3\lambda/8$ spacing.

An alternative method of feeding is shown in the small diagram in Fig 64. In this case the elements and the phasing line must be adjusted exactly to an electrical half wavelength. The impedance at the feed point will be resistive and on the order of 2 kΩ.

THE BI-SQUARE ANTENNA

A development of the lazy H, known as the *bi-square antenna*, is shown in **Fig 67**. The gain of the bi-square is somewhat less than that of the lazy-H, but this array is attractive because it can be supported from a single pole. It has a circumference of 2 λ at the operating frequency, and is horizontally polarized.

The bi-square antenna consists of two 1 λ radiators, fed 180° out-of-phase at the bottom of the array. The radiation resistance is 300 Ω, so it can be fed with either 300- or 600-Ω line. The free space gain of the antenna is about 5.8 dBi, which is 3.7 dB more than a single dipole element. Gain may be increased by adding a parasitic reflector or director. Two bi-square arrays can be mounted at right angles and switched to provide omnidirectional coverage. In this way, the antenna wires may be used as part of the guying system for the pole.

Although it resembles a loop antenna, the bi-square is not a true loop because the ends opposite the feed point

Freq. = 7.15 MHz

Max. Gain = 7.87 dBi (A)

Freq = 7.15 MHz

Max. Gain = 12.83 dBi ANT0359

Fig 66—Vertical pattern of the 4-element broadside antenna of Fig 64, when mounted with the elements horizontal and the lower set λ/4 above flat ground. Stacked arrays of this type give best results when the lowest elements are at least λ/2 high. The gain is reduced and the wave angle raised if the lowest elements are too close to ground.

Freq. = 7.15 MHz

Max. Gain = 7.87 dBi (B) ANT0358

Fig 65—Free-space directive diagrams of the 4-element antenna shown in Fig 64. At A is the E-plane pattern. The axis of the elements lies along the 90°-270° line. At B is the free-space H-plane pattern, viewed as if one set of elements is above the other from the ends of the elements.

λ/2

ANT0360

Fig 67—The bi-square array. It has the appearance of a loop, but is not a true loop because the conductor is open at the top. The length of each side, in feet, is 480/f (MHz).

are open. However, identical construction techniques can be used for the two antenna types. Indeed, with a means of remotely closing the connection at the top for lower frequency operation, the antenna can be operated on two harmonically

related bands. As an example, an array with 17 feet per side can be operated as a bi-square at 28 MHz and as a full-wave loop at 14 MHz. For two-band operation in this manner, the side length should favor the higher frequency. The length of a closed loop is not as critical.

End-Fire Arrays

The term *end-fire* covers a number of different methods of operation, all having in common the fact that the maximum radiation takes place along the array axis, and that the array consists of a number of parallel elements in one plane. End-fire arrays can be either bidirectional or unidirectional. In the bidirectional type commonly used by amateurs there are only two elements, and these are operated with currents 180° out-of-phase. Even though adjustment tends to be complicated, unidirectional end-fire driven arrays have also seen amateur use, primarily as a pair of phased, ground-mounted λ/4 vertical elements. Extensive discussion of this array is contained in earlier sections of this chapter.

Horizontally polarized unidirectional end-fire arrays see little amateur use except in log-periodic arrays (described in Chapter 10). Instead, horizontally polarized unidirectional arrays usually have parasitic elements (described in Chapter 11) and are called Yagis.

TWO-ELEMENT END-FIRE ARRAY

In a 2-element array with equal currents out-of-phase, the gain varies with the spacing between elements as shown in **Fig 68**. The maximum gain occurs in the neighborhood of 0.1 λ spacing. Below that the gain drops rapidly due to conductor loss resistance.

The feed-point resistance for either element is very low at the spacings giving greatest gain, as shown in Fig 8 earlier in this chapter. The spacings most frequently used are λ/8 and λ/4, at which the resistances of center-fed λ/2 elements are about 9 and 32 Ω, respectively.

The effect of conductor resistance on gain for various spacings is shown in **Fig 69**. Because current along the element is not constant (it is approximately sinusoidal), the resistance shown is the equivalent resistance (R_{eq}) inserted at the center of the element to account for the loss distributed along the element.

The equivalent resistance of a λ/2 element is one half the ac resistance (R_{ac}) of the complete element. R_{ac} is usually >> R_{dc} due to skin effect. For example, a 1.84 MHz dipole using #12 copper wire will have the following R_{eq}:

Wire length = 267 feet
Rdc = 0.00159 [/foot] × 267 [feet] = 0.42
Fr = Rac/Rdc = 10.8
Req =(Rdc/2) × Fr = 2.29

For a 3.75 MHz dipole made with #12 wire, Req = 1.59 Ω. In Fig 69, it is clear that end-fire antennas made with #12 or smaller wire will limit the attainable gain because of losses. There is no point in using spacings much less than λ/4 if you use wire elements. If instead you use elements made of aluminum tubing then smaller spacings can be used to increase gain. However, as the spacing is reduced below λ/4 the increase in gain is quite small even with good conductors. Closer spacings give little gain increase but can drastically

Fig 68—Gain of an end-fire array consisting of two elements fed 180° out-of-phase, as a function of the spacing between elements. Maximum radiation is in the plane of the elements and at right angles to them at spacings up to λ/2, but the direction changes at greater spacings.

Fig 69—Gain over a single element of two out-of-phase elements in free space as a function of spacing for various loss resistances.

reduce the operating bandwidth due to the rapidly increasing Q of the array.

Unidirectional End-Fire Arrays

Two parallel elements spaced λ/4 apart and fed equal currents 90° out-of-phase will have a directional pattern in the plane at right angles to the plane of the array. See **Fig 70**. The maximum radiation is in the direction of the element in which the current lags. In the opposite direction the fields from the two elements cancel.

When the currents in the elements are neither in-phase nor 180° out-of-phase, the feed-point resistances of the elements are not equal. This complicates the problem of feeding equal currents to the elements, as discussed in earlier sections.

Fig 70—Representative H-plane pattern for a 2-element end-fire array with 90° spacing and phasing. The elements lie along the vertical axis, with the uppermost element the one of lagging phase. Dissimilar current distributions are taken into account. (Pattern computed with *ELNEC*.)

Fig 71—H-plane pattern for a 3-element end-fire array with binomial current distribution (the current in the center element is twice that in each end element). The elements are spaced λ/4 apart along the 0°-180° axis. The center element lags the lower element by 90°, while the upper element lags the lower element by 180° in phase. Dissimilar current distributions are taken into account. (Pattern computed with *ELNEC*.)

More than two elements can be used in a unidirectional end-fire array. The requirement for unidirectivity is that there must be a progressive phase shift in the element currents equal to the spacing, in electrical degrees, between the elements. The amplitudes of the currents in the various elements also must be properly related. This requires binomial current

distribution. In the case of three elements, this requires that the current in the center element be twice that in the two outside elements, for 90° (λ/4) spacing and element current phasing. This antenna has an overall length of λ/2. The directive diagram is shown in **Fig 71**. The pattern is similar to that of Fig 70, but the 3-element binomial array has greater directivity, evidenced by the narrower half-power beamwidth (146° versus 176°). Its gain is 1.0 dB greater.

THE W8JK ARRAY

As pointed out earlier, John Kraus, W8JK, described his bidirectional flat-top W8JK beam antenna in 1940. See **Fig 72**. Two λ/2 elements are spaced λ/8 to λ/4 and driven 180° out-of-phase. The free-space radiation pattern for this antenna, using #12 copper wire, is given in **Fig 73**. The pattern is representative of spacings between λ/8 and λ/4 where the gain varies less than 0.5 dB. The gain over a dipole is about 3.3 dB (5.4 dBi referenced to an isotropic radiator), a worthwhile improvement. The feed-point impedance (including wire resistance) of *each* element is about 11 Ω for λ/8 spacing and 33 Ω for λ/4 spacing. The feed-point impedance at the center connection will depend on the length and Z_0 of the connecting transmission line.

Kraus gave a number of other variations for end-fire arrays, some of which are shown in **Fig 74**. The ones fed at the center (A, C and E) are usually horizontally polarized flat-top beams. The end-fed versions (B, D & F) are usually vertically polarized, where the feed point can be conveniently near ground.

A practical variation of Fig 74B is given in **Fig 75**. In this example, the height is limited to λ/4 so the ends can be bent over as shown, producing a 2-element Bruce array. This reduces the gain somewhat but allows much shorter supports, an important consideration on the low bands. If additional height is available, then you can achieve some additional gain. The upper ends can be bent over to fit the available height. The feed-point impedance will greater than 1 kΩ.

Fig 72—A 2-element W8JK array.

Freq. = 1.85 MHz

Max. Gain = 5.39 dBi

ANT0366

Fig 73—Free-space E-plane pattern for the 2-element W8JK array

ANT0368

Fig 75—A 2-element end-fire array with reduced height.

ANT0367

Fig 74—Six other variations of W8JK "flat-top beam" antennas.

FOUR-ELEMENT END-FIRE AND COLLINEAR ARRAYS

The array shown in **Fig 76** combines collinear in-phase elements with parallel out-of-phase elements to give both broadside and end-fire directivity. It is a *two-section W8JK*. The approximate free-space gain using #12 copper wire is 4.9 dBi with λ/8 spacing and 5.4 dBi with λ/4 spacing. Directive patterns are given in **Figs 77** for free space, and in **Fig 78** for heights of 1 λ and λ/2 above flat ground.

The impedance between elements at the point where the phasing line is connected is of the order of several thousand

Fig 76—A 4-element array combining collinear broadside elements and parallel end-fire elements, popularly known as a two-section W8JK array.

Fig 77—Free-space E-plane pattern for the antenna shown in Fig 76, with λ/8 spacing. The elements are parallel to the 90°-270° line in this diagram. Less than a 1° change in half-power beamwidth results when the spacing is changed from λ/8 to λ/4.

Fig 78—Elevation-plane pattern for the 4-element antenna of Fig 76 when mounted horizontally at two heights over flat ground. Solid line = 1 λ high; dashed line = λ/2 high.

ohms. The SWR with an unmatched line consequently is quite high, and this system should be constructed with open-wire line (500 or 600 Ω) if the line is to be resonant. With λ/4 element spacing the SWR on a 600 Ω line is estimated to be in the vicinity of 3 or 4:1.

To use a matched line, you could connect a closed stub 3λ/16 long at the transmission-line junction shown in Fig 76. The transmission line itself can then be tapped on this matching section at the point resulting in the lowest line SWR. This point can be determined by trial.

This type of antenna can be operated on two bands having a frequency ratio of 2 to 1, if a resonant feed line is used. For example, if you design for 28 MHz with λ/4 spacing between elements, you can also operate on 14 MHz as a simple 2-element end-fire array having λ/8 spacing.

Combination Driven Arrays

You can readily combine broadside, end-fire and collinear elements to increase gain and directivity, and this is in fact usually done when more than two elements are used in an array. Combinations of this type give more gain, in a given amount of space, than plain arrays of the types just described. Since the combinations that can be worked out are almost endless, this section describes only a few of the simpler types.

The accurate calculation of the power gain of a multi-element array requires a knowledge of the mutual impedances between all elements, as discussed in earlier sections. For approximate purposes it is sufficient to assume that each set (collinear, broadside, end-fire) will have the gains as given earlier, and then simply add up the gains for the combination. This neglects the effects of cross-coupling between sets of elements. However, the array configurations are such that the mutual impedances from cross-coupling should be relatively small, particularly when the spacings are λ/4 or more, so the estimated gain should be reasonably close to the actual gain. Alternatively, an antenna modeling program, such as *EZNEC*, can give good estimates of all parameters for a real-world antenna, providing that you take care to model all applicable parameters.

FOUR-ELEMENT DRIVEN ARRAYS

The array shown in **Fig 79** combines parallel elements with broadside and end-fire directivity. The smallest array (physically)—$3\lambda/8$ spacing between broadside and $\lambda/8$ spacing between end-fire elements—has an estimated gain of 6.5 dBi and the largest—$3\lambda/4$ and $\lambda/4$ spacing, respectively—about 8.4 dBi. Typical directive patterns for a $\lambda/4 \times \lambda/2$ array are given in **Figs 80** and **81**.

The impedance at the feed point will not be purely resistive unless the element lengths are correct and the phasing lines are exactly $\lambda/2$ long. (This requires somewhat less than $\lambda/2$ spacing between broadside elements.) In this

Fig 81—Vertical pattern of the antenna shown in Fig 79 at a mean height of $3\lambda/4$ (lowest elements $\lambda/2$ above flat ground) when the antenna is horizontally polarized. For optimum gain and low wave angle the mean height should

case the impedance at the junction is estimated to be over 10 kΩ. With other element spacings the impedance at the junction will be reactive as well as resistive, but in any event the SWR will be quite large. An open-wire line can be used as a resonant line, or a matching section may be used for non-resonant operation.

EIGHT-ELEMENT DRIVEN ARRAYS

The array shown in **Fig 82** is a combination of collinear and parallel elements in broadside and end-fire directivity. Common practice in a wire antenna is to use $\lambda/2$ spacing for the parallel broadside elements and $\lambda/4$ spacing for the end-fire elements. This gives a free-space gain of about 9.1 dBi. Directive patterns for an array using these spacings are similar to those of Figs 80 and 81, but are somewhat sharper.

The SWR with this arrangement will be high. Matching stubs are recommended for making the lines non-resonant. Their position and length can be determined as described in Chapter 26.

Fig 79—Four-element array combining both broadside and end-fire elements.

Fig 80—Free-space H-plane pattern of the 4-element antenna shown in Fig 79.

Fig 82—Eight-element driven array combining collinear and parallel elements for broadside and end-fire directivity.

This system can be used on two bands related in frequency by a 2-to-1 ratio, providing it is designed for the higher of the two, with $3\lambda/4$ spacing between the parallel broadside elements and $\lambda/4$ spacing between the end-fire elements. On the lower frequency it will then operate as a 4-element antenna of the type shown in Fig 79, with $3\lambda/8$ broadside spacing and $\lambda/8$ end-fire spacing. For two-band operation a resonant transmission line must be used.

PHASING ARROWS IN ARRAY ELEMENTS

In the antenna diagrams of preceding sections, the relative direction of current flow in the various antenna elements and connecting lines was shown by arrows. In laying out any antenna system it is necessary to know that the phasing lines are properly connected; otherwise the antenna may have entirely different characteristics than anticipated. The phasing may be checked either on the basis of current direction or polarity of voltages. There are two rules to remember:

1) In every $\lambda/2$ section of wire, starting from an open end, the current directions reverse. In terms of voltage, the polarity reverses at each $\lambda/2$ point, starting from an open end.

2) Currents in transmission lines always must flow in opposite directions in adjacent wires. In terms of voltage, polarities always must be opposite.

Examples of the use of current direction and voltage polarity are given at A and B, respectively, in **Fig 83**. The $\lambda/2$ points in the system are marked by small circles. When current in one section flows toward a circle, the current in the next section must also flow toward it, and vice versa. In the 4-element antenna shown at A, the current in the upper right-hand element cannot flow toward the transmission line because then the current in the right-hand section of the phasing line would have to flow upward and thus would be

flowing in the same direction as the current in the left-hand wire. The phasing line would simply act like two wires in parallel in such a case. Of course, all arrows in the drawing could be reversed, and the net effect would be unchanged.

C shows the effect of transposing the phasing line. This transposition reverses the direction of current flow in the lower pair of elements, as compared with A, and thus changes the array from a combination collinear and end-fire arrangement into a collinear-broadside array.

The drawing at D shows what happens when the transmission line is connected at the center of a section of phasing line. Viewed from the main transmission line, the two parts of the phasing line are simply in parallel, so the half wavelength is measured from the antenna element along the upper section of phasing line and thence along the transmission line. The distance from the lower elements is measured in the same way. Obviously, the two sections of phasing line should be the same length. If they are not, the current distribution becomes quite complicated; the element currents are neither in-phase nor 180° out-of-phase, and the elements at opposite ends of the lines do not receive the same current. To change the element current phasing at D into the phasing at A, simply transpose the wires in one section of the phasing line. This reverses the direction of current flow in the antenna elements connected to that section of phasing line.

BIBLIOGRAPHY

Source material and more extended discussion of topics covered in this chapter can be found in the references given below and in the textbooks listed at the end of Chapter 2.

D. W. Atchley, H. E. Stinehelfer, and J. F. White, "360°-Steerable Vertical Phased Arrays," *QST*, Apr 1976, pp 27-30.

G. H. Brown, "Directional Antennas," *Proc. IRE*, Vol 25, No. 1, Jan 1937, pp 78-145.

G. H. Brown, R. F. Lewis and J. Epstein, "Ground Systems as a Factor in Antenna Efficiency," *Proc. IRE*, Jun 1937, pp 753-787.

G. H. Brown and O. M. Woodward, Jr., "Experimentally Determined Impedance Characteristics of Cylindrical Antennas," *Proc. IRE*, Apr 1945.

L. B. Cebik, "Two Limitations of NEC-4", **www.cebik. com/model/fd.html**.

A. Christman, "Feeding Phased Arrays: An Alternate Method," *Ham Radio*, May 1985, pp 58-59, 61-64.

J. Devoldere, *ON4UN's Low-Band DXing*, 4th ed. (Newington, CT: ARRL, 2005).

EZNEC is an antenna-modeling computer program for Microsoft Windows. See **eznec.com** for full information.

F. Gehrke, "Vertical Phased Arrays," in six parts, *Ham Radio*, May-Jul, Oct and Dec 1983, and May 1984.

C. Harrison, Jr, and R. King, "Theory of Coupled Folded Antennas," *IRE Trans on Antennas and Propagation*, Mar 1960, pp131-135.

W. Hayward and D. DeMaw, *Solid State Design for the Radio Amateur* (Newington, CT: ARRL, 1977).

ANT0376

Fig 83—Methods of checking the phase of currents in elements and phasing lines.

W. Hayward, *Radio Frequency Design* (Newington, CT: ARRL, 1994).

H. Jasik, *Antenna Engineering Handbook*, 1st ed. (New York: McGraw-Hill, 1961). Later editions are edited by Richard C. Johnson.

R. King and C. Harrison, Jr, "Mutual and Self-Impedance for Coupled Antennas," *Journal of Applied Physics* , Vol 15, Jun 1944, pp 481-495.

R. King, "Self- and Mutual Impedances of Parallel Identical Antennas," *Proc. IRE*, Aug 1952, pp 981-988.

R. W. P. King, *Theory of Linear Antennas* (Cambridge, MA: Harvard Univ Press, 1956), p 275ff.

H. W. Kohler, "Antenna Design for Field-Strength Gain," *Proc. IRE*, Oct 1944, pp 611-616.

J. D. Kraus, "Antenna Arrays with Closely Spaced Elements," *Proc. IRE*, Feb, 1940, pp 76-84.

J. D. Kraus, *Antennas*, 2nd ed. (New York: McGraw-Hill Book Co., 1988).

Johnson, Richard C., *Antenna Engineering Handbook*, 3rd ed. (New York: McGraw-Hill Inc., 1993). This is a later edition of the volume by the same name edited by H. Jasik.

E. A. Laport, *Radio Antenna Engineering* (New York: Mc-Graw-Hill Book Co, 1952).

J. L. Lawson, "Simple Arrays of Vertical Antenna Elements," *QST*, May 1971, pp 22-27.

P. H. Lee, N6PL *The Amateur Radio Vertical Antenna Handbook*, 2nd ed. (Hicksville, NY: CQ Publishing, Inc., 1984).

R. W. Lewallen, "Baluns: What They Do and How They Do It," *The ARRL Antenna Compendium, Vol 1* (Newington: ARRL, 1985). Also available for viewing at **eznec.com/Amateur/Articles/Baluns.pdf**.

R. Lewallen, "The Impact of Current Distribution on Array Patterns," Technical Correspondence, *QST*, Jul 1990, pp 39-40. Also available for viewing at **eznec.com/Amateur/Articles/Current_Dist.pdf**.

R. Lewallen, "*MININEC*—The Other Edge of the Sword", *QST*, Feb 1991, pp 18-22. *ELNEC*, referenced in the article, is no longer available.

M. W. Maxwell, "Some Aspects of the Balun Problem," *QST*, Mar 1983, pp 38-40.

J. Sevick, "The Ground-Image Vertical Antenna," *QST*, Jul 1971, pp 16-19, 22.

J. Sevick, "The W2FMI Ground-Mounted Short Vertical," *QST*, Mar 1973, pp 13-28,41.

E. J. Wilkinson, "An N-Way Hybrid Power Divider," *IRE Transactions on Microwave Theory and Techniques*, Jan, 1960.

Radio Broadcast Ground Systems, available from Smith Electronics, Inc, 8200 Snowville Rd, Cleveland, OH 44141.

Appendix A—*EZNEC-ARRL* Examples

This appendix contains step-by-step procedures using *EZNEC-ARRL* (included on the *Antenna Book* CD) to illustrate various topics discussed in the main chapter. A standard *EZNEC* program type of v. 4.0 or later may also be used. Different versions, program types and calculating engines may give results that are slightly different from those shown in the examples. However, any differences should be insignificantly small.

EZNEC Example—Mutual Coupling

Illustrates the effect of mutual coupling on feed-point impedance. Open the **ARRL_Cardioid.EZ** file, which is mounted over "perfect" ground. Click the **View Ant** button to see a diagram of the antenna, a 2-element array of vertical elements. Click on the **Wires** line in the main window to open the Wires Window. Click the button at the left of the Wire 2 line, and then press the **Delete** key on your keyboard to delete wire #2. After clicking **Ok**, note that one of the verticals has disappeared from the View Antenna display, leaving a single element. Click **Src Dat** and note that the feed-point impedance of this single vertical is about $37 + j\,1\,\Omega$--it's very nearly resonant.

Next, in the Wires Window, open the **Edit** menu at the top and click **Undo delete wire(s)** to restore the second element. Click **Src Dat** again and notice that the feed-point

impedance of wire #1 is now about $21 - j\,19\,\Omega$. The feed-point impedance of the second element, which is identical to the first, is about $52 + j\,21\,\Omega$. This difference, and the change from the self-impedance of $37 + j\,1\,\Omega$, is due to mutual coupling. As you see, it's not at all a minor effect.

As an additional exercise, change the magnitude or phase angle of the source at the base of wire #2 (click **Sources** in the main window), and see how this changes the feed-point impedances of both elements. You should be able to confirm each of the four points enumerated in the **MUTUAL COUPLING** section.

EZNEC Example—Nulls

Illustrates the effect of current magnitude on nulls and gain. Again, open the **ARRL_Cardioid.EZ** file. Click the **FF Plot** button to generate the azimuth pattern of an ideal array. Save the plot for future reference as follows: In the plot window, open the **File** menu and select **Save Trace As**. Enter the name **Cardioid** and click **Save**. Now, in the main window click on the **Sources** line to open the Sources Window. Change the magnitude of source 1 from 1 to 1.1, and of source 2 from 1 to 0.9 and press **Enter** on your keyboard so that *EZNEC-ARRL* will accept the last change.

Click **FF Plot** to generate a pattern with the new currents. In the plot window, open the File menu and select **Add**

Trace. Enter the name **Cardioid** and click Open. You should now see the original plot and new plot overlaid. Notice that the null is much less deep with the altered currents, but the forward patterns are nearly identical. By clicking on the names of the traces, **Primary** and **Cardioid**, you can see in turn the gain and front-to-back ratio of each of the traces. The original, **Cardioid**, has a front-to-back ratio of about 32 dB, while Primary, the new plot, has a ratio of about 22.5 dB. The forward gain, however, differs by only 0.02 dB, a completely insignificant amount.

EZNEC Example—"Phasing-Line" Feed

Illustrates the effect of using a "phasing-line" feed. Open the **ARRL_CardTL.EZ** file. This is a model of an array fed with transmission lines whose lengths were designed using the *Arrayfeed1* program to take into account the actual load impedances of elements in a phased array. This model is mounted over "perfect" ground.

Click the **View Ant** button to show the array. Note that the lengths of the lines from the source (circle) to the elements don't represent the actual physical lengths of the lines. In the main window, click on the **Trans Lines** line to open the Transmission Lines window. In it you can see that the lengths of the feed lines, both of which are connected to the same source, are about 81° and 155°, a difference of 74° rather than 90°.

In the main window, click the **Currents** button and take a look at the current shown for segment 1 of wires 1 and 2. These are the currents at the element feed points. The ratio of the magnitude of currents is 4.577/4.561 = 1.003, and the phase difference is −56.3°−(−147.5°) = 91.2°. (A more accurate determination of feed-line lengths with program *Arrayfeed1* gives lengths of 80.61° and 153.70°, resulting in a current ratio of 1.000 at a phase of 90.02°. But the resulting pattern is very nearly the same.) But let's see what happens when we make the lines exactly 90° different in length.

First, click the **FF Plot** button to generate the azimuth pattern of the original model. Save the plot for future reference as follows: In the plot window, open the **File** menu and select **Save Trace As**. Enter the name **CardTL** and click **Save**. Now in the Transmission Lines Window, change the length of line number 1 from 80.56° to 90°. *Important:* In the line 1 Length box, enter **90d** to make the line 90° long. If you omit the **d**, it will become 90 meters long! Similarly, change the length of line 2 to 180° by entering **180d** in the line 2 Length box, then press **Enter** on your keyboard so that *EZNEC* will accept the last change.

Click **FF Plot** to generate a pattern with the new line lengths. In the plot window, open the **File** menu and select **Add Trace**. Enter the name **CardTL** and click **Open**. You should now see the original plot and new plot overlaid together. Notice that the gain of the modified model is about 1 dB greater than the original, but the front-to-back ratio has deteriorated to about 10 dB.

Experiment with different combinations of line lengths that differ by 90°--for example, 45° and 135° (don't forget the '**d**'!), or change the impedance of one or both lines and you'll see that you can get a wide variety of patterns. None, however, are likely to be as close to the ideal cardioid pattern as the original.

Broadband Antenna Matching

Antenna systems that provide a good impedance match to the transmitter over a wide frequency range have been a topic of interest to hams for many years. Most emphasis has been focused on the 80-meter band since a conventional half-wave dipole will provide better than 2:1 SWR over only about one-third of the 3.5 to 4.0 MHz band. The advantage of a broadband match is obvious—fewer adjustments during tune-up and an antenna tuner may not be required.

This chapter was written by Frank Witt, AI1H, who has written numerous articles in *QST* and in *The ARRL Antenna Compendium* series on this subject. See the Bibliography for details.

The term *broadband antennas* has frequently been used to describe antenna systems that provide a wideband impedance match to the transmitter. This is something of a misnomer, since most antennas are good radiators over a wide range of frequencies and are therefore "broadband antennas" by definition. The problem is getting the energy to the antenna so it can be radiated. Antenna tuners solve this problem in some cases, although losses in transmission lines, baluns and the antenna tuner itself can be excessive. Also worthy of mention is that antenna directional properties are usually frequency dependent. In this chapter, we discuss broadbanding the impedance match to the transmitter only.

GENERAL CONCEPTS

The Objective

Fig 1 shows a simplified system: the transmitter, an SWR meter and the transmitter load impedance. Modern transceivers are designed to operate properly into a 50-Ω load and they will deliver full power into the load impedance, at their rated level of distortion, when the SWR is less than about 1.5:1. Loads beyond this limit may cause the transceiver to protect itself by lowering the output power.

Many transceivers have built-in automatic antenna tuners that permit operation for loads outside the 1.5:1 SWR range, but the matching range is often limited, particularly on the lower-frequency bands. In practice, barefoot operation is simplified if the load SWR is held to less than 2:1.

For high-power amplifiers, it is also best to keep the load SWR to less than about 2:1, since output tuning components are commonly rated to handle such loads. You can see that the primary function of the SWR meter in Fig 1 is to measure the suitability of the load impedance so far as the transmitter is concerned. Henceforth, we will use the term *load SWR* as a description of the transmitter's load.

The SWR meter is actually reading a circuit condition at a single point in the system. In fact, the meter really measures magnitude of the reflection coefficient, but is calibrated in SWR. The relationships between the complex load impedance, Z_L, the magnitude of the reflection coefficient, $|\rho|$, and the load SWR are as follows:

$$|\rho| = \left| \frac{Z_L - 50}{Z_L + 50} \right| \qquad \text{(Eq 1)}$$

Fig 1—Basic antenna system elements at the output of a transmitter.

$$SWR = \frac{1 + |\rho|}{1 - |\rho|} \qquad \text{(Eq 2)}$$

where 50 Ω is used as the reference impedance, since the design load impedance for the transmitter is assumed to be 50 Ω.

An important point is that you need not know the output impedance of the transmitter to design a broadband matching network. The issue of the actual value of the output impedance of typical RF power amplifiers is a matter of continuing controversy in amateur circles. Fortunately, this issue is not important for the design of broadband matching networks, since the load SWR is independent of the output impedance of the transmitter. Our objective is to design the matching network so that the load SWR (with a 50-Ω reference resistance) is less than some value, say 2:1, over as wide a band as possible.

Resonant Antennas

The broadband matching techniques described here apply to antennas operating near resonance. Typical resonant antennas include half-wave dipoles, quarter-wave verticals over a ground plane and full-wave loops. To design a broadband matching network, you must know the antenna feed-point impedance near resonance. **Fig 2** shows the antenna-impedance equivalent circuit near resonance. Although the series RLC circuit is an approximation, it is good enough to allow us to design matching networks that significantly increase the band over which a good match to the transmitter is achieved.

Note that the impedance is defined by F_0, the resonant frequency, R_A, the antenna resistance at resonance, and Q_A, the antenna Q. R_A is actually the sum of the radiation resistance and any loss resistance, including conductor losses and losses induced by surrounding objects, such as the ground below the antenna. R_A is frequency dependent, but it is sufficient to assume it is fixed during the matching network design process. Minor adjustments to the matching network will correct for the frequency dependence of R_A.

The antenna resistance and Q depend on the physical properties of the antenna itself, the properties of ground and the height above ground. Consider as an example an 80-meter horizontal half-wave dipole made from #12 wire located over average ground (dielectric constant = 13 and conductivity = 5 mS/m). **Figs 3** and **4** show how feed-point resistance and Q vary with height. It is clear from these figures that there are wide gyrations in antenna parameters. The better these parameters are known, the more successful we will be at designing the broadband matching network. For horizontal dipoles, Figs 3 and 4 may be used to get a good idea of antenna resistance and Q, so long as the height is scaled in proportion to wavelength. For example, a 160-meter dipole at a height of 100 feet would have about the same resistance and Q as an 80-meter dipole at 50 feet.

For optimum results, the resistance and Q can be

Fig 3—Feed-point resistance (solid line) for 80-meter horizontal dipole at resonance versus height over ground. The free-space value is shown as a dashed line.

Fig 4—Antenna Q for 80-meter horizontal dipole (solid line) versus height. The free-space value is shown as a dashed line.

Fig 2—The equivalent circuit of a resonant antenna. The simple series RLC approximation applies to many resonant antenna types, such as dipoles, monopoles, and loops. R_A, Q_A and F_0 are properties of the entire antenna, as discussed in the text.

determined from computer simulation (using a program like *EZNEC*, for example) or measurement (using a low power SWR/Z meter such as the MFJ-259B or the Autek Research VA1 or RF-1). R_A can be computed using SWR measurements at resonance. **Fig 5** shows the typical bowl-shaped SWR curve as a function of frequency for a resonant antenna. S_0 is the SWR at resonance. You must take into account the loss of the feed line if the measurement must be made at the end of a long 50-Ω transmission line. If the line loss is low or if the measurement is made at the antenna terminals, the formulas given below apply.

For $R_A > 50\ \Omega$

$$R_A = S_0 \times 50 \qquad \text{(Eq 3)}$$

For $R_A < 50\ \Omega$

$$R_A = \frac{50}{S_0} \qquad \text{(Eq 4)}$$

There is an ambiguity, since we do not know if R_A is greater than or less than 50 Ω. A simple way of resolving this ambiguity is to take the same SWR measurement at resonance with a 10-Ω non-inductive resistor added in series with the antenna impedance. If the SWR goes up, $R_A > 45\ \Omega$. If the SWR goes down, $R_A < 45\ \Omega$. This will resolve the ambiguity.

Q_A may be determined by measuring the SWR bandwidth. Define BW_2 as the bandwidth over which the resonant antenna SWR is less than 2:1 (in the same units as F_0). See Fig 5.

For $R_A > 50\ \Omega$

$$Q_A = \frac{F_0}{BW_2}\sqrt{2.5\,S_0 - S_0^2 - 1} \qquad \text{(Eq 5)}$$

For $R_A < 50\ \Omega$

$$Q_A = \frac{F_0}{BW_2 \times S_0}\sqrt{2.5\,S_0 - S_0^2 - 1} \qquad \text{(Eq 6)}$$

Again, you must take into account the loss of the feed

line if you make the measurement at the end of a long 50-Ω transmission line.

For horizontal and inverted-V half-wave dipoles, a very good approximation for the antenna Q when R_A is known is given by:

$$Q_A = \frac{93.9\left[\ln\dfrac{8110}{D\,F_0} - 1\right]}{R_A} \qquad \text{(Eq 7)}$$

where D = the diameter of wire, in inches.

Loss

When you build a resonant antenna with some matching scheme designed to increase the bandwidth, you might overlook the loss introduced by the broadband matching components. Loss in dB is calculated from:

$$\text{Loss} = -10\log\frac{\text{Power radiated by antenna}}{\text{Total power from transmitter}} \qquad \text{(Eq 8)}$$

or, alternatively, define efficiency in % as

$$\text{Efficiency} = \frac{100 \times \text{Power radiated by antenna}}{\text{Total power from transmitter}} \qquad \text{(Eq 9)}$$

Fig 6—Matching the dipole with a complementary RLC network greatly improves the SWR characteristics, nearly 1:1 across the 3.5-MHz band. However, the relative loss at the band edges is greater than 5 dB.

Fig 5—SWR at the antenna versus frequency in the vicinity of resonance.

An extreme degree of bandwidth broadening of an 80-meter dipole is illustrated in **Fig 6**. This approach is not recommended, but it is offered here to make a point. The broadening is accomplished by adding resistive losses. From network theory we obtain the RLC (resistor, inductor, capacitor) matching network shown. The network provides the complement of the antenna impedance. Note that the SWR is virtually 1:1 over the entire band (and beyond), but the efficiency falls off dramatically away from resonance.

The band-edge efficiency of 25 to 30% shown in Fig 6 means that the antenna has about 5 to 6 dB of loss relative to an ideal dipole. At the band edges, 70 to 75% of the power delivered down the transmission line from the transmitter is heating up the matching-network resistor. For a 1-kW output level, the resistor must have a power rating of at least 750 W! Use of an RLC complementary network for broadbanding is not recommended, but it does illustrate how resistance (or losses) in the matching network can significantly increase the apparent antenna SWR bandwidth.

The loss introduced by any broadband matching approach must be taken into consideration. Lossy matching networks will usually provide more match bandwidth improvement than less lossy ones.

SIMPLE BROADBAND MATCHING TECHNIQUES

The Cage Dipole

You can increase the match bandwidth of a single-wire dipole by using a thick radiator, one with a large diameter. The gain and radiation pattern are essentially the same as that of a thin-wire dipole. The radiator does not necessarily have to be solid; open construction such as shown in **Fig 7** may be used.

The theoretical SWR response of an 80-meter cage dipole having a 6-inch diameter is shown in **Fig 8**. BW_2 for this antenna fed with 50-Ω line is 287 kHz, and the Q is approximately 8. Its 2:1-SWR frequency range is 1.79 times broader than a dipole with a Q of 13, typical for thin-wire dipoles.

There are other means of creating a thick radiator, thereby gaining greater match bandwidth. The bow-tie and the fan dipole make use of the same Q-lowering principle as the cage for increased match bandwidth. The broadbanding techniques described below are usually more practical than the unwieldy cage dipole.

Stagger-Tuned Dipoles

A single-wire dipole exhibits a relatively narrow bandwidth in terms of coverage for the 3.5 to 4.0-MHz band. A technique that has been used for years to cover the entire band is to use two dipoles, one cut for the CW portion and one for the phone portion. The dipoles are connected in parallel at the feed point and use a single feeder. This technique is known as *stagger tuning*.

Fig 9 shows the theoretical SWR response of a pair of stagger-tuned dipoles fed with 50-Ω line. No mutual coupling between the wires is assumed, a condition

Fig 8—Theoretical SWR versus frequency response for a cage dipole of length 122 feet 6 inches and a spreader diameter of 6 inches, fed with 50-Ω line. The 2:1-SWR bandwidth frequencies are 3.610 and 3.897 MHz, with a resulting BW_2 of 287 kHz.

Fig 7—Construction of a cage dipole, which has some resemblance to a round birdcage. The spreaders need not be of conductive material, and should be lightweight. Between adjacent conductors, the spacing should be 0.02 λ or less. The number of spreaders and their spacing should be sufficient to maintain a relatively constant separation of the radiator wires.

Fig 9—Theoretical SWR response of two stagger-tuned dipoles. They are connected in parallel at the feed point and fed with 50-Ω line. The dipoles are of wire such as #12 or #14, with total lengths of 119 and 132 feet.

that would exist if the two antennas were mounted at right angles to one another. As Fig 9 shows, the SWR response is less than 1.9:1 across the entire band.

A difficulty with such crossed dipoles is that four supports are required for horizontal antennas. A more common arrangement is to use inverted V dipoles with a single support, at the apex of each element. The radiator wires can also act as guy lines for the supporting mast.

When the dipoles are mounted at something other than a right angle, mutual coupling between them comes into play. This causes interaction between the two elements—tuning of one by length adjustment will affect the tuning of the other. The interaction becomes most critical when the two dipoles are run parallel to each other, suspended by the same supports, and the wires are close together. Finding the optimum length for each dipole for total band coverage can become a tedious and frustrating process.

Fig 10—At A, details of the inverse-fed ground-plane at W4PK. The inset shows the feed-point details. Keep the two sets of radials as close to 90· as possible. Don't try to resonate the antenna by adjusting radial lengths. At B, SWR curve of the inverse-fed ground plane antenna with stagger-tuned radials. The objective is to have a low SWR for both the CW and SSB 80/75-meter DX windows.

Stagger-Tuned Radials

A variation of the use of stagger tuning has been applied by Sam Leslie, W4PK. See his article entitled "Broadbanding the Elevated, Inverse-Fed Ground Plane Antenna" in *The ARRL Antenna Compendium, Vol 6*. An existing tower with a large beam and VHF/UHF antennas on top is used as an 80-meter monopole. See **Fig 10A**. The feed point is part way up the tower, at a point where the metal above it makes up an electrical quarter wavelength. Four elevated quarter-wave radials are used as a ground plane. The radials droop away from the tower. They are joined together at the tower but not connected to the tower. The antenna is fed with 50-Ω coax and an impedance step-down autotransformer (50:22 Ω unun) located at the tower. The shield of the coax is carried through the transformer and connected to the tower. The coax "hot side" is connected to the junction of the radials. A Q-section made from two paralleled RG-59 coax cables ($Z_0 = 75/2 = 37.5$ Ω) may be used instead of the autotransformer.

The broadband match is achieved by cutting two opposing radials for one end of the desired match range (75 meters) and cutting the other two for the other end of the range (80 meters). See Fig 10B for the resultant SWR versus frequency characteristic.

FEED-LINE IMPEDANCE MISMATCHING

The simplest broadband matching network is a transformer at the junction of the transmission line and the antenna. See Frank Witt's article entitled "Match Bandwidth of Resonant Antenna Systems" in October 1991 *QST*. Observe that the impedance of the series RLC resonant antenna model of Fig 2 increases at frequencies away from resonance. The result is that more bandwidth is achieved when SWR at resonance is not exactly 1:1. For example, if the antenna is fed with a low-loss 50-Ω transmission line, the maximum SWR bandwidth is obtained if the effective $R_A = 50/1.25 = 40$ Ω. The improvement in BW_2, the 2:1 SWR bandwidth, over a perfect match at resonance is only 6%, however. This condition of $R_A = 40$ Ω can be achieved by installing a transformer at the junction of the feed line and the antenna.

If the line loss is larger, you can gain more benefit in terms of bandwidth by deliberately mismatching at the antenna. If the matched-line loss is 2 dB, the improvement rises to 18%. To achieve this requires an $R_A = 28.2$ Ω. Again, the improvement over a perfect match at resonance is modest.

It is interesting to compare the 2:1 SWR bandwidth (at the transmitter end of the line) for the case of a lossless line versus the case of 2-dB matched-line loss. BW_2 for the lossy line case is 1.95 times that of the lossless line case, so substantial match bandwidth improvement occurs, but at the cost of considerable loss. The band edge loss for the lossy-line case is 3 dB!

This example is provided mostly as a reference for comparison with the more desirable broadbanding

PARALLEL-TUNED CIRCUITS AT THE ANTENNA TERMINALS

As mentioned previously, a resonant antenna has an equivalent circuit that may be represented as a series RLC circuit. We can cancel out some of the antenna reactance away from resonance with a parallel-tuned circuit connected across the antenna terminals. The impedance level of the parallel-tuned circuit must be low enough to be effective and must have the same resonant frequency as the antenna. You can use a parallel-tuned circuit made with lumped LC components or with transmission-line segments. A quarter-wave transmission line with a short at the far end, or a half-wave line with an open at the far end, each behave like a parallel-tuned LC circuit.

The Double Bazooka

The response of the controversial *double bazooka* antenna is shown in **Fig 11**. This antenna actually consists of a dipole with two quarter-wave coaxial resonator stubs connected in series. The stubs are connected across the antenna terminals.

Not much bandwidth enhancement is provided by this resonator connection because the impedance of the matching network is too high. The antenna offers a 2:1-SWR bandwidth frequency range that is only 1.14 times that of a simple dipole with the same feeder. And the bandwidth enhancement is partially due to the "fat" antenna wires composed mostly of the coax shield. No

Fig 11—The double bazooka, sometimes called a coaxial dipole. The antenna is self-resonant at 3.75 MHz. The resonator stubs are 43.23-foot lengths of RG-58A coax.

improvement in antenna gain or pattern over a thin-wire dipole can be expected from this antenna.

The Crossed Double Bazooka

A modified version of the double-bazooka antenna is shown in **Fig 12**. In this case, the impedance of the matching network is reduced to one-fourth of the impedance of the standard double-bazooka network. The lower impedance provides more reactance correction, and hence increases the bandwidth frequency range noticeably, to 1.55 times that of a simple dipole. Notice, however, that the efficiency of the antenna drops to about 80% at the 2:1-SWR points. This amounts to a loss of approximately 1 dB. The broadbanding, in part, is caused by the losses in the coaxial resonator stubs (made of RG-58A coax), which have a remarkably low Q (only 20).

MATCHING NETWORK DESIGN

Optimum Matching

You can improve the match bandwidth by using a transformer or a parallel-tuned circuit at the antenna terminals. A combination of these two techniques can yield a very effective match bandwidth enhancement. Again, you can make the impedance transformation and implement the tuned circuit using lumped-circuit elements (transformers, inductors and capacitors) or with distributed-circuit elements (transmission lines).

In 1950, an article by R. M. Fano presented the theory of broadband matching of arbitrary impedances. This classic work was limited to lossless matching networks.

Unfortunately, matching networks realized with transmission lines have enough loss to render the Fano results useful as only a starting point in the design process. A theory of optimum matching with lossy matching networks was presented in an article by Frank Witt entitled "Optimum Lossy Broadband Matching Networks for Resonant Antennas" that appeared in April 1990 *RF Design* and was summarized and extended in "Broadband Matching with the Transmission Line Resonator," in *The ARRL Antenna Compendium Vol 4*.

Using a matching network, the 2:1 SWR bandwidth can be increased by a factor of about 2.5. Instead of the familiar bowl-shaped SWR versus frequency characteristic seen in Fig 5, the addition of the matching network yields the W-shaped characteristic of **Fig 13**. The maximum SWR over the band is S_M. The band edges are F_L and F_H. Thus the bandwidth, BW, and the center frequency, F_0, are

$$BW = F_H - F_L \tag{Eq 10}$$

$$F_0 = \sqrt{F_H \times F_L} \tag{Eq 11}$$

Fig 14 shows the pertinent equivalent circuit for a typical broadband antenna system. The parallel LC matching network is defined by its resonant frequency, F_0 (which is the same as the resonant frequency of the antenna), its Q and its impedance level. The impedance level is the reactance of either the matching network inductance or capacitance at F_0. The optimum transmitter load resistance,

Fig 13—W-shaped SWR versus frequency characteristic that results when a transformer and parallel LC matching network are used.

Fig 12—The crossed double bazooka yields bandwidth improvement by using two quarter-wave resonators, parallel connected, as a matching network. As with the double bazooka, the resonator stubs are 43.23-foot lengths of RG-58A coax.

Fig 14—Assumed equivalent circuit for the broadband matching system. The antenna and the matching network have the same resonant frequency.

R_G, is achieved using an impedance transformer between the transmitter and the input to the parallel-tuned circuit. Thus for a transmitter whose optimum load resistance is 50 Ω, the required impedance transformer would have an impedance transformation ratio of 50:R_G.

The goal is to keep the SWR over the band as low as possible. There is a best or minimum value of S_M that may be achieved over the entire band. It depends on the desired match bandwidth and the Q's of the antenna and matching network and is given by the following formula:

$$S_{M\,min} = \frac{\sqrt{B_N^2 + 1} + \sqrt{B_N^2 + 1 + \dfrac{2Q_A}{Q_N}\left(1 + \dfrac{Q_A}{2Q_N}\right)}}{2\left(1 + \dfrac{Q_A}{2Q_N}\right)}$$

(Eq 12)

where $B_N = \dfrac{BW}{F_0}$ and

Q_A = antenna Q

Q_N = matching network Q.

The reactance at resonance of the parallel tuned LC matching network is given by:

$$X_{N0} = \frac{R_A}{Q_A}\left[\left(1 + \frac{Q_A}{2Q_N}\right)S_{M\,min}^2 - \frac{Q_A}{2Q_N}\right]$$

(Eq 13)

where R_A = antenna resistance in Ω.

The transmitter load resistance is calculated from:

$$R_G = \frac{S_{M\,min}\,R_A\,Q_N\,X_{N0}}{R_A + Q_N\,X_{N0}}$$

(Eq 14)

The loss of the matching network is always greatest at the edges of the band. This loss, L_{MNE}, in dB, is given by:

$$L_{MNE} = 10\log\left[1 + \frac{R_A}{Q_N\,X_{N0}}\left(B_N^2 + 1\right)\right]$$

(Eq 15)

Now you have all the information needed to design an optimal broadband matching network. An 80-meter dipole will serve as an example to illustrate the procedure. The following parameters are assumed:

F_L = 3.5 MHz
F_H = 4.0 MHz
R_A = 57.2 Ω
Q_A = 13
Q_N = 40.65

The values of R_A and Q_A are reasonable values for an 80-meter inverted V with an apex 60 feet above ground. Q_N = 40.65 is the calculated value of the Q of a resonator

made from RG-213 or similar cable in the middle of the 80-meter band. The results are:

BW = 0.5 MHz   (from Eq 10)
F_0 = 3.742 MHz   (from Eq 11)
S_{Mmin} = 1.8   (from Eq 12)
X_{N0} = 15.9 Ω (from Eq 13)
R_G = 94.8 Ω (from Eq 14)
L_{MNE} = 1.32 dB   (from Eq 15)

Shown in **Fig 15** is the plot of SWR and matching-network loss versus frequency for this example. The reference resistance for the SWR calculation is R_G or 94.8 Ω. Since the desired load resistance for the transmitter is 50 Ω, we need some means to transform from 94.8 Ω to 50 Ω. The examples given in the rest of this chapter will show a variety of ways of achieving the necessary impedance transformation.

The meaning of X_{N0} = 15.9 Ω is that the inductor and the capacitor in the matching network would each have a reactance of 15.9 Ω at 3.742 MHz. Methods for obtaining a particular value of X_{N0} are shown in the fol-

Fig 15—SWR and matching-network loss for example. Note that S_M is exactly 1.8 and the band-edge loss is exactly 1.32 dB, as calculated.

Fig 16—80-meter dipole example with a 1-λ resonator as the matching network.

lowing examples as well. The particular value of X_{N0} of this example may be obtained with a one-wavelength resonator (open-circuited at the far end) made from RG-213. The system described in this example is shown in **Fig 16**.

The broadband antenna system shown in Fig 16 has a desirable SWR characteristic, but the feed line to the transmitter is not yet present. Fortunately, the same cable segment that makes up the resonator may be used as the feed line. A property of a feed line whose length is a multiple of $\lambda/2$ (an even multiple of $\lambda/4$) is that its input impedance is a near replica of the impedance at the far end. This is exactly true for lossless lines at the frequencies where the $\lambda/2$ condition is true. Fortunately, practical lines have low-enough loss that the property mentioned above is true at the resonant frequency. Off resonance, the desired reactance cancellation we are looking for from the resonant line takes place. The very same design equations apply.

In **Fig 17**, the antenna shown in Fig 16 is moved to the far end of the 1λ resonator. The SWR and loss for this case are shown in **Fig 18**, which should be compared with Fig 15. The SWR is only slightly degraded, but the loss is about the same at the band edges. We have picked up a feed line that is 1λ long (173.5 feet) *and* broadband matching. You can make the SWR curve virtually the same as that of Fig 15 if the transmitter load resistance is increased from 94.8 Ω to 102 Ω. From a practical point of view, this degree of design refinement is unnecessary, but is instructive to know how the SWR characteristic may be controlled. You may apply the same approach when the resonator is an odd multiple of a wavelength, but in that case the transmitter or antenna must be connected $\lambda/4$ from the shorted end.

Chebyshev Matching

Although it is not as efficient from the standpoint of bandwidth improvement and loss, Chebyshev matching is useful for some purposes. This arrangement yields a transmitter load impedance of $50 + j\,0\ \Omega$ at two frequencies in the band. The matching network circuit is the same as the optimum matching case, but the parameters are different. In this case, we assume that the antenna parameters, F_0, R_A and Q_A, the network Q and the maximum SWR over the band are specified. The bandwidth, impedance level and generator resistance are given by:

$$BW = \frac{F_0}{Q_A\,Q_N}$$
$$\left\{\frac{(Q_A + Q_N)\left[(Q_A + 2Q_N)S_M - Q_A\right](S_M - 1)}{S_M}\right\}^{\frac{1}{2}}$$
(Eq 16)

$$X_{N0} = \frac{R_A}{Q_A}\left[S_M + \frac{Q_A}{Q_N}(S_M - 1)\right]$$
(Eq 17)

$$R_G = R_A\left(S_M - \frac{Q_A}{Q_A + Q_N}\right)$$
(Eq 18)

The loss at the band edges is given by Eq 15. The frequencies where the transmitter load is $50 + j\,0\ \Omega$, F_L and F_H, are given by:

$$F_L = \sqrt{F_0^{\;2} + F_M^{\;2}} - F_M$$
(Eq 19)

where

$$F_M = \frac{F_0}{2\,Q_A}\left[(S_M - 1)\left(1 + \frac{Q_A}{Q_N}\right)\right]^{\frac{1}{2}}$$
(Eq 20)

$$F_H = \frac{F_0^{\;2}}{F_L}$$
(Eq 21)

Fig 17—The antenna is at the far end of the 1-λ line. The line does double duty—broadband matching and signal transport.

Fig 18—SWR and loss for a 1-λ 50-Ω feed line. The antenna system model is the one shown in Fig 17.

LC-MATCHING NETWORKS

Before the theory of optimal matching above was developed, Frank Witt, AI1H, described in his article "Broadband Dipoles—Some New Insights" in October 1986 *QST* the basic principle and some applications of LC matching networks. **Fig 19** shows an LC matching network that is a modified version of one originally proposed by Alan Bloom, N1AL. Note that the basic ingredients are present: the parallel-tuned circuit for reactance cancellation and a transformer.

The network also functions as a voltage balun by connecting the shield of the coaxial feed line to the center tap of the inductor. The capacitor is connected across the entire coil to obtain practical element values. The SWR response and efficiency offered by a network of lumped components is shown in **Fig 20**. The 2:1-SWR bandwidth with 50-Ω line is 460 kHz. The design is a Chebyshev match, where SWR = 1:1 is achieved at two frequencies. For the same configuration, more match bandwidth and less loss could have been realized if the optimal-match theory had been applied.

The efficiency at the band edges for the antenna system shown in Fig 20 is 90% (Loss = 0.5 dB). This low loss is due to the high Q of the LC matching network ($Q_N \approx 200$). The very low-impedance level required ($X_{N0} = 12.4 \ \Omega$) cannot be easily realized with practical inductor-capacitor values. It is for this reason that the coil is tapped and serves as an autotransformer with multiple taps. The required impedance transformation ratio of 1:2.8 is easily achieved with this arrangement.

80-Meter DXer's Delight

A version of an antenna system with an LC broadbanding network is dubbed the *80-meter DXer's Delight*. This antenna has SWR minima near 3.5 and 3.8 MHz. A single antenna permits operation with a transmitter load impedance of about 50 Ω in the DX portions of the band, both CW and phone. The efficiency

and SWR characteristic are shown in **Fig 21**.

Fig 22 shows the method of construction. The selection of a capacitor for this application must be made carefully, especially if high power is to be used. For the capacitor described in the caption of Fig 22, the allowable peak power (limited by the breakdown voltage) is 2450 W. However, the allowable average power (limited by the RF current rating of 4 A) is only 88 W! These limits apply at the 1.8:1 SWR points.

Fig 20—Efficient broadband matching with a lumped element LC network. The antenna in this example has a resistance of 72 Ω and a Q of 12. The matching network has an impedance level of 12.4 Ω, and a Q of 200. The feed line is 50-Ω coax, and the matching network provides an impedance step-up ratio of 2.8:1.

Fig 21—The 80-meter DXer's Delight permits operation with a 50-Ω transmitter load in the DX portions of the band, both CW and phone. This network was designed to provide a broadband match for an inverted V with $F_0 = 3.67$ MHz, an antenna resistance of 60 Ω and a Q of 13. The matching network has an impedance level of 9 Ω, and a Q of 220. The feed line is 50-Ω coax, and the matching network provides an impedance step-up ratio of 2.0:1.

Fig 19—A practical LC matching network that provides reactance compensation, impedance transformation and balun action.

Fig 22—A method of constructing the LC broadband matching network. Components must be chosen for high Q and must have adequate voltage and current ratings. The network is designed for use at the antenna feed point, and should be housed in a weather-resistant package. The component values are as follows:

C1—400 pF transmitting mica rated at 3000 V, 4 A (RF)

L1—4.7 μH, $8^1/_2$ turns of B&W coil stock, type 3029 (6 turns per in., $2^1/_2$-in. dia, #12 wire). The LC circuit is brought to midband resonance by adjusting an end tap on the inductor. The primary and secondary portions of the coil have $1^3/_4$ and $2^1/_2$ turns, respectively.

PROPERTIES OF TRANSMISSION-LINE RESONATORS

One way around the power limitations of LC broadband matching networks is to use a transmission line as the resonator. Transmission line resonators, TLRs, typically have higher power-handling capability because the losses, though higher, are distributed over the length of the line instead of being concentrated in the lumped-LC components. Transmission-line resonators must be multiples of a quarter wavelength. For a parallel-tuned circuit, the odd-multiple λ/4 lines must be shorted at the far end and the even-multiple λ/4 lines must be open circuited.

The length of the matching network resonator is n electrical quarter wavelengths. The impedance level, Q, and line length are given by:

$$X_{N0} = \frac{4 Z_0}{n \pi}$$

or, solving for Z_0,

$$Z_0 = \frac{n \pi X_{N0}}{4} \qquad \text{(Eq 22)}$$

$$Q_N = \frac{2.774 \, F_0}{A_0 \, V} \qquad \text{(Eq 23)}$$

$$L_N = \frac{245.9 \, n \, V}{F_0} \qquad \text{(Eq 24)}$$

where

Z_0 = line characteristic impedance in Ω
A_0 = matched line loss in dB per 100 feet
V = velocity factor, and
L_N = line length in feet.

These equations may be used to find the properties of the transmission line resonator in the systems shown in Figs 16 and 17. The line is RG-213 with the following properties:

Z_0 = 50 Ω
V = 0.66
A_0 = 0.4 dB/100 feet at 4 MHz

We need the matched loss at 3.742 MHz. Since the line loss is approximately proportional to $\sqrt{\text{frequency}}$,

$$A_{0F2} = A_{0F1} \sqrt{\frac{F_2}{F_1}} \qquad \text{(Eq 25)}$$

where A_{0F1} and A_{0F2} are the matched line losses at frequencies F_1 and F_2, respectively. Hence,

A_0 = 0.387 dB/100 feet at 3.742 MHz
Q_N = 40.65 $\qquad$ (from Eq 23)

This is the Q of any resonator made from RG-213 for a frequency of 3.742 MHz. It does not matter how many quarter wavelengths (n) make up the cable segment. Earlier we calculated that the required impedance level, X_{N0}, is 15.9 Ω. Therefore, the required impedance level is:

$$Z_0 = \frac{n \pi \times 15.9}{4} = 12.5 \, n \, \Omega \qquad \text{(from Eq 22)}$$

This means that you could use a quarter-wavelength segment with a short at the far end if Z_0 = 12.5 Ω, or a half-wavelength segment with a open at the far end if Z_0 = 25 Ω. Our example used an open-circuited full-wavelength resonator (n = 4) with a Z_0 of 50 Ω. This example was crafted to make this happen (so that it fits RG-213 properties), but it illustrates that some juggling is required to obtain the right resonator properties when it is made from a transmission line, since we are stuck with the cable's characteristic impedance.

The TLR Transformer

A way around the limitation created by available characteristic impedance values is to use the *transmission-line resonator transformer*. The basic idea is to make the connection to the TLR at an intermediate point along the line instead of at the end of the line. It is analogous to using taps on a parallel-tuned LC resonant circuit to achieve transformer action (See Fig 19). The nature of the transformer action is seen in **Fig 23**, where the ends of the transformer are designated 1-1 and 2-2. The impedance ratio of the transformer, N_Z, is approximated by

Fig 23—Transformer action in the TLR. The definition of transformer terminals depends on whether the TLR end is open- or short-circuited. θ is the distance between the minimum of the voltage standing wave (at resonance) and the connection point, expressed as an electrical angle. The distance x is that same distance expressed in feet.

$$N_Z = \sin^2 \theta \qquad \text{(Eq 26)}$$

The distance in feet, x, is given by

$$x = \frac{\theta}{90} \times \frac{\lambda}{4} = \frac{\theta}{90} \times \frac{245.9 \text{ V}}{F_0} \qquad \text{(Eq 27)}$$

This approach may be used for the connection of the TLR to the transmitter or to the antenna or both. An example will help make the power of the TLR transformer clear. We want to broadband match an 80-meter dipole (where F_0 is 3.742 MHz, R_A is 65 Ω and Q_A is 13). The feed line is RG-213 50-Ω cable, and the total distance between the antenna and transmitter is less than 100 feet.

Since we know that $Z_0 = 50$ Ω, we will design a prototype system with a ³/₄ λ TLR (n=3). Since n is odd, the TLR must be shorted at one end, and we will place the short at the transmitter end of the line. The intermediate step of using a prototype system will enable us to design a system with the final TLR, but without transformer action. Then we'll calculate the proper connection points along the TLR. **Fig 24** shows the prototype system and the system with built-in transformers.

Note that the prototype antenna is connected to the open end of the TLR. The prototype generator (transmitter) is connected at a multiple of λ/2 from the antenna. Here, at resonance, an approximate replica of the antenna will appear. We will use primed variables to indicate prototype antenna system elements. The prototype antenna differs from the actual antenna in impedance level, so only R_A will change. F_0 and Q_A remain the same.

Starting with the ³/₄ λ TLR, we have:

$$X_{N0} = 21.2 \text{ Ω} \qquad \text{(from Eq 22)}$$

Fig 24—An optimized antenna system with a ³/₄ λ TLR made from RG-213 coaxial cable. The prototype system at A is a convenient intermediate step in the design process. At B is the configuration with TLR transformers. It has an open stub, L_O, a link, L_L (which serves as the feed line), and a shorted stub, L_S.

The prototype antenna resistance at resonance, R_A', is calculated by rearranging Eq 13.

$$R_G' = \frac{X_{N0} Q_A}{\left(1 + \dfrac{Q_A}{2 Q_N}\right) S_{M\min}{}^2 - \dfrac{Q_A}{2 Q_N}} \qquad \text{(Eq 28)}$$

Earlier we calculated that $Q_N = 40.65$ and $S_{Mmin} = 1.8$. Now we find

$R_A' = 76.3$ Ω   (from Eq 28)
$R_G' = 126.4$ Ω   (from Eq 14)

The electrical angles (in degrees) and connection locations (in feet) are given by

$$\theta_A = \sin^{-1} \sqrt{\frac{R_A}{R_A'}} \qquad \text{(Eq 29)}$$

$$\theta_G = \sin^{-1} \sqrt{\frac{R_G}{R_G'}} \qquad \text{(Eq 30)}$$

$$X_A = \frac{\theta_A}{90} L_1 \qquad \text{(Eq 31)}$$

$$X_G = \frac{\theta_G}{90} L_1 \qquad \text{(Eq 32)}$$

where

$$L_1 = \frac{\lambda}{4} = \frac{245.9 \, V}{F_0}$$

The lengths of the stubs and link of Fig 24 are given by

$L_O = L_1 = x_A$ (Eq 33)

$L_S = x_G$ (Eq 34)

$L_L = 3L_1 - L_O - L_S$ (Eq 35)

Since $L_1 = 43.4$ feet,

$\theta_A = 67.4°$ (from Eq 29)

$\theta_G = 39.0°$ (from Eq 30)

Fig 25—The SWR and loss of the TLR transformer antenna system. At A, the results are shown with the calculated line lengths. At B, the improvement after the lengths were optimized is shown in Table 1. At C, for comparison, SWR and loss for the same setup as at A, but with the stubs removed.

Table 1

Calculated and Optimized Parameters Using TLR Transformers

	Calculated	Optimized
Dipole resonant frequency (F_0)	3.742 MHz	3.710 MHz
Open stub (L_O)	10.9 feet	13.1 feet
Shorted stub (L_S)	18.8 feet	20.1 feet
Link (L_L)	100.4 feet	101.0 feet

$L_O = 10.9$ feet   (from Eq 33)

$L_S = 18.8$ feet   (from Eq 34)

$L_L = 100.4$ feet   (from Eq 35)

These dimensions are summarized in Fig 24. If required, additional 50-Ω cable may be added between the transmitter and the junction of the shorted stub and the link. A remarkable aspect of the TLR transformer, as demonstrated in this example, is that it is a transformer with multiple taps distributed over a great distance, in this case over 100 feet.

The calculated SWR and loss of the antenna system with the TLR transformer are shown in **Fig 25A**. We mentioned earlier that the stub calculations are an approximation. Fig 25 bears this out, but the changes necessary to achieve the optimized results are relatively small. By changing the lengths and dipole resonant frequency slightly, the target optimized SWR characteristic of Fig 25B results. See **Table 1** for a summary of the changes required.

To demonstrate the significant improvement in match bandwidth that the TLR transformer provides, the SWR and loss of the same dipole fed with 100.4 feet of RG-213 cable is shown in Fig 25C. The loss added by the two stubs used to obtain match bandwidth enhancement is negligible (0.2 to 0.5 dB).

A TLR transformer may be used by itself to achieve a low-loss narrow-band impedance transformation, functioning like a λ/4 Q-section. It is different in nature from a Q-section, in that it is a true impedance transformer, while a Q section is an *impedance inverter*. The TLR transformer may be designed into the antenna system and is a useful tool when a narrow-band impedance transformation is needed.

Fig 26—Dipole matching methods. At A, the T match; at B, the gamma match; at C, the coaxial resonator match.

Fig 27—Evolution of the coaxial-resonator-match broadband dipole. At A, a TLR transformer is used to match the feed line to the off-center-fed dipole. The match and dipole are made collinear at B. At C, the balanced transmission-line TLR transformer of A and B is replaced by a coaxial version. Because the shield of the coax can serve as a part of the dipole radiator, the wire adjacent to the coax match may be eliminated, D.

TRANSMISSION-LINE RESONATORS AS PART OF THE ANTENNA

The Coaxial-Resonator Match

This material is condensed from articles that appeared in April 1989 *QST* and *The ARRL Antenna Compendium, Vol 2*. The coaxial-resonator match, a concept based on the TLR transformer, performs the same function as the T match and the gamma match, that is, matching a transmission line to a resonant dipole. These familiar matching devices as well as the coaxial resonator match are shown in **Fig 26**. The coaxial resonator match has some similarity to the gamma match in that it allows connection of the shield of the coaxial feed line to the center of the dipole, and it feeds the dipole off center. The coaxial

Fig 28—Dimensions for the 80-Meter MHz DX Special, an antenna optimized for the phone and CW DX portions of the 3.5-MHz band. The coax segment lengths total to one quarter-wavelength. The overall length is the same as that of a conventional inverted V dipole.

resonator match has a further advantage: It can be used to broadband the antenna system while providing an impedance match.

The coaxial resonator match is a resonant transformer made from a quarter-wave long piece of coaxial cable. **Fig 27** shows the evolution of the coaxial-resonator match. Now it becomes clear why coaxial cable is used for the quarter-wave TLR transformer—interaction between the dipole and the matching network is minimized. The effective dipole feed point is located at the crossover, which is an off-center feed point. In effect, the match is physically located "inside" the dipole. Currents flowing on the inside of the shield of the coax are associated with the resonator; currents flowing on the outside of the shield of the coax are the usual dipole currents. Skin effect provides a degree of isolation and allows the coax to perform its dual function. The wire extensions at each end make up the remainder of the dipole, making the overall length equal to one half-wavelength.

A useful feature of an antenna using the coaxial-resonator match is that the entire antenna is at the same dc potential as the feed-line potential, thereby avoiding charge buildup on the antenna. Hence, noise and the potential of lightning damage are reduced.

Fig 28 shows the detailed dimensions of an 80-meter inverted-V dipole using a coaxial-resonator match. This design provides a load SWR better than 1.6:1 from 3.5 to 3.825 MHz and has been named the *80-Meter DX Special*. The coax is an electrical quarter wavelength, has a short at one end, an open at the other end, a strategically placed crossover, and is fed at a tee junction. (The crossover is made by connecting the shield of one coax segment to the center conductor of the adjacent segment and by connecting the remaining center conductor and shield in a similar way.) The antenna is constructed as an inverted-V dipole with a 110° included angle and an apex at 60 feet. The measured SWR versus frequency is shown in **Fig 29**. Also in Fig 29

Fig 29—Measured SWR performance of the 80-Meter DX Special, curve A. Note the substantial broadbanding relative to a conventional uncompensated dipole, curve B.

Fig 30—T and crossover construction. At A, a 2-inch PVC pipe coupling can be used for the T, and at B, a 1-inch coupling for the crossover. These sizes are the nominal inside diameters of the PVC pipe that is normally used with the couplings. The T could be made from standard UHF hardware (an M-358 T and a PL-258 coupler). An alternative construction for the crossover is shown at C, where a direct solder connection is made.

is the SWR characteristic for an uncompensated inverted-V dipole made from the same materials and positioned exactly like the broadband version.

The 80-Meter DX Special is made from RG-213 coaxial cable and #14 AWG wire, and is fed with 50-Ω coax. The coax forming the antenna should be cut so that the stub lengths of Fig 28 are within $^1/_2$ inch of the specified values. PVC plastic-pipe couplings and SO-239 UHF chassis connectors can be used to make the T and crossover connections, as shown in **Fig 30A** and 30B.

Alternatively, a standard UHF T connector and coupler can be used for the T, and the crossover may be a soldered connection (Fig 30C). RG-213 is used because of its ready availability, physical strength, power handling capability, and moderate loss.

Cut the wire ends of the dipole about three feet longer than the lengths given in Fig 28. If there is a tilt in the SWR-frequency curve when the antenna is first built, it may be flattened to look like the shape given in Fig 29 by increasing or decreasing the wire length. Each end should be lengthened or shortened by the same amount.

A word of caution: If the coaxial cable chosen is not RG-213 or equivalent, the dimensions will have to be modified. The following cable types have about the same characteristic impedance, loss and velocity factor as RG-213 and could be substituted: RG-8, RG-8A, RG-10, RG-10A and RG-215. If the Q of the dipole is particularly high or the radiation resistance is unusually low because of different ground characteristics, antenna height, surrounding objects and so on, then different segment lengths will be required.

What is the performance of this broadband antenna relative to that of a conventional inverted-V dipole? Aside from the slight loss (about 0.75 dB at band edges, less elsewhere) because of the non-ideal matching network, the broadband version will behave essentially the same as a dipole cut for the frequency of interest. That is, the radiation patterns for the two cases will be virtually the same.

The Snyder Dipole

A commercially manufactured antenna utilizing the principles described in the Matching Network Design section is the Snyder dipole. Patented by Richard D. Snyder in late 1984 (see Bibliography), it immediately received much public attention through an article that Snyder published. Snyder's claimed performance for the antenna is a 2:1 SWR bandwidth of 20% with high efficiency.

The configuration of the Snyder antenna is like that of the crossed-double bazooka of Fig 12, with 25-Ω line used for the cross-connected resonators. In addition, the antenna is fed through a 2:1 balun, and exhibits a W-shaped SWR characteristic like that of Fig 13. The SWR at band center, based on information in the patent document, is 1.7 to 1. There is some controversy in professional circles regarding the claims for the Snyder antenna.

The Improved Crossed-Double Bazooka

The following has been condensed from an article by Reed Fisher, W2CQH, that appeared in *The ARRL Antenna Compendium Volume 2*. The antenna is shown in **Fig 31**. Note that the half-wave flat-top is constructed of sections of RG-58 coaxial cable. These sections of coaxial cable serve as quarter-wave shunt stubs that are essentially connected *in parallel* at the feed point in the crossed double-bazooka fashion. At an electrical quarter

Fig 31—Details of the W2CQH broadband-matched 80-meter dipole.

Fig 32—SWR curves for the improved double bazooka. Curve A, the theoretical curve with 50-Ω stubs and a λ/4, 75-Ω matching transformer. Curve B, measured response of the same antenna, built with RG-58 stubs and an RG- 59 transformer. Curve C, measurements from a dipole without broadbanding. Measurements were made at W2CQH with the dipole horizontal at 30 feet.

Fig 33—This simple broadband antenna system resembles a conventional 80-meter dipole except for the λ/4-wavelength 75-Ω segment. The lengths of the Q-section, TLR (including balun) and dipole are 43.3 feet, 170.5 feet, and 122.7 feet, respectively.

wavelength (43 feet) from each side of the feed point X-Y, the center conductor is shorted to the braid of the coaxial cable.

The parallel stubs provide reactance compensation. The necessary impedance transformation at the antenna feed point is provided by the quarter-wave Q-section constructed of a 50-foot section of 75-Ω coaxial cable (RG-59). A W2DU 1:1 current balun is used at the feed point. See **Fig 32** for the SWR versus frequency for this antenna with and without the broadband matching network.

This antenna is essentially that of the crossed double bazooka antenna shown in Fig 12, with the addition of the 75-Ω Q-section. The improvement in match bandwidth is substantial. The antenna at W2CQH is straight and nearly horizontal with an average height of about 30 feet.

TRANSMISSION-LINE RESONATORS AS PART OF THE FEED LINE

A Simple Broadband Dipole for 80 Meters

This system was described in an article in September 1993 *QST*. It has the advantage that the radiator is the same as that of a conventional half-wave wire dipole. Thus the antenna is light weight, easy to support and has small wind and ice loading. The broadband matching network is integrated into the feed line.

The system is shown in **Fig 33**. It is a variation of the example shown in the Matching Network Design section of this chapter as shown in Fig 17. The TLR is a 1λ length of RG-213 50-Ω coax and the impedance transformation is accomplished with a 75-Ω Q-section

Fig 34—Measured SWR versus frequency for the broadband and conventional antenna systems.

Fig 35—Measured SWR for the 80- and 40-meter multiband antenna system.

made of RG-11. The antenna is an inverted-V with a 140° included angle and an apex height of 60 feet. The wire size is #14, but is not critical. The balun is a W2DU 1:1 current type. It easily handles the legal power limit over the entire 80-meter band. The measured SWR is shown in **Fig 34**.

A unique advantage of this antenna is that by paralleling a 40-meter dipole at the feed point and sharing the feed line, operation on both 80 and 40 meters is possible. The reason for this is that the lengths of the Q-section and the TLR are multiples of a half-wavelength on 40 meters. To minimize the interaction, the two dipoles should be spaced from each other away from the feed point. First tune the 80-meter antenna and then the 40-meter one. **Fig 35** shows the result of adding a 40-meter dipole to the system shown in Fig 33. Each 40-meter dipole leg is 34.4 feet long. Note that the SWR on 80 meters changes very little compared to Fig 34. No change was made to the 80-meter dipole or to the transmission line.

80-Meter Dipole with the TLR Transformer

The total length of the feed line in the system just described above in Fig 33 is quite long, about 214 feet. For installations with shorter runs, the TLR transformer concept may be employed to advantage. An example provided in "Optimizing the 80-Meter Dipole" in *The ARRL Antenna Compendium, Vol 4* is shown in **Fig 36**. Here the TLR is $^3/_4$ λ long overall and is made from RG-213 50-Ω cable. The design applies for an 80-meter horizontal dipole, 80 feet above average ground, with an

Fig 36—Broadbanding with the TLR transformer. The dimensions shown apply for an 80-meter horizontal dipole 80 feet above average ground.

assumed antenna F_0, R_A, and Q_A of 3.72 MHz, 92 Ω and 9, respectively. (See Figs 3 and 4). The lengths must be revised for other dipole parameters.

For this design, the feed line is 113.1 feet long and the shorted stub at the transmitter end is 21.6 feet long. You can add any length of 50-Ω cable between the transmitter and the junction of the shorted stub and the feed line. The shorted stub gives a dc path to ground for both sides of the dipole, preventing charge buildup and some lightning protection. For multiband operation with an antenna tuner, the stub should be removed.

The general application of the TLR transformer concept has a tap at both the transmitter end and a tap at the antenna end. (See Fig 24.) In this case, the concept was applied only at the transmitter end, since very little impedance transformation was required at the antenna end. The location of the TLR transformer is not obvious. Consider a $^3/_4$ λ TLR with a short at one end, and an open at the other end where the antenna is connected. The generator for no impedance transformation would be located λ/4 (43.6 feet @ 3.72 MHz) from the short. By connecting the transmitter 21.6 feet from the short, the required impedance transformation for a transmitter optimized for 50-Ω loads is achieved.

BIBLIOGRAPHY

Source material and more extended discussion of the topics covered in this chapter can be found in the references given below and in the textbooks listed at the end of Chapter 2.

A. Bloom, "Once More with the 80-Meter Dipole," Technical Correspondence, *QST*, Jun 1985, p 42.

R. E. Fisher, "A Simple, Broadband 80-Meter Dipole Antenna," *The ARRL Antenna Compendium, Vol 2* (Newington, CT: ARRL, 1989), pp 119-123.

R. M. Fano, "Theoretical Limitations on the Broadband Matching of Arbitrary Impedances," *Journal of the Franklin Inst*, Jan 1950, pp 57-83, and Feb 1950, pp 139-155.

J. Hall, "The Search for a Simple, Broadband 80-Meter Dipole," *QST*, Apr 1983, pp 22-27.

J. Hall, "Maxcom Antenna Matcher and Dipole Cable Kit," Product Review, *QST*, Nov 1984, pp 53-54.

R. C. Hansen, "Evaluation of the Snyder Dipole," *IEEE Trans on Antennas and Prop*, Vol AP-35, No. 2, Feb 1987, pp 207-210.

A. Harbach, "Broadband 80-Meter Antenna," *QST*, Dec 1980, pp 36-37 (presentation of a cage antenna).

S. Leslie, "Broadbanding the Elevated, Inverse-Fed Ground Plane Antenna," *The ARRL Antenna Compendium, Vol 6* (Newington, CT: 1999), pp 209-211.

R. D. Snyder, "The Snyder Antenna," *RF Design*, Sep/Oct 1984, pp 49-51.

R. D. Snyder, "Broadband Antennae Employing Coaxial Transmission Line Sections," United States Patent no. 4,479,130, issued Oct 23, 1984.

C. Whysall, "The 'Double Bazooka' Antenna," *QST*, Jul 1968, pp 38-39.

F. Witt, "A Simple Broadband Dipole for 80 Meters," *QST*, Sept 1993, pp 27-30, 76.

F. J. Witt, "Broadband Dipoles—Some New Insights," *QST*, Oct 1986, pp 27-37.

F. Witt, "Broadband Matching with the Transmission Line Resonator," *The ARRL Antenna Compendium, Vol 4*, (Newington, CT: 1995), pp 30-37.

F. Witt, "How to Design Off-Center-Fed Multiband Wire Antennas Using that Invisible Transformer in the Sky," *The ARRL Antenna Compendium, Vol 3,* (Newington, CT: ARRL, 1992), p 74.

F. Witt, "Match Bandwidth of Resonant Antenna Systems," *QST*, Oct 1991, pp 21-25

F. Witt, "Optimizing the 80-Meter Dipole," *The ARRL Antenna Compendium, Vol 4* (Newington, CT: 1995), pp 38-48.

F. Witt, "Optimum Lossy Broadband Matching Networks for Resonant Antennas," *RF Design*, Apr 1990, pp 44-51 and Jul 1990, p 10.

F. Witt, "The Coaxial Resonator Match and the Broadband Dipole," *QST*, Apr 1989, pp 22-27.

F. Witt, "The Coaxial Resonator Match, *The ARRL Antenna Compendium, Vol 2* (Newington, CT: ARRL, 1989), pp 110-118.

Log Periodic Arrays

This chapter was contributed by L. B. Cebik, W4RNL. The *Log Periodic Dipole Array* (*LPDA*) is one of a family of frequency-independent antennas. Alone, an LPDA forms a directional antenna with relatively constant characteristics across a wide frequency range. It may also be used with parasitic elements to achieve specific characteristic within a narrow frequency range. Common names for such hybrid arrays are the *log-cell Yagi* or the *Log-Yag*. We shall look at the essential characteristics of both types of arrays in this chapter.

The LPDA is the most popular form of log-periodic systems, which also include zig-zag, planar, trapezoidal, slot, and V forms. The appeal of the LPDA version of the log periodic antenna owes much to its structural similarity to the Yagi-Uda parasitic array. This permits the construction of directional LPDAs that can be rotated—at least within the upper HF and higher frequency ranges. Nevertheless, the LPDA has special structural as well as design considerations that distinguish it from the Yagi. A number of different construction techniques for both wire and tubular elements are illustrated later in this chapter.

Fig 1—The basic components of a log periodic dipole array (LPDA). The forward direction is to the left in this sketch. Many variations of the basic design are possible.

The LPDA in its present form derives from the pioneering work of D. E. Isbell at the University of Illinois in the late 1950s. Although you may design LPDAs for large frequency ranges—for example, from 3 to 30 MHz or a little over 3 octaves—the most common LPDA designs that radio amateurs use are limited to a one-octave range, usually from 14 to 30 MHz. Amateur designs for this range tend to consist of linear elements. However, experimental designs for lower frequencies have used elements shaped like inverted Vs, and some versions use vertically oriented $1/4$ λ elements over a ground system.

Fig 1 shows the parts of a typical LPDA. The structure consists of a number of linear elements, the longest of which is approximately $1/2$ λ long at the lowest design frequency. The shortest element is usually about $1/2$ λ long at a frequency well above the highest operating frequency. The antenna feeder, also informally called the *phase-line*, connects the center points of each element in the series, with a phase reversal or *cross-over* between each element. A stub consisting of a shorted length of parallel feed line is often added at the back of an LPDA.

The arrangement of elements and the method of feed yield an array with relatively constant gain and front-to-back ratio across the designed operating range. In addition, the LPDA exhibits a relatively constant feed-point impedance, simplifying matching to a transmission line.

BASIC DESIGN CONSIDERATIONS

For the amateur designer, the most fundamental facets of the LPDA revolve around three interrelated design variables: α (alpha), τ (tau), and σ (sigma). Any one of the three variables may be defined by reference to the other two.

Fig 2 shows the basic components of an LPDA. The angle α defines the outline of an LPDA and permits every dimension to be treated as a radius or the consequence of a radius (R) of a circle. The most basic structural dimensions are the element lengths (L), the distance (R) of each element from the apex of angle α, and the distance between elements (D). A single design constant, τ, defines all of these relationships in the following manner:

Fig 2—Some fundamental relationships that define an array as an LPDA. See the text for the defining equations.

$$\tau = \frac{R_{n+1}}{R_n} = \frac{D_{n+1}}{D_n} = \frac{L_{n+1}}{L_n} \qquad \text{(Eq 1)}$$

where element n and n+1 are successive elements in the array working toward the apex of angle α. The value of τ is always less than 1.0, although effective LPDA design requires values as close to 1.0 as may be feasible.

The variable τ defines the relationship between successive element spacings but it does not itself determine the initial spacing between the longest and next longest elements upon which to apply τ successively. The initial spacing also defines the angle α for the array. Hence, we have two ways to determine the value of σ, the relative spacing constant:

$$\sigma = \frac{1 - \tau}{4 \tan \alpha} = \frac{D_n}{2L_n} \qquad \text{(Eq 2)}$$

where D_n is the distance between any two elements of the array and L_n is the length of the longer of the two elements. From the first of the two methods of determining the value of σ, we may also find a means of determining α when we know both τ and σ.

For any value of τ, we may determine the optimal value of σ:

$$\sigma_{opt} = 0.243 \, \tau - 0.051 \qquad \text{(Eq 3)}$$

The combination of a value for τ and its corresponding optimal value of σ yields the highest performance of which an LPDA is capable. For values of τ from 0.80 through 0.98, the value of optimal σ varies from 0.143 to 0.187, in increments of 0.00243 for each 0.01 change in τ. However, using the optimal value of σ usually yields a total array length that is beyond ham construction or tower/mast support capabilities. Consequently, amateur LPDAs usually employ compromise values of τ and σ that yield lesser but acceptable performance.

For a given frequency range, increasing the value of

τ increases both the gain and the number of required elements. Increasing the value of σ increases both the gain and the overall boom length. A τ of 0.96—which approaches the upper maximum recommended value for τ—yields an optimal σ of about 0.18, and the resulting array grows to over 100 feet long for the 14 to 30 MHz range. The maximum free space gain is about 11 dBi, with a front-to-back ratio that approaches 40 dB. Normal amateur practice, however, uses values of τ from about 0.88 to 0.95 and values of σ from about 0.03 to 0.06.

Standard design procedures usually set the length of the rear element for a frequency about 7% lower than the lowest design frequency and use the common dipole formula ($L_{feet} = 468/f_{MHz}$) to determine its length (5% lower than a free-space half wavelength, where $L_{feet} = 493.56/f_{MHz}$). The upper frequency limit of the design is ordinarily set at about 1.3 times the highest design frequency. Since τ and σ set the increment between successive element lengths, the number of elements becomes a function of when the shortest element reaches the dipole length for the adjusted upper frequency.

The adjusted upper frequency limit results from the behavior of LPDAs with respect to the number of active elements. See **Fig 3**, which shows an edge view of a 10-element LPDA for 20 through 10 meters. The vertical lines represent the peak relative current magnitude for each element at the specified frequency. At 14 MHz, virtually every element of the array shows a significant cur-

Fig 3—The relative current magnitude on the elements of an LPDA at the lowest and highest operating frequencies for a given design. Compare the number of "active" elements, that is, those with current levels at least $^1/_{10}$ of the highest level.

rent magnitude. However, at 28 MHz, only the forward 5 elements carry significant current. Without the extended design range to nearly 40 MHz, the number of elements with significant current levels would be severely reduced, along with upper frequency performance.

The need to extend the design equations below the lowest proposed operating frequency varies with the value of τ. In **Fig 4**, we can compare the current on the rear elements of two LPDAs, both with a σ value of 0.04. The upper design uses a τ of 0.89, while the lower design uses a value of 0.93. The most significant current-bearing element moves forward with increases in τ, reducing (but not wholly eliminating) the need for elements whose lengths are longer than a dipole for the lowest operating frequency.

LPDA Design and Computers

Originally, LPDA design proceeded through a series of design equations intended to yield the complete specifications for an array. More recent techniques available to radio amateurs include basic LPDA design software and antenna modeling software. One good example of LPDA design software is *LPCAD28* by Roger Cox, WBØDGF. A copy of this freeware program is on the

Fig 4—Patterns of current magnitude at the lowest operating frequency of two different LPDA designs: a 10-element low-τ design and a 16-element higher-τ design.

CD-ROM that accompanies this volume. The user begins by specifying the lowest and highest frequencies in the design. He then enters either his selected values for τ and σ or his choices for the number of elements and the total length of the array. With this and other input data, the program provides a table of element lengths and spacings, using the adjusted upper and lower frequency limits described earlier.

The program also requests the diameters of the longest and shortest elements in the array, as well as the diameter of average element. From this data, the program calculates a recommended value for the phase-line connecting the elements and the approximate resistive value of the input impedance. Among the additional data that *LPCAD28* makes available is the spacing of conductors to achieve the desired characteristic impedance of the phase-line. These conductors may be round—as we would use for a wire phase-line—or square—as we might use for double-boom construction.

An additional vital output from *LPCAD28* is the conversion of the design into antenna modeling input files of several formats, including versions for *AO* and *NEC4WIN* (both *MININEC*-based programs), and a version in the standard *.NEC format usable by many implementations of *NEC-2* and *NEC-4*, including *NECWin Plus*, *GNEC*, and *EZNEC Pro*. Every proposed LPDA design should be verified and optimized by means of antenna modeling, since basic design calculations rarely provide arrays that require no further work before construction. A one-octave LPDA represents a segment of an arc defined by α that is cut off at both the upper and the lower frequency limits. Moreover, some of the design equations are based upon approximations and do not completely predict LPDA behavior. Despite these limitations, most of the sample LPDA designs shown later in this chapter are based directly upon the fundamental calculations. Therefore, the procedure will be outlined in detail before turning to hybrid log-cell Yagi concepts.

Modeling LPDA designs is most easily done on a version of *NEC*. The transmission line (TL) facility built into *NEC-2* and *NEC-4* alleviates the problem of modeling the phase-line as a set of physical wires, each section of which has a set of constraints in *MININEC* at the right-angle junctions with the elements. Although the *NEC* TL facility does not account for losses in the lines, the losses are ordinarily low enough to neglect.

NEC models do require some careful construction to obtain the most accurate results. Foremost among the cautions is the need for careful segmentation, since each element has a different length. The shortest element should have about 9 or 11 segments, so that it has sufficient segments at the highest modeling frequency for the design. Each element behind the shortest one should have a greater number of segments than the preceding element by the inverse of the value of τ. However, there is a further limitation. Since the transmission line is at the center of each

element, *NEC* elements should have an odd number of segments to hold the phase-line centered. Hence, each segmentation value calculated from the inverse of τ must be rounded up to the nearest odd integer.

Initial modeling of LPDAs in *NEC-2* should be done with uniform-diameter elements, with any provision for stepped-diameter element correction turned off. Since these correction factors apply only to elements within about 15% of dipole resonance at the test frequency, models with stepped-diameter elements will correct for only a few elements at any test frequency. The resulting combination of corrected and uncorrected elements will not yield a model with assured reliability.

Once one has achieved a satisfactory model with uniform-diameter elements, the modeling program can be used to calculate stepped-diameter substitutes. Each uniform-diameter element, when extracted from the larger array, will have a resonant frequency. Once this frequency is determined, the stepped-diameter element to be used in final construction can be resonated to the same frequency. Although *NEC-4* handles stepped diameter elements with much greater accuracy than *NEC-2*, the process just described is also applicable to *NEC-4* models for the greatest precision.

LPDA Behavior

Although LPDA behavior is remarkably uniform over a wide frequency range compared to narrow-band designs, such as the Yagi-Uda array, it nevertheless exhibits very significant variations within the design range. **Fig 5** shows several facets of these behaviors. Fig 5 shows the free-space gain for three LPDA designs using 0.5-inch diameter aluminum elements. The designations for each model list the values of τ (0.93, 0.89, and 0.85) and of σ (0.02, 0.04, and 0.06) used to design each array. The resultant

Short-Boom LPDAs: 14' to 18.5'
Free-Space Gain: 14 to 30 MHz

Fig 5—The modeled free-space gain of 3 relatively small LPDAs of different design. Note the relationship of the values of τ and of σ for these arrays with quite similar performance across the 14-30 MHz span.

array lengths are listed with each designator. The total number of elements varies from 16 for "9302" to 10 for "8904" to 7 for "8504."

First, the gain is never uniform across the entire frequency span. The gain tapers off at both the low and high ends of the design spectrum. Moreover, the amount of gain undulates across the spectrum, with the number of peaks dependent upon the selected value of τ and the resultant number of elements. The front-to-back ratio tends to follow the gain level. In general, it ranges from less than 10 dB when the free-space gain is below 5 dBi to over 20 dB as the gain approaches 7 dBi. The front-to-back ratio may reach the high 30s when the free-space array gain exceeds 8.5 dBi. Well-designed arrays, especially those with high values of τ and σ, tended to have well-controlled rear patterns that result in only small differences between the 180° front-to-back ratio and the averaged front-to-rear ratio.

Since array gain is a mutual function of both τ and σ, average gain becomes a function of array length for any given frequency range. Although the gain curves in Fig 5 interweave, there is little to choose among them in terms of average gain for the 14 to 18-foot range of array lengths. Well-designed 20- to 10-meter arrays in the 30-foot array length region are capable of about 7 dBi free-space gain, while 40-foot arrays for the same frequency range can achieve about 8 dBi free-space gain.

Exceeding an average gain of 8.5 dBi requires at least a 50-foot array length for this frequency range. Long arrays with high values of τ and σ also tend to show smaller excursions of gain and of front-to-back ratio in the overall curves. In addition, high-τ designs tend to show higher gain at the low frequency end of the design spectrum.

The frequency sweeps shown in Fig 5 are widely spaced at 1 MHz intervals. The evaluation of a specific design for the 14 to 30-MHz range should decrease the interval between check points to no greater than 0.25 MHz in order to detect frequencies at which the array may show a *performance weakness*. Weaknesses are frequency regions in the overall design spectrum at which the array shows unexpectedly lower values of gain and front-to-back ratio. In Fig 5 note the unexpected decrease in gain of model "8904" at 26 MHz. The other designs also have weak points, but they fall between the frequencies sampled.

In large arrays, these regions may be quite small and may occur in more than one frequency region. The weakness results from the harmonic operation of longer elements to the rear of those expected to have high current levels. Consider a 7-element LPDA about 12.25-foot long for 14 to 30 MHz using 0.5-inch aluminum elements. At 28 MHz, the rear elements operate in a harmonic mode, as shown by the high relative current magnitude curves in **Fig 6**. The result is a radical decrease in gain, as shown in the "No Stub" curve of **Fig 7**. The front-to-back ratio also drops as a result of strong radiation from the long

(A)

(B)

Fig 6—The relative current magnitude on the elements of model "8504" at 28 MHz without and with a stub. Note the harmonic operation of the rear elements before a stub is added to suppress such operation.

Fig 7—A graph of the gain of model "8504" showing the frequency region in which a "weakness" occurs and its absence once a suitable stub is added to the array.

elements to the rear of the array.

Early designs of LPDAs called for terminating transmission-line stubs as standard practice to help eliminate such weak spots in frequency coverage. In contemporary designs, their use tends to be more specific for eliminating or moving frequencies that show gain and front-to-back weakness. (Stubs have the added function of keeping both sides of each element at the same level of static charge or discharge.) The model dubbed "8504" was fitted (by trial and error) with an 18-inch shorted stub of 600-Ω transmission line. As Fig 6B shows, the harmonic operation of the rear elements is attenuated. The "stub" curve of Fig 7 shows the smoothing of the gain curve for the array throughout the upper half of its design spectrum. In some arrays showing multiple weaknesses, a

single stub may not eliminate all of them. However, it may move the weaknesses to unused frequency regions. Where full-spectrum operation of an LPDA is necessary, additional stubs located at specific elements may be needed.

Most LPDA designs benefit (with respect to gain and front-to-back ratio) from the use of larger-diameter elements. Elements with an average diameter of at least 0.5-inch are desirable in the 14 to 30 MHz range. However, standard designs usually presume a constant element length-to-diameter ratio. In the case of *LPCAD28*, this ratio is about 125:1, which assumes an even larger diameter. To achieve a relatively constant length-to-diameter ratio in the computer models, you can set the diameter of the shortest element in a given array design and then increase the element diameter by the inverse of τ for each succeeding longer element. This procedure is often likely to result in unreasonably large element diameters for the longest elements, relative to standard amateur construction practices.

Since most amateur designs using aluminum tubing for elements employ stepped-diameter (tapered) elements, roughly uniform element diameters will result unless the LPDA mechanical design tries to lighten the elements at the forward end of the array. This practice may not be advisable, however. Larger elements at the high end of the design spectrum often counteract (at least partially) the natural decrease in high-frequency gain and show improved performance compared to smaller diameter elements.

An alternative construction method for LPDAs uses wire throughout. At every frequency, single-wire elements reduce gain relative to larger-diameter tubular elements. An alternative to tubular elements appears in **Fig 8**. For each element of a tubular design, there is a roughly equivalent 2-wire element that may be substituted. The

Fig 8—A substitute for a large-diameter tubular element composed of two wires shorted at both the outer ends and at the center junction with the phase-line.

spacing between the wire is determined by taking one of the modeled tubular elements and finding its resonant frequency. A two-wire element of the same length is then constructed with shorts at the far ends and at the junctions with the phase-line. The separation of the two wires is adjusted until the wire element is resonant at the same frequency as the original tubular element. The required separation will vary with the wire chosen for the element. Models used to develop these substitutes must pay close attention to segmentation rules for *NEC* due to the short length of segments in the end and center shorts, and to the need to keep segment junctions as exactly parallel as possible with close-spaced wires.

Feeding and Constructing the LPDA

Original design procedures for LPDAs used a single, ordinarily fairly high, characteristic impedance for the phase-line (antenna feeder). Over time, designers real-ized that other values of impedance for the phase line offered both mechanical and performance advantages for LPDA performance. Consequently, for the contemporary designer, phase-line choice and construction techniques are almost inseparable considerations.

High-impedance phase lines (roughly 200 Ω and higher) are amenable to wire construction similar to that used with ordinary parallel-wire transmission lines. They require careful placement relative to a metal boom used to support individual elements (which themselves must be insulated from the support boom). Connections also re-quire care. If the phase-line is given a half-twist between each element, the construction of the line must ensure con-stant spacing and relative isolation from metal supports to maintain a constant impedance and to prevent shorts.

Along with the standard parallel-wire line, shown in **Fig 9A**, there are a number of possible LPDA struc-tures using booms. The booms serve both to support the elements and to create relatively low-impedance (under 200 Ω) phase-lines. Fig 9B shows the basics of a twin circular tubing boom with the elements cross-supported by insulated rods. Fig 9C shows the use of square tubing with the elements attached directly to each tube by through-bolts. Fig 9D illustrates the use of L-stock, which may be practical at VHF frequencies. Each of these sketches is incomplete, however, since it omits the nec-essary stress analyses that determine the mechanical fea-sibility of a structure for a given LPDA project.

The use of square boom material requires some adjustment when calculating the characteristic impedance of the phase-line. For conductors with a circular cross-section,

Fig 9—Four (of many) possible construction techniques, shown from the array end. In A, an insulated plate supports and separates the wires of the phase-line, suitable with wire or tubular elements. A dual circular boom phase-line also supports the elements, which are cross-supported for boom stability. Square tubing is used in C, with the elements joined to the boom/phase-line with through-bolts and an insert in each half element. The L-stock shown in D is useful for lighter VHF and UHF arrays.

$$Z_0 = 120\cosh^{-1}\frac{D}{d} \qquad \text{(Eq 4)}$$

where D is the center-to-center spacing of the conductors and d is the outside diameter of each conductor, both expressed in the same units of measurement. Since we are dealing with closely spaced conductors, relative to their diameters, the use of this version of the equation for calculating the characteristic impedance (Z_0) is recommended. For a square conductor,

$$d \approx 1.18\,w \qquad \text{(Eq 5)}$$

where d is the approximate equivalent diameter of the square tubing and w is the width of the tubing across one side. Thus, for a given spacing, a square tube permits you to achieve a lower characteristic impedance than round conductors. However, square tubing requires special attention to matters of strength, relative to comparable round tubing.

Electrically, the characteristic impedance of the LPDA phase-line tends to influence other performance parameters of the array. Decreasing the phase-line Z_0 also decreases the feed-point impedance of the array. For small designs with few elements, the decrease is not fully matched by a decrease in the excursions of reactance. Consequently, using a low impedance phase-line may make it more difficult to achieve a 2:1 or less SWR for the entire frequency range. However, higher-impedance phase-lines may result in a feed-point impedance that requires the use of an impedance-matching balun.

Decreasing the phase-line Z_0 also tends to increase LPDA gain and front-to-back ratio. There is a price to be paid for this performance improvement—weaknesses at specific frequency regions become much more pronounced with reductions in the phase-line Z_0. For a specific array you must weigh carefully the gains and losses, while employing one or more transmission line stubs to get around performance weaknesses at specific frequencies.

Depending upon the specific values of τ and σ selected for a design, you can sometimes select a phase-line Z_0 that provides either a 50-Ω or a 75-Ω feed-point impedance, holding the SWR under 2:1 for the entire design range of the LPDA. The higher the values of τ and σ for the design, the lower the reactance and resistance excursions around a central value. Designs using optimal values of σ with high values of τ show a very slight capacitive reactance throughout the frequency range. Lower design values obscure this phenomenon due to the wide range of values taken by both resistance and reactance as the frequency is changed.

At the upper end of the frequency range, the source resistance value decreases more rapidly than elsewhere in the design spectrum. In larger arrays, this can be overcome by using a variable Z_0 phase-line for approximately the first 20% of the array length. This technique is, however, difficult to implement with anything other than wire phase-lines. Begin with a line impedance about half of the final value and increase the wire spacing evenly until it reaches its final and fixed spacing. This technique can sometimes produce smoother impedance performance across the entire frequency span and improved high-frequency SWR performance.

Designing an LPDA requires as much attention to designing the phase-line as to element design. It is always useful to run models of the proposed design through several iterations of possible phase-line Z_0 values before freezing the structure for construction.

Special Design Corrections

The curve for the sample 8504 LPDA in Fig 7 revealed several deficiencies in standard LPDA designs. The weakness in the overall curve was corrected by the use of a stub to eliminate or move the frequency at which rearward elements operated in a harmonic mode. In the course of describing the characteristics of the array, we have noted several other means to improve performance. Fattening elements (either uniformly or by increasing their diameter in step with τ) and reducing the characteristic impedance of the phase-line are capable of small improvements in performance. However, they cannot wholly correct the tendency of the array gain and front-to-back ratio to fall off at the upper and lower limits of the LPDA frequency range.

One technique sometimes used to improve performances near the frequency limits is to design the LPDA for upper and lower frequency limits much higher and lower than the frequencies of use. This technique unnecessarily increases the overall size of the array and does not eliminate the downward performance curves. Increasing the values of τ and σ will usually improve perfor-

Fig 10—A before and after sketch of an LPDA, showing the original lengths of the elements and their adjustments from diminishing the value of τ at both ends of the array. See the text for the amount of change applicable to each element.

mance at no greater cost in size than extending the frequency range. Increasing the value of τ is especially effective in improving the low frequency performance of an LPDA.

Working within the overall size limits of a standard design, one may employ a technique of *circularizing* the value of τ for the rear-most and forward-most elements. See **Fig 10**, which is not to-scale relative to overall array length and width. Locate (using an antenna-modeling program) the element with the highest current at the lowest operating frequency, and the element with the highest current at the highest operating frequency. The adjustments to element lengths may begin with these elements or—at most—one element further toward the array center. For the first element (counting from the center) to be modified, reduce the value of τ by about 0.5%. For a rearward element, use the inverse of the adjusted value of τ to calculate the new length of the element relative to the unchanged element just forward of the change. For a forward element, use the new value of τ to calculate the new length of the element relative to the unchanged element immediately to the rear of it.

For succeeding elements outward, calculate new values of τ from the adjusted values, increasing the increment of decrease with each step. Second adjusted elements may use values of τ about 0.75% to 1.0% lower than the values just calculated. Third adjusted elements may use an increment of 1.0% to 1.5% relative to the preceding value.

Not all designs require extensive treatment. As the values of τ and σ increase, fewer elements may require adjustment to obtain the highest possible gain at the frequency limits, and these will always be the most outward elements in the array. A second caution is to check the feed-point impedance of the array after each change to ensure that it remains within design limits.

Fig 11 shows the free-space gain curves from 14 to 30 MHz for a 10-element LPDA with an initial τ of 0.89 and a σ of 0.04. The design uses a 200-Ω phase-line, 0.5-inch aluminum elements, and a 3-inch 600-Ω stub. The lowest curve shows the modeled performance across the design frequency range with only the stub. Performance at the frequency limits is visibly lower than within the peak performance region. The middle curve shows the effects of circularizing τ. Average performance levels have improved noticeably at both ends of the spectrum.

In lieu of, or in addition to, the adjustment of element lengths, you may also add a parasitic director to an LPDA, as shown in **Fig 12**. The director is cut roughly for the highest operating frequency. It may be spaced between 0.1 λ and 0.15 λ from the forward-most element of the LPDA. The exact length and spacing should be determined experimentally (or from models) with two factors in mind. First, the element should not adversely effect the feed-point impedance at the highest operating frequencies. Close spacing of the director has the greatest effect on this impedance. Second, the exact spacing and element length should be set to have the most desired effect on the overall performance curve of the array. The mechanical impact of adding a director is to increase overall array length by the spacing selected for the element.

The upper curve in Fig 11 shows the effect of adding a director to the circularized array already equipped with a stub. The effect of the director is cumulative, increasing the upper range gain still further. Note that the added parasitic director is not just effective at the highest

Special Corrections: 14 to 30 MHz LPDA
Stub, Circularization, Extra Director

Fig 11—The modeled free space gain from 14 to 30 MHz of an LPDA with τ of 0.89 and σ of 0.04. Squares: just a stub to eliminate a weakness; Triangles: with a stub and circularized elements, and Circles: with a stub, circularized elements and a parasitic director.

Fig 12—A generalized sketch of an LPDA with the addition of a parasitic director to improve performance at the higher frequencies within the design range.

frequencies within the LPDA design range. It has a perceptible effect almost all the way across the frequency span of the array, although the effect is smallest at the low-frequency end of the range.

The addition of a director can be used to enhance upper frequency performance of an LPDA, as in the illustration, or simply to equalize upper frequency performance with mid-range performance. High-τ designs, with good low-frequency performance, may need only a director to compensate for high-frequency gain decrease. One potential challenge to adding a director to an LPDA is sustaining a high front-to-back ratio at the upper frequency range.

Throughout the discussion of LPDAs, the performance curves of sample designs have been treated at all frequencies alike, seeking maximum performance across the entire design frequency span. Special compensations are also possible for ham-band-only LPDA designs. They include the insertion of parasitic elements within the array as well as outside the initial design boundaries. In addition, stubs may be employed not so much to eliminate weaknesses, but only to move them to frequencies outside the range of amateur interests.

A DESIGN PROCEDURE FOR AN LPDA

The following presents a systematic step-by-step design procedure for an LPDA with any desired bandwidth. The procedure requires some mathematical calculations, but a common calculator with square-root, logarithmic, and trigonometric functions is completely adequate. The notation used in this section may vary slightly from that used earlier in this chapter.

1) Decide on an operating bandwidth B between f_1, lowest frequency and f_n, highest frequency:

$$B = \frac{f_n}{f_1} \tag{Eq 6}$$

2) Choose τ and σ to give the desired estimated average gain.

$$0.8 \le \tau \le 0.98 \text{ and } 0.03 \le \sigma \le \sigma_{opt} \tag{Eq 7}$$

where σ_{opt} is calculated as noted earlier in this chapter.

3) Determine the value for the cotangent of the apex half-angle α from

$$\cot \alpha = \frac{4\sigma}{1-\tau} \tag{Eq 8}$$

Although α is not directly used in the calculations, $\cot \alpha$ is used extensively.

4) Determine the bandwidth of the active region B_{ar} from

$$B_{ar} = 1.1 + 7.7(1-\tau)^2 \cot \alpha \tag{Eq 9}$$

5) Determine the structure (array) bandwidth B_s from

$$B_S = B \times B_{ar} \tag{Eq 10}$$

6) Determine the boom length L, number of elements N, and longest element length ℓ_1.

$$L_n = \left(1 - \frac{1}{B_S}\right) \cot \alpha \times \frac{\lambda_{max}}{4} \tag{Eq 11}$$

$$\lambda_{max} = \frac{984}{f_1} \tag{Eq 12}$$

$$N = 1 + \frac{\log B_s}{\log \frac{1}{\tau}} = 1 + \frac{\ln B_S}{\ln \frac{1}{\tau}} \tag{Eq 13}$$

$$\lambda_{lft} = \frac{492}{f_1} \tag{Eq 14}$$

Usually the calculated value for N will not be an integral number of elements. If the fractional value is more than about 0.3, increase the value of N to the next higher integer. Increasing the value of N will also increase the actual value of L over that obtained from the sequence of calculations just performed.

Examine L, N and l_1 to determine whether or not the array size is acceptable for your needs. If the array is too large, increase f_1 or decrease σ or τ and repeat steps 2 through 6. Increasing f_1 will decrease all dimensions. Decreasing σ will decrease the boom length. Decreasing τ will decrease both the boom length and the number of elements.

7) Determine the terminating stub Z_t. (Note: For many HF arrays, you may omit the stub, short out the longest element with a 6-inch jumper, or design a stub to overcome a specific performance weakness.) For VHF and UHF arrays calculate the stub length from

$$Z_t = \frac{\lambda_{max}}{8} \tag{Eq 15}$$

8) Solve for the remaining element lengths from

$$\ell_n = \tau \, \ell_{n-1} \tag{Eq 16}$$

9) Determine the element spacing d_{1-2} from

$$d_{1-2} = \frac{(\ell_1 - \ell_2) \cot \alpha}{2} \tag{Eq 17}$$

where ℓ_1 and ℓ_2 are the lengths of the rearmost elements, and d_{1-2} is the distance between the elements with the lengths ℓ_1 and ℓ_2. Determine the remaining element-to-element spacings from

$$d_{(n-1)-n} = \tau \, d_{(n-2)-(n-1)} \tag{Eq 18}$$

10) Choose R_0, the desired feed-point resistance, to give the lowest SWR for the intended balun ratio and feed-line impedance. R_0, the mean radiation resistance level of the LPDA input impedance, is approximated by:

$$R_0 = \frac{Z_0}{\sqrt{1 + \dfrac{Z_0}{4\sigma' Z_{AV}}}} \qquad \text{(Eq 19)}$$

where the component terms are defined and/or calculated in the following way.

From the following equations, determine the necessary antenna feeder (phase-line) impedance, Z_0:

$$Z_0 = \frac{R_0{}^2}{8\sigma' Z_{AV}} + R_0 \sqrt{\left(\frac{R_0}{8\sigma' Z_{AV}}\right)^2 + 1} \qquad \text{(Eq 20)}$$

σ' is the mean spacing factor and is given by

$$\sigma' = \frac{\sigma}{\sqrt{\tau}} \qquad \text{(Eq 21)}$$

Z_{AV} is the average characteristic impedance of a dipole and is given by

$$Z_{AV} = 120 \left[\ln\left(\frac{\ell_n}{diam_n}\right) - 2.25 \right] \qquad \text{(Eq 22)}$$

The ratio, $l_n/diam_n$ is the length-to-diameter ratio of the element n.

11) Once Z_0 has been determined, select a combination of conductor size and spacing to achieve that impedance, using the appropriate equation for the shape of the conductors. If an impractical spacing results for the antenna feeder, select a different conductor diameter and repeat step 11. In severe cases it may be necessary to select a different R_0 and repeat steps 10 and 11. Once a satisfactory feeder arrangement is found, the LPDA design is complete.

A number of the LPDA design examples at the end of this chapter make use of this calculation method. However, the resultant design should be subjected to exten-

sive modeling tests to determine whether there are performance deficiencies or weaknesses that require modification of the design before actual construction.

Log-Cell Yagis

Fig 12 showed an LPDA with an added parasitic director. Technically, this converts the original design into a hybrid Log-Yag. However, the term *Log-Yag* (or more generally the *log-cell Yagi*) is normally reserved for monoband designs that employ two or more elements in a single-band LPDA arrangement, together with (usually) a reflector and one or more directors. The aim is to produce a monoband directive array with superior directional qualities over a wider bandwidth than can be obtained from many Yagi-Uda designs. Log-cells have also been successfully used as wide-band driver sections for multiband Yagi beams.

Fig 13 illustrates the general outline of a typical log-cell Yagi. The driver section consists of a log periodic array designed for the confines of a single amateur band or other narrow range of frequencies. The parasitic reflector is usually spaced about 0.085 λ behind the rear element of the log cell, while the parasitic director is normally placed between 0.13 and 0.15 λ ahead of the log cell.

Early log-cell Yagis tended to be casually designed. Most of these designs have inferior performance compared with present-day computer-optimized Yagis of the same boom length. Some were designed by adding one or more parasitic directors to simple phased pairs of elements. Although good performance is possible, the operating bandwidth of these designs is small, suitable only for the so-called WARC bands. However, when the log-cell is designed as a narrowly spaced monoband log periodic array, the operating bandwidth increases dramatically. Operating bandwidth here refers not just to the SWR bandwidth, but also to the gain and front-to-back bandwidth.

The widest operating bandwidths require log cells of 3 to 4 elements for HF bands like 20 meters, and 4 to 5 elements for bands as wide as 10 meters. (The bandwidth of the 20-meter band is approximately 2.4% of the center frequency, while the bandwidth of the 10-meter band approaches 9.4% of the center frequency.) A practical limit to σ for log cells used within parasitic arrays is about 0.05. Slightly higher gain may be obtained from higher values of σ, but at the cost of a much longer log cell. The limiting figure for σ results in a practical value for τ between 0.94 and 0.95 to achieve a cell with the desired bandwidth characteristics.

An array designed according to these principles has an overall length that varies with the size of the log cell. A typical array with a 4-element log-cell and single parasitic elements fore and aft is a bit over 0.35 λ long, while a 5-element log-cell Yagi will be between 0.4 and 0.45 λ long. Spacing the reflector more widely (for example, up

Fig 13—A sketch of a typical monoband log-cell Yagi. The reflector is, in principle, optional. The log-cell may have from 2 to 5 (or more elements). There may be one or more directors.

Freq = 28.5 MHz   0   Outer Ring = 7.48 dBi

Max. Gain = 7.48 dBi

Fig 14—Overlaid free-space azimuth patterns for virtually identical 5-element log-cell Yagis (with 3-element log-cells), one having the elements V'd forward at 40° from linear (dashed), the other with linear elements (solid).

to 0.25 λ) has little effect on either gain or front-to-back ratio. Wider spacing of the director will also have only a small effect on gain, since the arrangement is already close to the boom-length limit recommended for director-driver-reflector arrays. Further lengthening of the boom should be accompanied by the addition of one or more directors to the array, if additional gain is desired from the design.

Compared to a modern-day Yagi of the same boom length, the log-cell Yagi is considerably heavier and exhibits a higher wind load due to the requirements of the log-cell driver. Yagis with 3- and 4-elements within the boom lengths just given are capable of peak free-space gain values of 8.2 to 8.5 dBi, while sustaining a high front-to-back ratio. Peak front-to-back ratios are typically in

the vicinity of 25 dB. However, Yagi gain tends to decrease below the design frequency (and increase above it), while the front-to-back ratio tends to taper off as one moves away from the design frequency. For the largest log-cell sizes, log-cell Yagis of the indicated boom lengths are capable of sustaining at least 8.2 dBi free-space gain over the entire band, with front-to-back ratios of over 30 dB across the operating bandwidth.

The feed-point impedance of a log-cell Yagi is a function of both the cell design and the influence of the parasitic elements. However, for most cell designs and common phase-line designs, you can achieve a very low variation of resistance and reactance across a desired band. In many cases, the feed impedance will form a direct match for the standard 50-Ω coaxial cable used by most amateur installations. (In contrast, the high-gain, high-front-to-back Yagis used for comparison here have feed-point impedances ranging from 20 to 25 Ω.)

A common design technique used in some LPDA and log-cell Yagi designs is to bend the elements forward to form a series of Vs. A forward angle on each side of the array centerline of about 40° relative to a linear element has been popular. In some instances, the mechanical design of the array may dictate this element formation. However, this arrangement has no special benefits and possibly may degrade performance.

Fig 14 shows the free-space azimuth patterns of a single 5-element log-cell Yagi in two versions: with the elements linear and with the elements bent forward 40°. The V-array loses about $^1/_2$ dB gain, but more significantly, it loses considerable signal rejection from the sides. Similar comparisons can be obtained from pure LPDA designs and from Yagi-Uda designs when using elements in the vicinity of $^1/_2$ λ. Unless mechanical considerations call for arranging the elements in a V, the technique is not recommended.

Ultimately, the decision to build and use a log-cell Yagi involves balancing the additional weight and wind-load requirements of this design against the improvements in operating bandwidth for all of the major operating parameters, especially with respect to the front-to-back ratio and the feed-point impedance.

Wire Log-Periodic Dipole Arrays for 3.5 or 7 MHz

These wire log-periodic dipole arrays for the lower HF bands are simple in design and easy to build. They are designed to have reasonable gain, be inexpensive and lightweight, and may be assembled with stock items found in large hardware stores. They are also strong—they can withstand a hurricane! These antennas were first described by John J. Uhl, KV5E, in *QST* for August,

1986. **Fig 15** shows one method of installation. You can use the information here as a guide and point of reference for building similar LPDAs.

If space is available, the antennas can be rotated or repositioned in azimuth after they are completed. A 75-foot tower and a clear turning radius of 120 feet around the base of the tower are needed. The task is simplified

Fig 15—Typical lower-HF wire 4-element log periodic dipole array erected on a tower.

if you use only three anchor points, instead of the five shown in Fig 15. Omit the two anchor points on the forward element, and extend the two nylon strings used for element stays all the way to the forward stay line.

DESIGN OF THE LOG-PERIODIC DIPOLE ARRAYS

Design constants for the two arrays are listed in **Tables 1** and **2**. The preceding sections of this chapter contain the design procedure for arriving at the dimensions and other parameters of these arrays. The primary differences between these designs and one-octave upper HF arrays are the narrower frequency ranges and the use of wire, rather than tubing, for the elements. As design examples for the LPDA, you may wish to work through the step-by-step procedure and check your results against the values in Tables 1 and 2. You may also wish to compare these results with the output of an LPDA design software package such as *LPCAD28*.

From the design procedure, the feeder wire spacings for the two arrays are slightly different, 0.58 inch for the 3.5-MHz array and 0.66 inch for the 7-MHz version. As a compromise toward the use of common spacers for both bands, a spacing of $5/8$ inch is quite satisfactory. Surprisingly, the feeder spacing is not at all critical here from a matching standpoint, as may be verified from $Z_0 = 276 \log (2S/diam)$ and from Eq 4. Increasing the spacing to as much as $3/4$ inch results in an R_0 SWR of less than 1.1:1 on both bands.

Constructing the Arrays

Construction techniques are the same for both the 3.5 and the 7-MHz versions of the array. Once the designs are completed, the next step is to fabricate the fittings; see **Fig 16** for details. Cut the wire elements and feed

lines to the proper sizes and mark them for identification. After the wires are cut and placed aside, it will be difficult to remember which is which unless they are marked. When you have finished fabricating the connectors and cutting all of the wires, the antenna can be assembled. Use your ingenuity when building one of these antennas; it isn't necessary to duplicate these LPDAs precisely.

The elements are made of standard #14 stranded cop-

Table 1

Design Parameters for the 3.5-MHz Single-Band LPDA

f1 = 3.3 MHz	Element lengths:
f_n = 4.1 MHz	$\ell1$ = 149.091 feet
B = 1.2424	$\ell2$ = 125.982 feet
τ = 0.845	$\ell3$ = 106.455 feet
σ = 0.06	$\ell4$ = 89.954 feet
Gain = 5.9 dBi = 3.8 dBd	Element spacings:
cot α = 1.5484	d_{12}=17.891 feet
B_{ar} = 1.3864	d_{23} = 15.118 feet
B_s = 1.7225	d_{34} = 12.775 feet
L = 48.42 feet	Element diameters
N = 4.23 elements (decrease to 4)	All = 0.0641 inches
Zt = 6-inch short jumper	ℓ/diameter ratios:
R_0 = 208 Ω	ℓ/diam$_4$ = 16840
Z_{AV} = 897.8 Ω	ℓ/diam$_3$ = 19929
σ' = 0.06527	ℓ/diam$_2$ = 23585
Z_0 = 319.8 Ω	ℓ/diam$_1$ = 27911
Antenna feeder:	
#12 wire spaced 0.58 inches	
Balun: 4:1	
Feed line: 52-Ω coax	

Table 2

Design Parameters for the 7-MHz Single-Band LPDA

f1 = 6.9 MHz	Element lengths:
f_n = 7.5 MHz	$\ell1$ = 71.304 feet
B = 1.0870	$\ell2$ = 60.252 feet
τ = 0.845	$\ell3$ = 50.913 feet
σ = 0.06	$\ell4$ = 43.022 feet
Gain = 5.9 dBi = 3.8 dBd	Element spacings:
cot α = 1.5484	d_{12} = 8.557 feet
B_{ar} = 1.3864	d_{23} = 7.230 feet
B_s = 1.5070	d_{34} = 6.110 feet
L = 18.57 feet	Element diameters:
N = 3.44 elements (increase to 4)	All = 0.0641 inches
Z_t = 6-inch short jumper	ℓ/diameter ratios:
R_0 = 208 Ω	$\ell4$/diam$_4$ = 8054
Z_{AV} = 809.3 Ω	$\ell3$/diam$_3$ = 9531
σ' = 0.06527	$\ell2$/diam$_2$ = 11280
Z_0 = 334.2 Ω	$\ell1$/diam$_1$ = 13349
Antenna feeder:	
#12 wire spaced 0.66 inches	
Balun: 4:1	
Feed line: 52-Ω coax	

Fig 16—Pieces for the LPDA that require fabrication. At A is the forward connector, made from $^1/_2$-inch Lexan (polycarbonate). At B is the rear connector, also made from $^1/_2$-inch Lexan. At C is the pattern for the phase-line spacers, made from $^1/_4$-inch Plexiglas. Two spacers are required for the array.

Fig 17—The generic layout for the lower HF wire LPDA. Use a 4:1 balun on the forward connector. See Tables 1 and 2 for dimensions.

per wire. The two parallel feed lines are made of #12 solid copper-coated steel wire, such as Copperweld. Copperweld will not stretch when placed under tension. The front and rear connectors are cut from $^1/_2$-inch thick Lexan sheeting, and the feed-line spacers from $^1/_4$-inch Plexiglas sheeting.

Study the drawings carefully and be familiar with the way the wire elements are connected to the two feed lines, through the front, rear and spacer connectors. Details are sketched in **Figs 17** and **18**. Connections made in the way shown in the drawings prevent the wire from breaking. All of the rope, string, and connectors must be made of materials that can withstand the effects of tension and weathering. Use nylon rope and strings, the type that yachtsmen use. Fig 15 shows the front stay rope coming down to ground level at a point 120 feet from the base of a 75-foot tower. Space may not be available for this arrangement in all cases. An alternative installation technique is to put a pulley 40 feet up in a tree and run the front stay rope through the pulley and down to ground level at the base of the tree. The front stay rope will have to be tightened with a block and tackle at ground level.

Putting an LPDA together is not difficult if it is assembled in an orderly manner. It is easier to connect the elements to the feeder lines when the feed-line

① Mount Balun on Bottom
of front Connector
for Balance

② Feed with 50 Ω Coaxial
Cable and 4:1 Balun

③ Pay Close Attention to
Detail of Element
Connection to Feed Lines

to Tower

Rear Connector
1/2" Thick Lexan

Feeders

Elements

Spacers

Front Connector
and Balun Mount
1/2" Thick Lexan

to Front Stay

Fig 18—Details of the electrical and mechanical connections of the elements to the phase-line. Knots in the nylon rope stay line are not shown.

assembly is stretched between two points. Use the tower and a block and tackle. Attaching the rear connector to the tower and assembling the LPDA at the base of the tower makes raising the antenna into place a much simpler task. Tie the rear connector securely to the base of the tower and attach the two feeder lines to it. Then thread the two feed-line spacers onto the feed line. The spacers will be loose at this time, but will be positioned properly when the elements are connected. Now connect the front connector to the feed lines. A word of caution: Measure accurately and carefully! Double-check all measurements before you make permanent connections.

Connect the elements to the feeder lines through their respective plastic connectors, beginning with element 1, then element 2, and so on. Keep all of the element wires securely coiled. If they unravel, you will have a tangled mess of kinked wire. Recheck the element-to-feeder connections to ensure proper and secure junctions. (See Figs 17 and 18.) Once you have completed all of the element connections, attach the 4:1 balun to the underside of the front connector. Connect the feeder lines and the coaxial cable to the balun.

You will need a separate piece of rope and a pulley to raise the completed LPDA into position. First secure the eight element ends with nylon string, referring to Figs 15 and 17. The string must be long enough to reach the tie-down points. Connect the front stay rope to the front connector, and the completed LPDA is now ready to be raised into position. While raising the antenna, uncoil the element wires to prevent their getting away and tangling up into a mess. Use care! Raise the rear connector to the proper height and attach it securely to the tower, then pull the front stay rope tight and secure it. Move the elements so they form a 60° angle with the feed lines, in the direction of the front, and space them properly relative to one another. By adjusting the end positions of the elements as you walk back and forth, you will be able to align all the elements properly. Now it is time to hook your rig to the system and make some contacts.

Performance

The reports received from these LPDAs were compared with an inverted-V dipole. All of the antennas are fixed; the LPDAs radiate to the northeast, and the dipole to the northeast and southwest. The apex of the dipole is at 70 feet, and the 40- and 80-meter LPDAs are at 60 and 50 feet, respectively. Basic array gain was apparent from many of the reports received. During pileups, it was possible to break in with a few tries on the LPDAs, yet it was impossible to break in the same pileups using the dipole. The gain of the LPDAs is several dB over the dipole. For additional gain, experimenters may wish to try a parasitic director about $^1/_8 \lambda$ ahead of the array. Director length and spacing from the forward LPDA element should be field-adjusted for maximum performance while maintaining the impedance match across each of the bands.

Wire LPDA systems offer many possibilities. They are easy to design and to construct: real advantages in countries where commercially built antennas and parts are not available at reasonable cost. The wire needed can be obtained in all parts of the world, and cost of construction is low. If damaged, the LPDAs can be repaired easily with pliers and solder. For those who travel on DXpeditions where space and weight are large considerations, LPDAs are lightweight but sturdy, and they perform well.

5-Band Log Periodic Dipole Array

A rotatable log periodic array designed to cover the frequency range from 13 to 30 MHz is pictured in **Fig 19**. This is a large array having a free-space gain that varies from 6.6 to over 6.9 dBi, depending upon the operating portion of the design spectrum. This antenna system was originally described by Peter D. Rhodes, WA4JVE, in Nov 1973 *QST*. A measured radiation pattern for the array appears in **Fig 20**.

The characteristics of this array are:
1) Half-power beamwidth, 43° (14 MHz)
2) Design parameter $\tau = 0.9$
3) Relative element spacing constant $\sigma = 0.05$
4) Boom length, L = 26 feet
5) Longest element $\lambda 1$ = 37 feet 10 inches. (A tabulation

Table 3
13-30 MHz LPDA Dimensions, feet

Ele. No.	Length	$d_{n-1,n}$ (spacing)	Nearest Resonant
1	37′ 10.2″	—	
2	34′ 0.7″	3′ 9.4″ = d_{12}	14 MHz
3	30′ 7.9″	3′ 4.9″ = d_{23}	
4	27′ 7.1″	3′ 0.8″ = d_{34}	
5	24′ 10.0″	2′ 9.1″ = d_{45}	18 MHz
6	22′ 4.2″	2′ 5.8″ = d_{56}	21 MHz
7	20′ 1.4″	2′ 2.8″ = d_{67}	
8	18′ 1.2″	2′ 0.1″ = d_{78}	24.9 MHz
9	16′ 3.5″	1′ 9.7″ = d_{89}	28 MHz
10	14′ 7.9″	1′ 7.5″ = $d_{9,10}$	
11	13′ 2.4″	1′ 5.6″ = $d_{10,11}$	
12	11′ 10.5″	1′ 3.8″ = $d_{11,12}$	

Fig 19—The 13-30 MHz log periodic dipole array.

Table 4
Materials list: 13-30 MHz LPDA

Material Description	Quantity
1) Aluminum tubing—0.047″ wall thickness	
1″—12′ or 6′ lengths	126 lineal feet
7/8″—12′ lengths	96 lineal feet
7/8″—6′ or 12′ lengths	66 lineal feet
3/4″—8′ lengths	16 lineal feet
2) Stainless-steel hose clamps— 2″ max	48 ea
3) Stainless-steel hose clamps— 1 1/4″ max	26 ea
4) TV type U bolts	14 ea
5) U bolts, galv. type	
5/16″ × 1 1/2″	4 ea
1/4″ × 1″	2 ea
6) 1″ ID polyethylene water-service pipe 160 lb/in.² test, approx. 1 1/4″ OD	20 lineal feet
A) 1 1/4″ × 1 1/4 × 1/8″ aluminum Angle—6′ lengths	30 lineal feet
B) 1″ × 1/4″ aluminum bar— 6′ lengths	12 lineal feet
7) 1 1/4″ top rail of chain-link fence	26 lineal feet
8) 1:1 toroid balun	1 ea
9) 6-32 × 1″ stainless steel screws	24 ea
6-32 stainless steel nuts	48 ea
#6 solder lugs	24 ea
10) #12 copper feeder wire	60 lineal feet
11A) 12″ × 8″ × 1/4″ aluminum plate	1 ea
B) 6″ × 4″ × 1/4″ aluminum plate	1 ea
12A) 3/4″ galv. Pipe	3 lineal feet
B) 1″ galv. pipe-mast	5 lineal feet
13) Galv. guy wire	50 lineal feet
14) 1/4″ × 2″ turnbuckles	4 ea
15) 1/4″ × 1 1/2″ eye bolts	2 ea
16) TV guy clamps and eye bolts	2 ea

Fig 20—Measured radiation pattern of the 13-30 MHz LPDA. The front-to-back ratio is about 14 dB at 14 MHz and increases to 21 dB at 28 MHz.

Labels in diagram (A):
12a, 11b, 14, 6a, 6, 15, 13, 2, 9, 6b, 7, 4, 1, 3, 12b, 11a, 7, 14, 5, 10, 16, 8

Coax to Transceiver

(A)

6–32 ×1″ Stainless Steel
Screw Washer And Nut

Plastic Pipe – 1″ ID

Element

(B)

4 To 6

Solder Lug

Element

Solder to Lug

Bend Loops in Wire Where
Wires Cross. A Plastic
Spreader May be Used if
Necessary.
No 12 AWG Copper Wire

Boom

6

9

(C)

1–1/4″ OD Galv. Steel
Top Rail of Chain–link
Fence – 21 Ft. Section

2 Nuts

Wood
Dowel

3/16″ ×1–1/2″ Galv.
Stove Bolts

(D)

Fig 21—Construction diagrams of the 13-30 MHz LPDA. B and C show the method of making electrical connection between the phase-line and each half-element. D shows how the boom sections are joined.

Table 5
Element Material Requirements: 13-30 MHz LPDA

Ele. No.	1″ Tubing		7/8″ Tubing		3/4″ Tubing		1 1/4″ Angle	1″ Bar
	Len.	Qty	Len.	Qty	Len.	Qty	Len.	Len.
1	6′	2	6′	2	8′	2	3′	1′
2	6′	2	12′	2	—	—	3′	1′
3	6′	2	12′	2	—	—	3′	1′
4	6′	2	8.5′	2	—	—	3′	1′
5	6′	2	7′	2	—	—	3′	1′
6	6′	2	6′	2	—	—	3′	1′
7	6′	2	5′	2	—	—	2′	1′
8	6′	2	3.5′	2	—	—	2′	1′
9	6′	2	2.5′	2	—	—	2′	1′
10	3′	2	5′	2	—	—	2′	1′
11	3′	2	4′	2	—	—	2′	1′
12	3′	2	4′	2	—	—	2′	1′

of element lengths and spacings appears in **Table 3**.)
6) Total weight, 116 pounds
7) Wind-load area, 10.7 square feet
8) Required input impedance (mean resistance), R_0 = 72 Ω, Z_t = 6-inch jumper #18 wire
9) Average characteristic dipole impedance, Z_{AV}: 337.8 Ω
10) Impedance of the feeder, Z_0: 117.1 Ω
11) Feeder: #12 wire, close spaced
12) With a 1:1 toroid balun at the input terminals and a 72-Ω coax feed line, the maximum SWR is 1.4:1.

The mechanical assembly uses materials readily available from most local hardware stores or aluminum supply houses. The materials needed are given in **Table 4**. In the construction diagram, **Fig 21**, the materials are referenced by their respective material list numbers. The photograph shows the overall construction, and the drawings show the details. **Table 5** gives the required tubing lengths to construct the elements.

Experimenters may wish to improve the performance of the array at both the upper and lower frequency ends of the design spectrum so that it more closely approaches the performance in the middle of the design frequency range. The most apt general technique for raising both the gain and the front-to-back ratio at the frequency extremes would be to circularize τ as described earlier in this chapter. However, other techniques may also be applied.

The Telerana

The Telerana (Spanish for *spider web*) is a rotatable log periodic antenna that is lightweight, easy to construct and relatively inexpensive to build. Designed to cover 12.1 to 30 MHz, it was co-designed by George Smith, W4AEO, and Ansyl Eckols, YV5DLT, and first described by Eckols in *QST* for Jul 1981. Some of the design parameters are as follow.
1) τ = 0.9
2) σ = 0.05
3) Gain = 4.5 to 5.5 dBi (free-space) depending upon frequency
4) Feed arrangement: 400-Ω feeder line with 4:1 balun, fed with 52-Ω coax. The SWR is 1.5:1 or less in all amateur bands.

The array consists of 13 dipole elements, properly spaced and transposed, along an open wire feeder having an impedance of approximately 400 Ω. See **Figs 22** and **23**. The array is fed at the forward (smallest) end with a 4:1 balun and RG-8 cable placed inside the front arm and leading to the transmitter. An alternative feed method is to use open wire or ordinary TV ribbon and a tuner, eliminating the balun.

The frame that supports the array (**Fig 24**) consists of four 15-foot fiberglass vaulting poles slipped over short nipples at the hub, appearing like wheel spokes (**Fig 25**). Instead of being mounted directly into the fiberglass, the hub mounts into short metal tubing sleeves that are inserted into the ends of each arm to prevent crushing and splitting the fiberglass. The necessary holes are drilled to receive the wires and nylon.

A shopping list is provided in **Table 6**. The center hub is made from a 1 1/4-inch galvanized four-outlet cross or X and four 8-inch nipples (Fig 25). A 1-inch diameter X may be used alternatively, depending on the diameter of the fiberglass. A hole is drilled in the bottom of the hub to allow the cable to be passed through after welding the hub to the rotator mounting stub.

All four arms of the array must be 15 feet long. They should be strong and springy to maintain the tautness of the array. If vaulting poles are used, try to obtain all of them with identical strength ratings.

The forward spreader should be approximately 14.8 feet long. It can be much lighter than the four main arms, but must be strong enough to keep the lines rigid.

Fig 22—The overall configuration of the spider web antenna. Nylon monofilament line is used from the ends of the elements to the nylon cords. Use nylon line to tie every point where lines cross. The forward fiberglass feeder lies on the feeder line and is tied to it. Both metric and English measurements are shown, except for the illustration of the feed-line insulator. Use soft-drawn copper or stranded wire for elements 2 through 12. Element 1 should use 7/22 flexible wire or #14 AWG Copperweld.

Fig 23—The frame construction of the spider web antenna. Two different hub arrangements are illustrated.

Fig 24—Although the spider web antenna resembles a rotatable clothes line, it is much larger, as indicated by Figs 22 and 23. However, the antenna can be lifted by hand.

Fig 25—The simple arrangement of the spider web antenna hub. See Fig 23 and the text for details.

Fig 26—The elements, balun, transmission line and main bow of the spider web antenna.

Table 6
Shopping List for the Telerana

1—1¼-inch galvanized, 4-outlet cross or X.
4—8-inch nipples.
4—15-foot long arms. Vaulting poles suggested. These must be strong and all of the same strength (150 lb) or better.
1—Spreader, 14.8 foot long (must not be metal).
1—4:1 balun unless open-wire or TV cable is used.
12—Feed-line insulators made from Plexiglas or fiberglass.
36—Small egg insulators.
328 feet copper wire for elements; flexible 7/22 is suggested.
65.6 feet (20 m) #14 Copperweld wire for interelement feed line.
164 feet (50 m) strong ⅛-inch dia cord.
1—Roll of nylon monofilament fishing line, 50 lb test or better.
4—Metal tubing inserts go into the ends of the fiberglass arms.
2—Fiberglass fishing-rod blanks.
4—Hose clamps.

If tapered, the spreader should have the same measurements from the center to each end. *Do not use metal for this spreader*.

Building the frame for the array is the first construction step. Once the frame is prepared, then everything else can be built onto it. Begin by assembling the hub and the four arms, letting them lie flat on the ground with the rotator stub inserted in a hole in the ground. The tip-to-tip length should be about 31.5 feet each way. A hose clamp is used at each end of the arms to prevent splitting. Place the metal inserts in the outer ends of the arms, with 1 inch protruding. The mounting holes should have been drilled at this point. If the egg insulators and nylon cords are mounted to these tube inserts, the whole antenna can be disassembled simply by bending up the arms and pulling out the inserts with everything still attached.

Choose the arm to be at the front end. Mount two egg insulators at the front and rear to accommodate the inter-element feeder. These insulators should be as close as possible to the ends.

At each end of the cross-arm on top, install a small pulley and string nylon cord across and back. Tighten the cord until the upward bow reaches 3 feet above the hub. All cords will require retightening after the first few days because of stretching. The cross-arm can be laid on its side while preparing the feeder line. For the front-to-rear bowstring it is important to use a wire that will not stretch, such as #14 Copperweld. This bowstring is actually the inter-element transmission line. See **Fig 26**.

Secure the rear ends of the feeder to the two rear insulators, soldering the wrap. Before securing the fronts, slip the 12 insulators onto the two feed lines. A rope can be used temporarily to form the bow and to aid in mounting the feeder line. The end-to-end length of the feeder

Improving the Telerana

In *The ARRL Antenna Compendium, Vol 4*, Markus Hansen, VE7CA, described how he modified the Telerana to improve the front-to-back ratio on 20 and 15 meters. In addition, he added a trapped 30/40-meter dipole that functions as a top truss system to stabilize the modified Telerana in strong uprising winds that otherwise could turn the antenna into an "inside-out umbrella."

Fig A shows the layout for the modified Telerana, and Table A lists the lengths and spacings for the #14 wire elements. Note that VE7CA used tuning stubs to tweak the 15 and 20-meter reflector wires for best rearward pattern. The construction techniques used by VE7CA are the same as for the original Telerana. Fig B shows a side view of the additional 40/30-meter-dipole truss sytem.

Table A
Element Lengths and Spacings, in Inches

Element Number	1/2 Element Length (inches)	Total Distance (inches)
R1	202.0	0.0
L1	210.1	102.0
L2	191.2	140.7
R2	138.0	158.3
L3	174.0	175.9
L4	158.3	207.9
L5	144.1	237.0
L6	131.1	261.5
L7	119.3	285.6
L8	108.6	307.6
L9	98.8	327.6
L10	89.9	345.8
L11	82.4	364.5

Note: the reflector lengths do not include the length of the tuning stubs.

Fig A—Physical layout of modified Telerana with 20 and 15-meter reflectors added (in place of first two elements in original Telerana). Note the tuning stubs for the added reflectors.

Fig B—Side view of 30/40-meter addition to the modified Telerana, using 3/4-inch PVC pipe as a vertical stabilizer and support for the 30/40-meter trapped dipole.

should be 30.24 feet.

Now lift both bows to their upright position and tie the feeder line and the cross-arm bowstring together where they cross, directly over and approximately 3 feet above the hub.

The next step is to install the number 1 rear element from the rear egg insulators to the right and left cross-arms using other egg insulators to provide the proper element length. Be sure to solder the element halves to the transmission line. Complete this portion of the construction by installing the nylon cord catenaries from the front arm to the cross-arm tips. Use egg insulators where needed to prevent cutting the nylon cords.

When preparing the fiberglass forward spreader, keep in mind that it should be 14.75 feet long before bowing and is approximately 13.75 feet across when bowed. Secure the center of the bowstring to the end of the front arm. Lay the spreader on top of the feed line, then tie the feeder to the spreader with nylon fish line. String the catenary from the spreader tips to the cross-arm tips.

At this point of assembly, prepare antenna elements 2 through 13. There will be two segments for each element. At the outer tip make a small loop and solder the wrap. The loop will be for the nylon leader. Measure the length plus 0.4 inch for wrapping and soldering the element segment to the feeder. Seven-strand #22 antenna wire is suggested for the element wires. Slide the feed-line insulators to their proper position and secure them temporarily.

The drawings show the necessary transposition scheme. Each element half of elements 1, 3, 5, 7, 9, 11 and 13 is connected to its own side of the feeder, while elements 2, 4, 6, 8, 10 and 12 cross over to the opposite side of the transmission line.

There are four holes in each of the transmission-line insulators (see Fig 22). The inner holes are for the transmission line, and the outer ones are for the elements. Since the array elements are slanted forward, they should pass through the insulator from front to back, then back over the insulator to the front side and be soldered to the transmission line. The small drawings of Fig 22 show the details of the element transpositions.

Everywhere that lines cross, tie them together with nylon line, including all copper-nylon and nylon-nylon junctions. Careful tying makes the array much more rigid. However, all elements should be mounted loosely before you try to align the whole thing. Tightening any line or element affects all the others. There will be plenty of walking back and forth before the array is aligned properly. Expect the array to be firm but not extremely taut.

The Pounder: A Single-Band 144-MHz LPDA

The 4-element Pounder LPDA pictured in **Fig 27** was developed by Jerry Hall, K1TD, for the 144-148 MHz band. Because it started as an experimental antenna, it utilizes some unusual construction techniques. However, it gives a very good account of itself, exhibiting a theoretical free-space gain of about 7.2 dBi and a front-to-back ratio of 20 dB or better. The Pounder is small and light. It weighs just 1 pound, and hence its name. In addition, as may be seen in **Fig 28**, it can be disassembled and reassembled quickly, making it an excellent antenna for portable use. This array also serves well as a fixed-station antenna, and may be changed easily to either vertical or horizontal polarization.

The antenna feeder consists of two lengths of $1/2 \times 1/2 \times 1/16$-inch angle aluminum. The use of two facing flat surfaces permits the builder to obtain a lower characteristic impedance than can be obtained from round conductors with the same spacing. The feeder also serves as the boom for the Pounder. In the first experimental model, the array contained only two elements with a spacing of 1 foot, so a boom length of 1 foot was the primary design requirement for the 4-element version. **Table 7** gives the calculated design data for the 4-element array.

Construction

You can see the general construction approach for

Fig 27—The 144 MHz Pounder. The boom extension at the left of the photo is a 40-inch length of slotted PVC tubing, $7/8$-inch outer diameter. The tubing may be clamped to the side of a tower or attached to a mast with a small boom-to-mast plate. Rotating the tubing at the clamp will provide for either vertical or horizontal polarization.

Fig 28—One end of each half element is tapped to fasten onto boom-mounted screws. Disassembly of the array consists of merely unscrewing 8 half elements from the boom. The entire disassembled array creates a small bundle only 21 inches long.

Table 7
Design Parameters for the 144-MHz Pounder

$f_1 = 143$ MHz	Element lengths:
$f_n = 148$ MHz	$\ell_1 = 3.441$ feet
$B = 1.0350$	$\ell_2 = 3.165$ feet
$\tau = 0.92$	$\ell_3 = 2.912$ feet
$\sigma = 0.053$	$\ell_4 = 2.679$ feet
Gain = 7.2 dBi = 5.1 dBd	Element spacings:
$\cot \alpha = 2.6500$	$d_{12} = 0.365$ feet
$B_{ar} = 1.2306$	$d_{23} = 0.336$ feet
$B_s = 1.2736$	$d_{34} = 0.309$ feet
$L = 0.98$ feet	Element diameters:
$N = 3.90$ elements (increase to 4)	All = 0.25 inches
Z_t = none	ℓ/diameter ratios:
$R_0 = 52\ \Omega$	$\ell_4/\text{diam}_4 = 128.6$
$Z_{AV} = 312.8\ \Omega$	$\ell_3/\text{diam}_3 = 139.8$
$\sigma' = 0.05526$	$\ell_2/\text{diam}_2 = 151.9$
$Z_0 = 75.1\ \Omega$	$\ell_1/\text{diam}_1 = 165.1$

Antenna feeder: $1/2 \times 1/2 \times 1/16''$ angle aluminum
spaced $1/4''$
Balun: 1:1 (see text)
Feed line: 52-Ω coax (see text)

Fig 29—A close-up view of the boom, showing an alternative mounting scheme. This photo shows an earlier 2-element array, but the boom construction is the same for 2 or 4 elements. See the text for details.

Fig 30—The feed arrangement, using a right-angle chassis-mounted BNC connector, modified by removing a portion of the flange. A short length of bus wire connects the center pin to the opposite feeder conductor.

the Pounder in the photographs. Drilled and tapped pieces of Plexiglas sheet, $1/4$-inch thick, serve as insulating spacers for the angle aluminum feeder. Two spacers are used, one near the front and one near the rear of the array. Four #6-32 $\times$ $1/4$-inch pan head screws secure each aluminum angle section to the Plexiglas spacers, as shown in **Figs 29** and **30**. Use flat washers with each screw to prevent it from touching the angle stock on the opposite side of the spacer. Be sure the screws are not so long as to short out the feeder! A clearance of about $1/16$ inch is sufficient. If you have doubts about the screw lengths, check the assembled boom for a short with your ohmmeter on a Megohm range.

Either of two mounting techniques may be used for the Pounder. As shown in Figs 27 and 28, the rear spacer measures $10 \times 2^1/_2$ inches, with 45° corners to avoid sharp points. This spacer also accommodates a boom extension of PVC tubing, which is attached with two #10-32 $\times$ 1-inch screws. This tubing provides for side mounting the Pounder away from a mast or tower.

An alternative support arrangement is shown in Fig 29. Two $1/2 \times 3$-inch Plexiglas spacers are used at the front and rear of the array. Each spacer has four holes drilled $5/8$ inch apart and tapped with #6-32 threads. Two screws enter each spacer from either side to make a tight aluminum-Plexiglas-aluminum sandwich. At the center of the boom, secured with only two screws, is a 2×18-inch strip of $1/4$-inch Plexiglas. This strip is slotted about 2 inches from each end to accept hose clamps for mounting the Pounder atop a mast. As shown, the strip is attached for vertical polarization. Alternate mounting holes, visible on the now-horizontal lip of the angle stock, provide for horizontal polarization. Although sufficient, this mounting arrangement is not as sturdy as that shown in Fig 27.

The elements are lengths of thick-wall aluminum tubing, $1/4$-inch OD. The inside wall conveniently accepts a #10-32 tap. The threads should penetrate the tubing to a depth of at least 1 inch. Eight #10-32 $\times$ 1-inch screws are attached to the boom at the proper element spacings and held in place with #10-32 nuts, as shown in Fig 28. For assembly, the elements are then simply screwed into place.

Note that with this construction arrangement, the two halves of any individual element are not precisely collinear; their axes are offset by about $3/4$ inch. This offset does not seem to affect performance.

The Feed Arrangement

Use care initially in mounting and cutting the elements to length. To obtain the 180° crossover feed arrangement, the element halves from a single section of the feeder/boom must alternate directions. That is, for half-elements attached to one of the two pieces of angle stock, elements 1 and 3 will point to one side, and ele-

ments 2 and 4 to the other. This arrangement may be seen by observing the element-mounting screws in Fig 28. Because of this mounting scheme, the length of tubing for an element "half" is not simply half of the length given in Table 7. After final assembly, halves for elements 2 and 4 will have a slight overlap, while elements 1 and 3 are extended somewhat by the boom thickness. The best procedure is to cut each assembled element to its final length by measuring from tip to tip.

The Pounder may be fed with RG-58 or RG-59 coax and a BNC connector. A modified right-angle chassis-mount BNC connector is attached to one side of the feeder/boom assembly for cable connection, Fig 30. The modification consists of cutting away part of the mounting flange that would otherwise protrude from the boom assembly. This leaves only two mounting-flange holes, but these are sufficient for a secure mount. A short length of small bus wire connects the center pin to the opposite side of the feeder, where it is secured under the mounting-screw nut for the shortest element.

For operation, you may secure the coax to the PVC boom extension or to the mast with electrical tape. You should use a balun, especially if the Pounder is operated with vertical elements. A choke type of balun is satisfactory, formed by taping 6 turns of the coax into a coil of 3 inches diameter, but a bead balun is preferred (see Chapter 26). The balun should be placed at the point where the coax is brought away from the boom. If the mounting arrangement of Fig 29 is used with vertical polarization, a second balun should be located approximately $1/4$ wavelength down the coax line from the first. This will place it at about the level of the lower tips of the elements. For long runs of coax to the transmitter, a transition from RG-58 to RG-8 or from RG-59 to RG-9 is suggested, to reduce line losses. Make this transition at some convenient point near the array.

No shorting feeder termination is used with the array described here. The antenna feeder (phase-line) Z_0 of this array is in the neighborhood of 120 Ω, and with a resulting feed-point impedance of about 72 Ω. The theoretical mean SWR with 52 Ω line is 72/52 or 1.4 to 1. Upon array completion, the measured SWR (52-Ω line) was found to be relatively constant across the band, with a value of about 1.7 to 1. The Pounder offers a better match to 72-Ω coax.

Being an all-driven array, the Pounder is more immune to changes in feed-point impedance caused by nearby objects than is a parasitic array. This became obvious during portable use when the array was operated near trees and other objects... the SWR did not change noticeably with antenna rotation toward and away from those objects. Consequently, the Pounder should behave well in a restricted environment, such as an attic. Weighing just one pound, this array indeed does give a good account of itself.

Log Periodic-Yagi Arrays

Several possibilities exist for constructing high-gain arrays that use the log periodic dipole array concept. One technique is to add parasitic elements to the LPDA to increase both the gain and the front-to-back ratio for a specific frequency within the passband of the LPDA. The LPDA-Yagi combination is simple in concept. It utilizes an LPDA group of driven elements, along with parasitic elements at normal Yagi spacings from the active elements of the LPDA.

The LPDA-Yagi combinations are endless. An example of a single-band high-gain design is a 2- or 3-element LPDA for 21.0 to 21.45 MHz with the addition of two or three parasitic directors and one parasitic reflector. The name Log-Yag (log-cell Yagi) array has been coined for these hybrid antennas. The LPDA portion of the array is of the usual design to cover the desired bandwidth, and standard Yagi design procedures are used for the parasitic elements. Information in this section is based on a Dec 1976, *QST* article by P. D. Rhodes, K4EWG, and J. R. Painter, W4BBP, "The Log-Yag Array."

THE LOG-YAG ARRAY

The Log-Yag array, with its added parasitic elements, provides higher gain and greater directivity than would be realized with the LPDA alone. Yagi arrays require a long boom and wide element spacing for wide bandwidth and high gain, because the Q of the Yagi system increases as the number of elements is increased or as the spacing between adjacent elements is decreased. An increase in the Q of the Yagi array means that the total operating bandwidth of the array is decreased, and the gain and front-to-back ratio specified in the design are obtainable only over small portions of the band. [Older Yagi designs did indeed exhibit the limitations mentioned here. But modern, computer-aided design has resulted in wideband Yagis, provided that sufficient elements are used on the boom to allow stagger tuning for wide-band coverage. See Chapter 11.—*Ed.*]

The Log-Yag system overcomes this difficulty by using a multiple driven element cell designed in accordance with the principles of the log periodic dipole array. Since this log cell exhibits both gain and directivity by itself, it is a more effective wide-band radiator than a simple dipole driven element. The front-to-back ratio and gain of the log cell can then be improved with the addition of a parasitic reflector and director.

It is not necessary for the parasitic element spacings to be large with respect to wavelength, since the log cell is the determining factor in the array bandwidth. As well, the element spacings within the log cell may be small with respect to a wavelength without appreciable deterioration of the cell gain. For example, decreasing the relative spacing constant (σ) from 0.1 to 0.05 will decrease the array gain by less than 1 dB.

A Practical Example

The photographs and figures show a Log-Yag array for the 14-MHz amateur band. The array design takes the form of a 4-element log cell, a parasitic reflector spaced at 0.085 λ_{max}, and a parasitic director spaced at 0.15 λ_{max} (where λ_{max} is the longest free-space wavelength within the array passband). Array gain is almost unaffected with reflector spacings from 0.08 λ to 0.25 λ, and the increase in boom length is not justified. The function of the reflector is to improve the front-to-back ratio of the log cell, while the director sharpens the forward lobe and decreases the half-power beamwidth. As the spacing between the parasitic elements and the log cell decreases, the parasitic elements must increase in length.

The log cell is designed to meet upper and lower band limits with σ = 0.05. The design parameter τ is dependent on the structure bandwidth, B_s. When the log periodic design parameters have been found, the element length and spacings can be determined.

Array layout and construction details can be seen in Figs 31 through 34. Characteristics of the array are given in **Table 8**.

The method of feeding the antenna is identical to that of feeding the log periodic dipole array without the parasitic elements. As shown in **Fig 31**, a balanced feeder is required for each log-cell element, and all adjacent elements are fed with a 180° phase shift by alternating connections. Since the Log-Yag array will be covering a relatively small bandwidth, the radiation resistance of the narrow-band log cell will vary from 80 to 90 Ω (tubing

---

Table 8
Log-Yag Array Characteristics

1) Frequency range	14 to 14.35 MHz
2) Operating bandwidth	B = 1.025
3) Design parameter	τ = 0.946657
4) Apex half angle	α = 14.921°; cot α = 3.753
5) Half-power beamwidth	42° (14 to 14.35 MHz)
6) Bandwidth of structure	Bs = 1.17875
7) Free-space wavelength	λ_{max} = 70.28 feet
8) Log cell boom length	L = 10.0 feet
9) Longest log element	ℓ1 = 35.14 feet (a tabulation of element lengths and spacings is given in Table 9)
10) Forward gain (free space)	8.2 dBi
11) Front-to-back ratio	32 dB (theoretical)
12) Front-to-side ratio	45 dB (theoretical)
13) Input impedance	Z_0 = 37 Ω
14) SWR	1.3 to 1 (14 to 14.35 MHz)
15) Total weight	96 pounds
16) Wind-load area	8.5 sq feet
17) Reflector length	36.4 feet at 6.0 foot spacing
18) Director length	32.2 feet at 10.5 foot spacing
19) Total boom length	26.5 feet

Fig 31—Layout of the Log-Yag array.

Table 9
Log-Yag Array Dimensions

Element	Length Feet	Spacing Feet
Reflector	36.40	6.00 (Ref. to $\ell 1$)
$\ell 1$	35.14	3.51 (d_{12})
$\ell 2$	33.27	3.32 (d_{23})
$\ell 3$	31.49	3.14 (d_{34})
$\ell 4$	29.81	10.57 ($\ell 4$ to dir.)
Director	32.20	

elements) depending on the operating bandwidth. The addition of parasitic elements lowers the log-cell radiation resistance. Hence, it is recommended that a 1:1 balun be connected at the log-cell input terminals and 50-Ω coaxial cable be used for the feed line.

The measured radiation resistance of the 14-MHz Log-Yag is 37 Ω over the frequency range from 14.0 to 14.35 MHz. It is assumed that tubing elements will be used. However, if a wire array is used, then the radiation resistance R_0 and antenna-feeder input impedance Z_0 must be calculated so that the proper balun and coax may be used. The procedure is outlined in detail in an earlier part of this chapter. However, programs such as *LPCAD28* are also suitable to automate the calculations.

Table 9 has array dimensions. **Tables 10** and **11** contain lists of the materials necessary to build the Log-Yag array.

Fig 32—Assembly details. The numbered components refer to Table 11.

Table 10

Element Material Requirements: Log-Yag Array

	1-in. Tubing		7/8-in. Tubing		3/4-in. Tubing		1¼-in. Angle	1¼-in. Bar
	Len. Feet	Qty	Len. Feet	Qty	Len. Feet	Qty	Len. Feet	Len. Feet
Reflector	12	1	6	2	8	2	None	None
ℓ1	6	2	6	2	8	2	3	1
ℓ2	6	2	6	2	8	2	3	1
ℓ3	6	2	6	2	6	2	3	1
ℓ4	6	2	6	2	6	2	3	1
Director	12	1	6	2	6	2	None	None

Fig 33—The attachment of the elements to the boom.

Fig 34—Looking from the front to the back of the Log-Yag array. A truss provides lateral and vertical support.

Table 11

Materials List, Log-Yag Array

1) Aluminum tubing—0.047 in. wall thickness
   1 in.—12 ft lenths, 24 lin. ft
   1 in.—12 ft or 6 ft lengths, 48 lin. ft
   7/8 in.—12 ft or 6 ft lengths, 72 lin. ft
   3/4 in.—8 ft lengths, 48 lin. ft
   3/4 in.—6 ft lengths, 36 lin. ft
2) Stainless steel hose clamps—2 in. max, 8 ea
3) Stainless steel hose clamps—1¼ in. max, 24 ea
4) TV-type U bolts—1½ in., 6 ea
5) U bolts, galv. type: 5/16 in. × 1½ in., 6 ea
5A) U bolts, galv. type: ¼ in. × 1 in., 2 ea
6) 1 in. ID water-service polyethylene pipe 160 lb/in.² test, approx. 1⅜ in. OD, 7 lin. ft
7) 1¼ in. × 1¼ in. × ⅛ in. aluminum angle—6 ft lengths, 12 lin. ft

8) 1 in. × ¼ in. × ¼ in. aluminum angle—6 ft lengths, 6 lin. ft
9) 1¼ in. top rail of chain-link fence, 26.5 lin. ft
10) 1:1 toroid balun, 1 ea
11) No. 6-32 × 1 in. stainless steel screws, 8 ea
   No. 6-32 stainless steel nuts, 16 ea
   No. 6 solder lugs, 8 ea
12) #12 copper feed wire, 22 lin. ft
13) 12 in. × 6 in. × ¼ in. aluminum plate, 1 ea
14) 6 in. × 4 in. × ¼ in. aluminum plate, 1 ea
15) ¾ in. galv. pipe, 3 lin. ft
16) 1 in. galv. pipe—mast, 5 lin. ft
17) Galv. guy wire, 50 lin. ft
18) ¼ in. × 2 in. turnbuckles, 4 ea
19) ¼ in. × 1½ in. eye bolts, 2 ea
20) TV guy clamps and eyebolts, 2 ea

BIBLIOGRAPHY

Source material and more extended discussion of the topics covered in this chapter can be found in the references listed below and in the textbooks listed at the end of Chapter 2.

D. Allen, "The Log Periodic Loop Array (LPLA) Antenna," *The ARRL Antenna Compendium, Vol 3*, pp 115-117.

C. A. Balanis, *Antenna Theory, Analysis and Design*, 2nd Ed. (New York: John Wiley & Sons, 1997) Chapter 9.

P. C. Butson and G. T. Thompson, "A Note on the Calculation of the Gain of Log-Periodic Dipole Antennas," *IEEE Trans on Antennas and Propagation*, Vol AP-24, No. 1, Jan 1976, pp 105-106.

R. L. Carrel, "The Design of Log-Periodic Dipole Antennas," *1961 IRE International Convention Record*.

L. B. Cebik, "The Monoband Log-Cell Yagi Revisited," (4-part series) *National Contest Journal*, Jan-Jul 2000.

L. B. Cebik, "Some Preliminary Notes on Standard Design LPDAs for 3-30 MHz," (2-part series), *QEX*, Mar-May 2000.

R. H. DuHamel and D. E. Isbell, "Broadband Logarithmically Periodic Antenna Structures," *1957 IRE National Convention Record*, Part 1.

A. Eckols, "The Telerana: A Broadband 13- to 30-MHz Directional Antenna," *QST*, Jul 1981, pp 24-27.

J. Fisher, "Development of the W8JF Waveram: A Planar Log-Periodic Quad Array," *The ARRL Antenna Compendium, Vol 1*, pp 50-54.

M. Hansen, "The Improved Telerana, with Bonus 30/40 meter Coverage," *The ARRL Antenna Compendium, Vol 4*, pp 112-117.

K. Heitner, "A Wide-Band, Low-Z Antenna—New Thoughts on Small Antennas," *The ARRL Antenna Compendium, Vol 1*, pp 48-49.

D. E. Isbell, "Log-Periodic Dipole Arrays," *IRE Transactions on Antennas and Propagation*, Vol. AP-8, No. 3, May 1960.

J. D. Kraus, *Antennas*, 2nd Ed. (New York: McGraw-Hill, 1988), Chapter 15.

R. A. Johnson, ed., *Antenna Engineering Handbook*, 3rd Ed. (New York: McGraw-Hill, 1993), Chapters 14 and 26.

K. Luetzelschwab, "Log Periodic Dipole Array Improvements," *The ARRL Antenna Compendium, Vol 6*, pp 74-76.

D. A. Mack, "A Second-Generation Spiderweb Antenna," *The ARRL Antenna Compendium, Vol 1*, pp 55-59.

P. E. Mayes and R. L. Carrel, "Log Periodic Resonant-V Arrays," *IRE Wescon Convention Record*, Part 1, 1961.

P. E. Mayes, G. A. Deschamps, and W. T. Patton, "Backward Wave Radiation from Periodic Structures and Application to the Design of Frequency Independent Antennas," *Proc. IRE*.

J. J. Meyer, "A Simple Log-Yag Array for 50 MHz," *The ARRL Antenna Compendium, Vol 1*, pp 62-63.

C. T. Milner, "Log Periodic Antennas," *QST*, Nov 1959, pp 11-14.

W. I. Orr and S. D. Cowan, *Beam Antenna Handbook*, pp 251-253.

P. D. Rhodes, "The Log-Periodic Dipole Array," *QST*, Nov 1973, pp 16-22.

P. D. Rhodes and J. R. Painter, "The Log-Yag Array," *QST*, Dec 1976, pp 18-21.

P. D. Rhodes, "The Log-Periodic V Array," *QST*, Oct 1979, pp 40-43.

P. D. Rhodes, "The K4EWG Log Periodic Array," *The ARRL Antenna Compendium, Vol 3*, pp 118-123

V. H. Rumsey, *Frequency Independent Antennas* (New York: Academic Press, 1966).

F. Scholz, "A 14-30 MHz LPDA for Limited Space," *The ARRL Antenna Compendium, Vol 2*, pp 96-99

W. L. Stutzman and G. A. Thiele, *Antenna Theory and Design*, 2nd Ed. (New York: John Wiley & Sons, 1998), Chapter 6.

J. J. Uhl, "Construct a Wire Log-Periodic Dipole Array for 80 or 40 Meters," *QST*, Aug 1976, pp 21-24.

R. F. Zimmer, "Three Experimental Antennas for 15 Meters," *CQ*, Jan 1983, pp 44-45.

R. F. Zimmer, "Development and Construction of 'V' Beam Antennas," *CQ*, Aug 1983, pp 28-32.

Chapter 11

HF Yagi Arrays

Along with the dipole and the quarter-wave vertical, radio amateurs throughout the world make extensive use of the Yagi array. Hidetsugu Yagi and Shintaro Uda, two Japanese university professors, invented the Yagi in the 1920s. Uda did much of the developmental work, while Yagi introduced the array to the world outside Japan through his writings in English. Although the antenna should properly be called a *Yagi-Uda* array, it is commonly referred to simply as a *Yagi*.

The Yagi is a type of endfire multielement array. At the minimum, it consists of a single driven element and a single parasitic element. These elements are placed parallel to each other, on a supporting boom spacing them apart. This arrangement is known as a 2-element Yagi. The parasitic element is termed a *reflector* when it is placed behind the driven element, opposite to the direction of maximum radiation, and is called a *director* when it is placed ahead of the driven element. See **Fig 1**. In the VHF and UHF spectrum, Yagis employing 30 or more elements are not uncommon, with a single reflector and multiple directors. See Chapter 18, VHF and UHF Antenna Systems, for details on VHF and UHF Yagis. Large HF arrays may employ 10 or more elements, and will be covered in this chapter.

The gain and directional pattern of a Yagi array is determined by the relative amplitudes and phases of the currents induced into all the parasitic elements. Unlike the directly driven multielement arrays considered in Chapter 8, Multielement Arrays, where the designer must compensate for mutual coupling between elements, proper Yagi operation *relies on* mutual coupling. The current in each parasitic element is determined by its spacing from both the driven element and other parasitic elements, and by the tuning of the element itself. Both length and diameter affect element tuning.

For about 50 years amateurs and professionals created Yagi array designs largely by "cut and try" experimental techniques. In the early 1980s, Jim Lawson, W2PV, described in detail for the amateur audience the fundamental mathematics involved in modeling Yagis. His book *Yagi Antenna Design* is highly recommended for serious antenna designers. The advent of powerful microcomputers and sophisticated computer antenna modeling software in the mid 1980s revolutionized the field of Yagi design for the radio amateur. In a matter of minutes, a computer can

Fig 1—Two-element Yagi systems using a single parasitic element. At A the parasitic element acts as a director, and at B as a reflector. The arrows show the direction in which maximum radiation takes place.

try 100,000 or more different combinations of element lengths and spacings to create a Yagi design tailored to meet a particular set of high-performance parameters. To explore this number of combinations experimentally, a human experimenter would take an unimaginable amount of time and dedication, and the process would no doubt suffer from considerable measurement errors. With the computer tools available today, an antenna can be designed, constructed and then put up in the air, with little or no tuning or pruning required.

Yagi Performance Parameters

There are three main parameters used to characterize the performance of a particular Yagi—*forward gain*, *pattern* and *drive impedance/SWR.* Another important consideration is *mechanical strength.* It is very important to recognize that each of the three electrical parameters should be characterized over the frequency band of interest in order to be meaningful. Neither the gain, SWR nor the pattern measured at a single frequency gives very much insight into the overall performance of a particular Yagi.

Poor designs have been known to reverse their directionality over a frequency band, while other designs have excessively narrow SWR bandwidths, or overly "peaky" gain response. Finally, an antenna's ability to survive the wind and ice conditions expected in one's geographical location is an important consideration in any design. Much of this chapter will be devoted to describing detailed Yagi designs that are optimized for a good balance between gain, pattern and SWR over various amateur bands, and that are designed to survive strong winds and icing.

YAGI GAIN

Like any other antenna, the gain of a Yagi must be stated in comparison to some standard of reference. Designers of phased vertical arrays often state gain referenced to a single, isolated vertical element. See the section on "Phased Array Techniques" in Chapter 8, Multielement Arrays.

Many antenna designers prefer to compare gain to that of an *isotropic radiator in free space.* This is a theoretical antenna that radiates equally well in all directions, and by definition, it has a gain of 0 *dBi* (dB isotropic). Many radio amateurs, however, are comfortable using a dipole as a standard reference antenna, mainly because it is *not* a theoretical antenna.

In free space, a dipole does not radiate equally well in all directions—it has a figure-eight azimuth pattern, with deep nulls off the ends of the wire. In its favored directions, a free-space dipole has 2.15 dB gain compared to the isotropic radiator. You may see the term *dBd* in amateur literature, meaning gain referenced to a dipole in free space. Subtract 2.15 dB from gain in dBi to convert to gain in dBd.

Assume for a moment that we take a dipole out of "free space," and place it one wavelength over the ocean, whose saltwater makes an almost perfect ground. At an elevation angle of 15°, where sea water-reflected radiation adds in phase with direct radiation, the dipole has a gain of about 6 dB, compared to its gain when it was in free space, isolated from any reflections. See Chapter 3, The Effects of the Earth.

It is perfectly legitimate to say that this dipole has a gain of 6 dBd, although the term "dBd" (meaning "dB dipole") makes it sound as though the dipole somehow has gain over itself! Always remember that gain expressed in dBd (or dBi) refers to the *counterpart antenna in free space*. The gain of the dipole over saltwater in this example can be rated at either 6 dBd (over a dipole in free space), or as 8.15 dBi (over an isotropic radiator in free space). Each frame of reference is valid, as long as it is used consistently and clearly. In this chapter we will often switch between Yagis in free space and Yagis over ground. To prevent any confusion, gains will be stated in dBi.

Yagi free-space gain ranges from about 5 dBi for a small 2-element design to about 20 dBi for a 31-element long-boom UHF design. The length of the boom is the main factor determining the gain a Yagi can deliver. Gain as a function of boom length will be discussed in detail after the sections below defining antenna response patterns and SWR characteristics.

RESPONSE PATTERNS— FRONT-TO-REAR RATIO

As discussed in Chapter 2, Antenna Fundamentals, for an antenna to have gain, it must concentrate energy radiated in a particular direction, at the expense of energy radiated in other directions. Gain is thus closely related to an antenna's directivity pattern, and also to the losses in the antenna. **Fig 2** shows the *E-plane* (also called *E-field,* for electric field) and *H-plane* (also called *H-field*, for magnetic field) pattern of a 3-element Yagi in free space, compared to a dipole, and an isotropic radiator. These patterns were generated using the computer program *NEC-2*, which is highly regarded by antenna professionals for its accuracy and flexibility.

In free space there is no Earth reference to determine whether the antenna polarization is horizontal or vertical, and so its response patterns are labeled as E-field (electric) or H-field (magnetic). For a Yagi mounted over ground rather than in free space, if the

Fig 2—E-Plane (electric field) and H-Plane (magnetic field) response patterns for 3-element 20-meter Yagi in free space. At A the E-Plane pattern for a typical 3-element Yagi is compared with a dipole and an isotropic radiator. At B the H-Plane patterns are compared for the same antennas. The Yagi has an E-Plane half-power beamwidth of 66°, and an H-Plane half-power beamwidth of about 120°. The Yagi has 7.28 dBi (5.13 dBd) of gain. The front-to-back ratio, which compares the response at 0° and at 180°, is about 35 dB for this Yagi. The front-to-rear ratio, which compares the response at 0° to the largest lobe in the rearward 180° arc behind the antenna, is 24 dB, due to the lobes at 120° and 240°.

E-field is parallel to the earth (that is, the elements are parallel to the earth) then the antenna polarization is horizontal, and its E-field response is then usually referred to as its *azimuth* pattern. Its H-field response is then referred to as its *elevation* pattern.

Fig 2A demonstrates how this 3-element Yagi in free space exhibits 7.28 dBi of gain (referenced to isotropic), and has 5.13 dB gain over a free-space dipole. The gain is in the forward direction on the graph at 0° azimuth, and the forward part of the lobe is called the *main lobe*. For this particular antenna, the angular width of the E-plane main lobe at the half power, or 3 dB points compared to the peak, is about 66°. This performance characteristic is called the antenna's azimuthal *half-power beamwidth*.

Again as seen in Fig 2A, this antenna's response in the reverse direction at 180° azimuth is 34 dB less than in the forward direction. This characteristic is called the antenna's *front-to-back ratio*, and it describes the ability of an antenna to discriminate, for example, against interfering signals coming directly from the rear, when the antenna is being used for reception. In Fig 2A there are two sidelobes, at 120° and at 240° azimuth, which are about 24 dB down from the peak response at 0°. Since interference can come from any direction, not only directly off the back of an antenna, these kinds of sidelobes limit the ability to discriminate against rearward signals. The term *worst-case front-to-rear ratio* is used to describe the worst-case rearward lobe in the 180°-wide sector behind the antenna's main lobe. In this case, the worst-case front-to-rear ratio is 24 dB.

In the rest of this chapter the worst-case front-to-rear ratio will be used as a performance parameter, and will be abbreviated as "F/R." For a dipole or an isotropic radiator, Fig 2A demonstrates that F/R is 0 dB. Fig 2B depicts the H-field response for the same 3-element Yagi in free space, again compared to a dipole and an isotropic radiator in free space. Unlike the E-field pattern, the H-field pattern for a Yagi does not have a null at 90°, directly over the top of the Yagi. For this 3-element design, the H-field half-power beamwidth is approximately 120°.

Fig 3 compares the azimuth and elevation patterns for a horizontally polarized 6-element 14-MHz Yagi, with a 60-foot boom mounted one wavelength over ground, to a dipole at the same height. As with any horizontally polarized antenna, the height above ground is the main factor determining the peaks and nulls in the elevation pattern of each antenna. Fig 3A shows the E-field pattern, which has now been labeled as the Azimuth pattern. This antenna has a half-power azimuthal beamwidth of about 50°, and at an elevation angle of 12° it exhibits a forward gain of 16.02 dBi, including about 5 dB of ground reflection gain over relatively poor ground, with a dielectric constant of 13 and conductivity of 5 mS/m. In free space this Yagi has a gain of 10.97 dBi.

The H-field elevation response of the 6-element Yagi has a half-power beamwidth of about 60° in free space,

0

Dipole, 69 Ft High

330

300

270

240

210

180

Azimuth

6-Ele. Yagi,
69 Ft High

30

60

90

120

150

(A)

12° Elevation
0 dB = 16.02 dBi

14.174 MHz

90

6-Ele. Yagi, 69 ft High

60

60

Dipole 69 ft High

30

30

0

0

0 dB = 16.02 dBi

Elevation

14.174 MHz

(B)

Fig 3—Azimuth pattern for 6-element 20-meter Yagi on 60-foot long boom, mounted 60 feet over ground. At A, the azimuth pattern at 12° elevation angle is shown, compared to a dipole at the same height. Peak gain of the Yagi is 16.04 dBi, or just over 8 dB compared to the dipole. At B, the elevation pattern for the same two antennas is shown. Note that the peak elevation pattern of the Yagi is compressed slightly lower compared to the dipole, even though they are both at the same height over ground. This is most noticeable for the Yagi's second lobe, which peaks at about 40°, while the dipole's second lobe peaks at about 48°. This is due to the greater free-space directionality of the Yagi at higher angles.

but as shown in Fig 3B, the first lobe (centered at 12° in elevation) has a half-power beamwidth of only 13° when the antenna is mounted one wavelength over ground. The dipole at the same height has a very slightly larger first-lobe half-power elevation beamwidth of 14°, since its free-space H-field response is omnidirectional.

Note that the free-space H-field directivity of the Yagi suppresses its second lobe over ground (at an elevation angle of about 40°) to 8 dBi, while the dipole's response at its second lobe peak (at about 48°) is at a level of 9 dBi.

The shape of the azimuthal pattern for a Yagi oper-

Fig 4—SWR over the 28.0 to 28.8 MHz portion of the 10-meter band for two different 3-element Yagi designs. One is designed strictly for maximum gain, while the second is optimized for F/R pattern and SWR over the frequency band. A Yagi designed only for maximum gain usually suffers from a very narrow SWR bandwidth.

ated over real ground will change slightly as the Yagi is placed closer and closer to earth. Generally, however, the azimuth pattern doesn't depart significantly from the free-space pattern until the antenna is less than 0.5 λ high. This is just over 17 feet high at 28.4 MHz, and just under 35 feet at 14.2 MHz, heights that are not difficult to achieve for most amateurs. Some advanced computer programs can optimize Yagis at the exact installation height.

DRIVE IMPEDANCE AND SWR

The impedance at the driven element in a Yagi is affected not only by the tuning of the driven element itself, but also by the spacing and tuning of nearby parasitic elements, and to a lesser extent by the presence of ground. In some designs that have been tuned solely for maximum gain, the driven-element impedance can fall to very low levels, sometimes less than 5 Ω. This can lead to excessive losses due to conductor resistance, especially at VHF and UHF. In a Yagi that has been optimized solely for gain, conductor losses are usually compounded by large excursions in impedance levels with relatively small changes in frequency. The SWR can thus change dramatically over a band and can create additional losses in the feed cable. **Fig 4** illustrates the SWR over the 28 to 28.8 MHz portion of the 10-meter amateur band for a 5-element Yagi on a 24-foot boom, which has been tuned for maximum forward gain at a spot frequency of 28.4 MHz. Its SWR curve is contrasted to that of a Yagi designed for a good compromise of gain, SWR and F/R.

Even professional antenna designers have difficulty accurately measuring forward gain. On the other hand, SWR can easily be measured by professional and amateur alike. Few manufacturers would probably want to advertise an antenna with the narrow-band SWR curve shown in Fig 4!

Monoband Yagi Performance Optimization

DESIGN GOALS

The previous section discussing driven-element impedance and SWR hinted at possible design trade-offs among gain, pattern and SWR, especially when each parameter is considered over a frequency band rather than at a spot frequency. Trade-offs in Yagi design parameters can be a matter of personal taste and operating style. For example, one operator might exclusively operate the CW portions of the HF bands, while another might only be interested in the Phone portions. Another operator may want a good pattern in order to discriminate against signals coming from a particular direction; someone else may want the most forward gain possible, and may not care about responses in other directions.

Extensive computer modeling of Yagis indicates that the parameter that must be compromised most to achieve wide bandwidths for front-to-rear ratio and SWR is forward gain. However, not much gain must be sacrificed for good F/R and SWR coverage, especially on long-

boom Yagis. Although 10 and 7-MHz Yagis are not rare, the HF bands from 14 to 30 MHz are where Yagis are most often found, mainly due to the mechanical difficulties involved with making sturdy antennas for lower frequencies. The highest HF band, 28.0 to 29.7 MHz, represents the largest percentage bandwidth of the upper HF bands, at almost 6%. It is difficult to try to optimize in one design the main performance parameters of gain, worst-case F/R ratio and SWR over this large a band. Many commercial designs thus split up their 10-meter designs into antennas covering one of two bands: 28.0 to 28.8 MHz, and 28.8 to 29.7 MHz. For the amateur bands below 10 meters, optimal designs that cover the entire band are more easily achieved.

DESIGN VARIABLES

There are only a few variables available when one is designing a Yagi to meet certain design goals. The variables are:

(A)

(B)

(C)

Fig 5—Comparisons of three different 3-element 10-meter Yagi designs using 8-foot booms. At A, gain comparisons are shown. The Yagi designed for the best compromise of gain and SWR sacrifices an average of about 0.5 dB compared to the antenna designed for maximum gain. The Yagi designed for optimal F/R, gain and SWR sacrifices an average of 1.0 dB compared to the maximum-gain case, and about 0.4 dB compared to the compromise gain and SWR case. At B, the front-to-rear ratio is shown for the three different designs. The antenna designed for optimal combination of gain, F/R and SWR maintains a F/R higher than 20 dB across the entire frequency range, while the antenna designed strictly for gain has a F/R of 3 dB at the high end of the band. At C, the three antenna designs are compared for SWR bandwidth. At the high end of the band, the antenna designed strictly for gain has a very high SWR.

1. The physical length of the boom
2. The number of elements on the boom
3. The spacing of each element along the boom
4. The tuning of each element
5. The type of matching network used to feed the array.

GAIN AND BOOM LENGTH

As pointed out earlier, the gain of a Yagi is largely a function of the length of the boom. As the boom is made longer, the maximum gain potential rises. For a given boom length, the number of elements populating that boom can be varied, while still maintaining the antenna's gain, provided of course that the elements are tuned properly. In general, putting more elements on a boom gives the designer added flexibility to achieve desired design goals, especially to spread the response out over a frequency band.

Fig 5A is an example illustrating gain versus frequency for three different types of 3-element Yagis on 8-foot booms. The three antennas were designed for the lower end of the 10-meter band, 28.0 to 28.8 MHz, based on the following different design goals:

Antenna 1: Maximum mid-band gain, regardless of F/R or SWR across the band
Antenna 2: SWR less than 2:1 over the frequency band; best compromise gain, with no special consideration for F/R over the band.
Antenna 3: "Optimal" case: F/R greater than 20 dB, SWR less than 2:1 over the frequency band; best compromise gain.

Fig 5B shows the F/R over the frequency band for these three designs, and Fig 5C shows the SWR curves over the frequency band. Antenna 1, the design that strives strictly for maximum gain, has a poor SWR response over the band, as might be expected after the previous section discussing SWR. The SWR is 10:1 at 28.8 MHz and rises to 22:1 at 29 MHz. At 28 MHz, at the low end of the band, the SWR of the maximum-gain design is more than 6:1. Clearly, designing for maximum gain alone produces an unacceptable design in terms of SWR bandwidth. The F/R for Antenna 1 reaches a high point of about 20 dB at the low-frequency end of the band, but falls to only 3 dB at the high-frequency end.

Antenna 2, designed for the best compromise of gain while the SWR across the band is held to less than 2:1, achieves this goal, but at an average gain sacrifice of 0.7 dB compared to the maximum gain case. The F/R for this design is just under 15 dB over the band. This design is fairly typical of many amateur Yagi designs before the advent of computer modeling and optimization programs. SWR can easily be measured, and experimental optimization for forward gain is a fairly straightforward procedure. By contrast, overall pattern optimization is not a trivial thing to achieve experimentally, particu-

larly for antennas with more than four or five elements.

Antenna 3, designed for an optimum combination of F/R, SWR and gain, compromises forward gain an average of 1.0 dB compared to the maximum gain case, and about 0.4 dB compared to the compromise gain/SWR case. It achieves its design objectives of more than 20 dB F/R over the 28.0 to 28.8 MHz portion of the band, with an SWR less than 2:1 over that range.

Fig 6A shows the free-space gain versus frequency for the same three types of designs, but for a bigger 5-element 10-meter Yagi on a 20-foot boom. Fig 6B shows the variation in F/R, and Fig 6C shows the SWR curves versus frequency. Once again, the design that concentrates solely on maximum gain has a poor SWR curve over the band, reaching just over 6:1 toward the high end of the band. The difference in gain between the maximum gain case and the optimum design case has narrowed for this size of boom to an average of under 0.5 dB. This comes about because the designer has access to more variables in a 5-element design than he does in a 3-element design, and he can stagger-tune the various elements to spread the response out over the whole band.

Fig 7A, **B** and **C** show the same three types of designs, but for a 6-element Yagi on a 36-foot boom. The SWR bandwidth of the antenna designed for maximum gain has improved compared to the previous two shorter-boom examples, but the SWR still rises to more than 4:1 at 28.8 MHz, while the F/R ratio is pretty constant over the band, at a mediocre 11 dB average level. While the antenna designed for gain and SWR does hold the SWR below 2:1 over the band, it also has the same mediocre level of F/R performance as does the maximum-gain design.

The optimized 36-foot boom antenna achieves an excellent F/R of more than 22 dB over the whole 28.0 to 28.8 MHz band. Again, the availability of more elements and more space on the 36-foot long boom gives the designer more flexibility in broadbanding the response over the whole band, while sacrificing only 0.3 dB of gain compared to the maximum-gain design.

Fig 8A, **B**, and **C** show the same three types of 10-meter designs, but now for a 60-foot boom, populated with eight elements. With eight elements and a very long boom on which to space them out, the antenna designed solely for maximum gain can achieve a much better SWR response across the band, although the SWR does rise to more than 7:1 at the very high end of the band. The SWR remains less than 2:1 from 28.0 to 28.7 MHz, much better than for shorter-boom, maximum-gain designs. The worst-case F/R ratio is never better than 19 dB, however, and remains around 10 dB over much of the band. The antenna designed for the best compromise gain and SWR loses only about 0.1 dB of gain compared to the maximum-gain design, but does little better in terms of F/R across the band.

Contrasted to these two designs, the antenna optimized for F/R, SWR and gain has an outstanding pattern, exhibiting an F/R of more than 24 dB across the entire

(A)

(B)

(C)

Fig 6—Comparisons of three different designs for 5-element 10-meter Yagis on 20-foot booms. At A, the gain of three different 5-element 10-meter Yagi designs are graphed. The difference in gain between the three antennas narrows because the elements can be stagger-tuned to spread the response out better over the desired frequency band. The average gain reduction for the fully optimized antenna design is about 0.5 dB. At B, the optimal antenna displays better than 22 dB F/R over the band, while the Yagi designed for gain and SWR displays on average 10 dB less F/R throughout the band. At C, the SWR bandwidth is compared for the three Yagis. The antenna designed strictly for forward gain has a poor SWR bandwidth and a high peak SWR of 6:1 at 28.8 MHz.

band, while keeping the SWR below 2:1 from 28.0 to 28.9 MHz. It must sacrifice an average of only 0.4 dB compared to the maximum gain design at the low end of the band, and actually has more gain than the maximum gain and gain/SWR designs at the high-frequency end of the band.

The conclusion drawn from these and many other detailed comparisons is that designing strictly for maximum mid-band gain yields an inferior design when the antenna is examined over an entire frequency band, especially in terms of SWR. Designing a Yagi for both gain and SWR will yield antennas that have mediocre rearward patterns, but that lose relatively little gain compared to the maximum gain case, at least for designs with more than three elements.

However, designing a Yagi for an optimal combination of F/R, SWR and gain results in a loss of gain less than 0.5 dB compared to designs designed only for gain and SWR. **Fig 9** summarizes the forward gain achieved for the three different design types versus boom length,

as expressed in wavelength.

Except for the 2-element designs, the Yagis described in the rest of this chapter have the following design goals over a desired frequency band:

1. Front-to-rear ratio over the frequency band of more than 20 dB
2. SWR over the frequency band less than 2:1
3. Maximum gain consistent with points 1 and 2 above

Just for fun, **Fig 10** shows the gain versus boom length for theoretical 20-meter Yagis that have been designed to meet the three design goals above. The 31-element design for 14 MHz would be wondrous to behold. Sadly, it is unlikely that anyone will build one, considering that the boom would be 724 feet long! However, such a design *does* become practical when scaled to 432 MHz. In fact, a K1FO 22-element and a K1FO 31-element Yagi are the prototypes for the theoretical 14-MHz long-boom designs. See Chapter 18, VHF and UHF Antenna Systems.

(A)

(B)

(C)

Fig 7—Comparisons of three different 6-element 10-meter Yagi designs on 36-foot booms. At A, gain is shown over the band. With more elements and a longer boom, the tuning can be staggered even more to make the antenna gain more uniform over the band. This narrows the gain differential between the antenna designed strictly for maximum gain and the antenna designed for an optimal combination of F/R, SWR and gain. The average difference in gain is about 0.2 dB throughout the band. At B, the F/R performance over the band is shown for the three antenna designs. The antenna designed for optimal performance maintains an average of almost 15 dB better F/R over the whole band compared to the other designs. At C, the SWR bandwidth is compared. Again, the antenna designed strictly for maximum gain exhibits a high SWR of 4:1 at 28.8 MHz, and rises to more than 14:1 at 29.0 MHz.

OPTIMUM DESIGNS AND ELEMENT SPACING

Two-Element Yagis

Many hams consider a 2-element Yagi to give "the most bang for the buck" among various Yagi designs, particularly for portable operations such as Field Day. A 2-element Yagi has about 4 dB of gain over a simple dipole (sometimes jokingly called a "one-element Yagi") and gives a modest F/R of about 10 dB to help with rejection of interference on receive. By comparison, going from a 2-element to a 3-element Yagi increases the boom length by about 50% and adds another element, a 50% increase in the number of elements—for a gain increase of about 1 dB and another 10 dB in F/R.

Element Spacing in Larger Yagis

One of the more interesting results of computer modeling and optimization of high-performance Yagis with four or more elements is that a distinct pattern in the element spacings along the boom shows up consis-

tently. This pattern is relatively independent of boom length, once the boom is longer than about 0.3 λ.

The reflector, driven element and first director of these optimal designs are typically bunched rather closely together, occupying together only about 0.15 to 0.20 λ of the boom. This pattern contrasts sharply with older designs, where the amount of boom taken up by the reflector, driven element and first director was typically more than 0.3 λ. **Fig 11** shows the element spacings for an optimized 6-element, 36-foot boom, 10-meter design, compared to a W2PV 6-element design with constant spacing of 0.15 λ between all elements.

A problem arises with such a bunching of elements toward the reflector end of the boom—the wind loading of the antenna is not equal along the boom. Unless properly compensated, such new-generation Yagis will act like windvanes, punishing, and often breaking, the rotators trying to turn, or hold, them in the wind. One successful solution to windvaning has been to employ "dummy elements" made of PVC piping. These nonconducting elements are placed on the boom close to the last director so

(A)

(B)

(C)

Fig 8—Comparisons of three different 8-element 10-meter Yagi designs using 60-foot booms. At A, gain is shown over the frequency band. With even more freedom to stagger-tune elements and a very long boom on which to place them, the average antenna gain differential over the band is now less than 0.2 dB between the three design cases. At B, an excellent 24 dB F/R for the optimal design is maintained over the whole band, compared to the average of about 12 dB for the other two designs. At C, the SWR differential over the band is narrowed between the three designs, again because there are more variables available to broaden the bandwidth.

Fig 9—Gain versus boom length for three different 10-meter design goals. The goals are: (1) designed for maximum gain across band, (2) designed for a compromise of gain and SWR, and (3) designed for optimal F/R, SWR and gain across 28.0 to 28.8 MHz portion of 10-meter band. The gain difference is less than 0.5 dB for booms longer than approximately 0.5 λ.

the windload is equalized at the mast-to-boom bracket. In addition, it may be necessary to insert a small amount of lead weight at one end of the boom in order to balance the antenna weight.

Despite the relatively close spacing of the reflector, driven element and first director, modern optimal Yagi designs are not overly sensitive to small changes in either element length or spacing. In fact, these antennas can be constructed from design tables without excessive concern about close dimensional tolerances. In the HF range up to 30 MHz, building the antennas to the nearest $1/8$-inch results in performance remarkably consistent with the computations, without any "tweaking" or fine-tuning when the Yagi is on the tower.

ELEMENT TUNING

Element tuning (or *self-impedance*) is a complex function of the effective electrical length of each element and the effective diameter of the element. In turn, the effective length and diameter of each element is related to

Fig 10—Theoretical gain versus boom length for 20-meter Yagis designed for optimal combination of F/R, SWR and gain across the entire 14.0 to 14.35 MHz band. The theoretical gain approaches 20 dBi for a gigantic 724-foot boom, populated with 31 elements. Such a design on 20 meters is not too practical, of course, but can readily be achieved on a 24-foot boom on 432 MHz.

Fig 11—Tapering spacing versus constant element spacing. At A, illustration of how the spacing of the reflector, driven element and first director (over the first 0.19 λ of the boom) of an optimally designed Yagi is bunched together compared to the Yagi at B, which uses constant 0.15 λ spacing between all elements. The optimally designed antenna has more than 22 dB F/R and an SWR less than 1.5:1 over the frequency band 28.0 to 28.8 MHz.

the taper schedule (if telescoping aluminum tubing is used, the most common method of construction), the length of each telescoping section, the type and size of mounting bracket used to secure the element to or through the boom, and the size of the Yagi boom itself. See the section entitled "Antenna Frequency Scaling," and "Tapered Elements" in Chapter 2, Antenna Fundamentals, of this book for details about element tuning as a function of tapering and element diameter. Note especially that Yagis constructed using wire elements will perform very differently compared to the same antenna constructed with elements made of telescoping aluminum tubing.

The process by which a modern Yagi is designed usually starts out with the selection of the longest boom possible for a given installation. A suitable number of elements of a given taper schedule are then placed on this boom, and the gain, pattern and SWR are calculated over the entire frequency band of interest to the operator. Once an electrical design is chosen, the designer must then ensure the mechanical integrity of the antenna design. This involves verifying the integrity of the boom and each element in

the face of the wind and ice loading expected for a particular location. The section entitled "Construction with Aluminum Tubing" in Chapter 20, Antenna Materials and Accessories, of this book shows details of tapered telescoping aluminum elements for the upper HF bands. In addition, the ARRL book *Physical Design of Yagi Antennas*, by Dave Leeson, W6NL (ex-W6QHS), describes the mechanical design process for all portions of a Yagi antenna very thoroughly, and is highly recommended for serious Yagi builders.

Specific Monoband Yagi Designs

The detailed Yagi design tables that follow are for two taper schedules for HF Yagis covering the 14 through 30-MHz amateur bands. The heavy-duty elements are designed to survive at least 120-mph winds without icing, or 85-mph winds with $1/4$-inch radial ice. The medium-duty elements are designed to survive winds greater than 80 mph, or 60-mph winds with $1/4$-inch radial ice.

For 10.1 MHz, the elements shown are capable of surviving 105-mph winds, or 93-mph winds with $1/4$-inch radial ice. For 7.1 MHz the elements shown can survive 93-mph winds, or 69-mph winds with $1/4$-inch radial ice. For these two lower frequency bands, the elements and the booms needed are very large and heavy. Mounting, turning and keeping such antennas in the air is not a trivial task.

Each element is mounted above the boom with a heavy rectangular aluminum plate, by means of U-bolts with saddles, as shown in Fig 35 in Chapter 18, VHF and UHF Antenna Systems for a 6-meter Yagi. This method of element mounting is rugged and stable, and because the element is mounted away from the boom, the amount of element detuning due to the presence of the boom is minimal. The element dimensions given in each table already take into account any element detuning due to the boom-to-element mounting plate. For each element, the length of the tip determines the tuning, since the inner tubes are fixed in diameter and length.

Half Elements

Each design shows the dimensions for *one-half* of each element, mounted on *one side* of the boom. The other half of each element is symmetrical, mounted on the other side of the boom. The use of a tubing sleeve inside the center portion of the element is recommended, so that the element is not crushed by the mounting U-bolts. Unless otherwise noted, each section of tubing is made of 6061-T6 aluminum tubing, with a 0.058-inch wall thickness. This wall thickness ensures that the next standard size of tubing can telescope with it. Each telescoping section is inserted 3 inches into the larger tubing, and is secured by one of the methods shown in Fig 11 in Chapter 20, Antenna Materials and Accessories.

Matching System

Each antenna is designed with a driven-element length appropriate for a hairpin type of matching network. The driven-element's length may require slight readjustment for best match, particularly if a different matching network is used. *Do not change* either the lengths or the telescoping tubing schedule of the parasitic elements—they have been optimized for best performance and will not be affected by tuning of the driven element!

Fig 12—Typical construction techniques for an HF Yagi. This photo shows a hairpin match on a driven element that uses a fiberglass insulator (wrapped in black vinyl tape for protection against UV). Muffler clamps and saddles mount the element to the boom, while U-bolts and saddles mount the element to the boom-to-element plate. The gray PVC sleeves insulate the element from the plate. The feed coax is connected to the two bolts that also connect to the hairpin wire. Note that the hairpin is grounded at its opposite end to dissipate static charges that might otherwise build up.

Fig 12 is a photograph of the driven element for a 2-element 17-meter Yagi built by Chuck Hutchinson, K8CH, for the ARRL book *Simple and Fun Antennas for Hams.* The aluminum tubing on each side of the boom was 1-inch OD, and the two pieces were mechanically joined together with a $3/4$-inch OD fiberglass insulator. Chuck wound electrical tape over the insulator to protect the fiberglass from the sun's UV.

Chuck used 3-inch lengths of 1-inch sunlight-resistant PVC conduit, split lengthwise, to make the grey outer insulators for the driven element. The aluminum plates came from DX Engineering, as did the stainless-steel U-bolts and saddle clamps. These saddles ensured that the elements don't rotate on the 2-inch OD boom in the heavy winds in his part of rural Michigan.

You can see the bolts used to pin the center fiberglass insulator to the aluminum tubing, while also providing an electrical connection for the #12 hairpin wire and for the feed-line coax, which uses ferrite beads over the coax's outer vinyl jacket to make a common-mode current-type of balun (not shown in Fig 12). Note that the center of the hairpin is connected to the boom using a grounding lug for some measure of protection from static buildup.

10-METER YAGIS

Fig 13 describes the electrical performance of eight optimized 10-meter Yagis with boom lengths between 6 to 60 feet. The end of each boom includes 3 inches of space for the reflector and last-director (or driven element for the 2-element designs) mounting plates. Fig 13A shows the free-space gain versus frequency for each antenna; 13B shows the front-to-rear ratio, and 13C shows the SWR versus frequency. Each antenna with three or more elements was designed to cover the lower half of the 10-meter band from 28.0 to 28.8 MHz, with SWR less than 2:1 and F/R better than 20 dB over that range.

Fig 13D shows the taper schedule for two types of 10-meter elements. The heavy-duty design can survive 125-mph winds with no icing, and 88-mph winds with $^1/_4$-inch of radial ice. The medium-duty design can handle 96-mph winds with no icing, and 68-mph winds with $^1/_4$-inch of radial ice. The element-to-boom mounting plate for these Yagis is a 0.250-inch thick flat aluminum plate, 4 inches wide by 4 inches long. Each element except for the insulated driven element, is centered on the plate, held by two stainless-steel U-bolts with saddles. Another set

(A)

(B)

(C)

(D)

Fig 13—Gain, F/R and SWR performance versus frequency for optimized 10-meter Yagis. At A, gain is shown versus frequency for eight 10-meter Yagis whose booms range from 6 feet to 60 feet long. Except for the 2-element design, these Yagis have been optimized for better than 20 dB F/R and less than 2:1 SWR over the frequency range 28.0 to 28.8 MHz. At B, front-to-rear ratio for these antennas is shown versus frequency, and at C, SWR is shown over the frequency range. At D, the taper schedule is shown for heavy-duty and for medium-duty 10-meter elements. The heavy-duty elements can withstand 125-mph winds without icing, and 88-mph winds with $^1/_4$-inch radial ice. The medium-duty elements can survive 96-mph winds without icing, and 68-mph winds with $^1/_4$-inch radial ice. The wall thickness for each telescoping section of 6061-T6 aluminum tubing is 0.058 inches, and the overlap at each telescoping junction is 3 inches.

Table 1

Optimized 10-Meter Yagi Designs

Two-element 10-meter Yagi, 6 foot boom

Element	Spacing	Heavy-Duty Tip	Medium-Duty Tip
File Name		210-06H.YW	210-06M.YW
Reflector	0.000"	66.000"	71.500"
Driven Element	66.000"	57.625"	63.000"

Three-element 10-meter Yagi, 8 foot boom

Element	Spacing	Heavy-Duty Tip	Medium-Duty Tip
File Name		310-08H.YW	310-08M.YW
Reflector	0.000"	66.750"	71.875"
Driven Element	36.000"	57.625"	62.875"
Director 1	54.000"	53.125"	58.500"
Compensator	12" behind Dir. 1	19.000"	18.125"

Four-element 10-meter Yagi, 14 foot boom

Element	Spacing	Heavy-Duty Tip	Medium-Duty Tip
File Name		410-14H.YW	410-14M.YW
Reflector	0.000"	66.000"	72.000"
Driven Element	36.000"	58.625"	63.875"
Director 1	36.000"	57.000"	62.250"
Director 2	90.000"	47.750"	53.125"
Compensator	12" behind Dir. 2	22.000"	20.500"

Five-element 10-meter Yagi, 24 foot boom

Element	Spacing, inches	Heavy-Duty Tip	Medium-Duty Tip
File Name		510-24H.YW	510-24M.YW
Reflector	0.000"	65.625"	70.750"
Driven Element	36.000"	58.000"	63.250"
Director 1	36.000"	57.125"	62.375"
Director 2	99.000"	55.000"	60.250"
Director 3	111.000"	50.750"	56.125"
Compensator	12" behind Dir. 3	28.750"	26.750"

Six-element 10-meter Yagi, 36 foot boom

Element	Spacing, inches	Heavy-Duty Tip	Medium-Duty Tip
File Name		610-36H.YW	610-36M.YW
Reflector	0.000"	66.500"	71.500"
Driven Element	37.000"	58.500"	64.000"
Director 1	43.000"	57.125"	62.375"
Director 2	98.000"	54.875"	60.125"
Director 3	127.000"	53.875"	59.250"
Director 4	121.000"	49.875"	55.250"
Compensator	12" behind Dir. 4	32.000"	29.750"

Seven-element 10-meter Yagi, 48 foot boom

Element	Spacing, inches	Heavy-Duty Tip	Medium-Duty Tip
File Name		710-48H.YW	710-48M.YW
Reflector	0.000"	65.375"	70.500"
Driven Element	37.000"	59.000"	64.250"
Director 1	37.000"	57.500"	62.750"
Director 2	96.000"	54.875"	60.125"
Director 3	130.000"	52.250"	57.625"
Director 4	154.000"	52.625"	58.000"
Director 5	116.000"	49.875"	55.250"
Compensator	12" behind Dir. 5	35.750"	33.750"

Eight-element 10-meter Yagi, 60 foot boom

Element	Spacing, inches	Heavy-Duty Tip	Medium-Duty Tip
File Name		810-60H.YW	810-60M.YW
Reflector	0.000"	65.000"	70.125"
Driven Element	42.000"	58.000"	63.500"
Director 1	37.000"	57.125"	62.375"
Director 2	87.000"	55.375"	60.625"
Director 3	126.000"	53.250"	58.625"
Director 4	141.000"	51.875"	57.250"
Director 5	157.000"	52.500"	57.875"
Director 6	121.000"	50.125"	55.500"
Compensator	12" behind Dir. 6	59.375"	55.125"

These 10-meter Yagi designs are optimized for > 20 dB F/R, and SWR < 2:1 over frequency range from 28.000 to 28.800 MHz, for heavy-duty elements (125 mph wind survival) and for medium-duty (96 mph wind survival). For coverage from 28.8 to 29.7 MHz, subtract 2.000 inches from end of each element, but leave element spacings the same as shown here. Only element tip dimensions are shown, and all dimensions are inches. See Fig 13D for element telescoping tubing schedule. Torque compensator element is made of 2.5" OD PVC water pipe placed 12 inches behind last director. Dimensions shown for compensators is one-half of total length, centered on boom.

of U-bolts with saddles is used to secure the mounting plate to the boom.

Electrically each mounting plate is equivalent to a cylinder, with an effective diameter of 2.405 inches for the heavy-duty element, and 2.310 inches for the medium-duty element. The equivalent length on each side of the boom is 2 inches. These dimensions are incorporated in the files for the *YW* (Yagi for Windows) computer modeling program on the CD-ROM accompanying this book to simulate the effect of the mounting plate.

The second column in **Table 1** shows the spacing of each element relative to the next element in line on the boom, starting at the reflector, which itself is defined as being at the 0.000-inch reference point on the boom. The boom for antennas less than 30 feet long can be constructed of 2-inch OD tubing with 0.065-inch wall thickness. Designs larger than 30 feet long should use 3-inch OD heavy-wall tubing for the boom. Because each boom

has extra space at each end, the reflector is actually placed 3 inches from the end of the boom. For example, in the 310-08H.YW design (3 elements on an 8-foot boom), the driven element is placed 36 inches ahead of the reflector, and the director is placed 54 inches ahead of the driven element.

The next columns give the lengths for the variable tips for the heavy-duty and then the medium-duty elements. In the example above for the 310-08H.YW Yagi, the heavy-duty reflector tip, made out of $^1/_2$-inch OD tubing, sticks out 66.750 inches from the $^5/_8$-inch OD tubing. Note that each telescoping piece of tubing overlaps 3 inches inside the piece into which it fits, so the overall length of $^1/_8$-inch OD tubing is 69.750 inches long for the reflector. The medium-duty reflector tip has 71.875 inches protruding from the $^5/_8$-inch OD tube, and is 74.875 inches long overall. As previously stated, the dimensions are not extremely critical, although measurement accu-

Fig 14—Gain, F/R and SWR performance versus frequency for optimized 12-meter Yagis. At A, gain is shown versus frequency for seven 12-meter Yagis whose booms range from 6 feet to 54 feet long. Except for the 2-element design, these Yagis have been optimized for better than 20 dB F/R and less than 2:1 SWR over the narrow 12-meter band 24.89 to 24.99 MHz. At B, front-to-rear ratio for these antennas is shown versus frequency, and at C, SWR over the frequency range is shown. At D, the taper schedule for heavy-duty and for medium-duty 12-meter elements is shown. The heavy-duty elements can withstand 123-mph winds without icing, and 87-mph winds with $^1/_4$-inch radial ice. The medium-duty elements can survive 85-mph winds without icing, and 61-mph winds with $^1/_4$-inch radial ice. The wall thickness for each telescoping section of 6061-T6 aluminum tubing is 0.058 inches, and the overlap at each telescoping junction is 3 inches.

Table 2

Optimized 12-Meter Yagi Designs

Two-element 12-meter Yagi, 6 foot boom

Element	Spacing	Heavy-Duty Tip	Medium-Duty Tip
File Name		212-06H.YW	212-06M.YW
Reflector	0.000"	67.500"	72.500"
Driven Element	66.000"	59.500"	65.000"

Three-element 12-meter Yagi, 10 foot boom

Element	Spacing, inches	Heavy-Duty Tip	Medium-Duty Tip
File Name		312-10H.YW	312-10M.YW
Reflector	0.000"	69.000"	73.875"
Driven Element	40.000"	60.250"	65.250"
Director 1	74.000"	54.000"	59.125"
Compensator	12" behind Dir. 1	13.625"	12.000"

Four-element 12-meter Yagi, 15 foot boom

Element	Spacing, inches	Heavy-Duty Tip	Medium-Duty Tip
File Name		412-15H.YW	412-15M.YW
Reflector	0.000"	66.875"	71.875"
Driven Element	46.000"	61.000"	66.000"
Director 1	46.000"	58.625"	63.750"
Director 2	82.000"	50.875"	56.125"
Compensator	12" behind Dir. 2	16.375"	14.500"

Five-element 12-meter Yagi, 20 foot boom

Element	Spacing, inches	Heavy-Duty Tip	Medium-Duty Tip
File Name		512-20H.YW	512-20M.YW
Reflector	0.000"	69.750"	74.625"
Driven Element	46.000"	62.250"	67.000"
Director 1	46.000"	60.500"	65.500"
Director 2	48.000"	55.500"	60.625"
Director 3	94.000"	54.625"	59.750"
Compensator	12" behind Dir. 3	22.125"	19.625"

Six-element 12-meter Yagi, 30 foot boom

Element	Spacing, inches	Heavy-Duty Tip	Medium-Duty Tip
File Name		612-30H.YW	612-30M.YW
Reflector	0.000"	68.125"	73.000"
Driven Element	46.000"	61.750"	66.750"
Director 1	46.000"	60.250"	65.250"
Director 2	73.000"	52.375"	57.625"
Director 3	75.000"	57.625"	62.750"
Director 4	114.000"	53.625"	58.750"
Compensator	12" behind Dir. 4	30.000"	26.250"

Six-element 12-meter Yagi, 40 foot boom

Element	Spacing, inches	Heavy-Duty Tip	Medium-Duty Tip
File Name		612-40H.YW	612-40M.YW
Reflector	0.000"	67.000"	71.875"
Driven Element	46.000"	60.125"	65.500"
Director 1	46.000"	57.375"	62.500"
Director 2	91.000"	57.375"	62.500"
Director 3	157.000"	57.000"	62.125"
Director 4	134.000"	54.375"	59.500"
Compensator	12" behind Dir. 4	36.500"	31.625"

Seven-element 12-meter Yagi, 54 foot boom

Element	Spacing, inches	Heavy-Duty Tip	Medium-Duty Tip
File Name		712-54H.YW	712-54M.YW
Reflector	0.000"	68.000"	73.000"
Driven Element	46.000"	60.500"	65.500"
Director 1	46.000"	56.750"	61.875"
Director 2	75.000"	58.000"	63.125"
Director 3	161.000"	55.625"	60.750"
Director 4	174.000"	56.000"	61.125"
Director 5	140.000"	53.125"	58.375"
Compensator	12" behind Dir. 5	43.125"	37.500"

These 12-meter Yagi designs were optimized for > 20 dB F/R, and SWR < 2:1 over frequency range from 24.890 to 24.990 MHz, for heavy-duty elements (123 mph wind survival) and for medium-duty (85 mph wind survival). Only element tip dimensions are shown, and all dimensions are inches. See Fig 14D for element telescoping tubing schedule. Torque compensator element is made of 2.5" OD PVC water pipe placed 12" behind last director. Dimensions shown for compensators is one-half of total length, centered on boom.

15 Meter Yagis, Gain vs Frequency

(A)

15 Meter Yagis, F/R vs Frequency

(B)

15 Meter Yagis, SWR vs Frequency

(C)

Fig 15—Gain, F/R and SWR performance versus frequency for optimized 15-meter Yagis. At A, gain versus frequency is shown for eight 15-meter Yagis whose booms range from 6 feet to 80 feet long. Except for the 2-element design, these Yagis have been optimized for better than 20 dB F/R and less than 2:1 SWR over the frequency range 21.0 to 21.45 MHz. At B, front-to-rear ratio for these antennas is shown versus frequency, and at C, SWR over the frequency range is shown. At D, the taper schedule for heavy-duty and for medium-duty 15-meter elements is shown. The heavy-duty elements can withstand 124-mph winds without icing, and 90-mph winds with $^1/_4$-inch radial ice. The medium-duty elements can survive 86-mph winds without icing, and 61-mph winds with $^1/_4$-inch radial ice. The wall thickness for each telescoping section of 6061-T6 aluminum tubing is 0.058 inches, and the overlap at each telescoping junction is 3 inches.

(D)

racy to $^1/_8$ inch is desirable.

The last row in each variable tip column shows the length of one-half of the "dummy element" torque compensator used to correct for uneven wind loading along the boom. This compensator is made from 2.5 inches OD PVC water pipe mounted to an element-to-boom plate like those used for each element. The compensator is mounted 12 inches behind the last director, the first director in the case of the 3-element 310-08H.YW antenna. Note that the heavy-duty elements require a correspondingly longer torque compensator than do the medium-duty elements.

12-METER YAGIS

Fig 14 describes the electrical performance of seven optimized 12-meter Yagis with boom lengths between 6 to 54 feet. The end of each boom includes 3 inches of space for the reflector and last director (or driven element) mounting plates. The narrow frequency width of the 12-meter band allows the performance to be optimized easily. Fig 14A shows the free-space gain versus frequency for each antenna; 14B shows the front-to-rear ratio, and 14C shows the SWR versus frequency. Each antenna with three or more elements was designed to

Table 3
Optimized 15-Meter Yagi Designs

Two-element 15-meter Yagi, 6 foot boom

Element	Spacing	Heavy-Duty Tip	Medium-Duty Tip
File Name		215-06H.YW	215-06M.YW
Reflector	0.000"	62.000"	85.000"
Driven Element	66.000"	51.000"	74.000"

Three-element 15-meter Yagi, 12 foot boom

Element	Spacing	Heavy-Duty Tip	Medium-Duty Tip
File Name		315-12H.YW	315-12M.YW
Reflector	0.000"	62.000"	84.250"
Driven Element	48.000"	51.000"	73.750"
Director 1	92.000"	43.500"	66.750"
Compensator	12" behind Dir. 1	34.750"	37.625"

Four-element 15-meter Yagi, 18 foot boom

Element	Spacing	Heavy-Duty Tip	Medium-Duty Tip
File Name		415-18H.YW	415-18M.YW
Reflector	0.000"	61.000"	83.500"
Driven Element	56.000"	51.500"	74.500"
Director 1	56.000"	48.000"	71.125"
Director 2	98.000"	36.625"	60.250"
Compensator	12" behind Dir. 2	20.875"	18.625"

Five-element 15-meter Yagi, 24 foot boom

Element	Spacing	Heavy-Duty Tip	Medium-Duty Tip
File Name		515-24H.YW	515-24M.YW
Reflector	0.000"	62.000"	84.375"
Driven Element	48.000"	52.375"	75.250"
Director 1	48.000"	47.875"	71.000"
Director 2	52.000"	47.000"	70.125"
Director 3	134.000"	41.000"	64.375"
Compensator	12" behind Dir. 3	40.250"	35.125"

Six-element 15-meter Yagi, 36 foot boom

Element	Spacing	Heavy-Duty Tip	Medium-Duty Tip
File Name		615-36H.YW	615-36M.YW
Reflector	0.000"	61.000"	83.375"
Driven Element	53.000"	52.000"	75.000"
Director 1	56.000"	49.125"	72.125"
Director 2	59.000"	45.125"	68.375"
Director 3	116.000"	47.875"	71.000"
Director 4	142.000"	42.000"	65.375"
Compensator	12" behind Dir. 4	45.500"	39.750"

Seven-element 15-meter Yagi, 48 foot boom

Element	Spacing	Heavy-Duty Tip	Medium-Duty Tip
File Name		615-48H.YW	615-48M.YW
Reflector	0.000"	62.000"	84.000"
Driven Element	48.000"	52.000"	75.000"
Director 1	48.000"	51.250"	74.125"
Director 2	125.000"	48.000"	71.125"
Director 3	190.000"	45.500"	68.750"
Director 4	161.000"	42.000"	65.375"
Compensator	12" behind Dir. 4	51.500"	45.375"

Seven-element 15-meter Yagi, 60 foot boom

Element	Spacing	Heavy-Duty Tip	Medium-Duty Tip
File Name		715-60H.YW	715-60M.YW
Reflector	0.000"	59.750"	82.250"
Driven Element	48.000"	52.000"	75.000"
Director 1	48.000"	52.000"	74.875"
Director 2	93.000"	49.500"	72.500"
Director 3	173.000"	44.125"	67.375"
Director 4	197.000"	45.500"	68.750"
Director 5	155.000"	41.750"	65.125"
Compensator	12" behind Dir. 5	58.500"	51.000"

Eight-element 15-meter Yagi, 80 foot boom

Element	Spacing	Heavy-Duty Tip	Medium-Duty Tip
File Name		815-80H.YW	815-80M.YW
Reflector	0.000"	62.000"	84.000"
Driven Element	56.000"	52.500"	75.500"
Director 1	48.000"	51.500"	74.375"
Director 2	115.000"	48.375"	71.500"
Director 3	164.000"	45.750"	69.000"
Director 4	202.000"	43.125"	66.500"
Director 5	206.000"	44.750"	68.000"
Director 6	163.000"	40.875"	64.250"
Compensator	12" behind Dir. 6	95.000"	83.375"

These 15-meter Yagi designs are optimized for > 20 dB F/R, and SWR < 2:1 over entire frequency range from 21.000 to 21.450 MHz, for heavy-duty elements (124 mph wind survival) and for medium-duty (86 mph wind survival). Only element tip dimensions are shown. See Fig 15D for element telescoping tubing schedule. All dimensions are in inches. Torque compensator element is made of 2.5" OD PVC water pipe placed 12" behind last director, and dimensions shown for compensators is one-half of total length, centered on boom.

(A)

(B)

(C)

Fig 16—Gain, F/R and SWR performance versus frequency for optimized 17-meter Yagis. At A, gain versus frequency is shown for six 17-meter Yagis whose booms range from 6 feet to 60 feet long. Except for the 2-element design, these Yagis have been optimized for better than 20 dB F/R and less than 2:1 SWR over the narrow 17-meter band 18.068 to 18.168 MHz. At B, front-to-rear ratio for these antennas is shown versus frequency, and at C, SWR over the frequency range is shown. At D, the taper schedule for heavy-duty and for medium-duty 10-meter elements is shown. The heavy-duty elements can withstand 123-mph winds without icing, and 89-mph winds with ^{1}/4-inch radial ice. The medium-duty elements can survive 83-mph winds without icing, and 59-mph winds with ^{1}/4-inch radial ice. The wall thickness for each telescoping section of 6061-T6 aluminum tubing is 0.058 inches, and the overlap at each telescoping junction is 3 inches.

(D)

cover the narrow 12-meter band from 24.89 to 24.99 MHz, with SWR less than 2:1 and F/R better than 20 dB over that range.

Fig 14D shows the taper schedule for two types of 12-meter elements. The heavy-duty design can survive 123-mph winds with no icing, and 87-mph winds with ^{1}/4 inch of radial ice. The medium-duty design can handle 85-mph winds with no icing, and 61-mph winds with ^{1}/4 inch of radial ice. The element-to-boom mounting plate for these Yagis is a 0.375 inch thick flat aluminum plate, 5 inches wide by 6 inches long.

Electrically, each mounting plate is equivalent to a cylinder, with an effective diameter of 2.945 inches for the heavy-duty element, and 2.857 inches for the medium-

duty element. The equivalent length on each side of the boom is 3 inches. As usual, the torque compensator is mounted 12 inches behind the last director.

15-METER YAGIS

Fig 15 describes the electrical performance of eight optimized 15-meter Yagis with boom lengths between 6 feet to a spectacular 80 feet. The end of each boom includes 3 inches of space for the reflector and last-director (or driven element) mounting plates. Fig 15A shows the free-space gain versus frequency for each antenna; 15B shows the worst-case front-to-rear ratio, and 15C shows the SWR versus frequency. Each antenna with three or more elements was designed to cover the full 15-meter band from

Table 4

Optimized 17-meter Yagi Designs

Two-element 17-meter Yagi, 6 foot boom

Element	Spacing	Heavy-Duty Tip	Medium-Duty Tip
File Name		217-06H.YW	217-06M.YW
Reflector	0.000"	61.000"	89.000"
Driven Element	66.000"	48.000"	76.250"

Three-element 17-meter Yagi, 14 foot boom

Element	Spacing	Heavy-Duty Tip	Medium-Duty Tip
File Name		317-14H.YW	317-14M.YW
Reflector	0.000"	61.500"	91.500"
Driven Element	65.000"	52.000"	79.500"
Director 1	97.000"	46.000"	73.000"
	12" behind Dir. 1	12.625"	10.750"

Four-element 17-meter Yagi, 20 foot boom

Element	Spacing	Heavy-Duty Tip	Medium-Duty Tip
File Name		417-20H.YW	417-20M.YW
Reflector	0.000"	61.500"	89.500"
Driven Element	48.000"	54.250"	82.625"
Director 1	48.000"	52.625"	81.125"
Director 2	138.000"	40.500"	69.625"
Compensator	12" behind Dir. 2	42.500"	36.250"

Five-element 17-meter Yagi, 30 foot boom

Element	Spacing	Heavy-Duty Tip	Medium-Duty Tip
File Name		517-30H.YW	517-30M.YW
Reflector	0.000"	61.875"	89.875"
Driven Element	48.000"	52.250"	80.500"
Director 1	52.000"	49.625"	78.250"
Director 2	93.000"	49.875"	78.500"
Director 3	161.000"	43.500"	72.500"
Compensator	12" behind Dir. 3	54.375"	45.875"

Six-element 17-meter Yagi, 48 foot boom

Element	Spacing	Heavy-Duty Tip	Medium-Duty Tip
File Name		617-48H.YW	617-48M.YW
Reflector	0.000"	63.000"	90.250"
Driven Element	52.000"	52.500"	80.500"
Director 1	51.000"	45.500"	74.375"
Director 2	87.000"	47.875"	76.625"
Director 3	204.000"	47.000"	75.875"
Director 4	176.000"	42.000"	71.125"
Compensator	12" behind Dir. 4	68.250"	57.500"

Six-element 17-meter Yagi, 60 foot boom

Element	Spacing	Heavy-Duty Tip	Medium-Duty Tip
File Name		617-60H.YW	617-60M.YW
Reflector	0.000"	61.250"	89.250"
Driven Element	54.000"	54.750"	83.125"
Director 1	54.000"	52.250"	80.750"
Director 2	180.000"	46.000"	74.875"
Director 3	235.000"	44.625"	73.625"
Director 4	191.000"	41.500"	70.625"
Compensator	12" behind Dir. 4	62.875"	53.000"

These 17-m Yagi designs are optimized for > 20 dB F/R, and SWR < 2:1 over entire frequency range from18.068 to 18.168 MHz, for heavy-duty elements (123 mph wind survival) and for medium-duty (83 mph wind survival). Only element tip dimensions are shown. All dimensions are in inches. Torque compensator element is made of 2.5" OD PVC water pipe placed 12" behind last director, and dimensions shown for compensators is one-half of total length, centered on boom.

21.000 to 21.450 MHz, with SWR less than 2:1 and F/R ratio better than 20 dB over that range.

Fig 15D shows the taper schedule for two types of 15-meter elements. The heavy-duty design can survive 124-mph winds with no icing, and 90-mph winds with $1/4$ inch of radial ice. The medium-duty design can handle 86-mph winds with no icing, and 61-mph winds with $1/4$ inch of radial ice. The element-to-boom mounting plate for these Yagis is a 0.375-inch thick flat aluminum plate, 5 inches wide by 6 inches long.

Electrically, each mounting plate is equivalent to a cylinder, with an effective diameter of 3.0362 inches for

20 Meter Yagis, Gain vs Frequency

(A)

20 Meter Yagis, F/R vs Frequency

(B)

20 Meter Yagis, SWR vs Frequency

(C)

Fig 17—Gain, F/R and SWR performance versus frequency for optimized 20-meter Yagis. At A, gain versus frequency is shown for eight 20-meter Yagis whose booms range from 8 feet to 80 feet long. Except for the 2-element design, these Yagis have been optimized for better than 20 dB F/R and less than 2:1 SWR over the frequency range 14.0 to 14.35 MHz. At B, front-to-rear ratio for these antennas is shown versus frequency, and at C, SWR over the frequency range is shown. At D, the taper schedule for heavy-duty and for medium-duty 20-meter elements is shown. The heavy-duty elements can withstand 122-mph winds without icing, and 89-mph winds with $\frac{1}{4}$-inch radial ice. The medium-duty elements can survive 82-mph winds without icing, and 60-mph winds with $\frac{1}{4}$-inch radial ice. The wall thickness for each telescoping section of 6061-T6 aluminum tubing is 0.058 inches, and the overlap at each telescoping junction is 3 inches.

(D)

the heavy-duty element, and 2.9447 inches for the medium-duty element. The equivalent length on each side of the boom is 3 inches. As usual, the torque compensator is mounted 12 inches behind the last director.

17-METER YAGIS

Fig 16 describes the electrical performance of six optimized 17-meter Yagis with boom lengths between 6 to a heroic 60 feet. As usual, the end of each boom includes 3 inches of space for the reflector and last director (or driven element) mounting plates. Fig 16A shows the free-space gain versus frequency for each an-

Table 5

Optimized 20-Meter Yagi Designs

Two-element 20-meter Yagi, 8 foot boom

Element	Spacing	Heavy-Duty Tip	Medium-Duty Tip
File Name		220-08H.YW	220-08M.YW
Reflector	0.000"	66.000"	80.000"
Driven Element	90.000"	46.000"	59.000"

Three-element 20-meter Yagi, 16 foot boom

Element	Spacing	Heavy-Duty Tip	Medium-Duty Tip
File Name		320-16H.YW	320-16M.YW
Reflector	0.000"	69.625"	81.625"
Driven Element	80.000"	51.250"	64.500"
Director 1	106.000"	42.625"	56.375"
Compensator	12" behind Dir. 1	33.375"	38.250"

Four-element 20-meter Yagi, 26 foot boom

Element	Spacing	Heavy-Duty Tip	Medium-Duty Tip
File Name		420-26H.YW	420-26M.YW
Reflector	0.000"	65.625"	78.000"
Driven Element	72.000"	53.375"	65.375"
Director 1	60.000"	51.750"	63.875"
Director 2	174.000"	38.625"	51.500"
Compensator	12" behind Dir. 2	54.250"	44.250"

Five-element 20-meter Yagi, 34 foot boom

Element	Spacing	Heavy-Duty Tip	Medium-Duty Tip
File Name		520-34H.YW	520-34M.YW
Reflector	0.000"	68.625"	80.750"
Driven Element	72.000"	52.250"	65.500"
Director 1	71.000"	45.875"	59.375"
Director 2	68.000"	45.875"	59.375"
Director 3	191.000"	37.000"	51.000"
Compensator	12" behind Dir. 3	69.250"	56.250"

Five-element 20-meter Yagi, 40 foot boom

Element	Spacing	Heavy-Duty Tip	Medium-Duty Tip
File Name		520-40H.YW	520-40M.YW
Reflector	0.000"	68.375"	80.500"
Driven Element	72.000"	53.500"	66.625"
Director 1	72.000"	51.500"	64.625"
Director 2	139.000"	48.375"	61.750"
Director 3	191.000"	38.000"	52.000"
Compensator	12" behind Dir. 3	69.750"	56.750"

Five-element 20-meter Yagi, 48 foot boom

Element	Spacing	Heavy-Duty Tip	Medium-Duty Tip
File Name		520-48H.YW	520-48M.YW
Reflector	0.000"	66.250"	78.500"
Driven Element	72.000"	53.000"	66.000"
Director 1	88.000"	50.500"	63.750"
Director 2	199.000"	47.375"	60.875"
Director 3	211.000"	39.750"	53.625"
Compensator	12" behind Dir. 3	70.325"	57.325"

These 20-meter Yagi designs are optimized for > 20 dB F/R, and SWR < 2:1 over entire frequency range from 14.000 to 14.350 MHz, for heavy-duty elements (122 mph wind survival) and for medium-duty (82 mph wind survival). Only element tip dimensions are shown. See Fig 17 for element telescoping tubing schedule. All dimensions are in inches. Torque compensator element is made of 2.5" OD PVC water pipe placed 12" behind last director, and dimensions shown for compensators is one-half of total length, centered on boom.

Six-element 20-meter Yagi, 60 foot boom

Element	Spacing	Heavy-Duty Tip	Medium-Duty Tip
File Name		620-60H.YW	620-60M.YW
Reflector	0.000"	67.000"	79.250"
Driven Element	84.000"	51.500"	65.000"
Director 1	91.000"	45.125"	58.750"
Director 2	130.000"	41.375"	55.125"
Director 3	210.000"	46.875"	60.375"
Director 4	199.000"	39.125"	53.000"
Compensator	12" behind Dir. 4	72.875"	59.250"

Six-element 20-meter Yagi, 80 foot boom

Element	Spacing	Heavy-Duty Tip	Medium-Duty Tip
File Name		620-80H.YW	620-80M.YW
Reflector	0.000"	66.125"	78.375"
Driven Element	72.000"	52.375"	65.500"
Director 1	122.000"	49.125"	62.500"
Director 2	229.000"	44.500"	58.125"
Director 3	291.000"	42.625"	56.375"
Director 4	240.000"	38.750"	52.625"
Compensator	12" behind Dir. 4	78.750"	64.125"

(A)

30 Meter Yagis, Gain vs Frequency

Legend: 3-Ele. 48' Boom — 3-Ele. 32' Boom — 2-Ele. 15' Boom

(B)

30 Meter Yagis, F/R vs Frequency

Legend: 3-Ele. 48' Boom — 3-Ele. 32' Boom — 2-Ele. 15' Boom

(C)

30 Meter Yagis, SWR vs Frequency

Legend: 3-Ele. 48' Boom — 3-Ele. 32' Boom — 2-Ele. 15' Boom

Fig 18—Gain, F/R and SWR performance versus frequency for optimized 30-meter Yagis. At A, gain versus frequency is shown for three 30-meter Yagis whose booms range from 15 feet to 34 feet long, and which have been optimized for better than 10 dB F/R and less than 2:1 SWR over the frequency range 10.1 to 10.15 MHz. At B, front-to-rear ratio for these antennas is shown versus frequency, and at C, SWR over the frequency range is shown. At D, the taper schedule is shown for heavy-duty 30-meter elements, which can withstand 107-mph winds without icing, and 93-mph winds with $1/4$-inch radial ice. Except for the $2^{1}/_{4}$-inch and 2-inch sections, which have 0.083 inch thick walls, the wall thickness for the other telescoping sections of 6061-T6 aluminum tubing is 0.058 inches, and the overlap at the 1 inch telescoping junction with the $^{7}/_{8}$-inch section is complete. The 2-inch section utilizes two machined aluminum reducers to accommodate the 1-inch tubing.

(D)

tenna; 16B shows the worst-case front-to-rear ratio, and 16C shows the SWR versus frequency. Each antenna with three or more elements was designed to cover the narrow 17-meter band from 18.068 to 18.168 MHz, with SWR less than 2:1 and F/R ratio better than 20 dB over that range.

Fig 16D shows the taper schedule for two types of 17-meter elements. The heavy-duty design can survive 123-mph winds with no icing, and 83-mph winds with $1/4$-inch of radial ice. The medium-duty design can handle 83-mph winds with no icing, and 59-mph winds with ¼ inch of radial ice.

The element-to-boom mounting plate for these Yagis is a 0.375-inch thick flat aluminum plate, 6 inches wide by 8 inches long. Electrically, each mounting plate is equiva-

lent to a cylinder, with an effective diameter of 3.5122 inches for the heavy-duty element, and 3.3299 inches for the medium-duty element. The equivalent length on each side of the boom is 4 inches. As usual, the torque compensator is mounted 12 inches behind the last director.

20-METER YAGIS

Fig 17 describes the electrical performance of eight optimized 20-meter Yagis with boom lengths between 8 to a giant 80 feet. As usual, the end of each boom includes 3 inches of space for the reflector and last director (driven element) mounting plates. Fig 17A shows the free-space gain versus frequency for each antenna; 17B shows the front-to-rear ratio, and 17C shows the SWR versus frequency. Each antenna with three or more ele-

40 Meter Yagis, Gain vs Frequency

(A)

40 Meter Yagis, F/R vs Frequency

(B)

40 Meter Yagis, SWR vs Frequency

(C)

Fig 19—Gain, F/R and SWR performance versus frequency for optimized 40-meter Yagis. At A, gain versus frequency is shown for three 40-meter Yagis whose booms range from 20 feet to 48 feet long, and which have been optimized for better than 10 dB F/R and less than 2:1 SWR over the frequency range 7.0 to 7.2 MHz. At B, front-to-rear ratio for these antennas is shown versus frequency, and at C, SWR over the frequency range is shown. At D, the taper schedule is shown for heavy-duty 40-meter elements, which can withstand 107-mph winds without icing, and 93-mph winds with $1/4$-inch radial ice. Except for the $2^{1}/4$-inch and 2-inch sections, which have 0.083 inch thick walls, the wall thickness for the other telescoping sections of 6061-T6 aluminum tubing is 0.058 inches, and the overlap at the end telescoping junction is 3 inches. The 2-inch section utilizes two machined aluminum reducers to accommodate the 1-inch tubing.

(D)

ments was designed to cover the complete 20-meter band from 14.000 to 14.350 MHz, with SWR less than 2:1 and F/R ratio better than 20 dB over that range.

Fig 17D shows the taper schedule for two types of 20-meter elements. The heavy-duty design can survive 122-mph winds with no icing, and 89-mph winds with $1/4$ inch of radial ice. The medium-duty design can handle 82-mph winds with no icing, and 60-mph winds with $1/4$ inch of radial ice. The element-to-boom mounting plate for these Yagis is a 0.375-inch thick flat aluminum plate,

6 inches wide by 8 inches long. Electrically, each mounting plate is equivalent to a cylinder, with an effective diameter of 3.7063 inches for the heavy-duty element, and 3.4194 inches for the medium-duty element. The equivalent length on each side of the boom is 4 inches. As usual, the torque compensator is mounted 12 inches behind the last director.

30-METER YAGIS

Fig 18 describes the electrical performance of three

Table 6
Optimized 30-Meter Yagi Designs

Two-element 30-meter Yagi, 15 foot boom

Element	Spacing	Heavy-Duty Tip
File Name		230-15H.YW
Reflector	0.000"	50.250"
Driven Element	174.000"	14.875"

3-element 30-meter Yagi, 22 foot boom

Element	Spacing	Heavy-Duty Tip
File Name		330-22H.YW
Reflector	0.000	59.375
Driven Element	135.000	35.000
Director 1	123.000	19.625

Three-element 30-meter Yagi, 34 foot boom

Element	Spacing	Heavy-Duty Tip
File Name		330-34H.YW
Reflector	0.000"	53.750"
Driven Element	212"	29.000"
Director 1	190"	14.500"

These 30-m Yagi designs are optimized for > 10 dB F/R, and SWR < 2:1 over entire frequency range from 10.100 to 10.150 MHz for heavy-duty elements (105 mph wind survival). Only element tip dimensions are shown. See Fig 18D for element telescoping tubing schedule. All dimensions are in inches. No torque compensator element is required.

Table 7
Optimized 40-Meter Yagi Designs

Two-element 40-meter Yagi, 20 foot boom

Element	Spacing	Heavy-Duty Tip
File Name		240-20H.YW
Reflector	0.000"	85.000"
Driven Element	234.000"	35.000"

Three-element 40-meter Yagi, 32 foot boom

Element	Spacing	Heavy-Duty Tip
File Name		340-32H.YW
Reflector	0.000"	90.750"
Driven Element	196.000"	55.875"
Director 1	182.000"	33.875"

Three-element 40-meter Yagi, 48 foot boom

Element	Spacing	Heavy-Duty Tip
File Name		340-48H.YW
Reflector	0.000"	81.000"
Driven Element	300.000"	45.000"
Director 1	270.000"	21.000"

These 40-m Yagi designs are optimized for > 10 dB F/R, and SWR < 2:1 over low-end of frequency range from 7.000 to 7.200 MHz, for heavy-duty elements (95 mph wind survival). Only element tip dimensions are shown. See Fig 19D for element telescoping tubing schedule. All dimensions are in inches. No wind torque compensator is required.

optimized 30-meter Yagis with boom lengths between 15 to 34 feet. Because of the size and weight of the elements alone for Yagis on this band, only 2-element and 3-element designs are described. The front-to-rear ratio requirement for the 2-element antenna is relaxed to be greater than 10 dB over the band from 10.100 to 10.150 MHz, while that for the 3-element designs is kept at greater than 20 dB over that frequency range.

As usual, the end of each boom includes 3 inches of space for the reflector and last director mounting plates. Fig 18A shows the free-space gain versus frequency for each antenna; 18B shows the worst-case front-to-rear ratio, and 18C shows the SWR versus frequency.

Fig 18D shows the taper schedule for the 30-meter elements. Note that the wall thickness of the first two sections of tubing is 0.083 inches, rather than 0.058 inches. This heavy-duty element design can survive 107-mph winds with no icing, and 93-mph winds with 1/4 inch of radial ice. The element-to-boom mounting plate for these Yagis is a 0.500-inch thick flat aluminum plate, 6 inches wide by 24 inches long. Electrically, each mounting plate is equivalent to a cylinder, with an effective diameter of 4.684 inches. The equivalent length on each side of the boom is 12 inches. These designs require no torque compensator.

40-METER YAGIS

Fig 19 describes the electrical performance of three optimized 40-meter Yagis with boom lengths between 20

to 48 feet. Like the 30-meter antennas, because of the size and weight of the elements for a 40-meter Yagi, only 2-element and 3-element designs are described. The front-to-rear ratio requirement for the 2-element antenna is relaxed to be greater than 10 dB over the band from 7.000 to 7.300 MHz, while the goal for the 3-element designs is 20 dB over the frequency range of 7.000 to 7.200 MHz. It is exceedingly difficult to hold the F/R greater than 20 dB over the entire 40-meter band without sacrificing excessive gain with a 3-element design.

As usual, the end of each boom includes 3 inches of space for the reflector and last director mounting plates. Fig 19A shows the free-space gain versus frequency for each antenna; 19B shows the front-to-rear ratio, and 19C shows the SWR versus frequency.

Fig 19D shows the taper schedule for the 40-meter elements. Note that the wall thickness of the first two sections of tubing is 0.083 inches, rather than 0.058 inches. This element design can survive 93-mph winds with no icing, and 69-mph winds with 1/4 inch of radial ice. The element-to-boom mounting plate for these Yagis is a 0.500-inch thick flat aluminum plate, 6 inches wide by 24 inches long. Electrically each mounting plate is equivalent to a cylinder, with an effective diameter of 4.684 inches. The equivalent length on each side of the boom is 12 inches. These designs require no torque compensator.

Modifying Monoband Hy-Gain Yagis

Enterprising amateurs have long used the Telex Communications Hy-Gain "Long John" series of HF monobanders as a source of top-quality aluminum and hardware for customized Yagis. Often-modified older models include the 105BA for 10 meters, the 155BA for 15 meters, and the 204BA and 205BA for 20 meters.

Newer Hy-Gain designs, the 105CA, 155CA and 205CA, have been redesigned by computer for better performance.

Hy-Gain antennas have historically had an excellent reputation for superior mechanical design, and Hy-Gain proudly points out that many of their monobanders are still working after more than 30 years. In the older designs the elements were purposely spaced along the boom to achieve good weight balance at the mast-to-boom bracket, with electrical performance as a secondary goal. Thus, the electrical performance was not necessarily optimum, particularly over an entire amateur band. Newer Hy-Gain designs are electrically superior to the older ones, but because of their strong concern for weight-balance are still not optimal by the definitions used in this chapter.

Fig 20—Gain, F/R and SWR over the 28.0 to 28.8 MHz range for original and optimized Yagis using Hy-Gain hardware. Original 105BA design provided excellent weight balance at boom-to-mast bracket, but compromised the electrical performance somewhat because of non-optimum spacing of elements. Optimized design requires wind torque-balancing compensator element, and compensating weight at director end of boom to rebalance weight. The F/R ratio over the frequency range for the optimized design is more than 23 dB. Each element uses the original Hy-Gain taper schedule and element-to-boom clamp, but the length of the tip is changed per Table 8.

Fig 21—Gain, F/R and SWR over the 21.0 to 21.45 MHz band for original and optimized Yagis using Hy-Gain hardware. Original 155BA design provided excellent weight balance at boom-to-mast bracket, but compromised the electrical performance somewhat because of non-optimum spacing of elements. Optimized design requires wind torque-balancing compensator element, and compensating weight at director end of boom to rebalance weight. The F/R ratio over the frequency range for the optimized design is more than 22 dB. Each element uses the original Hy-Gain taper schedule and element-to-boom clamp, but the length of the tip is changed per Table 9.

Table 8
Optimized Hy-Gain 20-Meter Yagi Designs

Optimized 204BA, Four-element 20-meter Yagi, 26 foot boom

Element	Spacing	Element Tip
File Name		BV204CA.YW
Reflector	0.000"	56.000"
Driven Element	85.000"	52.000"
Director 1	72.000"	61.500"
Director 2	149.000"	50.125"

Optimized 205CA, Five-element 20-meter Yagi, 34 foot boom

Element	Spacing	Element Tip
File Name		BV205CA.YW
Reflector	0.000"	62.625"
Driven Element	72.000"	53.500"
Director 1	72.000"	63.875"
Director 2	74.000"	61.625"
Director 3	190.000"	55.000"

Table 9
Optimized Hy-Gain 15-Meter Yagi Designs

Optimized 155BA, Five-element 15-meter Yagi, 24 foot boom

Element	Spacing	Element Tip
File Name		BV155CA.YW
Reflector	0.000"	64.000"
Driven Element	48.000"	65.500"
Director 1	48.000"	63.875"
Director 2	82.750"	61.625"
Director 3	127.250"	55.000"

Fig 22—Gain, F/R and SWR over the 14.0 to 14.35 MHz band for original and optimized Yagis using Hy-Gain hardware. Original 205BA design provided good weight balance at boom-to-mast bracket, but compromised the electrical performance because of non-optimum spacing of elements. Optimized design requires wind torque-balancing compensator element, and compensating weight at director end of boom to rebalance weight. The F/R ratio over the frequency range for the optimized design is more than 23 dB, while the original design never went beyond 17 dB of F/R. Each element uses the original Hy-Gain taper schedule and element-to-boom clamp, but the length of the tip is changed per Table 10.

Table 10
Optimized Hy-Gain 10-Meter Yagi Designs

Optimized 105BA, Five-element 10-meter Yagi,
24 foot boom

Element	Spacing, inches	Element Tip
File Name		BV105CA.YW
Reflector	0.000"	44.250"
Driven Element	40.000"	53.625"
Director 1	40.000"	52.500"
Director 2	89.500"	50.500"
Director 3	112.250"	44.750"

With the addition of wind torque-compensation dummy elements, and with extra lead weights, where necessary, at the director end of the boom for weight-balance, the electrical performance can be enhanced, using the same proven mechanical parts.

Fig 20 shows the computed gain, F/R ratio and SWR for a 24-foot boom, 10-meter optimized Yagi (modified 105BA) using Hy-Gain hardware. **Fig 21** shows the same for a 26-foot boom 15-meter Yagi (modified 155BA), and **Fig 22** shows the same for a 34-foot boom (modified 205BA) 20-meter Yagi. **Tables 8** through **10** show dimensions for these designs. The original Hy-Gain taper schedule is used for each element. Only the length of the end tip (and the spacing along the boom) is changed for each element.

Multiband Yagis

So far, this chapter has discussed monoband Yagis—that is, Yagis designed for a single Amateur-Radio frequency band. Because hams have operating privileges on more than one band, multiband coverage has always been very desirable.

INTERLACING ELEMENTS

In the late 1940s, some experimenters tried interlacing Yagi elements for different frequencies on a single boom, mainly to cover the 10 and 20-meter bands (at that time the 15-meter band wasn't yet available to hams). The experimenters discovered, to their considerable chagrin, that the mutual interactions between different elements tuned to different frequencies are very difficult to handle.

Adjusting a lower-frequency element usually results in interaction with higher-frequency elements near it. In effect, the lower-frequency element acts like a retrograde reflector, throwing off the effectiveness of the higher-frequency directors nearby. Element lengths and the spacing between elements can be changed to improve performance of the higher-frequency Yagi, but the resulting compromise is rarely equal to that of an optimized

monoband Yagi. A reasonable compromise for portable operation may be found in Chapter 15, Portable Antennas, by VE7CA.

TRAPPED MULTIBANDERS

Multiband Yagis using a single boom can also be made using traps. Traps allow an element to have multiple resonances. See Chapter 7, Multiband Antennas, for details on trap designs. Commercial vendors have sold trapped antennas to hams since the 1950s and surveys show that after simple wire dipoles and multiband verticals, trapped triband Yagis are the most popular antennas in the Amateur Radio service.

The originator of the trapped tribander was Chester Buchanan, W3DZZ, in his Mar 1955 *QST* article, "The Multimatch Antenna System." On 10 meters this rather unusual tribander used two reflectors (one dedicated and one with traps) and two directors (one dedicated and one with traps). On 20 and 15 meters three of the five elements were active using traps. The W3DZZ tribander employed 12 traps overall, made with heavy wire and concentric tubular capacitors to hold down losses in the traps. Each trap was individually fine tuned after con-

struction before mounting it on an element.

Another example of a homemade tribander was the 26-foot boom 7-element 20/15/10-meter design described by Bob Myers, W1XT (ex-W1FBY) in Dec 1970 *QST*. The W1FBY tribander used only two sets of traps in the driven element, with dedicated reflectors and directors for each frequency band. Again, the traps were quite robust in this design to minimize trap losses, using $^7/_{16}$-inch aluminum tubing for the coils and short pieces of RG-8 coax as high-voltage tuning capacitors.

Only a relatively few hams actually built tribanders for themselves, mainly because of the mechanical complexity and the close tolerances required for such antennas. The traps themselves must be constructed quite accurately for reproducible results, and they must be carefully weatherproofed for long life in rain, snow, and often polluted or corrosive atmospheres.

Christmas Tree Stacks

Another possible method for achieving multiband coverage using monoband Yagis is to stack them in a "Christmas tree" arrangement. See **Fig 23**. For an installation covering 20, 15 and 10 meters, you could mount on the rotating mast just at the top of the tower the 20-meter monobander. Then perhaps 9 feet above that you would mount the 15-meter monobander, followed by the 10-meter monoband Yagi 7 feet further up on the mast. Another configuration would be to place the 10-meter Yagi in between the lower 20-meter and upper 15-meter Yagis. Whatever the arrangement, the antenna in the middle of such a Christmas-tree always suffers the most interaction from the lowest-frequency Yagi.

Dave Leeson, W6NL (ex-W6QHS), mentions that the 10-meter Yagi in his closely stacked Christmas Tree (15 meters at the top, 10 meters in the middle, and 20 meters at the bottom of the rotating mast) loses "substantial gain" because of serious interaction with the 20-meter antenna. (N6BV and K1VR calculated that the free-space gain in the W6NL stack drops to 5 dBi, compared to about 9 dBi with no surrounding antennas.) Monobanders are *definitely not* universally superior to tribanders in multiband installations. In private conversations, W6NL has indicated that he would not repeat this kind of short Christmas Tree installation again.

Forward Staggering

Some hams have built multiband Yagis on a common boom, using a technique called *forward staggering*. This means that that most (or all) of the higher-frequency elements are placed in front of any lower-frequency elements—in other words, most of the elements are not interlaced. Richard Fenwick, K5RR, described his triband Yagi design in Sep 1996 *QEX* magazine. This uses forward-stagger and open-sleeve design techniques and was optimized using several sophisticated modeling programs.

Fenwick's tribander used a 57-foot, 3-inch OD boom

Fig 23—"Christmas Tree" stack of 20/15/10-meter Yagis spaced vertically on a single rotating mast.

to hold 4 elements on 20 meters, 4 elements on 15 meters and 5 elements on 10 meters. **Fig 24** shows the element placement for the K5RR tribander. Most hams, of course, don't have the real-estate or the large rotator needed to turn such a large, but elegant solution to the interaction problem!

Force 12 C3 "Multi-Monoband" Triband Yagi

Antenna manufacturer Force 12 also uses forward-stagger layouts and patented combinations of open- and closed-sleeve drive techniques extensively in their product line of multiband antennas, which they call "multi-monoband Yagis." **Fig 25** shows the layout for the popular Force 12 C3 triband Yagi. The C3 uses no traps, thereby avoiding any losses due to traps. The C3 consists of three 2-element Yagis on an 18-foot boom, using full-sized elements designed to withstand high winds.

The C3 feed system employs open-sleeves, where the 20-meter driver element is fed with coax through a common-mode current balun and parasitically couples to the closely spaced 15-meter driver and the two 10-meter drivers to yield a feed-point impedances close to 50 Ω on all three bands. See the section on open-sleeve dipoles in Chapter 7, Multiband Antennas.

Note the use of the forward-stagger technique in the C3, especially on 10 meters. To reduce interaction with

Fig 24—Dimensions of K5RR's trapless tribander using "forward stagger" and open-sleeve techniques to manage interaction between elements for different frequencies.

Fig 25—Layout of Force 12 C3 multiband Yagi. Note that the 10-meter (driver/director) portion of the antenna is "forward staggered" ahead of the 15-meter (reflector/driver) portion, which in turn is placed ahead of the 20-meter (reflector/driver) portion. The antenna is fed at the 20-meter driver, which couples parasitically to the 15-meter driver and the two 10-meter drivers.

the lower-frequency elements behind it, the 10-meter portion of the C3 is mounted on the boom ahead of all the lower-frequency elements, with the main 10-meter parasitic element (#7) acting as a director. The lower-frequency elements behind the 10-meter section act as retrograde reflectors, gaining some improvement of the gain and pattern compared to a monoband 2-element Yagi. A simplified *EZNEC* model of the C3 is included on the CD-ROM accompanying this book.

On 15 meters, the main parasitic element (#2) is a dedicated reflector, but the other elements ahead on the boom act like retrograde directors to improve the gain and pattern somewhat over a typical 2-element Yagi with a reflector. On 20 meters, the C3 is a 2-element Yagi with a dedicated reflector (#1) at the back end of the boom.

The exact implementation of any Yagi, of course, depends on the way the elements are constructed using telescoping aluminum tubing. The C3 type of design is no exception.

Stacked Yagis

Monoband parasitic arrays are commonly stacked either in broadside or collinear fashion to produce additional directivity and gain. In HF amateur work, the most common broadside stack is a vertical stack of identical Yagis on a single tower. This arrangement is commonly called a *vertical stack*. At VHF and UHF, amateurs often employ collinear stacks, where identical Yagis are stacked side-by-side at the same height. This arrangement is called a *horizontal stack*, and is not usually found at HF, because of the severe mechanical difficulties involved with large, rotatable side-by-side arrays.

Fig 26 illustrates the two different stacking arrangements. In either case, the individual Yagis making up the stack are generally fed in phase. There are times, however, when individual antennas in a stacked array are purposely fed out of phase in order to emphasize a particular elevation pattern. See Chapter 17, Repeater Antenna Systems, for such a case where elevation pattern steering is implemented for a repeater station.

Let's look at the reasons hams stack Yagis:

- For more gain
- For a wider elevation footprint in a target geographical area
- For azimuthal diversity—two or more directions at once
- For less fading
- For less precipitation static

STACKS AND GAIN

Fig 27 compares the elevation responses for three antenna systems of 4-element 15-meter Yagis. The response for the single Yagi at a height of 120 feet peaks at an elevation of about 5°, with a second peak at 17° and a third at 29°. When operated by itself, the 60-foot high Yagi has its first peak at about 11° and its second peak beyond 34°.

The basic principle of a vertically stacked HF array is that it takes energy from higher-angle lobes and concentrates that energy into the main elevation lobe. The main lobe of the 120/60-foot stack peaks about 7° and is about 2 dB stronger than either the 60- or 120-foot antenna by itself. The shape of the left-hand side of the stack's main lobe is determined mainly by the 120-foot antenna's response. The right-hand side of the stack's main lobe is "stretched" rightwards (toward higher angles) mainly by the 60-foot Yagi, while the shape follows the curve of the 120-foot Yagi.

Look at the second and third lobes of the stack, which appear about 18° and 27°. These are about 14 dB down from the stack's peak gain, showing that energy has indeed been extracted from them. By contrast, look at the levels of the second and third lobes for the individual Yagis at 60 and 120 feet. These higher-angle lobes are almost as strong as the first lobes.

Fig 26—Stacking arrangements. At A, two Yagis are stacked vertically (broadside) on the same mast. At B, two Yagis are stacked horizontally (collinear) side-by-side. At HF the vertical stack is more common because of mechanical difficulties involved with large HF antennas stacked side-by-side, whereas at VHF and UHF the horizontal stack is common.

The stack squeezes higher-angle energy into its main elevation lobe, while maintaining the frontal lobe azimuth pattern of a single Yagi. This is the reason why many state-of-the-art contest stations are stacking arrays of relatively short-boom antennas, rather than stacking long-boom, higher-gain Yagis. A long-boom HF Yagi narrows the azimuthal pattern (and the elevation pattern too), making pointing the antenna more critical and making it more difficult to spread a signal over a wide azimuthal area, such as all of Europe and Asiatic Russia at one time.

STACKS AND WIDE ELEVATION FOOTPRINTS

Detailed studies using sophisticated computer models of the ionosphere have revealed that coverage

15 Meters
Stack vs. 120' and 60' Single 4-Element Yagis Over Flat Ground

Fig 27—Comparison of elevation patterns on 15 meters for a stack of 4-element Yagis at 120 and 60 feet and individual Yagis at those two heights. The shape of the stack's response is determined mainly by that of the top antenna.

10-Meters, W1 Boston to Europe
4-Ele. Yagis Over Flat Ground

Fig 28—Comparison of elevation patterns and elevation-angle statistics for individual 10-meter TH7DX tribanders mounted over flat ground aiming from New England to Europe. No single antenna can cover the wide range of angles needed—from 1° to 18°.

of a wide range of elevation angles is necessary to ensure consistent DX or contest coverage on the HF bands. These studies have been conducted over all phases of the 11-year solar cycle, and for numerous transmitting and receiving QTHs throughout the world.

Chapter 23, Radio Wave Propagation, covers these studies in more detail, and the CD-ROM accompanying this book contains a huge number of elevation-angle statistical tables for locations all around the world. The *HFTA* (HF Terrain Assessment) program on the CD-ROM can not only compute antenna elevation patterns over irregular local terrain, but it can compare them directly to the elevation-angle statistics for a particular target geographic area.

A 10-Meter Example

Fig 28 shows the 10-meter elevation-angle statistics for the New England path from Boston, Massachusetts, to all of the continent of Europe. The statistics are overlaid with the computed elevation response for three individual 4-element Yagis, at three heights: 90, 60 and 30 feet above flat ground. In terms of wavelength, these heights are 2.60 λ, 1.73 λ and 0.86 λ high.

You can see that the 90-foot high Yagi covers the lower elevation angles best, but it has a large null in its response centered at about 11°. This null puts a big hole in the coverage for some 22% of all the times the 10-meter band is open to Europe. At those angles where the 90-foot Yagi exhibits a null, the 60-foot Yagi would be effective, and so would the 30-foot Yagi. If that is the only antenna you have, the 90-foot high Yagi would be too high for good coverage of Europe from New England.

The peak statistical elevation angle into Europe is 5°, and this occurs about 11% of all the times the 10-meter band is open to Europe from Boston. At an

elevation of 5° the 30-foot high Yagi would be down almost 7 dB compared to the 90-foot high Yagi, but at 11° the 90-foot Yagi would be more than 22 dB down from the 30-foot Yagi. There is no single height at which one Yagi can optimally cover all the necessary elevation angles, especially to a large geographic area such as Europe—although the 60-foot high antenna is arguably the best compromise for a single height. To cover all the possibilities to Europe, however, you need a 10-meter antenna system that can cover equally well the entire range of elevation angles from 1° to 18°.

Fig 29 compares elevation-angle statistics for two 10-meter paths from New England to Europe and to Japan. The elevation angles needed for communications with the Far East are very low. Overlaid on Fig 29 for comparison are the elevation responses over flat ground for three different antenna systems, using identical 4-element Yagis:

- Three Yagis, stacked at 90, 60 and 30 feet
- Two Yagis, stacked at 70 and 40 feet
- One Yagi at 90 feet.

The best coverage of all the necessary angles on 10 meters to Europe is with the stack of three Yagis at 90/60/30 feet. The two-Yagi stack at 70 and 40 feet comes in a close second to Europe, and for elevation angles higher than about 9° the 70/40-foot stack is actually superior to the 90/60/30-foot stack.

Both of the stacks illustrated here give a wider *elevation footprint* than any single antenna, so that all the angles can be covered automatically without having to switch from higher to lower antennas manually. This is perhaps the major benefit of using stacks, but not the only

10 Meters, W1 Boston to Europe and Japan
Stacks vs. 90' Single 4-Element Yagi Over Flat Ground

Fig 29—Combinations of 4-element Yagis over flat ground. The elevation-angle statistics into Japan from New England (Boston) are represented by the black vertical bars, while the grey vertical bars represent the elevation-angle statistics to Europe. The 90/60/30-foot stack has the best *elevation footprint* into Japan, although the 70/40-foot stack performs well also.

one, as we'll see.

To Japan, the necessary range of elevation angles is considerably smaller than that needed to a larger geographic target area like Europe. The 90/60/30-foot stack is still best on the basis of having higher gain at low angles, although the two-Yagi stack at 70 and 40 feet is a good choice too. Note that the single 90-foot high Yagi's performance is very close to the 70/40-foot stack of two Yagis at low angles, but the two-Yagi stack is superior to the single 90-foot antenna for angles higher than about 5° on 10 meters.

A 15-Meter Example

The situation is similar on 15 meters from New England to Europe. On 15 meters, the range of angles needed to fully cover Europe is 1° to 28°. This large range of angles makes covering all the angles even more challenging. Ken Wolff, K1EA, a devoted contest operator and the author of the famous *CT* contest logging program, put it very clearly when he wrote in the bulletin for the Yankee Clipper Contest Club:

"Suppose you have 15-meter Yagis at 120 feet and 60 feet, but can feed only one at a time. A 15-meter beam at 120 feet has its first maximum at roughly 5° and the first minimum at 10°. The Yagi at 60 feet has a maximum at 10° and a minimum at 2°. At daybreak, the band is just opening, signals are arriving at 3° or less and the high Yagi outperforms the low one by 5-10 dB. Late in the morning, western Europeans are arriving at angles of 10° or more, while UA6 is still arriving at 4-5°. Western Europe can be 20-30 dB louder on the low antenna than the high! What to do? Stack em!"

15 Meters, W1 Boston to Europe
Stack vs. 120' and 60' Single 4-Element Yagis Over Flat Ground

Fig 30—Comparison of elevation patterns for K1EA's illustration about 15-meter Yagis mounted over flat ground, with elevation-angle statistics to Europe added. The stack at 120 and 60 feet yields a better footprint over the range of 3° to 11° at its half-power points, better than either antenna by itself.

Fig 30 illustrates K1EA's scenario, showing the elevation statistics to Europe from Massachusetts and the elevation responses for a 120- and a 60-foot high, 4-element Yagi, both over flat ground, together with the response for both antennas operated as vertical stack. The half-power beamwidth of the stack's main lobe is 6.9°, while that for the 120-foot antenna by itself is 5.5° and that for the 60-foot antenna by itself is 11.1°. The half-power beamwidth numbers by themselves can be deceiving, mainly because the stack starts out with a higher gain. A more meaningful observation is that the stack has equal to or more gain than either of the two individual antennas from 1° to about 10°.

Is such a stack of 15-meter Yagis at 120 and 60 feet optimal for the New England to Europe path? No, it isn't, as we'll explore later, but the stack is clearly better than either antenna by itself for the scenario K1EA outlined above.

A 20-Meter Example

Take a look now at **Fig 31**, which overlays elevation-angle statistics for Europe (gray vertical bars) and Japan (black vertical bars) from Boston on 20 meters, plus the elevation responses for four different sets of antennas mounted over flat ground. Just for emphasis, the highest antenna is a 200-foot high 4-Element Yagi. It is clearly too high for complete coverage of all the needed angles into Europe. A number of New England operators have verified that this is true—a really high Yagi will open the 20-meter band to Europe in the morning and may shut it down in the afternoon, but during the middle of the day the high antenna gets soundly beaten by lower antennas.

To Japan, however, from New England the range of angles needed narrows considerably on 20 meters,

Fig 31—Comparison of elevation patterns for individual 20-meter Yagis over flat ground, compared with the range of elevation angles needed on this band from New England to Europe (gray bars) and to Japan (black bars). For fun, the response of a 200-foot high Yagi is included—this antenna is far too high to cover the needed range of angles to Europe because of its deep nulls at critical angles, like 10°. But the 200 footer is great into Japan!

from 1° to only 11°. For these angles, the 200-foot Yagi is the best antenna to work Japan from New England on 20 meters.

This is true provided that the antenna is aiming out over flat ground. The actual, generally irregular, terrain in various directions can profoundly modify the takeoff angles favored by an antenna system, particularly on steep hills. There will be more discussion on this important topic later on.

SPARE ME THE NULLS!

Now, let's look closely at some other 20-meter antennas in Fig 28, the ones at 120 and 60 feet. At an elevation angle of 8° the difference in elevation response between the 60- and 120-foot high Yagis is just over 3 dB. Can you really notice a change of 3 dB on the air? Signals on the HF bands often rise and fall quickly due to fading, so differences of 2 or 3 dB are difficult to discern. Consequently, the difference between a Yagi at 120 feet and one at 60 feet may be difficult to detect at elevation angles covered well by both antennas. But a *deep null* in the elevation response is very noticeable.

Back in 1990, when editor Dean Straw, N6BV, put up his 120-foot tower in Windham, New Hampshire, his first operational antenna was a 5-element triband Yagi, with 3 elements on 40 and 4 elements on both 20 and 15 meters. Just as the sun was going down on a late August day Straw finished connecting the feed line in the shack. The antenna seemed to be playing like it should, with a good SWR curve and a good pattern when it was

rotated. So N6BV/1 called a nearby friend, John Dorr, K1AR, on the telephone and asked him to get on the air to make some signal comparisons on 20 meters into Europe.

Straw was shocked that every European they worked that evening said his signal was several S units weaker than K1AR's. Dorr was using a 4-element 20-meter monobander at 90 feet, which at first glance should have been comparable to Straw's 4-element antenna at 120 feet. But N6BV really shouldn't have been so shocked—in New England, the elevation angles from Europe late in the day on 20 meters are almost always higher than 11°, and that is true for the entire solar cycle.

The N6BV/1 station was located on a small hill, while K1AR was located on flat terrain towards Europe. The elevation response for N6BV/1's 120-foot high Yagi fell right into a deep null at 11°. This was later confirmed many times in the following eight years that the N6BV/1 station was operational. During the early morning opening on 20 meters into Europe, the top antenna was always very close to or equal to the stack of three TH7DX tribanders at 90/60/30 feet on the same tower. But in the afternoon the top antenna was *always* decidedly worse than the stack, so much so that Straw often wondered whether something had gone wrong with the top antenna!

So what's the moral to this short tale? It's simple: *The gain you can achieve, while useful, is not so important as the deep nulls you can avoid by using a stack.*

STACKING DISTANCES BETWEEN YAGIS

So far, we've examined stacks as a means of achieving more gain over an individual Yagi, while also matching the antenna system's response to the range of elevation angles needed for particular propagation paths. Most importantly, we seek to avoid nulls in the elevation response. Earlier we asked whether a 120/60-foot stack was optimal for the path from New England to Europe on 15 meters. Let's examine how the stacking distance between individual antennas affects the performance of a stack.

Fig 32 shows overlays of various combinations of 15-meter Yagis. Just for reference, a plot for a single 60-foot high Yagi is also included. Let's start by looking at the most widely spaced stack in the group: the 120/30-foot stack. Here, the spacing is obviously too large, since the second lobe is actually stronger than the first lobe. In terms of wavelength, the 90-foot spacing between antennas in this stack is 1.94 λ, a large spacing indeed.

There is a great deal of folklore and superstition among amateurs about stacking distances for HF arrays. For years, high-performance stacked Yagi arrays have been used for weak-signal DXing on the VHF and UHF bands. The most extreme example of weak-signal work is EME work (Earth-Moon-Earth, also called *moonbounce*) because of the huge path losses incurred on the way to and from the Moon. The most successful arrays used for

Fig 32—Various stacks towards Europe from New England for 15-meters. The stack at 120 and 30 feet is clearly suboptimal, since the second lobe is higher than the first lobe. The 120/60-foot stack is better in this regard, but is still not as good a performer as the 90/60/30-foot stack. It's debatable whether going to four Yagis in the 120/90/60/30-foot stack is a good idea because it drops below the performance of the 90/60/30-foot stack at about 10° in elevation. The exact distance between practical HF Yagis is not critical to obtain the benefits of stacking. For a stack of tribanders at 90, 60 and 30 feet, the distance in wavelengths between individual antennas is 0.87 λ at 28.5 MHz, 0.65 λ at 21.2 MHz, and 0.43 λ at 14.2 MHz.

moonbounce have low sidelobe levels and very narrow frontal lobes that give huge amounts of gain. The low sidelobes help minimize received noise, since the receive levels for signals that do manage to bounce off the Moon and return to Earth are exceedingly weak.

But HF work is different from moonbounce in that rigorously trying to minimize high-angle lobes is far less crucial at HF, where we've already shown that the main goal is to achieve gain over a wide elevation-plane footprint without any disastrous nulls in the pattern. The gain gradually increases as spacing in terms of wavelength is increased between individual Yagis in a stack, and then decreases slowly once the spacing is greater than about 1.0 λ. The difference in gain between spacings of 0.5 λ to 1.0 λ for a stack of typical HF Yagis amounts to only a fraction of a decibel. Stacking distances on the order of 0.6 λ to 0.75 λ give best gain commensurate with good patterns.

While the stack at 120/60 feet in Fig 32 doesn't have the second-lobe-stronger problem the 120/30-foot stack has, 60 feet between antennas is 1.29 λ, again outside the normal range of HF stack spacings. As a consequence, the 120/60-foot stack doesn't cover the range of elevation angles as well as it could, and is inferior to both the 90/60/30-foot stack and the 120/90/60/30-foot stack. The

120/60-foot two-Yagi stack needs at least one more antenna placed in-between to spread out the elevation-range coverage and to provide more gain.

It could be debated, but the 90/60/30-foot stack seems optimal for coverage of all the angles into Europe from New England on 15 meters. Note that the 30-foot spacing between Yagis is 0.65 λ on 21.2 MHz, right in the middle of the range of typical stack spacings.

Switching Out Yagis in the Stack

Still, the extra gain that is available at low elevation angles from a 120/90/60/30-foot high, four-Yagi stack in Fig 32 is alluring. For those statistically possible, but less likely, occasions when the elevation angle is higher than about 12°, it would be advantageous to switch out the top 120-foot Yagi and operate with only the lower three Yagis in a stack. (This also allows the top antenna to be rotated in another direction, an aspect we'll explore later.) There are even times when the incoming angles are really high and when the top two antennas might be switched out to create a 60/30-foot stack. Later in this chapter we'll explore flexible circuitry for such stack switching.

Stacking Distance and Lobes at HF

Let's look a little more closely at how a stack achieves gain and a wide elevation footprint. **Fig 33** shows a rectangular X-Y graph of the elevation response from 0° to 180° for two 3-element 15-meter Yagis (with 12-foot booms) spaced 30 feet apart (0.65 λ at 21.2 MHz), but mounted at two different heights: 95/65 and 85/55 feet. The rectangular plot gives more resolution than is possible on a polar plot. Note that the heights shown represent typical stacking heights on 15 meters—there's nothing magic about these choices. The free-space H-Plane pattern for the 30-foot spaced stack is also shown for reference.

The worst-case overhead elevation lobe, which ranges from about 60° to 120° in elevation (±30° from straight overhead at 90°), is about 14.7 dB down for the 95/65-foot stack. The overhead lobe peaks broadly at an elevation angle of about 82°. The overhead lobe for the lower 85/55-foot stack occurs at an elevation of about 64°, where it is 19 dB down.

The F/B for both 3-element sets of heights is about 15 dB, well down from the excellent 32 dB F/B for each Yagi by itself. The degradation of F/B is mainly due to mutual coupling to its neighbor in the stack.

The ground-reflection pattern in effect "modulates" the free-space pattern of the individual Yagi, but in a complex and not always intuitive manner. This is quite evident for the 85/55-foot stack at near-overhead angles. In this region things become complicated indeed, because the fourth and fifth lobes due to ground reflections are interacting with the free-space pattern of the stack.

Because the spacing remains constant at 30 feet for

Fig 33—Rectangular plot comparing two 15-meter stacks of 3-element Yagis—each antenna is spaced 30 feet from its partner, but at different heights. The lobes are a complicated function of the antenna height, not the spacing, since that remains constant.

Fig 34—Four spacing scenarios for two 3-element 15-meter Yagis. Things get very complicated. The optimal spacing in terms of stacking gain is 30 feet, which is 0.65 λ. The near-overhead lobes turn out to be ugly looking, but unimportant for skywave propagation.

these pairs of antennas, however, the main determinant for the upper-elevation angle lobes is the distance of the horizontally polarized antennas above the ground, not the spacing between them.

Changing the Stack Spacing

Fig 34 demonstrates just how complicated things get for four different spacing scenarios. Here, the lower Yagi in the stack is moved down in 5-foot increments from the 95/70 feet level, to 95/65, 95/60 and 95/55 feet. The closest spacing, 25 feet in the 95/70-foot stack, yields nominally the "cleanest" pattern in the overhead region from 60° to 120°. The worst-case overhead lobe for the 95/70-foot stack is down 28 dB from peak. The F/B is again about 15 dB.

The worst case overhead lobe for the widest spacing, 40 feet in the 95/55-foot stack, is about 11 dB down from peak. The F/B has increased marginally, but is still only about 16 dB. It is difficult to pinpoint directly whether the spacing or the height above ground is the major determinant for the various lobe amplitudes for the 3-element stack. We'll soon look closely at whether the overhead lobe is important or not for HF work.

Longer Boom Length and Stack Spacing

Fig 35 shows the same type overlay of elevation plots, but this time for two 7-element 15-meter Yagis on gigantic 64-foot booms. These Yagis are also spaced 30 feet apart (0.65 λ at 21.2 MHz), mounted at the same four sets of heights in Fig 34. As you'd expect, the free-space elevation pattern for a stacked pair of 7-element Yagis on 64-foot booms is narrower than that for a stacked pair of 3-element Yagis on 12-foot booms. The intrinsic

Fig 35—Four spacing scenarios for two large 7-element 15-meter Yagis (on 64-foot booms). Again, a 0.65 λ spacing (30 feet) provides the most stacking gain.

F/B of the longer Yagi is also better than the F/B of the shorter antenna. As a result, all lobes beyond the main lobe of the stacked 7-element pair are lower for both sets of heights than their 3-element counterparts. The worst-case overhead lobe for the 7-element 95/65-foot pair is about 22 dB down at 76° and the F/B at 172° is greater than 21 dB for all four sets of heights.

Table 11 summarizes the main performance characteristics for four sets of stacked Yagis. The first entry for each boom length is for the Yagi by itself at a height of 95 feet. Stacked configurations are next listed in order of gain. The column labeled "Worst lobe, dB re Peak" is the

Table 11

Example, Spacing Between 15–Meter Yagis

Antenna	Peak Gain dBi	Worst Lobe dB re Peak	Worst Lobe Angle,°	F/B dB	Overhead Lobe dB re Peak
3–Ele., 12' boom					
By itself 95'	13.2	−0.9	21	28.8	−17.5
95'/65' (Δ 30')	16.08	−4.5	25	14.9	−14.7
95'/60' (Δ 35')	16.01	−6.2	24	15.1	−10.9
95'/70' (Δ 25')	15.81	−3.2	24	14.8	−28
95'/55' (Δ 40')	15.71	−8.7	24	16.4	−11
95'/75' (Δ 20')	15.34	−2.3	23	16.3	−17.2
4–Ele., 18' boom					
By itself 95'	13.92	−1	21	28.3	−20.4
95'/65' (Δ 30')	16.63	−4.5	23	18.5	−17.3
95'/60' (Δ 35')	16.6	−6.2	24	18.2	−13.1
95'/55' (Δ 40')	16.36	−8.7	24	19.8	−13.2
95'/70' (Δ 25')	16.36	−3.3	24	20.4	−31.8
95'/75' (Δ 20')	15.92	−2.5	23	25.9	−19
5–Ele., 23' boom					
By itself 95'	14.26	−1.1	21	27.9	−22.3
95'/65' (Δ 30')	16.86	−4.6	24	20.8	−19
95'/60' (Δ 35')	16.86	−6.3	24	20.7	−14.4
95'/55' (Δ 40')	16.67	−8.8	24	23.5	−14.4
95'/70' (Δ 25')	16.59	−3.4	24	24.9	−34.4
95'/75' (Δ 20')	16.18	−2.6	23	34.3	−20.2
7–Ele., 64' boom					
By itself 95'	17.93	−2.2	21	28.9	−17.1
95'/65' (Δ 30')	19.39	−6.9	24.3	21.4	−21.9
95'/60' (Δ 35')	19.38	−8.6	24	21.4	−16.9
95'/55' (Δ 40')	19.29	−10.9	24	25.0	−18.6
95'/70' (Δ 25')	19.26	−5.5	23	24	−35.3
95'/75' (Δ 20')	19.08	−4.6	23	27	−23.4

amplitude of the second lobe due to ground reflections, and the elevation angle of that second lobe is listed as well.

Besides the 3- and 7-element designs discussed above, we've also added 4- and 5-element designs in Table 11. Over the range of stacking distances between 20 and 40 feet on 15 meters (0.43 λ to 0.86 λ), the peak gain for the 3-element stacks changes less than 0.75 dB, with the 30-foot spacing exhibiting the highest gain. The differences between peak gains versus stacking distance become smaller as the boom length increases. For example, for the 64-foot boom Yagi, the gain varies 19.39 – 19.08 = 0.31 dB for stack spacings from 20 to 40 feet.

In other words, changing the spacing from 20 to 40 feet (0.43 λ to 0.86 λ) doesn't change the gain significantly for boom lengths from 12 to 64 feet (0.26 λ to 1.38 λ). From the point of view of gain, the vertical spacing between individual antennas in an HF stack is not critical.

The worst-case lobes (generally speaking, the second lobe due to ground reflections) are highest for a Yagi operated by itself. After all, a single Yagi doesn't benefit from the redistribution of energy from higher-angle lobes into the main lobe that a stack gives. Thus, the 3-element, 12-foot boom Yagi by itself at 95 feet would have a second lobe at 21° that is only 0.9 dB down from the main lobe, while the stack of two such antennas at a 30-foot (0.65 λ) spacing at 95/65 feet would have a second lobe down 4.5 dB. As the spacing between antennas in a vertical stack increases, the second lobe is suppressed more, up to 8.7 dB at a 40-foot (0.86 λ) spacing.

Since the free-space elevation pattern for a 3-element Yagi is wider than that for a 7-element Yagi, the second lobe due to ground reflection will be somewhat reduced. This is true for all longer-boom antennas operating by themselves over ground. Used in stacks, the second lobe's amplitude will vary depending on spacing between antennas, but they range only about 6 dB.

The front-to-back ratio will also tend to increase with longer boom lengths on a properly designed Yagi. Table 11 shows that the F/B is somewhat better for closer spacings between antennas in a stack, a rather non-intuitive result, considering that the mutual coupling should be greater for closer antennas. For example, the 5-ele-

ment Yagi stack with a 20-foot spacing has a exceptional F/B of 34.3 dB, compared to a F/B of 21.4 dB with the 30-foot spacing distance that gives nominally the most gain. High values of F/B, however, rarely hold over a wide frequency range because of the very critical phasing relationships necessary to get a deep null, so the difference between 34.3 and 21.4 dB would rarely be noticeable in practice.

The near-overhead lobe structure (between 60° to 120° in elevation) tends also to be lower for smaller stack spacings—for all boom lengths—peaking in this example at a spacing of 25 feet for the boom lengths considered here. Since the peak gain actually occurs with smaller spacing between Yagis in this 7-element stack, even relatively large and messy looking overhead lobes are not subtracting from the stacking gain. In the next section we'll now examine whether this overhead lobe is important or not.

Are Higher-Angle Lobes Important?

We've already shown that the exact spacing between HF Yagis is not critical for stacking gain. Further, the heights (and hence spacing) of the individual Yagis in a stack interact in a complicated fashion to determine higher-angle lobes.

Let's examine the relevance of such higher-angle lobes for stacked HF Yagis, this time in terms of interference reduction on receive. As Chapter 23, Radio Wave Propagation, points out, few DX signals arrive at elevation angles greater than about 30°. In fact, DX signals only propagate at elevation angles in the range from 1° to 30° on all the bands where operators might reasonably expect to stack Yagis—nominally from 7 to 29.7 MHz.

You should remember that the definition of the *critical frequency* for HF propagation is the highest frequency for which a wave launched directly overhead at 90° elevation is reflected back down to Earth, rather than being lost into outer space. The maximum critical frequency for extremely high levels of solar flux is about 15 MHz. In other words, high overhead angles do not propagate signals on the upper HF bands.

However, some domestic signals do arrive at relatively high elevation angles. Let's look at some scenarios where higher angles might be encountered and how the elevation patterns of typical HF stacks affect these signals. Let's examine a situation where a medium-range interfering station is on the same heading as a more distant target station.

We'll examine a typical scenario involving stations in Atlanta, Boston and Paris. The heading from Atlanta to Paris is 49°, the same heading as Atlanta to Boston. In other words, the Atlanta station would have to transmit over (and listen through) a Boston station for communication with Paris. The distance between Atlanta and Boston is about 940 miles, while the distance from Atlanta

to Paris is about 4350 miles. Ground wave signals obviously cannot travel either of these distances at 21 MHz (ground wave coverage is less than about 10 miles at this frequency), and so the propagation between Atlanta to Boston and Atlanta to Paris will be entirely by means of the ionosphere.

Let's evaluate the situation on 15 meters in the month of October. We'll assume a smoothed sunspot number (SSN) of 100 and that each station puts 1500 W of power into theoretical isotropic antennas that have +10 dBi of gain at all elevation and azimuth angles. [We use such theoretical isotropic antennas because they make it easier to work in *VOACAP*. We will factor in real-world stacks later.] *VOACAP* predicts that the signal from Boston will be S9 + 8 dB in Atlanta at 1400 UTC, arriving at an elevation angle of 21.3° on a single F_2 hop. This elevation angle is higher than commonly encountered angles for DX signals, but it is still far away from near-overhead angles.

The signal from Paris into Atlanta is predicted to be about S6 for the same theoretical isotropic antennas, at an incoming elevation angle of 6.4° on three F_2 hops. The S6 level validates the rule-of-thumb that each extra hop loses approximately 10 dB of signal strength, assuming that each S unit is about 4 dB, typical for modern receivers.

Now look at **Fig 36**, which shows the response for a stack of 3-element Yagis at 90/60/30 feet over flat ground, along with the response for a similar stack of 7-element Yagis. Again, we'll assume that all three stations are using such 3-element 90/60/30-foot stacks. The stations in Atlanta and Boston point their stacks into Europe and the Parisian station points his stack towards the USA. The gain of the Atlanta array at 6.4° into Paris will be about 16 dBi, or 6 dB more than the isotropic array with its +10 dBi of gain selected for use in *VOACAP*. Similarly, the French station's transmitted signal will enjoy a 6 dB gain advantage over the isotropic array used in the *VOACAP* calculation, and thus the French signal into Atlanta will now be S6 + 12 dB, or about S9.

By comparison, the interfering signal from Boston into Atlanta will be reduced by the rearward pattern of his array, which will launch a signal at 180° − 21.3° = 158.7° in elevation at the single F_2 mode from Boston to Atlanta. From Fig 33, the Boston station's gain at this rearward elevation is going to drop from the isotropic's +10 dBi of gain down to –11 dBi, a drop of 21 dB. The signal into the Atlanta receiver will also be reduced by the pattern of the Atlanta array on receive, which has a gain of about 0 dBi at 21.3°, compared to the isotropic's +10 dBi gain at 6.4°, a net drop of 10 dB.

Thus, the Boston station's signal will drop by about 21 + 10 = 31 dB, bringing the interfering signal from Boston, which would be S9 + 8 dB for isotropic antennas, down to about S3 due to the combined effects of the arrays. This is a very significant reduction in interference. But you will note that the reduction has nothing to

Fig 36—Stacks of three 3-element and 7-element Yagis on 15 meters at 90/60/30 feet heights. The F/B for the 7-element stack is superior to the 3-element stack mainly because the F/B is intrinsically better for the long-boom design.

do with the near-overhead lobes, dealing as it does with the trailing edge of the main lobe and the F/B lobe.

Even Higher Elevation Angles

Now let's evaluate a station that is even closer to Boston, say a station in Philadelphia. The heading from Philadelphia to Paris is 53° and the distance is 3220 miles. On the same day in October as above, *VOACAP* predicts a signal strength of S8 from Paris to Philadelphia, at a 2.7° elevation angle on two F_2 hops. Again, the *VOACAP* computations assume isotropic antennas with +10 dBi gain at all three stations. The gain of the 3-element stacks at both ends of the circuit at 2.7° is also about +10 dBi, so the signal level from Paris to Philadelphia would be S8 with the 3-element stacks.

Now *VOACAP* computes the elevation angle from Philadelphia to Boston as 56.3°, on one F_2 hop launched at an azimuth of 53°, well within the azimuthal beamwidth of the stack. *VOACAP* says the predicted signal strength for isotropic antennas with +10 dBi of gain is less than S1!

What's happening here? Boston and Philadelphia are within the "skip" region on 21 MHz and signals are skipping right over Boston from Philadelphia (and vice versa). Actual signals would be much weaker than they would be with theoretical isotropic antennas because of the actual patterns of the transmitting and receiving stacks. At an elevation angle of 56.3° the receiving stack would have a gain of –10 dBi, while at an elevation of 180° – 56.3° = 123.7° the transmitting stack would be down to –10 dBi as well. The net reduction for the stacks compared to isotropics with +10 dBi gain each would be 40 dB, putting the interfering signal well into the receiver noise.

You can safely say that near-overhead angles don't enter into the picture, simply because signals at intermediate distances are in the ionospheric skip zone and interfering signals are very weak in that zone already.

Even in situations where having a poor front-to-back ratio might be beneficial—because it alerts stations tuning across your signal that you are occupying that frequency—the ionosphere doesn't cooperate for intermediate-distance signals that are in the skip zone. Often two stations may be on the same frequency without either knowing that the other is there.

Ground Wave?

What happens, you might wonder, for ground-wave signals? Let's look at a situation where the interfering station is in the same direction as the desired target, but is only 5 miles away. Unfortunately, his signal is S9 + 50 dB. Even reducing the level by 30 dB, a huge number, is still going to make his signal 20 dB stronger than signals from your desired target location! There is not much you can do about ground-wave signals and fretting about optimizing stack heights to discriminate against local signals is generally futile.

Stacking Distances for Multiband Yagis

By definition, a stack of multiband Yagis (such as a "tribander" covering 20/15/10 meters) has a constant vertical spacing between antennas in terms of feet or meters, but not in terms of wavelength. Tribanders are no different than monobanders in terms of optimal spacing between individual antennas. Again, the difference in gain between spacings of 0.5 λ and 1.0 λ for a stack of triband Yagis amounts to only a fraction of a decibel. Furthermore, the main practical constraint that limits choice of stacking distances between any kind of Yagis, multiband or monoband, is the spacing between guy wire sets on the tower itself.

Summary, Stacking Distances

In short, let us summarize that there is nothing magical about stacking distances for practical HF Yagis—a good rule-of-thumb is a stacking distance of 0.65 λ. This is 23 feet on 10 meters, 30 feet on 15 meters and 45 feet on 20 meters for monoband stacks. Practically speaking, however, you've only got limited places where you can mount antennas on the tower—mainly where guy wires allow you to place them. This is especially applicable if you wish to rotate lower antennas on the tower, where you must clear the guys from up above.

STACKS AND FADING

The following is derived from an article by Fred Hopengarten, K1VR, and Dean Straw, N6BV, in a Feb 1994 *QST* article. Using stacked Hy-Gain TH7DXs or TH6DXXs at their respective stations, they have solicited a number of reports from stations, mainly in Europe,

to compare various combinations of antennas in stacks and as single antennas. The peak gain of the stack is usually just a little bit higher than that for the best of the single antennas, which is not surprising. Even a large stack has no more than about 6 dB of gain over a single Yagi at a height favoring the prevailing elevation angle. Fading on the European path can easily be 20 dB or more, so it is very confusing to try to make definitive comparisons. They have noticed over many tests that the stacks are much less susceptible to fading compared to single Yagis. Even within the confines of a typical SSB bandwidth, frequency-selective fading occasionally causes the tonal quality of a voice to change on both receive and transmit, often dramatically becoming fuller on the stacks, and tinnier on the single antennas. This doesn't happen all the time, but is often seen. They have also observed often that the depth of a fade is less, and the period of fading is longer, on the stacks compared to single antennas.

Exactly *why* stacks exhibit less fading is a fascinating subject, for which there exist a number of speculative ideas, but little hard evidence. Some maintain that stacks outperform single antennas because they can afford *space diversity* effects, where by virtue of the difference in physical placement one antenna will randomly pick up signals that another one in another physical location might not hear.

This is difficult to argue with, and equally difficult to prove scientifically. A more plausible explanation about why stacked Yagis exhibit superior fading performance is that their narrower frontal elevation lobes can discriminate against undesired propagation modes. Even when band conditions favor, for example, a very low 3° elevation angle on 10 or 15 meters from New England to Western Europe, there are signals, albeit weaker ones, that arrive at higher elevation angles. These higher-angle signals have traveled longer distances on their journey through the ionosphere, and thus their signal levels and their phase angles are different from the signals traversing the primary propagation mode. When combined with the dominant mode, the net effect is that there is both destructive and constructive fading. If the elevation response of a stacked antenna can discriminate against signals arriving at higher elevation angles, then in theory the fading will be reduced. Suffice it to say: In practice, stacks do reduce fading.

STACKS AND PRECIPITATION STATIC

The top antenna in a stack is often much more affected by rain or snow precipitation static than is the lower antenna. N6BV and K1VR have observed this phenomenon, where signals on the lower antenna by itself are perfectly readable, while S9+ rain static is rendering reception impossible on the higher antenna or on the stack. This means that the ability to select individual antennas in a stack can sometimes be extremely important.

STACKS AND AZIMUTHAL DIVERSITY

Azimuthal diversity is a term coined to describe the situation where one of the antennas in a stack is purposely pointed in a direction different from the main direction of the stack. During most of the time in a DX contest from the East Coast, the lower antennas in a stack are pointed into Europe, while the top antenna is often rotated toward the Caribbean or Japan. In a stack of three identical Yagis, the first-order effect of pointing one antenna in a different direction is that one-third of the transmitter power is diverted from the main target area. This means that the peak gain is reduced by 1.8 dB, not a very large amount considering that signals are often 10 to 20 dB over S9 anyway when the band is open from New England to Europe.

Fig 37 shows the 3D pattern of a pair of 4-element Yagis fed in-phase at 95 and 65 feet, but where the lower antenna has been rotated 180° to fire in the –X direction. The backwards lobe peaks at a higher elevation angle because the antenna doing the radiating in this direction is lower on the tower. The forward lobe peaks at a lower angle because its main radiator is higher.

THE N6BV/1 ANTENNA SYSTEM—
BRUTE FORCE FEEDING

The N6BV/1 system in Windham, New Hampshire, was located on the crest of a small hill about 40 miles from Boston, and could be characterized as a good, but not dominant, contesting station. A number of top-10 contest results were achieved from that station in the 1990s before N6BV returned to California.

There was a single 120-foot high Rohn 45 tower, guyed at 30-foot intervals, with a 100-foot horizontal spread from tower base to each guy point so there was sufficient room for rotation of individual Yagis on the tower. Each set of guy wires employed heavy-duty insulators at 57-foot intervals, to avoid resonances in the 80 through 10-meter amateur bands. There were five Yagis on the tower. A heavy-duty 12-foot long steel mast with 0.25-inch walls was at the top of the tower, turned by an Orion 2800 rotator. Two thrust bearings were used above the rotator, one at the top plate of the tower itself, and the other about 2 feet down in the tower on a modified rotator shelf plate. The two thrust bearings allowed the rotator to be removed for service.

At the top of the mast, 130 feet high, was a 5-element, computer-optimized 10-meter Yagi, which was a modified Create design on a 24-foot boom. The element tuning was modified from the stock antenna in order to achieve higher gain and a better pattern over the band. At the top of the tower (120-foot level) was mounted a Create 714X-3 triband Yagi. This was a large tribander, with a 32-foot boom and five elements. Three elements were active on 40 meters, four were active on 20 meters and four were active on 15 meters. The 40-meter elements were loaded with coils, traps and

Fig 37—3D representation of the pattern for two 4-element 15-meter Yagis, with the top antenna at 95 and the bottom at 65 feet, but pointed in the opposite direction.

capacitance hats, and were approximately 46 feet long. A triband 20/15/10-meter Hy-Gain TH7DX tribander was fixed into Europe at the 90-foot level on the tower, just above the third set of guys.

At the 60-foot level on the tower, just above the second set of guys, there was a "swinging-gate" side-mount bracket, made by DX Engineering of Oregon. A Hy-Gain *Tailtwister* rotator turned a TH7DX on this side mount.

(Note that both the side mount and the element spacings of the TH7DX itself prevented full rotation around the tower—about 280° of rotation was achieved with this system.) At the 30-foot level, just above the first set of guys, was located the third TH7DX, also fixed on Europe.

All five Yagis were fed with equal lengths of Belden 9913 low-loss coaxial cable, each measured with a noise bridge to ensure equal electrical characteristics. At each feed point a ferrite-bead choke balun (using seven large beads) was placed on the coax. All five coaxial cables went to a relay switch box mounted at the 85-foot level on the tower. **Fig 38** shows the schematic for the switch box, which was fed with 250 feet of 75-Ω, 0.75-inch OD Hardline coaxial cable.

The stock DX Engineering remote switch box was modified by adding relay K6, so that either the 130-foot or the 120-foot rotating antenna could be selected through a second length of 0.75-inch Hardline going to the shack. This created a *Multiplier* antenna, independent of the *Main* antennas. A second band could be monitored in this fashion while calling CQ using the main antennas on another band. Band-pass filters were required at the multiplier receiver to prevent overload from the main transmitter.

The 0.75-inch Hardline had very low losses, even when presented with a significant amount of SWR at the switch-box end. This was important, because unlike K1VR's system, no attempt was made at N6BV to maintain a constant SWR when relays K1 through K5 were switched in or out. This seemingly cavalier attitude came about because of several factors. First, there were many

Fig 38—N6BV/1 switch box system. This uses a modified DX Engineering remote switch box, with relay K6 added to allow selection of either of the two top antennas (5-element 10-meter Yagi or 40/20/15-meter triband 714X-3) as a "multiplier" antenna. There is no special provision for SWR equalization when any or all of the Yagis are connected in parallel as a stack fed by the Main coaxial cable. Each of the five Yagis is fed with equal lengths of flexible Belden 9913 coax, so phasing can be maintained on any band. The Main and "Multiplier" coaxes going to the shack are 0.75" OD 75-Ω Hardline cables.

different combinations of antennas that could be used together in this system. Each relay coil was independently controlled by a toggle switch in the shack. N6BV was unable to devise a matching system that did not become incredibly complex because of the numerous impedance combinations used over all the five bands.

Second, the worst-case additional transmission line loss due to a 4:1 SWR mismatch when four antennas were connected in parallel on 10 meters was only 0.5 dB. It was true that the linear amplifier had to be retuned slightly when combinations of antennas were switched in and out, but this was a small penalty to pay for the reduced complexity of the switching and matching networks. The 90/60/30-foot stack into Europe was used for about 95% of the time during DX contests, so the small amount of amplifier retuning for other antenna combinations was considered only a minor irritation.

WHY TRIBANDERS?

Without a doubt, the most common question K1VR and N6BV have been asked is: "Why did you pick *tribanders* for your stacks?" Triband antennas were chosen with full recognition that they are compromise antennas. Other enterprising amateurs have built stacked tribander arrays. Bob Mitchell, N5RM, is a prominent example, with his so-called *TH28DX* array of four TH7DX tribanders on a 145-foot-high rotating tower. Mitchell employed a rather complex system of relay-selected tuned networks to choose either the upper stacked pair, the lower stacked pair or all four antennas in stack. Others in Texas have also had good results with their tribander stacks. Contester Danny Eskenazi, K7SS, has very successfully used a pair of stacked KT-34XA tribanders for years.

A major reason why tribanders were used is that over the years both authors have had good results using TH6DXX or TH7DX antennas. They are ruggedly built, mechanically and electrically. They are able to withstand New England winters without a whimper, and their 24-foot long booms are long enough to produce significant gain, despite trap-loss compromises. Amateurs speculating about trap losses in tribanders freely bandy about numbers between 0.5 and 2 dB. Both N6BV and K1VR are comfortable with the lower figure, as are the Hy-Gain engineers.

Consider this: If 1500 W of transmitter power is going into an antenna, a loss of 0.5 dB amounts to 163 W. This would create a significant amount of heat in the six traps that are on average in use on a TH6DXX, amounting to 27 W per trap. If the loss were as high as 1 dB, this would be 300 W total, or 50 W per trap. Common sense says that if the overall loss were greater than about 0.5 dB, the traps would act more like big *firecrackers* than resonant circuits! A long-boom tribander like the TH6DXX or TH7DX also has enough space to employ elements dedicated to different bands, so the compromises in element spacing

usually found on short-boom 3 or 4-element tribanders can be avoided.

Another factor in the conscious choice of tribanders was first-hand frustration with the serious interaction that can result from stacking monoband antennas closely together on one mast in a Christmas Tree configuration. N6BV's worst experience was with the ambitious 10 through 40-meter Christmas Tree at W6OWQ in the early 1980s. This installation used a Tri-Ex SkyNeedle tubular crankup tower with a rotating 10-foot-long heavy-wall mast. The antenna suffering the greatest degradation was the 5-element 15-meter Yagi, sandwiched 5 feet below the 5-element 10-meter Yagi at the top of the mast, and 5 feet above the full-sized 3-element 40-meter Yagi, which also had five 20-meter elements interlaced on its 50-foot boom.

The front-to-back ratio on 15 meters was at best about 12 dB, down from the 25+ dB measured with the bottom 40/20-meter Yagi removed. No amount of fiddling with element spacing, element tuning or even orientation of the 15-meter boom with respect to the other booms (at 90° or 180°, for example) improved its performance. Further, the 20-meter elements had to be lengthened by almost a foot *on each end of each element* in order to compensate for the effect of the interlaced 40-meter elements. It was a lucky thing that the tower was a motorized crankup, because it went up and down hundreds of times as various experiments were attempted!

Interaction due to close proximity to other antennas in a short Christmas Tree can definitely destroy carefully optimized patterns of individual Yagis. Nowadays, such interaction can be modeled using a computer program such as *EZNEC* or *NEC*. A gain reduction of as much as 2 to 3 dB can easily result due to close vertical spacing of monobanders, compared to the gain of a single monoband antenna mounted in the clear. Curiously enough, at times such a reduction in gain can be found even when the front-to-back ratio is not drastically degraded, or when the front-to-back occasionally is actually *improved*.

If you plan on stacking monoband Yagis—for example, putting only 15-meters Yagis on a single tower, with your other monoband stacks on other towers—do make sure you model the system to see if any interactions occur. You may be quite surprised.

Finally, in the N6BV/1 installation, triband antennas were chosen because the system was meant to be as simple as possible, given a certain desired level of performance, of course. Triband antennas make for less mechanical complexity than do an equivalent number of monobanders. There were five Yagis on the N6BV/1 tower, yielding gain from 40 to 10 meters, as opposed to using 12 or 13 monobanders on the tower.

THE K1VR ARRAY: A MORE ELEGANT APPROACH TO MATCHING

The K1VR stacked array is on a 100-foot high Rohn

25 tower, with sets of guy wires at 30, 60 and 90 feet, made of nonconducting Phillystran. Phillystran is a non-metallic Kevlar rope covered by black polyethylene to protect against the harmful effects of the sun's ultraviolet rays. A caution about Phillystran: Don't allow tree branches to rub against it. It is designed to work in tension, but unlike steel guy wire, it does not tolerate abrasion well.

Both antennas are Hy-Gain TH6DXX tribanders, with the top one at 97 feet and the bottom one at 61 feet. The lower antenna is rotated by a Telex Ham-M rotator on a homemade swinging-gate side mount, which allows it to be rotated 300° around the tower without hitting any guy wires or having an element swing into the tower. At the 90-foot point on the tower, a 2-element 40-meter Cushcraft Yagi has been mounted on a RingRotor so it can be rotated 360° around the tower.

After several fruitless attempts trying to match the TH6DXX antennas so that either could be used by itself or together in a stack, K1VR settled on using a relay-selected broadband toroidal matching transformer. When both triband antennas are fed together in parallel as a stack, it transforms the resulting 25-Ω impedance to 50 Ω. The transformer is wound on a T-200A powdered-iron core, available from Amidon, Palomar Engineering or Ocean State Electronics. Two lengths of twin RG-59 coax (sometimes called Siamese or WangNet), four turns each, are wound on the core. Two separate RG-59 cables could be used, but the Siamese-twin cable makes the assembly look much more tidy. The shields of the RG-59 cables are connected in series, and the center conductors are connected in parallel. See **Fig 39** for details.

Fig 40 shows the schematic of the K1VR switch box, which is located in the shack. Equal electrical lengths of 50-Ω Hardline are brought from the antennas into the shack and then to the switch box. Inside the box, the relay contacts were soldered directly to the SO-239 chassis connectors to keep the wire lengths down to the absolute minimum. K1VR used a metal box that was larger than

Fig 39—Diagram for matching transformer for K1VR stacked tribander system. The core is powdered iron-core T-200A, with four turns of two RG-59A or "Siamese" coax cables. Center conductors are connected in parallel and shields are connected in series to yield 0.667:1 turns ratio, close to desired 25-Ω to 50-Ω transformation.

Fig 40—Relay switch box for K1VR stacked tribander system. Equal lengths of 50-Ω Hardline (with equal lengths of flexible 50-Ω cable at each antenna to allow rotation) go to the switch box in the shack. The SWR on all three bands for Upper, Lower or Both switch positions is very close to constant.

might appear necessary because he wanted to mount the toroidal transformer with plenty of clearance between it and the box walls. The toroid is held in place with a piece of insulation foam board. Before placing the switch box in service, the system was tested using two 50-Ω dummy loads, with equal lengths of cable connected in parallel to yield 25 Ω. The maximum SWR measured was 1.25:1 at 14 MHz, 1.3:1 at 21 MHz and 1.15:1 at 28 MHz, and the core remained cold with 80 W of continuous output power.

One key to the system performance is that K1VR made the electrical lengths of the two hardlines the same (within 1 inch) by using a borrowed TDR (time domain reflectometer). Almost as good as Hardline, K1VR points out, would be to cut exactly the same length of cable from the same 500-foot roll of RG-213. This eliminates manufacturing tolerances between different rolls of cable.

K1VR's experience over the last 10 years has been that at the beginning of the 10 or 15-meter morning opening to Europe the upper antenna is better. Once the band is wide open, both antennas are fed in phase to cast a bigger shadow, or footprint, on Europe. By mid-morning, the lower antenna is better for most Europeans, although he continues to use the stack in case someone is hearing him over a really long distance path throughout Europe. He reports that it is always very pleasant to be called by a 4S7 or HSØ or VU2 when he is working Europeans at a fast clip!

SOME SUGGESTIONS FOR STACKING TRIBANDERS

It is unlikely that many amateurs will try to duplicate exactly K1VR's or N6BV's contest setups. However, many hams already have a tribander on top of a moderately tall tower, typically at a height of about 70 feet. It is not terribly difficult to add another, identical tribander at about the 40-foot level on such a tower. The second tribander can be pointed in a fixed direction of particular interest (such as Europe or Japan), or it can be rotated around the tower on a side mount or a Ring Rotor. If guy wires get in the way of rotation, the antenna can usually be arranged so that it is fixed in a single direction.

Insulate the guy wires at intervals to ensure that they don't shroud the lower antenna electrically. A simple feed system consists of equal-length runs of surplus 0.5-inch 75-Ω Hardline (or more expensive 50-Ω Hardline, if you are really obsessed by SWR) from the shack up the tower to each antenna. Each tribander is connected to its respective Hardline feeder by means of an equal length of flexible coaxial cable, with a ferrite choke balun, so that the antenna can be rotated.

Down in the shack, the two hardlines can simply be switched in and out of parallel to select the upper antenna only, the lower antenna only, or the two antennas as a stack. See **Fig 41**. Any impedance differences can be handled as stated previously, simply by retuning the lin-

Fig 41—Simple feed system for 70/40-foot stack of tribanders. Each tribander is fed with equal lengths of 0.5-inch 75-Ω Hardline cables (with equal lengths of flexible coax at the antenna to allow rotation), and can be selected singly or in parallel at the operator's position in the shack. Again, no special provision is made in this system to equal SWR for any of the combinations.

ear amplifier, or by means of the internal antenna tuner (included in most modern transceivers) when the transceiver is run barefoot. The extra performance experienced in such a system will be far greater than the extra decibel or two that modeling calculates.

THE WXØB APPROACH TO STACK MATCHING AND FEEDING

Earlier we mentioned how useful it would be to switch various antennas in or out of a stack, depending on the elevation angles that need to be emphasized at that moment. Jay Terleski, WXØB, of Array Solutions has designed switchable matching systems, called *StackMatches*, for stacks of monoband or multiband Yagis.

The StackMatch uses a 50-Ω to 22.25-Ω broadband transmission-line transformer to match combinations of up to three Yagis in a stack. See **Fig 42** for a schematic of the StackMatch. For selection of any 50-Ω Yagi by itself, no matching transformer is needed and Relay IN routes RF directly to the common bus going to Relay 1, 2 and 3. For selection of two Yagis together the parallel impedance is 50/2 = 25 Ω and Relay IN routes RF to the matching transformer. The SWR is 25/22.25 = 1.1:1. For three Yagis used together, the parallel impedance is 50/3 = 16.67 Ω, and the SWR is 22.25/16.67 = 1.3:1.

The broadband transformer consists of four trifilar turns of #12 enamel-insulated wire wound on a Ferrite Corporation FT-240 2.4-inch OD core made of #61

Fig 42—Schematic of WXØB's StackMatch 2000 switchbox, which uses a broadband transmission line transformer using trifilar #12 enamel-insulated wires. (*Courtesy Array Solutions.*)

material (μ = 125). WXØB uses 10-A relays enclosed in plastic cases to do the RF switching, selected by a control box at the operating position. (10-A relays can theoretically handle 10 $A^2 \times 50 \Omega$ = 5000 W.) **Fig 43** shows a photo of the transmission-line transformer and StackMaster PCB.

The control/indicator box uses a diode matrix to switch various combinations of antennas in/out of the stack. Three LEDs lined up vertically on the front panel indicate which antennas in a stack are selected.

"BIP/BOP" OPERATION

The contraction "BIP" means "both in-phase," while "BOP" means "both out-of-phase." BIP/BOP refer to stacks containing two Yagis, although the term is commonly used for stacks containing more than two Yagis. In theory, feeding a stack with the antennas out-of-phase will shift the elevation response higher than in-phase feeding.

Fig 44 shows a rectangular plot comparing BIP/BOP operation of two 3-element 15-meter Yagis at heights of 2 λ and 1 λ (93 and 46 feet) over flat ground. The BOP pattern is the higher-angle lobe and the two lobes cross over about 14°. The maximum amplitude of the BOP stack's gain is about ½ dB less than the BIP pair. For reference, the pattern of a single 46-foot high Yagi is overlaid on the pattern for the stacks.

The most common method for feeding one Yagi 180° out-of-phase is to include an extra electrical half wave-

Fig 43—Inside view of StackMatch. (*Photo courtesy Array Solutions.*)

length of feed-line coax going to one of the antennas. This method obviously works on a single frequency band and thus is not applicable to stacks of multiband Yagis, such as tribanders. For such multiband stacks, feeding only the lower antenna(s)—by switching out higher antenna(s) in the stack—is a practical method for achieving better coverage at medium or high elevation angles.

Fig 44—*HFTA* screen shot of "BIP/BOP" operation of two 4-element 15-meter Yagis at 93 and 46 feet above flat ground. The elevation response in BOP (both out-of-phase) operation is shifted higher, peaking at about 21°, compared to the BIP (both in-phase) operation where the peak is at 8°. The dashed line is response of single Yagi at 46 feet.

STACKING DISIMILAR YAGIS

So far we have been discussing vertical stacks of identical Yagis. Less commonly, hams have successfully stacked dissimilar Yagis. For example, consider a case where two 5-element 10-meter Yagis are placed 46 and 25 feet above flat ground, with a 7-element 10-meter Yagi at 68 feet on the same tower. See **Fig 45**, which is a schematic of the layout for this stack. Note that the driven element for the top 7-element Yagi is well behind the vertical plane of the driven elements for the two 5-element Yagis. This offset distance must be compensated for with a phase shift in the drive system for the top Yagi.

Fig 46 shows the elevation-pattern responses for uncompensated (equal-length feed lines) and the compensated (additional 150° of phase shift to top Yagi) stacks. These patterns were computed using *EZNEC ARRL*, which is included with this book. Not only is about 1.7 dB of maximum gain lost, but the peak elevation angle is shifted upwards by 11° from the optimal takeoff angle of 8°—where some 10 dB of gain is also lost. Without compensation, this is a severe distortion of the stack's elevation pattern.

For RG-213 coax, the extra length needed to provide an additional 150° of phase shift = 150°/360° λ = 0.417 λ = 9.53 feet at 28.4 MHz. This was computed

Fig 45—Stacking dissimilar Yagis. In this case a 7-element 10-meter Yagi is stacked over two 5-element Yagis. Note the displacement of the 7-element Yagi's driven element compared to the position of the two 5-element Yagis. This leads to an undesired phase shift for the higher antenna.

Fig 46—Comparison of elevation responses for 7/5/5-element 10-meter stacks, with and without compensation for driven-element offset.

using the program *TLW* (Transmission Line for Windows) included on the CD-ROM accompanying this book.

It is not always possible to compensate for dissimilar Yagis in a stack with a simple length of extra coax, so you should be sure to model such combinations to make sure that they work properly. A safe alternative, of course, is to stack only identical Yagis, feeding all of them with equal lengths of coax to ensure in-phase operation.

Real-World Terrain and Stacks

So far, the stacking examples shown have been for flat ground. Things can become a lot more complicated when you deal with real-world irregular terrains! See Chapter 3, The Effects of Ground, for a description of the *HFTA* (High Frequency Terrain Assessment) program that is included with this book.

Fig 47 shows the *HFTA*-computed 20-meter elevation responses towards Europe (at an azimuth of 45°) for three antennas at the N6BV/1 location in Windham, New Hampshire. Overlaid as a bar graph are the elevation-angle statistics for the path to all of Europe from New England (Massachusetts). The stack at 90/60/30 feet clearly covers all the angles needed best at 14 MHz. The N6BV 120-foot Yagi has a severe null in the region from about 7° to about 20°, with the deepest part of that null occurring at about 13° and is roughly comparable to the 90/60/30-foot stack between 2° to 7°.

In practice, the 120-foot Yagi was indeed comparable to the stack during morning openings to Europe on 20 meters, when the elevation angles are typically about 5°. In the New England afternoon, when the elevation angles typically rise to about 11°, the 120-foot Yagi was always distinctly inferior to the stack.

For reference, the response of a single 120-foot high Yagi over flat ground is also shown. Note that the N6BV 120-foot high Yagi has about 3 dB more gain at a 5° takeoff angle than does its flatland counterpart. This additional gain is due to the focusing effects of the local terrain, which had about a 3° downwards slope towards Europe.

Fig 48 shows the *HFTA*-computed 15-meter elevation responses towards Europe for the 90/60/30-foot stack at 90/60/30 feet at N6BV/1, compared to the same 120-foot high Yagi and a 90/60/30-foot stack, but this time over flat ground. Again, the N6BV/1 terrain towards Europe has a significant effect on the gain of the stack compared to that of an identical stack over flat ground. In fact, the peak gain of 20.1 dBi at a 4° elevation angle is close to moon-bounce levels.

OPTIMIZING OVER LOCAL TERRAIN

There are only a small number of possibilities to optimize an installation over local terrain:

- Change the antenna height(s) above ground.
- Stack two (or more) Yagis.
- Change the spacing between stacked Yagis.
- Move the tower back from a cliff (or a hill).
- BIP/BOP (Both In Phase/Both Out of Phase).

The *HFTA* program on the CD-ROM accompanying this book can be used, together with Digital Elevation Model (DEM) topographic data available on the Internet, to evaluate all these options.

SO NEAR, YET SO FAR

It is sometimes very surprising to compare elevation responses for different towers located at various points on the same property, particularly when that prop-

Fig 47—*HFTA* screen shot showing how complicated things become when real-world irregular terrain is analyzed. This is the 20-meter elevation pattern for the N6BV/1 station location in Windham, NH, for the 90/60/30-foot stack of triband TH7DX Yagis and a 4-element Yagi at 120 feet on the same tower. For comparison, the response of a 120-foot Yagi over flat ground is also included.

Fig 48—*HFTA* screen shot showing the 15-meter elevation pattern for the N6BV/1 station location in Windham, NH, for the 90/60/30-foot stack of triband TH7DX Yagis and a 4-element Yagi at 120 feet on the same tower. For comparison, the response of a 120-foot Yagi over flat ground is also included.

Fig 49—*HFTA* screen shot showing the 20-meter elevation pattern for K1KI's North and South towers, with 100-foot high 4-element Yagis pointing into Europe at an azimuth of 45°. The responses are surprisingly different for two towers separated by only 600 feet.

Fig 50—K1KI's terrain profiles for the North and South towers at an azimuth of 45° into Europe.

erty is located in the mountains. **Fig 49** shows the computed elevation responses for three 100-foot high 14-MHz Yagis over three terrains towards Europe: from the North tower at K1KI's location in West Suffield, Connecticut, from the South tower at K1KI, and over flat ground. The elevation response from the South tower follows that over flat ground well, while the response from the North tower is quite a bit stronger at low elevation angles—about 1.5 dB on average, as the Figure of Merit shows from *HFTA*.

Fig 50 shows the reason why this happens—the terrain from the North tower slopes down quickly towards Europe, while the terrain from the South tower goes out almost 900 feet before starting to fall off. These two towers are about 600 feet apart.

Moxon Rectangle Beams

LB Cebik, W4RNL, has written extensively about the *Moxon rectangle*, an antenna invented by Les Moxon, G6XN, derived from a design by VK2ABQ. The Moxon rectangle beam takes less space horizontally than a conventional 2-element Yagi design, yet it offers nearly the same amount of gain and a superior front-to-back ratio. And as an additional benefit, the drive-point impedance is close to 50 Ω, so that it doesn't need a matching section.

For example, rather than a "wingspan" of 17 feet for the reflector in a conventional 2-element 10-meter Yagi, the Moxon rectangle is 13 feet wide, a saving of almost 25%. The Moxon rectangle W4RNL created for *The ARRL Antenna Compendium, Vol 6*, had an SWR less than 2:1 from 28.0 to 29.7 MHz, with a gain over ground of 11 dBi. It had a F/B of 15 dB at 28.0 MHz, more than 20 dB at 28.4 MHz, and 12 dB at 29.7 MHz.

The Moxon rectangle relies on controlling the spacing (hence controlling the coupling) between the ends of the driven element tips and the ends of the reflector tips, which are both bent toward each other. See **Fig 51**, which shows the general outline for W4RNL's 10-meter aluminum Moxon rectangle. The tips of the elements are kept a fixed distance from each other by PVC spacers. The closed rectangular mechanical assembly gives some rigidity to the design, keeping it stable in the wind. W4RNL described other Moxon rectangle designs using wire elements in June 2000 *QST*.

Fig 51—General outline of the 10-meter aluminum Moxon rectangle, showing tubing dimensions.

Quad Arrays

Chapter 11, HF Yagi Arrays, discussed Yagi arrays as systems of approximately half-wave dipole elements that are coupled together mutually. You can also employ other kinds of elements using the same basic principles of analysis. For example, loops of various types may be combined into directive arrays. A popular type of parasitic array using loops is the *quad antenna*, in which loops having a perimeter of about one wavelength are used in much the same way as half-wave dipole elements in the Yagi antenna.

Clarence Moore, W9LZX, created the quad antenna in the early 1940s while he was at the Missionary Radio Station HCJB in Quito, Ecuador. He developed the quad to combat the effects of corona discharge at high altitudes. The problem at HCJB was that their large Yagi was literally destroying itself by melting its own element tips. This occurred due to the huge balls of corona it generated in the thin atmosphere of the high Andes mountains. Moore reasoned correctly that closed loop elements would generate less high voltage—and hence less corona—than would the high impedances at the ends of a half-wave dipole element.

Fig 1 shows the original version of the two-element quad, with a driven element and a parasitic reflector. The square loops may be mounted either with the corners lying on horizontal and vertical lines, as shown at the left, or with two sides horizontal and two vertical (right). The feed points shown for these two cases will result in horizontal polarization, which is commonly used.

Since its inception, there has been controversy whether the quad is a better performer than a Yagi. Chapter 11 showed that the three main electrical performance parameters of a Yagi are gain, response patterns (front-to-rear ratio, F/R) and drive impedance/SWR. Proper analysis of a quad also involves checking all these parameters across the entire frequency range over which you intend to use it. Both a quad and a Yagi are classified as "parasitic, end-fire arrays." Modern antenna modeling by computer shows that monoband Yagis and quads with the same boom lengths and optimized for the same performance parameters have gains within about 1 dB of each other, with the quad slightly ahead of the Yagi.

Fig 2 plots the three parameters of gain, front-to-

Fig 1—The basic two-element quad antenna, with driven-element loop and reflector loop. The driven loops are electrically one wavelength in circumference ($^1/_4$ wavelength on a side); the reflectors are slightly longer. Both configurations shown give horizontal polarization. For vertical polarization, the driven element should be fed at one of the side corners in the arrangement at the left, or at the center of a vertical side in the "square" quad at the right.

Fig 2—Comparison of gain, F/R and SWR over the 14.0 to 14.35-MHz range for an optimized three-element quad and an optimized three-element Yagi, both on 26-foot booms. The quad exhibits almost 0.5 dB more gain for the same boom length, but doesn't have as good a rearward pattern over the whole frequency range compared to the Yagi. This is evidenced by the F/R curve. The quad's SWR curve is also not quite as flat as the Yagi. The quad's design emphasizes gain more than the other two parameters.

rear ratio (F/R) and SWR over the 14.0 to 14.35-MHz band for two representative antennas—a monoband three-element quad and a monoband four-element Yagi. Both of these have 26-foot booms and both are optimized for the best compromise of gain, F/R and SWR across the whole band.

While the quad in Fig 2 consistently exhibits about 0.5 dB more gain over the whole band, its F/R pattern toward the rear isn't quite as good as the Yagi's over that span of frequencies. This quad attains a maximum F/R of 25 dB at 14.1 MHz, but it falls to 17 dB at the bottom end of the band and 15 dB at the top. On the other hand, the Yagi's F/R stays consistently above 21 dB across the whole 20-meter band. The quad's SWR rises to just under 3:1 at the top end of the band, but stays below 2:1 from 14.0 to almost 14.3 MHz. The Yagi's SWR remains lower than 1.5:1 over the whole band.

The reason the Yagi in Fig 2 has more consistent responses for gain, F/R and SWR across the whole 20-meter band is that it has an additional parasitic element, giving two additional variables to play with—that is, the length of that additional element and the spacing of that element from the others on the boom.

Yagi advocates point out that it is easier to add extra elements to a Yagi, given the mechanical complexities of adding another element to a quad. Extra parasitic elements give a designer more flexibility to tailor all performance parameters over a wide frequency range. Quad designers have historically opted to optimize strictly for gain and, as stated before, they can achieve as much as 1 dB more gain than a Yagi with the same length boom. But in so doing, a quad designer typically has to settle for front-to-rear patterns that are peaked over more narrow frequency ranges. The 20-meter quad plots in Fig 2 actually represent an even-handed approach, where the gain is compromised slightly to obtain a more consistent pattern and SWR across the whole band.

Fig 3 plots gain, F/R and SWR for two 10-meter monoband designs: a five-element quad and a five-element Yagi, both placed on 26-foot booms. The quad now has the same degrees of freedom as the Yagi, and as a consequence the pattern and SWR are more consistent across the range from 28.0 to 28.8 MHz. The quad's F/R remains above about 18.5 dB from 28.0 to 28.8 MHz. Meanwhile, the Yagi maintains an F/R of greater than 22 dB over the same range, but has almost 0.8 dB less gain compared to the quad at the low end of the band, eventually catching up at the high end of the band. The SWR for the quad is just over 2:1 at the bottom of the band, but remains less than 2:1 up to 28.8 MHz. The SWR on the Yagi remains less than 1.6:1 over the whole band.

Fig 4 shows the performance parameters for two 15-meter monoband designs: a five-element quad and a five-element Yagi, both on 26-foot booms. The quad is still the leader in gain, but has a less optimal rearward pattern and a somewhat less flat SWR curve than the Yagi. One thing should be noted in Figs 2 through 4. The F/R pattern on the

Fig 3—Comparison of gain, F/R and SWR over the 28.0 to 28.8-MHz range for an optimized five-element quad and an optimized five-element Yagi, both on 26-foot booms. The gain advantage of the quad is about 0.25 dB at the low end of the band. The F/R is more peaked in frequency for the quad, however, than the Yagi.

Fig 4—Comparison of gain, F/R and SWR over the 21.0 to 21.45-MHz range for an optimized 5-element quad and optimized 5-element Yagi, both on 26-foot booms. The quad enjoys a gain advantage of about 0.5 dB over most of the band. Its rearward pattern is not as good as the Yagi, which remains higher than 24 dB across the whole range, compared to the quad, which remains in the 16-dB average range.

Yagi is largely determined by the response at the 180° point, directly in back of the frontal lobe. This point is usually referred to when discussing the "front-to-back ratio."

The quad on the other hand has what a sailor might term "quartering lobes" (referring to the direction back towards the "quarterdeck" at the stern of a sailing vessel) in the rearward pattern. These quartering lobes are often

15-Meter 5-Ele. Quad and 5-Ele. Yagi
21.2 MHz, 26-Foot Booms, Free Space

Fig 5—Comparing the pattern of the 15-meter quad and Yagi shown in Fig 4. The quad has a slightly narrower frontal beamwidth (it has 0.5 dB more gain than the Yagi), but has higher "rear quartering" sidelobes at about 125° (with a twin sidelobe, not shown, at 235°). These sidelobes limit the worst-case front-to-rear (F/R) to about 17 dB, while the F/B (at 180°, directly at the back of the quad) is more than 24 dB for each antenna.

Table 1

Dimensions for Optimized Monoband Quads in Figs 2, 3 and 4, on 26-Foot Booms

	14.2 MHz	21.2 MHz	28.4 MHz
Reflector	73′ 9"	49′ 6"	37′ 3"
R-DE Spacing	17′ 8"	7′	6′ 4"
Driven Element	71′ 8"	47′ 6"	35′ 9"
DE-D1 Spacing	8′ 3"	5′	5′ 6"
Director 1	68′ 7"	46′ 8"	34′ 8"
D1-D2 Spacing	—	6′ 8"	6′ 9"
Director 2	—	46′ 10"	35′ 2"
D2-D3 Spacing	—	7′ 4"	7′ 5"
Director 3	—	45′ 8"	34′ 2"
Feed method	Direct 50 Ω	Direct 50 Ω	Direct 50 Ω

10-Meter Optimized Quad and Yagi
28.4 MHz Gain, 50' Height

Fig 6—A comparison on 10 meters between an optimized five-element quad and an optimized five-element Yagi, both mounted 50 feet high over flat ground and both employing 26-foot booms. There is no appreciable difference in the peak elevation angle for either antenna. In other words, a quad does not have an appreciable elevation-angle advantage over a Yagi mounted at the same boom height. Note that the quad achieves its slightly higher gain by taking energy from higher-angle lobes and concentrating that energy in the main elevation lobe. This is a process that is similar to what happens with stacked Yagis.

worse than the response at 180°, directly in back of the main beam. **Fig 5** overlays the free-space E-Field responses of the 15-meter quad and Yagi together. At 21.2 MHz, the quad actually has a front-to-back ratio (F/B) of about 24 dB, excellent in anyone's book. The Yagi at 180° has a F/B of about 25 dB, again excellent.

However, at an azimuth angle of about 125° (and at 235° azimuth on the other side of the main lobe) the quad's "quartering lobe" is down only some 17 dB, setting the worst-case F/R at 17 dB also. As explained in Chapter 11, the reason F/R is more important than just the F/B is that on receive signals can come from any direction, not just from directly behind the main beam.

Table 1 lists the dimensions for the three computer-optimized monoband quads shown in Figs 2, 3 and 4.

Is a Quad Better at Low Heights than a Yagi?

Another belief held by some quads enthusiasts is that they need not be mounted very high off the ground to give excellent DX performance. Quads are somehow supposed to be greatly superior to a Yagi at the same height above ground. Unfortunately, this is mainly wishful thinking.

Fig 6 compares the same two 10-meter antennas as in Fig 3, but this time with each one mounted on a 50-foot tower over flat ground, rather than in theoretical free space. The quad does indeed have slightly more gain than a Yagi with the same boom length, as it has in free space. This is evidenced by the very slight compression of the quad's main lobe, but is more obvious when you look at the third lobe, which peaks at about 53° elevation. In effect, the quad squeezes some energy out of its second

and third lobes and adds that to the first lobe. However, the difference in gain compared to the Yagi is only 0.8 dB for this particular quad design at a 9° elevation angle. And while it's true that every dB counts, you can also be certain that on the air you wouldn't be able to tell the difference between the two antennas. After all, a 10-to 20-dB variation in the level of signals is pretty common because of fading at HF.

Multiband Quads

On the other hand, one of the valid reasons quads have remained popular over the years is that antenna homebrewers

can build multiband quads far more easily than they can construct multiband Yagis. In effect, all you have to do with a quad is add more wire to the existing support arms. It's not quite as simple as that, of course, but the idea of ready expandability for other bands is very appealing to experimenters.

Like the Yagi, the quad does suffer from interactions between wires of different frequencies, but the degree of interaction between bands is usually less for a quad. The higher-frequency bands are the ones that often suffer most from any interaction, for both Yagis and quads. For example, the 10- and 15-meter bands are usually the ones affected most by nearby 20-meter wires in a triband quad, while the 20-meter elements are not affected by the 10- or 15-meter elements.

Modern computer modeling software can help you counteract at least some of the interaction by allowing you to do virtual "retuning" of the quad on the computer screen — rather than clinging precariously to your tower fiddling with wires. However, the programs (such as *NEC-2* or *EZNEC*) that can model three-dimensional wire antennas such as quads typically run far more slowly than those designed for monoband Yagis (such as *YW* included with this book). This makes optimizing rather tedious, but you use the same considerations for tradeoffs between gain, pattern (F/R) and SWR over the operating bandwidth as you do with monoband Yagis.

CONSTRUCTING A QUAD

The parasitic element shown in Fig 1 is tuned in much the same way as the parasitic element in a Yagi antenna. That is, the parasitic loop is tuned to a lower frequency than the driven element when the parasitic is to act as a reflector, and to a higher frequency when it is to act as a director. Fig 1 shows the parasitic element with an adjustable tuning stub, a convenient method of tuning since the resonant frequency can be changed simply by changing the position of the shorting bar on the stub. In practice, it has been found that the length around the loop should be approximately 3.5% greater than the self-resonant length if the element is a reflector, and about 3.0% shorter than the self-resonant length if the parasitic element is a director. Approximate formulas for the loop lengths in feet are:

$$\text{Driven Element} = \frac{1008}{f_{MHz}}$$

$$\text{Reflector} = \frac{1045}{f_{MHz}}$$

$$\text{Director} = \frac{977}{f_{MHz}}$$

These are valid for quad antennas intended for operation below 30 MHz and using uninsulated #14 stranded copper wire. At VHF, where the ratio of loop circumference to conductor diameter is usually relatively small, the circumference must be increased in comparison to the wavelength. For example, a one-wavelength loop constructed of $\frac{1}{4}$-inch tubing for 144 MHz should have a circumference about 2% greater than in the above equation for the driven element.

Element spacings on the order of 0.14 to 0.2 free-space wavelengths are generally used. You would employ the smaller spacings for antennas with more than two elements, where the structural support for elements with larger spacings tends to become challenging. The feed-point impedances of antennas having element spacings on this order have been found to be in the 40- to 60-Ω range, so the driven element can be fed directly with coaxial cable with only a small mismatch.

For spacings on the order of 0.25 wavelength (physically feasible for two elements, or for several elements at 28 MHz) the impedance more closely approximates the impedance of a driven loop alone—that is, 80 to 100 Ω. The feed methods described in Chapter 26 can be used, just as in the case of the Yagi.

Making It Sturdy

The physical sturdiness of a quad is directly proportional to the quality of the material used and the care with which it is constructed. The size and type of wire selected for use with a quad antenna is important because it will determine the capability of the spreaders to withstand high winds and ice. One of the more common problems confronting the quad owner is that of broken wires. A solid conductor is more apt to break than stranded wire under constant flexing conditions. For this reason, stranded copper wire is recommended. For 14-, 21- or 28-MHz operation, #14 or #12 stranded wire is a good choice. Soldering of the stranded wire at points where flexing is likely to occur should be avoided.

You may connect the wires to the spreader arms in many ways. The simplest method is to drill holes through the fiberglass at the appropriate points on the arms and route the wires through the holes. Soldering a wire loop across the spreader, as shown later, is recommended. However, you should take care to prevent solder from flowing to the corner point where flexing could break it.

While a boom diameter of 2 inches is sufficient for smaller quads using two or even three elements for 14, 21 and 28 MHz, when the boom length reaches 20 feet or longer a 3-inch diameter boom is highly recommended. Wind creates two forces on the boom, vertical and horizontal. The vertical load on the boom can be reduced with a guy-wire truss cable. The horizontal forces on the boom are more difficult to relieve, so 3-inch diameter tubing is desirable.

Generally speaking, three grades of material can be used for quad spreaders. The least expensive material is bamboo. Bamboo, however, is also the weakest material normally used for quad construction. It has a short life, typically only three or four years, and will not withstand a harsh climate very well. Also, bamboo is heavy in con-

trast to fiberglass, which weighs only about a pound per 13-foot length. Fiberglass is the most popular type of spreader material, and will withstand normal winter climates. One step beyond the conventional fiberglass arm is the pole-vaulting arm. For quads designed to be used on 7 MHz, surplus "rejected" pole-vaulting poles are highly recommended. Their ability to withstand large amounts of bending is very desirable. The cost of these poles is high, and they are difficult to obtain. See Chapter 21 for dealers and manufacturers of spreaders.

Diamond or Square?

The question of how to orient the spreader arms has been raised many times over the years. Should you mount the loops in a diamond or a square configuration? Should one set of spreaders be horizontal to the earth as shown in Fig 1 (right), or should the wire itself be horizontal to the ground (spreaders mounted in the fashion of an X) as shown in Fig 1 (left)? From the electrical point of view, there is not enough difference in performance to worry about.

From the mechanical point of view there is no question which version is better. The diamond quad, with the associated horizontal and vertical spreader arms, is capable of holding an ice load much better than a system where no vertical support exists to hold the wire loops upright. Put another way, the vertical poles of a diamond array, if sufficiently strong, will hold the rest of the system erect. When water droplets are accumulating and forming into ice, it is very reassuring to see water running down the wires to a corner and dripping off, rather than just sitting there on the wires and freezing. The wires of a loop (or several loops, in the case of a multiband antenna) help support the horizontal spreaders under a load of ice. A square quad will droop severely under heavy ice conditions because there is nothing to hold it up straight.

Of course, in climates where icing is not a problem, many amateurs point out that they like the aesthetics of the square configuration. There are thousands of square-configuration quads in temperate areas around the world.

Another consideration will enter into your choice of orientation for a quad. You must mount a diamond quad somewhat higher on the mast or tower than for an equivalent square array, just to keep the bottom spreader away from the tower guys when you rotate the antenna.

Two Multiband Quads

This section describes two multiband quad designs. The first is a large triband 20/15/10-meter quad built on a 26-foot boom made of 3-inch irrigation tubing. This antenna has three elements on 20 meters, four elements on 15 meters, and five elements on 10 meters. **Fig 7** shows a photograph of the five-element triband quad.

The second project is a compact two-element triband quad on an 8-foot boom that covers 20, 17, 15, 12 and 10 meters. We call this a "pentaband" quad since it covers five bands. This antenna uses five concentric wire loops mounted on each of the two sets of spreaders. Either antenna may be constructed in a diamond or square configuration.

While the same basic construction techniques are employed for both multiband quads, the scale of the larger triband antenna makes it a far more ambitious undertaking! The large quad requires a strong tower and a rugged rotator. It also requires a fair amount of real estate in order to raise the quad to the top of the tower without entangling trees or other antennas.

A FIVE-ELEMENT, 26-FOOT BOOM TRIBAND QUAD

Five sets of element spreaders are used to support the three elements used on 14 MHz, four elements on 21 MHz and five elements on 28-MHz. We chose to use four elements on 15 meters in this design (rather than the five we could have been employed on this length of boom) because the difference in optimized performance wasn't great enough to warrant the extra complexity of using five elements. The dimensions are listed in **Table 2**, and are designed for center frequencies of 14.175, 21.2 and 28.4 MHz.

The spacing between elements has been chosen to provide good compromises in performance consistent with boom length and mechanical construction. You can see that the element spacings for 20 meters are quite different from those for the optimized monoband design. This is because the same set of spreaders is used for all

Fig 7—Photo of the three-band, five-element quad antenna.

Fig 8—Layout for the three-band, five-element quad, not drawn to scale. See Table 2 for dimensions.

three bands on three out of the five elements, and the higher-frequency bands dictate the spacing because they are more critical.

Each of the parasitic loops is closed (ends soldered together) and requires no tuning. **Fig 8** shows the physical layout of the triband quad. **Fig 9** plots the computed free-space gain, front-to-rear ratio and SWR response across the 20-meter band. With only a few degrees of freedom in tuning and spacing of the three elements, it is impossible to spread the response out to cover the entire 20-meter band. The compromise design results in a rearward pattern that varies from a worst-case of just under 10 dB at the high end of the band, to a peak F/R of just

under 19 dB at 14.2 MHz, in the phone portion of the band. The F/R is about 11 dB at the low end of the band.

The SWR remains under 3:1 for the entire 20-meter band, rising to 2.8:1 at the high end. The feed system for this triband quad consists of three separate 50-Ω coax

Fig 9—Computed performance of the triband, five-element quad over the 20-meter band. The direct 50-Ω feed system holds the SWR below 2.8: 1 across the whole band. This could be improved with a gamma-match system tuned to 14.1 MHz if the builder really desires a low SWR. The F/R peaks at 14.1 MHz and remains above 10 dB across the whole band.

Table 2
Three-Band Five-Element Quad on 26-Foot Boom

	14.15 MHz	21.2 MHz	28.4 MHz
Reflector	72′ 6"	49′ 4"	36′ 8"
R-DE Spacing	12′	12′	6′
Driven Element	71′	47′ 6"	35′ 4"
DE-D1 Spacing	14′	7′	6′
Director 1	68′ 6"	46′ 8"	34′ 8"
D1-D2 Spacing	—	14′	7′
Director 2	—	46′ 5"	34′ 8"
D2-D3 Spacing	—	—	7′
Director 3	—	—	34′
Feed method	Direct 50 Ω	Direct 50 Ω	Direct 50 Ω

lines, one per driven element, together with a relay switchbox mounted to the boom so that a single coax can be used back to the operating position. Each feed line uses a ferrite-bead balun to control common-mode currents and preserve the radiation pattern and each coax going to the switchbox is cut to be an electrical three-quarter wavelength on 15 meters. This presents a short at the unused driven elements since modeling indicated that the 15-meter band is adversely affected by the presence of the 20-meter driven element if it is left open-circuited. If you use RG-213 coax, the $^3/_4$-λ electrical length of each feed line is 23 feet long at 21.2 MHz. This is sufficient physical length to reach each driven element from the switchbox.

Fig 10 shows the free-space response for the 15-meter band. The rearward response is roughly 15 dB across the band. This is a result of the residual interaction between the 20-meter elements on 15 meters, and no further tuning could improve the F/R. Note how flat the SWR curve is. This SWR characteristic is what gives the quad the reputation of being "wideband." A flat SWR curve, however, is not necessarily a good indicator of optimal performance for directional antennas like quads or Yagis, particularly multiband designs where compromises must be made by physical necessity.

Fig 11 shows the characteristics of the 10-meter portion of the two-element triband quad. The response favors the low-phone band, with the F/R falling to about 12 dB at the low end of the frequency range and rising to just about 23 dB at 28.4 MHz. The SWR curve is once again relatively flat across the major portion of the band up to 28.8 MHz.

Construction

The most obvious problem related to quad antennas is the ability to build a structurally sound system. If high winds or heavy ice are a normal part of the environment, special precautions are necessary if the antenna is to survive a winter season. Another stumbling block for would-be quad builders is the installation of a three-dimensional system (assuming a Yagi has only two important dimensions) on top of a tower—especially if the tower needs guy wires for support. With proper planning, however, many of these obstacles can be overcome. For example, a tram system may be used.

Both multiband quad arrays use fiberglass spreaders (see Chapter 21 for suppliers). Bamboo is a suitable substitute (if economy is of great importance). However, the additional weight of the bamboo spreaders over fiberglass is an important consideration. A typical 12-foot bamboo pole weighs about 2 pounds; the fiberglass type weighs less than a pound. By multiplying the difference times 8 for a two-element array, times 12 for a three-element antenna, and so on, it quickly becomes apparent that fiberglass is worth the investment if weight is an important factor. Properly treated, bamboo has a useful life of three or four years, while fiberglass life is probably 10 times longer.

Spreader supports (sometimes called *spiders*) are available from many different manufacturers. If the builder is keeping the cost at a minimum, he should consider building his own. The expense is about half that of a commercially manufactured equivalent and, according to some authorities, the homemade arm supports described below are less likely to rotate on the boom as a result of wind pressure.

A 3-foot length of steel angle stock, 1 inch per side, is used to interconnect the pairs of spreader arms. The steel is drilled at the center to accept a muffler clamp of sufficient size to clamp the assembly to the boom. The fiberglass is clamped to the steel angle stock with auto-

Fig 10—Computed performance of the triband, five-element quad over the 15-meter band. There is some degree of interaction with the 20-meter elements, limiting the worst-case F/R to about 15 dB. The gain and SWR curves are relatively flat across the band.

Fig 11—Computed performance of the triband, five-element quad over the 10-meter band. The F/R is higher than 12 dB across the band from 28.0 to 29.0 MHz, but the SWR rises at the top end of the band beyond 2:1. The free-space gain is higher than 10 dBi across the band.

Fig 12—Details of one of two assemblies for a spreader frame. The two assemblies are joined back-to-back to form an X with a muffler clamp mounted at the position shown.

Fig 14—An alternative method of assembling the wire of a quad loop to the spreader arm.

Fig 13—A method of assembling a corner of the wire loop of a quad element to the spreader arm.

Fig 15—Suitable circuit for relay switching of bands for the three-band quad. A three-wire control cable is required. K1, K2—any type of relay suitable for RF switching, coaxial type not required (Potter and Brumfeld MR11A acceptable; although this type has double-pole contacts, mechanical arrangements of most single-pole relays make them unacceptable for switching of RF).

motive hose clamps, two per pole. Each quad-loop spreader frame consists of two assemblies of the type shown in **Fig 12**.

Connecting the wires to the fiberglass can be done in a number of different ways. Holes can be drilled at the proper places on the spreader arms and the wires run through them. A separate wrap wire should be included

at the entry/exit point to prevent the loop from slipping. Details are presented in **Fig 13**. Some amateurs have experienced cracking of the fiberglass, which might be a result of drilling holes through the material. However, this seems to be the exception rather than the rule. The model described here has no holes in the spreader arms; the wires are attached to each arm with a few layers of

Fig 16—The relay box is mounted on the boom near the center. Each of the spreader-arm fiberglass poles is attached to steel angle stock with hose clamps.

plastic electrical tape and then wrapped approximately 20 times in a crisscross fashion with $^1/_8$-inch diameter nylon string, followed by more electrical tape for UV protection, as shown in **Fig 14**.

The wire loops are left open at the bottom of each driven element where the feed-line coaxes are attached. All of the parasitic elements are continuous loops of wire; the solder joint is at the base of the diamond.

Although you could run three separate coax cables down to the shack, we suggest that you install a relay box at the center of the boom. A three-wire control system may be used to apply power to the proper relay for changing bands. The circuit diagram of a typical configuration is presented in **Fig 15** and its installation is shown in **Fig 16**.

Every effort must be placed upon proper construction if you want to have freedom from mechanical problems. Hardware must be secure or vibration created by the wind may cause separation of assemblies. Solder joints should be clamped in place to keep them from flexing, which might fracture a connection point.

A TWO-ELEMENT, 8-FOOT BOOM PENTABAND QUAD

This two-element pentaband (20/17/15/12/10-meter) quad uses the same construction techniques as its big brother above. Since only two elements are used, the boom can be less robust for this antenna, at 2 inches diameter rather than 3 inches. Those who like really rugged antennas can still use the 3-inch diameter boom, of course.

Table 3 lists the element dimensions for the pentaband quad. The following plots show the performance for each of the five bands covered. The feed system for the pentaband quad uses five, direct 50-Ω coaxes, one to each driven element. These five coaxes are cut to be $^3/_4$-λ electrically on 10 meters (17 feet, 2 inches for RG-213 at 28.4 MHz). In this design the 10-meter band is the one most affected by the presence of the other driven elements if they are left unshorted. The $^3/_4$-λ lines open-circuited at the switchbox are long enough physically to reach all elements from a centrally mounted switchbox. This length assumes that the switchbox open-circuits the unused coaxes. If the switchbox short-circuits unused coaxes (as several commercial switchboxes do), then use $^1/_2$-λ long lines to feed all five driven elements (11 feet,

Fig 17—Computed performance of the pentaband two-element quad on 20 meters. With the simple direct-feed system, the SWR rises to about 2.3:1 at the low end of the band. A gamma match can bring the SWR down to 1:1 at 14.1 MHz, if desired.

Table 3
Five-Band Two-Element Quad on 8-Foot Boom

	14.2 MHz	18.1 MHz	21 MHz	24.9 MHz	28.4 MHz
Reflector	72′ 4"	56′ 4"	48′ 6"	40′ 11$^1/_4$"	37′ 5$^1/_2$"
R-DE Spacing	8′	8′	8′	8′	8′
Driven Element	69′ 10$^1/_2$"	54′ 10$^1/_2$"	46′ 7"	39′ 10$^1/_2$"	34′ 6"

5 inches for RG-213 at 28.4 MHz).

The SWR curves do not necessarily go down to 1:1 because of this simple, direct feed system. If anyone is bothered by this, of course they can always implement individual matching systems, such as gamma matches. Most amateurs would agree that such a degree of complexity is not warranted. The worst-case SWR is less than 2.3:1 on each band, even with direct feed on 20 meters. With typical lengths of coaxial feed line from the shack to the switchbox at the antenna, say 100 feet of RG-213, the SWR at the transmitter would be less than 2.0:1 on all bands due to losses in the feed line.

Fig 17 shows the computed responses for the pentaband quad over the 20-meter band. With only two degrees of freedom (spacing and element tuning) there is not much that can be done to spread the response out over the entire 20-meter band. Nonetheless, the performance over the band is still pretty reasonable for an antenna this small. The F/R pattern peaks at 19 dB at 14.1 MHz and falls to about 10 dB at either end of the band. The free-space gain varies from about 7.5 dBi to just above 6 dBi, comparable to a short-boom three-element Yagi. The SWR curve remains below 2.3:1 across the band. If you were to employ a gamma match tuned at 14.1 MHz, you could limit the peak SWR to less than 2.0:1, and this would still occur at 14.0 MHz.

Fig 18—Computed performance of the pentaband two-element quad on 17 meters. There is some interaction with the other elements, but overall the performance is satisfactory on this band.

Fig 20—Computed performance of the pentaband two-element quad on 12 meters.

Fig 19—Computed performance of the pentaband two-element quad on 15 meters. The performance is acceptable across the whole band.

Fig 21—Computed performance of the pentaband two-element quad on 10 meters. The SWR curve is slightly above the target 2:1 at the low end of the band and rises to about 2.2:1 at 28.8 MHz. This unlikely to be a problem, even with rigs with automatic power-reduction due to SWR, since the SWR at the input of a typical coax feed line will be lower than that at the antenna due to losses in the line.

On 17 meters, **Fig 18** shows that the other elements are affecting 18 MHz, even with element-length optimization. Careful examination of the current induced on the other elements shows that the 20-meter driven element is interacting on 18 MHz, deteriorating the pattern and gain slightly. Even still, the performance on 17 meters is reasonable, especially for a five-band quad on an 8-foot boom.

On 15 meters, the interactions seems to have been contained, as **Fig 19** demonstrates. The F/R peaks at 21.1 MHz, at 19 dB and remains better than 12 dB past the top of the band. The SWR curve is low across the whole band.

On 12 meters, the interaction between bands is minor, leading to the good results shown in **Fig 20**. The SWR change across this band is quite flat, which isn't surprising given the narrow bandwidth of the 12-meter band.

On 10 meters, the interaction seems to have been tamed well by computer-tuning of the elements. The F/R remains higher than about 14 dB from 28 to 29 MHz. The SWR remains below 2.2:1 up to about 28.8 MHz, while the gain is relatively flat across the band at more than 7.2 dBi in free space. See **Fig 21**.

Overall, this pentaband quad is physically compact and yet it provides good performance across all five bands.

It is competitive with commercial Log Periodic Dipole Array (LPDA) designs and triband Yagi designs that employ longer booms.

BIBLIOGRAPHY

Source material and more extended discussions of the topics covered in this chapter can be found in the references given below and in the textbooks listed at the end of Chapter 2.

P. S. Carter, C. W. Hansell and N. E. Lindenblad, "Development of Directive Transmitting Antennas by R.C.A. Communications," *Proc. IRE*, Oct 1931.

C. Cleveland, "More'n One Way to Switch an Antenna," Technical Correspondence, *QST*, Nov 1986.

D. Cutter, "Simple Switcher," *73*, May 1980.

D. DeMaw, "A Remote Antenna Switcher for HF," *QST*, Jun 1986.

M. G. Knitter, Ed., *Loop Antennas—Design and Theory* (Cambridge, WI: National Radio Club, 1983).

H. Landskov, W7KAR, "Evolution of a Quad Array," *QST*, Mar 1977.

J. Lindsay, "Quads and Yagis," *QST*, May 1968.

F. E. Terman, *Radio Engineering*, 3rd ed. (New York: McGraw-Hill Book Co, 1947).

E. M. Williams, "Radiating Characteristics of Short-Wave Loop Aerials," *Proc. IRE*, Oct 1940.

Long-Wire and Traveling-Wave Antennas

The power gain and directive characteristics of electrically long wires (that is, wires that are long in terms of wavelength), as described in Chapter 2, make them useful for long-distance transmission and reception on the higher frequencies. Long wires can be combined to form antennas of various shapes that increase the gain and directivity over a single wire. The term *long wire*, as used in this chapter, means any such configuration, not just a straight-wire antenna.

Long Wires Versus Multielement Arrays

In general, the gain obtained with long-wire antennas is not as great, when the space available for the antenna is limited, as you can obtain from the multielement phased arrays in Chapter 8 or from a parasitic array such as a Yagi or quad (Chapters 11 or 12). However, the long-wire antenna has advantages of its own that tend to compensate for this deficiency. The construction of long-wire antennas is simple both electrically and mechanically, and there are no especially critical dimensions or adjustments. The long-wire antenna will work well and give satisfactory gain and directivity over a 2-to-1 frequency range. In addition, it will accept power and radiate well on any frequency for which its overall length is not less than about a half wavelength. Since a wire is not electrically long, even at 28 MHz, unless its physical length is equal to at least a half wavelength on 3.5 MHz, any long-wire can be used on all amateur bands that are useful for long-distance communication.

Between two directive antennas having the same theoretical gain, one a multielement array and the other a long-wire antenna, many amateurs have found that the long-wire antenna seems more effective in reception. One possible explanation is that there is a *diversity effect* with a long-wire antenna because it is spread out over a large distance, rather than being concentrated in a small space, as would be the case with a Yagi, for example. This may raise the average level of received energy for ionospheric-propagated signals. Another factor is that long-wire antennas have directive patterns that can be extremely sharp in the horizontal (azimuthal) plane. This is an advantage that other types of multielement arrays do not have, but it can be a double-edged sword too. We'll discuss this aspect in some detail in this chapter.

General Characteristics of Long-Wire Antennas

Whether the long-wire antenna is a single wire running in one direction or is formed into a V-beam, rhombic, or some other configuration, there are certain general principles that apply and some performance features that are common to all types. The first of these is that the power gain of a long-wire antenna as compared with a half-wave dipole is not considerable until the antenna is really long (its length measured in wavelengths rather than in a specific number of feet). The reason for this is that the fields radiated by elementary lengths of wire along the antenna do not combine, at a distance, in as simple a fashion as the fields from half-wave dipoles used in other types of directive arrays.

There is no point in space, for example, where the distant fields from all points along the wire are exactly in phase (as they are, in the optimum direction, in the case of two or more collinear or broadside dipoles when fed with in-phase currents). Consequently, the field strength at a distance is always less than would be obtained if the same length of wire were cut up into properly phased and sepa-

rately driven dipoles. As the wire is made longer, the fields combine to form increasingly intense main lobes, but these lobes do not develop appreciably until the wire is several wavelengths long. See **Fig 1**.

The longer the antenna, the sharper the lobes become, and since it is really a hollow cone of radiation about the wire in free space, it becomes sharper in both planes. Also, the greater the length, the smaller the angle with the wire at which the maximum radiation lobes occur. There are four main lobes to the directive patterns of long-wire antennas; each makes the same angle with respect to the wire.

Fig 2A shows the azimuthal radiation pattern of a 1-λ long-wire antenna, compared with a ¹/₂-λ dipole. Both antennas are mounted at the same height of 1 λ above flat ground (70 feet high at 14 MHz, with a wire length of 70 feet) and both patterns are for an elevation angle of

10°, an angle suitable for long-distance communication on 20 meters. The long-wire in Fig 2A is oriented in the 270° to 90° direction, while the dipole is aligned at right angles so that its characteristic figure-8 pattern goes left-to-right. The 1-λ long-wire has about 0.6 dB more gain than the dipole, with four main lobes as compared to the two lobes from the dipole.

You can see that the two lobes on the left side of Fig 2A are about 1 dB down compared to the two lobes on the right side. This is because the long-wire here is fed at the left-hand end in the computer model. Energy is radiated as a wave travels down the wire and some energy is also lost to ohmic resistance in the wire and the ground. The forward-going wave then reflects from the open-circuit at the right-hand end of the wire and reverses direction, traveling toward the left end, still radiating as it

Fig 1—Theoretical gain of a long-wire antenna, in dBi, as a function of wire length. The angle, with respect to the wire, at which the radiation intensity is maximum also is shown.

Max. Gain = 7.41 dBi
Freq = 14.0 MHz
(A)
Azimuth Plot
Elevation Angle = 10°

Max Gain = 8.10 dBi
Freq = 14.0 MHz
Elevation Plot
Azimuth Angle = 38°
(B)

Fig 2—At A, comparison of azimuthal patterns for a 1-λ long-wire antenna (solid line) and a ½-λ dipole (dashed line) at an elevation angle of 10°. Each antenna is located 1 λ (70 feet) over flat ground at 14 MHz. At B, the elevation-plane patterns at peak azimuth angles for each antenna. The long-wire has about 0.6 dB more gain than the dipole.

travels. An antenna operating in this way has much the same characteristics as a transmission line that is terminated in an open circuit—that is, it has standing waves on it. Unterminated long-wire antennas are often referred to as *standing wave antennas*. As the length of a long-wire antenna is increased, a moderate front-to-back ratio results, about 3 dB for very long antennas.

Fig 2B shows the elevation-plane pattern for the long-wire and for the dipole. In each case the elevation pattern is at the azimuth of maximum gain—at an angle of 38° with respect to the wire-axis for the long-wire and at 90° for the dipole. The peak elevation for the long-wire is very slightly lower than that for the dipole at the same height above ground, but not by much. In other words, the height above ground is the main determining factor for the shape of the main lobe of a long-wire's elevation pattern, as it is for most horizontally polarized antennas.

The shape of the azimuth and elevation patterns in Fig 2 might lead you to believe that the radiation pattern is simple. **Fig 3** is a 3-D representation of the pattern from a 1-λ long-wire that is 1 λ high over flat ground. Besides the main low-angle lobes, there are strong lobes at higher angles. Things get even more complicated when the length of the long-wire increases.

Directivity

Because many points along a long wire are carrying currents in different phases (with different current amplitudes as well), the field pattern at a distance becomes more complex as the wire is made longer. This complexity is manifested in a series of minor lobes, the number of which increases with the wire length. The intensity of radiation from the minor lobes is frequently as great as, and sometimes greater than, the radiation from a half-wave dipole. The energy radiated in the minor lobes is not available to improve the gain in the major lobes, which is another reason why a long-wire antenna must be long to give appreciable gain in the desired directions.

Fig 4 shows an azimuthal-plane comparison between a 3-λ (209 feet long) long-wire and the comparison $1/2$-λ dipole. The long-wire now has 8 minor lobes besides the four main lobes. Note that the angle the main lobes make with respect to the axis of the long-wire (also left-to-right in Fig 4) becomes smaller as the length of the long-wire increases. For the 3-λ long-wire, the main lobes occur 28° off the axis of the wire itself.

Other types of simple driven and parasitic arrays do not have minor lobes of any great consequence. For that reason they frequently seem to have much better directivity than long-wire antennas, because their responses in undesired directions are well down from their response in the desired direction. This is the case even if a multielement array and a long-wire antenna have the same peak gain in the favored direction. **Fig 5** compares the same 3-λ long-wire with a 4-element Yagi and a ½-λ dipole, again both at the same height as the long-wire. Note that the Yagi has only a single backlobe, down about 21 dB from its broad main lobe, which has a 3-dB beamwidth of 63°. The 3-dB beamwidth of the long-wire's main lobes (at a 28° angle from the wire axis) is far more narrow, at only 23°.

For amateur work, particularly with directive antennas that cannot be rotated, the minor lobes of a long-wire antenna have some advantages. Although the nulls in the

Fig 3—A 3-D representation of the radiation pattern for the 1-λ long-wire shown in Fig 2. The pattern is obviously rather complex. It gets even more complicated for wires longer than 1 λ.

Max. Gain = 10.33 dBi
Freq = 14.0 MHz

Azimuth Plot
Elevation Angle = 10°

Fig 4—An azimuthal-plane comparison between a 3-λ (209 feet long) long-wire (solid line) and the comparison ½-λ dipole (dashed line) at 70 feet high (1 λ) at 14 MHz.

Long-Wire and Traveling-Wave Antennas   13-3

Fig 5—A comparison between the 3-λ long-wire (solid line) in Fig 4, a 4-element 20-meter Yagi on a 26-foot boom (dotted line), and a ½-λ dipole (dashed line), again at a height of 70 feet. The main lobes of the long-wire are very narrow compared to the wide frontal lobe of the Yagi. The long-wire exhibits an azimuthal pattern that is more omnidirectional in nature than a Yagi, particularly when the narrow, deep nulls in the long-wire's pattern are filled-in due to irregularities in the terrain under its long span of wire.

computer model in Fig 5 are deeper than 30 dB, they are not so dramatic in actual practice. This is due to irregularities in the terrain that inevitably occur under the span of a long wire. In most directions the long-wire antenna will be as good as a half-wave dipole, and in addition will give high gain in the most favored directions, even though that is over narrow azimuths.

Fig 6A compares the azimuth responses for a 5-λ long-wire (350 feet long at 14 MHz) to the same 4-element Yagi and dipole. The long-wire now exhibits 16 minor lobes in addition to its four main lobes. The peaks of these sidelobes are down about 8 dB from the main lobes and they are stronger than the dipole, making this long-wire antenna effectively omnidirectional. Fig 6B shows the elevation pattern of the 5-λ long-wire at its most effective azimuth compared to a dipole. Again, the shape of the main lobe is mainly determined by the long-wire's height above ground, since the peak angle is only just a bit lower than the peak angle for the dipole. The long-wire's elevation response breaks up into numerous lobes above the main lobes, just as it does in the azimuth plane.

For the really ambitious, **Fig 7** compares the performance for an 8-λ (571 feet) long-wire antenna with a 4-element Yagi and the $^1/_2$-λ dipole. Again, in actual practice, the nulls would tend to be filled in by terrain irregularities, so a very long antenna like this would be a pretty potent performer.

Calculating Length

In this chapter, lengths are discussed in terms of wave-

(A)

(B)

Fig 6—At A, the azimuth responses for a 5-λ long-wire (350 feet long at 14 MHz—solid line) to the same 4-element Yagi (dotted line) and dipole (dashed line) as in Fig 5. At B, the elevation-plane responses for the long-wire (solid line) and the dipole (dashed line) by themselves. Note that the elevation angle giving peak gain for each antenna is just about the same. The long-wire achieves gain by compressing mainly the azimuthal response, squeezing the gain into narrow lobes; not so much by squeezing the elevation pattern for gain.

Fig 7—The azimuthal-plane performance for an 8-λ (571 feet) long-wire antenna (solid line), compared with a 4-element Yagi (dotted line) and a ½-λ dipole (dashed line).

Fig 8—Methods for feeding long single-wire antennas.

lengths. Throughout the preceding discussion the frequency in the models was held at 14 MHz. Remember that a long-wire that is 4 λ long at 14 MHz is 8 λ long at 28 MHz.

There is nothing very critical about wire lengths in an antenna system that will work over a frequency range including several amateur bands. The antenna characteristics change very slowly with length, except when the wires are short (around one wavelength, for instance). There is no need to try to establish exact resonance at a particular frequency for proper antenna operation.

The formula for determining the lengths for harmonic wires is:

$$\text{Length (feet)} = \frac{984 \left(N - 0.025 \right)}{f \left(\text{MHz} \right)} \qquad \text{(Eq 1)}$$

where N is the antenna length in wavelengths. In cases where precise resonance is desired for some reason (for obtaining a resistive load for a transmission line at a particular frequency, for example) it is best established by trimming the wire length until the standing-wave ratio on the line is minimum.

Tilted Wires

In theory, it is possible to maximize gain from a long-wire antenna by tilting it to favor a desired elevation take-off angle. Unfortunately, the effect of real ground under the antenna negates the possible advantages of tilting, just as it does when a Yagi or other type of parasitic array is tilted from horizontal. You would do better keeping a long-wire antenna horizontal, but raising it higher above ground, to achieve more gain at low takeoff angles.

Feeding Long Wires

A long-wire antenna is normally fed at the end or at a current loop. Since a current loop changes to a node when the antenna is operated at any even multiple of the frequency for which it is designed, a long-wire antenna will operate as a true long wire on all bands only when it is fed at the end.

A common method of feeding a long-wire is to use a resonant open-wire line. This system will work on all bands down to the one, if any, at which the antenna is only a half wave long. Any convenient line length can be used if you match the transmitter to the line's input impedance using an antenna tuner, as described in Chapter 25.

Two arrangements for using nonresonant lines are given in **Fig 8**. The one at A is useful for one band only since the matching section must be a quarter wave long, approximately, unless a different matching section is used for each band. In B, the λ/4 transformer (Q-section) impedance can be designed to match the antenna to the line, as described in Chapter 26. You can determine the value of radiation resistance using a modern modeling program or you can actually measure the feed-point impedance. Although it will work as designed on only one band, the antenna can be used on other bands by treating the line and matching transformer as a resonant line. In this case, as mentioned earlier, the antenna will not radiate as a true long wire on even multiples of the frequency for which the matching system is designed.

The end-fed arrangement, although the most convenient when tuned feeders are used, suffers the disadvantage that there is likely to be a considerable antenna current on the line. In addition, the antenna reactance changes rap-

idly with frequency. Consequently, when the wire is several wavelengths long, a relatively small change in frequency—a fraction of the width of a band—may require major changes in the adjustment of the antenna tuner. Also, the line becomes unbalanced at all frequencies between those at which the antenna is resonant. This leads to a considerable amount of radiation from the line. The unbalance can be overcome by using multiple long wires in a V or rhombic shape, as described below.

COMBINATIONS OF LONG WIRES

The directivity and gain of long wires may be increased by using two wires placed in relation to each other such that the fields from both combine to produce the greatest possible field strength at a distant point. The principle is similar to that used in designing the multi-element arrays described in Chapter 8.

Parallel Wires

One possible method of using two (or more) long wires is to place them in parallel, with a spacing of $^1/_2 \lambda$ or so, and feed the two in phase. In the direction of the wires the fields will add in phase. However, the takeoff angle is high directly in the orientation of the wire, and this method will result in rather high-angle radiation even if the wires are several wavelengths long. With a parallel arrangement of this sort the gain should be about 3 dB over a single wire of the same length, at spacings in the vicinity of $^1/_2$ wavelength.

The V-Beam Antenna

Instead of using two long wires parallel to each other, they may be placed in the form of a horizontal V, with the included angle between the wires equal to twice the angle made by the main lobes referenced to the wire axis for a single wire of the same physical length. For example, for a leg length of 5 λ, the angle between the legs of a V should be about 42°, twice the angle of 21° of the main lobe refer-

enced to the long-wire's axis. See Fig 6A.

The plane directive patterns of the individual wires combine along a line in the plane of the antenna and bisecting the V, where the fields from the individual wires reinforce each other. The sidelobes in the azimuthal pattern are suppressed by about 10 dB, so the pattern becomes essentially bidirectional. See **Fig 9**.

The included angle between the legs is not particularly critical. This is fortunate, especially if the same antenna is used on multiple bands, where the electrical length varies directly with frequency. This would normally require different included angles for each band. For multiband V-antennas, a compromise angle is usually chosen to equalize performance. **Fig 10** shows the azimuthal pattern for a V-beam with 1-λ legs, with an included angle of 75° between the legs, mounted 1 λ above flat ground. This is for a 10° elevation angle. At 14 MHz the antenna has two 70-foot high, 68.5-foot long legs, separated at their far ends by 83.4 feet. For comparison the azimuthal patterns for the same 4-element Yagi and ½-λ dipole used previously for the long-wires are overlaid on the same plot. The V has about 2 dB more gain than the dipole but is down some 4 dB compared to the Yagi, as expected for relatively short legs.

Fig 11 shows the azimuthal pattern for the same antenna in Fig 10, but at 28 MHz and at an elevation angle of 6°. Because the legs are twice as long electrically at 28 MHz, the V-beam has compressed the main lobe into a narrow beam that now has a peak gain equal to the Yagi, but with a 3-dB beamwidth of only 18.8°. Note that you could obtain about 0.7 dB more gain at 14 MHz, with a 1.7-dB degradation of gain at 28 MHz, if you increase the included angle to 90° rather than 75°.

Fig 12 shows the azimuthal pattern for a V-beam with 2-λ legs (137 feet at 14 MHz), with an included angle of 60° between them. As usual, the assumed height is 70 feet, or 1 λ at 14 MHz. The peak gain for the V-beam is just about equal to that of the 4-element Yagi, although the 3-dB

Fig 9—Two long wires and their respective patterns are shown at the left. If these two wires are combined to form a V with an angle that is twice that of the major lobes of the wires and with the wires excited out of phase, the radiation along the bisector of the V adds and the radiation in the other directions tends to cancel.

Fig 10— Azimuthal-plane pattern at 10° elevation angle for a 14-MHz V-beam (solid line) with 1-λ legs (68.5 feet long), using an included angle of 75° between the legs. The V-beam is mounted 1 λ above flat ground, and is compared with a ½-λ dipole (dashed line) and a 4-element 20-meter Yagi on a 26-foot boom (dotted line).

Max. Gain = 12.75 dBi
Freq = 14.0 MHz
Azimuth Plot
Elevation Angle = 10°

Fig 12—Azimuthal pattern for a V-beam (solid line) with 2-λ legs (137 feet at 14 MHz), with an included angle of 60° between them. The height is 70 feet, or 1 λ, over flat ground. For comparison, the response for a 4-element Yagi (dotted line) and a dipole (dashed line) are shown. The 3-dB beamwidth has decreased to 23.0°.

Max. Gain = 12.75 dBi
Freq = 14.0 MHz
Azimuth Plot
Elevation Angle = 10°

Fig 11—The same V-beam as in Fig 10 at 28 MHz (solid line), at an elevation angle of 6°, compared to a 4-element Yagi (dotted line) and a dipole (dashed line). The V-beam's pattern is very narrow, at 18.8° at the 3-dB points, requiring accurate placement of the supports poles to aim the antenna at the desired geographic target.

Max. Gain = 13.61 dBi
Freq = 28.0 MHz
Azimuth Plot
Elevation Angle = 6°

nose beamwidth is narrow, at 23°. This makes setting up the geometry critical if you want to maximize gain into a particular geographic area. While you might be able to get away with using convenient trees to support such an antenna, it's far more likely that you'll have to use carefully located towers to make sure the beam is aimed where you expect it to be pointed.

For example, in order to cover all of Europe from San Francisco, an antenna must cover from about 11° (to Moscow) to about 46° (to Portugal). This is a range of 35° and signals from the V-beam in Fig 12 would be down some 7 dB over this range of angles, assuming the center of the beam is pointed exactly at a heading of 28.5°. The 4-element Yagi on the other hand would cover this range of azimuths more consistently, since its 3-dB beamwidth is 63°.

Fig 13 shows the same V-beam as in Fig 12, but this time at 28 MHz. The peak gain of the main lobe is now about 1 dB stronger than the 4-element Yagi used as a reference, and the main lobe has two nearby sidelobes that tend to broaden out the azimuthal response. At this frequency the V-beam would cover all of Europe better from San Francisco.

Fig 14 shows a V-beam with 3-λ (209 feet at 14 MHz) legs with an included angle of 50° between them. The peak gain is now greater than that of a 4-element Yagi, but the 3-dB beamwidth has been reduced to 17.8°, making aim-

Long-Wire and Traveling-Wave Antennas   13-7

Max. Gain = 14.67 dBi
Freq = 28.0 MHz
Azimuth Plot
Elevation Angle = 6°

Fig 13—The same 2-λ per leg V-beam (solid line) as in Fig 12, but at 28 MHz and at a 6° takeoff elevation angle. Two sidelobes have appeared flanking the main lobe, making the effective azimuthal pattern wider at this frequency.

Max. Gain = 15.46 dBi
Freq = 28.0 MHz
Azimuth Plot
Elevation Angle = 6°

Fig 15—The same 209-foot/leg V-beam as Fig 14, but at 28 MHz. Again, the two close-in sidelobes tend to spread out the azimuthal response some at 28 MHz.

Max. Gain = 13.71 dBi
Freq = 14.0 MHz
Azimuth Plot
Elevation Angle = 10°

Fig 14—A V-beam (solid line) with 3-λ (209 feet at 14 MHz) legs using an included angle of 50° between them, compared to a 4-element Yagi (dotted line) and a dipole (dashed line). The 3-dB beamwidth has now decreased to 17.8°.

ing the antenna even more critical. **Fig 15** shows the same V-beam at 28 MHz. Here again, the main lobe has nearby sidelobes that broaden the effective azimuth to cover a wider area.

Fig 16 shows the elevation-plane response for the same 209-foot leg V-beam at 28 MHz (3-λ at 14 MHz), compared to a dipole at the same height of 70 feet. The higher-gain V-beam suppresses higher-angle lobes, essentially stealing energy from them and concentrating it in the main beam at 6° elevation.

The same antenna can be used at 3.5 and 7 MHz. The gain will not be large, however, because the legs are not very long at these frequencies. **Fig 17** compares the V-beam versus a horizontal ½-λ 40-meter dipole at 70 feet. At low elevation angles there is about 2 dB of advantage on 40 meters. **Fig 18** shows the same type of comparison for 80 meters, where the 80-meter dipole is superior at all angles.

Other V Combinations

A gain increase of about 3 dB can be had by stacking two V-beams one above the other, a half wavelength apart, and feeding them with in-phase currents. This will result in a lowered angle of radiation. The bottom V should be at least a quarter wavelength above the ground, and preferably a half wavelength. This arrangement will narrow the

13-8   Chapter 13

Fig 16—The elevation-plane of the 209-foot/leg V-beam (solid line) compared to the dipole (dashed line). Again, the elevation angle for peak gain corresponds well to that of the simple dipole at the same height.

Fig 18—Elevation pattern for the same 209-foot-per-leg V-beam (solid line), at 3.5 MHz, compared to an 80-meter dipole at 70 feet (dashed line).

Fig 17—Elevation pattern for the same 209-foot-per-leg V-beam (solid line), at 7 MHz, compared to a 40-meter dipole (dashed line) at the same height of 70 feet.

elevation pattern and it will also have a narrow azimuthal pattern.

The V antenna can be made unidirectional by using a second V placed an odd multiple of a quarter wavelength in back of the first and exciting the two with a phase difference of 90°. The system will be unidirectional in the direction of the antenna with the lagging current. However, the V reflector is not normally employed by amateurs at low frequencies because it restricts the use to one band and requires a fairly elaborate supporting structure. Stacked Vs with driven reflectors could, however, be built for the 200- to 500-MHz region without much difficulty.

Feeding the V Beam

The V-beam antenna is most conveniently fed with tuned open-wire feeders with an antenna tuner, since this permits multiband operation. Although the length of the wires in a V-beam is not at all critical, it is important that both wires be the same electrical length. If a single band

matching solution is desired, probably the most appropriate matching system is that using a stub or quarter-wave matching section. The adjustment of such a system is described in Chapter 26.

THE RESONANT RHOMBIC ANTENNA

The diamond-shaped or rhombic antenna shown in **Fig 19** can be looked upon as two acute-angle V-beams placed end-to-end. This arrangement is called a *resonant rhombic*. The leg lengths of the resonant rhombic must be an integral number of half wavelengths to avoid reactance at its feed point.

The resonant rhombic has two advantages over the simple V-beam. For the same total wire length it gives somewhat greater gain than the V-beam. A rhombic with 3 λ on a leg, for example, has about 1 dB gain over a V antenna with 6 wavelengths on a leg. **Fig 20** compares the azimuthal pattern at a 10° elevation for a resonant rhombic with 3 λ legs on 14 MHz, compared to a V-beam with 6 λ legs at the same height of 70 feet. The 3-dB nose beamwidth of the resonant rhombic is only 12.4° wide, but the gain is very high at 16.26 dBi.

The directional pattern of the rhombic is less frequency sensitive than the V when the antenna is used over a wide frequency range. This is because a change in frequency causes the major lobe from one leg to shift in one direction while the lobe from the opposite leg shifts the other way. This automatic compensation keeps the direction the same over a considerable frequency range. The disadvantage of the rhombic as compared with the V-beam is that an additional support is required.

The same factors that govern the design of the V-beam apply in the case of the resonant rhombic. The optimal apex angle A in Fig 19 is the same as that for a V having an equal leg length. The diamond-shaped antenna also can be operated as a terminated antenna, as described later in this chapter, and much of the discus-

Long-Wire and Traveling-Wave Antennas   13-9

Fig 19—The resonant rhombic or diamond-shaped antenna. All legs are the same length, and opposite angles of the diamond are equal. Length ℓ is an integral number of half wavelengths for resonance.

Max. Gain = 15.61 dBi
Freq = 14.0 MHz

Azimuth Plot
Elevation Angle = 10°

Fig 20—Azimuthal-plane pattern of resonant (unterminated) rhombic (solid line) with 3-λ legs on 14 MHz, at a height of 70 feet above flat ground, compared with a 6-λ per leg V-beam (dashed line) at the same height. Both azimuthal patterns are at a takeoff angle of 10°. The sidelobes for the resonant rhombic are suppressed to a greater degree than those for the V-beam.

sion in that section applies to the resonant rhombic as well.

The resonant rhombic has a bidirectional pattern, with minor lobes in other directions, their number and intensity depending on the leg length. In general, these sidelobes are suppressed better with a resonant rhombic than with a V-beam. When used at frequencies below the VHF region, the rhombic antenna is always mounted with the plane containing the wires horizontal. The polarization in this plane,

and also in the perpendicular plane that bisects the rhombic, is horizontal. At 144 MHz and above, the dimensions are such that the antenna can be mounted with the plane containing the wires vertical if vertical polarization is desired.

When the rhombic antenna is to be used on several HF amateur bands, it is advisable to choose the apex angle, A, on the basis of the leg length in wavelengths at 14 MHz. Although the gain on higher frequency bands will not be quite as favorable as if the antenna had been designed for the higher frequencies, the system will still work well at the low angles that are necessary at such frequencies.

The resonant rhombic has lots of gain, but you must not forget that this gain comes from a radiation pattern that is very narrow. This requires careful placement of the supports for the resonant rhombic to cover desired geographic areas. This is definitely not an antenna that allows you to use just any convenient trees as supports!

The resonant rhombic antenna can be fed in the same way as the V-beam. Resonant feeders are necessary if the antenna is to be used in several amateur bands.

TERMINATED LONG-WIRE ANTENNAS

All the antenna systems considered so far in this chapter have been based on operation with standing waves of current and voltage along the wire. Although most hams use antenna designs based on using resonant wires, resonance is by no means a necessary condition for the wire to radiate and intercept electromagnetic waves efficiently, as discussed in Chapter 2. The result of using nonresonant wires is reactance at the feed point, unless the antenna is terminated with a resistive load.

In **Fig 21**, suppose that the wire is parallel with the ground (horizontal) and is terminated by a load Z equal to its characteristic impedance, Z_{ANT}. The wire and its image in the ground create a transmission line. The load Z can represent a receiver matched to the line. The *terminating resistor* R is also equal to the Z_{ANT} of the wire. A wave coming from direction X will strike the wire first at its far end and sweep across the wire at some angle until it reaches the end at which Z is connected. In so doing, it will induce voltages in the antenna, and currents will flow as a result. The current flowing toward Z is the useful output of the antenna, while the current flowing backwards toward R will be absorbed in R. The same thing is true of a wave coming from the direction X'. In such an antenna there are no standing waves, because all received power is absorbed at either end.

The greatest possible power will be delivered to the load Z when the individual currents induced as the wave sweeps across the wire all combine properly on reaching the load. The currents will reach Z in optimum phase when the time required for a current to flow from the far end of the antenna to Z is exactly one-half cycle longer than the time taken by the wave to sweep over the antenna. A half cycle is equivalent to a half wavelength greater than the distance traversed by the wave from the instant it strikes

Fig 21—Layout for a terminated long-wire antenna.

Max. Gain = 11.64 dBi
Freq = 14.0 MHz

Azimuth Plot
Elevation Angle = 10°

Fig 22—Azimuthal-plane pattern for 5-λ long-wire antenna at 14 MHz and 70 feet above flat ground. The solid line shows the long-wire terminated with 600-Ω to ground, while the dashed line is for the same antenna unterminated. For comparison, the response for a ½-λ dipole is overlaid with the two other patterns. You can see that the terminated long-wire has a good front-to-back pattern, but it loses about 2 dB in forward gain compared to the unterminated long-wire.

the far end of the antenna to the instant that it reaches the near end. This is shown by the small drawing, where AC represents the antenna, BC is a line perpendicular to the wave direction, and AB is the distance traveled by the wave in sweeping past AC. AB must be one-half wavelength shorter than AC. Similarly, AB' must be the same length as AB for a wave arriving from X'.

A wave arriving at the antenna from the opposite direction Y (or Y'), will similarly result in the largest possible current at the far end. However, since the far end is terminated in R, which is equal to Z, all the power delivered to R by the wave arriving from Y will be absorbed in R. The current traveling to Z will produce a signal in Z in proportion to its amplitude. If the antenna length is such that all the individual currents arrive at Z in such phase as to add up to zero, there will be no current through Z. At other lengths the resultant current may reach appreciable values. The lengths that give zero amplitude are those which are odd multiples of $^1/_4$ λ, beginning at $^3/_4$ λ. The response from the Y direction is greatest when the antenna is any even multiple of $^1/_2$ λ long; the higher the multiple, the smaller the response.

Directional Characteristics

Fig 22 compares the azimuthal pattern for a 5-λ long 14-MHz long-wire antenna, 70 feet high over flat ground, when it is terminated and when it is unterminated. The rearward pattern when the wire is terminated with a 600 Ω resistor is reduced about 15 dB, with a reduction in gain in the forward direction of about 2 dB.

For a shorter leg length in a terminated long-wire antenna, the reduction in forward gain is larger—more energy is radiated by a longer wire before the forward wave is absorbed in the terminating resistor. The azimuthal pat-

terns for terminated and unterminated V-beams with 2-λ legs are overlaid for comparison in **Fig 23**. With these relatively short legs the reduction in forward gain is about 3.5 dB due to the terminations, although the front-to-rear ratio approaches 20 dB for the terminated V-beam. Each leg of this terminated V-beam use a 600-Ω non-inductive resistor to ground. Each resistor would have to dissipate about one-quarter of the transmitter power. For average conductor diameters and heights above ground, the Z_{ANT} of the antenna is of the order of 500 to 600 Ω.

THE TERMINATED RHOMBIC ANTENNA

The highest development of the long-wire antenna is the *terminated rhombic*, shown schematically in **Fig 24**. It consists of four conductors joined to form a diamond, or *rhombus*. All sides of the antenna have the same length and the opposite corner angles are equal. The antenna can be considered as being made up of two V antennas placed end to end and terminated by a noninductive resistor to produce a unidirectional pattern. The terminating resistor is connected between the far ends of the two sides, and is made approximately equal to the characteristic impedance of the antenna as a unit. The rhombic may be constructed either horizontally or vertically, but is practically always constructed horizontally at frequencies below 54 MHz,

Max. Gain = 11.64 dBi
Freq = 14.0 MHz

Azimuth Plot
Elevation Angle = 10°

Fig 23—The azimuthal patterns for a shorter-leg V-beam (2-λ legs) when it is terminated (solid line) and unterminated (dashed line). With shorter legs, the terminated V-beam loses about 3.5 dB in forward gain compared to the unterminated version, while suppressing the rearward lobes as much as 20 dB.

Fig 24—The layout for a terminated rhombic antenna.

since the pole height required is considerably less. Also, horizontal polarization is equally, if not more, satisfactory at these frequencies over most types of soil.

The basic principle of combining lobes of maximum radiation from the four individual wires constituting the rhombus or diamond is the same in either the terminated type or the resonant type described earlier in this chapter.

Tilt Angle

In dealing with the terminated rhombic, it is a matter of custom to talk about the *tilt angle* (φ in Fig 24), rather than the angle of maximum radiation with respect to an individual wire. **Fig 25** shows the tilt angle as a function of the antenna leg length. The curve marked "0°" is used for a takeoff elevation angle of 0°; that is, maximum radiation in the plane of the antenna. The other curves show the proper tilt angles to use when aligning the major lobe with a desired takeoff angle. For a 5° takeoff angle, the difference in tilt angle is less than 1° for the range of lengths shown.

The broken curve marked "optimum length" shows the leg length at which maximum gain is obtained at any given takeoff angle. Increasing the leg length beyond the optimum will result in less gain, and for that reason the curves do not extend beyond the optimum length. Note that the

optimum length becomes greater as the desired takeoff angle decreases. Leg lengths over 6 λ are not recommended because the directive pattern becomes so sharp that the antenna performance is highly variable with small changes in the angle, both horizontal and vertical, at which an incoming wave reaches the antenna. Since these angles vary to some extent in ionospheric propagation, it does not pay to attempt to try for too great a degree of directivity.

Multiband Design

When a rhombic antenna is to be used over a considerable frequency range, a compromise must be made in the tilt angle. **Fig 26** gives the design dimensions of a suitable compromise for a rhombic that covers the 14 to 30 MHz range well. **Fig 27** shows the azimuth and elevation patterns for this antenna at 14 MHz, at a height of 70 feet over flat ground. The comparison antenna in this case is a 4-element Yagi on a 26-foot boom, also 70 feet above flat ground. The rhombic has about 2.2 dB more gain, but its azimuthal pattern is 17.2° wide at the 3 dB points, and only 26° at the –20 dB points! On the other hand, the Yagi has a 3-dB beamwidth of 63°, making it far easier to aim at a distant geographic location. Fig 27B shows the elevation-plane patterns for the same antennas above. As usual, the peak angle for either horizontally polarized antenna is determined mainly by the height above ground.

The peak gain of a terminated rhombic is less than that of an unterminated resonant rhombic. For the rhombic of Fig 26, the reduction in peak gain is about 1.5 dB. **Fig 28** compares the azimuthal patterns for this rhombic with and without an 800-Ω termination.

Fig 29 shows the azimuth and elevation patterns for the terminated rhombic of Fig 26 when it is operated at 28 MHz. The main lobe becomes very narrow, at 6.9° at the 3-dB points. However, this is partially compensated for by the appearance of two sidelobes each side of the main beam. These tend to spread out the main pattern some. Again, a 4-element Yagi at the same height is used for comparison.

Fig 25—Rhombic-antenna design chart. For any given leg length, the curves show the proper tilt angle to give maximum radiation at the selected takeoff angle. The broken curve marked "optimum length" shows the leg length that gives the maximum possible output at the selected takeoff angle. The optimum length as given by the curves should be multiplied by 0.74 to obtain the leg length for which the takeoff angle and main lobe are aligned.

Fig 26—Rhombic antenna dimensions for a compromise design between 14- and 28-MHz requirements, as discussed in the text. The leg length is 6 λ at 28 MHz, 3 λ at 14 MHz.

Termination

Although the difference in the gain is relatively small with terminated or unterminated rhombics of comparable design, the terminated antenna has the advantage that over a wide frequency range it presents an essentially resistive and constant load to the transmitter. In a sense, the power dissipated in the terminating resistor can be considered power that would have been radiated in the other direction had the resistor not been there. Therefore, the fact that some of the power (about one-third) is used up in heating the resistor does not mean that much actual loss in the desired direction.

The characteristic impedance of an ordinary rhombic antenna, looking into the input end, is in the order of 700 to 800 Ω when properly terminated in a resistance at the far end. The terminating resistance required to bring about the matching condition usually is slightly higher than the input impedance because of the loss of energy through radiation by the time the far end is reached. The correct value usually will be found to be of the order of 800 Ω, and should be determined experimentally if the flattest possible antenna is desired. However, for average work a noninductive resistance of 800 Ω can be used with the assurance that the operation will not be far from optimum.

The terminating resistor must be practically a pure resistance at the operating frequencies; that is, its inductance and capacitance should be negligible. Ordinary wire-wound resistors are not suitable because they have far too much inductance and distributed capacitance. Small carbon resistors have satisfactory electrical characteristics but will not dissipate more than a few watts and so cannot be used, except when the transmitter power does not exceed 10 or 20 watts or when the antenna is to be used for reception only. The special resistors designed either for use as dummy antennas or for terminating rhombic antennas should be used in other cases. To allow a factor of safety, the total rated power dissipation of the resistor or resistors should be equal to half the power output of the transmitter.

To reduce the effects of stray capacitance it is desirable to use several units, say three, in series even when one alone will safely dissipate the power. The two end units should be identical and each should have one fourth to one third the total resistance, with the center unit making up the difference. The units should be installed in a weather-

Max. Gain = 14.97 dBi
Freq = 14.0 MHz

Azimuth Plot
Elevation Angle = 10°

Max Gain = 15.92 dBi
Freq = 14.0 MHz

Elevation Plot
Azimuth Angle = 0°

Fig 27—At left, azimuthal pattern for 3-λ (at 14 MHz) terminated rhombic (solid line) shown in Fig 26, compared with 4-element 20-meter Yagi (dotted line) on a 26-foot boom and a 20-meter dipole (dashed line). All antennas are mounted 70 feet (1 λ) above flat ground. The rearward pattern of the terminated rhombic is good and the forward gain exceeds that of the Yagi, but the frontal lobe is very narrow. Above, elevation-plane pattern of terminated rhombic compared to that of a simple dipole at the same height.

Max. Gain = 16.26 dBi
Freq = 14.0 MHz

Azimuth Plot
Elevation Angle = 10°

Fig 28—Comparison of azimuthal patterns for terminated (solid line) and unterminated (dashed line) rhombic antennas, using same dimensions as Fig 26 at a frequency of 14 MHz. The gain tradeoff is about 1.5 dB in return for the superior rearward pattern of the terminated antenna.

proof housing at the end of the antenna to protect them and to permit mounting without mechanical strain. The connecting leads should be short so that little extraneous inductance is introduced.

Alternatively, the terminating resistance may be placed at the end of an 800-Ω line connected to the end of the antenna. This will permit placing the resistors and their housing at a point convenient for adjustment rather than at the top of the pole. Resistance wire may be used for this line, so that a portion of the power will be dissipated before it reaches the resistive termination, thus permitting the use of lower wattage lumped resistors.

Multiwire Rhombics

The input impedance of a rhombic antenna constructed as in Fig 26 is not quite constant as the frequency is varied. This is because the varying separation between the wires causes the characteristic impedance of the antenna to vary along its length. The variation in Z_{ANT} can be minimized by a conductor arrangement that increases the capacitance per unit length in proportion to the separation between the wires.

The method of accomplishing this is shown in **Fig 30**. Three conductors are used, joined together at the ends but with increasing separation as the junction between legs is approached. For HF work the spacing between the wires at the center is 3 to 4 feet, which is similar to that used in commercial installations using legs several wavelengths long. Since all three wires should have the same length, the top and bottom wires should be slightly farther from the support than the middle wire. Using three wires in this way reduces the Z_{ANT} of the antenna to approximately 600 Ω, thus providing a better match for practical open-wire line, in addition to smoothing out the impedance variation over the frequency range.

A similar effect (although not quite as favorable) is obtained by using two wires instead of three. The 3-wire system has been found to increase the gain of the

Max. Gain = 16.82 dBi
Freq = 28.0 MHz **(A)**
Azimuth Plot
Elevation Angle = 6°

Max Gain = 15.92 dBi
Freq = 14.0 MHz
Elevation Plot
Azimuth Angle = 0°
Rombic
(B)

Fig 29—At A, the azimuthal pattern for the same terminated antenna in Fig 26, but now at 28 MHz compared to a 4-element 10-meter Yagi. At B, the elevation-plane pattern comparison for these antennas.

infinite front-to-back ratio can be obtained only at frequencies for which the leg length is an odd multiple of a quarter wavelength. The front-to-back ratio is smallest at frequencies for which the leg length is a multiple of a half wavelength.

When the leg length is not an odd multiple of a quarter wave at the frequency under consideration, the front-to-back ratio can be made very high by decreasing the value of terminating resistance slightly. This permits a small reflection from the far end of the antenna, which cancels out the residual response at the input end. With large antennas, the front-to-back ratio may be made very large over the whole frequency range by experimental adjustment of the terminating resistance. Modification of the terminating resistance can result in a splitting of the back null into two nulls, one on either side of a small lobe in the back direction. Changes in the value of terminating resistance thus permit steering the back null over a small horizontal range so that signals coming from a particular spot not exactly to the rear of the antenna may be minimized.

Fig 30—Three-wire rhombic antenna. Use of multiple wires improves the impedance characteristic of a terminated rhombic and increases the gain somewhat.

antenna by about 1 dB over that of a single-conductor version.

Front-to-Back Ratio

It is theoretically possible to obtain an infinite front-to-back ratio with a terminated rhombic antenna, and in practice very large values can be had. However, when the antenna is terminated in its characteristic impedance, the

Methods of Feed

If the broad frequency characteristic of the terminated rhombic antenna is to be utilized fully, the feeder system must be similarly broadbanded. Open-wire transmission line of the same characteristic impedance as that shown at the antenna input terminals (approximately 700 to 800 Ω) may be used. Data for the construction of such lines is given in Chapter 24. While the usual matching stub can be used to provide an impedance transformation to more satisfactory line impedances, this limits the operation of the antenna to a comparatively narrow range of frequencies centering about that for which the stub is adjusted. Probably a more satisfactory arrangement would be to use a coaxial transmission line and a broadband transformer balun at the antenna feed point.

Receiving Wave Antennas

Perhaps the best known type of wave antenna is the *Beverage*. Many 160-meter enthusiasts have used Beverage antennas to enhance the signal-to-noise ratio while attempting to extract weak signals from the often high levels of atmospheric noise and interference on the low bands. Alternative antenna systems have been developed and used over the years, such as loops and long spans of unterminated wire on or slightly above the ground, but the Beverage antenna seems to be the best for 160-meter weak-signal reception. The information in this section was prepared originally by Rus Healy, K2UA (ex-NJ2L).

THE BEVERAGE ANTENNA

A Beverage is simply a directional wire antenna, at least one wavelength long, supported along its length at a fairly low height and terminated at the far end in its characteristic impedance. This antenna is shown in **Fig 31A**. It takes its name from its inventor, Harold Beverage, W2BML.

Many amateurs choose to use a single-wire Beverage because they are easy to install and they work well. The drawback is that Beverages are physically long and they do require that you have the necessary amount of real estate to install them. Sometimes, a neighbor will allow you to put up a temporary Beverage for a particular contest or DXpedition on his land, particularly during the winter months.

Beverage antennas can be useful into the HF range, but they are most effective at lower frequencies, mainly on 160 through 40 meters. The antenna is responsive mostly to low-angle incoming waves that maintain a constant (vertical) polarization. These conditions are nearly always satisfied on 160 meters, and most of the time on 80 meters. As the frequency is increased, however, the polarization and arrival angles are less and less constant and favorable, making Beverages less effective at these frequencies. Many amateurs have, however, reported excellent performance from Beverage antennas at frequencies as high as 14 MHz, especially when rain or snow (precipitation) static prevents good reception on the Yagi or dipole transmitting antennas used on the higher frequencies.

Beverage Theory

The Beverage antenna acts like a long transmission line with one lossy conductor (the earth), and one good conductor (the wire). Beverages have excellent directivity if erected properly, but they are quite inefficient because they are mounted close to the ground. This is in contrast with the terminated long-wire antennas described earlier, which are typically mounted high off the ground. Beverage antennas are not suitable for use as transmitting antennas.

Because the Beverage is a traveling wave, terminated antenna, it has no standing waves resulting from radio

signals. As a wave strikes the end of the Beverage from the desired direction, the wave induces voltages along the antenna and continues traveling in space as well. Fig 31B shows part of a wave on the antenna resulting from a desired signal. This diagram also shows the tilt of the wave. The signal induces equal voltages in both directions. The resulting currents are equal and travel in both directions; the component traveling toward the termination end moves *against* the wave and thus builds down to a very low level at the termination end. Any residual signal resulting from this direction of current flow will be absorbed in the termination (if the termination is equal to the antenna impedance). The component of the signal flowing in the other direction, as we will see, becomes a key part of the received signal.

As the wave travels along the wire, the wave in space travels at approximately the same velocity. (There is some phase delay in the wire, as we shall see.) At any given point in time, the wave traveling along in space induces a voltage in the wire in addition to the wave already travel-

Fig 31—At A, a simple one-wire Beverage antenna with a variable termination impedance and a matching 9:1 autotransformer for the receiver impedance. At B, a portion of a wave from the desired direction is shown traveling down the antenna wire. Its tilt angle and effective takeoff angle are also shown. At C, a situation analogous to the action of a Beverage on an incoming wave is shown. See text for discussion.

ing on the wire (voltages already induced by the wave). Because these two waves are nearly in phase, the voltages add and build toward a maximum at the receiver end of the antenna.

This process can be likened to a series of signal generators lined up on the wire, with phase differences corresponding to their respective spacings on the wire (Fig 31C). At the receiver end, a maximum voltage is produced by these voltages adding in phase. For example, the wave component induced at the receiver end of the antenna will be in phase (at the receiver end) with a component of the same wave induced, say, 270° (or any other distance) down the antenna, after it travels to the receiver end.

In practice, there is some phase shift of the wave on the wire with respect to the wave in space. This phase shift results from the velocity factor of the antenna. (As with any transmission line, the signal velocity on the Beverage is somewhat less than in free space.) Velocity of propagation on a Beverage is typically between 85 and 98% of that in free space. As antenna height is increased to a certain optimum height (which is about 10 feet for 160 meters), the velocity factor increases. Beyond this

height, only minimal improvement is afforded, as shown in **Fig 32**. These curves are the result of experimental work done in 1922 by RCA, and reported in a *QST* article (November 1922) entitled "The Wave Antenna for 200-Meter Reception," by H. H. Beverage. The curve for 160 meters was extrapolated from the other curves.

Phase shift (per wavelength) is shown as a function of velocity factor in **Fig 33**, and is given by:

$$\theta = 360 \left(\frac{100}{k} - 1 \right) \qquad \text{(Eq 2)}$$

where k = velocity factor of the antenna in percent.

The signals present on and around a Beverage antenna are shown graphically in A through D of **Fig 34**. These curves show relative voltage levels over a number of periods of the wave in space and their relative effects in terms of the total signal at the receiver end of the antenna.

Fig 32—Signal velocity on a Beverage increases with height above ground, and reaches a practical maximum at about 10 feet. Improvement is minimal above this height. (The velocity of light is 100%.)

Fig 33—This curve shows phase shift (per wavelength) as a function of velocity factor on a Beverage antenna. Once the phase shift for the antenna goes beyond 90°, the gain drops off from its peak value, and any increase in antenna length will decrease gain.

Signal
Strength

(A)

Voltage Induced
in Wire (P.U. Length)
by All Signals

(B)

Voltage Induced
by an Undesired
Signal from Rear

(C)

Voltage Induced
by
Desired Signal

(D)

Fig 34—These curves show the voltages that appear in a Beverage antenna over a period of several cycles of the wave. Signal strength (at A) is constant over the length of the antenna during this period, as is voltage induced per unit length in the wire (at B). (The voltage induced in any section of the antenna is the same as the voltage induced in any other section of the same size, over the same period of time.) At C, the voltages induced by an undesired signal from the rearward direction add in phase and build to a maximum at the termination end, where they are dissipated in the termination (if $Z_{term} = Z_0$). The voltages resulting from a desired signal are shown at D. The wave on the wire travels closely with the wave in space, and the voltages resulting add in phase to a maximum at the receiver end of the antenna.

Performance in Other Directions

The performance of a Beverage antenna in directions other than the favored one is quite different than previously discussed. Take, for instance, the case of a signal arriving perpendicular to the wire (90° either side of the favored direction). In this case, the wave induces voltages along the wire that are essentially *in phase*, so that they arrive at the receiver end more or less out of phase, and thus cancel. (This can be likened to a series of signal generators lined up along the antenna as before, but having no progressive phase differences.)

As a result of this cancellation, Beverages exhibit deep nulls off the sides. Some minor sidelobes will exist,

as with other long-wire antennas, and will increase in number with the length of the antenna.

In the case of a signal arriving from the rear of the antenna, the behavior of the antenna is very similar to its performance in the favored direction. The major difference is that the signal from the rear adds in phase at the termination end and is absorbed by the termination impedance. **Fig 35** compares the azimuth and elevation patterns for a 2-λ (1062 foot) and a 1-λ (531 foot) Beverage at 1.83 MHz. The wire is mounted 8 feet above flat ground (to keep it above deer antlers and away from humans too) and is terminated with a 500-Ω resistor in each case, although the exact value of the terminating resistance is not very critical. The ground constants assumed in this computer model are conductivity of 5 mS/m and a dielectric constant of 13. Beverage dielectric performance tends to decrease as the ground becomes better. Beverages operated over saltwater do not work as well as they do over poor ground.

For most effective operation, the Beverage should be terminated in an impedance equal to the characteristic impedance Z_{ANT} of the antenna. For maximum signal transfer to the receiver you should also match the receiver's input impedance to the antenna. If the termination impedance is not equal to the characteristic impedance of the antenna, some part of the signal from the rear will be reflected back toward the receiver end of the antenna.

If the termination impedance is merely an open circuit (no terminating resistor), total reflection will result and the antenna will exhibit a bidirectional pattern (still with very deep nulls off the sides). An unterminated Beverage will not have the same response to signals in the rearward direction as it exhibits to signals in the forward direction because of attenuation and reradiation of part of the reflected wave as it travels back toward the receiver end. **Fig 36** compares the response from two 2-λ Beverages, one terminated and the other unterminated. Just like a terminated long-wire transmitting antenna (which is mounted higher off the ground than a Beverage, which is meant only for receiving), the terminated Beverage has a reduced forward lobe compared to its unterminated sibling. The unterminated Beverage exhibits about a 5 dB front-to-back ratio for this length because of the radiation and wire and ground losses that occur before the forward wave gets to the end of the wire.

If the termination is between the extremes (open circuit and perfect termination in Z_{ANT}), the peak direction and intensity of signals off the rear of the Beverage will change. As a result, an adjustable reactive termination can be employed to *steer* the nulls to the rear of the antenna (see **Fig 37**). This can be of great help in eliminating a local interfering signal from a rearward direction (typically 30° to 40° either side of the back direction). Such a scheme doesn't help much for interfering skywave signals because of variations encountered in the ionosphere that constantly shift polarity, amplitude, phase and

Max. Gain = 8.52 dBi
Freq = 1.83 MHz
(A)
Azimuth Plot
Elevation Angle = 10°

Max Gain = 6.57 dBi
Freq = 1.83 MHz
Elevation Plot
Azimuth Angle = 0°
(B)

Fig 35—At A, azimuthal patterns of a 2-λ (solid line) and a 1-λ (dashed line) Beverage antenna, terminated with 550-Ω resistor at 1.83 MHz, at an elevation angle of 10°. The rearward pattern around 180° is more than 20 dB down from the front lobe for each antenna. At B, the elevation-plane patterns. Note the rejection of very high-angle signals near 90°.

Max. Gain = 7.88 dBi
Freq = 1.83 MHz
Azimuth Plot
Elevation Angle = 10°

Fig 36—Comparing the azimuthal patterns for a 2-λ Beverage, terminated (solid line) and unterminated (dashed line).

incoming elevation angles.

To determine the appropriate value for a terminating resistor, you need to know the characteristic impedance (surge impedance), Z_{ANT}, of the Beverage. It is interesting to note that Z_{ANT} is not a function of the length, just like a transmission line.

$$Z_{ANT} = 138 \times \log\left(\frac{4h}{d}\right) \qquad \text{(Eq 3)}$$

where

Z_{ANT} = characteristic impedance of the Beverage = terminating resistance needed
h = wire height above ground
d = wire diameter (in the same units as h)

Another aspect of terminating the Beverage is the quality of the RF ground used for the termination. For most types of soil a ground rod is sufficient, since the optimum value for the termination resistance is in the range of 400 to 600 Ω for typical Beverages and the ground-loss resistance is in series with this. Even if the ground-loss resistance at the termination point is as high as 40 or 50 Ω, it still is not an appreciable fraction of the overall terminating resistance. For soil with very poor conductivity, however, (such as sand or rock) you can achieve a better ground termination by laying radial wires on the ground at both the receiver and termination ends. These wires need not be resonant quarter-wave in length, since the ground detunes them anyway. Like the ground counterpoise for a vertical antenna, a number of short radials is better than a few long ones. Some amateurs use chicken-wire ground screens for their ground terminations.

As with many other antennas, improved directivity and gain can be achieved by lengthening the antenna and by arranging several antennas into an array. One item that must be kept in mind is that by virtue of the velocity factor of the antenna, there is some phase shift of the wave on the antenna with respect to the wave in space. Because of this phase shift, although the directivity will continue to sharpen with increased length, there will be some optimum length at which the gain of the antenna will peak. Beyond this

Long-Wire and Traveling-Wave Antennas   13-19

Fig 37—A two-wire Beverage antenna that has provisions for direction switching and null steering in the rear quadrant. Performance improves with height to a point, and is optimum for 1.8-MHz operation at about 10 to 12 feet. Parts identifications are for text reference.

length, the current increments arriving at the receiver end of the antenna will no longer be in phase, and will not add to produce a maximum signal at the receiver end. This optimum length is a function of velocity factor and frequency, and is given by:

$$L = \frac{\lambda}{4\left(\dfrac{100}{k} - 1\right)}$$ (Eq 4)

where

    L = maximum effective length
    λ = signal wavelength in free space (same units as L)
    k = velocity factor of the antenna in percent

Because velocity factor increases with height (to a point, as mentioned earlier), optimum length is somewhat longer if the antenna height is increased. The maximum effective length also increases with the number of wires in the antenna system. For example, for a two-wire Beverage like the bidirectional version shown in Fig 37, the maximum effective length is about 20% longer than the single-wire version. A typical length for a single-wire 1.8-MHz Beverage (made of #16 wire and erected 10 feet above ground) is about 1200 feet.

Feed-Point Transformers for Single-Wire Beverages

Matching transformer T1 in Fig 31 is easily constructed. Small toroidal ferrite cores are best for this application, with those of high permeability (μ_i = 125 to 5000) being the easiest to wind (requiring fewest turns) and having the best high-frequency response (because few turns are used). Trifilar-wound autotransformers are most convenient.

Most users are not concerned with a small amount of SWR on the transmission line feeding their Beverages. For example, let us assume that the Z_{ANT} of a particular Beverage is 525 Ω and the terminating resistance is made equal to that value. If a standard 3:1 turns-ratio autotrans-

former is used at the input end of the antenna, the nominal impedance transformation 50 $\Omega \times 3^2$ = 450 Ω. This leads to the terminology often used for this transformer as a *9:1 transformer*, referring to its impedance transformation. The resulting SWR on the feed line going back to the receiver would be 525/450 = 1.27:1, not enough to be concerned about. For a Z_{ANT} of 600 Ω, the SWR is 600/450 = 1.33:1, again not a matter of concern.

Hence, most Beverage users use standard 9:1 (450:50 Ω) autotransformers. You can make a matching transformer suitable for use from 160 to 40 meters using eight trifilar turns of #24 enameled wire wound over a stack of two Amidon FT-50-75 or two MN8-CX cores. See **Fig 38**.

Make your own trifilar cable bundle by placing three 3-foot lengths of the #24 wire side-by-side and twisting them in a hand drill so that there is a uniform twist about one twist-per-inch. This holds the three wires together in a bundle that can be passed through the two stacked cores, rather like threading a needle. Remember that each time you put the bundle through the center of the cores counts as one turn.

After you finish winding, cut the individual wires to leave about ³/₄-inch leads, sand off the enamel insulation and tin the wires with a soldering iron. Identify the individual wires with an ohmmeter and then connect them together following Fig 38. Coat the transformer with Q-dope (liquid polystyrene) to finalize the transformer. White glue will work also. See Chapters 25 and 26 and *The ARRL Handbook* for more information on winding toroidal transformers or see Chapter 7 (Special Receiving Antennas) of *ON4UN's Low-Band DXing* book.

The Two-Wire Beverage

The two-wire antenna shown in Fig 37 has the major advantage of having signals from both directions available at the receiver at the flip of a switch between J1 and J2. Also, because there are two wires in the system (equal amounts of signal voltage are induced in both wires), greater signal voltages will be produced.

Fig 38—Constructing the feed-point transformer for a single-wire Beverage. See text for details.

A signal from the left direction in Fig 37 induces equal voltages in both wires, and equal in-phase currents flow as a result. The *reflection transformer* (T3 at the right-hand end of the antenna) then inverts the phase of these signals and reflects them back down the antenna toward the receiver, using the antenna wires as a balanced open-wire transmission line. This signal is then transformed by T1 down to the input impedance of the receiver (50 Ω) at J1.

Signals traveling from right to left also induce equal voltages in each wire, and they travel in phase toward the receiver end, through T1, and into T2. Signals from this direction are available at J2.

T1 and T2 are standard 9:1 wideband transformers capable of operating from 1.8 to at least 10 MHz. Like any two parallel wires making up a transmission line, the two-wire Beverage has a certain characteristic impedance—we'll call it Z_1 here—depending on the spacing between the two wires and the insulation between them. T3 transforms the terminating resistance needed at the end of the line to Z_1. Keep in mind that this terminating resistance is equal to the characteristic impedance Z_{ANT} of the Beverage—that is, the impedance of the parallel wires over their images in the ground below. For example, if Z_1 of the Beverage wire is 300 Ω (that is, you used TV twin-lead for the two Beverage wires), T3 must transform the balanced 300 Ω to the unbalanced 500 Ω Z_{ANT} impedance used to terminate the Beverage.

The design and construction of the reflection transformer used in a two-wire Beverage is more demanding than that for the straightforward matching transformer T1 because the exact value of terminating impedance is more critical for good F/B. See Chapter 7 (Special Receiving Antennas) in *ON4UN's Low-Band DXing* for details on winding the

reflection transformers for a two-wire Beverage.

Another convenient feature of the two-wire Beverage is the ability to steer the nulls off either end of the antenna while receiving in the opposite direction. For instance, if the series RLC network shown at J2 is adjusted while the receiver is connected to J1, signals can be received from the left direction while interference coming from the right can be partially or completely nulled. The nulls can be steered over a 60° (or more) area off the right-hand end of the antenna. The same null-steering capability exists in the opposite direction with the receiver connected at J2 and the termination connected at J1.

The two-wire Beverage is typically erected at the same height as a single-wire version. The two wires are at the same height and are spaced uniformly—typically 12 to 18 inches apart for discrete wires. Some amateurs construct two-wire Beverages using "window" ladder-line, twisting the line about three twists per foot for mechanical and electrical stability in the wind.

The characteristic impedance Z_{ANT} of a Beverage made using two discrete wires with air insulation between them depends on the wire size, spacing and height and is given by:

$$Z_{ANT} = \frac{69}{\sqrt{\varepsilon}} \times \log\left[\frac{4h}{d}\sqrt{1+\left(\frac{2h}{S}\right)^2}\right] \qquad \text{(Eq 5)}$$

where

Z_{ANT} = Beverage impedance = desired terminating resistance
S = wire spacing
h = height above ground
d = wire diameter (in same units as S and h)
ε = 2.71828

Beverages in Echelon

The pattern of a Beverage receiving antenna is dependent on the terminating resistance used for a particular antenna, as was demonstrated at the extremes by Fig 36. This compared the patterns for a terminated and an unterminated Beverage. The pattern of even a poorly terminated Beverage can be significantly improved by the addition of a second Beverage. The additional Beverage is installed so that it is operated *in echelon*, a word deriving from the fact that the two wires look like the parallel rungs on a ladder. For a practial 160- and 80-meter setup the second Beverage wire is parallel to the first Beverage, spaced from it by about 5 meters, and also staggered 30 meters ahead. See **Fig 38**.

The forward Beverage is fed with a phase difference of +125° such that the total phase, including that due to the forward staggering, is 180°. This forms the equivalent of an end-fire array fed out-of-phase, but it takes advantage of the natural directivity of each Beverage. **Fig 39** compares the pattern of a single 1-λ 160-meter Beverage that is sloppily terminated with two Beverages fed in echelon. The

Beverages in echelon gives a modest additional gain of almost 2 dB. But where the two Beverages in echelon really shine is how they cleans up the rearward pattern—from an average about 15 dB for the single Beverage to more than 25 dB for the two Beverages.

Even at a spacing of 5 meters, there is very little mutual coupling between the two Beverage wires because of their inherently small radiation resistance when they are mounted low above lossy ground. If you adjust for a low SWR (using proper transformers to match the feed-line coaxes), the phase difference will depend solely on the difference in length of the two coaxes feeding the Beverage wires. **Fig 40** shows a wideband feed system designed by Tom Rauch, W8JI, as a "cross-fire" feed system. The 180° wideband phase-inverting transformer allows the system to work on two bands, say 160 and 80 meters. See Chapter 7, Receiving Antennas, in *ON4UN's Low-Band DXing* book, 4th Edition for transformer details.

Practical Considerations

Even though Beverage antennas have excellent directive patterns if terminated properly, gain never exceeds about −3 dBi in most practical installations. However, the directivity that the Beverage provides results in a much higher signal-to-noise ratio for signals in the desired direction than almost any other real-world antenna used at low frequencies.

A typical situation might be a station located in the US Northeast (W1), trying to receive Topband signals from Europe to the northeast, while thunderstorms behind him in the US Southeast (W4) are creating huge static crashes. Instead of listening to an S7 signal with 10-dB over S9 noise and interference on a vertical, the directivity of a Beverage will typically allow you to copy the same signal at perhaps S5 with only S3 (or lower) noise and interference. This is certainly a worthwhile improvement. However, if you are in the middle of a thunderstorm, or if there is a thunderstorm in the direction from which you are trying to receive a signal, no Beverage is going to help you!

There are a few basic principles that must be kept in mind when erecting Beverage antennas if optimum performance is to be realized.

1) Plan the installation thoroughly, including choosing an antenna length consistent with the optimum length values discussed earlier.
2) Keep the antenna as straight and as nearly level as possible over its entire run. Avoid following the terrain under the antenna too closely—keep the antenna level with the average terrain.
3) Minimize the lengths of vertical downleads at the ends of the antenna. Their effect is detrimental to the directive pattern of the antenna. It is best to slope the antenna wire from ground level to its final height (over a distance of 50 feet or so) at the feed-point end. Similar action should be taken at the termination end. Be sure to seal the transformers against weather.

Fig 39—Layout of two 160-meter 1-λ long Beverages in echelon, spaced 5 meters apart, with 30 meter forward stagger. The upper antenna has a 125° phase shift in its feed system.

Fig 40—Azimuth pattern at 10° takeoff angle for single Beverage (dashed line) and two Beverages in an echelon end-fire array. The rearward pattern is considerably cleaner on the echelon. Thus, two closely spaced, short Beverages can give considerable improvement over a single short Beverage.

Fig 41—Two ways of feeding the two-Beverage echelon array in Fig 39. On the left, a feed system good for one frequency; on the right, a "cross-fire" feed system good for 1.8 and 3.6 MHz. For this system we want a phase shift due to the coax length of +116° at the back Beverage A. The angle φ is thus 180°–116° = 64° long on 160 meters. In the system on the right, a 64° length on 160 meters becomes 128° long on 80 meters. So with the phase-inverting transformer the net phase shift becomes 53° on 80 meters, a reasonable compromise. (*Courtesy W8JI and ON4UN.*)

LBDX04_07-013

4) Use a noninductive resistor for terminating a single-wire Beverage. If you live in an area where lightning storms are common, use 2-W terminating resistors, which can survive surges due to nearby lightning strikes.

5) Use high-quality insulators for the Beverage wire where it comes into contact with the supports. Plastic insulators designed for electric fences are inexpensive and effective.

6) Keep the Beverage away from parallel conductors such as electric power and telephone lines for a distance of at least 200 feet. Perpendicular conductors, even other Beverages, may be crossed with relatively little interaction, but do not cross any conductors that may pose a safety hazard.

7) Run the coaxial feed line to the Beverage so that it is not directly under the span of the wire. This prevents common-mode currents from appearing on the shield of the coax. It may be necessary to use a ferrite-bead choke on the feed line if you find that the feed line itself picks up signals when it is temporarily disconnected from the Beverage. See Chapter 26 for details on common-mode chokes.

8) If you use elevated radials in your transmitting antenna system, keep your Beverage feed lines well away from them to avoid stray pickup that will ruin the Beverage's directivity.

BIBLIOGRAPHY

Source material and more extended discussion of topics covered in this chapter can be found in the references given below.

A. Bailey, S. W. Dean and W. T. Wintringham, "The Receiving System for Long-Wave Transatlantic Radio Telephony," *The Bell System Technical Journal*, Apr 1929.

J. S. Belrose, "Beverage Antennas for Amateur Communications," Technical Correspondence, *QST*, Sep 1981.

H. H. Beverage, "Antennas," *RCA Review*, Jul 1939.

H. H. Beverage and D. DeMaw, "The Classic Beverage Antenna Revisited," *QST* , Jan 1982.

B. Boothe, "Weak-Signal Reception on 160—Some Antenna Notes," *QST*, Jun 1977.

E. Bruce, "Developments in Short-Wave Directive Antennas," *Proc IRE*, Aug 1931.

E. Bruce, A. C. Beck and L. R. Lowry, "Horizontal Rhombic Antennas," *Proc IRE*, Jan 1935.

P. S. Carter, C. W. Hansel and N. E. Lindenblad, "Development of Directive Transmitting Antennas by R.C.A. Communications," *Proc IRE*, Oct 1931.

J. Devoldere, *Low-Band DXing* (Newington: ARRL, 1987).

J. Devoldere, *ON4UN's Low-Band DXing* (Newington: ARRL, 1999). See in particular Chapter 7, "Special Receiving Antennas," for many practical details on Beverage antennas.

A. E. Harper, *Rhombic Antenna Design* (New York: D. Van Nostrand Co, Inc).

E. A. Laport, "Design Data for Horizontal Rhombic Antennas," *RCA Review*, Mar 1952.

G. M. Miller, *Modern Electronic Communication* (Englewood Cliffs, NJ: Prentice Hall, 1983).

V. A. Misek, *The Beverage Antenna Handbook* (Wason Rd., Hudson, NH: W1WCR, 1977).

F. E. Terman, *Radio Engineering*, Second Edition (New York: McGraw-Hill, 1937).

Direction Finding Antennas

The use of radio for direction-finding purposes (RDF) is almost as old as its application for communications. Radio amateurs have learned RDF techniques and found much satisfaction by participating in hidden-transmitter hunts. Other hams have discovered RDF through an interest in boating or aviation, where radio direction finding is used for navigation and emergency location systems.

In many countries of the world, the hunting of hidden amateur transmitters takes on the atmosphere of a sport, as participants wearing jogging togs or track suits dash toward the area where they believe the transmitter is located. The sport is variously known as *fox hunting*, *bunny hunting*, ARDF (Amateur Radio direction finding) or simply transmitter hunting. In North America, most hunting of hidden transmitters is conducted from automobiles, although hunts on foot are gaining popularity.

There are less pleasant RDF applications as well, such as tracking down noise sources or illegal operators from unidentified stations. Jammers of repeaters, traffic nets and other amateur operations can be located with RDF equipment. Or sometimes a stolen amateur rig will be operated by a person who is not familiar with Amateur Radio, and by being lured into making repeated transmissions, the operator unsuspectingly permits himself to be located with RDF equipment. The ability of certain RDF antennas to reject signals from selected directions has also been used to advantage in reducing noise and interference. Through APRS, radio navigation is becoming a popular application of RDF. The locating of downed aircraft is another, and one in which amateurs often lend their skills. Indeed, there are many useful applications for RDF.

Although sophisticated and complex equipment pushing the state of the art has been developed for use by governments and commercial enterprises, relatively simple equipment can be built at home to offer the Radio

Amateur an opportunity to RDF. This chapter deals with antennas suitable for that purpose.

RDF by Triangulation

It is impossible, using amateur techniques, to pinpoint the whereabouts of a transmitter from a single receiving location. With a directional antenna you can determine the direction of a signal source, but not how far away it is. To find the distance, you can then travel in the determined direction until you discover the transmitter location. However, that technique can be time consuming and often does not work very well.

A preferred technique is to take at least one additional direction measurement from a second receiving location. Then use a map of the area and plot the bearing or direction measurements as straight lines from points on the map representing the two locations. The approximate location of the transmitter will be indicated by the point where the two bearing lines cross. Even better results can be obtained by taking direction measurements from three locations and using the mapping technique just described. Because absolutely precise bearing measurements are difficult to obtain in practice, the three lines will almost always cross to form a triangle on the map, rather than at a single point. The transmitter will usually be located inside the area represented by the triangle. Additional information on the technique of triangulation and much more on RDF techniques may be found in recent editions of *The ARRL Handbook*.

DIRECTION FINDING SY\STEMS

Required for any RDF system are a directive antenna and a device for detecting the radio signal. In amateur applications the signal detector is usually a transceiver and for convenience it will usually have a meter to indicate signal strength. Unmodified, commercially available portable or mobile receivers are generally quite satisfac-

tory for signal detectors. At very close ranges a simple diode detector and dc microammeter may suffice for the detector.

On the other hand, antennas used for RDF techniques are not generally the types used for normal two-way communications. Directivity is a prime requirement, and here the word *directivity* takes on a somewhat different meaning than is commonly applied to other amateur antennas. Normally we associate directivity with gain, and we think of the ideal antenna pattern as one having a long, thin main lobe. Such a pattern may be of value for coarse measurements in RDF work, but precise bearing measurements are not possible. There is always a spread of a few (or perhaps many) degrees on the *nose* of the lobe, where a shift of antenna bearing produces no detectable change in signal strength. In RDF measure-ments, it is desirable to correlate an exact bearing or compass direction with the position of the antenna. In order to do this as accurately as possible, an antenna exhibiting a *null* in its pattern is used. A null can be very sharp in directivity, to within a half degree or less.

Loop Antennas

A simple antenna for HF RDF work is a small loop tuned to resonance with a capacitor. Several factors must be considered in the design of an RDF loop. The loop must be small in circumference compared with the wavelength. In a single-turn loop, the conductor should be less than 0.08 λ long. For 28 MHz, this represents a length of less than 34 inches (a diameter of approximately 10 inches). Maximum response from the loop antenna is in the plane of the loop, with nulls exhibited at right angles to that plane.

To obtain the most accurate bearings, the loop must be balanced electrostatically with respect to ground. Otherwise, the loop will exhibit two modes of operation.

One is the mode of a true loop, while the other is that of an essentially nondirectional vertical antenna of small dimensions. This second mode is called the *antenna effect*. The voltages introduced by the two modes are seldom in phase and may add or subtract, depending upon the direction from which the wave is coming.

The theoretical true loop pattern is illustrated in **Fig 1A**. When properly balanced, the loop exhibits two nulls that are 180° apart. Thus, a single null reading with a small loop antenna will not indicate the exact direction toward the transmitter—only the line along which the transmitter lies. Ways to overcome this ambiguity are discussed later.

When the antenna effect is appreciable and the loop is tuned to resonance, the loop may exhibit little directivity, as shown in Fig 1B. However, by detuning the loop to shift the phasing, a pattern similar to 1C may be obtained. Although this pattern is not symmetrical, it does exhibit a null. Even so, the null may not be as sharp as that obtained with a loop that is well balanced, and it may not be at exact right angles to the plane of the loop.

By suitable detuning, the unidirectional cardioid pattern of Fig 1D may be approached. This adjustment is sometimes used in RDF work to obtain a unidirectional bearing, although there is no complete null in the pattern. A cardioid pattern can also be obtained with a small loop antenna by adding a *sensing element*. Sensing elements are discussed in a later section of this chapter.

An electrostatic balance can be obtained by shielding the loop, as **Fig 2** shows. The shield is represented by the broken lines in the drawing, and eliminates the antenna effect. The response of a well-constructed shielded loop is quite close to the ideal pattern of Fig 1A.

Fig 1—Small-loop field patterns with varying amounts of antenna effect—the undesired response of the loop acting merely as a mass of metal connected to the receiver antenna terminals. The straight lines show the plane of the loop.

Fig 2—Shielded loop for direction finding. The ends of the shielding turn are not connected, to prevent shielding the loop from magnetic fields. The shield is effective against electric fields.

Fig 3—Small loop consisting of several turns of wire. The total conductor length is very much less than a wavelength. Maximum response is in the plane of the loop.

For the low-frequency amateur bands, single-turn loops of convenient physical size for portability are generally found to be unsatisfactory for RDF work. Therefore, multiturn loops are generally used instead. Such a loop is shown in **Fig 3**. This loop may also be shielded, and if the total conductor length remains below 0.08 λ, the directional pattern is that of Fig 1A. A sensing element may also be used with a multiturn loop.

Loop Circuits and Criteria

No single word describes a direction-finding loop of high performance better than *symmetry*. To obtain an undistorted response pattern from this type of antenna, you must build it in the most symmetrical manner possible. The next key word is *balance*. The better the electrical balance, the deeper the loop null and the sharper the maxima.

The physical size of the loop for 7 MHz and below is not of major consequence. A 4-foot diameter loop will exhibit the same electrical characteristics as one which is only an inch or two in diameter. The smaller the loop, however, the lower its efficiency. This is because its aperture samples a smaller section of the wave front. Thus, if you use loops that are very small in terms of a wavelength, you will need preamplifiers to compensate for the reduced efficiency.

An important point to keep in mind about a small loop antenna oriented in a vertical plane is that it is vertically polarized. It should be fed at the bottom for the best null response. Feeding it at one side, rather than at the bottom, will not alter the polarization and will only degrade performance. To obtain horizontal polarization from a small loop, it must be oriented in a horizontal plane, parallel to the earth. In this position the loop response is essentially omnidirectional.

The earliest loop antennas were of the *frame antenna* variety. These were unshielded antennas built on a wooden frame in a rectangular format. The loop conductor could be a single turn of wire (on the larger units) or several turns if the frame was small. Later, shielded versions of the frame antenna became popular, providing electrostatic shielding—an aid to noise reduction from such sources as precipitation static.

Ferrite Rod Antennas

With advances in technology, magnetic-core loop antennas came into use. Their advantage was reduced size, and this appealed especially to the designers of aircraft and portable radios. Most of these antennas contain ferrite bars or cylinders, which provide high inductance and Q with a relatively small number of coil turns.

Magnetic-core antennas consist essentially of turns of wire around a ferrite rod. They are also known as *loopstick* antennas. Probably the best-known example of this type of antenna is that used in small portable AM broadcast receivers. Because of their reduced-size advantage, ferrite-rod antennas are used almost exclusively for portable work at frequencies below 150 MHz.

As implied in the earlier discussion of shielded loops in this chapter, the true loop antenna responds to the magnetic field of the radio wave, and not to the electrical field. The voltage delivered by the loop is proportional to the amount of magnetic flux passing through the coil, and to the number of turns in the coil. The action is much the same as in the secondary winding of a transformer. For a given size of loop, the output voltage can be increased by increasing the flux density, and this is done with a ferrite core of high permeability. A $1/2$-inch diameter, 7-inch rod of Q2 ferrite ($m_i = 125$) is suitable for a loop core from the broadcast band through 10 MHz. For increased output, the turns may be wound on two rods that are taped together, as shown in **Fig 4**. Loopstick antennas for con-

Fig 4—A ferrite-rod or loopstick antenna. Turns of wire may be wound on a single rod, or to increase the output from the loop, the core may be two rods taped together, as shown here. The type of core material must be selected for the intended frequency range of the loop. To avoid bulky windings, fine wire such as #28 or #30 is often used, with larger wire for the leads.

Fig 5—Field pattern for a ferrite rod antenna. The dark bar represents the rod on which the loop turns are wound.

(A)

(B)

Fig 6—At A, the directivity pattern of a loop antenna with sensing element. At B is a circuit for combining the signals from the two elements. C1 is adjusted for resonance with T1 at the operating frequency.

struction are described later in this chapter.

Maximum response of the loopstick antenna is broadside to the axis of the rod as shown in **Fig 5**, whereas maximum response of the ordinary loop is in a direction at right angles to the plane of the loop. Otherwise, the performances of the ferrite-rod antenna and of the ordinary loop are similar. The loopstick may also be shielded to eliminate the antenna effect, such as with a U-shaped or C-shaped channel of aluminum or other form of *trough*. The length of the shield should equal or slightly exceed the length of the rod.

Sensing Antennas

Because there are two nulls that are 180° apart in the directional pattern of a loop or a loopstick, an ambiguity exists as to which one indicates the true direction of the station being tracked. For example, assume you take a bearing measurement and the result indicates the transmitter is somewhere on a line running approximately east and west from your position. With this single reading, you have no way of knowing for sure if the transmitter is east of you or west of you.

If more than one receiving station takes bearings on a single transmitter, or if a single receiving station takes bearings from more than one position on the transmitter, the ambiguity may be worked out by triangulation, as described earlier. However, it is sometimes desirable to have a pattern with only one null, so there is no question about whether the transmitter in the above example would be east or west from your position.

A loop or loopstick antenna may be made to have a single null if a second antenna element is added. The element is called a *sensing antenna*, because it gives an added sense of direction to the loop pattern. The second element must be omnidirectional, such as a short vertical. When the signals from the loop and the vertical element are combined with a 90° phase shift between the two, a cardioid pattern results. The development of the pattern is shown in **Fig 6A**.

Fig 6B shows a circuit for adding a sensing antenna to a loop or loopstick. R1 is an internal adjustment and is used to set the level of the signal from the sensing

antenna. For the best null in the composite pattern, the signals from the loop and the sensing antenna must be of equal amplitude, so R1 is adjusted experimentally during setup. In practice, the null of the cardioid is not as sharp as that of the loop, so the usual measurement procedure is to first use the loop alone to obtain a precise bearing reading, and then to add the sensing antenna and take another reading to resolve the ambiguity. (The null of the cardioid is 90° away from the nulls of the loop.) For this reason, provisions are usually made for switching the sensing element in an out of operation.

PHASED ARRAYS

Phased arrays are also used in amateur RDF work. Two general classifications of phased arrays are end-fire and broadside configurations. Depending on the spacing and phasing of the elements, end-fire patterns may exhibit a null in one direction along the axis of the elements. At the same time, the response is maximum off the other end of the axis, in the opposite direction from the null. A familiar arrangement is two elements spaced $^1/_4$ λ apart and fed 90° out of phase. The resultant pattern is a *cardioid*, with the null in the direction of the leading element. Other arrangements of spacing and phasing for an end-fire array are also suitable for RDF work. One of the best known is the *Adcock array*, discussed in the next section.

Broadside arrays are inherently bidirectional, which means there are always at least two nulls in the pattern. Ambiguity therefore exists in the true direction of the transmitter, but depending on the application, this may be no handicap. Broadside arrays are seldom used for amateur RDF applications however.

The Adcock Antenna

Loops are adequate in RDF applications where only the ground wave is present. The performance of an RDF system for sky-wave reception can be improved by the use of an Adcock antenna, one of the most popular types of end-fire phased arrays. A basic version is shown in **Fig 7**.

This system was invented by F. Adcock and patented in 1919. The array consists of two vertical elements fed 180° apart, and mounted so the system may be rotated. Element spacing is not critical, and may be in the range from 0.1 to 0.75 λ. The two elements must be of identical lengths, but need not be self-resonant. Elements that are shorter than resonant are commonly used. Because neither the element spacing nor the length is critical in terms of wavelengths, an Adcock array may be operated over more than one amateur band.

The response of the Adcock array to vertically polarized waves is similar to a conventional loop, and the directive pattern is essentially the same. Response of the array to a horizontally polarized wave is considerably different from that of a loop, however. The currents induced in the horizontal members tend to balance out regardless of the orientation of the antenna. This effect has been verified in practice, where good nulls were obtained with an experimental Adcock under sky-wave conditions. The same circumstances produced poor nulls with small loops (both conventional and ferrite-loop models).

Generally speaking, the Adcock antenna has attractive properties for amateur RDF applications. Unfortunately, its portability leaves something to be desired, making it more suitable to fixed or semi-portable applications. While a metal support for the mast and boom could be used, wood, PVC or fiberglass are preferable because they are nonconductors and would therefore cause less pattern distortion.

Since the array is balanced, an antenna tuner is required to match the unbalanced input of a typical receiver. **Fig 8** shows a suitable link-coupled network. C2 and C3 are null-balancing capacitors. A low-power signal source is placed some distance from the Adcock

Fig 7—A simple Adcock antenna.

Fig 8—A suitable coupler for use with the Adcock antenna.

(A)   (B)

Fig 9—At A, the pattern of the Adcock array with an element spacing of ¹/₂ wavelength. In these plots the elements are aligned with the horizontal axis. As the element spacing is increased beyond ³/₄ wavelength, additional nulls develop off the ends of the array, and at a spacing of 1 wavelength the pattern at B exists. This pattern is unsuitable for RDF work.

antenna and broadside to it. C2 and C3 are then adjusted until the deepest null is obtained. The tuner can be placed below the wiring-harness junction on the boom. Connection can be made by means of a short length of 300-Ω twin-lead.

The radiation pattern of the Adcock is shown in **Fig 9A**. The nulls are in directions broadside to the array, and become sharper with greater element spacings. However, with an element spacing greater than 0.75 λ, the pattern begins to take on additional nulls in the directions off the ends of the array axis. At a spacing of 1 λ the pattern is that of Fig 9B, and the array is unsuitable for RDF applications.

Short vertical monopoles are often used in what is sometimes called the *U-Adcock*, so named because the elements with their feeders take on the shape of the letter U. In this arrangement the elements are worked against the earth as a ground or counterpoise. If the array is used only for reception, earth losses are of no great consequence. Short, elevated vertical dipoles are also used in what is sometimes called the *H-Adcock*.

The Adcock array, with two nulls in its pattern, has the same ambiguity as the loop and the loopstick. Adding a sensing element to the Adcock array has not met with great success. Difficulties arise from mutual coupling between the array elements and the sensing element, among other things. Because Adcock arrays are used primarily for fixed-station applications, the ambiguity presents no serious problem. The fixed station is usually one of a group of stations in an RDF network.

LOOPS VERSUS PHASED ARRAYS

Although loops can be made smaller than suitable phased arrays for the same frequency of operation, the

phased arrays are preferred by some for a variety of reasons. In general, sharper nulls can be obtained with phased arrays, but this is also a function of the care used in constructing and feeding the individual antennas, as well as of the size of the phased array in terms of wavelengths. The primary constructional consideration is the shielding and balancing of the feed line against unwanted signal pickup, and the balancing of the antenna for a symmetrical pattern.

Loops are not as useful for skywave RDF work because of random polarization of the received signal. Phased arrays are somewhat less sensitive to propagation effects, probably because they are larger for the same frequency of operation and therefore offer some space diversity. In general, loops and loopsticks are used for mobile and portable operation, while phased arrays are used for fixed-station operation. However, phased arrays are used successfully above 144 MHz for portable and mobile RDF work. Practical examples of both types of antennas are presented later in this chapter.

THE GONIOMETER

Most fixed RDF stations for government and commercial work use antenna arrays of stationary elements, rather than mechanically rotatable arrays. This has been true since the earliest days of radio. The early-day device that permits finding directions without moving the elements is called a *radiogoniometer*, or simply a *goniometer*. Various types of goniometers are still used today in many installations, and offer the amateur some possibilities.

The early style of goniometer is a special form of RF transformer, as shown in **Fig 10**. It consists of two fixed coils mounted at right angles to one another. Inside the fixed coils is a movable coil, not shown in Fig 10 to

Fig 10—An early type of goniometer that is still used today in some RDF applications. This device is a special type of RF transformer that permits a movable coil in the center (not shown here) to be rotated and determine directions even though the elements are stationary.

Fig 11—This diagram illustrates one technique used in electronic beam forming. By delaying the signal from element A by an amount equal to the propagation delay, the two signals may be summed precisely in phase, even though the signal is not in the broadside direction. Because this time delay is identical for all frequencies, the system is not frequency sensitive.

avoid cluttering the diagram. The pairs of connections marked A and B are connected respectively to two elements in an array, and the output to the detector or receiver is taken from the movable coil. As the inner coil is rotated, the coupling to one fixed coil increases while that to the other decreases. Both the amplitude and the phase of the signal coupled into the pickup winding are altered with rotation in a way that corresponds to actually rotating the array itself. Therefore, the rotation of the inner coil can be calibrated in degrees to correspond to bearing angles from the station location.

In the early days of radio, the type of goniometer just described saw frequent use with fixed Adcock arrays. A refinement of that system employed four Adcock elements, two arrays at right angles to each other. With a goniometer arrangement, RDF measurements could be taken in all compass directions, as opposed to none off the ends of a two-element fixed array. However, resolution of the 4-element system was not as good as with a single pair of elements, probably because of mutual coupling among the elements. To overcome this difficulty a few systems of eight elements were installed.

Various other types of goniometers have been developed over the years, such as commutator switching to various elements in the array. A later development is the diode switching of capacitors to provide a commutator effect. As mechanical action has gradually been replaced with electronics to "rotate" stationary elements, the word goniometer is used less frequently these days. However, it still appears in many engineering reference texts. The more complex electronic systems of today are called *beam-forming networks*.

Electronic Antenna Rotation

With an array of many fixed elements, beam rotation can be performed electronically by sampling and combining signals from various individual elements in the array.

Contingent upon the total number of elements in the system and their physical arrangement, almost any desired antenna pattern can be formed by summing the sampled signals in appropriate amplitude and phase relationships. Delay networks are used for some of the elements before the summation is performed. In addition, attenuators may be used for some elements to develop patterns such as from an array with binomial current distribution.

One system using these techniques is the *Wullenweber* antenna, employed primarily in government and military installations. The Wullenweber consists of a very large number of elements arranged in a circle, usually outside of (or in front of) a circular reflecting screen. Depending on the installation, the circle may be anywhere from a few hundred feet to more than a quarter of a mile in diameter. Although the Wullenweber is not one that would be constructed by an amateur, some of the techniques it uses may certainly be applied to Amateur Radio.

For the moment, consider just two elements of a Wullenweber antenna, shown as A and B in **Fig 11**. Also shown is the wavefront of a radio signal arriving from a distant transmitter. As drawn, the wavefront strikes element A first, and must travel somewhat farther before it strikes element B. There is a finite time delay before the wavefront reaches element B.

The propagation delay may be measured by delaying the signal received at element A before summing it with that from element B. If the two signals are combined directly, the amplitude of the resultant signal will be maximum when the delay for element A exactly equals the propagation delay. This results in an in-phase condition at the summation point. Or if one of the signals is inverted and the two are summed, a null will exist when the element-A delay equals the propagation delay; the signals will combine in a 180° out-of-phase relationship. Either way, once the time delay is known, it may be converted to distance. Then the direction from which the wave

is arriving may be determined by trigonometry.

By altering the delay in small increments, the peak of the antenna lobe (or the null) can be steered in azimuth. This is true without regard to the frequency of the incoming wave. Thus, as long as the delay is less than the period of one RF cycle, the system is not frequency sensitive, other than for the frequency range that may be covered satisfactorily by the array elements themselves. Surface acoustic wave (SAW) devices or lumped-constant networks can be used for delay lines in such systems if the system is used only for receiving. Rolls of coaxial cable of various lengths are used in installations for transmitting. In this case, the lines are considered for the time delay they provide, rather than as simple phasing lines. The difference is that a phasing line is ordinarily designed for a single frequency (or for an amateur band), while a delay line offers essentially the same time delay at all frequencies.

By combining signals from other Wullenweber elements appropriately, the broad beamwidth of the pattern from the two elements can be narrowed, and unwanted sidelobes can be suppressed. Then, by electronically switching the delays and attenuations to the various elements, the beam so formed can be rotated around the compass. The package of electronics designed to do this, including delay lines and electronically switched attenuators, is the beam-forming network. However, the Wullenweber system is not restricted to forming a single beam. With an isolation amplifier provided for each element of the array, several beam-forming networks can be operated independently. Imagine having an antenna system that offers a dipole pattern, a rhombic pattern, and a Yagi beam pattern, all simultaneously and without frequency sensitivity. One or more may be rotating while another is held in a particular direction. The Wullenweber was designed to fulfill this type of requirement.

One feature of the Wullenweber antenna is that it can operate 360° around the compass. In many government installations, there is no need for such coverage, as the areas of interest lie in an azimuth sector. In such cases an in-line array of elements with a backscreen or curtain reflector may be installed broadside to the center of the sector. By using the same techniques as the Wullenweber, the beams formed from this array may be slewed left and right across the sector. The maximum sector width available will depend on the installation, but beyond 70° to 80° the patterns begin to deteriorate to the point that they are unsatisfactory for precise RDF work.

RDF SYSTEM CALIBRATION AND USE

Once an RDF system is initially assembled, it should be calibrated or checked out before actually being put into use. Of primary concern is the balance or symmetry of the antenna pattern. A lop-sided figure-8 pattern with a loop, for example, is undesirable; the nulls are not 180° apart, nor are they at exact right angles to the plane of the loop. If you didn't know this fact in actual RDF work, measurement accuracy would suffer.

Initial checkout can be performed with a low-powered transmitter at a distance of a few hundred feet. It should be within visual range and must be operating into a vertical antenna. (A quarter-wave vertical or a loaded whip is quite suitable.) The site must be reasonably clear of obstructions, especially steel and concrete or brick buildings, large metal objects, nearby power lines, and so on. If the system operates above 30 MHz, you should also avoid trees and large bushes. An open field makes an excellent site.

The procedure is to find the transmitter with the RDF equipment as if its position were not known, and compare the RDF null indication with the visual path to the transmitter. For antennas having more than one null, each null should be checked.

If imbalance is found in the antenna system, there are two options available. One is to correct the imbalance. Toward this end, pay particular attention to the feed line. Using a coaxial feeder for a balanced antenna invites an asymmetrical pattern, unless an effective balun is used. A balun is not necessary if the loop is shielded, but an asymmetrical pattern can result with misplacement of the break in the shield itself. The builder may also find that the presence of a sensing antenna upsets the balance slightly, due to mutual coupling. Experiment with its position with respect to the main antenna to correct the error. You will also note that the position of the null shifts by 90° as the sensing element is switched in and out, and the null is not as deep. This is of little concern, however, as the intent of the sensing antenna is only to resolve ambiguities. The sensing element should be switched out when accuracy is desired.

The second option is to accept the imbalance of the antenna and use some kind of indicator to show the true directions of the nulls. Small pointers, painted marks on the mast, or an optical sighting system might be used. Sometimes the end result of the calibration procedure will be a compromise between these two options, as a perfect electrical balance may be difficult or impossible to attain.

The discussion above is oriented toward calibrating portable RDF systems. The same general suggestions apply if the RDF array is fixed, such as an Adcock. However, it won't be possible to move it to an open field. Instead, the array must be calibrated in its intended operating position through the use of a portable or mobile transmitter. Because of nearby obstructions or reflecting objects, the null in the pattern may not appear to indicate the precise direction of the transmitter. Do not confuse this with imbalance in the RDF array. Check for imbalance by rotating the array 180° and comparing readings.

Once the balance is satisfactory, you should make a table of bearing errors noted in different compass directions. These error values should be applied as corrections when actual measurements are made. The mobile or por-

Fig 12—A multiturn frame antenna is shown at A. L2 is the coupling loop. The drawing at B shows how L2 is connected to a preamplifier.

Fig 13—A wooden frame can be used to contain the wire of the loop shown in Fig 12.

Fig 14—An assembled table-top version of the electrostatically shielded loop. RG-58 cable is used in its construction.

table transmitter should be at a distance of two or three miles for these measurements, and should be in as clear an area as possible during transmissions. The idea is to avoid conduction of the signal along power lines and other overhead wiring from the transmitter to the RDF site. Of course the position of the transmitter must be known accurately for each transmission.

FRAME LOOPS

It was mentioned earlier that the earliest style of receiving loops was the frame antenna. If carefully constructed, such an antenna performs well and can be built at low cost. **Fig 12** illustrates the details of a practical frame type of loop antenna. This antenna was designed by Doug DeMaw, W1FB, and described in *QST* for July 1977. (See the Bibliography at the end of this chapter.) The circuit in Fig 12A is a 5-turn system tuned to resonance by C1. If the layout is symmetrical, good balance should be obtained. L2 helps to achieve this objective by eliminating the need for direct coupling to the feed ter-

minals of L1. If the loop feed were attached in parallel with C1, a common practice, the chance for imbalance would be considerable.

L2 can be situated just inside or slightly outside of L1; a 1-inch separation works nicely. The receiver or preamplifier can be connected to terminals A and B of L2, as shown in Fig 12B. C2 controls the amount of coupling between the loop and the preamplifier. The lighter the coupling, the higher is the loop Q, the narrower is the frequency response, and the greater is the gain requirement from the preamplifier. It should be noted that no attempt is being made to match the extremely low loop impedance to the preamplifier.

A supporting frame for the loop of Fig 12 can be constructed of wood, as shown in **Fig 13**. The dimensions given are for a 1.8-MHz frame antenna. For use on 75 or 40 meters, L1 of Fig 12A will require fewer turns, or the size of the wooden frame should be made somewhat smaller than that of Fig 13.

SHIELDED FRAME LOOPS

If electrostatic shielding is desired, the format shown in **Fig 14** can be adopted. In this example, the loop conductor and the single-turn coupling loop are made from RG-58 coaxial cable. The number of loop turns should be sufficient to resonate with the tuning capacitor at the operating frequency. Antenna resonance can be checked by first connecting C1 (Fig 12A) and setting it at midrange. Then connect a small 3-turn coil to the loop feed terminals, and couple to it with a dip meter. Just remember that the pickup coil will act to lower the frequency slightly from actual resonance.

In the antenna photographed for Fig 14, the 1-turn coupling loop was made of #22 plastic-insulated wire. However, electrostatic noise pickup occurs on such a coupling loop, noise of the same nature that the shield on the main loop prevents. This can be avoided by using RG-58 for the coupling loop. The shield of the coupling loop should be opened for about 1 inch at the top, and each end of the shield grounded to the shield of the main loop.

Larger single-turn frame loops can be fashioned from aluminum-jacketed Hardline, if that style of coax is available. In either case, the shield conductor must be opened at the electrical center of the loop, as shown in **Fig 15** at A and B. The design example is for 1.8-MHz operation.

To realize the best performance from an electrostatically shielded loop antenna, you must operate it near to and directly above an effective ground plane. An automobile roof (metal) qualifies nicely for small shielded loops. For fixed-station use, a chicken-wire ground screen can be placed below the antenna at a distance of 1 to 6 feet.

Fig 15—Components and assembly details of the shielded loop shown in Fig 14.

Fig 16—At A, the diagram of a ferrite loop. C1 is a dual-section air-variable capacitor. The circuit at B shows a rod loop contained in an electrostatic shield channel (see text). A suitable low-noise preamplifier is shown in Fig 19.

Fig 17—The assembly at the top of the picture is a shielded ferrite-rod loop for 160 meters. Two rods have been glued end to end (see text). The other units in the picture are a low-pass filter (lower left), broadband preamplifier (lower center) and a Tektronix step attenuator (lower right). These were part of the test setup used when the antenna was evaluated.

FERRITE-CORE LOOPS

Fig 16 contains a diagram for a rod loop (loopstick antenna). This antenna was also designed by Doug DeMaw, W1FB, and described in *QST* for July 1977. The winding (L1) has the appropriate number of turns to permit resonance with C1 at the operating frequency. L1 should be spread over approximately $^1/_3$ of the core cen-

ter. Litz wire will yield the best Q, but Formvar magnet wire can be used if desired. A layer of 3M Company glass tape (or Mylar tape) is recommended as a covering for the core before adding the wire. Masking tape can be used if nothing else is available.

L2 functions as a coupling link over the exact center of L1. C1 is a dual-section variable capacitor, although a differential capacitor might be better toward obtaining optimum balance. The loop Q is controlled by means of C2, which is a mica-compression trimmer.

Electrostatic shielding of rod loops can be effected by centering the rod in a U-shaped aluminum, brass or copper channel, extending slightly beyond the ends of the rod loop (1 inch is suitable). The open side (top) of the channel can't be closed, as that would constitute a shorted turn and render the antenna useless. This can be proved by shorting across the center of the channel with a screwdriver blade when the loop is tuned to an incoming signal. The shield-braid gap in the coaxial loop of Fig 15 is maintained for the same reason.

Fig 17 shows the shielded rod loop assembly. This antenna was developed experimentally for 160 meters and uses two 7-inch ferrite rods, glued together end-to-end with epoxy cement. The longer core resulted in improved sensitivity for weak-signal reception. The other items in the photograph were used during the evaluation tests and are not pertinent to this discussion. This loop and the frame loop discussed in the previous section have bidirectional nulls, as shown in Fig 1A.

Obtaining a Cardioid Pattern

Although the bidirectional pattern of loop antennas

Fig 18—Schematic diagram of a rod-loop antenna with a cardioid response. The sensing antenna, phasing network and a preamplifier are shown also. The secondary of T1 and the primary of T2 are tuned to resonance at the operating frequency of the loop. T-68-2 to T-68-6 Amidon toroid cores are suitable for both transformers. Amidon also sells ferrite rods for this type of antenna.

Fig 19—Schematic diagram of a two-stage broadband amplifier patterned after a design by Wes Hayward, W7ZOI. T1 and T2 have a 4:1 impedance ratio and are wound on FT-50-61 toroid cores (Amidon) which have a μ_i of 125. They contain 12 turns of #24 enamel wire, bifilar wound. The capacitors are disc ceramic. This amplifier should be built on double-sided circuit board for best stability.

can be used effectively in tracking down signal sources by means of triangulation, an essentially unidirectional loop response will help to reduce the time spent finding the fox. Adding a sensing antenna to the loop is simple to do, and it will provide the desired cardioid response. The theoretical pattern for this combination is shown in Fig 1D.

Fig 18 shows how a sensing element can be added to a loop or loopstick antenna. The link from the loop is connected by coaxial cable to the primary of T1, which is a tuned toroidal transformer with a split secondary winding. C3 is adjusted for peak signal response at the frequency of interest (as is C4), then R1 is adjusted for minimum back response of the loop. It will be necessary to readjust C3 and R1 several times to compensate for the interaction of these controls. The adjustments are repeated until no further null depth can be obtained. Tests at ARRL Headquarters showed that null depths as great as 40 dB could be obtained with the circuit of Fig 18 on 75 meters. A near-field weak-signal source was used during the tests.

The greater the null depth, the lower the signal output from the system, so plan to include a preamplifier with 25 to 40 dB of gain. Q1 shown in Fig 18 will deliver approximately 15 dB of gain. The circuit of **Fig 19** can be used following T2 to obtain an additional 24 dB of gain. In the interest of maintaining a good noise figure, even at 1.8 MHz, Q1 should be a low-noise device. A 2N4416, an

MPF102, or a 40673 MOSFET would be satisfactory. The sensing antenna can be mounted 6 to 15 inches from the loop. The vertical whip need not be more than 12 to 20 inches long. Some experimenting may be necessary in order to obtain the best results. Optimization will also change with the operating frequency of the antenna.

A SHIELDED LOOP WITH SENSING ANTENNA FOR 28 MHz

Fig 20 shows the construction and mounting of a simple shielded 10-meter loop. The loop was designed by Loren Norberg, W9PYG, and described in *QST* for April 1954. (See the Bibliography at the end of this chapter.) It is made from an 18-inch length of RG-11 coax (either solid or foam dielectric) secured to an aluminum box of any convenient size, with two coaxial cable hoods (Amphenol 83-1HP). The outer shield must be broken at the exact center. C1 is a 25-pF variable capacitor, and is connected in parallel with a 33-pF fixed mica padder capacitor, C3. C1 must be tuned to the desired frequency while the loop is connected to the receiver in the same way as it will be used for RDF. C2 is a small differential capacitor used to provide electrical symmetry. The lead-in to the receiver is 67 inches of RG-59 (82 inches if the cable has a foamed dielectric).

The loop can be mounted on the roof of the car with a rubber suction cup. The builder might also fabricate some kind of bracket assembly to mount the loop tempo-

rarily in the window opening of the automobile, allowing for loop rotation. Reasonably true bearings may be obtained through the windshield when the car is pointed in the direction of the hidden transmitter. More accurate bearings may be obtained with the loop held out the window and the signal coming toward that side of the car.

Sometimes the car broadcast antenna may interfere with accurate bearings. Disconnecting the antenna from the broadcast receiver may eliminate this trouble.

Sensing Antenna

A sensing antenna can be added to Norberg's loop above to determine which of the two directions indicated by the loop is the correct one. Add a phono jack to the top of the aluminum case shown in Fig 20. The insulated center terminal of the jack should be connected to the side of the tuning capacitors that is common to the center conductor of the RG-59 coax feed line. The jack then takes a short vertical antenna rod of the diameter to fit the jack, or a piece of #12 or #14 solid wire may be soldered to the

Fig 20—Sketch showing the constructional details of the 28-MHz RDF loop. The outer braid of the coax loop is broken at the center of the loop. The gap is covered with waterproof tape, and the entire assembly is given a coat of acrylic spray.

center pin of a phono plug for insertion in the jack. The sensing antenna can be plugged in as needed. Starting with a length of about four times the loop diameter, the length of the sensing antenna should be pruned until the pattern is similar to that of Fig 1D.

THE SNOOP LOOP—FOR CLOSE-RANGE HF RDF

Picture yourself on a hunt for a hidden 28-MHz transmitter. The night is dark, very dark. After you take off at the start of the hunt, heading in the right direction, the signal gets stronger and stronger. Your excitement increases with each additional S unit on the meter. You follow your loop closely, and it is working perfectly. You're getting out of town and into the countryside. The roads are unfamiliar. Now the null is beginning to swing rather rapidly, showing that you are getting close.

Suddenly the null shifts to give a direction at right angles to the car. With your flashlight you look carefully across the deep ditch beside the road and into the dark field where you know the transmitter is hidden. There are no roads into the field as far as you can see in either direction. You dare not waste miles driving up and down the road looking for an entrance, for each tenth of a mile counts. But what to do?—Your HF transceiver is mounted in your car and requires power from your car battery.

In a brief moment your decision is made. You park

Fig 21—The box containing the detector and amplifier is also the "handle" for the Snoop Loop. The loop is mounted with a coax T as a support, a convenience but not an essential part of the loop assembly. The loop tuning capacitor is screwdriver adjusted. The on-off switch and the meter sensitivity control may be mounted on the bottom.

Fig 22—The Snoop Loop circuit for 28-MHz operation. The loop is a single turn of RG-8 inner conductor, the outer conductor being used as a shield. Note the gap in the shielding; about a 1-inch section of the outer conductor should be cut out. Refer to Fig 23 for alternative connection at points A and B for other frequencies of operation.

BT1—Two penlight cells.
C1—25-pF midget air padder.
D1—Small-signal germanium diode such as 1N34A or equiv.
DS1—Optional 2-cell penlight lamp for meter illumination, such as no. 222.
Q1—PNP transistor such as ECG102 or equiv.
R1—100-kΩ potentiometer, linear taper. May be PC-mount style.
R2—50-kΩ potentiometer, linear taper.
S1—SPST toggle.
S2—Optional momentary push for illuminating meter.

Fig 23—Input circuit for lower frequency bands. Points A and B are connected to corresponding points in the circuit of Fig 22, substituting for the loop and C1 in that circuit. L1-C1 should resonate within the desired amateur band, but the L/C ratio is not critical. After construction is completed, adjust the position of the tap on L1 for maximum signal strength. Instead of connecting the RDF loop directly to the tap on L1, a length of low impedance line may be used between the loop and the tuned circuit, L1-C1.

Fig 24—Unidirectional 3.5-MHz RDF using ferrite-core loop with sensing antenna. Adjustable components of the circuit are mounted in the aluminum chassis supported by a short length of tubing.

beside the road, take your flashlight, and plunge into the veldt in the direction your loop null clearly indicated. But after taking a few steps, you're up to your armpits in brush and can't see anything forward or backward. You stumble on in hopes of running into the hidden transmitter—you're probably not more than a few hundred feet from it. But away from your car and radio equipment, it's like the proverbial hunt for the needle in the haystack. What you really need is a portable setup for hunting at close range, and you may prefer something that is inexpensive. The Snoop Loop was designed for just these requirements by Claude Maer, Jr, WØIC, and was described in *QST* for February 1957. (See the Bibliography at the end of this chapter.)

The Snoop Loop is pictured in **Fig 21**. The loop itself is made from a length of RG-8 coax, with the shield broken at the top. A coax T connector is used for convenience and ease of mounting. One end of the coax loop is connected to a male plug in the conventional way, but the center conductor of the other end is shorted to the shield so the male connector at that end has no connection to the center prong. This results in an unbalanced circuit,

but seems to give good bidirectional null readings, as well as an easily detectable maximum reading when the grounded end of the loop is pointed in the direction of the transmitter. Careful tuning with C1 will improve this maximum reading. Don't forget to remove one inch of shielding from the top of the loop. You won't get much signal unless you do.

The detector and amplifier circuit for the Snoop Loop

Fig 25—Circuit of the 3.5-MHz direction finder loop.
**C1—140 pF variable (125-pF ceramic trimmer in
parallel with 15-pF ceramic fixed.**
**L1—Approximately 140 µH adjustable (Miller No. 4512
or equivalent.**
R1—1-kΩ carbon potentiometer.
S1—SPST toggle.
**Loopstick—Approximately 15 µH (Miller 705-A, with
original winding removed and wound with 20 turns of
#22 enamel). Link is two turns at center. Winding ends
secured with Scotch electrical tape. This type of
ferrite rod may also be found in surplus transistor AM
radios.**

is shown in **Fig 22**. The model photographed does not include the meter, as it was built for use only with high-impedance headphones. The components are housed in an aluminum box. Almost any size box of sufficient size to contain the meter can be used. At very close ranges, reduction of sensitivity with R2 will prevent pegging the meter.

The Snoop Loop is not limited to the 10-meter band or to a built-in loop. **Fig 23** shows an alternative circuit for other bands and for plugging in a separate loop connected by a low-impedance transmission line. Select coil and capacitor combinations that will tune to the desired frequencies. Plug-in coils could be used. It is a good idea to have the RF end of the unit fairly well shielded, to eliminate signal pickup except through the loop. This little unit should certainly help you on those dark nights in the country. (Tip to the hidden-transmitter operator—if you want to foul up some of your pals using these loops, just hide near the antenna of a 50-kW broadcast transmitter!)

A LOOPSTICK FOR 3.5 MHz

Figs 24 through 26 show an RDF loop suitable for the 3.5-MHz band. It uses a construction technique that has had considerable application in low-frequency marine direction finders. The loop is a coil wound on a ferrite rod from a broadcast-antenna loopstick. The loop was designed by John Isaacs, W6PZV, and described in *QST* for June

1958. Because you can make a coil with high Q using a ferrite core, the sensitivity of such a loop is comparable to a conventional loop that is a foot or so in diameter. The output of the vertical-rod sensing antenna, when properly combined with that of the loop, gives the system the cardioid pattern shown in Fig 1D.

To make the loop, remove the original winding on the ferrite core and wind a new coil, as shown in **Fig 25**. Other types of cores than the one specified may be substituted; use the largest coil available and adjust the winding so that the circuit resonates in the 3.5-MHz band within the range of C1. The tuning range of the loop may be checked with a dip meter.

The sensing system consists of a 15-inch whip and an adjustable inductor that resonates the whip as a quarter-wave antenna. It also contains a potentiometer to control the output of the antenna. S1 is used to switch the sensing antenna in and out of the circuit.

The whip, the loopstick, the inductance L1, the capacitor C1, the potentiometer R1, and the switch S1 are all mounted on a $4 \times 5 \times 3$-inch box chassis, as shown in **Fig 26**. The loopstick may be mounted and protected inside a piece of $\frac{1}{2}$-inch PVC pipe. A section of $\frac{1}{2}$-inch electrical conduit is attached to the bottom of the chassis box and this supports the instrument.

To produce an output having only one null there must a 90° phase difference between the outputs of the loop and sensing antennas, and the signal strength from each must be the same. The phase shift is obtained by tuning the sensing antenna slightly off frequency, using the slug in L1. Since the sensitivity of the whip antenna is greater than that of the loop, its output is reduced by adjusting R1.

Adjustment

To adjust the system, enlist the aid of a friend with a mobile transmitter and find a clear spot where the transmitter and RDF receiver can be separated by several hundred feet. Use as little power as possible at the transmitter. (Make very sure you don't transmit into the loop if you are using a transceiver as a detector.) With the test transmitter operating on the proper frequency, disconnect the sensing antenna with S1, and peak the loopstick using C1, while watching the S meter on the transceiver. Once the loopstick is peaked, no further adjustment of C1 will be necessary. Next, connect the sensing antenna and turn R1 to minimum resistance. Then vary the adjustable slug of L1 until a maximum reading of the S meter is again obtained. It may be necessary to turn the unit a bit during this adjustment to obtain a higher reading than with the loopstick alone. The last turn of the slug is quite critical, and some hand-capacitance effect may be noted.

Now turn the instrument so that one side (not an end) of the loopstick is pointed toward the test transmitter. Turn R1 a complete revolution and if the proper side was chosen a definite null should be observed on the S meter for one particular position of R1. If not, turn the RDF 180° and try again. This time leave R1 at the setting producing

Fig 26—Components of the 3.5-MHz RDF are mounted on the top and sides of a channel-lock type box. In this view R1 is on the left wall at the upper left and C1 is at the lower left. L1, S1 and the output connector are on the right wall. The loopstick and whip mount on the outside.

Fig 27—At A is a simple configuration that can produce a cardioid pattern. At B is a convenient way of fabricating a sturdy mount for the radiator using BNC connectors.

the minimum reading. Now adjust L1 very slowly until the S-meter reading is reduced still further. Repeat this several times, first R1, and then L1, until the best minimum is obtained.

Finally, as a check, have the test transmitter move around the RDF and follow it by turning the RDF. If the tuning has been done properly the null will always be broadside to the loopstick. Make a note of the proper side of the RDF for the null, and the job is finished.

A 144-MHZ CARIOID-PATTERN RDF ANTENNA

Although there may be any number of different VHF antennas that can produce a cardioid pattern, a simple design is depicted in **Fig 27**. Two $^1/_4$-wavelength vertical elements are spaced one $^1/_4$-λ apart and are fed 90° out of phase. Each radiator is shown with two radials approximately 5% shorter than the radiators. This array was designed by Pete O'Dell, KB1N, and described in *QST* for March 1981.

Computer modeling showed that slight alterations in the size, spacing and phasing of the elements strongly impact the pattern. The results suggest that this system is a little touchy and that the most significant change comes at the null. Very slight alterations in the dimensions caused the notch to become much more shallow and, hence, less usable for RDF. Early experience in building a working model bore this out.

This means that if you build this antenna, you will find it advantageous to spend a few minutes to tune it carefully for the deepest null. If it is built using the techniques presented here, then this should prove to be a small task, well worth the extra effort. Tuning is accomplished by adjusting the length of the vertical radiators, the spacing between them and, if necessary, the lengths of the phasing harness that connects them. Tune for the deepest

null on your S meter when using a signal source such as a moderately strong repeater.

This should be done outside, away from buildings and large metal objects. Initial indoor tuning on this project was tried in the kitchen, which revealed that reflections off the appliances were producing spurious readings. Beware too of distant water towers, radio towers, and large office or apartment buildings. They can reflect the signal and give false indications.

Construction is simple and straightforward. Fig 27B shows a female BNC connector (RadioShack 278-105) that has been mounted on a small piece of PC-board material. The BNC connector is held upside down, and the vertical radiator is soldered to the center solder lug. A 12-inch piece of brass tubing provides a snug fit over the solder lug. A second piece of tubing, slightly smaller in diameter, is telescoped inside the first. The outer tubing is crimped slightly at the top after the inner tubing is installed. This provides positive contact between the two tubes. For 146 MHz the length of the radiators is calculated to be about 19 inches. You should be able to find small brass tubing at a hobby store. If none is available in your area, consider brazing rods. These are often available in hardware sections of discount stores. It will probably be necessary to solder a short piece to the top since these come in 18-inch sections. Also, tuning will not be quite as convenient. Two 18-inch radials are added to each element by soldering them to the board. Two 36-inch pieces of heavy brazing rod were used in this project.

The Phasing Harness

As shown in **Fig 28**, a T connector is used with two different lengths of coaxial line to form the phasing harness. This method of feeding the antenna is superior over

Fig 28—The phasing harness for the phased 144-MHz RDF array. The phasing sections must be measured from the center of the T connector to the point that the vertical radiator emerges from the shielded portion of the upside-down BNC female. Don't forget to take the length of the connectors into account when constructing the harness. If care is taken and coax with solid polyethylene dielectric is used, you should not have to prune the phasing line. With this phasing system, the null will be in a direction that runs along the boom, on the side of the $^1/_4$-wavelength section.

Fig 29—A simple mechanical support for the DF antenna, made of PVC pipe and fittings.

other simple systems to obtain equal currents in the two radiators. Unequal currents tend to reduce the depth of the null in the pattern, all other factors being equal.

The $^1/_2$-wavelength section can be made from either RG-58 or RG-59, because it should act as a 1:1 transformer. With no radials or with two radials perpendicular to the vertical element, it was found that a $^1/_4$-wavelength section made of RG-59 75-Ω coax produced a deeper notch than a $^1/_4$-wavelength section made of RG-58 50-Ω line. However, with the two radials bent downward somewhat, the RG-58 section seemed to outperform the RG-59. Because of minor differences in assembly techniques from one antenna to another, it will probably be worth your time and effort to try both types of coax and determine what works best for your antenna. You may also want to try bending the radials down at slightly different angles for the best null performance.

The most important thing about the coax for the harness is that it be of the highest quality (well-shielded and with a polyethylene dielectric). The reason for avoiding foam dielectric is that the velocity factor can vary from one roll to the next—some say that it varies from one foot to the next. Of course, it can be used if you have test equipment available that will allow you to determine its electrical length. Assuming that you do not want to or cannot go to that trouble, stay with coax having a solid

polyethylene dielectric. Avoid coax that is designed for the CB market or do-it-yourself cable-TV market. (A good choice is Belden 8240 for the RG-58 or Belden 8241 for the RG-59.)

Both RG-58 and RG-59 with polyethylene dielectric have a velocity factor of 0.66. Therefore, for 146 MHz a quarter wavelength of transmission line will be 20.2 inches × 0.66 = 13.3 inches. A half-wavelength section will be twice this length or 26.7 inches. One thing you must take into account is that the transmission line is the total length of the cable *and the connectors*. Depending on the type of construction and the type of connectors that you choose, the actual length of the coax by itself will vary somewhat. You will have to determine that for yourself.

Y connectors that mate with RCA phono plugs are widely available and the phono plugs are easy to work with. Avoid the temptation, however, to substitute these for the T and BNC connectors. Phono plugs and a Y connector were tried. The results with that system were not satisfactory. The performance seemed to change from day to day and the notch was never as deep as it should have been. Although they are more difficult to find, BNC T connectors will provide superior performance and are well worth the extra cost. If you must make substitutions, it would be preferable to use UHF connectors (type PL-259).

Fig 29 shows a simple support for the antenna. PVC tubing is used throughout. Additionally, you will need a T fitting, two end caps, and possibly some cement. (By not cementing the PVC fittings together, you will have the option of disassembly for transportation.) Cut the PVC for the dimensions shown, using a saw or a tubing cutter.

Fig 30—At the left, A_T represents the antenna of the hidden transmitter, T. At the right, rapid switching between antennas A_1 and A_2 at the receiver samples the phase at each antenna, creating a pseudo-Doppler effect. An FM detector detects this as phase modulation.

Fig 31—If both receiving antennas are an equal distance (D) from the transmitting antenna, there will be no difference in the phase angles of the signals in the receiving antennas. Therefore, the detector will not detect any phase modulation, and the audio tone will disappear from the output of the detector.

A tubing cutter is preferred because it produces smooth, straight edges without making a mess. Drill a small hole through the PC board near the female BNC of each element assembly. Measure the 20-inch distance horizontally along the boom and mark the two end points. Drill a small hole vertically through the boom at each mark. Use a small nut and bolt to attach each element assembly to the boom.

Tuning

The dimensions given throughout this section are those for approximately 146 MHz. If the signal you will be hunting is above that frequency, then the measurements should be a bit shorter. If you wish to operate below that frequency, then they will need to be somewhat longer. Once you have built the antenna to the rough size, the fun begins. You will need a signal source near the frequency that you will be using for your RDF work. Adjust the length of the radiators and the spacing between them for the deepest

null on your S meter. Make changes in increments of $^1/_4$ inch or less. If you must adjust the phasing line, make sure that the $^1/_4$-wavelength section is exactly one-half the length of the half-wavelength section. Keep tuning until you have a satisfactorily deep null on your S meter.

THE DOUBLE-DUCKY DIRECTION FINDER

For direction finding, most amateurs use antennas having pronounced directional effects, either a null or a peak in signal strength. FM receivers are designed to eliminate the effects of amplitude variations, and so they are difficult to use for direction finding without looking at an S meter. Most modern HT transceivers do not have S meters.

This classic "Double-Ducky" direction finder (DDDF) was designed by David Geiser, WA2ANU, and was described in *QST* for July 1981. It works on the principle of switching between two nondirectional antennas, as shown in **Fig 30**. This creates phase modulation on the incoming signal that is heard easily on the FM receiver. When the two antennas are exactly the same distance (phase) from the transmitter, as in **Fig 31**, the tone disappears. (This technique is also known in the RDF literature as *Time-Difference-of-Arrival*, or TDOA, since signals arrive at each antenna at slightly different times, and hence at slightly different phases, from any direction except on a line perpendicular to and halfway in-between the two antennas. Another general term for this kind of two-antenna RDF technique is *interferometer*. —*Ed.*)

In theory the antennas may be very close to each other, but in practice the amount of phase modulation increases directly with the spacing, up to spacings of a half wavelength. While a half-wavelength separation on 2 meters (40 inches) is pretty large for a mobile array, a quarter wavelength gives entirely satisfactory results, and even an eighth wavelength (10 inches) is acceptable.

Think in terms of two antenna elements with fixed spacing. Mount them on a ground plane and rotate that ground plane. The ground plane held above the hiker's head or car roof reduces the needed height of the array and the directional-distorting effects of the searcher's body or other conducting objects.

The DDDF is bidirectional and, as described, its tone null points both toward and away from the signal origin. An L-shaped search path would be needed to resolve the ambiguity. Use the techniques of triangulation described earlier in this chapter.

Specific Design

It is not possible to find a long-life mechanical switch operable at a fairly high audio rate, such as 1000 Hz. Yet we want an audible tone, and the 400- to 1000-Hz range is perhaps most suitable considering audio amplifiers and average hearing. Also, if we wish to use the transmit function of a transceiver, we need a switch that will carry per-

Fig 32—Schematic diagram of the DDDF circuit. Construction and layout are not critical. Components inside the broken lines should be housed inside a shielded enclosure. Most of the components are available from RadioShack, except D1, D2, the antennas and RFC1-RFC3. These components are discussed in the text. S1—See text.

haps 10 W without much problem.

A solid-state switch, the PIN diode is used. The intrinsic region of this type of diode is ordinarily bare of current carriers and, with a bit of reverse bias, looks like a low-capacitance open space. A bit of forward bias (20 to 50 mA) will load the intrinsic region with current carriers that are happy to dance back and forth at a 148-MHz rate, looking like a resistance of an ohm or so. In a 10-W circuit, the diodes do not dissipate enough power to damage them.

Because only two antennas are used, the obvious approach is to connect one diode *forward* to one antenna, to connect the other *reverse* to the second antenna and to drive the pair with square-wave audio-frequency ac. **Fig 32** shows the necessary circuitry. RF chokes (Ohmite Z144, J. W. Miller RFC-144 or similar vhf units) are used

to let the audio through to bias the diodes while blocking RF. Of course, the reverse bias on one diode is only equal to the forward bias on the other, but in practice this seems sufficient.

A number of PIN diodes were tried in the particular setup built. These were the Hewlett-Packard HP5082-3077, the Alpha LE-5407-4, the KSW KS-3542 and the Microwave Associates M/A-COM 47120. All worked well, but the HP diodes were used because they provided a slightly lower SWR (about 3:1).

A type 567 IC is used as the square-wave generator. The output does have a dc bias that is removed with a nonpolarized coupling capacitor. This minor inconvenience is more than rewarded by the ability of the IC to work well with between 7 and 15 volts (a nominal 9-V minimum is recommended).

Fig 33—Ground-plane layout and detail of parts at the antenna connectors.

Fig 34—Photo of Fox-Hunting DF Twin 'Tenna set up as a horizontally polarized, 3-element Yagi.

The nonpolarized capacitor is also used for dc blocking when the function switch is set to XMIT. D3, a light-emitting diode (LED), is wired in series with the transmit bias to indicate selection of the XMIT mode. In that mode there is a high battery current drain (20 mA or so). S1 should be a center-off locking type toggle switch. An ordinary center-off switch may be used, but beware. If the switch is left on XMIT you will soon have dead batteries.

Cables going from the antenna to the coaxial T connector were cut to an electrical $^1/_2$ wavelength to help the open circuit, represented by the reverse-biased diode, look open at the coaxial T. (The length of the line within the T was included in the calculation.)

The length of the line from the T to the control unit is not particularly critical. If possible, keep the total of the cable length from the T to the control unit to the transceiver under 8 feet, because the capacitance of the cable does shunt the square-wave generator output.

Ground-plane dimensions are not critical. See **Fig 33**. Slightly better results may be obtained with a larger ground plane than shown. Increasing the spacing between the pickup antennas will give the greatest improvement. Every doubling (up to a half wavelength maximum) will cut the width of the null in half. A 1° wide null can be obtained with 20-inch spacing.

DDDF Operation

Switch the control unit to DF and advance the drive potentiometer until a tone is heard on the desired signal. Do not advance the drive high enough to distort or "hash up" the voice. Rotate the antenna for a null in the fundamental tone. Note that a tone an octave higher may appear.

If the incoming signal is quite out of the receiver linear region (10 kHz or so off frequency), the off-null antenna aim may present a fairly symmetrical AF output to one side, **Fig 35A**. It may also show instability at a sharp null position, indicated by the broken line on the display in Fig 35B. Aimed to the other side of a null, it will give a greatly increased AF output, Fig 35C. This is caused by the different parts of the receiver FM detector curve used. The sudden tone change is the tip-off that the antenna null position is being passed.

The user should practice with the DDDF to become acquainted with how it behaves under known situations of signal direction, power and frequency. Even in difficult nulling situations where a lot of second-harmonic AF exists, rotating the antenna through the null position causes a very distinctive tone change. With the same frequencies and amplitudes present, the quality of the tone (timbre) changes. It is as if a note were first played by a violin, and then the same note played by a trumpet. (A good part of this is the change of phase of the fundamental and odd harmonics with respect to the even harmonics.) The listener can recognize differences (passing through the null) that would give an electronic analyzer indigestion.

A FOX-HUNTING DF TWIN 'TENNA

Interferometers give sharp bearings, but they lack sensitivity for distant work. Yagis are sensitive, but they provide relatively broad bearings. This project yields an antenna that blends both on a single boom to cover both ends of the hunt. This is a condensation of a October 1998 *QST* article by R. F. Gillette, W9PE.

A good fox-hunting antenna must meet a number of criteria: (1) small size, (2) gain to detect weak signals and (3) high directivity to pinpoint the fox. Small antennas, however, do not normally yield both gain and direc-

Fig 35—Schematic of the Yagi/interferometer antenna system.

Table 1

Yagi Design

Item	Overall Length	Boom to Element Tip
	(Inches)	(Inches)
Director length	34.75	17.00
Director to Driven El. spacing	15.75	16.00
Driven El. length	37.75	18.50
Driven El. to Reflector spacing	15.75	16.00
Reflector length	40.75	20.00
*SWR less than 1.3:1 from 144.5 to 148 MHz		

tivity. By combining two antennas, all three requirements are satisfied in a way that makes a nice build-it-yourself project.

This antenna uses slide switches to configure it as either a Yagi or a single-channel interferometer. When used as an interferometer, a GaAs RF microcircuit switches the FM receiver between two matched dipoles at an audio frequency. To make the antenna compact W9PE used hinged, telescopic whips as the elements; they collapse and fold parallel to the boom for storage.

The Yagi

The Yagi is a standard three-element design, based on 0.2-λ spacing between the director, the driven element

and the reflector. It yields about 7 dBi gain and a front-to-back ratio of over 15 dB. Because a slide switch is used at the center of each element and the elements have small diameters, their resonant lengths are different from typical ones. **Table 1** shows the sizes used and **Fig 34** shows the Yagi.

To make sure that radiation from the coax does not affect the pattern, the author used some ferrite beads as coaxial choke-baluns. This also prevents objects near the coax from affecting signal-strength readings. The Yagi also has a low SWR; with uncalibrated equipment, he measured less than 1.3:1 over most of the 2-meter band.

This Yagi has a lot more gain than a "rubber ducky," but we need more directivity for fox hunting. That's where the interferometer comes in.

An Interferometer

To form the interferometer, the two end elements are converted to dipoles and the center element is disabled. When the three switches in **Fig 35** are thrown to the right, the feed line to the receiver is switched from the center element to the RF switch output, and the end elements are connected via feed lines to the RF switch inputs. With the Yagi's feed point open and the driven element equidistant from both interferometer antennas, the center element should have no effect on the interferometer. Nonetheless, it's easier to collapse the driven-element whips and get them out of the way than to worry about spacing.

Now if both interferometer coax cables are of equal length (between the antennas and switch) and the two antennas are the same distance from the transmitter (broadside to it), the signals from both antennas will be in phase. Switching from one antenna to the other will have no effect on the received signal. If one antenna is a little closer to the transmitter than the other, however, there will be a phase shift when we switch antennas.

When the antenna switch is at an audio rate, say 700 Hz, the repeated phase shifts result in a set of 700 Hz sidebands. At this point, all that was needed was a circuit to switch from one antenna to the other at an audio rate. W9PE chose a low-cost Mini-Circuits MSWA-2-20 GaAs RF switch driven by a simple multivibrator and buffer. The GaAs switch is rated to 2.0 GHz, hence this switching concept can easily be scaled to other ham bands. The PC board should work through the 440 MHz ham band. The author suggests adding a ground plane under the RF portion of the PC board and testing it before using it at a higher frequency.

The RF switch is controlled by a set of equal-amplitude, opposite-phase square waves: 0 V at one control port and –8 to –12 V at the other. (Mini Circuits is unclear about maximum voltages for this device. For safety, don't power it with more than 9 V.—*Ed*.) The opposite controls the other switch position. A 9-V battery was used as the power supply, with the positive terminal grounded. This results in a 0 V control signal to

Table 2
Bill of Materials

Quantity	Item
3 ft	$^3/_4$-inch aluminum U channel
6 sets	insulated shoulder washers for elements
1	9 V battery
1	9 V battery connector
1	10 µF, 16 V electrolytic capacitor
1	0.01 µF, 25 V capacitor
2	0.022 µF, 25 V capacitor
2	1 kΩ $^1/_8$ W resistor
2	4.7 kΩ $^1/_8$ W resistor
2	10 kΩ $^1/_8$ W resistor
2	47 kΩ $^1/_8$ W resistor
2	1 kΩ $^1/_8$ W resistor
4	2N2222 transistors
1	Mini-Circuits MSWA-2-20 (Mini-Circuits Labs, 13 Neptune Ave, Brooklyn, NY 11235; tel 718-934-4500, 417-335-5935, fax 718-332-4661; e-mail **sales@minicircuits.com**; URL **www.minicircuits.com**)
3	DPDT slide switch (1$^1/_8$-inch, 29 mm, mounting centers), Stackpole, 3 A, 125 V used
10 ft	50 Ω coax (0.140-inch maximum OD)
1	coaxial connector (receiver dependent)
1	lot, mounting hardware
1	lot, heat-shrink tubing or equal
4	cable ties
1	2 × 3.5-inch single-sided fiberglass PC board
1	1-inch PVC conduit
12	#FB-20 ferrite beads 0.14-inch ID, 0.5-inch long (All Electronics Corp: PO Box 567, Van Nuys, CA 91408-0567; tel 888-826-5432, fax 818-781-2653, e-mail: **allcorp@allcorp.com**; URL **www.allcorp.com/**.)
6	20$^1/_2$-inch telescoping antenna elements (Nebraska Surplus, tel 402-346-4750; e-mail **grinnell@probe.net**)
1	Special resist film (Techniks Inc, PO Box 463, Ringoes, NJ 08551; tel 908-788-8249, fax 908-788-8837; e-mail **techniks@idt.net**; URL **www.techniks.com/**)

the RF switch when the buffer transistor is off and a Vsat (about 0.2 V less than the –9 V battery: –8.8 V) signal when the buffer transistor is saturated. The multi-vibrator has two outputs, and each drives a buffer resulting in the required equal-and-opposite-phase drive signals.

Circuit Construction

After he selected the Mini-Circuits RF switch, W9PE realized that its small size would be best handled with a simple PC board. He made the prototype boards with a photocopy transparency technique.

A power on-off switch was not used, as the 9-V bat-

3/4" Aluminum U Boom Drilling

Drill 6 at 5/32"

Center 3 at 1/4"× 1/2"

3/4"

3/4"

1-1/8"

1/2"

1/4"

Drill 6 at Insulated-Bushing Size

16"

16"

1/2"

33"

(A)

Fig 36—Boom-drilling and mast-machining details.

3/4"

1-3/8"

1" PVC Mast Machining

1"

1/4"

NOTE: Cut a 1/2" wide ring from a PVC union that will slip over the prongs; heat prongs to bend out forming a small detent. With mast in place, (horizontal or vertical) the ring slipped over the prongs will lock the mast.

(B)

tery connector serves the same function. The battery fits tightly in the $^{3}/_{4}$-inch U channel. W9PE covered the circuit board with a plastic-lined aluminum cover, but plastic film and some aluminum foil, provide the same function. A cable tie will strap either into the U channel.

Table 2 is a complete bill of materials. You can use any telescoping elements, providing that they extend to over 20 inches and have a mounting stud long enough to accommodate the insulated washers. As an alternate to the stud, they can have ends tapped to receive a screw for the insulated mounting. The author picked up his elements at a hamfest from the vendor listed; they are also available from most electronic parts houses. The Mini-Circuit RF switch is a currently available part.

Antenna Construction

Fig 35 shows the antenna schematic. It shows all three switches in the Yagi position; each would slide to the right for interferometer use. Slide switches work pretty well at 2 meters. Each of the elements is mounted to the boom with insulating washers, and a strip of copper stock connects each element to its slide switch. (You can sub-

stitute copper braid, solder wick, coax shield or any short, low resistance, low inductance conductor for the copper stock.) This switching arrangement allows you to switch the reflector and director from being parasitic elements (electrically continuous) to being dipoles (center fed).

Because the elements telescope, you can adjust the interferometer dipoles to exactly equal lengths each time you switch the antenna configuration from Yagi to interferometer. Again, choke baluns block RF on the outside of each element's coax.

Caution: Do not transmit when the RF switch is selected. Transmit only when in the Yagi configuration. RF power will destroy the Mini-Circuits RF switch. To be safe, lock out your transmit function. Most HTs have this capability. When using a mobile radio, disconnect the microphone. It is, however, safe to transmit in the Yagi configuration—which is nice for portable operating.

Fig 36 gives dimensions for drilling a standard $^{3}/_{4}$-inch aluminum U channel for the boom and shows how the author cut a 1-inch PVC pipe (plastic conduit) for a mast and a mast locking ring. If PVC conduit is not available in your area, PVC water pipe (and a PVC union for

the locking ring) will work. This mast allows mounting the antenna for either vertical or horizontal polarization.

Be sure to test the plastic pipe you use for low RF loss. Do this by heating a sample in a microwave oven. Place a pipe sample and a glass of water in the oven. (The sample is not placed in the glass of water; the water keeps the microwave from operating without a load.) Bring the water to a boil, and then carefully check the sample's temperature. If the sample is not hot, its RF loss is low, and the plastic can be used.

Using the Antenna

When starting a hunt, set up the Yagi antenna by placing all switches in the Yagi position. Swing all of the telescoping elements perpendicular to the boom and set the whip lengths to achieve the proper element lengths, while keeping each element symmetrical about the boom. The cables or boom can be marked with the length data.

While the signal is weak, use the Yagi. It has 7 dBi gain, but its bearing resolution is only about 20°. When the signal gets stronger, use the interferometer. It has less gain, but its bearing resolution is better than 1°. If the fox transmitter begins overloading your receiver, collapse the whips (equally) to reduce the gain and continue triangulating. Near the transmitter, you should triangulate both horizontally (azimuth) and vertically (elevation). The antenna works both ways, and the transmitter may be located above or below you.

Antenna Alternative

As an alternative to the telescoping elements, George Holada, K9GLJ, suggested using fixed-length elements with banana plugs matched to banana jacks on the boom. Three pairs would be used for the Yagi, an extra driven-element pair for the interferometer mode and two short-element pairs to reduce the received signal level if an overload condition occurs. He also suggested a PVC boom allowing the elements to be stored inside the boom.

THE FOUR-WAY MOBILE DF SYSTEM

This innovative, yet simple, RDF antenna system was described in an article by Malcolm C. Mallette, WA9BVS, in November 1995 *QST*. It is derived from the TDOA design shown earlier in this chapter by David T. Geiser, WA2ANU, and by a design by Paul Bohrer, W9DUU. (See Bibliography.)

Direction-finding often involves two different activities: DFing on foot and DFing from a vehicle. Often, you must track the signal using a vehicle, then finish the hunt on foot. Whether on foot or in a vehicle, the primary problem you'll encounter when trying to locate the transmitter is multipath reception. Multipath reception involves receiving the same signal by more than one path, one signal from the true direction of the transmitter and others by reflected paths that may come from widely different directions. VHF and UHF signals bounce off almost any

object and hide the true source of a signal. For example, if there's a large metal building north of you, a signal from the south may arrive from the north because the signal bounces off the building and back to you.

Multipath reception effects can be defeated by taking a number of readings from different positions and arriving at an average direction. While moving at road speeds in a vehicle, it's possible to take a number of readings from different positions and average them, and it's also possible to average a number of readings over a distance of travel by electronic means. The true bearing to the transmitter can usually be found by either method.

DFing equipment for use on foot is simpler than systems for use on a vehicle. While afoot, you can turn at will or easily rotate an antenna. Turning a vehicle while going down a street may result in a fender-bender if you're not careful!

The simplest DFing system to use while on foot consists of an S-meter-equipped hand-held receiver and a small, hand-held Yagi with an attenuator in line between the antenna and receiver. The attenuator keeps the S meter from pinning. The direction in which the beam points when the strongest signal is received is the direction of the transmitter. Of course, you'll want to take readings at several locations at least a wavelength apart to obtain an average heading, as multipath reception can still cause false readings in some locations.

Another approach that many hams have taken is the simple WA2ANU DDFF—it is now commonly known simply as the "buzzbox." Various commercial versions of the hand-held buzzbox system are available. Some sys-

Fig 37—Front panel of the Four-Way DFer. At the extreme left of the front panel is the VOLUME control. Immediately to the right is the RCV/OFF/DF center-off toggle switch, with the damping (DMP) control switch nearby. Four LEDs mounted in a diamond pattern indicate signal direction: front (yellow), right (green), back (orange) and left (red). The horizontally mounted zero-center meter indicates left/right signal reception, the vertically mounted meter displays front/back signal reception. A small speaker is mounted on the top cover.

Fig 38—Placement of the four antennas on the author's car roof. The small object to the left of the antennas is the switch board.

tems have been upgraded to indicate whether the signal is arriving from the left or right of your position. The main drawback, however, to the buzzbox is that it's not as sensitive as a simple dipole and not nearly as sensitive as a beam.

In theory, you could take a buzzbox or Yagi/attenuator system in a car, stop periodically, get out and check the direction to the transmitter, then climb back in and drive off. Although this procedure works, it isn't very practical—it takes a long time to find the transmitter.

This design is for a left-right, front-back box (LRFB box) that indicates whether the received signal is to the left or right and whether it is to the front or back of the receiver. The location display consists of four LEDs arranged in a diamond pattern (see the title-page photo). When the top LED is on, the signal is coming from the front. When the top and right LEDs are on, the transmitter is between the front and the right. When only the right LED is on, the signal is directly to the right. When the bottom LED and right LED are on, the transmitter is to the right and to the back. The same pattern occurs around the clock. Therefore, four LEDs indicate eight directions. As most highways and streets have intersections that force a driver to choose moving straight ahead, right or left, the indication is sufficiently precise for practical transmitter hunting.

If the four-LED display is used alone, all parts can be obtained from your local Radio Shack store. Two zero-center 50-µA meters (50-0-50)—M1 and M2—can be used in addition to, or in place of, the LEDs, but RadioShack does not stock such meters. **Fig 37** shows the front panel layout of the LRFB.

The LRFB box uses four mag-mount $^1/_4$-λ antennas placed on the vehicle roof as shown in **Fig 38**. The whips in the mag mounts can be changed to $^1/_4$-λ 440-MHz whips and the antennas placed closer together when switching from 144-MHz to 440-MHz operation.

Circuit Description

See **Fig 39** in the following discussion (pages 26 and 27). U2, a 555 timer, generates a string of square-wave pulses at pin 3. The pulse frequency is determined by the setting of R4. The pulses are fed to the clock input (pin 14) of U3, a 4017 decade counter. On the first pulse, a positive voltage appears at U3, pin 3. On receipt of the second pulse from U2, pin 3 of U3 goes to ground and a positive voltage appears on pin 2. This sequence continues on successive pulses from U2 as pins 3, 2, 4, 7, 10, 1, 5, 6, 9 and 11 go positive in succession.

D1 through D5, and D6 through D10, OR the pulses. The result is that TP3 goes positive on the first pulse from U2, while TP2 is at 0 V. The next pulse of U2 results in TP2 going positive and TP3 going to 0 V. This sequence repeats as the counter goes around to make pin 3 positive again, and recycles.

Antenna Switching

U2 and U3 produce alternating pulses at TP2 and TP3. If we wanted only to alternately turn on and off two antennas, we could use the pulses at TP2 and TP3. The design ensures that the pulses at TP2 are the same length as the pulses at TP3. For the LRFB box, however, we need to switch between the left-right antennas many times, then switch between the front-back antennas many times.

Pin 12 of U3, CARRY OUT, emits a pulse every time U3 counts through its cycle of 10 pulses. The carry pulses from U3 go to U4, pin 14, the clock input of that 4017 counter. As U4 cycles, its output pins pulse; those pulses are, in effect, directed by D11 through D20.

As a result, TP4 is positive during the first 50 pulses from U2 and TP5 is positive during the second 50 pulses of U2. Q1 through Q6 form a quad AND gate. They AND the pulses at TP4 and TP5 with the alternating pulses at TP2 and TP3 so that the result is a pulse at the base of Q9, followed by a pulse at the base of Q10, a pulse at the base of Q9, and so on. The pulses alternate 25 times between Q9 and Q10. Then, as TP4 goes to 0 V, TP5 rises from 0 V to some positive voltage and the alternating pulses appear at the bases of Q7 and Q8. The pulses alternately go to the bases of Q7 and Q8 25 times. Then they alternate between the bases of Q9 and Q10 25 times. This pattern continues as long as the unit is in DF operation.

In **Fig 40**, two leads of a four-conductor-plus-ground cable to the antenna-switch board are connected to points A and B. The same pulses that turn Q7 and Q8 off and on turn on and off the left and right antennas. One of those two antennas is turned on and off in phase with Q7 and the other is turned on and off in phase with Q8. The PHASE switch, S3, determines which antenna is in phase with which transistor. Similarly, the two front/back antennas are turned on and off in phase with Q9 and Q10, and S4 determines which antenna is in phase with which transistor.

The pulses arriving at points A and B turn on and off the diodes connecting the coax of the left and right

Fig 39—Unless otherwise specified, part numbers in parentheses are RadioShack. All fixed-value resistors are ¼-W, 5%-tolerance units. Equivalent parts can be substituted.

C1, C15—0.1-µF, 50-V (272-1069)
C2—10-µF, 35-V electrolytic capacitor (272-1025)
C3—0.01-µF, 25-V disc-ceramic capacitor (272-131)
C4, C5—1-µF, 16-V electrolytic capacitor (272-1434)
C6—0.001-µF, 25-V disc-ceramic capacitor (272-126)
C7, C9—100-µF, 6.3-V bipolar (nonpolarized) capacitor;
  Digi-Key P-1102, available from Digi-Key Corp, 701
  Brooks Ave S, PO Box 677, Thief River Falls, MN
  56701-0677, tel 800-344-4539, 218-681-6674; fax: 218-
  681-3880; RadioShack stocks 100-µF, 35-V axial (272-
  1016) and radial-lead (272-1028) electrolytic
  capacitors.
C8, C10—4700-µF, 6.3-V bipolar capacitor (made of five
  1000-µF, 6.3-V bipolar capacitors), Digi-Key P1106.

Standard 1000-µF, 35-V radial and axial-lead
electrolytic capacitors are available from
RadioShack; a 4700-µF, 35-V axial-lead electrolytic
capacitor is also available (272-1022). Note that C7,
C8, C9 and C10 are non-polarized capacitors because
a small reverse voltage can appear across the meter
and capacitors when the system is in use. Standard
polarized electrolytics have been used in a number of
units using this circuit (the same detector circuit
used in W9DUU's unit) without any known ill effects,
however.
D1-D20—1N914 silicon switching diode (276-1620 or
  276-1122)
F1—2-A fuse (270-1007)
LS1—8-W speaker (40-245)

M1, M2—Zero-center, 50-µA meter; optional—see text
Q1-Q10—MPS2222 or 2N2222 NPN silicon general-
  purpose transistors (276-2009)
R1, R24, R27—4.7 kΩ (271-281); note: many of the
  fixed-value resistors can be found in RadioShack
  resistor assortment packages 271-308 and 271-312.
R2, R12, R14, R16, R18—220 Ω (271-1330)
R3, R25, R26, R28, R29—1 kΩ (271-1321)
R4—100-kΩ trimmer potentiometer (271-284)
R5—10 kΩ (271-1335)
R6, R8, R21, R22—100 kΩ (271-1347)
R7, R9, R11, R13, R15, R17—47 kΩ (271-1342)
R10—1-kΩ trimmer potentiometer (271-280)
R19—25-Ω panel-mount potentiometer (271-265A)

R23—1 MΩ (271-1134)
R45—1.5 kΩ (part of 271-312 assortment)
S1—SPDT, center-off switch (275-325)
S2—DPDT switch (275-626)
T1—8-Ω to 1-kΩ audio-output transformer (273-1380)
U1—LM317T, 1.5-A, three-terminal, adjustable voltage
  regulator (276-1778)
U2—555 timer (276-1723)
U3, U4—4017 decade counter (276-2417)
U5—LM741 op amp (276-007)
Misc: two 8-pin IC sockets (276-1995); two 16-pin IC
  sockets (276-1992); experimenter's PC board (276-
  148) or FAR Circuits PC board set; enclosure; four
  mag-mount antennas, four-conductor shielded cable;
  in-line fuse holder (270-1281).

Fig 40—Schematic of the antenna switch board. Part numbers in parentheses are RadioShack. All fixed-value resistors are $^1/_4$-W, 5%-tolerance units. Equivalent parts can be substituted.

D22-D25—1N914 silicon switching diode (276-1620 or 276-1122)

J1—Six-pin female Molex connector (274-236 or 274-155)

P1—Six-pin male Molex connector (274-226 or 274-152)

R50-R54—2.2 kΩ (can be found in RadioShack resistor assortment packages 271-308 and 271-312); also available in pack of five (271-1325)

S3, S4—DPDT switch (275-626)

Fig 41—Schematic of the LED driver circuit. Part numbers in parentheses are RadioShack. All fixed-value resistors are $^1/_4$-W, 5%-tolerance units. Equivalent parts can be substituted.

C11-C14—0.1-μF, 25-V disc-ceramic capacitor (272-135)

D21—1N4733, 5.1-V, 1-W Zener diode (276-565)

DS1-DS4—LEDs; one each red (276-066); green (276-022); yellow (276-021); orange (276-012)

R30, R32, R41, R43—10 kΩ (271-1335)

R34, R39, R40, R61—470 kΩ (271-1354)

R35-R38—1 kΩ (271-1321)

R31, R33, R42, R44—100-kΩ trimmer potentiometer (271-284)

U6, U7—LM339 quad comparator (276-1712)

Misc: two 14-pin IC sockets (276-1999)

antennas to the receiver coax. This occurs 25 times, thereby switching the receiver between the left and right antennas 25 times. Similar switching then occurs between the front and the back antennas from pulses arriving at points C and D.

Detector Circuit

The detector circuit (back again in Fig 39) starts with

U5, a 741 op amp that amplifies the receiver's audio output. The audio is fed into R24 and R27, two 4.7-kΩ pots. The zero-center, 50-μA meters across R24 and R27 are optional. The meters, as well as the LEDs, indicate front/back and left/right. Such meters can be expensive unless you find surplus meters, and they're not really necessary.

When the left/right antennas are active, one end of R24 is grounded by Q7 and Q8 on each alternate pulse.

If Q7 is conducting, Q8 is not conducting. On each pulse, one of the left/right antennas is turned on and one end of R24 is grounded. On the next pulse, the other left/right antenna is turned on and the other end of R24 is grounded. If there is a phase difference between the signal received by the left antenna and the signal received by the right antenna, a dc voltage is built up across R24. That voltage causes the quad comparator, U7 in **Fig 41** to turn on DS3 (red) or DS4 (green) L/R LEDs. If the optional left/right meter is installed, it deflects to indicate the direction as do the LEDs.

After 25 cycles, the left and right antennas are both turned off and the front and back antennas are cycled on and off 25 times with the same detection process, producing a voltage across R27 if there is a phase difference between the RF received by the front and the back antennas. That voltage across R27 causes quad comparator U6 to turn on DS1 or DS2.

C9 and C10, for the F/B detector, and C7 and C8, for the L/R detector, damp the voltage swings caused by multipath reception. To control damping, S2A and S2B switch the 4700-µF capacitors in or out of the circuit. You want the greatest amount of damping when you drive through an area with a lot of multipath propagation (as from buildings); a lot of damping helps under those circumstances.

Construction

The prototype was built using a pad-per-hole RadioShack board. However, a PC board makes construction a lot faster. Far Circuits offers a printed-circuit project on their Web site: **www.cl.ais.net/farcir**). Except for the optional meters and the nonpolarized capacitors, most parts are available from RadioShack.

First build the power supply so you can power the unit from your car or another 12-V source. Apply 12 V to the DFer and adjust R1 until U1's output is +9 V. (You can use a 9-V battery and omit the power-supply section, but you'd better take along a spare battery when you go DFing.)

Install U2 and its associated parts. Power up and turn on S1. A string of pulses should appear at TP1. If you have a frequency counter, set R4 for a pulse frequency of 2200 Hz at TP1. If you don't have a counter, connect a 0.1-µF capacitor from TP1 to headphones or a small speaker and set R4 for a tone of about 2 kHz. Later, you'll adjust the clock so the unit works with the passband of your receiver.

Turn off S1 and remove the power source. Install U3 and its diodes. Pin 12 of U3 need not be connected yet. Apply power and turn on S1. At TP2 and TP3, you should find alternating 1100-Hz pulses. If you have a dual-trace scope, you can see that the pulses alternate. If you have a single-trace scope, connect TP3 to TP2 and to the scope input and the trace will appear as a solid line as there is a pulse at either TP2 or TP3 at all times. If you

don't have a scope, the tone in a speaker or earphones from TP2 or TP3 will sound half as high (about 1 kHz) as the tone at TP1.

Turn off S1. Install U4 and its diodes. Note that pin 12 of U3 is connected to pin 14 of U4. At TP4 and TP5, there should be long pulses—five times longer than the pulses at TP1, and the pulses should alternate between TP4 and TP5. The pulse frequency should be about 44 Hz. Power down and turn off S1. Install the remaining circuit components. When you power up, 25 alternating pulses should appear at A and B, then 25 alternating pulses should appear at C and D. Use a scope to verify that.

If you're not using the optional panel meters, connect a voltmeter across R24 (L/R BALANCE), using the lowest dc-voltage range. Note that neither end of R24 is grounded. With no audio input, adjust R24 until there is no voltage across it. Do the same with R27 (F/B BALANCE). If you use the optional meters, adjust R24 and R27 so there's no current shown on either meter.

Power down and assemble the rest of the circuit. With power applied, but with no audio input, adjust R31, 33, 42 and 44 so that the four LEDs (DS1 through DS4) are off. The objective of the following adjustments is to get the red and green LEDs to turn on with the same voltage amplitude, but opposite polarity, across R24. Move R24's wiper so a low positive voltage appears across R24, as indicated by the voltmeter connected across R24 or movement of the panel-meter needle. Adjust R44 (LED ADJ 1A) and R42 (LED ADJ 1B) so that the green LED (DS4) comes on when the voltage goes positive at one end of

Fig 42—An inside view of one DF unit built into a 2 × 8 × 5³/₄-inch (HWD) box. Because of the height restriction, the two 4700-µF damping capacitors (C8 and C10) are not mounted on the PC board, but near the rear panel behind the smaller of the two PC boards. One of the 4700-µF damping capacitors is a standard electrolytic, the other is a parallel combination of five 1000-µF, 6.3-V bipolar (nonpolarized) capacitors wrapped in electrical tape.

Fig 43—The rear panel of the DF unit supports the two DPDT PHASE toggle switches. Grommets in the panel holes allow abrasion-free passage of the antenna, dc-power and audio cables. The dc power cord is outfitted with an inline fuse holder and a male Jones plug. A six-pin female Molex connector (five pins are used) feeds the four antennas. The audio-input cable is terminated in a $1/8$-inch diameter male plug.

R24, but goes off when R24 is adjusted for 0 V across R24.

Next, adjust R24 for a slight negative-voltage indication and adjust R42 and R44 so that the red LED (DS3) comes on, but extinguishes when the voltage across R24 is 0 V. When you're done, adjusting R24's wiper slightly one way should illuminate the red LED. Both LEDs should be off when there's no voltage across R24; rotating R24's wiper slightly in the opposite direction should turn on the green LED.

Connect the voltmeter across R27 or use the panel meter as an indicator. With no audio input, adjust R27 so that there's no voltage across R27. Adjust R31 (F/B LED ADJ 1A) and R33 (F/B LED 1B) so that a F/B LED (DS1) is on when there is a slight positive voltage across R27 and the other F/B LED (DS2) is on when there is a negative voltage across R27.

Switch Board

Assemble the switch board for the four mag-mount antennas (see Fig 40). You can use half of a RadioShack dual pad-per-hole PC board (RS 276-148) as a platform. Lead length is critical only on this board and in the length of the coax from the switching board to the antennas, so avoid wire-wrap construction here.

Feed Lines

The coax lines from the switch board to each of the four antennas must be of equal length. The coax lengths should be long enough to permit each antenna to be placed slightly less than $1/4$ λ from its counterpart, at the lowest frequency of operation. (There's a local belief that $27^1/_2$ inches is the best length. The author used that length and it works, but other lengths might work as well.) An

attempt to locate the switch board inside the vehicle and run equal-length 12-foot-long cables to the antennas failed. Keep the switch board on the vehicle's roof.

Use the same type of coax for all lines—that is, don't mix foam and polyethylene dielectric coax on the antenna lines. If the velocity factor of the lines is not equal, a phase shift in the signals will exist even when the transmitter is dead ahead and it will lead you astray.

Solder the coax from the antennas directly to the board—don't use connectors. From the switch board to the receiver, use 50-Ω coax of any type and length. Equip the receiver end of the line with a connector that mates with your receiver's antenna-input jack. Make the four-conductor shielded cable from the main DFer box to the switch board long enough to reach from the LRFB box's operating position to the roof of the car. Construct the antennas so that the whips can be changed easily for use on any frequency in which you're interested.

Mechanical Assembly

Mount the finished PC boards in a metal box of your choice. You can follow the construction method used in the prototype (see **Fig 42** and **Fig 43**), but do ensure that R4 can be adjusted easily with a tuning tool from outside the box. A hole drilled in the box at the right point will suffice. Arrange the LEDs in a diamond pattern on the front panel, with the left LED (red) to the left, the right LED (green) on the right, and the front and back LEDs at the top and the bottom.

Wrap the switch board with tape to waterproof it, or place it in a watertight box. Arrange the mag-mount antennas on top of the vehicle in a diamond shape. The distance between each antenna pair should be less than $1/4$ λ at the operating frequency. (In limiting the distance between antennas in a pair—F/B or L/R—to less than $1/4$ λ, the author followed W9DUU's example.)

Final Adjustments

It's best to start on 2 meters. Install the 2-meter whips in the antenna bases. Mount the antennas on the top of your vehicle. Identify the left and right antenna bases with L and R, and mark the front and back antenna bases, too.

A good way to find out if the antennas are properly installed is to short either the left or right antenna with a clip lead from the whip to the metal base; the L/R meter will deflect one way and the left or right LED will light. If you short one of the front and back antennas with a clip lead, the front or back LED will come on. If you short one of the L/R antennas and it makes the meter go to the right, it does not necessarily mean you have the PHASE switch in the proper position. That depends on the relative phase determined by the number of audio stages in your receiver, each of which may contribute a shift of 180°.

Connect the coax from the switch board to your FM receiver. It must be an FM receiver; an AM VHF or AM aircraft receiver won't suffice. Connect the audio output

of your 2-meter receiver to the LRFB box audio input. If you're using a transceiver, disable its transmit function by removing the mike. You don't want to transmit into the switch board!

Turn on the receiver and place the LRFB box in receive by setting S1 to the RCV position. Center R10. Only one of the antennas will be turned on and the DF operation will be disabled. Back off the squelch and notice that you hear the audio from the speaker of the LRFB box. Switch to an unused simplex channel. Have a friend with an HT stand 20 feet or so in front of the vehicle. With the receiver in the car turned off, turn S1 to DF. The four LEDs should be off. If an LED lights, adjust R24 and R27 for zero voltage. If the LED is still on, readjust R31 and R33, or R42 and R44 as explained earlier. When all four LEDs are off with the antennas connected, no audio from the receiver and no RF input signal, you're ready. Turn on your receiver and have your friend transmit on the 2-meter frequency (simplex) that your receiver is set to. When he transmits, one or more of the LEDs should illuminate. Ignore the front/back LEDs, but check to see if the right or left LED is on. If the right LED is on and your friend is standing to the right of the center of the vehicle front, all is well. Have him walk back and forth in front of the vehicle and notice that when he is to the right, the green LED turns on, and when he's to the left, the red LED glows. If the indications are reversed, that is, if the LRFB box indicates left when your friend is to your right, reverse the position of PHASE switch S3.

When the L/R indicators are working properly, have your friend walk back and forth between a position 20 feet to the front and right of the car and a position 20 feet away to the rear and right of the car. The right LED should stay on, but the front LED should be on when the HT is in front of the antennas, and the back LED should be on when the HT is behind the antennas. If the front/back indications are reversed, reverse the position of PHASE switch S4.

While receiving a signal from your friend's HT, adjust R4 for maximum deflection on any one of the two optional meters, or on a voltmeter (set on the lowest dc voltage range) connected across R24 or R27. Look for the maximum deflection of the meter needle as the meter swings both ways while the signal source moves from back to front or left to right (depending, of course, on which panel meter you're looking at or which resistor—R24 or R27—your voltmeter is across). The audio passband of FM receivers varies, and if you switch from an ICOM IC-27 to an ICOM IC-W2A, for example, you'll have to change U2's master clock frequency. You may encounter receivers that don't require readjusting R4, but such readjustment should be expected. When changing receivers, you may also need to change the position of PHASE switches S3 and S4. This may also be necessary when changing from UHF to VHF, or VHF to UHF on the same receiver, as the number of receiver stages (and, hence, the audio phase) may change from band to band.

Audio Level Adjustments

With meter damping (S2) off, adjust R10 so that you have full deflection of one of the two meters (or your multimeter) with the signal source at a 45° angle from the vehicle (halfway between ahead and right), and a reasonable audio level from the speaker. Turn the rig's volume control all the way up to ensure that the audio circuit doesn't overload. If it overloads, the meters won't deflect. From zero to full blast, the meter should deflect more and more (unless the signal is straight ahead or exactly left or right). If you're using an H-T, maximum deflection of the meter should occur before the volume control is $^3/_4$ of maximum, or before the volume control is at $^1/_2$ of maximum if you're using a mobile rig. If R10 is properly adjusted, turning the volume control to maximum won't cause the meter to fall back toward zero. If increasing the volume causes the meter to deflect less, then R10's setting is too high.

Now have your friend walk around the vehicle with the HT transmitting and notice that the LEDs indicate the signal direction. On 2 meters in a clear field, the indications should be correct 80 or 90% of the time. The erroneous readings that occasionally occur are due to multipath propagation caused by the irregular shape of the vehicle. Slight adjustments in the positions of the L/R and F/B antennas may be necessary to make the zero points fall directly in front of the vehicle (neither left nor right LED on) and at the center of the antennas (neither front nor back LED on).

Try the same procedure on 440 MHz. You may have to flip the PHASE switches when you move to another band, even when using the same receiver. Remember that the total length of the 440-MHz antennas must be $^1/_4$ λ or less, and the antennas must be placed less than $^1/_4$ λ apart. The results on 440 MHz probably won't be as consistent as the results on 2 meters, as there is likely to be a lot more multipath propagation caused by the irregular shape of the vehicle.

Fox Hunting

Before heading out to find the fox, check to be certain the LRFB box is working properly. Tune to the fox's frequency and drive off. Turning on the DAMPING switch stabilizes the indication as you drive along. Follow indications generated as you travel over the road or street. If an indication is constant for 15 or 20 seconds while you're moving down the road, it's probably the true direction to the fox. It's possible to have a reflection from a mountain over a long distance down the road, however. When you can hear the fox with no antenna, it's time to get out of the car, switch to the hand-held system and hunt for the fox on foot.

If you switch to a new receiver, you may have to readjust R4, CLOCK FREQ. That's because both receivers may not have the same audio bandwidth. Author WA9BVS forgot this while chasing a balloon once and

the results were comical. When chasing balloons with ham radio transmitters, the readings you get are likely to be confusing when the balloon is at a high angle with respect to the plane of the car top. Use a hand-held Yagi to verify the balloon location. Even with a simple buzzbox, you should be able to find a keyed transmitter.

A TAPE-MEASURE BEAM FOR RDFING

Joe Leggio, WB2HOL, designed this antenna while searching for a beam with a really great front-to-back ratio to use in hidden transmitter hunts. It exhibits a very clean pattern and is perfect for RDF use. You can construct this beam using only simple hand tools, and it has been duplicated many times.

WB2HOL's first design requirement was to be able to get in and out of his car easily when hunting for a hidden transmitter. He accomplished this by using steel "tape-measure" elements, which fold easily when putting the antenna into a car and yet are self supporting. They also hold up well while crashing through the underbrush on a fox hunt.

WB2HOL decided to use three elements to keep the boom from getting too long. He used inexpensive

Fig 44—Tape-measure beam dimensions.

Fig 45—Photo of driven-element mounted to PVC tee using hose clamps. The hairpin match wires is shown here soldered to the tape-measure elements, along with the RG-58 feed line.

Fig 46—Photo of complete tape-measure beam, ready to hunt foxes!

Schedule-40 PVC pipe, crosses and tees that can be found at any hardware store for the boom and element supports.

He used a simple hairpin match, consisting of a 5-inch length of #14 solid wire bent into the shape of a U, with the two legs about $3/4$ inch apart. This gave in a very good match across the 2-meter band after he tweaked the distance (1-inch on his prototype) between the halves of the driven element for minimum SWR.

You can cut the 1-inch wide tape-measure elements with a pair of shears, chamfering the ends of the elements. Be very careful—the edges are very sharp and will inflict a nasty cut if you are careless. Use some sandpaper to remove the sharp edges and burrs and put some vinyl electri-cal tape on the ends of the elements to protect yourself from getting cut. Wear safety glasses while cutting the elements. See **Fig 44** for dimensions.

The RG-58 coax feed line is wound into a 8-turn coil along the boom to form a choke balun. The coil is covered with vinyl black tape to secure it to the boom. Make sure you scrape or sand the paint off the tape-measure elements where the feed line is attached. Most tape measures have a very durable paint finish designed to stand up to heavy use. You do not want the paint to insulate your feed-line connection!

If you are careful, you can solder the feed line to the element halves, but take care since the steel tape measure does not solder easily and the PVC supports can be easily melted. Tin the tape-measure elements before mounting them to the PVC cross if you decide to connect the feed line in this fashion.

If you decide not to solder to the tape-measure elements, you can use two other methods to attach the feed line. One method employs ring terminals on the end of the coax. The ring terminals are then secured under self-tapping screws or with 6-32 bolts and nuts into holes drilled in the driven-element halves. However, with this method you cannot fine-tune the antenna by moving the halves of the driven element in and out.

The simplest method is simply to slide the ends of the feed line under the driven element hose clamps and tighten the clamps to hold the ends of the coax. This is low-tech but it works just fine.

WB2HOL used $1^1/2$-inch stainless-steel hose clamps to attach each driven-element half to the PVC cross that acts as its support. This allowed him to fine-tune his antenna for lowest SWR simply by loosening the hose clamps and sliding the halves of the driven element in or out to lengthen or shorten the element. He achieved a 1:1 SWR at 146.565 MHz (the local fox-hunt frequency) when the two elements were spaced about 1 inch apart. **Fig 45** shows the hose-clamp method for attaching the driven element to the PVC cross, along with the hairpin wire and feed-line coax.

Some builders have used rubber faucet washers between the tape-measure elements and the PVC-cross fittings on the director and reflector. These allow for the tape to fit the contour of the PVC fitting better and will make the antenna look nicer. It is normal for the reflector and director elements to buckle a bit as they are tightened to the PVC tee and cross if you don't use faucet washers. You can also eliminate the buckling if you use self-tapping screws to attach these elements instead of hose clamps. The beam will not be as rugged, however, as when you use hose clamps.

This beam has been used on fox hunts, on mountain tops, at local public-service events, outdoors, indoors in attics—just about everywhere. The SWR is typically very close to 1:1 once adjusted. Front-to-back performance is exactly as predicted. The null in the rear of the pattern is perfect for transmitter hunts.

BIBLIOGRAPHY

Source material and more extended discussion of topics covered in this chapter can be found in the references given below and in the textbooks listed at the end of Chapter 2.

W. U. Amphar, "Unidirectional Loops for Transmitter Hunting," *QST*, Mar 1955.

G. Bonaguide, "HF DF—A Technique for Volunteer Monitoring," *QST*, Mar 1984.

D. S. Bond, *Radio Direction Finders*, 1st edition (New York: McGraw-Hill Book Co).

R. E. Cowan and T. A. Beery, "Direction Finding with the Interferometer," *QST*, Nov 1985.

D. DeMaw, "Beat the Noise with a Scoop Loop," *QST*, Jul 1977.

D. DeMaw, "Maverick Trackdown," *QST*, Jul 1980.

T. Dorbuck, "Radio Direction-Finding Techniques," *QST*, Aug 1975.

D. T. Geiser, "Double-Ducky Direction Finder," *QST*, Jul 1981.

D. T. Geiser, "The Simple Seeker," *The ARRL Antenna Compendium, Vol 3*, p 126.

N. K. Holter, "Radio Foxhunting in Europe," Parts 1 and 2, *QST*, Aug and Nov 1976.

J. Isaacs, "Transmitter Hunting on 75 Meters," *QST*, Jun 1958.

H. Jasik, *Antenna Engineering Handbook*, 1st edition (New York: McGraw-Hill, 1961).

R. Keen, *Wireless Direction Finding*, 3rd edition (London: Wireless World).

J. Kraus, *Antennas*, 2nd edition (New York: McGraw-Hill Book Co, 1988).

J. Kraus, *Electromagnetics*, 4th edition (New York: McGraw-Hill Book Co, 1992).

C. M. Maer, Jr., "The Snoop-Loop," *QST*, Feb 1957.

M. C. Mallette, "The Four-Way DFer," *QST*, Nov 1995. A set of two PC boards is available from FAR Circuits for the "Four-Way DFer" project. 18N640 Field Ct, Dundee, IL 60118-9269, tel 708-576-3540 (voice and fax). Note: No component pads for C15 exist. Mount C15 between U2 pin 5 and ground on the bottom (foil) side of the board. A PC-board template package is available from the ARRL free of charge. Send your request for the MALLETTE 4-WAY DFER, along with a business size SASE, to the Technical Department Secretary, 225 Main St, Newington, CT 06111-1494.

L. R. Norberg, "Transmitter Hunting with the DF Loop," *QST*, Apr 1954.

P. O'Dell, "Simple Antenna and S-Meter Modification for 2-Meter FM Direction Finding," Basic Amateur Radio, *QST*, Mar 1981.

Ramo and Whinnery, *Fields and Waves in Modern Radio* (New York: John Wiley & Sons, 1944).

F. Terman, *Electronic and Radio Engineering* (New York: McGraw-Hill Book Co, 1955).

Radio Direction Finding , published by the Happy Flyer, 1811 Hillman Ave, Belmont, CA 94002.

For more information on direction finding, see *The ARRL Handbook* and *Transmitter Hunting: Radio Direction Finding Simplified*, by Joe Moell, KØOV, and Thomas Curlee, WB6UZZ. These books are available from your local dealer or can be ordered directly from ARRL.

Chapter 15

Portable Antennas

For many amateurs, the words *portable antennas* may conjure visions of antenna assemblies that can be broken down and carried in a backpack, suitcase, golf bag, or what-have-you, for transportation to some out-of-the way place where they will be used. Or the vision could be of larger arrays that can be disassembled and moved by pickup truck to a Field Day site, and then erected quickly on temporary supports. Portable antennas come in a wide variety of sizes and shapes, and can be used on any amateur frequency.

Strictly speaking, the words "portable antenna" really means *transportable antenna*—one that is moved to some (usually temporary) operating position for use. As such, portable antennas are not placed into service when they are being transported. This puts them in a different class from mobile antennas, which are intended to be used while in motion. Of course this does not mean that mobile antennas cannot be used during portable operation. Rather, true portable antennas are designed to be packed up and moved, usually with quick reassembly being one of the design requisites. This chapter describes antennas that are designed for portability. However, many of these antennas can also be used in more permanent installations.

Any of several schemes can be employed to support an antenna during portable operation. For HF antennas made of wire, probably the most common support is a conveniently located tree at the operating site. Temporary, lightweight masts are also used. An aluminum extension ladder, properly guyed, can serve as a mast for Field Day operation. Such supports are discussed in Chapter 22, Antenna Supports.

A SIMPLE TWIN-LEAD ANTENNA FOR HF PORTABLE OPERATION

The typical portable HF antenna is a random-length wire flung over a tree and end-fed through an antenna tuner. Low-power antenna tuners can be made quite compact, but each additional piece of necessary equipment makes portable operation less attractive. The station can be simplified by using resonant impedance-matched antennas for the bands of interest. Perhaps the simplest antenna of this type is the half-wave dipole, center-fed with 50- or 75-Ω coax. Unfortunately, RG-58, RG-59 or RG-8 cable is quite heavy and bulky for backpacking, and the miniature cables such as RG-174 are too lossy.

A practical solution to the coax problem, developed by Jay Rusgrove, W1VD, and Jerry Hall, K1TD, is to use folded dipoles made from lightweight TV twin-lead. The characteristic impedance of this type of dipole is near 300 Ω, but this can easily be transformed to a 50-Ω impedance. The transformation is obtained by placing a lumped capacitive reactance at a strategic distance from the input end of the line. **Fig 1** illustrates the construction method and gives important dimensions for the twin-lead dipole.

A silver-mica capacitor is shown for the reactive element, but an open-end stub of twin-lead can serve as well, provided it is dressed at right angles to the transmission line for some distance. The stub method has the advantage of easy adjustment of the system resonant frequency.

The dimensions and capacitor values for twin-lead dipoles for the HF bands are given in **Table 1**. To pre-

Fig 1—A twin-lead folded dipole makes an excellent portable antenna that is easily matched to 50-Ω equipment. See text and Table 1 for details.

serve the balance of the feeder, a 1:1 balun must be used at the end of the feed line. In most backpack QRP applications the balance is not critical, and the twin-lead can be connected directly to a coaxial output jack—one lead to the center contact, and one lead to the shell.

Because of the transmission-line effect of the shorted-radiator sections, a folded dipole exhibits a wider bandwidth than a single-conductor type. The antennas described here are not as broad as a standard folded dipole because the impedance-transformation mechanism is frequency selective. However, the bandwidth should be adequate. An antenna cut for 14.175 MHz, for example, will present an SWR of less than 2:1 over the entire 14-MHz band.

ZIP-CORD ANTENNAS

Zip cord is readily available at hardware and department stores, and it's not expensive. The nickname, *zip cord*, refers to that parallel-wire electrical cord with brown or white insulation used for lamps and many small appliances. The conductors are usually #18 stranded copper wire, although larger sizes may also be found. Zip cord is light in weight and easy to work with.

For these reasons, zip cord can be pressed into service as both the transmission line and the radiator section for an emergency dipole antenna system. This information by Jerry Hall, K1TD, appeared in *QST* for March 1979. The radiator section of a zip-cord antenna is obtained simply by "unzipping" or pulling the two conductors apart for the length needed to establish resonance for the operating frequency band. The initial dipole length can be determined from the equation $\ell = 468/f$, where ℓ is the length in feet and f is the frequency in MHz. (It would be necessary to unzip only half the length found

from the formula, since each of the two wires becomes half of the dipole.) The insulation left on the wire will have some loading effect, so a bit of length trimming may be needed for exact resonance at the desired frequency.

For installation, you may want to use the electrician's knot shown in **Fig 2** at the dipole feed point. This is a balanced knot that will keep the transmission-line part of the system from unzipping itself under the tension of dipole suspension. This way, if zip cord of sufficient length for both the radiator and the feed line is obtained, a solder-free installation can be made right down to the input end of the line.

(Purists may argue that knots at the feed point will create an impedance mismatch or other complications, but as will become evident in the next section, this is not a major consideration.) Granny knots (or any other variety) can be used at the dipole ends with cotton cord to suspend the system. You end up with a lightweight, low-cost antenna system that can serve for portable or emergency use.

But just how efficient is a zip-cord antenna system? Since it is easy to locate the materials and simple to install, how about using such for a more permanent installation? Upon casual examination, zip cord looks about like 72-Ω balanced feed line. Does it work as well?

Zip Cord as a Transmission Line

To determine the electrical characteristics of zip cord as a radio-frequency transmission line, a 100-foot roll was subjected to tests in the ARRL laboratory with an RF impedance bridge. Zip cord is properly called *parallel power cord*. The variety tested was manufactured for GC Electronics, Rockford, IL, being 18-gauge, brown, plastic-insulated type SPT-1, GC cat. no. 14-118-2G42. Undoubtedly, minor variations in the electrical-characteristics will occur among similar cords from different manufacturers, but the results presented here are probably typical.

The characteristic impedance was determined to be 107 Ω at 10 MHz, dropping in value to 105 Ω at 15 MHz and to a slightly lower value at 29 MHz. The nominal

Fig 2—This electrician's knot, often used inside lamp bases and appliances in lieu of a plastic grip, can also serve to prevent the transmission-line section of a zip-cord antenna from unzipping itself under the tension of dipole suspension. To tie the knot, first use the right-hand conductor to form a loop, passing the wire behind the unseparated zip cord and off to the left. Then pass the left-hand wire of the pair behind the wire extending off to the left, in front of the unseparated pair, and thread it through the loop already formed. Adjust the knot for symmetry while pulling on the two dipole wires.

Fig 3—Attenuation of zip cord in decibels per hundred feet when used as a transmission line at radio frequencies. Measurements were made only at the three frequencies where plot points are shown, but the curve has been extrapolated to cover all high-frequency amateur bands.

value is 105 Ω at HF. The velocity factor of the line was determined to be 69.5%.

Who needs a 105-Ω line, especially to feed a dipole? A dipole in free space exhibits a feed-point resistance of 73 Ω, and at heights above ground of less than $^1/_4$ wavelength the resistance can be even lower. An 80-meter dipole at 35 feet over average soil, for example, will exhibit a feed-point resistance of about 35 Ω. Thus, for a resonant antenna, the SWR in the zip-cord transmission line can be 105/35 or 3:1, and maybe even higher in some installations. Depending on the type of transmitter in use, the rig may not like working into the load presented by the zip-cord antenna system.

But the really bad news is still to come—line loss! **Fig 3** is a plot of line attenuation in decibels per hundred feet of line versus frequency. Chart values are based on the assumption that the line is perfectly matched (sees a 105-Ω load as its terminating impedance).

In a feed line, losses up to about 1 decibel or so can be tolerated, because at the receiver a 1-dB difference in signal strength is just barely detectable. But for losses above about 1 dB, beware. Remember that if the total losses are 3 dB, half of your power will be used just to heat the transmission line. Additional losses over those charted in Fig 3 will occur when standing waves are present. (See Chapter 24, Transmission Lines.) The trouble is, you can't use a 50- or 75-Ω SWR instrument to measure the SWR in zip-cord line accurately.

Based on this information, we can see that a hun-dred feet or so of zip-cord transmission line on 80 meters might be acceptable, as might 50 feet on 40 meters. But for longer lengths and higher frequencies, the losses become appreciable.

Zip Cord Wire as the Radiator

For years, amateurs have been using ordinary copper house wire as the radiator section of an antenna, erecting it without bothering to strip the plastic insulation. Other than the loading effects of the insulation mentioned earlier, no noticeable change in performance has been noted with the insulation present. And the insulation does offer a measure of protection against the weather. These same statements can be applied to single conductors of zip cord.

The situation in a radiating wire covered with insulation is not quite the same as in two parallel conductors, where there may be a leaky dielectric path between the two conductors. In the parallel line, it is the current leakage that contributes to line losses. This leakage current is set up by the voltage potential that exists on the two adjacent wires. The current flowing through the insulation on a single radiating wire is quite small by comparison, and so as a radiator the efficiency is high.

In short, communications can certainly be established with a zip-cord antenna in a pinch on 160, 80, 40, 30 and perhaps 20 meters. For higher frequencies, especially with long line lengths for the feeder, the efficiency of the system is so low that its value becomes questionable.

A TREE-MOUNTED HF GROUND-PLANE ANTENNA

A tree-mounted, vertically polarized antenna may sound silly. But is it really? Perhaps engineering references do not recommend it, but such an antenna does not cost much, is inconspicuous, and it works. This idea was described by Chuck Hutchinson, K8CH, in *QST* for September 1984.

The antenna itself is simple, as shown in **Fig 4**. A piece of RG-58 cable runs to the feed point of the antenna, and is attached to a porcelain insulator. Two radial wires are soldered to the coax-line braid at this point. Another piece of wire forms the radiator. The top of the radiator section is suspended from a tree limb or other convenient support, and in turn supports the rest of the antenna.

The dimensions for the antenna are given in **Fig 5**. All three wires of the antenna are ¼ wavelength long. This generally limits the usefulness of the antenna for portable operation to 7 MHz and higher bands, as temporary supports higher than 35 or 40 feet are difficult to come by. Satisfactory operation might be had on 3.5 MHz with an inverted-L configuration of the radiator, if you can overcome the accompanying difficulty of erecting the antenna at the operating site.

The tree-mounted vertical idea can also be used for fixed station installations to make an invisible antenna.

Shallow trenches can be slit for burying the coax feeder and the radial wires. The radiator itself is difficult to see unless you are standing right next to the tree.

A PORTABLE DIPOLE FOR 80 TO 2 METERS

This dipole antenna, described by Robert Johns, W3JIP, in August 1998 *QST*, can be used for any band from 80 through 2 meters. One half of the dipole is an inductively loaded aluminum tube. Its length is adjustable from 4 to 11 feet, depending on how much room is available. The other half is flexible insulated wire that can be spooled out as necessary. The tube is supported by a flagpole bracket attached to a long carpenter's clamp. The clamp mounts the antenna to practically anything: a windowsill, railing, a chair or post. If there is no structure to mount the antenna (a parking lot or the beach), the clamp attaches to two light wooden legs to form a tripod, as shown in **Fig 6**.

The key to mounting flexibility is the large clamp. The key to electrical flexibility is a large adjustable coil that lets you resonate the tube on many bands. The coil is wound with #8 aluminum ground wire from RadioShack. The form is a four-inch (4½-inch OD) styrene drain coupling from the Home Depot or a large plumbing supply store. A movable tap adjusts the inductance to tune the upright tube to the desired band. The wire half of the antenna is always a bit less than λ/4 on each band. Hang it from any convenient support or drape it over bushes to keep it off the ground.

Fig 4—The feed point of the tree-mounted ground-plane antenna. The opposite ends of the two radial wires may be connected to stakes or other convenient points.

In the figure: $L_{FT} = \frac{234}{f_{MHz}}$, $L = \frac{234}{f}$, $L = \frac{234}{f}$, RG – 58

Fig 5—Dimensions and construction of the tree-mounted ground-plane antenna.

Construction

The 18-inch carpenter's clamp (sometimes called a *bar clamp*, such as Jorgensen's No. 3718) and flagpole bracket that takes a $3/4$-inch pole are common hardware items. Insulate the bracket from the clamp jaw with a $1^{1}/_{2}$-inch length of 1-inch PVC pipe (see **Fig 7**). Hammer the PVC over the end clamp jaw to make it take the shape of the jaw. Secure the flagpole bracket to PVC with a large ground clamp (for $1/2$ or 1-inch conduit). The ground clamp includes $1/4$-inch bolts; enlarge the flagpole bracket holes to accept them. Some flagpole brackets have an integral cleat; the author hammered the cleat ears flat on his.

Mount an SO-239 chassis connector on the flagpole bracket using RadioShack insulated standoffs (276-1381). The standoffs tightly press the center pin of the SO-239 against the bracket surface; no other connection is needed. Other mounting hardware may require a connection from the coax center conductor to the bracket. The spooled wire's inner end wraps around a standoff and connects to a ring terminal under a screw holding the SO-239 flange to the standoff.

The 1×2-inch wooden legs for the tripod are each 30 inches long. Bolt them together at one end with a 1 or $1^{1}/_{4}$-inch-long bolt. Countersink the bolt head and nut below the surface of the wood so they don't interfere with the clamp jaws.

Aluminum Element

You can make this element from three lengths of telescoping aluminum tubing ($3/4$, $5/8$ and $1/2$ inch, 0.058-inch walls). The author used tubing with thinner walls for less weight and easier handling. A 45-inch-long, $3/4$-inch tube fits the flagpole bracket. He chose this length because it and the flagpole bracket make $\lambda/4$ on 6 meters. The two outer tubes are both $5/8$ inch, made by cutting a seven-foot aluminum clothesline pole in halves. They are

Fig 6—At top, the portable antenna in some of the many places it may be mounted around the house, porch and yard. At bottom, the simple ground-mounted legs that make a tripod.

Fig 7—The flagpole bracket that supports the tubing elements is clamped to the long carpenter's clamp, but insulated from it by a small section of 1-inch PVC pipe. A coax connector is mounted to the bracket and the spool of wire is attached to the coax connector.

joined together with a copper coupling ($^5/_8$ inch ID) for $^1/_2$-inch copper pipe. The coupling is bolted to one of the $^5/_8$-inch sections, and a slot is cut in the free half of the coupling. The remaining $^5/_8$-inch tube is inserted there and secured with a hose clamp. See **Fig 8**.

One $^5/_8$-inch tube slides into the $^3/_4$-inch tube to provide a continuously variable element length from about 4 to $7^1/_2$ feet. This extends from $7^1/_2$ to 11 feet when the two $^5/_8$-inch sections are joined together.

Loading Coil

The loading coil has 12 turns of bare aluminum wire spaced to fill the $3^1/_2$-inch length of the drain coupling. Drill $^9/_{64}$-inch holes at the ends of the coil form to accept the ends of the coil wire. (See **Fig 9**.) To wind the coil, feed four inches of wire through the form, make a sharp bend in the wire and start winding away from the nearby mounting hole. Wind 12 turns on the form, spacing them only approximately. Cut the wire for a 4-inch lead and feed it through the other hole in the form. Tighten the wire as best you can and bend it into another acute angle where it passes into the form. Space the turns about equally, but don't fuss with them. Final spacing will be set after the wire is tightened.

Tighten the coil wire by putting a screwdriver or a needle-nose pliers jaw under one turn, and pry the wire up and away from the surface of the coil form. While this can be done anywhere, it's best to put these kinks on the backside, away from the mounting shaft. Put kinks in every other turn, removing any slack from the coil and holding the turns in place. Should the coil ever loosen, simply retighten it with a screwdriver. If you prefer, glue the coil turns in place with epoxy or coil dope. Use a thin bead of glue that won't interfere with the clip that connects to the coil.

The coil form mounts on a nine-inch-long $^3/_4$-inch PVC pipe. (See Fig 9 and **Fig 10**.) The inside diameter is slightly larger than the $^3/_4$-inch aluminum, but slotting the PVC and tightening it with a hose clamp secures the tube. (Use a wide saw to cut these slots, not a hacksaw.) The coil form mounts to the PVC pipe with #6-32 × $1^1/_2$-inch bolts. A five-inch long, $^3/_4$-inch aluminum tube permanently attaches to one end of the coil assembly and slides into the

flagpole bracket. One end of the coil wire connects to this short tube. Flatten the wire end by hammering it on something hard, then drill a $^9/_{64}$-inch hole in the flattened end and attach it to the short tube with a #6-32 × 1-inch bolt. Tighten the bolt until the $^1/_2$-inch tube starts to flatten. This will keep pressure on the aluminum-to-aluminum joint.

The aluminum element slides into the opposite end of the coil assembly. The hose clamp there can be tightened until the element just slides in snugly.

A 12-inch clip lead connects the aluminum element to the coil. Bolt the plain wire end to the $^3/_4$-inch tube three inches from its end. Many alligator clips will fit in the space between the turns of the coil (about $^3/_{16}$ inch), but W3JIP preferred using a solid-copper clip (Mueller TC-1). Cut off most of the jaws, so that only the part close to the hinge grabs the coil. This shorter lever grips very tightly.

Wire and Spool

The lower half of the antenna is insulated wire that is about λ/4 on the band of operation. The wire is pulled from the spool, and the remaining wire forms an inductance that doesn't add much to the antenna length. The Home Depot sells #12 and #14 insulated stranded copper wire in 50 and 100-foot lengths, on plastic spools. (See **Fig 11**.) A $^1/_2$-inch dowel fits into the spool to make a

Fig 9—Holes to be drilled in the styrene coupling and the $^3/_4$-inch PVC pipe. All holes are $^9/_{64}$-inch diameter, to provide clearance for #6-32 bolts. The hole $1^1/_2$ inches from one end holds a bolt that serves as a stop, so that the antenna tube does not slide in too far. Space the holes for coil leads far enough from the mounting holes to clear the $^3/_4$-inch pipe.

Fig 8—The joint between two sections of $^5/_8$-inch tubing is made from a $^1/_2$-inch copper pipe coupling, bolted to one section and hose clamped to the other.

Fig 10—Top photo shows the loading coil for the 20, 30, and 40-meter band coverage. The short aluminum tube on the coil slides into the flagpole bracket, and the tubing element slides into the other end of the PVC pipe. The wire and clip connect the element to the coil. Bottom photo shows the coil for operating the antenna on 80 meters. This is placed in the flagpole bracket and the 40-meter aluminum coil plus the tubing element is inserted into it.

Fig 11—The wire spool has a wooden axle/handle and small handle for winding the wire. A bungee cord stretched over the spool and around the axle prevents the wire from unwinding.

Table 2

	Tubing Length (feet)	Coil Turns	Wire Length (feet)
6 meters	4	0	4
10 meters	7	0	8
	4	1.7	7
12 meters	8	0	8.3
	4	1.8	9
15 meters	10	0	10.3
	8	1.8	10
	4	3.5	10
17 meters	11	0	13
	8	2.2	13
	4	4.2	13
20 meters	11	1	16
	8	4	16
	4	6.2	16
30 meters	11	4	24
	8	7	24
	4	10.5	24
40 meters	11	9	32
	8	12	32

handle and spool axle. Bolts through the dowel on either side of the spool hold it in place. A crank handle is made by putting a one-inch-long bolt through the spool flange.

The author calibrates the wire on the spool with markers and electrical-tape flags. There's a mark (from a permanent marking pen) at each foot, a black flag every five feet and a length-marked colored flag every 10 feet. Simply mark the length for each band, if you like.

Make sure you prevent the wire from unspooling, especially when it's hanging from a window mounting. A heavy rubber band works, but it doesn't last long. A better solution is a loop of light bungee cord, preferably with a knot for grip. The bungee loop runs from the axle/handle around the spool making a half twist on the way, and then passes over the axle end on the other side of the spool. (See Fig 11.)

Operation

Table 2 lists element length, wire length and coil tap point for various bands. When the number of turns shown is zero, the coil is not needed. On all bands except 6 meters, you can simply bypass the coil with the clip lead—the extra length just lowers the frequency a bit. For 6 meters, the coil *must* be removed. The location of the unspooled wire greatly affects the settings, so these numbers are only starting points. The lengths in the table were taken with the wire one to three feet above ground, draped

over and through bushes and flowerbeds. The antenna will still work if the wire is lying on the ground, but it will require less unspooled wire to resonate. A balun is not needed, and an SWR analyzer is very helpful while adjusting this antenna.

The SWR is less than 1.5:1 on all bands, and it's usually below 1.2:1. Occasionally, a band shows a higher SWR (still less than 2:1), but that can always be lowered by adjusting the length or location of the lower wire. Never set up the antenna where it could fall and injure someone, or where the unwary could get an RF burn by touching it.

The author's results with this antenna have been excellent, both from home and on vacation. If you haven't

yet operated from a seashore location, be prepared for a pleasant surprise! The good ground afforded by the salt water really makes a difference.

80 Meters

It's easy to add this lower frequency band. Fig 10 shows a 35 µH coil for 80 meters. It's constructed and tightened just like the 40-meter coil, but has 20 turns of #12 magnet wire.

To operate on 75/80 meters, insert the new coil into the flagpole bracket and plug the 40-meter coil into it. Tune across the band with the movable tap on the 40-meter coil. This varies antenna resonance from below 3.5 to above 4.0 MHz, with the full 11 feet of tubing extended. If your version doesn't achieve this tuning range, adjust the spacing of the turns on the 80-meter coil.

The 80-meter coil has a five-inch length of $^3/_4$-inch aluminum tube inserted into one end of the $^1/_2$-inch PVC pipe that supports the coil form. One end of the coil is connected to this aluminum tube. The other end is secured under the bolt that holds the coil form to the PVC pipe. A second clip lead connects the base of the 40-meter coil to the outer end of the larger coil. The length of wire on the spool must also be increased to about 64 feet.

2 Meters

A $\lambda/2$ dipole for 2 meters can be made with about 15 inches of $^1/_2$-inch aluminum tubing in the flagpole bracket, and 18 inches of wire. The tubing element is shorter than normal for 2 meters because the bracket is also part of the antenna. You can also shorten the 6-meter wire a bit and operate the 6-meter antenna as a $3\lambda/2$ on 2 meters, with a somewhat higher SWR.

Continuous Coverage

With easily changed element lengths and a continuously variable loading coil, you may operate the antenna on any frequency from 6.5 to 60 MHz, if coverage for other services is needed. With taps in the 80-meter coil at 8, 11 and 14 turns, the antenna will also tune from 4 to 7 MHz.

THE HF CABOVER ANTENNA

If you have ever had the pleasure of traveling across the country with an HF mobile in a camper, trailer or motor home you may want to duplicate this antenna for use when you park. This antenna was described in *The ARRL Antenna Compendium, Vol 5*, by Jim Ford, N6JF.

The author's camper has limited spots on which to mount an HF mobile antenna. The back ladder is a convenient place to mount a small mobile whip. However, the efficiency of typical mobile center-loaded antennas, depending on coil Q and other assumptions, is often less than 2% for 80 meters and 10% for 40 meters. (These numbers come from the excellent, easy-to-use *MOBILE* antenna design program by Leon Braskamp, AA6GL, which is on the CD-ROM bundled with this book.)

At some locations, N6JF used an 80-meter dipole, which was very efficient and worked great on all bands when fed with open-wire line and an antenna tuner. However, it took over 40 minutes to set up and about 20 minutes to tear down, working with a sling shot and many tree snags. This is too much time to make a schedule or for an early morning departure, although it's OK if you plan to stay for a while. Even more important, there were often too many trees or other barriers (perhaps some even social) to allow putting up the dipole at a campsite.

When this happened he was stuck with the mobile antenna with poor efficiency. There had to be a better antenna for camper operation. The author decided on a large vertical.

A telescoping aluminum extension pole used for roller painting would make a good bottom section for the loaded vertical. These are available at many local home supply centers. The author's was 1 inch in diameter and 6 feet long, telescoping to almost 12 feet. He disassembled both sections and cross-cut a 1-inch slot in the top of the bottom section with a hacksaw to allow compression clamping with a hose clamp. The tip of the top section was fitted with an aluminum plug that had a 3/8-24 hole tapped in it. This procedure was a simple machine-shop operation. The plug was pounded into the top section and is quite snug. He tapped some set screws through the pole into the plug, however, just to be sure. An insulated, lay-down marine antenna mount fit perfectly into the bottom of the aluminum base and was secured with a bolt that also served as the electrical connection from the capacitor matching box. See **Fig 12** showing the aluminum base plate, the laydown mount and the antenna

Fig 12—Photo of aluminum base plate, showing details of mounting to the camper. The four banana-plug jacks on the bottom are for extra radials, if desired.

Fig 13—Photo showing the back of the camper, with the antenna in the lowered position, parallel to the ladder. The "Outback" standby mobile antenna is shown clamped to the left side of the ladder.

Fig 15—Close-up photo of 80 and 40-meter coils, with top section and telescoping whip antenna with swivel bracket for tuning the top section for the higher bands. Note quick-disconnect connectors at top and bottom of both coils. The top whip is a Fiberglas CB whip, used on 80 and 40 meters.

Fig 14—Schematic of tuning capacitor at base plate. C2 is an 800 pF transmitting mica capacitor. C1 is a three-section 365 pF broadcast tuning capacitor. S1 is closed for 80-meter operation.

mast itself lowered down the back of the camper. **Fig 13** shows the layout of the back of the camper, with the antenna on the right-hand side, laid down for travel.

The variable capacitor in the matching box is a surplus three-section 365-pF broadcast tuning capacitor. Two of three sections are connected in parallel and a switch parallels in the third section, along with an extra 800 pF mica capacitor for use on 80 meters. See the schematic in **Fig 14**.

The capacitor assembly was put in a custom-glued Plexiglas box to keep out the weather and mounted to a piece of plate aluminum, along with an SO-239 connector. The aluminum plate was riveted to the camper shell using a lot of aluminum rivets. Do not use steel. N6JF peeled back about a 4-inch wide section of the side of the camper for this direct aluminum-to-aluminum connection. People who are hesitant to modify their campers like this need to find an alternate low-resistance connection method. His camper was old enough not to be an issue.

For an extra low-resistance connection a $1^1/_2$-inch aluminum strip was added from the top of the base plate to the camper, as shown in Fig 12 near the 80-meter

switch. The tuning knob protrudes from the side of the Plexiglas box. The four bottom holes in the plate are for banana plugs to connect ground radials if extra efficiency is desired. However, the roof of a camper is one of the better places for a mobile antenna, so the author seldom hooks up the radials. When he does use them, the tuning changes only a little.

To keep losses down, N6JF used coils wound with aluminum clothes-line wire on old mobile coil center sections with quick disconnect fittings. See **Fig 15**, which shows both the 80 and 40 meter coils, together with the top portion of the antenna. An article by Robert Johns, W3JIP, in October 1992 *QST* described techniques for building your own loading coils. The coils ended with a little more inductance than calculated and the author had to remove some turns. Both coils are spaced at 4 turns per inch. The 8-inch long 80-meter coil has 18 turns. The 7-inch long 40-meter coil has 8 turns.

The matching network is actually an L-section step-up match, using the net inductive reactance of the antenna plus the center loading coil. The PVC coil construction technique was described in W3JIP's *QST* article and a follow-up Technical Correspondence piece in October 1992 *QST*. Basically, it consists of drilling an accurate row of slightly undersized holes along a length of $^1/_2$-inch PVC pipe and then carefully sawing down the center of the row of holes with a hack saw. Then, you trap the coil wires in the grooves between the two sawed halves and tie the two halves together with string. When you are satisfied that everything is proper, you then tighten the string and apply epoxy glue to make it strong and permanent.

One advantage of aluminum clothes line wire is that it is already coiled at the approximate diameter needed when you buy it and it is easy to position on the coil form.

The clothes line wire had a plastic coating, which wasn't removed except at the contact points. Once the epoxy dries, this method of construction does a good job of holding the finished coil together and it is lightweight.

The computed coil Q from the *MOBILE* antenna program is about 800 for the 80-meter coil and about 400 for the 40-meter coil. The author accidentally made the 40-meter coil 7 inches in diameter instead of a higher-Q 6 inch diameter. Even so, the whole antenna system with a 9-foot top section calculates as being 56% efficient on 80 meters and 85% for 40 meters.

The removable top section for 80 and 40 meters is a full-size fiberglass CB whip from RadioShack. The fiberglass whip has about a #16 hole in the center of it. Be sure to sand and paint the whip for protection against UV and to protect yourself against fiberglass spurs in the hands. N6JF tried a full-size stainless steel CB whip to get a slightly higher capacitance to ground because of larger conductor size but discovered it was far too heavy. That experience reinforced his decision that aluminum was a far more practical coil and base section material for this project.

Quick-disconnect connectors found years ago at a hamfest were used for both coil forms and for the top section. Bands higher than 40 meters don't need any loading coils and the antenna length can be telescoped to get a $1/4$ wavelength. Ten meters doesn't require any top section. Be sure to use some NOALOX or similar compound to prevent corrosion and poor connections at all aluminum joints. This is especially true for the telescoping sections and the aluminum rivets. The matching capacitor is in the circuit at all times but when the 80-meter switch is off you can set the capacitor at minimum (about 14 pF) and it is effectively out of the circuit, even at 10 meters. The author has not tried this antenna on power levels greater than about 100 W but the weakest link would probably be the matching capacitor. The voltage at the matching capacitor is low, so 200 W should be no problem.

You can achieve a 1:1 SWR match for 80 or 40 meters and a good SWR is obtained without retuning the base matching capacitor for approximately 100 kHz on 80 meters and most of 40 meters. The top section, however, does not have such low Q and needs to be tuned. The 2:1 SWR bandwidth on 80 meters is about 25 kHz and 150 kHz for 40 meters. Tuning is accomplished by using a telescoping FM portable radio antenna connected to the top-section whip with a stainless steel hose clamp. The maximum length of the telescoping section used was 29 inches, and it collapses down to 7 inches. A whip with an elbow was used to adjust the angle of the whip as well. A telescoping whip half the length would still be long enough for the full adjustment of both bands.

Adjustment of the top section is one of the penalties paid to achieve high efficiency for operation on 80 and 40 meters. Substituting an automatic antenna tuner would likely lose efficiency, particularly on 80 meters since the

base resistance calculates to about 10 Ω. N6JF has not tried to make the antenna work on 160 meters. The SWR for the higher bands was good enough without any matching network.

As light as the antenna is, it still won't hold up in a moderate wind without some support guys. N6JF used $3/4$-inch and $1/2$-inch PVC support pipes in a telescoping arrangement for storage, but expanding to give an approximate 45° support at the top of the bottom section from both directions. One end of the telescoping section was connected to the camper roof with a hinge. The other end formed a snap-fit out of a PVC barrel that was cut lengthwise. See **Fig 16** and **Fig 17** for details. Even though it formed a good snap fit, N6JF didn't trust the joint for strong winds so he glued a piece of Velcro to the joint to close up the open end. Be careful, though, because Velcro deteriorates with exposure.

Another hose clamp near the top of the bottom section holds an $1/8$-inch line taken up the ladder to pull up the antenna without the need of an assistant. The disadvantage is you have to climb the roof. Use a non-slip floor mat or something similar to spread the load on the roof and to avoid slipping. Once on the roof, however, the coil is at a height for easy adjustment when the telescoping section is in the down position.

An advantage of being able to assemble the whole antenna on the roof is that you don't need a lot of swing-up room and you can clear trees easily. You can put calibration marks on the upper aluminum section for resonant lengths on the higher bands but just raise the top section up all the way for 80 or 40 meters. Mark also the small

Fig 16—Close-up of one of the snap-on support brackets used to brace the antenna. Note the Velcro pieces used to ensure that the antenna doesn't pop out of the bracket in the wind.

Fig 17—Photo showing the two support bracket poles bracing the bottom section of the antenna. The top tuning whip is evident above the homemade loading coil at the top of the bottom section.

coil tuning whip for 80 or 40 meters, although different locations may require slightly different settings due to detuning from nearby metal objects.

The overall length is about 21 feet. The top of the author's camper is about 10 feet high when on the truck, putting the tip at 31 feet. This antenna is definitely designed for use when you are parked at a fixed location. N6JF can put up this antenna in less than 5 minutes and can take it down in half the time. The success of this project has as much to do with knowing how and where you operate as it does paying attention to mechanical and electrical details. The antenna has been a good compromise between efficiency and convenience.

TWO PORTABLE 6-METER ANTENNAS

These antennas were described by Markus Hansen, VE7CA, in *The ARRL Antenna Compendium, Vol 5*. After years of HF operation, he became enthusiastic about VHF/UHF operation when he found a used Yaesu FT-726R VHF/UHF all-mode transceiver at a reasonable price.

But he became really enthused when he got on 6 meters and discovered the joys of driving to high mountain peaks to operate. Not only does an antenna have to be portable for this kind of operation, it must be easily assembled and disassembled, just in case you have to move quickly to a better location.

A Portable Two-Element Six-Meter Quad

VE7CA's primary objective was to construct a two-element quad using material found in any small town. It should not use a complicated matching network. The Gamma matches commonly used on quads do not hold up well when you are setting up and taking down these antennas in the field. The final design adjusted the distance between the driven and the reflector elements so that the intrinsic feed-point impedance was 50 Ω.

Fig 18 shows the dimensions for the boom and the boom-to-mast bracket. The boom is made from a $27^{1}/_{4}$-inch length of 2×2. (The actual dimension of 2×2 is closer to $1^{3}/_{4}$ by $1^{3}/_{4}$ inches but it is commonly known in lumber yards as a 2×2.) Use whatever material is available in your area, but lightweight wood is preferred, so clear cedar or pine is ideal. Drill the four $^{1}/_{2}$-inch holes for the spreaders with a wood bit, two at each end, through one of the faces of the 2×2 and the other through the other face. The boom-to-mast bracket is made from $^{1}/_{4}$-inch fir plywood.

The spreaders are $^{1}/_{2}$-inch dowel. The local lumberyard had a good supply of fir dowels but other species of wood are available. The exact material is not important. Maple is stronger but expensive. Fiberglass would be ideal but it is not always available locally. Cut two of the $^{1}/_{2}$-inch dowels to a length of $83^{5}/_{8}$ inches for the driven element spreaders and two to 88 inches for the reflector spreaders. **Fig 19** shows one end of the boom with the two spreaders inserted. The mast was made from two six-foot lengths of $1^{3}/_{4}$-inch fir dowel. Again, use whatever you may have available. Waterproof all wooden parts with at least two coats of exterior varnish.

While you are at the lumberyard or hardware store look for plastic pipe that fits over the end of the $^{1}/_{2}$-inch spreaders. You will need a one-foot length, with some to spare. Cut it into seven equal lengths, approximately one inch long, and one to a length of $1^{1}/_{2}$ inches. Drill a $^{1}/_{16}$-inch hole through the seven equal lengths $^{1}/_{4}$ inch from the ends, and two holes one above the other $^{1}/_{4}$-inch apart on the $1^{1}/_{2}$-inch sleeve. VE7CA used #14 hard-drawn stranded bare copper wire for the elements. Do not use insulated wire unless you are willing to experimentally

Fig 18—Dimensions for the boom-to-mast bracket for VE7CA's portable two-element 6-meter quad.

Fig 19—Photo of one end of the VE7CA quad with the two spreaders inserted.

determine the element lengths, since the insulation detunes each element slightly.

Cut the reflector element 251 inches long and slip one end of the wire through the holes you drilled in four of the plastic sleeves. Don't attempt to secure the wire to the plastic sleeves at this point. Cross the end of the reflector elements one inch from their respective ends and twist and solder together. The total circumference of the reflector element should be 249 inches when the ends are connected together.

Cut the driven element wire to 241 inches and slip three of the 1-inch sleeves onto the wire. Again, don't secure the wires to the sleeves yet. Then the ends are passed through the two holes in the $1^1/2$-inch pipe. Wrap the ends around the pipe and twist them back onto themselves to secure the wire. The coax feed line is attached directly to the two ends at this point. The circumference of the driven-element loop from the points where the coax is attached should be $236^5/8$ inches. Solder the coax feed

line to the driven element and waterproof the coax with silicone seal. The author used RG-58, as it is lightweight. The length required for a portable installation is typically not very long, maybe 20 feet, so the loss in the small cable is not excessive. Near the feed point, coil the coax into six turns with an inside diameter of two inches. This is an effective method of choking any RF from flowing on the outside of the coax shield.

Begin assembling the quad by pushing the two reflector spreaders, without wires attached, through one end of the boom and the two shorter driven-element spreaders through the holes in the other end of the boom. Center the spreaders and mark the spreaders with a black felt-tip pen next to the boom. Now insert a $1^1/2$ #8 wood screw or a threaded L-hook into the boom so that it just touches one of the spreaders. Take the screw or L-hook out and file the end flat, then reinsert it so that it is just snug against the spreaders. The author only used two L-hooks for the two vertical spreaders; the horizontal spreaders are held in the proper position by the tension of the wire loops. If you use an L-hook, you can unscrew it with your hands—you won't have to worry about leaving the screwdriver at home.

You are now ready to assemble the wire loops. Take the reflector loop and place the four plastic caps over the ends of the reflector spreaders. Equalize the wire lengths between the spreader so that the loop is square. Now, secure the plastic sleeve pipes by tightly wrapping wire around the sleeve and the wire element and soldering the wire in place. See **Fig 20**, a photo showing one of the plastic sleeves slipped over one of the spreader ends, with the wire element through the hole and fastened in place. Follow the same procedure with the driven element.

Fig 21 shows the quad's boom, with the plywood boom-to-mast bracket fastened with wood screws and glue. Two U-bolts are used to attach to the mast. When the quad is raised, the shape of the loop is commonly known as a diamond configuration. The mast consists of two six-foot lengths of doweling joined together with a two-foot length of PVC plastic pipe, held together with wood screws.

Make a slot the width of a #8 wood screw about one inch deep from the top of the plastic PVC pipe and then put the top mast into the plastic pipe. Insert a one inch #8 wood screw into the bottom of the slot you cut into the top of the pipe and tighten only enough so that the top mast can be removed without unscrewing it. VE7CA drove a nail into the end of the lower mast and left it exposed an inch or more. This end is placed in the ground and the nail holds the pole in place. A strip of wood approximately 1×3 and long enough to cross over the roof rack of the family van is used to hold the center of the antenna mast to the roof rack of the van with small diameter rope. See **Fig 22** for a photo of the quad in action next to the family van.

To disassemble the quad, lay it on its side, slip the plastic sleeves off the ends of the spreaders and roll up

Fig 20—Photo showing one of the plastic sleeves slipped over end of a spreader to provide a mechanical mounting point and support for the wires.

Fig 21—Photo of the two-element quad's boom, with the plywood boom-to-mast bracket secured with wood screws and glue.

Fig 22—Ready for action! VE7CA has set up his quad next to the family van.

the wire loops. Loosen the L-hooks holding the vertical spreaders in place. Push the spreaders out of the boom, loosen the U-bolts and free the mast from the boom.

That is all there is to it. It takes about two minutes to put it up, or take it down. It is quite sturdy and has survived several high-wind storms.

A Three-Element Portable 6-Meter Yagi

The idea to build a Yagi antenna resulted when the author traded the family van for a compact car. He needed something that would fit into the trunk of the car. At close to 7-feet long, the quad spreaders were too long. Computer modeling showed that a three-element Yagi on a five-foot boom also could pick up about 1.5 dB gain over the short-boom two-element quad. A five-foot boom fits into the trunk or across the back seat of the car, but something had to be done about the nine-foot elements!

One day VE7CA noticed a box of portable-radio telescoping antenna elements at the radio parts store. They were 54 inches long when fully extended. He next found a 60-inch length of aluminum tubing that fit over the end of the telescoping elements. There are many different sizes of telescoping antenna elements, with different diameters. This is where you will have to use your scrounging skills! **Fig 23** shows how the tubing is used as a center section to join two telescoping elements together. It also serves to extend the total length of each element, since two telescoping elements themselves are not long enough to resonate on six meters. See **Table 3** for dimensions and element spacings. Each center section is slotted at both ends with a hacksaw, and stainless-steel hose clamps are used to secure the telescoping elements.

Fig 24 shows the center sections of the three elements with their mounting brackets. A square boom was used to obtain a flat surface to work with. **Fig 25** shows how the reflector is attached to the end of the boom with two $1^{1}/_{2}$-inch 10-32 bolts and wingnuts. **Fig 26A** provides the dimensions and details for the reflector and director element-to-boom brackets, which are formed from $^{1}/_{16}$-inch plate aluminum. The driven element is split in the center and is insulated from the boom. Fig 26B shows details for the driven-element bracket. **Fig 27** is a photo

Fig 23—Photo showing a piece of aluminum tubing used as a center section to join the two telescoping tips together.

Drill all hole sizes to suit available hardware

Curve aluminum snugly over center element

(A)

Holes for banana sockets

Bend snugly over plastic sleeve

(B)

Fig 26—At A, details for the reflector and director element-to-boom brackets, made of $1/16$-inch plate aluminum. At B, details for the driven-element bracket. These are screwed to the square boom.

Fig 24—A view of the center sections of the three Yagi elements with their mounting brackets.

Fig 25—Photo detailing attachment of the reflector to the square-section boom, using two #10 bolts and wingnuts.

of the driven element with the hairpin matching wire and the banana plugs used to connect the coax to the driven element. You could use a female PL-259 connector if you wish. VE7CA used #14 solid bare copper wire for the hairpin. It is very durable—even after being severely warped in the car trunk, it can be bent back into shape quickly and easily.

The boom is $3/4$-inch square aluminum, 65 inches long. The material was found at a local hardware store. To detach the elements, just loosen the wing nuts and remove the elements from the boom. A similar method was used to attach the support mast to the boom.

As with the quad, a choke balun was used, consisting of a coil of 6 turns of coax with an inside diameter of 2 inches. To tune the hairpin match, assemble the Yagi on its mast and extend the elements. Spray switch contact solution on a cloth and wipe any dirt and grease from the elements. Push the elements together and apart a

Table 3

Three-Element Yagi, Element Lengths and Spacing Along the Boom, and Hairpin Dimensions

Element Along Boom	Spacing Section Ele. (inches)	Center Length (inches)	Telescoping (inches)	Total Length (inches)
Reflector	0	$22^3/4$	$51^1/2$	$125^3/4$
Driven	28	$9^3/4$ *	$48^5/8$	$58^3/16$
Director	$63^3/8$	$14^1/2$	$51^1/4$	117
Hairpin	#14 wire	4 long	$1^5/8$ spacing	

* Driven-element uses 2 sections insulated at center

Fig 27—Photo of the driven element, complete with hairpin match and the banana plugs used to connect the coax cable to the driven element.

couple of times so that the contact solution cleans the elements thoroughly. Attach the antenna mast to your vehicle or use whatever method of support you intend to use in the field. Connect an SWR meter and a transmitter to the coax feeding the antenna. VE7CA used two alligator clips soldered together to slide along the two hairpin wires to find the position for the lowest SWR. The dimensions computed by computer were correct! The SWR was below 1.16:1 from 50.05 to 50.2 MHz.

You can take this antenna out of the trunk of the car and assemble it in less than two minutes. One caution: the telescoping elements when fully extended are quite fragile. VE7CA has not broken one as yet, but carrying a spare element just in case would be a good idea.

VE7CA 2-Element Portable HF Triband Yagis

These portable HF wire Yagis were described by Markus Hansen, VE7CA, in November 2001 *QST* and in *The ARRL Antenna Compendium, Vol 7*.

A 20/15/10-Meter Triband 2-Element Yagi

VE7CA wanted a simple 2-element wire Yagi for 20/15/10 meters that could be stored in the ski boot of his car. The basic concept comprises three individual dipole driven elements, one each for 20, 15 and for 10 meters tied to a common feed point, plus three separate reflector elements. The elements are strung between two 2.13-meter (7-foot) long, 2 × 2-inch wood spreaders, each just long enough to fit into the ski boot of his car.

By playing with the reflector-to-driven element spacing and the initial driven-element lengths, VE7CA was able to come up with a feed-point impedance on each band that allowed the use of a single setting for the shorting bar on a hairpin match. The result was a very acceptable match over the lower portions of each band. The layout of the 20/15/10-meter triband wire Yagi is shown in **Fig 28**, with the dimensions provided in **Table 4**.

The dimensions shown in Table 4 are what resulted after tuning for the lowest SWR in the middle of the lower portion of each band. VE7CA set his system up by hang-ing one end of the antenna from a tree and sloped it downwards at 45°, tying the lower end to a peg in the ground. The height at the feed point was 30 feet.

The feed-point impedance of an antenna is affected by many environmental factors. The presence of a reflector relatively close to the driven element has a major effect, since the impedance at the driven element in a Yagi is affected by the tuning of the driven element itself, by the spacing and length of the reflector element and to a lesser extent the height of the antenna above ground and the character of the soil itself. The real challenge in a multiband Yagi with a single feed line is to obtain a low SWR on all the bands.

The hairpin match is one of the easiest matching systems to make. It is easy to adjust and since wire is the only ingredient, it can be coiled up with the rest of the antenna when the antenna is disassembled. The feed-point impedance of the Yagi with a reflector element spaced 0.1 λ behind the driven element typically produces a resistance around 20 Ω. By shortening the driven element from its resonant length, capacitive reactance is added to the feed-point resistance. This can be cancelled by shunting the feed point with an inductor in the shape of a wire loop resembling a *hairpin*. This causes a step up of the 20-Ω feed-point resistance to 50 Ω.

Table 4

Dimensions for 20/15/10-Meter Tribander

Frequency MHz	Spacing DE to Refl cm (feet)	Driven Element Half Length cm (feet)	Reflector Length cm (feet)	Hairpin Length cm (inches)
14.1	213 (6.99)	488 (16.01)	1065 (34.94)	43 (14.9)
21.1	175 (5.74)	335 (10.99)	708 (23.23)	
28.25	125 (4.1)	254 (8.33)	531 (17.42)	
Spacing between hairpin wires is 10 cm (4 inches).				

Fig 28—Dimensions for VE7CA's 2-element 20/15/10-meter triband Yagi.

The Balun

Fig 29 shows the hairpin match and the common-mode choke balun for the 10/15/20-meter triband wire Yagi. You should let the coax drop straight down from the center insulator and attach it to the center of the hairpin shorting bar. Continue by making a coil using the coax of 8 turns, with a diameter of about 4 inches. This balun will choke off RF flowing along the outside of the coax shield that would otherwise distort the radiation pattern of the antenna. The center of the shorting bar is at a neutral potential, so there is no harm in attaching the coax feed line at that point.

Flattop or Tilted?

If DX is your main interest, then you want to tilt the antenna towards the vertical to emphasize the lower elevation angles. Remember that the radiation pattern is quite dependent on ground conductivity and dielectric constant for a vertically polarized antenna. A location close to saltwater will yield the highest gain and the lowest radiation angle. With very poor soil in the near and far field, the peak radiation angle will be higher and the gain less.

VE7CA has had numerous opportunities to test this out while operating portable at his favorite location. Using two trees as supports he can pull the antenna to horizontal with the feed line about 7 meters above the ground. In this position, with 20 meters open to Europe, he found it difficult to work DX on CW with 3 W of output power. However, when he changed the slope of the antenna so that it is nearly vertical he not only heard more DX stations, but he found it relatively easy to work DX. The sloping antenna always performs much better for working DX than a low horizontal antenna.

Fig 29—Details of feed point for 20/15/10-meter triband Yagi. The same mechanical support is provided for the balun and feed coax for the 30/17/12-meter tribander.

A 30/17/12-Meter Triband 2-Element Yagi

When the author attempted to add 17 and 12 meter elements to the existing 20/15/10-meter Yagi model he became exasperated. Adding two more driven elements and reflectors brings many more variables into the equation! It became clear that there was serious interaction between the elements. He could not obtain a workable feed-point impedance on all five bands that could be transformed to 50 Ω using a single hairpin match. There was also serious pattern distortion on 12 meters.

Even building a WARC-only triband Yagi for 30/17/12 meters turned out to be a real challenge. VE7CA had difficulty finding a combination that would allow him to use a single matching system to transform the feed-point impedance of the combined driven elements to 50 Ω. He couldn't create a 30/17/12 triband Yagi using the same design principles as his 20/15/10-meter version. The main problem occurred on 12 meters. Not only was the feed-point impedance unmanageable, but the radiation pattern had four lobes, not the single lobe you'd like from a Yagi.

He decided to try the *Modified Coaxial-Sleeve* method, more aptly termed by K9AY the *Coupled-Resonator (C-R)* in his article in *The ARRL Antenna Compendium, Vol 5*. The K9AY method uses a single driven element, with other elements placed in very close proximity (but not physically connected) to the driven element. By starting with the dimensions suggested by K9AY for a triband 30/17/12-meter dipole, VE7CA was able to develop a 2-element Yagi with acceptable feed-point impedances on all three bands using a single hairpin match. Notice that this WARC design uses a 2 × 2-inch wooden boom length that is 230 cm (7.5 feet) long. Of course, the antenna can't fit into a typical ski boot anymore, so VE7CA had to put it on a roof rack for transportation.

The space between the tightly coupled driven elements is only 3.7 cm (1.5 inches), so you need to use more PVC pipe spreaders than in the 20/15/10 design to make sure the driven-element wires stay as close as possible to the desired spacing without physically touching each other. The driven elements lie in the horizontal plane and the hairpin match and feed line hang down vertically from the center of the 30-meter driven element.

The spacing between the 30-meter driven elements and the other two conductors and the size of the wire all played a part in developing this antenna for a single feed line with the common hairpin match. Do not change the wire size from the recommended #14 for the driven elements unless you are willing to spend a considerable amount of time with a *NEC*-based modeling program retweaking the antenna. This is not the case with the 20/15/10 tri-band Yagi, where any convenient sized wire is acceptable.

Using #14 gauge wire allows all the Yagi antennas in this article to be used at the maximum power levels allowed in North America. The only limiting factor is the power handling capability of the feed line. However, even RG-58 should work for the relatively short length from the feed point down to ground level, where you can change to RG-8 or some other higher-power, lower-loss coaxial cable if you wish. **Fig 30** is a detailed drawing of the 30/17/12-meter driven element. The other dimensions for the 30/17/12-meter triband Yagi are shown in **Table 5**.

Assembly

When you are ready to assemble your wire Yagi, start by attaching the longest reflector element and the driven element assembly to the wood end booms. Do this with the wires and the booms on the ground. Next attach the V slings to both of the booms and with ropes attached to the V slings pull the array up off the ground between two supports (perhaps two trees). A height of 1.5 meters (5 feet) above the ground makes it easy to work on the antenna while you add the other reflector elements and adjust the V slings. Pull them tight so that the array is fairly flat. It won't stay horizontal, because the driven elements are heavier than a single reflector element. So you will need to support the 2 × 2-inch spreaders so they are horizontal. Lean the booms on something at a convenient height, such as the rungs of two step ladders. Now add the two other reflector elements, but don't pull them as tight as the longest reflector. Next attach the feed line.

Table 5
Dimensions for 30/17/12-Meter Tribander

Frequency MHz	Spacing DE to Refl cm (feet)	Driven Element Length cm (feet)	Reflector Length cm (feet)	Hairpin Length cm (inches)
10.12	230 (7.5)	713 (23.4) Half	1476 (48.4)	24.5 (9.5)
18.11	165 (5.4)	808 (26.5)	822 (27.0)	
24.91	120 (3.9)	570 (18.7)	606 (19.9)	

Spacing between hairpin wires is 10 cm (4 inches). Note that dimensions for 17 and 12-meter driven elements are full lengths, since they are not broken with insulator in the middle, unlike all driven elements for 20/15/10-meter triband design in Table 4.

Fig 30—Layout of 30-meter driven element with coupled resonators for 17 and 12 meters.

V Slings

Since the author wanted to be able to raise the 30/17/12-meter triband antenna by himself, he again used only one rope on either end of the array. One end goes over a tree limb and the other end is tied to a stake in the ground or some other nearby support, perhaps a tree trunk. Using only one attachment rope on either end makes it very easy to change beam direction by walking the antenna around the antenna support tree or tower. To accomplish this he used two V slings, one on each end attached to the 2 × 2-inch spreaders.

The secret to keeping the antenna level in the horizontal plane is that the V slings are not equilateral in shape. The combined weight of driven elements, balun and feed line is heavier than the reflectors. If the length of the sides of the V are equal, the array will rotate downwards. The driven elements will end up facing the ground, with the reflectors facing up. Adjust the V slings so that the antenna will stay level in the horizontal plane by shortening the length of the side of the V attached to the driven elements. It is quite easy to adjust in the field, and once you have it adjusted it stays balanced.

Once you raise the antenna to its operating position and in the horizontal plane, you can change direction 180° by pulling on the feed line. As you pull, the whole array will slowly turn over. Stop it from turning by holding onto the feed line once the array has swung over to face the opposite direction.

SWR Adjustment

Since you may situate your antenna in an entirely different position than VE7CA did, you may need to fine tune your antenna. Begin with the dimensions in Table 5 as a starting point. Make a temporary shorting bar using two alligator clips joined by a piece of wire and attach them at the recommended position. Next raise the antenna to the desired final position. Using an antenna analyzer (or transmitter and SWR meter) plot the SWR over all three bands. Start with the lowest band, 30 meters and

Fig 31—Layout for inverted-V 40-meter portable wire Yagi suspended from tower.

adjust the shorting bar up or down to find the lowest SWR point in the portion of the band you plan to operate in. (This procedure also works if you wish to adjust the 20/15/10-meter tribander. Start with the lowest frequency.)

You shouldn't have to move the shorting bar very far from the suggested length. Now that you have determined the right shorting-bar position, adjust the other two driven element lengths for the lowest SWR in the portion of those bands in which you plan to operate. You may have to compromise with the position of the shorting bar to find a satisfactory range where the SWR is acceptable on all three bands. After satisfying himself with the position of the shorting bar, VE7CA replaced the alligator clips simply by folding one side of the parallel hair-pin

wire lengths over to the other side and soldering it in the position where the alligator clips had been attached. The author does not recommend changing the reflector element lengths unless you are familiar with antenna modeling programs and are willing to model different spacing or element lengths.

40-Meter Wire Yagis

After his November 2001 *QST* article, VE7CA received several requests for a 40-meter wire Yagi. One ham mentioned that he wanted to be able to pull up a 40-meter Yagi between two towers and to be able to flip it over to change direction. Another wanted a 40-meter Yagi he could pull up on a single tower for the winter DX contests and then put it away during the summer. So VE7CA ran four different 40-meter scenarios in his computer models:

1. A horizontal 2-element wire Yagi at 65 feet.
2. A sloping 2-element wire Yagi, with one end at 65 feet and sloping downward 30° from vertical.
3. A sloping 2-element wire Yagi, with one end at 65 feet and sloping downward 65° from vertical.
4. An inverted-V 2-element wire Yagi with the apex at 65 feet and an included angle between the wires of 120°.

Fig 31 shows the layout for an inverted-V system and **Table 6** lists the element and hairpin lengths. Elevation patterns for the 40 meter antennas are compared in **Fig 32**, with a reference antenna of a single flattop dipole at 65 feet. As they say, a picture is worth a thousand words. If your interest is DX, it is very clear that horizontal and high is a very good rule of thumb for most antennas.

Yes, a $^{1}/_{4}$ wave vertical over salt water or 120 $^{1}/_{4}$-wave radials over good ground will produce very low radiation angles, but such systems are not exactly portable and we don't all live near the ocean. Mind you, if you can manage to locate antenna Number 3 (the most vertically oriented wire Yagi) next to the ocean, you would be very happy.

The point here is that if you have two towers and you're not fortunate enough to be located on a saltwater marsh, you should pull the 40-meter array up as high and as horizontal as you can. If you have only one tower and don't need to change direction often, then try the inverted-V configuration. You can still change the direction by walking each end around the tower.

However, even the sloping 40-meter Yagi with one end at 65 feet up a tower (or tree) and the other end attached with a long rope as far as possible from the tower will still put out a very respectable signal. It is directional, and you can walk it around the tower to change direction or you can

Table 6
40-Meter Wire Yagi Configurations

Configuration	Driven Element cm (feet)	Reflector cm (feet)	Hairpin Length cm (feet)
1. Horizontal	1978 (64.90)	2098 (68.83)	Approx 50 cm
2. −30° Sloper	1978 (64.90)	2113 (69.32)	(22 inches)
3. −65° Sloper	1978 (64.90)	2101 (68.93)	
4. Inverted V	2040 (66.93)	2126 (69.75)	

Spacing between driven element and reflector is 427 cm (14 feet). Spacing between parallel hairpin wires is 10 cm (4 inches). The lengths shown above are the total wire length for each element.

Fig 32—Comparisons of elevation patterns for five 40-meter antennas: a 2-element flattop Yagi at 65 feet; a 2-element inverted-V Yagi at 65 feet; a 2-element Yagi sloped 65° from the vertical plane; a 2-element Yagi sloped 30° from the vertical plane; and a horizontal dipole at 65 feet.

Fig 33 — VE7CA portable 2-element 20/15/10-meter wire Yagi installed at Plimoth Plantation in Plymouth, Massachusetts. (*Photo courtesy K1HTN*).

flip the antenna over and change direction 180° very quickly.

Summary

You don't need a 10-meter (60-foot) high tower, a commercial triband Yagi and a rotator to put out a good signal on the HF bands. Wire Yagis work very well and they can be inexpensive and easy-to-build, using components found at your local hardware store. **Fig 33** is a photograph of a successful portable installation in Massachusetts.

BIBLIOGRAPHY

Source material and more extended discussion of topics covered in this chapter can be found in the references given below.

G. Breed, K9AY, "The Coupled-Resonator Principle: A Flexible Method for Multiband Antennas," *The ARRL Antenna Compendium, Vol 5* (Newington: ARRL, 1996), p 109ff.

R. J. Decesari, "A Portable Quad for 2 Meters," *QST*, Oct 1980, and "Portable Quad for 2 Meters, Part 2," Technical Correspondence, *QST*, Jun 1981, p 39ff.

D. DeMaw, "A Traveling Ham's Trap Vertical," *QST*, Oct 1980, p 28ff.

J. Hall, "Zip-Cord Antennas—Do They Work?" *QST*, Mar 1979, p 31ff.

M. Hansen, "A Portable 2-Element Triband Yagi," *QST*, Nov 2001, p 35ff.

M. Hansen, "Some More VE7CA 2-Element Portable Yagis," *The ARRL Antenna Compendium, Vol7* (Newington: ARRL, 2002, p 183ff.

C. L. Hutchinson, "A Tree-Mounted 30-Meter Ground-Plane Antenna," *QST*, Sep 1974, p 16ff.

C. W. Schecter, "A Deluxe RV 5-Band Antenna," *QST*, Oct 1980, p 38.

Mobile and Maritime Antennas

Mobile antennas are those designed for use while antennas, most amateurs think of a whip mounted on an automobile or other highway vehicle, perhaps on a recreational vehicle (RV) or maybe on an off-road vehicle. While it is true that most mobile antennas are vertical whips, mobile antennas can also be found in other places. For example, antennas mounted aboard a boat or ship are mobile, and are usually called *maritime antennas*. **Fig 1** shows yet another type of mobile antenna—those for use on handheld transceivers. Because they may be used while in motion, even these antennas are mobile by literal definition.

Pictured in Fig 1 is a telescoping full-size quarter-wave antenna for 144 MHz, and beside it a *stubby* antenna for the same band. The stubby is a helically wound radiator, made of stiff copper wire enclosed in a protective covering of rubber-like material. The inductance of the helical windings provides electrical loading for the antenna. For frequencies above 28 MHz, most mobile installations permit the use of a full-size antenna, but sometimes smaller, loaded antennas are used for convenience. The stubby, for example, is convenient for short-range communications, avoiding the problems of a lengthier, cumbersome antenna attached to a handheld radio.

Below 28 MHz, physical size becomes a problem with full-size whips, and some form of electrical loading (as with the stubby) is usually employed. Commonly used loading techniques are to place a coil at the base of the whip (base loading), or at the center of the whip (center loading). These and other techniques are discussed in this chapter.

Few amateurs construct their own antennas for HF mobile and maritime use, since safety reasons dictate very sound mechanical construction. Several construction projects are included, however, in this chapter for those who may wish to build their own mobile antenna. Even if commercially made antennas are installed, most require some adjustment for the particular installation and type of operation desired and the information given here may provide a better understanding of the optimization requirements.

HF-MOBILE FUNDAMENTALS

Fig 2 shows a typical bumper-mounted center-loaded whip suitable for operation in the HF range. Jack Schuster, W1WEF, operates 80 through 2 meters from his car. The antenna could also be mounted on the car body itself (such as a fender), and mounts are available for this purpose. The base spring and tennis ball act as shock absorbers for the bottom of the whip, as the continual flexing while in motion would otherwise weaken the antenna. A short heavy mast section is mounted between the base spring and loading coil. Some models have a mechanism that allows the antenna to be tipped over for adjustment or for fastening to the roof of the car when not in use.

It is also advisable to extend a couple of guy lines from the base of the loading coil to clips or hooks fastened to the roof gutter on the car, or to the trunk and

Fig 1—Two mobile antennas—mobile because they may be used while in motion. Shown here are a telescoping ¹/₄-λ antenna and a "stubby" antenna, both designed for use at 144 MHz. The ¹/₄-λ antenna is 19 inch long, while the stubby antenna is only 3¹/₂ inch long. (Both dimensions exclude the length of the BNC connectors. The stubby is a helically wound radiator.

Fig 2—A typical bumper-mounted HF mobile antenna, as used by W1WEF. Note the nylon guy lines and the tennis ball used as a shock absorber. (*Photo courtesy W1WEF.*)

rear bumper, as W1WEF has done. Nylon fishing line (about 40-pound test) is suitable for this purpose. The guy lines act as safety cords and also reduce the swaying motion of the antenna considerably. The feed line to the transmitter is connected to the bumper and base of the antenna. Good low-resistance connections are important here.

Tune-up of the antenna is usually accomplished by changing the height of the adjustable whip section above the precut loading coil. First, tune the receiver and try to determine where the signals seem to peak up. Once this frequency is found, check the SWR with the transmitter on, and find the frequency where the SWR is lowest. Shortening the adjustable section will increase the resonant frequency, and making it longer will lower the frequency. It is important that the antenna be away from surrounding objects such as overhead wires by ten feet or more, as considerable detuning can occur. Once the setting is found where the SWR is lowest at the center of the desired frequency range, the length of the adjustable section should be recorded.

Propagation conditions and ignition noise are usually the limiting factors for mobile operation on 10 through 28 MHz. Antenna size restrictions affect operation somewhat on 7 MHz and much more on 3.5 and 1.8 MHz. From this standpoint, perhaps the optimum band for HF-mobile operation is 7 MHz. The popularity of the regional mobile nets on 7 MHz is perhaps the best indication of its suitability. For local work, 28 MHz is also useful, as antenna efficiency is high and relatively simple antennas without loading coils are easy to build.

As the frequency of operation is lowered, an antenna

of fixed length looks (at its feed point) like a decreasing resistance in series with an increasing capacitive reactance. The capacitive reactance must be tuned out, necessitating the use of an equivalent series inductive reactance or loading coil. The amount of inductance required will be determined by the placement of the coil in the antenna system.

Base loading requires the lowest value of inductance for a fixed-length antenna, and as the coil is placed farther up the whip, the necessary value increases. This is because the capacitance of the shorter antenna section (above the coil) to the car body is now lower (higher capacitive reactance), requiring more inductance to tune the antenna to resonance. The advantage is that the current distribution on the whip is improved, increasing the radiation resistance. The disadvantage is that requirement of a larger coil also means the coil size and losses increase. Center loading has been generally accepted as a good compromise with minimal construction problems. Placing the coil $^2/_3$ the distance up the whip seems to be about the optimum position.

For typical antenna lengths used in mobile work, the difficulty in constructing suitable loading coils increases as the frequency of operation is lowered. Since the required resonating inductance gets larger and the radiation resistance decreases at lower frequencies, most of the power is dissipated in the coil's loss resistance and in other ohmic losses. This is one reason why it is advisable to buy a commercially made loading coil with the highest power rating possible, even if only low-power operation is planned.

Coil losses in the higher-power loading coils are usually less (percentage-wise), with subsequent improvement in radiation efficiency, regardless of the power level used. Of course, the above philosophy also applies to homemade loading coils, and design considerations will be considered in a later section.

Once the antenna is tuned to resonance, the input impedance at the antenna terminals will look like a pure resistance. Neglecting losses, this value drops from nearly 15 Ω at 21 MHz to 0.1 Ω at 1.8 MHz for an 8-foot whip. When coil and other losses are included, the input resistance increases to approximately 20 Ω at 1.8 MHz and 16 Ω at 21 MHz. These values are for relatively high-efficiency systems. From this it can be seen that the radiation efficiency is much poorer at 1.8 MHz than at 21 MHz under typical conditions.

Since most modern gear is designed to operate with a 50-Ω transmission line, a matching network is usually necessary, especially with the high-efficiency antennas previously mentioned. This can take the form of either a broadband transformer, a tapped coil, or an LC matching network. With homemade or modified designs, the tapped-coil arrangement is perhaps the easiest one to build, while the broadband transformer requires no adjustment. As the losses go up, so does the input resis-

tance, and in less efficient systems the matching network may not be needed.

The Equivalent Circuit of a Typical Mobile Antenna

In the previous section, some of the general considerations were discussed, and these will now be taken up in more detail. It is customary in solving problems involving electric and magnetic fields (such as antenna systems) to try to find an equivalent network with which to replace the antenna for analysis reasons. In many cases, the network may be an accurate representation over only a limited frequency range. However, this is often a valuable method in matching the antenna to the transmission line.

Antenna resonance is defined as the frequency at which the input impedance at the antenna terminals is purely resistive. The shortest length at which this occurs for a vertical antenna over a ground plane is when the antenna is an electrical quarter wavelength at the operating frequency; the impedance value for this length (neglecting losses) is about 36 Ω. The idea of resonance can be extended to antennas shorter (or longer) than a quarter wave, and means only that the input impedance is purely resistive. As pointed out previously, when the frequency is lowered, the antenna looks like a series RC circuit, as shown in **Fig 3**. For the average 8-foot whip, the capacitive reactance of C_A may range from about −150 Ω at 21 MHz to as high as −8000 Ω at 1.8 MHz, while the radiation resistance R_R varies from about 15 Ω at 21 MHz to as low as 0.1 Ω at 1.8 MHz.

For an antenna less than 0.1 λ long, the approximate radiation resistance may be determined from the following:

$$R_R = 273 \times (\ell f)^2 \times 10^{-8} \qquad \text{(Eq 1)}$$

where ℓ is the length of the whip in inches, and f is the frequency in megahertz.

Since the resistance is low, considerable current must flow in the circuit if any appreciable power is to be dissipated in the form of radiation in R_R. Yet it is apparent that little current can be made to flow in the circuit as long as the comparatively high series reactance remains.

Antenna Capacitance

Capacitive reactance can be canceled by connecting an equivalent inductive reactance, (coil L_L) in series, as shown in **Fig 4**, thus tuning the system to resonance.

The capacitance of a vertical antenna shorter than a quarter wavelength is given by:

$$C_A = \frac{17\ell}{\left[\left(\ln \frac{24\ell}{D}\right) - 1\right]\left[1 - \left(\frac{f\ell}{234}\right)^2\right]} \qquad \text{(Eq 2)}$$

where

$\quad C_A$ = capacitance of antenna in pF
$\quad \ell$ = antenna height in feet
$\quad D$ = diameter of radiator in inches
$\quad f$ = operating frequency in MHz

$$\ln \frac{24\ell}{D} = 2.3 \log_{10} \frac{24\ell}{D}$$

Fig 5 shows the approximate capacitance of whip antennas of various average diameters and lengths. For 1.8, 4 and 7 MHz, the loading coil inductance required (when the loading coil is at the base) would be approximately the inductance required to resonate in the desired band (with the whip capacitance taken from the graph). For 10 through 21 MHz, this rough calculation will give more than the required inductance, but it will serve as a

Fig 3—At frequencies below resonance, the whip antenna will show capacitive reactance as well as resistance. R_R is the radiation resistance, and C_A represents the antenna capacitance.

Fig 4—The capacitive reactance at frequencies below the resonant frequency of the whip can be canceled by adding an equivalent inductive reactance in the form of a loading coil in series with the antenna.

Fig 5—Graph showing the approximate capacitance of short vertical antennas for various diameters and lengths. These values should be approximately halved for a center-loaded antenna.

starting point for the final experimental adjustment that must always be made.

LOADING COIL DESIGN

To minimize loading coil loss, the coil should have a high ratio of reactance-to-resistance (that is, a high unloaded Q). A 4-MHz loading coil wound with small wire on a small-diameter solid form of poor quality, and enclosed in a metal protector, may have a Q as low as 50, with a loss resistance of 50 Ω or more. High-Q coils require a large conductor, air-wound construction, large spacing between turns, and the best insulating material available. A diameter not less than half the length of the coil (not always mechanically feasible) and a minimum of metal in the field of the coil are also necessities for optimum efficiency. Such a coil for 4 MHz may show a Q of 300 or more, with a resistance of 12 Ω or less.

The coil could then be placed in series with the feed line at the base of the antenna to tune out the unwanted capacitive reactance, as shown in Fig 4. Such a method is often referred to as *base-loading*, and many practical mobile antenna systems have been built using this scheme.

Over the years, the question has come up as to whether or not more efficient designs are possible compared with simple base loading. While many ideas have been tried with varying degrees of success, only a few have been generally accepted and incorporated into actual systems. These are center loading, continuous loading, and combinations of the latter with more conventional antennas.

Base Loading and Center Loading

If a whip antenna is short compared to a wavelength *and the current is uniform along the length* ℓ, the electric field strength E, at a distance d, away from the antenna is approximately:

$$E = \frac{120\pi I\ell}{d\lambda} \qquad \text{(Eq 3)}$$

where

I is the antenna current in amperes
λ is the wavelength in the same units as D and ℓ.

A uniform current flowing along the length of the whip is an idealized situation, however, since the current is greatest at the base of the antenna and goes to a minimum at the top. In practice, the field strength will be less than that given by the above equation, because it is a function of the current distribution on the whip.

The reason that the current is not uniform on a whip antenna can be seen from the circuit approximation shown in **Fig 6**. A whip antenna over a ground plane is similar in many respects to a tapered coaxial cable where the center conductor remains the same diameter along its length, but with an increasing diameter outer conductor. The inductance per unit length of such a cable would increase along the line, while the capacitance per unit

Fig 6—A circuit approximation of a simple whip over a perfectly conducting ground plane. The shunt capacitance per unit length gets smaller as the height increases, and the series inductance per unit length gets larger. Consequently, most of the antenna current returns to the ground plane near the base of the antenna, giving the current distribution shown at the right.

Fig 7—Improved current distribution resulting from center loading.

length would decrease. In Fig 6 the antenna is represented by a series of LC circuits in which C1 is greater than C2, which is greater than C3, and so on. L1 is less than L2, which is less than succeeding inductances. The net result is that most of the antenna current returns to ground near the base of the antenna, and very little near the top.

Two things can be done to improve this distribution and make the current more uniform. One would be to increase the capacitance of the top of the antenna to ground through the use of top loading or a capacitance hat, as discussed in Chapter 6. Unfortunately, the wind resistance of the hat makes it somewhat unwieldy for mobile use. The other method is to place the loading coil farther up the whip, as shown in **Fig 7**, rather than at the base. If the coil is resonant (or nearly so) with the

Table 1
Approximate Values for 8-ft Mobile Whip

f(MHz)	Loading L μH	R_C(Q50) Ω	R_C(Q300) Ω	R_R Ω	Feed R* Ω	Matching L μH
Base Loading						
1.8	345	77	13	0.1	23	3
3.8	77	37	6.1	0.35	16	1.2
7.2	20	18	3	1.35	15	0.6
10.1	9.5	12	2	2.8	12	0.4
14.2	4.5	7.7	1.3	5.7	12	0.28
18.1	3.0	5.0	1.0	10.0	14	0.28
21.25	1.25	3.4	0.5	14.8	16	0.28
24.9	0.9	2.6	—	20.0	22	0.25
29.0	—	—	—	—	36	0.23
Center Loading						
1.8	700	158	23	0.2	34	3.7
3.8	150	72	12	0.8	22	1.4
7.2	40	36	6	3.0	19	0.7
10.1	20	22	4.2	5.8	18	0.5
14.2	8.6	15	2.5	11.0	19	0.35
18.1	4.4	9.2	1.5	19.0	22	0.31
21.25	2.5	6.6	1.1	27.0	29	0.29

R_C = loading coil resistance; R_R = radiation resistance.
*Assuming loading coil Q = 300, and including estimated ground-loss resistance.

Table 2
Suggested Loading Coil Dimensions

Req'd L(μH)	Turns	Wire Size	Dia. Inches	Length Inches
700	190	22	3	10
345	135	18	3	10
150	100	16	2$^1/_2$	10
77	75	14	2$^1/_2$	10
77	29	12	5	4$^1/_4$
40	28	16	2$^1/_2$	2
40	34	12	2$^1/_2$	4$^1/_4$
20	17	16	2$^1/_2$	1$^1/_4$
20	22	12	2$^1/_2$	2$^3/_4$
8.6	16	14	2	2
8.6	15	12	2$^1/_2$	3
4.5	10	14	2	1$^1/_4$
4.5	12	12	2$^1/_2$	4
2.5	8	12	2	2
2.5	8	6	2$^3/_8$	4$^1/_2$
1.25	6	12	1$^3/_4$	2
1.25	6	6	2$^3/_8$	4$^1/_2$

capacitance to ground of the section above the coil, the current distribution is improved as also shown in Fig 7. The result with both top loading and center loading is that the radiation resistance is increased, offsetting the effect of losses and making matching easier.

Table 1 shows the approximate loading coil inductance for the various amateur bands. Also shown in the table are approximate values of radiation resistance to be expected with an 8-foot whip, and the resistances of loading coils—one group having a Q of 50, the other a Q of 300. A comparison of radiation and coil resistances will show the importance of reducing the coil resistance to a minimum, especially on the three lower frequency bands. Table 2 shows suggested loading-coil dimensions for the inductance values given in Table 1.

OPTIMUM DESIGN OF SHORT COIL-LOADED HF MOBILE ANTENNAS

Optimum design of short HF mobile antennas results from a careful balance of the appropriate loading coil Q-factor, loading coil position in the antenna, ground loss resistance, and the length-to-diameter ratio of the antenna. The optimum balance of these parameters can be realized only through a thorough understanding of how they interact. This section presents a mathematical approach to designing mobile antennas for maximum radiation efficiency. Bruce Brown, W6TWW, in *The ARRL Antenna Compendium Volume 1*, first presented this approach. (See the Bibliography at the end of this chapter.)

The optimum location for a loading coil in an antenna can be found experimentally, but it requires many hours of designing and constructing models and making measurements to ensure the validity of the design. A faster and more reliable way of determining optimum coil location is through the use of a personal computer. This approach allows the variation of any single variable, while observing the cumulative effects on the system. When plotted graphically, the data reveals that the placement of the loading coil is critical if maximum radiation efficiency

Table 3
Variables used in Eqs 4 through 20

A = area in degree-amperes
a = antenna radius in English or metric units
dB = signal loss in decibels
E = efficiency in percent
f (MHz) = frequency in megahertz
H = height in English or metric units
h = height in electrical degrees
h_1 = height of base section in electrical degrees
h_2 = height of top section in electrical degrees
I = I_{base} = 1 ampere base current
k = 0.0128
k_m = mean characteristic impedance
k_{m1} = mean characteristic impedance of base section
k_{m2} = mean characteristic impedance of top section
L = length or height of the antenna in feet
P_I = power fed to the antenna
P_R = power radiated
Q = coil figure of merit
R_C = coil loss resistance in Ω
R_G = ground loss resistance in Ω
R_R = radiation resistance in Ω
X_L = loading-coil inductive reactance

Fig 8—Relative current distribution on a vertical antenna of height h = 90 electrical degrees.

is to be realized. (See the program *MOBILE.EXE*, which is included on the CD-ROM in the back of this book.)

Radiation Resistance

The determination of radiation efficiency requires the knowledge of resistive power losses and radiation losses. Radiation loss is expressed in terms of radiation resistance. Radiation resistance is defined as the resistance that would dissipate the same amount of power that is radiated by the antenna. The variables used in the equations that follow are defined once in the text, and are summarized in **Table 3**. Radiation resistance of vertical antennas shorter than 45 electrical degrees ($^1/_8$ wavelength) is approximately:

$$R_R = \frac{h^2}{312} \qquad \text{(Eq 4)}$$

where

R_R = radiation resistance in Ω
h = antenna length in electrical degrees.

Antenna height in electrical degrees is expressed by:

$$h = \frac{\ell}{984} \times f\left(MHz\right) \times 360 \qquad \text{(Eq 5)}$$

where

ℓ = antenna length in feet
f (MHz) = operating frequency in megahertz.

End effect is purposely omitted to ensure that an

antenna is electrically long. This is so that resonance at the design frequency can be obtained easily by removing a turn or two from the loading coil.

Eq 4 is valid only for antennas having a sinusoidal current distribution and no reactive loading. However, it can be used as a starting point for deriving an equation that is useful for shortened antennas with other than sinusoidal current distributions.

Refer to **Fig 8**. The current distribution on an antenna 90° long electrically ($^1/_4$ wavelength) varies with the cosine of the length in electrical degrees. The current distribution of the top 30° of the antenna is essentially linear. It is this linearity that allows for derivation of a simpler, more useful equation for radiation resistance.

The radiation resistance of an electrically short base-loaded vertical antenna can be conveniently defined in terms of a geometric figure, a triangle, as shown in **Fig 9**. The radiation resistance is given by:

$$R_R = KA^2 \qquad \text{(Eq 6)}$$

where

K is a constant (to be derived shortly)
A = area of the triangular current distribution in degree-amperes.

Degree-ampere area is expressed by

$$A = \frac{1}{2} h \times I_{base} \qquad \text{(Eq 7)}$$

Fig 9—Relative current distribution on a base-loaded vertical antenna of height H = 30 electrical degrees (linearized). The base loading coil is not shown here.

Fig 10—Relative current distribution on a center-loaded antenna with base and top sections each equal to 15 electrical degrees in length. The cross-hatched area shows the current distribution that would exist in the top 15° of a 90°-high vertical fed with 1 ampere at the base.

By combining Eqs 4 and 6 and solving for K, we get

$$K = \frac{h^2}{312 \times A^2} \qquad \text{(Eq 8)}$$

By substituting the values from Fig 9 into Eq 8 we get

$$K = \frac{30^2}{312 \times (0.5 \times 30 \times 1)^2} = 0.0128$$

and by substituting the derived value of K into Eq 6 we get

$$R_R = 0.0128 \times A^2 \qquad \text{(Eq 9)}$$

Eq 9 is useful for determining the radiation resistance of coil-loaded vertical antennas less than 30° in length. The derived constant differs slightly from that presented by Laport (see Bibliography), as he used a different equation for radiation resistance Eq 4.

When the loading coil is moved up an antenna (away from the feed point), the current distribution is modified as shown in **Fig 10**. The current varies with the cosine of the height in electrical degrees at any point in the base section. Therefore, the current flowing into the bottom of the loading coil is less than the current flowing at the base of the antenna.

But what about the current in the top section of the antenna? The loading coil acts as the lumped constant that it is, and disregarding losses and coil radiation, main-tains the same current flow throughout. As a result, the current at the top of a high-Q coil is essentially the same as that at the bottom of the coil. This is easily verified by installing RF ammeters immediately above and below the loading coil in a test antenna. Thus, the coil "forces" much more current into the top section than would flow in the equivalent section of a full 90° long antenna. This occurs as a result of the extremely high voltage that appears at the top of the loading coil. This higher current flow results in more radiation than would occur from the equivalent section of a quarter-wave antenna. (This is true for conventional coils. However, radiation from long thin coils allows coil current to decrease, as in helically wound antennas.)

The cross-hatched area in Fig 10 shows the current that would flow in the equivalent part of a 90° high antenna, and reveals that the degree-ampere area of the whip section of the short antenna is greatly increased as a result of the modified current distribution. The current flow in the top section decreases almost linearly to zero at the top. This can be seen in Fig 10.

The degree-ampere area of Fig 10 is the sum of the triangular area represented by the current distribution in the top section, and the nearly trapezoidal current distri-bution in the base section. Radiation from the coil is not included in the degree-ampere area because it is small and difficult to define. Any radiation from the coil can be considered a bonus.

The degree-ampere area is expressed by:

$$A = \frac{1}{2}\left[h_1\left(1 + \cos h_1\right) + h_2\left(\cos h_1\right)\right] \qquad \text{(Eq 10)}$$

where

h_1 = electrical length in degrees of the base section
h_2 = electrical height in degrees of the top section.

The degree-ampere area (calculated by substituting Eq 10 into Eq 9) can be used to determine the radiation resistance when the loading coil is at any position other than the base of the antenna. Radiation resistance has been calculated with these equations and plotted against loading coil position at three different frequencies for 8- and 11-foot antennas, **Fig 11**. Eight feet is a typical length for commercial antennas, and 11-foot antennas are about the maximum practical length that can be installed on a vehicle.

In Fig 11, the curves reveal that the radiation resistance rises almost linearly as the loading coil is moved up the antenna. They also show that the radiation resistance rises rapidly as the frequency is increased. If the analysis were stopped at this point, one might conclude that the loading coil should be placed at the top of the antenna. This is not so, and will become apparent shortly.

A1	1.9 MHz, 8'
A2	1.9 MHz, 11'
A3	3.9 MHz, 8'
A4	3.9 MHz, 11'
A5	7.225 MHz, 8'
A6	7.225 MHz, 11'

Fig 11—Radiation resistance plotted as a function of loading coil position.

Required Loading Inductance

Calculation of the loading coil inductance needed to resonate a short antenna can be done easily and accurately by using the antenna transmission-line analog described by Boyer in *Ham Radio*. For a base-loaded antenna, Fig 9, the loading coil reactance required to resonate the antenna is given by

$$X_L = -j\, K_m \cot h \qquad \text{(Eq 11)}$$

where

X_L = inductive reactance required
K_m = mean characteristic impedance (defined in Eq 12).

The $-j$ term indicates that the antenna presents capacitive reactance at the feed point. A loading coil must cancel this reactance.

The mean characteristic impedance of an antenna is expressed by

$$K_m = 60\left[\left(\ln \frac{2H}{a}\right) - 1\right] \qquad \text{(Eq 12)}$$

where

H = physical antenna height (excluding the length of the loading coil)
a = radius of the antenna in the same units as H.

From Eq 12 you can see that decreasing the height-to-diameter ratio of an antenna by increasing the radius results in a decrease in K_m. With reference to Eq 11, a decrease in K_m decreases the inductive reactance required to resonate an antenna. As will be shown later, this will increase radiation efficiency. In mobile applications, we quickly run into wind-loading problems if we attempt to use an antenna that is physically large in diameter.

If the loading coil is moved away from the base of the antenna, the antenna is divided into a base and top section, as depicted in Fig 10. The loading coil reactance required to resonate the antenna when the coil is away from the base is given by

$$X_L = j\, K_{m2}\left(\cot h_2\right) - j\, K_{m1}\left(\tan h_1\right) \qquad \text{(Eq 13)}$$

In mobile-antenna design and construction, the top section is usually a whip with a much smaller diameter than the base section. Because of this, it is necessary to compute separate values of K_m for the top and base sections. K_{m1} and K_{m2} are the mean characteristic impedances of the base and top sections, respectively.

Loading coil reactance curves for the 3.8-MHz antennas of Fig 11 have been calculated and plotted in **Fig 12**. These curves show the influence of the loading coil position on the reactance required for resonance. The curves in Fig 12 show that the required reactance decreases with longer antennas. The curves also reveal that the required loading coil reactance grows at an increasingly rapid rate after the coil passes the center of the antenna. Because the highest possible loading coil Q

Fig 12—Loading coil reactance required for resonance, plotted as a function of coil height above the antenna base. The resonant frequency is 3.9 MHz.

factor is needed, and because optimum Q is attained when the loading coil diameter is twice the loading coil length, the coil would grow like a smoke ring above the center of the antenna, and would quickly reach an impractical size. It is for this reason that the highest loading coil position is limited to one foot from the top of the antenna in all computations.

Loading Coil Resistance

Loading coil resistance constitutes one of the losses that consumes power that could otherwise be radiated by the antenna. Heat loss in the loading coil is not of any benefit, so it should be minimized by using the highest possible loading coil Q. Loading coil loss resistance is a function of the coil Q and is given by

$$R_C = \frac{X_L}{Q} \qquad \text{(Eq 14)}$$

where

R_C = loading coil loss resistance in Ω
X_L = loading coil reactance
Q = coil figure of merit

Inspection of Eq 14 reveals that, for a given value of inductive reactance, loss resistance will be lower for higher Q coils. Measurements made with a Q meter show that typical, commercially manufactured coil stock pro-

duces a Q between 150 and 160 in the 3.8-MHz band.

Higher Q values can be obtained by using larger diameter coils having a diameter-to-length ratio of two, by using larger diameter wire, by using more spacing between turns, and by using low-loss polystyrene supporting and enclosure materials. In theory, loading coil turns should not be shorted for tuning purposes because shorted turns somewhat degrade Q. Pruning to resonance should be done by removing turns from the coil.

In fairness, it should be pointed out that many practical mobile antennas use large-diameter loading coils with shorted turns to achieve resonance. The popular "Texas Bug Catcher" coils come to mind here. Despite general proscriptions against shorting turns, these systems are often more efficient than antennas with small, relatively low-Q, fixed loading coils.

Radiation Efficiency

The ratio of power radiated to power fed to an antenna determines the radiation efficiency. It is given by:

$$E = \frac{P_R}{P_I} \times 100\% \qquad \text{(Eq 15)}$$

where

E = radiation efficiency in percent
P_R = power radiated
P_I = power fed to the antenna at the feed point.

In a short, coil-loaded mobile antenna, a large portion of the power fed to the antenna is dissipated in ground and coil resistances. A relatively insignificant amount of power is also dissipated in the antenna conductor resistance and in the leakage resistance of the base insulator. Because these last two losses are both very small and difficult to estimate, they are here neglected in calculating radiation efficiency.

Another loss worth noting is matching network loss. Because we are concerned only with power fed to the antenna in the determination of radiation efficiency, matching network loss is not considered in any of the equations. Suffice it to say that matching networks should be designed for minimum loss in order to maximize the transmitter power available at the antenna.

The radiation efficiency equation may be rewritten and expanded as follows:

$$E = \frac{I^2 \, R_R \times 100}{I^2 \, R_R + I^2 \, R_G + \left(I \cos h_1\right)^2 R_C} \qquad \text{(Eq 16)}$$

where

I = antenna base current in amperes
R_G = ground loss resistance in Ω
R_C = coil loss resistance in Ω.

Each term of Eq 16 represents the power dissipated in its associated resistance. All the current terms cancel,

simplifying this equation to

$$E = \frac{R_R \times 100}{R_R + R_G + R_C \left(\cos^2 h_1 \right)}$$ (Eq 17)

For base-loaded antennas the term $\cos^2 h_1$ drops to unity and may be omitted.

Ground Loss

Eq 14 shows that the total resistive losses in the antenna system are:

$$R_T = R_R + R_G + R_c (\cos^2 h_1)$$ (Eq 18)

where R_T is the total resistive loss. Ground loss resistance can be determined by rearranging Eq 18 as follows:

$$R_G = R_T - R_R - R_C \cos^2 h_1$$ (Eq 19)

R_T may be measured in a test antenna installation on a vehicle using an R-X noise bridge or an SWR analyzer. You can then calculate R_R and R_C.

Ground loss is a function of vehicle size, placement of the antenna on the vehicle, and conductivity of the ground over which the vehicle is traveling. Only the first two variables can be feasibly controlled. Larger vehicles provide better ground planes than smaller ones. The vehicle ground plane is only partial, so the result is considerable RF current flow (and ground loss) in the ground around and under the vehicle.

By raising the antenna base as high as possible on the vehicle, ground losses are decreased. This results from a decrease in antenna capacitance to ground, which increases the capacitive reactance to ground. This, in turn, reduces ground currents and ground losses.

This effect has been verified by installing the same antenna at three different locations on two different vehicles, and by determining the ground loss from Eq 19. In the first test, the antenna was mounted 6 inches below the top of a large station wagon, just behind the left rear window. This placed the antenna base 4 feet 2 inches above the ground, and resulted in a measured ground loss resistance of 2.5 Ω. The second test used the same antenna mounted on the left rear fender of a mid-sized sedan, just to the left of the trunk lid. In this test, the measured ground loss resistance was 4 Ω. The third test used the same mid-sized car, but the antenna was mounted on the rear bumper. In this last test, the measured ground loss resistance was 6 Ω.

The same antenna therefore sees three different ground loss resistances as a direct result of the antenna mounting location and size of the vehicle. It is important to note that the measured ground loss increases as the antenna base nears the ground. The importance of minimizing ground losses in mobile antenna installations cannot be overemphasized.

Efficiency Curves

With the equations defined previously, a computer

Fig 13—Radiation efficiency of 8-foot antennas at 3.9 MHz.

Fig 14—Radiation efficiency of 11-foot antennas at 3.9 MHz.

Fig 15—Radiation efficiency of 8-foot antennas at 7.225 MHz.

Fig 16—Radiation efficiency of 11-foot antennas at 7.225 MHz.

was used to calculate the radiation efficiency curves depicted in **Figs 13** through **16**. These curves were calculated for 3.8- and 7-MHz antennas of 8- and 11-foot lengths. Several values of loading coil Q were used, for both 2 and 10 Ω of ground loss resistance. For the calculations, the base section is ¹/₂-inch diameter electrical EMT, which has an outside diameter of ¹¹/₁₆ inch. The top section is fiberglass bicycle-whip material covered with Belden braid. These are readily available materials, which can be used by the average amateur to construct an inexpensive but rugged antenna.

Upon inspection, these radiation-efficiency curves reveal some significant information:
1) Higher coil Q produces higher radiation efficiencies,
2) longer antennas produce higher radiation efficiencies,
3) higher frequencies produce higher radiation efficiencies,
4) lower ground loss resistances produce higher radiation efficiencies,
5) higher ground loss resistances force the loading coil above the antenna center to reach a crest in the radiation-efficiency curve, and
6) higher coil Q sharpens the radiation-efficiency curves, resulting in the coil position being more critical for optimum radiation efficiency.

Note that the radiation efficiency curves reach a peak and then begin to decline as the loading coil is raised farther up the antenna. This is because of the rapid increase in loading coil reactance required above the antenna center. Refer to Fig 12. The rapid increase in coil size required for resonance results in the coil loss resistance increasing much more rapidly than the radiation resistance. This results in decreased radiation efficiency, as shown in Fig 11.

A slight reverse curvature exists in the curves between the base-loaded position and the one-foot coil-height position. This is caused by a shift in the curve resulting from insertion of a base section of larger diameter than the whip when the coil is above the base.

The curves in Figs 13 through 16 were calculated with constant (but not equal) diameter base and whip sections. Because of wind loading, it is not desirable to increase the diameter of the whip section. However, the base-section diameter can be increased within reason to further improve radiation efficiency. **Fig 17** was calculated for base-section diameters ranging from ¹¹/₁₆ inch to 3 inches. The curves reveal that a small increase in radiation efficiency results from larger diameter base sections.

The curves in Figs 13 through 16 show that radiation efficiencies can be quite low in the 3.8-MHz band compared to the 7-MHz band. They are lower yet in the 1.8-MHz band. To gain some perspective on what these low efficiencies mean in terms of signal strength, **Fig 18** was calculated using the following equation:

$$dB = \log \frac{100}{E} \qquad \text{(Eq 20)}$$

Fig 17—Radiation efficiency plotted as a function of base section diameter. Frequency = 3.9 MHz, ground loss resistance = 2 Ω, and whip section = ¹/₄-inch diameter.

Fig 18—Mobile antenna signal loss as a function of radiation efficiency, compared to a quarter-wave vertical antenna over perfect ground.

where

dB = signal loss in decibels
E = efficiency in percent.

The curve in Fig 18 reveals that an antenna having 25% efficiency has a signal loss of 6 dB (approximately one S unit) below a quarter-wave vertical antenna over perfect ground. An antenna efficiency in the neighborhood of 6% will produce a signal strength on the order of two S units or about 12 dB below the same quarter-wave reference vertical. By careful optimization of mobile-antenna design, signal strengths from mobiles can be made fairly competitive with those from fixed stations using comparable power. And don't forget: Moving your car near saltwater, with its high conductivity, can result in surprisingly strong signals from a mobile station!

Impedance Matching

The input impedance of short, high-Q coil-loaded antennas is quite low. For example, an 8-foot antenna optimized for 3.9 MHz with an unloaded coil Q of 300 and a ground-loss resistance of 2 Ω has a base input impedance of about 13 Ω. This low impedance value causes a standing wave ratio of 4:1 on a 50-Ω coaxial line at resonance. This high SWR is not compatible with the requirements of solid-state transmitters. Also, the bandwidth of shortened vertical antennas is very narrow. This severely limits the capability to maintain transmitter loading over even a small frequency range.

Impedance matching can be accomplished by means of L networks or impedance-matching transformers, but the narrow bandwidth limitation remains. A more elegant solution to the impedance matching and narrow bandwidth problem is to install an automatic tuner at the antenna base. Such a device matches the antenna and coaxial line automatically, and permits operation over a wide frequency range.

The tools are now available to tailor a mobile antenna design to produce maximum radiation efficiency. Mathematical modeling with a personal computer reveals that loading coil Q factor and ground loss resistance greatly influence the optimum loading coil position in a short vertical antenna. It also shows that longer antennas, higher coil Q, and higher operating frequencies produce higher radiation efficiencies.

End effect has not been included in any of the equations to assure that the loading coil will be slightly larger than necessary. Pruning the antenna to resonance should be done by removing coil turns, rather than by shorting turns or shortening the whip section excessively. Shortening the whip reduces radiation efficiency, by both shortening the antenna and moving the optimum coil position. Shorting turns in the loading coil degrades the Q of the coil.

Shortened Dipoles

Mathematical modeling techniques can be applied to shortened dipoles by using zero ground loss resistance

and by doubling the computed values of radiation resistance and feed-point impedance. Radiation efficiency, however, does not double. Rather, it remains unchanged, because a second loading coil is required in the other leg of the dipole. The addition of the second coil offsets the gain in efficiency that occurs when the feed-point impedance and radiation resistance are doubled. There is a gain in radiation efficiency over a vertical antenna worked against ground, though, because the dipole configuration allows ground loss resistance to be eliminated from the calculations.

CONTINUOUSLY LOADED ANTENNAS

The design of high-Q air core inductors for RF work is complicated by the number of parameters that must be optimized simultaneously. One of these factors affecting coil Q adversely is radiation from a discrete loading coil. Therefore, the possibility of cutting down other losses while incorporating the coil radiation into that from the rest of the antenna system is an attractive one.

The general approach has been to use a coil made from heavy wire (#14 or larger), with length-to-diameter ratios as high as 21. British experimenters have reported good results with 8-foot overall lengths on the 1.8- and 3.5-MHz bands. The idea of making the entire antenna out of one section of coil has also been tried with some success. This technique is referred to as linear loading. Further information on linear-loaded antennas can be found in Chapter 6.

While going to extremes trying to find a perfect loading arrangement may not improve antenna performance very much, a poor system with lossy coils and high-resistance connections must be avoided if a reasonable signal is to be radiated.

MATCHING TO THE TRANSMITTER

Most modern transmitters require a 50-Ω output load, and because the feed-point impedance of a mobile whip is quite low, a matching network is usually necessary. Although calculations are helpful in the initial design, considerable experimenting is often necessary in final tune-up. This is particularly true for the lower bands, where the antenna is electrically short compared with a quarter-wave whip. The reason is that the loading coil is required to tune out a very large capacitive reactance, and even small changes in component values result in large reactance variations. Since the feed-point resistance is low to begin with, the problem is even more aggravated.

You can transform the low resistance of the whip to a value suitable for a 50-Ω system with an RF transformer or with a shunt-feed arrangement, such as an L network. The latter may only require a shunt coil or shunt capacitor at the base of the whip, since the net series capacitive or inductive reactance of the antenna and its loading coil may be used as part of the network. The following example illustrates the calculations involved.

Assume that a center-loaded whip antenna, 8.5 feet in overall length, is to be used on 7.2 MHz. From Table 1, earlier in this chapter, we see that the feed-point resistance of the antenna will be approximately 19 Ω, and from Fig 5 that the capacitance of the whip, as seen at its base, is approximately 24 pF. Since the antenna is to be center loaded, the capacitance value of the section above the coil will be cut approximately in half, to 12 pF. From this, it may be calculated that a center-loading inductor of 40.7 μH is required to resonate the antenna, that is, to cancel out the capacitive reactance. (This figure agrees with the approximate value of 40 μH shown in Table 1. The resulting feed-point impedance would then be 19 + j 0 Ω—a good match, *if* one happens to have a supply of 19-Ω coax.)

Solution: The antenna can be matched to a 52-Ω line such as RG-8 by tuning it either above or below reso-

Fig 19—Admittance diagram of the RLC circuit consisting of the whip capacitance, radiation resistance and loading coil discussed in text. The horizontal axis represents conductance, and the vertical axis susceptance. The point P_0 is the input admittance with no whip loading inductance. Points P1 and P2 are described in the text. The conductance equals the reciprocal of the resistance, if no reactive components are present. For a series RX circuit, the conductance is given by

$$G = \frac{R}{R^2 + X^2}$$

and the susceptance is given by

$$B = \frac{-X}{R^2 + X^2}$$

Consequently, a parallel equivalent GB circuit of the series RX one can be found which makes computations easier. This is because conductances and susceptances add in parallel the same way resistances and reactances add in series.

nance and then canceling out the undesired component with an appropriate shunt element, capacitive or inductive. The way in which the impedance is transformed up can be seen by plotting the admittance of the series RLC circuit made up of the loading coil, antenna capacitance, and feed-point resistance. Such a plot is shown in **Fig 19** for a constant feed-point resistance of 19 Ω. There are two points of interest, P1 and P2, where the input conductance is 19.2 millisiemens, corresponding to 52 Ω. The undesired susceptance is shown as $1/X_P$ and $-1/X_P$, which must be canceled with a shunt element of the opposite sign, but with the same magnitude. The value of the canceling shunt reactance, X_P, may be found from the formula:

$$X_p = \frac{R_f \, Z_0}{\sqrt{R_f \left(Z_0 - R_f \right)}} \qquad \text{(Eq 21)}$$

where X_p is the reactance in Ω, R_f is the feed-point resistance, and Z_0 is the feed-line impedance. For Z_0 = 52 Ω and R_f = 19 Ω, X_p = ±39.5 Ω. A coil or good quality mica capacitor may be used as the shunt element. With the tune-up procedure described later, the value is not critical, and a fixed-value component may be used.

To arrive at point P1, the value of the center loading-coil inductance would be less than that required for resonance. The feed-point impedance would then appear capacitive, and an inductive shunt matching element would then be required. To arrive at point P2, the center loading coil should be more inductive than required for resonance, and the shunt element would need to be capacitive.

The value of the center loading coil required for the shunt-matched and resonated condition may be deter-

mined from the equation:

$$L = \frac{10^6}{4\pi^2 f^2 C} \pm \frac{X_S}{2\pi f} \qquad \text{(Eq 22)}$$

where addition is performed if a capacitive shunt is to be used, or subtraction performed if the shunt is inductive, and where L is in μH, f is the frequency in MHz, C is the capacitance of the antenna section being matched in pF, and

$$X_S = \sqrt{R_f \left(Z_0 - R_f \right)} \qquad \text{(Eq 23)}$$

For the example given, where Z_0 = 52 Ω, R_f = 19 Ω, f = 7.2 MHz, and C = 12 pF, X_S is found to be 25.0 Ω. The required antenna loading inductance is either 40.2 μH or 41.3 μH, depending on the type of shunt. Various matching possibilities for this example are shown in **Fig 20**. At A, the antenna is shown as tuned to resonance with L_L, a 40.7 μH coil, but with no provisions included for matching the resulting 19-Ω impedance to the 52-Ω line. At B, L_L has been reduced to 40.2 μH to make the antenna appear net capacitive, and L_M, having a reactance of 39.5 Ω, is added in shunt to cancel the capacitive reactance and transform the feed-point impedance to 50 Ω. The arrangement at C is similar to that at B except that L_L has been increased to 41.3 μH, and C_M (a shunt capacitor having a negative reactance of 39.5 Ω) is added, which also results in a 52-Ω nonreactive termination for the feed line.

The values determined for the loading coil in the above example point out an important consideration concerning the matching of short antennas—relatively small changes in values of the loading components will have a greatly magnified effect on the matching requirements. A change of less than 3% in the loading coil inductance value necessitates a completely different matching network! Likewise, calculations show that a 3% change in antenna capacitance will give similar results, and the value of the precautions mentioned earlier becomes clear. The sensitivity of the circuit with regard to frequency variations is also quite critical, and an excursion around practically the entire circle in Fig 19 may represent only 600 kHz, centered around 7.2 MHz, for the above example. This is why tuning up a mobile antenna can be very frustrating unless a systematic procedure is followed.

Tune-Up

Assume that inductive shunt matching is to be used with the antenna in the previous example, Fig 20B, where 39.5 Ω is needed for L_M. This means that at 7.2 MHz, a coil of 0.87 μH will be needed across the whip feed-point terminal to ground. With a 40-μH loading coil in place, the adjustable whip section above the loading coil should be set for minimum height. Signals in the receiver will sound weak and the whip should be lengthened a bit at a time until signals start to peak. Turn the transmitter on and check the SWR at a few frequencies to find where a

Fig 20—At A, a whip antenna that is resonated with a center loading coil. At B and C, the value of the loading coil has been altered slightly to make the feed-point impedance appear reactive, and a matching component is added in shunt to cancel the reactance. This provides an impedance transformation to match the Z_0 of the feed line. An equally acceptable procedure, rather than altering the loading coil inductance, is to adjust the length of the top section above the loading coil for the best match, as described in the tune-up section of the text.

minimum occurs. If it is below the desired frequency, shorten the whip slightly and check again. It should be moved approximately $1/4$ inch at a time until the SWR is minimum at the center of the desired range. If the frequency where the minimum SWR occurs is above the desired frequency, repeat the procedure above, but lengthen the whip only slightly.

If a shunt capacitance is to be used, as in Fig 20C, a value of 560 pF would correspond to the required $-39.5\ \Omega$ of reactance at 7.2 MHz. With a capacitive shunt, start with the whip in its longest position and shorten it until signals peak up.

Fig 21—A capacitance hat can be used to improve the performance of base- or center-loaded whips. A solid metal disc can be used in place of the skeleton disc shown here.

TOP-LOADING CAPACITANCE

Because the loss resistance varies with the inductance of the loading coil, the resistance can be reduced by removing turns from the coil. This must be compensated by adding capacitance to the portion of the mobile antenna that is *above* the loading coil (**Fig 21**). *Capacitance hats*, as they are called, can consist of a single stiff wire, two wires or more, or a disc made up of several wires like the spokes of a wheel. A solid metal disc could also be used, but is less practical for mobile work. The larger the capacitance hat (physically), the greater is the capacitance. The greater the capacitance, the less is the inductance required for resonance at a given frequency.

Capacitance-hat loading is applicable in either base-loaded or center-loaded systems. Since more inductance is required for center-loaded whips to make them resonant at a given frequency, capacitance hats are particularly useful in improving their efficiency.

TAPPED-COIL MATCHING NETWORK

Some of the drawbacks of the L-network can be eliminated by the use of the tapped-coil arrangement shown in **Fig 22**. Tune-up still remains critical, however, although somewhat more straightforward than for an L-network.

Fig 22—A mobile antenna using shunt-feed matching. Overall antenna resonance is determined by the combination of L1 and L2. Antenna resonance is set by pruning the turns of L1, or adjusting the top section of the whip, while observing the field-strength meter or SWR indicator. Then adjust the tap on L2 for the lowest SWR.

Coil L2 can be inside the car body, at the base of the antenna, or at the base of the whip. As L2 helps determine the resonance of the antenna, L1 should be tuned to resonance in the desired part of the band with L2 in the circuit. The top section of the whip can be telescoped until a field-strength maximum is found. The tap on L2 is then adjusted for the lowest reflected power. Repeat these two adjustments until no further increase in field strength can be obtained; this point should coincide with the lowest SWR. The number of turns needed for L2 will have to be determined experimentally.

THE "SCREWDRIVER" MOBILE ANTENNA

Imagine QSYing from the bottom of 80 meters to the top of 10 meters, right from the driver's seat. With this antenna you will enjoy a very high Q antenna that has no taps or external adjustments, and that exhibits an SWR under 1.5:1 on all bands. Max Bloodworth, KO4TV, described this antenna in *The ARRL Antenna Compendium, Vol 7*.

The Screwdriver type of antenna was the brainchild of Don Johnson, W6AAQ, who developed it after many years of experimenting with mobile antennas. **Fig 23** is a

Fig 23—The completed Screwdriver antenna mounted on KO4TV's truck rear bumper. (*Photo courtesy of Gary Pearce, KN4AQ.*)

photo of the completed antenna mounted on KO4TV's truck.

THE LOADING COIL

The general concept for the Screwdriver is that of a center-loaded antenna with an adjustable loading coil. This is an old idea; however, most previous multi-band antennas required multiple coil taps and an adjustable top whip section, as well as an impedance-matching unit at the base.

The problem of tapping a coil is well known. If you leave one end of the coil open, you have a miniature Tesla Coil, which can cause corona discharge and arcing. If you short the turns, the Q of the loading coil usually drops drastically. The Screwdriver is remarkable in that it does not have any coil taps and yet it can cover a wide range of frequencies with very high Q.

The secret is in the manner of adjusting the coil. It simply slides up or down into a metal tube (the base section), and makes contact with the top of the tube by means of "finger stock," which is made of spring-like Beryllium Copper. The coil is pushed up or down by an ordinary cordless screwdriver; hence the name, Screwdriver. This turns a section of threaded rod and moves the coil form up or down. The section of coil above the finger stock is the active loading coil, and the part of the coil just below the finger stock simply "disappears" into the base tube and is totally out of the circuit. No taps, no loose ends—just a high-Q coil in the middle of two solid metal tubes. Although this antenna is available ready-made from several commercial sources, making one is well within the capabilities of any ham who is relatively handy with ordinary hand tools, and who has access to either a small lathe or a common $1^1/_4$-inch pipe die.

Finger Stock

2" Base Tube

Fig 24—The base tube, with finger stock attached to the top.

CONSTRUCTING YOUR SCREWDRIVER ANTENNA

Construction begins by locating a 2-inch inside-diameter tube, about 3 to $3^{1}/_{2}$ feet long. See **Fig 24**. The author had used such diverse materials as:

- Aluminum irrigation pipe
- Schedule-20 copper tubing
- A stainless-steel hydraulic cylinder
- A section of aluminum from a 6-meter beam that was damaged by a tornado
- And even a brass bedpost salvaged from the local garbage dump.

The brass bedpost looked especially good on his vehicle, which was Burgundy with gold trim. Whatever material you use for the bottom tube, you can either leave it unfinished or painted to your taste.

The other essential item is a cordless screwdriver, minus its batteries and switch. You can often find one at yard sales or flea markets for a dollar or so, usually with dead batteries, since it is often just as cheap to buy another one new as it is to buy new batteries. So long as it will fit snugly inside the base tube, the brand name is immaterial. KO4TV has used Skil, Black & Decker, or even a Wal-Mart $8 special, all with equal success. The most difficult part of the job will be making the coil form and winding the loading coil, but with a little patience you should be able to do this satisfactorily.

Bear in mind that it is *not* a "Heathkit" type project, and it will require some innovation and ingenuity on your part. Next, obtain a 2-foot long piece of $1^{1}/_{4}$-inch PVC pipe (*not* CPVC, which is vulnerable to ultraviolet rays from the sun). With either a lathe or a pipe die, thread approximately 20 inches from one end, at 10 to 12 threads per inch (See **Fig 25**). If you use a pipe die, it helps to loosen the cutters slightly, to make the grooves shallower.

When using a lathe, temporarily insert a piece of 1-inch water pipe inside the coil form to hold it steady in the lathe. The grooves should be just deep enough to comfortably hold the wire in place when it is wound. The choice of coil wire is up to you. The author has used #16 or #18 tinned copper, bare copper, or best yet, 17-gauge aluminum electric fence wire. This is available from any

1-1/4" PVC Cap

180 Turns Bare Wire

1-1/4" x 24" PVC

1" PVC Cap Inside Form

1/4" Threaded Insert

Fig 25—The coil form, with a threaded insert inserted into the bottom PVC cap inside the coil form.

Fig 26—Photo of the top of the loading coil. (*Photo courtesy of Gary Pearce, KN4AQ.*)

farm supply store at a very reasonable cost. It will take about 65 to 70 feet of wire.

Begin by drilling a $^1/_{16}$-inch hole through the PVC pipe at the bottom end of the threaded portion. Slip the end of the wire through this hole and tie a knot in it to serve as a stop. You could also insert a nut and bolt through a loop in the wire. Then carefully wind the coil to within an inch of the end of the threaded portion. The preferred method of winding is to put a stick or pipe through the holes of the wire reel and hold it between your feet and the floor, to provide the necessary tension to allow tight winding.

About an inch below the top of the coil, drill a $^1/_{16}$-inch hole and thread about 6 or 8 inches of wire through it. This will be the top connection from the coil to the whip. The bottom of the coil has no electrical connection.

The method of attaching the whip to the top of the coil form is up to you. I usually drill a $^3/_8$-inch hole through a $1^1/_4$-inch PVC pipe cap and place a $^3/_8 \times 1^1/_2$-inch SAE bolt through the hole, with a matching washer and nut on top. The bolt can be drilled and tapped for mounting the whip, which should be about 5 to 6 feet long. (It will be pruned for resonance later.) See **Fig 26**, a photo showing the top of the coil.

A more elegant way of connecting the whip is to obtain a swivel or quick-disconnect antenna fitting from your nearest truck stop. These are widely available for use with CB antennas and are threaded $^3/_8$-inch SAE. Do not attach the cap to the coil form until after the coil is inserted in the base tube.

Now that you have a coil form and a base tube, the next step will be to plug the bottom of the PVC coil form with a 1-inch PVC pipe cap, which fits snugly inside the coil form. Drill a hole directly in the center of this cap, and install a $^1/_4$-20 threaded insert, available at most hardware stores for about 25 or 30 cents. These are commonly used in wooden furniture to provide a thread for attaching bolts to wood. See **Fig 27**.

It is imperative that you install this insert squarely. The best method is to screw a short bolt into it and chuck the bolt in a drill press, placing the pipe cap

Fig 27—The coil assembly and cordless screwdriver drive assembly.

Fig 28—The complete antenna assembly.

squarely on the drill press table. Carefully turn the drill chuck by hand until the insert is properly seated.

The Motor

Now prepare the cordless drill by removing the dead batteries and the switch. Install a pair of 1 or 1.5-Ω, 10-W resistors in series with each motor lead. Connect a 0.1 µF 50-V disc ceramic capacitor across the motor leads to suppress motor noise.

Connect a pair of wires, about a foot long, to the other ends of the resistors. These will power the screwdriver from your car's 12-V system. Next, procure a 20-inch long piece of $^1/_4$-20 threaded rod (also called "all-thread"). Insert one end of this into the cordless screwdriver chuck, and drill a $^1/_{16}$-inch or $^3/_{32}$-inch hole through both the chuck and the rod. Secure the rod in place with either a roll or cotter pin, and install a pair of $^1/_4$-inch nuts on the rod near the screwdriver chuck. This will be the lower stop for the coil travel and will be adjusted later.

Thread the rod into the threaded insert at the bottom of the coil form, and install another pair of stop nuts on the top side of the rod. It will be easier to do this before attaching the bottom plug to the coil form. Again, these nuts will be adjusted later for proper coil travel.

Place the bottom plug into the coil form, drill a couple of holes through the form and the plug and tap them for 6-32 flat head bolts. Countersink the form so that the heads will be flush with the outside. Again, see **Fig 27**.

Finger Stock

Now, let's go back to the base tube. You must install a circle of finger-stock strip on the top of the tube to make contact with the coil, as shown in Fig 24. This can either be soldered or riveted, depending on your choice of tube material. Next, insert the coil and screwdriver assembly through the bottom of the tube, making sure that the coil clears the finger stock without deforming or bending it.

The best method I have found for attaching the screwdriver to the bottom tube is to fit a piece of 1$^1/_2$-inch PVC pipe, about 8 or 10 inches long, over the handle of the screwdriver and attach it with a couple of flat-head 6-32 bolts. You may have to either grind some material off the handle or wrap it with some duct tape to make a snug fit inside the 1$^1/_2$-inch PVC pipe, which should slip snugly into the base tube.

Place a matching 1$^1/_2$-inch PVC pipe cap on the bottom of the pipe, and secure it with a couple of 6-32 screws. Drill a $^1/_4$-inch hole through one side of the cap, which will serve to pass the wires from the screwdriver motor. Drill a $^3/_8$-inch hole directly in the center of this cap for the base

mount. See **Fig 28**, which is a drawing of the completed antenna assembly.

MOUNTING THE ANTENNA

At this point you must determine exactly how you wish to mount the antenna on your vehicle. You could fasten it to a standard mobile antenna mount, but *do not* use a spring! I prefer to fasten the assembly to a thick metal plate about 6×18 inches in size. I mount this to the frame of the car, protruding about 4 or 5 inches from the lower car body, just behind the rear wheel. You could also fasten such a plate to the lower fender sheet metal with large sheet-metal screws. The SO-239 connector is mounted to this plate also. See **Fig 29**.

An upper bracket, made from Plexiglas or similar insulating material, can be mounted from the trunk lip with an L-angle and used to support the top of the lower tube. See **Fig 30**. With a Plexiglas bracket about 4-inches wide, a 2-inch hole can be drilled in it to pass the tube. This will make a snug and rigid fit at the top. Under no circumstances use a metal band around the tube, as this will form a shorted turn and drastically lower the antenna Q.

With a little care, this type of mounting will leave no visible holes in the vehicle, which will likely enhance its trade-in value. If you mount the antenna on a pickup truck, it can be mounted directly on the rear safety bumper with a 1$^1/_2$ inch pipe floor flange and matching adaptor on the bottom of the tube.

Electrical Connections

After mounting the base, your next job is to connect the wires from the screwdriver to a DPDT, spring-return center-off switch, mounted in a convenient location in your car. See the schematic in **Fig 31**. Connect the coax from the radio to the base tube, with the center conductor going to the base tube and the shield connected to ground at the base of the antenna.

If you like, you could install a simple base-matching network to give a perfect match on the lower bands. Even with no matching unit, SWR is usually under 2:1 on all

Fig 29—Base-mounting plate for Screw-driver installation on KO4TV's truck. Note the quick-disconnect dc motor con-nections and the SO-239 coax connector.

Fig 30—The support Plexiglas plate. (*Photo courtesy of Gary Pearce, KN4AQ.*)

Fig 31—The DPDT center-off spring-loaded switch used to control the screwdriver motor.

Fig 33—Alternative matching scheme using a single shunt matching coil.

15 T, #14 Enamel 1/2" Dia.

400 pF

800 pF

Relay 1

Relay 2

40m   80m

SPDT Center Off Switch

12 V

Fig 32—Relay-switched matching capacitors for 40 and 80 meters.

bands. See **Fig 32**. One matching network consists of a couple of trimmer capacitors switched from the bottom of the base tube to ground using a pair of small relays. For 80 meters, approximately 800 pF is required, and for 40 meters about 400 pF. No matching is required for 30 meters or higher.

An alternative matching method is to install a 15-turn coil made from #14 enamel wire, about $^1/_2$ inch diameter, from the base to ground. See **Fig 33**. In either case, adjust the whip length for proper resonance at both ends of the HF spectrum over the range of movement of your coil.

This antenna may have different matching requirements, depending on the vehicle type and mounting location, so you may need to do some experimentation to obtain optimum results. If it doesn't work exactly right at first, be prepared to do a little experimenting.

A COIL COVER

Most builders will want to provide a coil cover, both for protection and appearance. KO4TV's favorite cover is made from a plastic mailing tube, about 24 to 30 inches long and about $^1/_2$ inches in diameter. You can find these at an office supply store. They have a screw-on cap on one end, which can be mounted to the top of the loading coil.

Fig 34—Remote control by the rear-view mirror—tuning by the stripes! (*Photo courtesy of Gary Pearce, KN4AQ.*)

You trim the bottom of the cover to the proper length to allow the coil to be fully retracted into the base tube while still clearing the top bracket. Other builders have used such diverse materials as:

- Several 1-liter soft drink bottles cut off, swaged and glued together
- Sections of Schedule 20 PVC pipe with matching cap
- Empty beef jerky tubes (usually available for the asking at convenience stores)
- Wands from a shop vacuum cleaner, fitted with the cap from an aerosol spray can.

Just let your imagination run wild and you may be surprised at your own ingenuity. Whatever material you do use, paint it to match your vehicle. Just be sure to use non-metallic paint.

TUNING BY THE STRIPES

The author used different colored vinyl tapes to mark the tuning points for the amateur bands along the tuning coil. The lower edge of the supporting Plexiglas middle support acts as a pointer, which he can spot from his rear-view mirror. See **Fig 34**. This may be low-tech tuning method, but it works!

THE PROOF IS IN THE PUDDING

Now, you are ready to enjoy some real mobile communications on all bands, without even stopping the vehicle to QSY. KO4TV's antenna has contacted over 100 DX countries, from as far away as Tasmania and Japan from the East Coast. He enjoys regular contacts with Israel and other stations in the Mid-East, running 100 W or less.

A MOBILE J ANTENNA FOR 144 MHz

The J antenna is a mechanically modified version of the Zepp (Zeppelin) antenna. It consists of a half-wavelength radiator fed by a quarter-wave matching stub. This antenna exhibits an omnidirectional pattern with little high-angle radiation, but does not require the ground plane that $1/4$-wave and $5/8$-wave antennas do to work properly. The material in this section was prepared by Domenic Mallozzi, N1DM, and Allan White, W1EYI.

Fig 35 shows two common configurations of the J antenna. Fig 35A shows the shorted-stub version that is usually fed with 200- to 600-Ω open-wire line. Some have attempted to feed this antenna directly with coax without a balun, and this usually leads to less than optimum results. Among the problems with such a configuration are a lack of reproducibility and heavy coupling with nearby objects. To eliminate these problems, many

Fig 35—Two configurations of the J antenna.

Fig 36—The mount for the mobile J is made from stainless-steel angle stock and secured to the bumper with stainless-steel hardware. Note the $1/2$-inch pipe plug and a PL-259 (with a copper disc soldered in its unthreaded end). These protect the mount and connector threads when the antenna is not in use.

Fig 37—The J antenna, ready for use. Note the bakelite insulator and the method of feed. Tie wraps are used to attach the balun to the mounting block and to hold the coax to the support pipe. Clamps made of flashing copper are used to connect the balun to the J antenna just above the insulating block. The ends of the balun should be weatherproofed.

Fig 38—Details of the insulated mounting block. The material is bakelite.

Fig 39—Measured SWR of the mobile J antenna.

amateurs have used a 4:1 half-wave balun between the feed point and a coaxial feed line. This simple addition results in an antenna that can be easily reproduced and that does not interact so heavily with surrounding objects. The bottom of the stub may be grounded (for mechanical or other reasons) without impairing the performance of the antenna.

The open-stub-fed J antenna shown in Fig 35B can be connected directly to low-impedance coax lines with good results. The lack of a movable balun (which allows some impedance adjustment) may make this antenna a bit more difficult to adjust for minimum SWR, however.

The Length Factor

Dr. John S. Belrose, VE2CV, noted in *The Canadian Amateur* that the diameter of the radiating element is important to two characteristics of the antenna—its bandwidth and its physical length. (See Bibliography at the end of this chapter.) As the element diameter is increased, the usable bandwidth increases, while the physical length of the radiating element decreases with respect to the free-space half-wavelength. The increased diameter makes the end effect more pronounced, and also slows the velocity of propagation on the element. These two effects are related to resonant antenna lengths by a factor, "k." This factor is expressed as a decimal fraction giving the equivalent velocity of propagation on the antenna wire as a function of the ratio of the element diameter to a wavelength. The k factor is discussed at length in Chapter 2.

The length of the radiating element is given by

$$\ell = \frac{5904 \times k}{f} \qquad \text{(Eq 25)}$$

where

 ℓ = length in inches
 f = frequency in MHz
 k = k factor.

The k factor can have a significant effect. For example, if you use a $^5/_8$-inch diameter piece of tubing for the radiator at 144 MHz, the k value is 0.907 (9.3% shorter than a free-space half wavelength).

The J antenna gives excellent results for both mobile and portable work. The mobile described here is similar to an antenna described by W. B. Freely, K6HMS, in April 1977 *QST*. This design uses mechanical components that are easier to obtain. As necessary with all mobile antennas, significant attention has been paid to a strong, reliable, mechanical design. It has survived not only three New England winters, but also two summers of 370-mile weekend commutes. During this time, it has maintained consistent electrical performance with no noticeable deterioration.

The mechanical mount to the bumper is a 2 × 2-inch stainless steel angle iron, 10 inches long. It is secured to the bumper with stainless steel hardware, as shown in **Fig 36**. A stainless steel $^1/_2$-inch pipe coupling is welded to the left side of the bracket, and an SO-239 connector is mounted at the right side of the bracket. The bracket is mounted to the bumper so a vertical pipe inserted in the coupling will allow the hatchback of the vehicle to be opened with the antenna installed, **Fig 37**.

A $^1/_2$-inch galvanized iron pipe supports the antenna so the radiating portion of the J is above the vehicle roof line. This pipe goes into a bakelite insulator block, visible in Fig 37. The insulator block also holds the bottom of the stub. This block was first drilled and then split with a band saw, as shown in **Fig 38**. After splitting, the two portions are weatherproofed with varnish and rejoined with 10-32 stainless hardware. The corners of the insulator are cut to clear the L sections at the shorted end of the stub.

The quarter-wave matching section is made of $^1/_4$-inch type L copper tubing ($^5/_{16}$ inch ID, $^3/_8$ inch OD). The short at the bottom of the stub is made from two copper L-shaped sections and a short length of $^1/_4$-inch tubing. Drill a $^1/_8$-inch hole in the bottom of this piece of tubing to drain any water that may enter or condense in the stub.

A $^5/_{16}$-inch diameter brass rod, $1^1/_2$ to 2 inches long, is partially threaded with a $^5/_{16} \times 24$ thread to accept a Larsen whip connector. This rod is then sweated into one of the legs of the quarter-wave matching section. A 40-inch whip is then inserted into the Larsen connector.

The antenna is fed with 50-Ω coaxial line and a coaxial 4:1 half-wave balun. This balun is described at the end of Chapter 26. As with any VHF antenna, use high-quality coax for the balun. Seal all open cable ends and the rear of the SO-239 connector on the mount with RTV sealant.

Adjustment is not complicated. Set the whip so that its tip is 41 inches above the open end of the stub, and adjust the balun position for lowest SWR. Then adjust the height of the whip for the lowest SWR at the center frequency you desire. **Fig 39** shows the measured SWR of the antenna after adjustments are completed.

THE SUPER-J MARITIME ANTENNA

This 144-MHz vertical antenna doesn't have stringent grounding requirements and can be made from easy to find parts. The material in this section was prepared by Steve Cerwin, WA5FRF, who developed the Super-J for use on his boat.

Antennas for maritime use must overcome difficulties that other kinds of mobile antennas normally do not encounter. For instance, the transom of a boat is the logical place to mount an antenna. But the transoms of many boats are composed mostly of fiberglass, and they ride some distance out of the water—from several inches to a few feet, depending on the size of the vessel. Because the next best thing to a ground plane (the water surface) is more than an appreciable fraction of a wavelength away at 144 MHz, none of the popular gain-producing antenna designs requiring a counterpoise are suitable. Also, since a water surface does a good job of assuming the earth's lowest mean elevation (at least on a calm day), anything that can be done to get the radiating part of the antenna up in the air is helpful.

One answer is the venerable J-pole, with an extra in-phase half-wave section added on top—the Super-J antenna. The two vertical half waves fed in phase give outstanding omnidirectional performance for a portable antenna. Also, the J-pole feed arrangement provides the desired insensitivity to height above ground (or water) plus added overall antenna height. Best of all, a $^1/_4$-wave CB whip provides enough material to build the whole driven element of the antenna, with a few inches to spare. The antenna has enough bandwidth to cover the entire 144-MHz band, and affords a measure of lightning protection by being a grounded design.

Antenna Operation

The antenna is represented schematically in **Fig 40**. The classic J-pole antenna is the lower portion shown between points A and C. The half-wave section between points B and C does most of the radiating. The added half-wave section of the Super-J version is shown between points C and E. The side-by-side quarter-wave elements between points A and B comprise the J feed arrangement.

At first glance, counterproductive currents in the J section between points A and B may seem a waste of element material, but it is through this arrangement that

Fig 40—Schematic representation of the Super-J maritime antenna. The radiating section is two half waves in phase.

the antenna is able to perform well in the absence of a good ground. The two halves of the J feed arrangement, side by side, provide a loading mechanism regardless of whether or not a ground plane is present.

The radiation resistance of any antenna fluctuates as a function of height above ground, but the magnitude of this effect is small compared to the wildly changing impedance encountered when the distance from a ground plane element to its counterpoise is varied. Also, the J section adds ¼ wavelength of antenna height, reducing the effect of ground height variations even further. Reducing ground-height sensitivity is particularly useful in maritime operation on those days when the water is rough.

The gain afforded by doubling the aperture of a J-pole with the extra half-wave section can be realized only if the added section is excited in phase with the half-wave element B-C. This is accomplished in the Super-J in a conventional manner, through the use of the quarter-wave phasing stub shown between C and D.

Construction and Adjustment

The completed Super-J is shown in **Fig 41**. Details of the individual parts are given in **Fig 42**. The driven element can be liberated from a quarter-wave CB whip antenna and cut to the dimensions shown. All other metal stock can be obtained from metal supply houses or machine shops. Metal may even be scrounged for little or nothing as scraps or remnants, as were the parts for the antenna shown here.

The center insulator and the two J stub spacers are made of ¹/₂-inch fiberglass and stainless steel stock, and the end caps are bonded to the insulator sections with epoxy. If you don't have access to a lathe to make the end caps, a simpler one-piece insulator design of wood or fiberglass could be used. However, keep in mind that good electrical connections must be maintained at all joints, and strength is a consideration for the center insulator.

The quarter-wave phasing stub is made of ¹/₈-inch stainless steel tubing, **Fig 43**. The line comprising this stub is bent in a semicircular arc to narrow the vertical profile and to keep the weight distribution balanced. This makes for an attractive appearance and keeps the antenna from leaning to one side.

Fig 41—Andy and the assembled Super-J antenna.

The bottom shorting bar and base mounting plate are made of ¹/₄-inch stainless steel plate, shown in **Fig 44**. The J stub is made of ³/₁₆-inch stainless-steel rod stock. The RF connector may be mounted on the shorting bar as shown, and connected to the adjustable slider with a short section of coaxial cable. RTV sealant should be used at the cable ends to keep out moisture. The all-stainless construction looks nice and weathers well in maritime mobile applications.

The antenna should work well over the whole 144-MHz band if cut to the dimensions shown. The only tuning required is adjustment of the sliding feed point for minimum SWR in the center of the band segment you use most. Setting the slider 2¹³/₁₆ inch above the top of the shorting bar gave the best match for this antenna and may be used for a starting point. Four turns of coax made into a coil at the feed point or a ferrite-sleeve balun act as a common-mode choke balun to ensure satisfactory performance.

#7(.201") Drill Through

8-32 Tapped Hole (3 plcs)

3/8"

1-1/8"

1/8" Through Cross Hole Drill After Assembly to Insulator

3/16"

1/4-Wave Phasing Stub Folded Around Antenna 1/8" SS Tubing

18"

3/8"

7/8"   Fiberglass   1-1/4"

3/8"

3/8"

2-1/2"

2"

1/4" Through (4 plcs)

3/8"   3/8"Min.   1"

3/8 X 24NF Tapped Hole

2-1/2"

2"

1/4"

1/4"   1/4"

1/2"

Base Mounting Plate 1/4" Stainless Plate

Center Insulator 1/2" Stock

1/4"   1/4"   1/4"

#7(.201")Through Cross Hole Drill After Assembly to Insulator Piece

3/8"   Fiberglass

8-32 Tapped Hole

1/2-Wave Top Section 38-3/8"

Top "J" Stub Spacer Insulator End Caps Identical Assemble with Epoxy

1/4"Min.   3/4"   1/8"

4-40 Tapped for Feed Line Connection

1/2"   3/8"   Fiberglass

8-32 Tapped Hole

3/4-Wave Bottom Section 58-3/8"

1/2"   1-1/4"

End View

Sliding Feeder Insulator

#7(.201") Drill Through 2 Holes

1/4"

1/4"   1/4"

1-1/4"

1-3/4"

20-3/8"

1/4"

1"   8-32 Tapped Holes (4 plcs)

1/4"

Driven Element Obtained from 1/4-Wave CB Whip

Base Shorting Bar 1/4" Stainless Plate

"J" Stub 3/16 SS Rod

Fig 42—Details of parts used in the construction of the 144-MHz Super-J. Not to scale.

Fig 43—A close-up look at the $^1/_4$-λ phasing section of the Super-J. The insulator fitting is made of stainless-steel end caps and fiberglass rod.

Fig 44—The bottom shorting bar and base mounting plate assembly.

Fig 45—The Super-J in portable use at a field site.

Performance

Initial tests of the Super-J were performed in portable use and were satisfactory, if not exciting. **Fig 45** shows the Super-J mounted on a wooden mast at a portable site. Simplex communication with a station 40 miles away with a 10-W mobile rig was full quieting both ways. Stations were worked through distant repeaters that were thought inaccessible from this location.

Comparative tests between the Super-J and a commercial $^5/_8$-wave antenna mounted on the car showed the Super-J to give superior performance, even when the Super-J was lowered to the same height as the car roof. The mast shown in Fig 45 was made from two 8-foot lengths of 1×2-inch pine. (The two mast sections and the Super-J can be easily transported in most vehicles.)

The Super-J offers a gain of about 6 dB over a quarter-wave whip and around 3 dB over a $^5/_8$-wave antenna. Actual performance, especially under less-than-ideal or variable ground conditions, is substantially better than other vertical antennas operated under the same conditions. The freedom from ground-plane radials proves to be a real benefit in maritime mobile operation, especially for those passengers in the back of the boat with sensitive ribs!

A TOP-LOADED 144-MHz MOBILE ANTENNA

Earlier in this chapter, the merits of various loading schemes for shortened whip antennas were discussed. Quite naturally, one might be considering HF mobile operation for the application of those techniques. But the principles may be applied at any frequency. **Fig 46** shows a 144-MHz antenna that is both top and center loaded. This antenna is suitable for both mobile and portable operation, being intended for use on a handheld transceiver. This antenna was devised by Don Johnson, W6AAQ, and Bruce Brown, W6TWW.

Fig 46—This 144-MHz antenna uses a combination of top and center loading. It offers low construction cost and improved efficiency over continuously loaded rubber-ducky antennas.

A combination of top and center loading offers improved efficiency over continuously loaded antennas such as the "stubby" pictured at the beginning of this chapter. This antenna also offers low construction cost. The only materials needed are a length of stiff wire and a scrap of circuit-board material, in addition to the appropriate connector.

Construction

The entire whip section with above-center loading coil is made of one continuous length of material. An 18-inch length of brazing rod or #14 Copperweld wire is suitable.

In the antenna pictured in Fig 46, the top loading disk was cut from a scrap of circuit-board material, but flashing copper or sheet brass stock could be used instead. Aluminum is not recommended.

The dimensions of the antenna are given in **Fig 47**. First wind the center loading coil. Use a $1/2$-inch bolt, wood dowel, or other cylindrical object for a coil form. Begin winding at a point 3 inches from one end of the wire, and wrap the wire tightly around the coil form. Wind $5^{1}/_{2}$ turns, with just enough space between turns so they don't touch.

Remove the coil from the form. Next, determine the length necessary to insert the wire into the connector you'll be using. Cut the long end of the wire to this length plus 4 inches, measured from the center of the coil. Solder the wire to the center pin and assemble the connector. A tight-fitting sleeve made of Teflon or Plexiglas rod may be used to support and insulate the antenna wire inside the shell. An alternative is to fill the shell with epoxy cement, and allow the cement to set while the wire is held centered in the shell.

The top loading disk may be circular, cut with a hole saw. A circular disk is not required, however—it may be of any shape. Just remember that with a larger disk, less coil inductance will be required, and vice versa. Drill a hole at the center of the disk

Fig 47—Dimensions for the top-loaded 144-MHz antenna. See text regarding coil length.

for mounting it to the wire. For a more rugged antenna, reinforce the hole with a brass eyelet. Solder the disk in place at the top of the antenna, and construction is completed.

Tune-Up

Adjustment consists of spreading the coil turns for the correct amount of inductance. Do this at the center frequency of the range you'll normally be using. Optimum inductance is determined with the aid of a field strength meter at a distance of 10 or 15 feet.

Attach the antenna to a handheld transceiver operating on low power, and take a field-strength reading. With the transmitter turned off, spread the coil turns slightly, and then take another reading. By experiment, spread or compress the coil turns for the maximum field-strength reading. Very little adjustment should be required. There is one precaution, however. You must keep your body, arms, legs, and head in the same relative position for each field-strength measurement. It is suggested that the transceiver be placed on a nonmetal table and operated at arm's length for these checks.

Once the maximum field-strength reading is obtained, adjustments are completed. With this antenna in operation, you'll likely find it possible to access repeaters that are difficult to reach with other shortened antennas. W6AAQ reports that in distant areas his antenna even outperforms a $5/8$-λ vertical.

VHF QUARTER-WAVELENGTH VERTICAL

Ideally, a VHF vertical antenna should be installed over a perfectly flat reflector to assure uniform omni-directional radiation. This suggests that the center of the automobile roof is the best place to mount it for mobile use. Alternatively, the flat portion of the trunk deck can be used, but will result in a directional pattern because of car-body obstruction.

Fig 48 illustrates how a Millen high-voltage connector can be used as a roof mount for a VHF whip. The hole in the roof can be made over the dome light, thus providing accessibility through the upholstery. RG-59 and the $1/4$-wave matching section, L (Fig 48C), can be routed between the car roof and the ceiling upholstery and brought into the trunk compartment, or down to the dashboard of the car. Instead of a Millen connector, some operators install an SO-239 coax connector on the roof for mounting the whip. The method is similar to that shown in Fig 48.

It has been established that in general, $1/4$-λ vertical antennas for mobile repeater work are not as effective as $5/8$-λ verticals are. With a $5/8$-λ antenna, more of the transmitted signal is directed at a low wave angle, toward the horizon, offering a gain of about 1 dB over the $1/4$-λ vertical. However, in areas where the repeater is located nearby on a very high hill or a mountain top, the $1/4$-λ antenna will usually offer more reliable per-

Fig 48—At A and B, an illustration of how a quarter-wavelength vertical antenna can be mounted on a car roof. The whip section should be soldered into the cap portion of the connector and then screwed into the base socket. This arrangement allows for the removal of the antenna when desired. Epoxy cement should be used at the two mounting screws to prevent the entry of moisture through the screw holes. Diagram C is discussed in the text.

formance than a $^5/_8$-λ antenna. This is because there is more power in the lobe of the $^1/_4$-λ vertical at higher angles.

144-MHz 5/8-WAVELENGTH VERTICAL

Perhaps the most popular antenna for 144-MHz FM mobile and fixed-station use is the $^5/_8$-wavelength vertical. As compared to a $^1/_4$-wavelength vertical, it has 1 dB of gain.

This antenna is suitable for mobile or fixed-station use because it is small, omnidirectional, and can be used with radials or a solid-plane ground (such as a car body). If radials are used, they need be only $^1/_4$ wavelength long.

Construction

The antenna shown here is made from low-cost materials. **Fig 49** shows the base coil and aluminum mounting plate. The coil form is a piece of low-loss solid rod, such as Plexiglas or phenolic. The dimensions for this and other parts of the antenna are given in **Fig 50**. A length of brazing rod is used as the whip section.

The whip should be 47 inches long. However, brazing rod comes in standard 36-inch lengths, so if used, it is necessary to solder an 11-inch extension to the top of the whip. A piece of #10 copper wire will suffice. Alternatively, a stainless-steel rod can be purchased to

Fig 49—At top, a photograph of the $^5/_8$-λ vertical base section. The matching coil is affixed to an aluminum bracket that screws onto the inner lip of the car trunk. Above, the completed assembly. The coil has been wrapped with vinyl electrical tape to keep out dirt and moisture.

make a 47-inch whip. Shops that sell CB antennas should have such rods for replacement purposes on base-loaded antennas. The limitation one can expect with brazing rod is the relative fragility of the material, especially when the threads are cut for screwing the rod into the base coil form. Excessive stress can cause the rod to break where it enters the form. The problem is compli-

Fig 50—Structural details for the 2-meter ⁵⁄₈-λ antenna are provided at A. The mounting bracket is shown at B and the equivalent circuit is given at C.

cated somewhat in this design because a spring is not used at the antenna mounting point. Builders of this antenna can find all kinds of solutions to the problems just outlined by changing the physical design and using different materials when constructing the antenna. The main purpose of this description is to provide dimensions and tune-up information.

The aluminum mounting bracket must be shaped to fit the car with which it will be used. The bracket can be used to effect a no-holes mount with respect to the exterior portion of the car body. The inner lip of the vehicle trunk (or hood) can be the point where the bracket is attached by means of no. 6 or no. 8 sheet-metal screws. The remainder of the bracket is bent so that when the trunk lid or car hood is raised and lowered, there is no contact between the bracket and the moving part. Details of the mounting unit are given in Fig 50B. A 14-gauge metal (or thicker) is recommended for rigidity.

Wind 10¹⁄₂ turns of #10 or #12 copper wire on the ³⁄₄-inch diameter coil form. The tap on L1 is placed approximately four turns below the whip end. A secure solder joint is imperative.

Tune-Up

After the antenna has been mounted on the vehicle, connect an SWR indicator in the 50-Ω transmission line. Key the 144-MHz transmitter and experiment with the coil tap placement. If the whip section is 47 inches long, an SWR of 1:1 can be obtained when the tap is at the right location. As an alternative method of adjustment, place the tap at four turns from the top of L1, make the whip 50 inches long, and trim the whip length until an SWR of 1:1 occurs. Keep the antenna well away from other objects during tune-up, as they may detune the antenna and yield false adjustments for a match.

A 5/8-WAVELENGTH 220-MHz MOBILE ANTENNA

The antenna shown in **Figs 51** and **52** was developed to fill the gap between a homemade ¹⁄₄-λ mobile antenna and a commercially made ⁵⁄₈-λ model. While antennas can be made by modifying CB models, that presents the problem of cost in acquiring the original antenna. The major cost in this setup is the whip portion. This can be any tempered rod that will spring easily.

Construction

The base insulator portion is made of ¹⁄₂-inch Plexiglas rod. A few minutes' work on a lathe is sufficient to shape and drill the rod. (The innovative builder can use an electric drill and a file for the lathe work.)

Fig 51—The 220-MHz ⁵/₈-λ mobile antenna. The coil turns are spaced over a distance of 1 inch, and the bottom end of the coil is soldered to the coax connector.

The bottom $^1/_2$ inch of the rod is turned down to a diameter of $^3/_8$ inch. This portion will now fit into a PL-259 UHF connector. A $^1/_8$-inch diameter hole is drilled through the center of the rod. This hole will hold the wires that make the connections between the center conductor of the connector and the coil tap. The connection between the whip and the top of the coil is also run through this opening. A stud is force-fitted into the top of the Plexiglas rod. This allows for removal of the whip from the insulator.

The coil should be initially wound on a form slightly smaller than the base insulator. When the coil is transferred to the Plexiglas rod, it will keep its shape and will not readily move. After the tap point has been determined,

Fig 52—Diagram of the 220-MHz mobile antenna.

a longitudinal hole is drilled into the center of the rod. A #22 wire can then be inserted through the center of the insulator into the connector. This method is also used to attach the whip to the top of the coil. After the whip has been fully assembled, a coating of epoxy cement is applied. This seals the entire assembly and provides some additional strength. During a full winter's use there was no sign of cracking or other mechanical failure. The adjustment procedure is the same as for the 144-MHz version described previously.

HF Antennas For Sailboats

This material was contributed by Rudy Severns, N6LF. Many of the antenna ideas appearing earlier in this chapter can be applied to sailboats. However, the presence of the mast and the rigging, plus the prevalence of non-conducting fiberglass hulls complicates the issue. There are many possibilities for antennas aboard sailboats. This includes both permanently installed antennas and antennas that can be hoisted for temporary use at anchor:

1. *Permanent*
   Commercial or home-brew automobile-type verticals
   Backstay verticals and slopers
   Shunt feed of uninsulated rigging

2. *Temporary*
   Sloping dipoles
   Inverted V's
   Yagis

You should remember some basic facts of life on a sailboat:

1) On most boats the spars, standing rigging and some running rigging will be conductors. Stainless steel wire is usually used for the rigging and aluminum for the spars.
2) Topping lifts, running backstays and jackstays all may be made of conducting materials and may often change position while the boat is underway. This changes the configuration of the rigging and may affect radiation patterns and feed-point impedances.
3) Shipboard antennas will always be close to the mast and rigging, in terms of electrical wavelength. Some antennas may in fact be part of the rigging.
4) The feed-point impedance and radiation pattern can be strongly influenced by the presence of the rigging.
5) Because of the close proximity, the rigging is an integral part of the antenna and should be viewed as such.
6) The behavior of a given antenna will depend on the details of the rigging on a particular vessel. The performance of a given antenna can vary widely on different boats, due to differences in dimensions and arrangement of the rigging.
7) Even though you may be floating on a sea of salt water, grounding still requires careful attention!

ANTENNA MODELING

Because of the strong interaction between the rigging and the antenna, accurate prediction of radiation patterns and a reasonable guess at expected feed-point impedance requires that you model both the antenna and the rigging. Unless you do accurately model the system, considerable cut-and-try may be needed. This can be expensive when it has to be done in 1 × 19 stainless steel wire with $300 swaged insulator fittings!

In fact, when your antenna is going to be part of standing rigging, it's a very good idea to try your designs out at the dock. You could temporarily use Copperweld wire and inexpensive insulators in place of the stainless rigging wire and the expensive insulators. This approach can save a good deal of money and aggravation. A wide variety of modeling programs are available and can be very helpful in designing a new antenna but they have to be used with some caution:

1) The rigging will have many small intersection angles and radically different conductor diameters, this can cause problems for *NEC* and *MININEC* programs.
2) You must usually taper the segment lengths near the junctions. This is done automatically in programs like *ELNEC* and *EZNEC*.
3) It is usually necessary to use one wire size for the mast, spars and rigging. Some improvement in accuracy can be obtained by modeling the mast as a cage of 3 or 4 wires.

The predicted radiation patterns will be quite good but the feed-point impedance predictions should be viewed as preliminary. Some final adjustment will usually be required. Because of the wide variation between boats, even those of the same class, each new installation is unique and should be analyzed separately.

Fig 53—An example of a 20-meter λ/4 whip mounted on the transom. A local ground system must also be provided, as described in the section on grounding.

A SAFETY NOTE

Ungrounded rigging endpoints near deck level can have high RF potentials on them when you transmit. For example, the shrouds on a fiberglass boat connect to chainplates that are bolted to the hull, but are not grounded. These can inflict painful RF burns on the unwary, even while operating at low power! As a general rule all rigging, spars and lifelines near deck level should be grounded. This also makes good sense for lightning protection. For a backstay antenna with its feed point near deck level, a sleeve of heavy wall PVC pipe can be placed over the lower end of the stay as a protective shield.

TRANSOM AND MASTHEAD MOUNTED VERTICALS

A very common antenna for boats is a vertical, either a short mobile antenna or a full λ/4, placed on the transom, as shown in **Fig 53**. Note that in this ex-ample the antenna is mounted off to one side—it could also be mounted in the center of the transom. The 20-meter radiation pattern for this antenna as shown in **Fig 54**. Unlike a free standing vertical, this antenna doesn't have an omnidirectional pattern. It is asymmetrical, with a front-to-back ratio of about 13 dB. Further, the angle for maximum gain is offset in the direction the antenna is placed on the transom.

This is a very good example of the profound effect the rigging can have on any antenna used on board a sailboat. Not only is the pattern affected but the feed-point impedance will be reduced from a nominal 36 Ω to 25 to 30 Ω.

The directive gain can be useful—if you point the boat in the right direction! Usually, however, a more uniform omnidirectional pattern is more desirable. It is tempting to suggest putting the vertical at the masthead, perhaps using a 6-foot loaded automobile whip, with the mast and rigging acting as a ground plane. **Fig 55** shows such a system. Unfortunately, this usually doesn't work very well because the overall height of the mast and antenna will very likely be > 5/8 λ. This will result in high-angle lobes, as shown in **Fig 56**. Depending on the mast height, this idea may work reasonably well on 40 or 80 meters, but

Freq=14.2 MHz

Elevation Angle=15.0 deg

(A)

Freq=14.2 MHz

Az. Bearing=90.0 deg

(B)

Fig 54—Typical radiation pattern for the λ/4 transom mounted whip in Fig 53.

Feed Point

Masthead Vertical

Fig 55—A whip mounted at the masthead. The feed line is fed back down the mast either inside or outside. The base of the mast and the rigging is assumed to be properly grounded.

Fig 56—Typical radiation pattern for a masthead-mounted vertical. The multiple vertical lobes are due to the fact the antenna is higher than λ/2.

you will still be faced with severe mechanical stress due to magnified motion at the masthead in rough sea. The masthead is usually reserved to VHF antennas, with their own radial ground plane.

THE BACKSTAY VERTICAL

A portion of the backstay can be insulated and used as a vertical as shown in **Fig 57**. The length of the insulated section will be λ/4 on the lowest band of interest. Typically, due to the loading effect of the rest of the rigging, the resonant length of the insulated section will be shorter than the classic 234/f (MHz) relation, although it can in some case actually be longer. Either modeling or trial adjustment can be used to determine the actual length needed. On a typical 35 to 40-foot sailboat, the lowest band for λ/4 resonance will be 40 meters due to the limited length of the backstay. Examples of the radiation patterns on several bands for such an an-

Fig 57—An example of a backstay vertical. A local ground point must be established on the transom next to the base of the backstay.

Fig 58—Typical radiation patterns on 40 meters for the backstay vertical in Fig 57.

Freq=14.2 MHz

Outer Ring=2.90 dBi   Elevation Angle=15.0 deg

(A)

Freq=14.2 MHz

Max. Gain=3.53 dBi   Az. Bearing=90.0 deg

(B)

Fig 59—Typical radiation patterns on 20 meters for the backstay vertical in Fig 57.

Freq=21.3 MHz

Max. Gain=4.13 dBi   Elevation Angle=15.0 deg

(A)

Freq=14.2 MHz

Max. Gain=4.19 dBi   Az. Bearing=90.0 deg

(B)

Fig 60—Typical radiation patterns on 15 meters for the backstay vertical in Fig 57.

tenna are given in **Figs 58** through **60**.

The pattern is again quite directional due to the presence of the mast and rigging. On 15 meters, where the antenna is approximately $^3/_4$ λ, higher angle lobes appear. On 40 and 15 meters, the feed point is near a current maximum and is in the range of 30 to 50 Ω. On 20 meters, however, the feed point is a very high impedance because the antenna is near λ/2 resonance. One way to get around this problem for multiband use is to make the antenna longer than λ/4 on the lowest band. If the lowest band is 40 meters then on 20 meters the feed-point impedance will be much lower. This antenna is non-resonant on any of the bands but can be conveniently fed with a tuner because the feed-point impedances are within the range of commonly available commercial tuners. Tuners specifically intended for marine applications frequently can

accommodate very high input impedances, but they tend to be quite expensive.

The sensitivity of the radiation pattern to small details of the mast and rigging is illustrated in **Fig 61**. This is the same antenna as shown in Fig 57 with the exception that the forestay is assumed to be ungrounded. In this particular example, ungrounding the forestay drastically increases the front-to-back ratio. With slightly different dimensions, however, the pattern could have changed in other ways.

High-quality insulators for rigging wire can be quite expensive and represent a potential weak point—if they fail the mast may come down. It is not absolutely necessary to use two insulators in a backstay vertical. As shown in **Fig 62**, the upper insulator may be omitted. The radiation patterns are shown in **Figs 63** and **64**. In this case

Freq=7.2 MHz

Max. Gain=3.25 dBi   Elevation Angle=15.0 deg

(A)

Freq=7.2 MHz

Max. Gain=4.29 dBi   Az. Bearing=90.0 deg

(B)

Fig 61—The effect of ungrounding the forestay on the radiation pattern. This is for 40-meter operation.

Series Backstay Feed

Feed point can be moved for Z match

Fig 62—Feeding the backstay without an insulator at the top. The feed point may be moved along the antenna to find a point with a better match on a particular band or to provide a better range of impedances for the tuner to match. The coaxial feed line is taped to the lower portion of the backstay. Again, a good local ground is needed at the base of the backstay.

the pattern is actually more symmetrical than it was with an upper insulator—but this may not hold true for other rigging dimensions. The feed point does not have to be at the bottom of the backstay. As indicated in Fig 62, the feed point can be moved up into the backstay to achieve a better match or a more desirable feed-point impedance variation with frequency. In that case, the center of the coaxial feed line is connected to the upper section and the shield to the lower section. The cable is then taped to the lower portion of the backstay.

If single-band operation is all you want, even the lower insulator can be omitted by using shunt feed. A gamma match would be quite effective for this purpose, as discussed in Chapter 6 when driving a grounded tower.

A 40-METER BACKSTAY HALF SLOPER

A half-sloper antenna can be incorporated into the backstay, as shown in **Fig 65**. This will behave very much the same as the slopers described in Chapter 6. The advantage of this antenna for a sailboat installation is that you don't need to create a good ground connection at the stern, as you would have to do for a transom-mounted vertical or the backstay vertical just described. This may be more convenient. The mast, shrouds and stays must still be grounded for the half-sloper but the arrangement is somewhat simpler.

TEMPORARY ANTENNAS

Not everyone needs permanent antennas. A variety

Freq=7.2 MHz

Max. Gain=0.16 dBi   Elevation Angle=15.0 deg

(A)

Freq=7.2 MHz

Max. Gain=1.12 dBi   Az. Bearing=90.0 deg

(B)

Fig 63—Typical 40-meter radiation pattern in Fig 62.

Freq=14.2 MHz

Max. Gain=3.28 dBi   Elevation Angle=15.0 deg

(A)

Freq=14.2 MHz

Max. Gain=5.66 dBi   Az. Bearing=90.0 deg

(B)

Fig 64—Typical 20-meter radiation pattern in Fig 62.

of temporary antennas can be arranged. A few of these are shown in **Figs 66** through **68**. Of all of these the rigid dipole (Fig 66) will provide the best operation and will have a pattern close to that expected from a freestanding dipole. The other two examples will be strongly affected by their close proximity to the rigging.

GROUNDING SYSTEMS

You may be sitting in the middle of a thousand miles of saltwater. This is great for propagation but you will still have to connect to that ground if you want to use a vertical. There are many possibilities, but the scheme shown in **Fig 69** is representative. First a bonding wire, or better yet a copper strap (it can be very thin!), is connected from bow-to-stern on each side, connecting the forestay, lifeline stan-

chions, chainplates, bow and stern pulpits and the backstay. Other bonding wires are run from the bow, stern and chainplates on both sides to a common connection at the base of the mast. The fore-and-aft bonding can be attached to the engine and to the keel bolts. The question arises: "What about electrolysis between the keel and propeller if you bond them together?" This has to be dealt with on a case-by-case basis. If your protective zincs are depleting more rapidly after you install a bonding scheme, change it by disconnecting something, the engine-shaft-propeller, for example.

Grounding will vary in every installation and has to be customized to each vessel. However, just as on shore, the better the ground system, the better the performance of the vertical!

Feed Point

Z

40 m Backstay Sloper

40 m, λ/4
Backstay Antenna
(Sloper)

Y

X

Fig 65—A 40-meter half-sloper fed at the masthead.

HOISTED DIPOLE

Pole with Dipole Taped on

Control
Line

Control
Brace

Mast

Fig 66—A dipole can be taped to a wood or bamboo pole and hoisted to the masthead with the main halyard while at anchor. It is possible to make this a multiband dipole.

Z

Sloping Dipole

Y

X

End Can Be Poled

Fig 67—One end of dipole can be attached to the main halyard and pulled up to the masthead. The bottom end of the dipole should be pulled out away from the rigging as much as possible to reduce the impact of the rigging on the impedance.

Z

Inverted V

Feed
Point

Y

X

Fig 68—The flag halyard can be used to hoist the center of an inverted V to the spreaders, or alternatively, the main halyard can be used to hoist the center of the antenna to the masthead. Interaction between the rigging and the antenna will be very pronounced and the length of the antenna will have to be adjusted on a cut-and-try basis.

Antennas for Power Boats

Powerboaters are not usually faced with the problems and opportunities created by the mast and rigging on a sailboat. A powerboat may have a small mast, but usually not on the same scale as a sailboat. Antennas for power boats have much more in common with automotive mobile operation, but with some important exceptions:

1) In an automobile, the body is usually metal and it provides a groundplane or counterpoise for a whip antenna. Most modern powerboats, however, have fiberglass hulls. These are basically insulators, and will not work as counterpoises. (On the other hand, metal-hulled power boats can provide nearly ideal grounding!)
2) A height restriction on automotive mobile whips is imposed by clearance limits on highway overpasses and also by the need to sustain wind speeds of up to 80 miles per hour on the highway.
3) In general, powerboats can have much taller antennas that can be lowered for the occasional low bridge.
4) The motion on a powerboat, especially in rough seas, can be quite severe. This places additional mechanical strain on the antennas.
5) On both powerboats and sailboats, operation in a salt-water marine environment is common. This means that a careful choice of materials must be made for the antennas to prevent corrosion and premature failure.

The problem of a ground plane for vertical antennas can be handled in much the same manner as shown in **Fig 69** for sailboats. Since there will most likely not be a large keel structure to connect to and provide a large surface area, additional copper foil can be added inside the hull to increase the counterpoise area. Because of the small area of the propeller, it may be better not to connect to the engine, but to rely instead on increasing the area of the counterpoise and operate it as a true counterpoise—that is, isolated from ground. Sometimes a number of radial wires are used for a vertical, much like that

for a ground-plane antenna. This is not a very good idea unless the "wires" are actually wide copper-foil strips that can lower the Q substantially.

The problem is the high voltage present at the ends of normal ground-plane antenna radials. For a boat these radials are likely to be in close proximity to the cabin, which in turn contains both people and electronic equipment. The high potential at the ends of the radials is both a safety hazard and can result in RF coupling back into the equipment, including ham gear, navigational instruments and entertainment devices. The cook is not likely to be happy if he or she gets an RF burn after touching the galley stove! Decoupling the counterpoise from the transmission line, as discussed in Chapter 6, can be very helpful to keep RF out of other equipment.

One way to avoid many of the problems associated with grounding is to use a rigid dipole antenna. On 20 meters and higher, a rigid dipole made up from aluminum tubing, fiberglass poles or some combination of these, can be effective. As shown in **Fig 70A** the halves of the dipole can be slanted upward like rabbit ears to reduce the wingspan and increase the feed-point impedance for a better match to common coax lines. On the lower bands a pair of mobile whips can be used, as shown in Fig 70B. Home-brew coils could also be used.

For short-range communication, a relatively low dipole over saltwater can be effective. However, if long-range communication is needed, then a well-designed vertical, operating over seawater, will work much better. For these to work, of course, you must solve the ground problems associated with a vertical.

Fig 69—A typical sailboat grounding scheme.

Fig 70—At A, a rigid dipole made from aluminum tubing, fiberglass poles or a combination of these. At B, a pair of mobile whips used as a dipole.

It is not uncommon for large powerboats to have a two or three-element multiband Yagi installed on a short mast. While these can be effective, if they are not mounted high ($> \lambda/2$) they may be disappointing for longer-range communication. Over saltwater, vertical polarization is very effective for longer distances. A simpler, but well-designed, vertical system on a boat may outperform a low Yagi.

The combination of a good ground system and one of the high-quality, motor-tuned multiband mobile whips now available commercially can also be very effective.

BIBLIOGRAPHY

Source material and more extended discussions of topics covered in this chapter can be found in the references given below and in the textbooks listed at the end of Chapter 2.

J. S. Belrose, "Short Antennas for Mobile Operation," *QST*, Sep 1953.

J. S. Belrose, "Vertical J Antenna for 2 meters," *The Canadian Amateur*, Jul/Aug 1979, pp 23-26.

J. M. Boyer, "Antenna-Transmission Line Analog," *Ham Radio*, May 1977.

B. F. Brown, "Tennamatic: An Auto-Tuning Mobile Antenna System," *73*, Jul 1979.

B. F. Brown, "Optimum Design of Short Coil-Loaded High-Frequency Mobile Antennas," *ARRL Antenna Compendium Volume 1* (Newington: ARRL, 1985), p 108.

W. B. Freely, "A Two-meter J Antenna," *QST*, Apr 1977, pp 35-36.

E. A. Laport, *Radio Antenna Engineering* (New York: McGraw-Hill Book Co., 1952), p 23.

C. E. Smith and E. M. Johnson, "Performance of Short Antennas," Proceedings of the IRE, Oct 1947.

F. E. Terman, *Radio Engineering Handbook*, 3rd edition (New York: McGraw-Hill Book Co., 1947), p 74.

Repeater Antenna Systems

There is an old adage in Amateur Radio that goes, "If your antenna did not fall down last winter, it wasn't big enough." This adage might apply to antennas for MF and HF work, but at VHF things are a bit different, at least as far as antenna size is concerned. VHF antennas are smaller than their HF counterparts, but yet the theory is the same—a dipole is a dipole, and a Yagi is a Yagi, regardless of frequency. A 144-MHz Yagi may pass as a TV antenna, but most neighbors can easily detect a radio hobbyist if a 14-MHz Yagi looms over his property.

Repeater antennas are discussed in this chapter. Because the fundamental operation of these antennas is no different than presented in earlier chapters, there is no need to delve into any exotic theory. Certain considerations must be made and certain precautions must be observed, however, since most repeater operations—amateur and commercial—take place at VHF and UHF.

Basic Concepts

The antenna is a vital part of any repeater installation. Because the function of a repeater is to extend the range of communications between mobile and portable stations, the repeater antenna should be installed in the best possible location to provide the desired coverage. This usually means getting the antenna as high above average terrain as possible. In some instances, a repeater may need to have coverage only in a limited area or direction. When this is the case, antenna installation requirements will be completely different, with certain limits being set on height, gain and power.

Horizontal and Vertical Polarization

Until the upsurge in FM repeater activity in the 1970s, most antennas used in amateur VHF work were horizontally polarized. These days, very few repeater groups use horizontal polarization. (One of the major rea-sons for using horizontal polarization is to allow separate repeaters to share the same input and/or output frequencies with closer-than-normal geographical spacing.) The vast majority of VHF and UHF repeaters use vertically polarized antennas, and all the antennas discussed in this chapter are of that type.

Transmission Lines

Repeaters provide the first venture into VHF and UHF work for many amateurs. The uninitiated may not be aware that the transmission lines used at VHF become very important because feed-line losses increase with frequency.

The characteristics of feed lines commonly used at VHF are discussed in Chapter 24, Transmission Lines. Although information is provided there for small-diameter RG-58 and RG-59 coaxes, these should not be used except for very short feed lines (25 feet or less). These cables are very lossy at VHF. In addition, the losses can be much higher if fittings and connections are not carefully installed.

The differences in loss between solid-polyethylene dielectric types (RG-8 and RG-11) and those using foam polyethylene are significant at VHF and UHF. If you can afford the line with the least loss, buy it.

If you must bury coaxial cable, check with the cable manufacturer before doing so. Many popular varieties of coaxial cable should not be buried, since the dielectric can become contaminated from moisture and soil chemicals. Some coaxial cables are labeled as non-contaminating. Such a label is the best way to be sure your cable can be buried without damage.

Matching

Losses are lowest in transmission lines that are matched to their characteristic impedances. If there is a

mismatch at the end of the line, the losses increase. The *only way* to reduce the SWR on a transmission line is by matching the line *at the antenna*. Changing the length of a transmission line does not reduce the SWR. The SWR is established by the impedance of the line and the impedance of the antenna, so matching must be done at the antenna end of the line.

The importance of matching, so far as feed-line

losses are concerned, is sometimes overstressed. But under some conditions, it is necessary to minimize feed-line losses related to SWR if repeater performance is to be consistent. It is important to keep in mind that most VHF/UHF equipment is designed to operate into a 50-Ω load. The output circuitry will not be loaded properly if connected to a mismatched line. This leads to a loss of power, and in some cases, damage to the transmitter.

Repeater Antenna System Design

Choosing a repeater or remote-base antenna system is as close as most amateurs come to designing a commercial-grade antenna system. The term *system* is used because most repeaters utilize not only an antenna and a transmission line, but also include duplexers, cavity filters, circulators or isolators in some configuration. Assembling the proper combination of these items in constructing a reliable system is both an art and a science. In this section prepared by Domenic Mallozzi, N1DM, the functions of each component in a repeater antenna system and their successful integration are discussed. While every possible complication in constructing a repeater cannot be foreseen at the outset, this discussion should serve to steer you along the right lines in solving any problems encountered.

COMPUTING THE COVERAGE AREA FOR A REPEATER

Modern computer programs can show the coverage of a repeater using readily available topographic data from the Internet. In Chapter 3, The Effects of Ground, we described the *MicroDEM* program supplied on the CD-ROM accompanying this book. Dr Peter Guth, the author of *MicroDEM*, built into it the ability to generate terrain profiles that can be used with ARRL's *HFTA* (HF Terrain Assessment) program (also included on the CD-ROM).

MicroDEM has a wide range of capabilities beyond simply making terrain profiles. It can do *LOS* (line of sight) computations, based on visual or radio-horizon considerations. **Fig 1** shows a *MicroDEM* map for the area around Glastonbury, Connecticut. This is somewhat hilly terrain, and as a result the coverage for a repeater placed here on a 30-meter (100-foot) high tower would be somewhat spotty. Fig 1 shows a "Viewshed" on the map, in the form of the white terrain profile strokes in 5° increments around the tower.

Fig 2 shows the LOS for an azimuth of 80°, from a 30-meter high tower out to a distance of 8000 meters. The light-shaded areas on the profile are those that are illuminated directly by the antenna on the tower, while the dark portions of the profile are those that cannot be seen

Fig 1—*MicroDEM* topographic map, showing the coverage for a repeater placed on a 30-meter high tower in Glastonbury, CT. The white radial lines indicate the coverage in 5° increments of azimuth around the tower. The range circles are 1000 meters apart.

Fig 2—An "LOS" (line of sight) profile at an azimuth of 80° from the tower in Fig 1. The light-gray portions of the terrain profile are visible from the top of the tower, while the dark portions are blocked by the terrain.

directly from the tower. This profile assumes that the mobile station is 2 meters high—the height of a 6-foot high person with a handheld radio.

The terrain at an 80° azimuth allows direct radio view from the top of the tower out to about 1.8 km. From here, the downslope prevents direct view until about 2.5 km,

where the terrain is briefly visible again from several hundred meters, disappearing from radio view until about 2.8 km, after which it becomes visible until about 3.6 km. Note that other than putting the repeater antenna on a higher tower, there is nothing that can be done to improve repeater coverage over this hilly terrain, although knife-edge diffraction off the hill tops will help fill in coverage gaps.

The Repeater Antenna

The most important part of the system is the antenna itself. As with any antenna, it must radiate and collect RF energy as efficiently as possible. Many repeaters use omnidirectional antennas, but this is not always the best choice. For example, suppose a group wishes to set up a repeater to cover towns A and B and the interconnecting state highway shown in **Fig 3**. The available repeater site is marked on the map. No coverage is required to the west or south, or over the ocean. If an omnidirectional antenna is used in this case, a significant amount of the radiated signal goes in undesired directions. By using an antenna with a cardioid pattern, as shown in Fig 1, the coverage is concentrated in the desired directions. The repeater will be more effective in these locations, and signals from low-power portables and mobiles will be more reliable.

In many cases, antennas with special patterns are more expensive than omnidirectional models. This is an obvious consideration in designing a repeater antenna system. Over terrain where coverage may be difficult in some direction from the repeater site, it may be desirable to skew the antenna pattern in that direction. This can be accomplished by using a phased-vertical array or a com-

(A)

(B)

Fig 4—The "keyhole" horizontal radiation pattern at A is generated by the combination of phased Yagis and vertical elements shown at B. Such a pattern is useful in overcoming coverage blockages resulting from local terrain features. (*Based on a design by Decibel Products, Inc.*)

Fig 3—There are many situations where equal repeater coverage is not desired in all directions from the "machine." One such situation is shown here, where the repeater is needed to cover only towns A and B and the interconnecting highway. An omnidirectional antenna would provide coverage in undesired directions, such as over the ocean. The broken line shows the radiation pattern of an antenna that is better suited to this circumstance.

Fig 5—Vertical-beam downtilt is another form of radiation-pattern distortion useful for improving repeater coverage. This technique can be employed in situations where the repeater station is at a greater elevation than the desired coverage area, when a high-gain omnidirectional antenna is used. Pattern A shows the normal vertical-plane radiation pattern of a high-gain omnidirectional antenna with respect to the desired coverage area (the town). Pattern B shows the pattern tilted down, and the coverage improvement is evident.

bination of a Yagi and a phased vertical to produce a "keyhole" pattern. See **Fig 4**.

Repeaters are common on 440 MHz and above, and many groups invest in high-gain omnidirectional antennas. A consequence of getting high gain from an omnidirectional antenna is vertical beamwidth reduction. In most cases, these antennas are designed to radiate their peak gain at the horizon, resulting in optimum coverage when the antenna is located at a moderate height over normal terrain. Unfortunately, in cases where the antenna is located at a very high site (overlooking the coverage area) this may not be the most desirable pattern. The vertical pattern of the antenna can be tilted downward, however, to facilitate coverage of the desired area. This is called *vertical-beam downtilt*.

An example of such a situation is shown in **Fig 5**. The repeater site overlooks a town in a valley. A 450-MHz repeater is needed to serve low-power portable and mobile stations. Constraints on the repeater dictate the use of an antenna with a gain of 11 dBi. (An omnidirec-

Fig 6—Vertical-beam downtilt can be facilitated by inserting 52-Ω delay lines in series with the 75-Ω feed lines to the collinear elements of an omnidirectional antenna. The delay lines to each element are progressively longer so the phase shift between elements is uniform. Odd ¹/₄-λ coaxial transformers are used in the main (75-Ω) feed system to match the dipole impedances to the driving point. Tilting the vertical beam in this way often produces minor lobes in the vertical pattern that do not exist when the elements are fed in phase.

tional antenna with this gain has a vertical beamwidth of approximately 6°.) If the repeater antenna has its peak gain at the horizon, a major portion of the transmitted signal and the best area from which to access the repeater exists *above* the town. By tilting the pattern down 3°, the peak radiation will occur in the town.

Vertical-beam downtilt is generally produced by feeding the elements of a collinear vertical array slightly out of phase with each other. Lee Barrett, K7NM, showed such an array in *Ham Radio* magazine. (See the Bibliography at the end of this chapter.) Barrett gives the geometry and design of a four-pole array with progressive phase delay, and a computer program to model it. The technique is shown in **Fig 6**, with a free-space elevation plot showing downtilting in **Fig 7**.

Commercial antennas are sometimes available (at extra cost) with built-in downtilt characteristics. Before ordering such a commercial antenna, make sure that you really require it—they generally are special-order items and are not returnable.

There are disadvantages to improving coverage by means of vertical-beam downtilt. When compared to a standard collinear array, an antenna using vertical-beam downtilt will have somewhat greater extraneous lobes in the vertical pattern, resulting in reduced gain (usually less than 1 dB). Bandwidth is also slightly reduced. The reduction in gain, when combined with the downtilt characteristic, results in a reduction in total coverage area. These trade-offs, as well as the increased cost of a

Fig 7—Free-space elevation-plane patterns showing downtilting that results from progressive phase shifts for the feed currents for the dipole in Fig 6.

commercial antenna with downtilt, must be compared to the improvement in total performance in a situation where vertical-beam downtilt is contemplated.

Top Mounting and Side Mounting

Amateur repeaters often share towers with commercial and public service users. In many of these cases, other antennas are at the top of the tower, so the amateur antenna must be side mounted. A consequence of this arrangement is that the free-space pattern of the repeater antenna is distorted by the tower. This effect is especially noticeable when an omnidirectional antenna is side mounted on a structure.

The effects of supporting structures are most pronounced at close antenna spacings to the tower and with large support dimensions. The result is a measurable increase in gain in one direction and a partial null in the other direction (sometimes 15 dB deep). The shape of the supporting structure also influences pattern distortion. Many antenna manufacturers publish radiation patterns showing the effect of side mounting antennas in their catalogs.

Side mounting is not always a disadvantage. In cases where more (or less) coverage is desired in one direction, the supporting structure can be used to advantage. If pattern distortion is not acceptable, a solution is to mount antennas around the perimeter of the structure and feed them with the proper phasing to synthesize an omnidirectional pattern. Many manufacturers make antennas to accommodate such situations.

The effects of different mounting locations and arrangements can be illustrated with an array of exposed dipoles, **Fig 8**. Such an array is a very versatile antenna because, with simple rearrangement of the elements, it can develop either an omnidirectional pattern or an offset pattern. Drawing A of Fig 8 shows a basic collinear array of four vertical ½-λ elements. The vertical spacing between adjacent elements is 1 λ. All elements are fed in phase. If this array is placed in the clear and supported by a nonconducting mast, the calculated radiation resistance of each dipole element is on the order of 63 Ω. If the feed line is completely decoupled, the resulting azimuth pattern is omnidirectional. The vertical-plane pattern is shown in **Fig 9**.

Fig 8B shows the same array in a side-mounting arrangement, at a spacing of ¼ λ from a conducting mast. In this mounting arrangement, the mast takes on the role of a reflector, producing an F/B on the order of 5.7 dB. The azimuth pattern is shown in **Fig 10**. The vertical pattern is not significantly different from that of Fig 9, except the four small minor lobes (two on either side of the vertical axis) tend to become distorted. They are not as "clean," tending to merge into one minor lobe at some mast heights. This apparently is a function of currents in the supporting mast. The proximity of the mast also alters the feed-point impedance. For elements that

are resonant in the configuration of Fig 8A, the calculated impedance in the arrangement of Fig 8B is in the order of $72 + j\,10\,\Omega$.

If side mounting is the only possibility and an omnidirectional pattern is required, the arrangement of Fig 8C may be used. The calculated azimuth pattern takes on a slight cloverleaf shape, but is within 1.5 dB of being circular. However, gain performance suffers, and the idealized vertical pattern of Fig 9 is not achieved. See **Fig 11**. Spacings other than $^1\!/_4$-λ from the mast were not investigated.

One very important consideration in side mounting an antenna is mechanical integrity. As with all repeater components, reliability is of great importance. An antenna hanging by the feed line and banging against the tower provides far from optimum performance and reliability. Use a mount that is appropriately secured to the tower and the antenna. Also use good hardware, preferably stainless steel (or bronze). If your local hardware store does not carry stainless steel hardware, try a boating supplier.

Fig 8—Various arrangements of exposed dipole elements. At A is the basic collinear array of four elements. B shows the same elements mounted on the side of a mast, and C shows the elements in a side-mounted arrangement around the mast for omnidirectional coverage. See text and Figs 9 through 11 for radiation-pattern information.

Fig 10—Calculated azimuth pattern of the side-mounted array of Fig 8B, assuming $^1\!/_4$-λ spacing from a 4-inch mast. The calculated gain in the favored direction, away from the mast and through the elements, is 10.6 dBi.

Fig 9—Calculated vertical-plane pattern of the array of Fig 8A, assuming a nonconducting mast support and complete decoupling of the feeder. In azimuth the array is omnidirectional. The calculated gain of the array is 8.6 dBi at 0° elevation; the –3 dB point is at 6.5°.

Fig 11—Calculated vertical pattern of the array of Fig 8C, assuming $^1\!/_4$-λ element spacing from a 4-inch mast. The azimuth pattern is circular within 1.5 dB, and the calculated gain is 4.4 dBi.

Be certain that the feed line is properly supported along its length. Long lengths of cable are subject to contraction and expansion with temperature from season to season, so it is important that the cable not be so tight that contraction causes it to stress the connection at the antenna. This can cause the connection to become intermittent (and noisy) or, at worst, an open circuit. This is far from a pleasant situation if the antenna connection is 300 feet up a tower, and it happens to be the middle of the winter!

Effects of Other Conductors

Feed-line proximity and tower-access ladders or cages also have an effect on the radiation patterns of side-mounted antennas. This subject was studied by Connolly and Blevins, and their findings are given in *IEEE Conference Proceedings* (see the Bibliography at the end of this chapter). Those considering mounting antennas on air-conditioning evaporators or maintenance penthouses on commercial buildings should consult this article. It gives considerable information on the effects of these structures on both unidirectional and omnidirectional antennas.

Metallic guy wires also affect antenna radiation patterns. Yang and Willis studied this and reported the results in *IRE Transactions on Vehicular Communications*. As expected, the closer the antenna is to the guy wires, the greater the effect on the radiation patterns. If the antennas are near the point where the guy wires meet the tower, the effect of the guy wires can be minimized by breaking them up with insulators every 0.75 λ for 2.25 λ to 3.0 λ.

ISOLATION REQUIREMENTS IN REPEATER ANTENNA SYSTEMS

Because repeaters generally operate in full *duplex* (the transmitter and receiver operate simultaneously), the antenna system must act as a filter to keep the transmitter from blocking the receiver. The degree to which the transmitter and receiver must be isolated is a complex problem. It is quite dependent on the equipment used and the difference in transmitter and receiver frequencies (offset). Instead of going into great detail, a simplified example can be used for illustration.

Consider the design of a 144-MHz repeater with a 600-kHz offset. The transmitter has an RF output power of 10 watts, and the receiver has a squelch sensitivity of 0.1 μV. This means there must be at least 1.9×10^{-16} watts at the 52-Ω receiver-antenna terminals to detect a signal. If both the transmitter and receiver were on the same frequency, the isolation (attenuation) required between the transmitter and receiver antenna jacks to keep the transmitter from activating the receiver would be

$$\text{Isolation} = 10\log\frac{10\text{ watts}}{1.9\times10^{-16}\text{ watts}} = 167\text{ dB}$$

Obviously there is no need for this much attenuation, because the repeater does not transmit and receive on the same frequency.

If the 10-watt transmitter has noise 600 kHz away from the carrier frequency that is 45 dB below the carrier power, that 45 dB can be subtracted from the isolation requirement. Similarly, if the receiver can detect a 0.1 μV on-frequency signal in the presence of a signal 600 kHz away that is 40 dB greater than 0.1 μV, this 40 dB can also be subtracted from the isolation requirement. Therefore, the isolation requirement is

167 dB − 45 dB − 40 dB = 82 dB

Other factors enter into the isolation requirements as well. For example, if the transmitter power is increased by 10 dB (from 10 to 100 watts), this 10 dB must be added to the isolation requirement. Typical requirements for 144- and 440-MHz repeaters are shown in **Fig 12**.

Obtaining the required isolation is the first problem to be considered in constructing a repeater antenna system. There are three common ways to obtain this isolation:

1) Physically separate the receiving and transmitting antennas so the combination of path loss for the spacing and the antenna radiation patterns results in the required isolation.
2) Use a combination of separate antennas and high-Q filters to develop the required isolation. (The high-Q filters serve to reduce the physical distance required between antennas.)
3) Use a combination filter and combiner system to

Fig 12—Typical isolation requirements for repeater transmitters and receivers operating in the 132-174 MHz band (Curve A), and the 400-512 MHz band (Curve B). Required isolation in dB is plotted against frequency separation in MHz. These curves were developed for a 100-W transmitter. For other power levels, the isolation requirements will differ by the change in decibels relative to 100 W. Isolation requirements will vary with receiver sensitivity. (The values plotted were calculated for transmitter-carrier and receiver-noise suppression necessary to prevent more than 1 dB degradation in receiver 12-dB SINAD sensitivity.)

allow the transmitter and receiver to share one antenna. Such a filter and combiner is called a *duplexer*.

Repeaters operating on 28 and 50 MHz generally use separate antennas to obtain the required isolation. This is largely because duplexers in this frequency range are both large and very expensive. It is generally less expensive to buy two antennas and link the sites by a committed phone line or an RF link than to purchase a duplexer. At 144 MHz and higher, duplexers are more commonly used. Duplexers are discussed in greater detail in a later section.

Separate Antennas

Receiver desensing (gain limiting caused by the presence of a strong off-frequency signal) can be reduced, and often eliminated, by separation of the transmitting and receiving antennas. Obtaining the 55 to 90 dB of isolation required for a repeater antenna system requires separate antennas to be spaced a considerable distance apart (in wavelengths).

Fig 13 shows the distances required to obtain specific values of isolation for vertical dipoles having horizontal separation (at A) and vertical separation (at B).

The isolation gained by using separate antennas is subtracted from the total isolation requirement of the system. For example, if the transmitter and receiver antennas for a 450-MHz repeater are separated horizontally by 400 feet, the total isolation requirement in the system is reduced by about 64 dB.

Note from Fig 13B that a vertical separation of only about 25 feet also provides 64 dB of isolation. Vertical separation yields much more isolation than does horizontal separation. Vertical separation is also more practical than horizontal, since only a single support is required.

An explanation of the significant difference between the two graphs is in order. The vertical spacing requirement for 60 dB attenuation (isolation) at 150 MHz is about 43 feet. The horizontal spacing for the same isolation level is on the order of 700 feet. **Fig 14** shows why this difference exists. The radiation patterns of the antennas at A overlap; each antenna has gain in the direction of the other. The path loss between the antennas is given by

$$\text{Path loss (dB)} = 20 \log \frac{4 \pi d}{\lambda} \qquad \text{(Eq 1)}$$

where

    d = distance between antennas
    λ = wavelength, in the same units as d.

The isolation between the antennas in Fig 14A is the path loss less the antenna gains. Conversely, the antennas at B share pattern nulls, so the isolation is the path loss added to the depth of these nulls. This significantly reduces the spacing requirement for vertical sepa-

Fig 13—At A, the amount of attenuation (isolation) provided by horizontal separation of vertical dipole antennas. At B, isolation afforded by vertical separation of vertical dipoles.

Fig 14—A relative representation of the isolation advantage afforded by separating antennas horizontally (A) and vertically (B) is shown. A great deal of isolation is provided by vertical separation, but horizontal separation requires two supports and much greater distance to be as effective. Separate-site repeaters (those with transmitter and receiver at different locations) benefit much more from horizontal separation than do single-site installations.

ration. Because the depth of the pattern nulls is not infinite, some spacing is required. Combined horizontal and vertical spacing is much more difficult to quantify because the results are dependent on both radiation patterns and the positions of the antennas relative to each other.

Separate antennas have one major disadvantage: They create disparity in transmitter and receiver coverage. For example, say a 50-MHz repeater is installed over average terrain with the transmitter and repeater separated by 2 miles. If both antennas had perfect omnidirectional coverage, the situation depicted in **Fig 15** would exist. In this case, stations able to hear the repeater may not be able to access it, and vice versa. In practice, the situation can be considerably worse. This is especially true if the patterns of both antennas are not omnidirectional. If this disparity in coverage cannot be tolerated, the solution involves skewing the patterns of the antennas until their coverage areas are essentially the same.

Cavity Resonators

As just discussed, receiver desensing can be reduced by separating the transmitter and receiver antennas. But the amount of transmitted energy that reaches the receiver input must often be decreased even farther. Other nearby transmitters can cause desensing as well. A *cavity resonator* (cavity filter) can be helpful in solving these problems. When properly designed and constructed, this type of resonator has very high Q. A commercially made cavity is shown in **Fig 16**.

A cavity resonator placed in series with a transmission line acts as a band-pass filter. For a resonator to operate in series, it must have input and output coupling loops (or probes). A cavity resonator can also be connected across (in parallel with) a transmission line. The cavity then acts as a band-reject (notch) filter, greatly attenuating energy at the frequency to which it is tuned. Only one coupling loop or probe is required for this method of filtering. This type of cavity could be used in

the receiver line to "notch" the transmitter signal. Several cavities can be connected in series or parallel to increase the attenuation in a given configuration. The graphs of **Fig 17** show the attenuation of a single cavity (A) and a pair of cavities (B).

The only situation in which cavity filters would not help is the case where the off-frequency noise of the transmitter was right on the receiver frequency. With cavity resonators, an important point to remember is that addition of a cavity across a transmission line may change the impedance of the system. This change can be compensated by adding tuning stubs along the transmission line.

Duplexers

The material in this section was prepared by Domenic Mallozzi, N1DM. Most amateur repeaters in the 144-, 220- and 440-MHz bands use duplexers to obtain the necessary transmitter to receiver isolation. Duplexers have been commonly used in commercial repeaters for many years. The duplexer consists of two high-Q filters. One filter is used in the feed line from the transmitter to the antenna, and another between the antenna and the receiver. These filters must have low loss at the frequency to which they are tuned while having very high attenuation at the surrounding frequencies. To meet the high attenuation requirements at frequencies within as little as 0.4% of the frequency to which they are tuned, the filters usually take the form of cascaded transmission-line cavity filters. These are either band-pass filters, or band-pass filters with a rejection notch. (The rejection notch is tuned to the center frequency of the other filter.) The number of cascaded filter sections is determined by the frequency separation and the ultimate attenuation requirements.

Fig 15—Coverage disparity is a major problem for separate-site repeater antennas. The transmitter and receiver coverage areas overlap, but are not entirely mutually inclusive. Solving this problem requires a great deal of experimentation, as many factors are involved. Among these factors are terrain features and distortion of the antenna radiation patterns from supports.

Fig 16—A coaxial cavity filter of the type used in many amateur and commercial repeater installations. Center-conductor length (and thus resonant frequency) is varied by adjustment of the knob (top).

Fig 17—Frequency response curves for a single cavity (A) and two cavities cascaded (B). These curves are for cavities with coupling loops, each having an insertion loss of 0.5 dB. (The total insertion loss is indicated in the body of each graph.) Selectivity will be greater if lighter coupling (greater insertion loss) can be tolerated.

Fig 18—Cutaway view of a typical cavity. Note the relative locations of the coupling loops to each other and to the center conductor of the cavity. A locknut is used to prevent movement of the tuning rod after adjustment.

Duplexers for the amateur bands represent a significant technical challenge, because in most cases amateur repeaters operate with significantly less frequency separation than their commercial counterparts. Information on home construction of duplexers is presented in a later section of this chapter. Many manufacturers market high-quality duplexers for the amateur frequencies.

Duplexers consist of very high-Q cavities whose resonant frequencies are determined by mechanical components, in particular the tuning rod. **Fig 18** shows the cutaway view of a typical duplexer cavity. The rod is usually made of a material that has a limited thermal expansion coefficient (such as Invar). Detuning of the cavity by environmental changes introduces unwanted losses in the antenna system. An article by Arnold in *Mobile Radio Technology* considered the causes of drift in the

cavity (see the Bibliography at the end of this chapter). These can be broken into four major categories.

1) Ambient temperature variation (which leads to mechanical variations related to the thermal expansion coefficients of the materials used in the cavity).
2) Humidity (dielectric constant) variation.
3) Localized heating from the power dissipated in the cavity (resulting from its insertion loss).
4) Mechanical variations resulting from other factors (vibration, etc).

In addition, because of the high-Q nature of these cavities, the insertion loss of the duplexer increases when the signal is not at the peak of the filter response. This means, in practical terms, that less power is radiated for a given transmitter output power. Also, the drift in cavities in the receiver line results in increased system noise figure, reducing the sensitivity of the repeater.

As the frequency separation between the receiver and the transmitter decreases, the insertion loss of the duplexer reaches certain practical limits. At 144 MHz, the minimum insertion loss for 600 kHz spacing is 1.5 dB per filter.

Testing and using duplexers requires some special considerations (especially as frequency increases). Because duplexers are very high-Q devices, they are very sensitive to the termination impedances at their ports. A high SWR on any port is a serious problem, because the apparent insertion loss of the duplexer will increase, and the isolation may appear to decrease. Some have found that when duplexers are used at the limits of their isolation capabilities, a small change in antenna SWR is enough to cause receiver desensitization. This occurs most often under ice-loading conditions on antennas with open-wire phasing sections.

The choice of connectors in the duplexer system is important. BNC connectors are good for use below 300 MHz. Above 300 MHz, their use is discouraged because even though many types of BNC connectors work well up to 1 GHz, older style standard BNC connectors are inadequate at UHF and above. Type N connectors should be used above 300 MHz. It is false economy to use marginal quality connectors. Some commercial users have reported deteriorated isolation in commercial UHF repeaters when using such connectors. The location of a bad connector in a system is a complicated and frustrating process. Despite all these considerations, the duplexer is still the best method for obtaining isolation in the 144- to 925 MHz range.

ADVANCED TECHNIQUES

As the number of available antenna sites decreases and the cost of various peripheral items (such as coaxial cable) increases, amateur repeater groups are required to devise advanced techniques if repeaters are to remain effective. Some of the techniques discussed here have been applied in commercial services for many years, but until recently have not been economically justified for amateur use.

One technique worth consideration is the use of *cross-band couplers*. To illustrate a situation where a cross-band coupler would be useful, consider the following example. A repeater group plans to install 144- and 902-MHz repeaters on the same tower. The group intends to erect both antennas on a horizontal cross arm at the 325-foot level. A 325-foot run of $^7/_8$-inch Heliax costs approximately $2000. If both antennas are to be mounted at the top of the tower, the logical approach would require two separate feed lines. A better solution involves the use of a single feed line for both repeaters, along with a cross-band coupler at each end of the line.

The use of the cross-band coupler is shown in **Fig 19**. As the term implies, the coupler allows two signals on different bands to share a common transmission line. Such couplers cost approximately $300 each. In our hypothetical example, this represents a saving of $1400 over the cost of using separate feed lines. But, as with all compromises, there are disadvantages. Cross-band cou-

Fig 19—Block diagram of a system using cross-band couplers to allow the use of a single feed line for two repeaters. If the feeder to the antenna location is long (more than 200 feet or so), cross-band couplers may provide a significant saving over separate feed lines, especially at the higher amateur repeater frequencies. Cross-band couplers cannot be used with two repeaters on the same band.

plers have a loss of about 0.5 dB per unit. Therefore, the pair required represents a loss of 1.0 dB in *each* transmission path. If this loss can be tolerated, the cross-band coupler is a good solution.

Cross-band couplers do not allow two repeaters *on the same band* to share a single antenna and feed line. As repeater sites and tower space become more scarce, it may be desirable to have two repeaters on the same band share the same antenna. The solution to this problem is the use of a *transmitter multicoupler*. The multicoupler is related to the duplexers discussed earlier. It is a cavity filter and combiner that allows multiple transmitters and receivers to share the same antenna. This is a common commercial practice. A block diagram of a multicoupler system is shown in **Fig 20**.

The multicoupler, however, is a very expensive device, and has the disadvantage of even greater loss per transmission path than the standard duplexer. For example, a well-designed duplexer for 600 kHz spacing at 146 MHz has a loss per transmission path of approximately 1.5 dB. A four-channel multicoupler (the requirement for two repeaters) has an insertion loss per transmission path on the order of 2.5 dB or more. Another constraint of such a system is that the antenna must present a good match to the transmission line at all frequencies on which it will be used (both transmitting and receiving). This becomes difficult for the system with two repeaters operating at opposite ends of a band.

If you elect to purchase a commercial base-station antenna that requires you to specify a frequency to which the antenna must be tuned, be sure to indicate to the manufacturer the intended use of the antenna and the frequency extremes. In some cases, the only way the manufacturer can accommodate your request is to provide an antenna with some vertical-beam uptilt at one end of the band and some downtilt at the other end of the band. In the case of antennas with very high gain, this in itself may become a serious problem. Careful analysis of the situation is necessary before assembling such a system.

Diversity Techniques for Repeaters

Mobile flutter, "dead spots" and similar problems are a real problem for the mobile operator. The popularity of hand-held transceivers using low power and mediocre antennas causes similar problems. A solution to these difficulties is the use of some form of *diversity reception*. Diversity reception works because signals do not fade at the same rate when received by antennas at different locations (space diversity) or of different polarizations (polarization diversity).

Repeaters with large transmitter coverage areas often have difficulty "hearing" low power stations in peripheral areas or in dead spots. Space diversity is especially useful in such a situation. Space diversity utilizes separate receivers at different locations that are linked to the repeater. The repeater uses a circuit called a *voter*

Fig 20—Block diagram of a system using a transmitter multicoupler to allow a single feed line and antenna to be used by two repeaters on one band. The antenna must be designed to operate at all frequencies that the repeaters utilize. More than two repeaters can be operated this way by using a multicoupler with the appropriate number of input ports.

that determines which receiver has the best signal, and then selects the appropriate receiver from which to feed the repeater transmitter. This technique is helpful in urban areas where shadowing from large buildings and bridges causes problems. Space-diversity receiving, when properly executed, can give excellent results. But with the improvement come some disadvantages: added initial cost, maintenance costs, and the possibility of failure created by the extra equipment required. If installed and maintained carefully, problems are generally minimal.

A second improvement technique is the use of *circularly polarized* repeater antennas. This technique has been used in the FM broadcast field for many years, and has been considered for use in the mobile telephone service as well. Some experiments by amateurs have proved very promising, as discussed by Pasternak and Morris (see the Bibliography at the end of this chapter).

The improvement afforded by circular polarization is primarily a reduction in *mobile flutter*. The flutter on a mobile signal is caused by reflections from large buildings (in urban settings) or other terrain features. These reflections cause measurable polarization shifts, sometimes to the point where a vertically polarized signal at the transmitting site may appear to be primarily horizontally polarized after reflection.

A similar situation results from *multipath propagation*, where one or more reflected signals combine with the direct signal at the repeater, having varying effects on the signal. The multipath signal is subjected to large amplitude and phase variations at a relatively rapid rate.

In both of the situations described here, circular polarization can offer considerable improvement. This is because circularly polarized antennas respond equally to all linearly polarized signals, regardless of the plane of polarization. At this writing, there are no known sources of commercial circularly polarized omnidirectional antennas for the amateur bands. Pasternak and Morris describe a circularly polarized antenna made by modifying two commercial four-pole arrays.

EFFECTIVE ISOTROPIC RADIATED POWER (EIRP)

It is useful to know effective isotropic radiated power (EIRP) in calculating the coverage area of a repeater. The FCC formerly required EIRP to be entered in the log of every amateur repeater station. Although logging EIRP is no longer required, it is still useful to have this information on hand for repeater-coordination purposes and so system performance can be monitored periodically.

Calculation of EIRP is straightforward. The PEP output of the transmitter is simply multiplied by the gains and losses in the transmitting antenna system. (These gains and losses are best added or subtracted in decibels and then converted to a multiplying factor.) The following worksheet and example illustrates the calculations.

Feed-line loss	——	dB
Duplexer loss	——	dB
Isolator loss	——	dB
Cross-band coupler loss	——	dB
Cavity filter loss	——	dB
Total losses (L)	——	dB

G (dB) = antenna gain (dBi) – L

where G = antenna system gain. (If antenna gain is specified in dBd, add 2.14 dB to obtain the gain in dBi.)

$M = 10^{G/10}$

where M = multiplying factor

EIRP (watts) = transmitter output (PEP)×M

Example

A repeater transmitter has a power output of 50 W PEP (50-W FM transmitter). The transmission line has 1.8 dB loss. The duplexer used has a loss of 1.5 dB, and a circulator on the transmitter port has a loss of 0.3 dB. There are no cavity filters or cross-band couplers in the system. Antenna gain is 5.6 dBi.

Feed-line loss	1.8 dB
Duplexer loss	1.5 dB
Isolator loss	0.3 dB
Cross-band coupler loss	0 dB
Cavity filter loss	0 dB
Total losses (L)	3.6 dB

Antenna system gain in dB = G = antenna gain (dBi) –L

$G = 5.6$ dBi – 3.6 dB = 2 dB

Multiplying factor = $M = 10^{G/10}$

$M = 10^{2/10} = 1.585$

EIRP (watts) = transmitter output (PEP) $\times$ M

EIRP = 50 W $\times$ 1.585 = 79.25 W

If the antenna system is lossier than this example, G may be *negative*, resulting in a multiplying factor less than one. The result is an EIRP that is less than the transmitter output power. This situation can occur in practice, but for obvious reasons is not desirable.

Assembling a Repeater Antenna System

This section will aid you in planning and assembling your repeater antenna system. The material was prepared by Domenic Mallozzi, N1DM. Consult Chapter 23, Radio Wave Propagation, for information on propagation for the band of your interest.

First, a repeater antenna selection checklist such as this will help you in evaluating the antenna system for your needs.

Gain needed   _____ dBi

Pattern required   _____ Omnidirectional

                             _____ Offset

                             _____ Cardioidal

                             _____ Bidirectional

                             _____ Special pattern (specify)

_____

Mounting   _____ Top of tower

                             _____ Side of tower

(Determine effects of tower on pattern. Is the result consistent with the pattern required?)

Is downtilt required?   _____ Yes

                             _____ No

Type of RF connector   _____ UHF

                             _____ N

                             _____ BNC

      _____ Other (specify)

Size (length)   _____

Weight   _____

Maximum cost $_____

Table 1 (see next page) has been compiled to provide general information on commercial components available for repeater and remote-base antenna systems. The various components are listed in a matrix format by manufacturer, for equipment designed to operate in the various amateur bands. See Chapter 21, Antenna Products Suppliers, for further information for these components. Although every effort has been made to make this data complete, the ARRL is not responsible for omissions or errors. The listing of a product in Table 1 does not constitute an endorsement by ARRL. Manufacturers are urged to contact the editors with updating information.

Even though almost any antenna can be used for a repeater, the companies indicated in the *Antennas* column in Table 1 are known to have produced heavy-duty antennas to commercial standards for repeater service. Many of these companies offer their antennas with special features for repeater service (such as vertical-beam downtilt). It is best to obtain catalogs of current products from the manufacturers listed, both for general information and to determine which special options are available on their products.

A 144 MHz Duplexer

Obtaining sufficient isolation between the transmitter and receiver of a repeater can be difficult. Many of the solutions to this problem compromise receiver sensitivity or transmitter power output. Other solutions create an imbalance between receiver and transmitter coverage areas. When a duplexer is used, insertion loss is the compromise. But a small amount of insertion loss is more than offset by the use of one antenna for both the transmitter and receiver. Using one antenna assures equal antenna patterns for both transmitting and receiving, and reduces cost, maintenance and mechanical complexity.

As mentioned earlier in this chapter, duplexers may be built in the home workshop. Bob Shriner, WA0UZO, presented a small, mechanically simple duplexer for low-power applications in April 1979 *QST*. Shriner's design is unique, as the duplexer cavities are constructed of circuit-board material. Low cost and simplicity are the result, but with a trade-off in performance. A silver-plated version of Shriner's design has an insertion loss of approximately 5 dB at 146 MHz. The loss is greater if the copper is not plated, and increases as the inner walls of the cavities tarnish.

This duplexer construction project by John Bilodeau, W1GAN, represents an effective duplexer. The information originally appeared in July 1972 *QST*. It is a time-proven project used by many repeater groups, and can be duplicated relatively easily. Its insertion loss is just 1.5 dB.

Fig 21 will help you visualize the requirements for a duplexer, which can be summed up as follows. The duplexer must attenuate the transmitter carrier to avoid overloading the receiver and thereby reducing its sensitivity. It must also attenuate any noise or spurious frequencies from the transmitter on or near the receiver frequency. In addition, a duplexer must provide a proper impedance match between transmitter, antenna, and receiver.

Table 1
Product Matrix Showing Repeater Equipment and Manufacturer by Frequency Band

Source	Antennas							Duplexers				Cavity Filters			
	28	50	144	220	450	902	1296	144	220	450	902	144	220	450	902
Austin	S	S	S	S	S	S	S								
Celwave	C	C	C	C	C	C		C	C	C	C	C	C	C	C
Comet															
Cushcraft		C	C	C	C										
Dec Prod		C	C	C	C	C		C	C		C	C		C	
MA/COM												C		C	
RF Parts			C		C	C	C								
Sinclair	C	C	C					C		C		C		C	C
TX/RX								C	C	C		C		C	C
Wacom															

Source	Isolators/Circulators						Transmitter Combiners				Cross-Band Couplers			
	28	50	144	220	450	902	144	220	450	902	0-174 450-512	0-512 800-960	59-174 806-960	406-512 806-960
Celwave			C	C	C	C	C	C	C	C			S	
Dec Prod			C		C	C	C	C	C					
Sinclair			C		C	C								
TX/RX			C		C	C	C	C	C	C	C	C	C	C
Wacom			C	C	C	C	C	C	C	C		C		C

Abbreviated names above are for the following manufacturers: Austin Antennas, Celwave RF Inc, Cushcraft Corp, Decibel Products Inc, RF Parts, Sinclair Radio Laboratories Inc, TX/RX Systems Inc and Wacom Inc. A manufacturer's contact list appears in Chapter 21.

Key to codes used:
C = catalog (standard) item
S = special-order item

Note: Coaxial cable is not listed, because most manufacturers sell only to dealers.

Fig 21—Duplexers permit using one antenna for both transmitting and receiving in a repeater system. Section 1 prevents energy at the transmitter frequency from interfering with the receiver, while section 2 attenuates any off-frequency transmitter energy that is at or near the receiver frequency.

As shown in Fig 21, transmitter output on 146.94 MHz going from point C to D should not be attenuated. However, the transmitter energy should be greatly attenuated between points B and A. Duplexer section 2 should attenuate any noise or signals that are on or near the receiver input frequency of 146.34 MHz. For good reception the noise and spurious signal level must be less than −130 dBm (0 dBm = 1 milliwatt into 50 Ω). Typical transmitter noise 600 kHz away from the carrier frequency is 80 dB below the transmitter power output. For 60 watts of output (+48 dBm), the noise level is −32 dBm. The duplexer must make up the difference between −32 dBm and −130 dBm, or 98 dB.

The received signal must go from point B to A with a minimum of attenuation. Section 1 of the duplexer must also provide enough attenuation of the transmitter energy to prevent receiver overload. For an average receiver, the transmitter signal must be less than −30 dBm to meet this requirement. The difference between the transmitter output of +48 dBm and the receiver overload point of −30 dBm, 78 dB, must be made up by duplexer section 1.

THE CIRCUIT

Fig 22 shows the completed 6-cavity duplexer, and **Fig 23** shows the assembly of an individual cavity. A $1/4$-λ resonator was selected for this duplexer design. The length of the center conductor is adjusted by turning a

Fig 22—A six-cavity duplexer for use with a 144-MHz repeater. The cavities are fastened to a plywood base for mechanical stability. Short lengths of double-shielded cable are used for connections between individual cavities. An insertion loss of less than 1.5 dB is possible with this design.

threaded rod, which changes the resonant frequency of the cavity. Energy is coupled into and out of the tuned circuit by the coupling loops extending through the top plate.

The cavity functions as a series resonant circuit. When a reactance is connected across a series resonant circuit, an anti-resonant notch is produced, and the resonant frequency is shifted. If a capacitor is added, the notch appears below the resonant frequency. Adding inductance instead of capacitance makes the notch appear above the resonant frequency. The value of the added component determines the spacing between the notch and the resonant frequency of the cavity.

Fig 24 shows the measured band-pass characteristics of the cavity with shunt elements. With the cavity tuned to 146.94 MHz and a shunt capacitor connected from input to output, a 146.34-MHz signal is attenuated

Fig 23—The assembly of an individual cavity. A Bud Minibox is mounted on the top plate with three screws. A clamping sleeve made of brass pipe is used to prevent crushing the box when the locknut is tightened on the tuning shaft. Note that the positions of both C1 and L1 are shown, but that three cavities will have C1 installed and three will have L1 in place.

Fig 24—Typical frequency response of a single cavity of the type used in the duplexer. The dotted line represents the passband characteristics of the cavity alone; the solid line for the cavity with a shunt capacitor connected between input and output. An inductance connected in the same manner will cause the rejection notch to be above the frequency to which the cavity is tuned.

by 35 dB. If an inductance is placed across the cavity and the cavity is tuned to 146.34 MHz, the attenuation at 146.94 MHz is 35 dB. Insertion loss in both cases is 0.4 dB. Three cavities with shunt capacitors are tuned to 146.94 MHz and connected together in cascade with short lengths of coaxial cable. The attenuation at 146.34 MHz is more than 100 dB, and insertion loss at 146.94 MHz is

1.5 dB. Response curves for a six-cavity duplexer are given in **Fig 25**.

Construction

The schematic diagram for the duplexer is shown in **Fig 26**. Three parts for the duplexer must be machined; all others can be made with hand tools. A small lathe can be used to machine the brass top plate, the threaded tuning plunger bushing and the Teflon insulator bushing. The dimensions of these parts are given in **Fig 27**.

Type DWV copper tubing is used for the outer conductor of the cavities. The wall thickness is 0.058 inch, with an outside diameter of $4^1/_8$ inches. You will need a tubing cutter large enough to handle this size (perhaps borrowed or rented). The wheel of the cutter should be tight and sharp. Make slow, careful cuts so the ends will be square. The outer conductor is $22^1/_2$ inches long.

The inner conductor is made from type M copper tubing having an outside diameter of $1^3/_8$ inches. A 6-inch length of 1-inch OD brass tubing is used to make the tuning plunger.

The tubing types mentioned above are designations used in the plumbing and steam-fitting industry. Other types may be used in the construction of a duplexer, but you should check the sizes carefully to assure that the parts will fit each other. A greater wall thickness will make the assembly heavier, and the expense will increase accordingly. Soft solder is used throughout the assembly. Unless you have experience with silver solder, do not use it. Eutectic type 157 solder with paste or acid

Fig 25—Frequency response of the six-cavity duplexer. One set of three cavities is tuned to pass 146.34 MHz and notch 146.94 MHz (the receiver leg). The remaining set of three cavities is tuned to pass 146.94 MHz and notch 146.34 MHz. This duplexer provides approximately 100 dB of isolation between the transmitter and receiver when properly tuned.

Fig 26—Diagram of the six-cavity duplexer. Coaxial cable lengths between cavities are critical and must be followed closely. Double shielded cable and high quality connectors should be used throughout. The sizes and shapes of the coupling loops, L1, and the straps for connecting C1 should be observed.
C1—1.7-11 pF circuit-board mount, E. F. Johnson 189-5-5 or equiv. Set at ³/₄ closed for initial alignment.

Fig 27—Dimensions for the three parts that require machining. A small metal-working lathe should be used for making these parts.

flux makes very good joints. This type has a slightly higher melting temperature than ordinary tin-lead alloy, but has considerably greater strength.

First solder the inner conductor to the top plate (**Fig 28**). The finger stock can then be soldered inside the lower end of the inner conductor, while temporarily held in place with a plug made of aluminum or stainless steel. While soldering, do not allow the flame from the torch to overheat the finger stock. The plunger bushing is soldered into the tuning plunger and a 20-inch length of threaded rod is soldered into the bushing.

Cut six slots in the top of the outer conductor. They should be $^5/_8$ inch deep and equally spaced around the tubing. The bottom end of the 4-inch tubing is soldered to the square bottom plate. The bottom plates have holes in the corners so they can be fastened to a plywood base by means of wood screws. Because the center conductor has no support at one end, the cavities must be mounted vertically.

The size and position of the coupling loops are critical. Follow the given dimensions closely. Both loops should be $^1/_8$ inch away from the center conductor on opposite sides. Connect a solder lug to the ground end of the loop, then fasten the lug to the top plate with a screw. The free end of the loop is insulated by Teflon bushings where it passes through the top plate for connection to the BNC fittings.

Before final assembly of the parts, clean them thoroughly. Soap-filled steel wool pads and hot water work well for this. Be sure the finger stock makes firm contact with the tuning plunger. The top plate should fit snugly in the top of the outer conductor—a large hose clamp tightened around the outer conductor will keep the top plate in place.

Fig 28—Two of the center conductor and top plate assemblies. In the assembly at the left, C1 is visible just below the tuning shaft, mounted by short straps made from sheet copper. The assembly on the right has L1 in place between the BNC connectors. The Miniboxes are fastened to the top plate by a single large nut in these units. Using screws through the Minibox into the top plate, as described in the text, is preferred.

ADJUSTMENT

After the cavities have been checked for band-pass characteristics and insertion loss, install the anti-resonant elements, C1 and L1. (See Fig 24.) It is preferable to use laboratory test equipment when tuning the duplexer. An option is to use a low-power transmitter with an RF probe and an electronic voltmeter. Both methods are shown in **Fig 29**.

With the test equipment connected as shown in Fig 29A, adjust the signal generator frequency to the desired repeater input frequency. Connect a calibrated step attenuator between points X and Y. With no attenuation, adjust the HP-415 for 0 on the 20-dB scale. You can check the calibration of the 415 by switching in different amounts of attenuation and noting the meter reading. You may note a small error at either high or very low signal levels.

Next, remove the step attenuator and replace it with a cavity that has the shunt inductor, L1, in place. Adjust the tuning screw for maximum reading on the 415 meter. Remove the cavity and connect points X and Y. Set the

Fig 29—The duplexer can be tuned by either of the two methods shown here, although the method depicted at A is preferred. The signal generator should be modulated by a 1-kHz tone. If the setup shown at B is used, the transmitter should not be modulated, and should have a minimum of noise and spurious signals. The cavities to be aligned are inserted between X and Y in the setup at A, and between P and Q in B.

signal generator to the repeater output frequency and adjust the 415 for a 0 reading on the 20-dB scale.

Reinsert the cavity between X and Y and adjust the cavity tuning for minimum reading on the 415. The notch should be sharp and have a depth of at least 35 dB. It is important to maintain the minimum reading on the meter while tightening the locknut on the tuning shaft.

To check the insertion loss of the cavity, the output from the signal generator should be reduced, and the calibration of the 415 meter checked on the 50-dB expanded scale. Use a fixed 1-dB attenuator to make certain the error is less than 0.1 dB. Replace the attenuator with the cavity and read the loss. The insertion loss should be 0.5 dB or less. The procedure is the same for tuning all six cavities, except that the frequencies are reversed for those having the shunt capacitor installed.

Adjustment with Minimum Equipment

A transmitter with a minimum of spurious output is required. Most modern transmitters meet this requirement. The voltmeter in use should be capable of reading 0.5 volt (or less), full scale. The RF probe used should be rated to 150 MHz or higher. Sections of RG-58 cable are used as attenuators, as shown in Fig 29B. The loss in these 140-foot lengths is nearly 10 dB, and helps to isolate the transmitter in case of mismatch during tuning.

Set the transmitter to the repeater input frequency and connect P and Q. Obtain a reading between 1 and 3 volts on the voltmeter. Insert a cavity with shunt capacitors in place between P and Q and adjust the cavity tuning for a minimum reading on the voltmeter. (This reading should be between 0.01 and 0.05 volt.) The rejection in dB can be calculated by

dB = 20 log (V1/V2)

This should be at least 35 dB. Check the insertion loss by putting the receiver on the repeater output frequency and noting the voltmeter reading with the cavity out of the circuit. A 0.5-dB attenuator can be made from a 7-foot length of RG-58. This 7-foot cable can be used to check the calibration of the detector probe and the voltmeter.

Cavities with shunt inductance can be tuned the same way, but with the frequencies reversed. If two or more cavities are tuned while connected together, transmitter noise can cause the rejection readings to be low. In other words, there will be less attenuation.

Results

The duplexer is conservatively rated at 150 watts input, but if constructed carefully should be able to handle as much as 300 watts. Silver plating the interior surfaces of the cavities is recommended if input power is to be greater than 150 watts. A duplexer of this type with silver-plated cavities has an insertion loss of less than 1 dB, and a rejection of more than 100 dB. Unplated cavi-

ties should be disassembled at least every two years, cleaned thoroughly, and then retuned.

Miscellaneous Notes

1) Double shielded cable and high quality connectors are *required* throughout the system.
2) The SWR of the antenna should not exceed 1.2:1 for proper duplexer performance.
3) Good shielding of the transmitter and receiver at the repeater is essential.
4) The antenna should have four or more wavelengths of vertical separation from the repeater.
5) Conductors in the near field of the antenna should be well bonded and grounded to eliminate noise.
6) The feed line should be electrically bonded and mechanically secured to the tower or mast.
7) Feed lines and other antennas in the near field of the repeater antenna should be well bonded and as far from the repeater antenna as possible.
8) Individual cavities can be used to improve the performance of separate antenna or separate site repeaters.
9) Individual cavities can be used to help solve intermodulation problems.

BIBLIOGRAPHY

Source material and more extended discussions of the topics covered in this chapter can be found in the references below.

P. Arnold, "Controlling Cavity Drift in Low-Loss Combiners," *Mobile Radio Technology*, Apr 1986, pp 36-44.

L. Barrett, "Repeater Antenna Beam Tilting," *Ham Radio*, May 1983, pp 29-35. (See correction, *Ham Radio*, Jul 1983, p 80.)

W. F. Biggerstaff, "Operation of Close Spaced Antennas in Radio Relay Systems," *IRE Transactions on Vehicular Communications*, Sep 1959, pp 11-15.

J. J. Bilodeau, "A Homemade Duplexer for 2-Meter Repeaters," *QST*, Jul 1972, pp 22-26, 47.

W. B. Bryson, "Design of High Isolation Duplexers and a New Antenna for Duplex Systems," *IEEE Transactions on Vehicular Communications*, Mar 1965, pp 134-140.

K. Connolly and P. Blevins, "A Comparison of Horizontal Patterns of Skeletal and Complete Support Structures," *IEEE 1986 Vehicular Technology Conference Proceedings*, pp 1-7.

S. Kozono, T. Tsuruhara and M. Sakamoto, "Base Station Polarization Diversity Reception for Mobile Radio," *IEEE Transactions on Vehicular Technology*, Nov 1984, pp 301-306.

J. Kraus, *Antennas*, 2nd ed. (New York: McGraw-Hill Book Co., 1988).

W. Pasternak and M. Morris, *The Practical Handbook of Amateur Radio FM & Repeaters*, (Blue Ridge Summit, PA: Tab Books Inc., 1980), pp 355-363.

M. W. Scheldorf, "Antenna-To-Mast Coupling in Com-

munications," *IRE Transactions on Vehicular Communications*, Apr 1959, pp 5-12.

R. D. Shriner, "A Low Cost PC Board Duplexer," *QST*, Apr 1979, pp 11-14.

W. V. Tilston, "Simultaneous Transmission and Reception with a Common Antenna," *IRE Transactions on Vehicular Communications*, Aug 1962, pp 56-64.

E. P. Tilton, "A Trap-Filter Duplexer for 2-Meter Repeaters," *QST*, Mar 1970, pp 42-46.

R. Wheeler, "Fred's Advice solves Receiver Desense Problem," *Mobile Radio Technology*, Feb 1986, pp 42-44.

R. Yang and F. Willis, "Effects of Tower and Guys on Performance of Side Mounted Vertical Antennas," *IRE Transactions on Vehicular Communications*, Dec 1960, pp 24-31.

Chapter 18

VHF and UHF Antenna Systems

A good antenna system is one of the most valuable assets available to the VHF/UHF enthusiast. Compared to an antenna of lesser quality, an antenna that is well designed, is built of good quality materials, and is well maintained, will increase transmitting range, enhance reception of weak signals and reduce interference problems. The work itself building antennas is by no means the least attractive part of the job. Even with high-gain antennas, experimentation is greatly simplified at VHF and UHF because the antennas are a physically manageable size. Setting up a home antenna range is within the means of most amateurs, and much can be learned about the nature and adjustment of antennas. No large investment in test equipment is necessary.

The Basics

Selecting the best VHF or UHF antenna for a given installation involves much more than scanning gain figures and prices in a manufacturer's catalog. There is no one "best" VHF or UHF antenna design for all purposes. The first step in choosing an antenna is figuring out what you want it to do.

Gain

At VHF and UHF, it is possible to build Yagi antennas with very high gain—15 to 20 dBi—on a physically manageable boom. Such antennas can be combined in arrays of two, four, six, eight or more antennas. These arrays are attractive for EME, tropospheric scatter or other weak-signal communications modes.

Radiation Patterns

Antenna radiation can be made omnidirectional, bidirectional, practically unidirectional, or anything between these conditions. A VHF net operator may find an omnidirectional system almost a necessity, but it may be a poor choice otherwise. Noise pickup and other interference problems are greater with such omnidirec-tional antennas, and omnidirectional antennas having some gain are especially bad in these respects. Maximum gain and low radiation angle are usually prime interests of the weak-signal DX aspirant. A clean pattern, with lowest possible pickup and radiation off the sides and back, may be important in high-activity areas, or where the noise level is high.

Frequency Response

The ability to work over an entire VHF band may be important in some types of work. Modern Yagis can achieve performance over a remarkably wide frequency range, providing that the boom length is long enough and enough elements are used to populate the boom. Modern Yagi designs in fact are competitive with directly driven collinear arrays of similar size and complexity. The primary performance parameters of gain, front-to-rear ratio and SWR can be optimized over all the VHF or UHF amateur bands readily, with the exception of the full 6meter band from 50.0 to 54.0 MHz, which is an 8% wide bandwidth. A Yagi can be easily designed to cover any 2.0 MHz portion of the 6-meter band with superb performance.

Height Gain

In general, higher is better in VHF and UHF antenna installations. Raising the antenna over nearby obstructions may make dramatic improvements in coverage. Within reason, greater height is almost always worth its cost, but height gain (see Chapter 23, Radio Wave Propagation) must be balanced against increased transmission-line loss. This loss can be considerable, and it increases with frequency. The best available line may not be very good if the run is long in terms of wavelengths. Line loss considerations (see Chapter 24, Transmission Lines) are important in antenna planning.

Physical Size

A given antenna design for 432 MHz has the same gain as the same design for 144 MHz, but being only one-third as large intercepts only one-ninth as much energy in receiving. In other words, the antenna has less pickup efficiency at 432 MHz. To be equal in communication effectiveness, the 432-MHz array should be at least equal in *size* to the 144-MHz antenna, which requires roughly three times as many elements. With all the extra difficulties involved in using the higher frequencies effectively, it is best to keep antennas as large as possible for these bands.

DESIGN FACTORS

With the objectives sorted out in a general way, decisions on specifics, such as polarization, type of transmission line, matching methods and mechanical design must be made.

Polarization

Whether to position antenna elements vertically or horizontally has been widely debated since early VHF pioneering days. Tests have shown little evidence about which polarization sense is most desirable. On long propagation paths there is no consistent advantage either way. Shorter paths tend to yield higher signal levels with horizontally polarized antennas over some kinds of terrain. Man-made noise, especially ignition interference, also tends to be lower with horizontal antennas. These factors make horizontal polarization somewhat more desirable for weak-signal communications. On the other hand, vertically polarized antennas are much simpler to use in omnidirectional systems and in mobile work.

Vertical polarization was widely used in early VHF work, but horizontal polarization gained favor when directional arrays started to become widely used. The major use of FM and repeaters, particularly in the VHF/UHF bands, has tipped the balance in favor of vertical antennas in mobile and repeater use. Horizontal polarization predominates in other communication on 50 MHz and higher frequencies. An additional loss of 20 dB or more can be expected when cross-polarized antennas are used.

TRANSMISSION LINES

Transmission line principles are covered in detail in Chapter 24, Transmission Lines. Techniques that apply to VHF and UHF operation are dealt with in greater detail here. The principles of carrying RF from one location to another via a feed line are the same for all radio frequencies. As at HF, RF is carried principally via open wire lines and coaxial cables at VHF/UHF. Certain aspects of these lines characterize them as good or bad for use above 50 MHz.

Properly built open-wire line can operate with very low loss in VHF and UHF installations. A total line loss under 2 dB per 100 feet at 432 MHz can easily be obtained. A line made of #12 wire, spaced $^3/_4$ inch or more with Teflon spreaders and run essentially straight from antenna to station, can be better than anything but the most expensive coax. Such line can be home made or purchased at a fraction of the cost of coaxial cables, with comparable loss characteristics. Careful attention must be paid to efficient impedance matching if the benefits of this system are to be realized. A similar system for 144 MHz can easily provide a line loss under 1 dB.

Small coax such as RG-58 or RG-59 should never be used in VHF work if the run is more than a few feet. Lines of $^1/_2$-inch diameter (RG-8 or RG-11) work fairly well at 50 MHz, and are acceptable for 144-MHz runs of 50 feet or less. These lines are somewhat better if they employ foam instead of ordinary PE dielectric material. Aluminum-jacket *hardline* coaxial cables with large inner conductors and foam insulation are well worth their cost, and can sometimes be obtained for free from local Cable TV operators as "end runs"—pieces at the end of a roll. The most common CATV cable is $^1/_2$-inch OD 75-Ω hardline. Matched-line loss for this cable is about 1.0 dB/100 feet at 146 MHz and 2.0 dB/100 feet at 432 MHz. Less commonly available from CATV companies is the $^3/_4$-inch 75Ω hardline, sometimes with a black self-healing hard plastic covering. This line has 0.8 dB of loss per 100 feet at 146 MHz, and 1.6 dB loss per 100 feet at 432 MHz. There will be small additional losses for either line if 75-to-50Ω transformers are used at each end.

Commercial connectors for hardline are expensive but provide reliable connections with full waterproofing. Enterprising amateurs have homebrewed low-cost connectors. If they are properly water proofed, connectors and hardline can last almost indefinitely. Hardline must not be bent too sharply, because it will kink. See Chapter 24, Transmission Lines, for details on hardline connectors.

Beware of any "bargains" in coax for VHF or UHF use. Feed-line loss can be compensated to some extent by increasing transmitter power, but once lost, a weak signal can never be recovered in the receiver. Effects of weather on transmission lines should not be ignored. Well-constructed open-wire line works optimally in nearly any weather, and it stands up well. Twin-lead is almost useless in heavy rain, wet snow or icing. The best grades of

coax are completely impervious to weather—they can be run underground, fastened to metal towers without insulation and bent into any convenient position with no adverse effects on performance.

WAVEGUIDES

Above 2 GHz, coaxial cable is a losing proposition for communications work. Fortunately, at this frequency the wavelength is short enough to allow practical, efficient energy transfer by an entirely different means. A *waveguide* is a conducting tube through which energy is transmitted in the form of electromagnetic waves. The tube is not considered as carrying a current in the same sense that the wires of a two-conductor line do, but rather as a *boundary* that confines the waves in the enclosed space. Skin effect prevents any electromagnetic effects from being evident outside the guide. The energy is injected at one end, either through capacitive or inductive coupling or by radiation, and is removed from the other end in a like manner. Waveguide merely confines the energy of the fields, which are propagated through it to the receiving end by means of reflections against its inner walls.

Analysis of waveguide operation is based on the assumption that the guide material is a perfect conductor of electricity. Typical distributions of electric and magnetic fields in a rectangular guide are shown in **Fig 1**. The intensity of the electric field is greatest (as indicated by closer spacing of the lines of force) at the center along the X dimension (Fig 1C), diminishing to zero at the end walls. The fields must diminish in this manner, because the existence of any electric field parallel to the walls at the surface would cause an infinite current to flow in a perfect conductor. Waveguides, of course, cannot carry RF in this fashion.

Modes of Propagation

Fig 1 represents the most basic distribution of the electric and magnetic fields in a waveguide. There are an infinite number of ways in which the fields can arrange themselves in a waveguide (for frequencies above the low cutoff frequency of the guide in use). Each of these field configurations is called a *mode.*

The modes may be separated into two general groups. One group, designated *TM* (transverse magnetic), has the magnetic field entirely transverse to the direction of propagation, but has a component of the electric field in that direction. The other type, designated *TE* (transverse electric) has the electric field entirely transverse, but has a component of magnetic field in the direction of propagation. TM waves are sometimes called *E waves*, and TE waves are sometimes called *H waves*, but the TM and TE designations are preferred.

The mode of propagation is identified by the group letters followed by two subscript numerals. For example, TE_{10}, TM_{11}, etc. The number of possible modes increases

with frequency for a given size of guide, and there is only one possible mode (called the *dominant mode*) for the lowest frequency that can be transmitted. The dominant mode is the one generally used in amateur work.

Waveguide Dimensions

In rectangular guide the critical dimension is X in Fig 1. This dimension must be more than $^1/_2 \lambda$ at the lowest frequency to be transmitted. In practice, the Y dimension usually is made about equal to $^1/_2$ X to avoid the possibility of operation in other than the dominant mode.

Cross-sectional shapes other than a rectangle can be used, the most important being the circular pipe. Much the same considerations apply as in the rectangular case.

Wavelength dimensions for rectangular and circular guides are given in **Table 1**, where X is the width of a rectangular guide and r is the radius of a circular guide. All figures apply to the dominant mode.

Fig 1—Field distribution in a rectangular waveguide. The TE10 mode of propagation is depicted.

Coupling to Waveguides

Energy may be introduced into or extracted from a waveguide or resonator by means of either the electric or magnetic field. The energy transfer frequently is through a coaxial line. Two methods for coupling to coaxial line are shown in **Fig 2**. The probe shown at A is simply a short extension of the inner conductor of the coaxial line, oriented so that it is parallel to the electric lines of force. The loop shown at B is arranged so that it encloses some of the magnetic lines of force. The point at which maximum coupling is obtained depends upon the mode of propagation in the guide or cavity. Coupling is maximum when the coupling device is in the most intense field.

Coupling can be varied by turning the probe or loop through a 90° angle. When the probe is perpendicular to the electric lines the coupling is minimum. Similarly, when the plane of the loop is parallel to the magnetic lines the coupling is minimum.

If a waveguide is left open at one end it will radiate energy. This radiation can be greatly enhanced by flaring the waveguide to form a pyramidal horn antenna. The horn acts as a transition between the confines of the waveguide and free space. To effect the proper impedance transformation the horn must be at least $1/2 \lambda$ on a side. A horn of this dimension (cutoff) has a unidirectional radiation pattern with a null toward the waveguide transition. The gain at the cutoff frequency is 3 dB, increasing 6 dB with each doubling of frequency. Horns are used extensively in microwave work, both as primary radiators and as feed elements for more elaborate focusing systems. Details for constructing 10-GHz horn antennas are given later in this chapter.

Evolution of a Waveguide

Suppose an open-wire line is used to carry RF energy from a generator to a load. If the line has any appreciable length it must be mechanically supported. The line must be well insulated from the supports if high losses are to be avoided. Because high-quality insulators are difficult to construct at microwave frequencies, the logical alternative is to support the transmission line with $1/4 \lambda$ stubs, shorted at the end opposite the feed line. The open end of such a stub presents an infinite impedance to the transmission line, provided the shorted stub is nonreactive. However, the shorting link has a finite length, and therefore some inductance. The effect of this inductance can be removed by making the RF current flow on the surface of a plate rather than a thin wire. If the plate is large enough, it will prevent the magnetic lines of force from encircling the RF current.

An infinite number of these $1/4 \lambda$ stubs may be connected in parallel without affecting the standing waves of voltage and current. The transmission line may be supported from the top as well as the bottom, and when an infinite number of supports are added, they form the walls of a waveguide at its cutoff frequency. **Fig 3** illustrates

Table 1
Waveguide Dimensions

	Rectangular	Circular
Cutoff wavelength	2X	3.41r
Longest wavelength transmitted with little attenuation	1.6X	3.2r
Shortest wavelength before next mode becomes possible	1.1X	2.8r

Fig 2—Coupling coaxial line to waveguide and resonators.

how a rectangular waveguide evolves from a two-wire parallel transmission line as described. This simplified analysis also shows why the cutoff dimension is $1/2 \lambda$.

While the operation of waveguides is usually described in terms of fields, current does flow on the inside walls, just as on the conductors of a two-wire transmission line. At the waveguide cutoff frequency, the current is concentrated in the center of the walls, and disperses toward the floor and ceiling as the frequency increases.

IMPEDANCE MATCHING

Impedance matching is covered in detail in Chapter 25, Coupling the Transmitter to the Line, and Chapter 26, Coupling the Line to the Antenna. The theory is the same for frequencies above 50 MHz. Practical aspects are similar, but physical size can be a major factor in the choice of methods. Only the matching devices used in practical construction examples later in this chapter are discussed in detail here. This should not rule out consideration of other methods, however, and you should read the relevant portions of both Chapters 25 and 26.

Universal Stub

As its name *universal stub* implies, the double-adjustment stub of **Fig 4A** is useful for many matching purposes. The stub length is varied to resonate the system and the transmission-line attachment point is varied until the transmission line and stub impedances are equal. In practice this involves moving both the sliding short and

Fig 3—At its cutoff frequency a rectangular waveguide can be thought of as a parallel two-conductor transmission line supported from top and bottom by an infinite number of $1/4$-λ stubs.

Fig 4—Matching methods commonly used at VHF. The universal stub, A, combines tuning and matching. The adjustable short on the stub and the points of connection of the transmission line are adjusted for minimum reflected power on the line. In the delta match, B and C, the line is fanned out and connected to the dipole at the point of optimum impedance match. Impedances need not be known in A, B or C. The gamma match, D, is for direct connection of coax. C1 tunes out inductance in the arm. A folded dipole of uniform conductor size, E, steps up antenna impedance by a factor of four. Using a larger conductor in the unbroken portion of the folded dipole, F, gives higher orders of impedance transformation.

the point of line connection for zero reflected power, as indicated on an SWR bridge connected in the line.

The universal stub allows for tuning out any small reactance present in the driven part of the system. It permits matching the antenna to the line without knowledge of the actual impedances involved. The position of the short yielding the best match gives some indication of the amount of reactance present. With little or no reactive component to be tuned out, the stub must be approximately $1/2$ λ from load toward the short.

The stub should be made of stiff bare wire or rod, spaced no more than $1/20$ λ apart. Preferably it should be mounted rigidly, on insulators. Once the position of the short is determined, the center of the short can be grounded, if desired, and the portion of the stub no longer needed can be removed.

It is not necessary that the stub be connected directly to the driven element. It can be made part of an open-wire line as a device to match coaxial cable to the line. The stub can be connected to the lower end of a delta match or placed at the feed point of a phased array. Examples of these uses are given later.

Delta Match

Probably the most basic impedance matching device is the *delta match*, fanned ends of an open-wire line tapped onto a $1/2$ λ antenna at the point of the most-efficient power transfer. This is shown in Fig 4B. Both the side length and the points of connection either side of the center of the element must be adjusted for minimum reflected power on the line, but as with the universal stub, you needn't know the impedances. The delta match makes no provision for tuning out reactance, so the universal stub is often used as a termination for it.

At one time, the delta match was thought to be inferior for VHF applications because of its tendency to radiate if improperly adjusted. The delta has come back into favor now that accurate methods are available for measuring the effects of matching. It is very handy for phasing multiple-bay arrays with open-wire lines, and its

dimensions in this use are not particularly critical. It should be checked out carefully in applications like that of Fig 4C, where no tuning device is used.

Gamma and T Matches

An application of the same principle allowing direct connection of coax is the *gamma match*, Fig 4D. Because the RF voltage at the center of a $1/2$ λ dipole is zero, the outer conductor of the coax is connected to the element at this point. This may also be the junction with a metallic or wooden boom. The inner conductor, carrying the RF current, is tapped out on the element at the matching point. Inductance of the arm is tuned out by

means of C1, resulting in electrical balance. Both the point of contact with the element and the setting of the capacitor are adjusted for zero reflected power, with a bridge connected in the coaxial line.

The capacitance can be varied until the required value is found, and the variable capacitor replaced with a fixed unit of that value. C1 can be mounted in a waterproof box. The maximum required value should be about 100 pF for 50 MHz and 35 to 50 pF for 144 MHz.

The capacitor and arm can be combined in one coaxial assembly, with the arm connected to the driven element by means of a sliding clamp and the inner end of the arm sliding inside a sleeve connected to the center conductor of the coax. An assembly of this type can be constructed from concentric pieces of tubing, insulated by plastic or heat-shrink sleeving. RF voltage across the capacitor is low when the match is adjusted properly, so with a good dielectric, insulation presents no great problem. The initial adjustment should be made with low power. A clean, permanent high-conductivity bond between arm and element is important, since the RF current is high at this point.

Because it is inherently somewhat unbalanced, the gamma match can sometimes introduce pattern distortion, particularly on long-boom, highly directive Yagi arrays. The *T-match*, essentially two gamma matches in series creating a balanced feed system, has become popular for this reason. A coaxial balun like that shown in **Fig 5** is used from the 200 Ω balanced T-match to the unbalanced 50 Ω coaxial line going to the transmitter. See the K1FO Yagi designs later in this chapter for details on practical use of a T-match.

Folded Dipole

The impedance of a $1/2$ λ dipole broken at its center is about 70 Ω. If a single conductor of uniform size is folded to make a $1/2$ λ dipole as shown in Fig 4E, the impedance is stepped up four times. Such a folded dipole can be fed directly with 300Ω line with no appreciable

mismatch. If a 4:1 balun is used, the antenna can be fed with 75Ω coaxial cable. (See balun information presented below.) Higher step-up impedance transformation can be obtained if the unbroken portion is made larger in cross-section than the fed portion, as shown in Fig 4F.

Hairpin Match

The feed-point resistance of most multielement Yagi arrays is less than 50 Ω. If the driven element is split and fed at the center, it may be shortened from its resonant length to add capacitive reactance at the feed point. Then, shunting the feed point with a wire loop resembling a *hairpin* causes a step-up of the feed-point resistance. The hairpin match is used together with a 4:1 coaxial balun in the 50 MHz arrays described later in this chapter. See Chapter 26, Coupling the Line to the Antenna, for details on the hairpin match.

BALUNS AND ANTENNA TUNERS

Conversion from balanced loads to unbalanced lines (or vice versa) can be performed with electrical circuits, or their equivalents made of coaxial cable. A balun made from flexible coax is shown in Fig 5A. The looped portion is an electrical $1/2$ λ. The physical length depends on the velocity factor of the line used, so it is important to check its resonant frequency as shown in Fig 5B. The two ends are shorted, and the loop at one end is coupled to a dip meter coil. This type of balun gives an impedance step-up of 4:1 (typically 50 to 200 Ω, or 75 to 300 Ω).

Coaxial baluns that yield 1:1 impedance transformations are shown in **Fig 6**. The coaxial sleeve, open at the top and connected to the outer conductor of the line at the lower end (A) is the preferred type. At B, a conductor of approximately the same size as the line is used with the outer conductor to form a $1/4$ λ stub. Another piece of coax, using only the outer conductor, will serve this purpose. Both baluns are intended to present an infi-

Fig 5—Conversion from unbalanced coax to a balanced load can be done with a ½-λ, coaxial balun at A. Electrical length of the looped section should be checked with a dip meter, with the ends shorted, as at B. The ½-λ balun gives a 4:1 impedance step-up.

Fig 6—The balun conversion function, with no impedance transformation, can be accomplished with ¼-λ lines, open at the top and connected to the coax outer conductor at the bottom. The coaxial sleeve at A is preferred.

nite impedance to any RF current that might otherwise flow on the outer conductor of the coax.

The functions of the balun and the impedance transformer can be handled by various tuned circuits. Such a device, commonly called an *antenna tuner* or a *Transmatch*, can provide a wide range of impedance transformations. Additional selectivity inherent in the antenna tuner can reduce RFI problems.

THE YAGI AT VHF AND UHF

Without doubt, the Yagi is king of home-station antennas these days. Today's best designs are computer optimized. For years amateurs as well as professionals designed Yagi arrays experimentally. Now we have powerful (and inexpensive) personal computers and sophisticated software for antenna modeling. These have brought us antennas with improved performance, with little or no element pruning required. Chapter 11, HF Yagi Arrays, describes the parameters associated with Yagi-Uda arrays. Except for somewhat tighter dimensional tolerances needed at VHF and UHF, the properties that make a good Yagi at HF also are needed on the higher frequencies. See the end of this chapter for practical Yagi designs.

STACKING YAGIS

Where suitable provision can be made for supporting them, two Yagis mounted one above the other and fed in phase can provide better performance than one long Yagi with the same theoretical or measured gain. The pair occupies a much smaller turning space for the same gain, and their wider elevation coverage can provide excellent results. The wide azimuthal coverage for a vertical stack often results in QSOs that might be missed with a single narrow-beam long-boom Yagi pointed in a different direction. On long ionospheric paths, a stacked pair occasionally may show an *apparent* gain much greater than the measured 2 to 3 dB of stacking gain. (See also the extensive section on stacking Yagis in Chapter 11, HF Yagi Arrays.)

Optimum vertical spacing for Yagis with boom longer than 1 λ or more is about 1 λ (984/50.1 = 19.64 feet), but this may be too much for many builders of 50-MHz antennas to handle. Worthwhile results can be obtained with as little as $^1/_2$ λ (10 feet), but $^5/_8$ λ (12 feet) is markedly better. The difference between 12 and 20 feet, however, may not be worth the added structural problems involved in the wider spacing, at least at 50 MHz. The closer spacings give lower measured gain, but the antenna patterns are cleaner in both azimuth and elevation than with 1 λ spacing. Extra gain with wider spacings is usually the objective on 144 MHz and higher-frequency bands, where the structural problems are not as severe.

Yagis can also be stacked in the same plane (collinear elements) for sharper azimuthal directivity. A spacing of $^5/_8$ λ between the ends of the inner elements yields the maximum gain within the main lobe of the array.

If individual antennas of a stacked array are properly designed, they look like noninductive resistors to the phasing system that connects them. The impedances involved can thus be treated the same as resistances in parallel.

Three sets of stacked dipoles are shown in **Fig 7**. Whether these are merely dipoles or the driven elements of Yagi arrays makes no difference for the purpose of these examples. Two 300 Ω antennas at A are 1 λ apart, resulting in a paralleled feed-point impedance of 150 Ω at the center. (Actually it is slightly less than 150 Ω because of coupling between bays, but this can be neglected for illustrative purposes.) This value remains the same regardless of the impedance of the phasing line. Thus, any convenient line can be used for phasing, as long as the *electrical* length of each line is the same.

The velocity factor of the line must be taken into account as well. As with coax, this is subject to so much variation that it is important to make a resonance check on the actual line used. The method for doing this is shown in Fig 5B. A $^1/_2$ λ line is resonant both open and shorted, but the shorted condition (both ends) is usually the more convenient test condition.

Fig 7—Three methods of feeding stacked VHF arrays. A and B are for bays having balanced driven elements, where a balanced phasing line is desired. Array C has an all-coaxial matching and phasing system. If the lower section is also $^3/_4$ λ no transposition of line connections is needed.

The impedance transforming property of a $^1/_4$ λ line section can be used in combination matching and phasing lines, as shown in Fig 7B and C. At B, two bays spaced $^1/_2$ λ apart are phased and matched by a 400-Ω line, acting as a double-Q section, so that a 300-Ω main transmission line is matched to two 300-Ω bays. The two halves of this phasing line could also be $^3/_4$-λ or $^5/_4$-λ long, if such lengths serve a useful mechanical purpose. (An example is the stacking of two Yagis where the desirable spacing is more than $^1/_2$ λ.)

A double-Q section of coaxial line is illustrated in Fig 7C. This is useful for feeding stacked bays that were designed for 50-Ω feed. A spacing of $^5/_8$ λ is useful for small Yagis, and this is the equivalent of a full electrical wavelength of solid-dielectric coax such as RG-11.

If one phasing line is electrically $^1/_4$ λ and $^3/_4$ λ on the other, the connection to one driven element should be reversed with respect to the other to keep the RF currents in the elements in phase—the gamma match is located on opposite sides of the driven elements in Fig 7C. If the number of $^1/_4$ λ lengths is the same on either side of the feed point, the two connections should be in the same position, and not reversed. Practically speaking however, you can ensure proper phasing by using exactly equal lengths of line from the same roll of coax. This ensures that the velocity factor for each line is identical.

One marked advantage of coaxial phasing lines is that they can be wrapped around the vertical support,

taped or grounded to it, or arranged in any way that is mechanically convenient. The spacing between bays can be set at the most desirable value, and the phasing lines placed anywhere necessary.

Stacking Yagis for Different Frequencies

In stacking horizontal Yagis one above the other on a single rotating support, certain considerations apply when the bays are for different bands. As a very general rule of thumb, the minimum desirable spacing is half the boom length of the higher frequency Yagi.

For example, assume the stacked two-band array of **Fig 8A** is for 50 and 144 MHz. This vertical arrangement is commonly referred to as a *Christmas tree*, because it resembles one. The 50MHz Yagi has 5elements on a 12-foot boom. It tends to look like "ground" to the 8-element 144 MHz Yagi on a 12-foot boom directly above it. [The exact Yagi designs for the examples used in this section are located on the CD-ROM accompanying this book. They may be evaluated as monoband Yagis using the *YW* (Yagi for Windows) program also supplied on the CD-ROM. In each case the bottom Yagi in the stack (at the top of the tower) is assumed to be 20 feet high.]

SWR Change in a Multi-Frequency Stack

Earlier editions of *The ARRL Antenna Book* stated that the feed-point impedance of the higher-frequency antenna would likely be affected the most by the proxim-

Fig 8—In stacking Yagi arrays one above the other, the minimum spacing between bays (S) should be about half the boom length of the smaller array. Wider spacing is desirable, in which case it should be ½ λ or some multiple thereof, at the frequency of the smaller array. At A, stack of 8-element 2-meter Yagi on a 12-foot boom over a 5-element 6-meter Yagi, also on a 12-foot boom. At B, 5-element 2-meter beam on a 6-foot boom over a 3-element 6-meter beam on a 4-foot boom. At C, a 14-element 70-cm beam on a 9-foot boom, mounted over a 8-element 2-meter beam on a 12-foot boom and a 7-element 6-meter beam on a 22-foot boom.

ity of the lower-frequency Yagi. Modern computer modeling programs reveal that while the feed-point SWR can indeed be affected, by far the greatest degradation is in the forward gain and rearward pattern of the higher-frequency Yagi when the booms are closely spaced. In fact, the SWR curve is usually not affected enough to make it a good diagnostic indicator of interaction between the two Yagis.

Fig 9 shows an overlay of the SWR curves across the 2-meter band for four configurations: an 8-element 2-meter Yagi by itself, and then over a 5-element 6-meter Yagi with spacings between the booms of 1, 2, 4 and 6 feet. The SWR curves are similar—it would be difficult to see any difference between these configurations using typical amateur SWR indicators for anything but the very closest (1-foot) spacing. For example, the SWR curve for the 2-foot spacing case is virtually indistinguishable from that of the Yagi by itself, while the forward gain has dropped more than 0.6 dB because of interactions with the 6-meter Yagi below it.

Gain and Pattern Degradation Due to Stacking

Fig 10 shows four overlaid rectangular plots of the azimuth response from 0° to 180° for the 8-element 2-meter Yagi described above, spaced 1, 2, 4 and 6 feet over a 5-element 6-meter beam. The rectangular presentation gives more detail than a polar plot. The most closely spaced configuration (with 1-foot spacing between the booms) shows the largest degradation in the forward gain, a drop of 1.7 dB. The worst-case front-to-rear ratio for the 6-foot spacing is 29.0 dB, while it is 36.4 dB for the 1-foot spacing—actually better than the F/R for the 8-element 2-meter Yagi by itself. Performance change due to the nearby presence of other Yagis can be enormously

complicated (and sometimes is non-intuitive as well).

What happens when a different kind of 6-meter Yagi is mounted below the 8-element 2-meter Yagi? **Fig 11** compares the change in forward gain and the worst-case F/R performance as a function of spacing between the booms for two varieties of 6-meter Yagis: the 5-element design on a 12-foot boom and a 7-element Yagi on a

Fig 10—Plots of the 8-element 2-meter Yagi's azimuth response from 0° to 180° for spacing distances from 1 to 6 feet. The sidelobe at about 60° varies about 6 dB over the range of boom spacings, while the shape of worst-case F/R curve varies considerably due to interactions with the lower 6-meter beam. The gain for the 1-foot spacing is degraded by more than 3 dB compared to the 2-meter antenna by itself.

Fig 9—SWR curves for different boom spacing between 8-element 2-meter Yagi on 12-foot boom, over a 5-element 6-meter Yagi on a 12-foot boom. For spacings greater than 1 foot between the booms, differences between the SWR curves are difficult to discern.

Fig 11—Plot of 8-element 2-meter Yagi's gain and worst-case F/R as a function of distance over two types of 6-meter beams, one on a 12-foot boom and the other on a 22-foot boom. Beyond a spacing of about 5 feet the performance is degraded a minimal amount.

22-foot boom. The spacing of "0 feet" represents the 8-element 2-meter Yagi when it is used alone, with no other antenna nearby. This sets the reference expectations for gain and F/R.

The most severe degradation occurs for the 1-foot spacing, as you might imagine, for both the 12 and 22-foot boom lengths. Over the 5-element 6-meter Yagi, the 2-meter gain doesn't recover to the reference level of the 8-element 2-meter beam by itself until the spacing is greater than 9 feet. However, the gain is within 0.25 dB of the reference level for spacings of 3 feet or more. Interestingly, the F/R is higher than that of the 2-meter antenna by itself for the 1, 2 and 5-foot spacings and for spacings greater than 11 feet. The 2-meter F/R in the presence of the 12-foot 5-element 6-meter Yagi remains above 20 dB for spacings beyond 1 feet.

Overall, the 2-meter beam performs reasonably well for spacings of 3 feet or more over the 5-element 6-meter Yagi. Put another way, the 2-meter beam's performance is degraded only slightly for boom spacings greater than 3 feet. A spacing of 3 feet is less than the old rule of thumb that the minimum spacing between booms be greater than one-half the boomlength of the higher-frequency Yagi, which in this case is 6 feet long.

For the 7-element 6-meter Yagi, the 2-meter gain recovers to the reference level for spacings beyond 7 feet, but the F/R is degraded below the reference level for all spacings shown in Fig 11. If we use a gain reduction criterion of less than 0.25 dB and a 20-dB F/R level as the minimum acceptable level, then the spacing must be 5 feet or more over the larger 6-meter Yagi. Again, this is less than the rule of thumb that the minimum spacing between booms be greater than one-half the boomlength of the higher-frequency Yagi.

Now, let's try a smaller setup of 2- and 6-meter Yagis stacked vertically in a Christmas-tree configuration to see

if the rule of thumb for spacing the booms still holds. **Fig 12** shows the performance curves versus boom spacing for a 5-element 2-meter Yagi on a 4-foot boom stacked over a 3-element 6-meter Yagi on a 6-foot boom. Again, the 1-foot spacing produces a substantial gain reduction of about 1.3 dB compared to the reference gain when the 2-meter Yagi is used by itself. Beyond a boom spacing of 3 feet the 2-meter gain drops less than 0.25 dB from the reference level of the 2-meter Yagi by itself and the F/R remains above about 20 dB. In this example, the simple rule of thumb that the minimum spacing between booms be greater than half the boom length (half of 4 feet) of the higher-frequency Yagi does not hold up. However, the same minimum spacing of 3 feet we found for the larger 2-meter Yagi remains true. Three feet spacing is almost 0.5 λ between the booms at the higher frequency.

Adding a 70-cm Yagi to the Christmas Tree

Let's get more ambitious and set up a larger VHF/UHF Christmas tree, with a 14-element 70-cm Yagi on a 9-foot boom at the top, mounted 5 feet over an 8-element 2-meter Yagi on a 12-foot boom. At the bottom of the stack (at the top of the tower) is either the 5-element 6-meter beam on a 12-foot boom, or a 7-element 6-meter beam on a 22-foot boom. See Fig 8C. As before, we will vary the spacing between the 70-cm Yagi and the 2-meter Yagi below it to assess the interactions that degrade the 70-cm performance.

Fig 13 compares the change in gain and F/R curves as a function of boom spacings between the 70-cm and 2-meter Yagis for the two different 6-meter Yagis (with a fixed distance of 5 feet between the 2-meter and 6-meter Yagis). In this example, the 70-cm Yagi was designed to be an intrinsic 50-Ω feed, where the F/R has been compromised to some extent. Still, the F/R is greater than 20 dB when the 70-cm Yagi is used by itself.

For spacings greater than 4 feet between the 70-cm and 2-meter booms, the 70-cm gain is equal to or even slightly greater than that of the 70-cm antenna by itself. The increase of gain indicates that the elevation pattern of the 70-cm antenna is slightly compressed by the presence of the other Yagis below it. The F/R stays above at 19.5 dB for spacings greater than or equal to 4 feet. This falls just below our desired lower limit of 20 dB, but it is highly doubtful that anyone would notice this 0.5-dB drop in actual operation. A spacing of 4 feet between booms falls under the rule of thumb that the minimum spacing be at least half the boomlength of the higher-frequency Yagi, which in this case is 9 feet.

What should be obvious in this discussion is that you should model the exact configuration you plan to build to avoid unnecessary performance degradation.

Stacking Same-Frequency Yagis

This subject has been examined in some detail in Chapter 11, HF Yagi Arrays. The same basic principles

502 - 2 Performance vs Spacing, Over 306 - 6 @ 20' Height

Fig 12— Plot of gain and worst-case F/R of a 5-element 2-meter Yagi on a 4-foot boom as a function of distance over a 3-element 6-meter beam on a 6-foot boom. Beyond a spacing of about 3 feet the performance is degraded a minimal amount.

1470 - 9 Performance vs Spacing,
Over 802 - 12 and 5' Over 506 - 12 or 706 - 22 @ 20' Height

— Gain, 506   —◇— Gain, 706   —■— F/R, 506   —□— F/R, 706

Fig 13—Performance of a 14-element 70-cm Yagi on a 9-foot boom, mounted a variable distance over an 8-element 2-meter Yagi on a 12-foot boom, which is mounted 5 feet above either a 5-element 6-meter Yagi on a 12-foot boom or a 7-element 6-meter Yagi on a 22-foot boom. Beyond a spacing of about 4 feet, the performance of the 70-cm beam is degraded a minimal amount.

Fig 14—*HFTA* comparison plots of the elevation responses for two 5-element 6-meter Yagis mounted at 42 and 30 feet above flat ground, when they are fed in-phase and out-of-phase. By switching the phasing (adding a half-wavelength of coax to one of the antennas), the elevation angle can be controlled to enhance performance when a Sporadic-E cloud is nearly overhead.

hold at VHF and UHF as they do on HF. That is, the gain increases gradually with increasing spacing between the booms, and then falls off gradually past a certain spacing distance.

At HF, Chapter 11 emphasizes that you should avoid nulls in the antenna's elevation response—so that you can cover all the angles needed for geographic areas of interest. At VHF/UHF, propagation is usually at low elevation angles for most propagation modes, and signals are often extremely weak. Thus, achieving maximum gain is the most common design objective for a VHF/UHF stack. Of secondary importance is the cleanliness of the beam pattern, to discriminate against interference and noise sources.

Six-meter Sporadic-E can sometimes occur at high elevation angles, especially if the E_s cloud is overhead, or nearly overhead. Since Sporadic-E is exactly that, *sporadic*, it's not a good design practice to try to cover a wide range of elevation angles, as you must often do at HF to cover large geographic areas. On 6 meters, you can change to high-angle coverage when necessary. For example, you might switch to a separate Yagi mounted at a low height, or you might provide means to feed stacked antennas out-of-phase. **Fig 14** shows an *HFTA* (HF Terrain Assessment) plot of two 5-element 6-meter Yagis, fed either in-phase or out-of-phase to cover a much wider range of elevation angles than the in-phase stack alone.

Fig 15A shows the change in gain for four 2-meter stacked designs, as a function of the spacing in wavelengths between the booms. The 3-element Yagi is

mounted on a 2-foot boom (occupying 0.28 λ of that boom). The 5-element Yagi is on a 4-foot boom (0.51 λ of the boom), while the 8-element Yagi is on a 12-foot boom (1.72 λ of boom). The biggest antenna in the group has 16 elements, on a 27-foot boom (4.0 λ of boom). This range of boom lengths pretty much covers the practical range of antennas used by hams.

The stack of two 3-element Yagis peaks at 3.2 dB of additional gain over a single Yagi for 0.75 λ spacing between the booms. Further increases in spacing see the gain change gradually drop off. Fig 15B shows the worst-case F/R of the four stacks, again as a function of boom length. The F/R of a single 3-element Yagi is just over 24 dB, but in the presence of the second 3-element Yagi in the stack, the F/R of the pair oscillates between 15 to 26 dB, finally remaining consistently over the desired 20-dB level for spacings greater than about 1.7 λ, where the gain has fallen about 0.6 dB from the peak possible gain. A boom spacing of 1.7 λ at 146 MHz is 11.5 feet. Thus you must compromise in choosing the boom spacing between achieving maximum gain and the best pattern.

The increase in gain of the stack of two 5-element Yagis peaks at a spacing of about 1 λ (6.7 feet), where the F/R is an excellent 25 dB. Having more elements on a particular length of boom aids in holding a more consistent F/R in the presence of the second antenna.

The gain increase for the bigger stack of 8-element Yagis peaks at a spacing of about 1.5 λ (10.1 feet), where the F/R is more than 27 dB. The 16-element Yagi's gain

Fig 15—Performance of two different 2-meter Yagis (5-elements on 4-foot boom and 8-elements on 12-foot boom) fed in-phase, as a function of spacing between the booms. Note that the distance is measured in wavelengths.

increase is 2.6 dB for a spacing of about 2.25 λ (15.2 feet), where the F/R remains close to 25 dB. The stacking distance of 15.2 feet for an antenna with a 27-foot long boom may be a real challenge physically, requiring a very sturdy rotating mast to withstand wind pressures without bending.

These examples show that the exact spacing between booms is not overly critical, since the gain varies relatively slowly around the peak. Fig 15A shows that the boom spacing needed to achieve peak gain from a stack increases when higher-gain (longer-boom) individual antennas are used in that stack. It also shows that the increase in maximum gain from stacking decreases for long-boom antennas. Fig 15B shows that beyond boom spacings of about 1 λ, the F/R pattern holds well for Yagi designs with booms longer than about 0.5 λ, which is about 4 feet at 146 MHz.

The plots in Fig 15 are representative of typical modern Yagis. You could simply implement these designs as is, and you'll achieve good results. However, we recommend that you model any specific stack you design, just to make sure. Since the boom spacings are displayed in terms of wavelength, you can extend the results for 2 meters to other bands, provided that you use properly scaled Yagi designs to the other bands too.

You can even tweak the element dimensions and spacings of each Yagi used in a stack to optimize the rearward pattern for a particular stacking distance. This strategy can work out well at VHF/UHF, where stacks are often configured for best gain (and pattern) and are "hard-wired" with fixed lengths of feed lines permanently junctioned together.

This is in contrast to the situation at HF (and even on 6 meters). The HF operator usually wants flexibility to select individual Yagis (or combinations of Yagis) from the stack, to match the array's takeoff angle with ionospheric propagation conditions. See Chapter 11, HF Yagi Arrays. The designer of a flexible HF stack thus usually doesn't try to redo the element lengths and spacings of the Yagis to optimize a particular stack.

Stacking Stacks of Different-Frequency Yagis

The investment in a tower is usually substantial, and most hams want to put as many antennas as possible on a tower, provided that interaction between the antennas can be held to a reasonable level. Really ambitious weak-signal VHF/UHF enthusiasts may want "stacked stacks"—sets of stacked Yagis that cover different bands. For example, a VHF contester might want a stack of two 8-element 2-meter Yagis mounted on the same rotating mast as a stack of two 5-element 6-meter Yagis. Let's assume that the boom length of the 8-element 2-meter Yagis is 12 feet (1.78 λ). We'll assume a boom length of 12 feet (0.61 λ) for the 5-element 6-meter Yagi.

From Fig 15, we find the stacking distance between the 8-element 2-meter beams for peak gain and good pattern is 1.5 λ, or 10 feet, but adequate performance can be had for a boom spacing of 0.75 λ, which is 5 feet on 2 meters.

The boom spacing for two 5-element 6-meter beams is 1 λ for peak stacking gain, but a compromise of 0.625 λ (12 feet) still yields an acceptable gain increase of 2 dB over a single Yagi. The overall height of the rotating mast sticking out of the top of the tower is thus set by the 0.625 λ stacking distance on 6 meters, at 12 feet. In-between the 6-meter Yagis at the bottom and top of the rotating mast we will mount the 2-meter Yagi stack. With only 12 feet available on the mast, the spacing for symmetric placement of the two 2-meter Yagis in-between the 6-meter Yagis dictates a distance of only 4 feet between the 2-meter beams. This is less than optimal.

The performance of the 2-meter stack in this "stack within a stack" is affected by the close spacing, but the

interactions are not disastrous. The stacking gain is 1.62 dB more than the gain for a single 8-element 2-meter Yagi and the F/R remains above 20 dB across the 2-meter band.

On 6 meters, the stacking gain for two 5-element 6-meter Yagis spaced 12 feet apart is 2.2 dB more than the gain of a single Yagi, while the F/R pattern remains about 20 dB over the weak-signal portion of the 6-meter band. As described in Chapter 11, HF Yagi Arrays, stacking gives more advantages than merely a gain increase, and 6-meter propagation does require coverage of a range of elevation angles because much of the time ionospheric modes are involved.

Increasing the length of the rotating mast to 18 feet sticking out of the top of the tower will increase performance, particularly on 2 meters. The stacking gain on 6 meters will increase to 2.3 dB while the F/R decreases to 18.5 dB, modest changes both. The 18-foot mast allows the 2-meter Yagis to be spaced 6 feet from each other and 6 feet away from both top and bottom 6-meter antennas. The stacking gain goes to 2.14 dB and the F/R approaches 27 dB in the weak-signal portion of the 2-meter band.

Whether the modest increase in stacking gain is worth the cost and mechanical complexity of stacking two 2-meter Yagis in-between a stack of 6-meter Yagis is a choice left to the operator. Certainly the cost and weight of a rotating mast that is 20 feet long (18 feet out of the top of the tower and 2 feet down inside the tower), a mast that must be sturdy enough to support the antennas in high winds without bending, should give pause to even the most enthusiastic 6-meter weak-signal operator.

QUADS FOR VHF

The quad antenna can be built with inexpensive materials, yet its performance is comparable to other arrays of its size. Adjustment for resonance and impedance matching can be accomplished readily. Quads can be stacked horizontally and vertically to provide high gain, without sharply limiting frequency response. Construction of quad antennas for VHF use is covered later in this chapter.

Stacking Quads

Quads can be mounted side by side or one above the other, or both, in the same general way as other beam antennas. Sets of driven elements can also be mounted in front of a screen reflector. The recommended spacing between adjacent element sides is $1/2 \lambda$. Phasing and feed methods are similar to those employed with other antennas described in this chapter.

Adding Quad Directors

Parasitic elements ahead of the driven element work in a manner similar to those in a Yagi array. Closed loops can be used for directors by making them 5% shorter than the driven element. Spacings are similar to those for conventional Yagis. In an experimental model the reflector was spaced 0.25 λ and the director 0.15 λ. A square array using four 3element bays worked extremely well.

VHF AND UHF QUAGIS

At higher frequencies, especially 420 MHz and above, Yagi arrays using dipole-driven elements can be difficult to feed and match, unless special care is taken to keep the feed-point impedance relatively high by proper element spacing and tuning. The cubical quad described earlier overcomes the feed problems to some extent. When many parasitic elements are used, however, the loops are not nearly as convenient to assemble and tune as are straight cylindrical ones used in conventional Yagis. The *Quagi*, designed and popularized by Wayne Overbeck, N6NB, is an antenna having a full-wave loop driven element and reflector, and Yagi type straight rod directors. Construction details and examples are given in the projects later in this chapter.

COLLINEAR ANTENNAS

The information given earlier in this chapter pertains mainly to parasitic arrays, but the collinear array is worthy of consideration in VHF/UHF operations. This array tends to be tolerant of construction tolerances, making it easy to build and adjust for VHF applications. The use of many collinear driven elements was once popular in very large phased arrays, such as those required in moonbounce (EME) communications, but the advent of computer-optimized Yagis has changed this.

Large Collinear Arrays

Bidirectional curtain arrays of four, six, and eight half waves in phase are shown in **Fig 16**. Usually reflector elements are added, normally at about 0.2 λ behind each driven element, for more gain and a unidirectional pattern. Such parasitic elements are omitted from the sketch in the interest of clarity.

The feed-point impedance of two half waves in phase is high, typically 1000 Ω or more. When they are combined in parallel and parasitic elements are added, the feed impedance is low enough for direct connection to open wire line or twin-lead, connected at the points indicated by black dots. With coaxial line and a balun, it is suggested that the universal stub match, Fig 4A, be used at the feed point. All elements should be mounted at their electrical centers, as indicated by open circles in Fig 16. The framework can be metal or insulating material. The metal supporting structure is entirely behind the plane of the reflector elements. Sheet-metal clamps can be cut from scraps of aluminum for this kind of assembly. Collinear elements of this type should be mounted at their centers (where the RF voltage is zero), rather than at their ends, where the voltage is high and insulation losses and detuning can be harmful.

Collinear arrays of 32, 48, 64 and even 128 elements can give outstanding performance. Any collinear array

should be fed at the center of the system, to ensure balanced current distribution. This is very important in large arrays, where sets of six or eight driven elements are treated as "sub arrays," and are fed through a balanced harness. The sections of the harness are resonant lengths, usually of open wire line. The 48-element collinear array for 432 MHz in **Fig 17** illustrates this principle.

Fig 16—Element arrangements for 8-, 12- and 16-element collinear arrays. Elements are ½ λ long and spaced ½ λ. Parasitic reflectors, omitted here for clarity, are 5% longer and 0.2 λ behind the driven elements. Feed points are indicated by black dots. Open circles show recommended support points. The elements can run through wood or metal booms, without insulation, if supported at their centers in this way. Insulators at the element ends (points of high RF voltage) detune and unbalance the system.

A reflecting plane, which may be sheet metal, wire mesh, or even closely spaced elements of tubing or wire, can be used in place of parasitic reflectors. To be effective, the plane reflector must extend on all sides to at least $^1/_4$ λ beyond the area occupied by the driven elements. The plane reflector provides high F/B ratio, a clean pattern, and somewhat more gain than parasitic elements, but large physical size limits it to use above 420 MHz. An interesting space-saving possibility lies in using a single plane reflector with elements for two different bands mounted on opposite sides. Reflector spacing from the driven element is not critical. About 0.2 λ is common.

THE CORNER REFLECTOR

When a single driven element is used, the reflector screen may be bent to form an angle, giving an improvement in the radiation pattern and gain. At 222 and 420 MHz its size assumes practical proportions, and at 902 MHz and higher, practical reflectors can approach ideal dimensions (very large in terms of wavelengths), resulting in more gain and sharper patterns. The corner reflector can be used at 144 MHz, though usually at much less than optimum size. For a given aperture, the corner reflector does not equal a parabola in gain, but it is simple to construct, broadbanded, and offers gains from about 9 to 14 dBi, depending on the angle and size. This section was written by Paul M. Wilson, W4HHK.

The corner angle can be 90, 60 or 45°, but the side length must be increased as the angle is narrowed. For a 90° corner, the driven element spacing can be anything from 0.25 to 0.7 λ, 0.35 to 0.75 λ for 60°, and 0.5 to

Fig 17—Large collinear arrays should be fed as sets of no more than eight driven elements each, interconnected by phasing lines. This 48-element array for 432 MHz (A) is treated as if it were four 12-element collinear antennas. Reflector elements are omitted for clarity. The phasing harness is shown at B. Squares represent insulators.

Fig 18—Radiation resistance of the driven element in a corner reflector array for corner angles of 180° (flat sheet), 90°, 60° and 45° as a function of spacing D, as shown in Fig 19.

0.8 λ for 45°. In each case the gain variation over the range of spacings given is about 1.5 dB. Because the spacing is not very critical to gain, it may be varied for impedance-matching purposes. Closer spacings yield lower feed-point impedances, but a folded dipole radiator could be used to raise this to a more convenient level.

Radiation resistance is shown as a function of spacing in **Fig 18**. The maximum gain obtained with minimum spacing is the primary mode (the one generally used at 144, 222 and 432 MHz to maintain reasonable side lengths). A 90° corner, for example, should have a minimum side length (S, **Fig 19**) equal to twice the dipole spacing, or 1 λ long for 0.5-λ spacing. A side length greater than 2 λ is ideal. Gain with a 60° or 90° corner reflector with 1-λ sides is about 10 dB. A 60° corner with 2-λ sides has about 13 dBi gain, and a 45° corner with 3-λ sides has about 14 dBi gain.

Reflector length (L, Fig 19) should be a minimum of 0.6 λ. Less than that spacing causes radiation to increase to the sides and rear, and decreases gain.

Spacing between reflector rods (G, Fig 19) should not exceed 0.06 λ for best results. A spacing of 0.06 λ results in a rear lobe that is about 6% of the forward lobe

Fig 19—Construction of a corner reflector array. The frame can be wood or metal. Reflector elements are stiff wire or tubing. Dimensions for several bands are given in Table 2. Reflector element spacing, G, is the maximum that should be used for the frequency; closer spacings are optional. The hinge permits folding for portable use.

(down 12 dB). A small mesh screen or solid sheet is preferable at the higher frequencies to obtain maximum efficiency and highest F/B ratio, and to simplify construction. A spacing of 0.06 λ at 1296 MHz, for example, requires mounting reflector rods about every ¹/₂ inch along the sides. Rods or spines may be used to reduce wind loading. The support used for mounting the reflector rods may be of insulating or conductive material. Rods or mesh weave should be parallel to the radiator.

A suggested arrangement for a corner reflector is shown in Fig 19. The frame may be made of wood or metal, with a hinge at the corner to facilitate portable work or assembly atop a tower. A hinged corner is also useful in experimenting with different angles. **Table 2** gives the principal dimensions for corner reflector arrays for 144 to 2300 MHz. The arrays for 144, 222 and 420 MHz have side lengths of twice to four times the driven element spacing. The 915 MHz corner reflectors use side lengths of three times the element spacing, 1296 MHz corners use side lengths of four times the spacing, and 2304 MHz corners employ side lengths of six times the spacing. Reflector lengths of 2, 3, and 4 wavelengths are used on the 915, 1296 and 2304 MHz reflectors, respectively. A 4 × 6 λ reflector closely approximates a sheet of infinite dimensions.

A corner reflector may be used for several bands, or for UHF television reception, as well as amateur UHF work. For operation on more than one frequency, side length and reflector length should be selected for the lowest frequency, and reflector spacing for the highest frequency. The type of driven element plays a part in determining bandwidth, as does the spacing to the corner. A fat cylindrical element (small λ/dia ratio) or triangular dipole (bow tie) gives more bandwidth than a thin driven element. Wider spacings between driven element and corner give greater bandwidths. A small increase in gain can be obtained for any corner reflector by mounting collinear elements in a reflector of sufficient size, but

Table 2
Dimensions of Corner Reflector Arrays for VHF and UHF

Freq, MHz	Side Length S, in.	Dipole to Vertex D, in.	Reflector Length L, in.	Reflector Spacing G, in.	Corner Angle, Vo	Radiation Resistance, Ω
144*	65	27½	48	7¾	90	70
144	80	40	48	4	90	150
222*	42	18	30	5	90	70
222	52	25	30	3	90	150
222	100	25	30	Screen	60	70
420	27	8¾	16¼	2⁵/₈	90	70
420	54	13½	16¼	Screen	60	70
915	20	6½	25¾	0.65	90	70
915	51	16¾	25¾	Screen	60	65
915	78	25¾	25¾	Screen	45	70
1296	18	4½	27½	½	90	70
1296	48	11¾	27½	Screen	60	65
1296	72	18¼	27½	Screen	45	70
2304	15½	2½	20½	¼	90	70
2304	40	6¾	20½	Screen	60	65
2304	61	10¼	20½	Screen	45	70

*Side length and number of reflector elements somewhat below optimum—slight reduction in gain.

Notes:
915 MHz
Wavelength is 12.9 in.
Side length S is 3 × D, dipole to vertex distance
Reflector length L is 2.0 λ
Reflector spacing G is 0.05 λ

1296 MHz
Wavelength is 9.11 in.
Side length S is 4 × D, dipole to vertex distance
Reflector length L is 3.0 λ
Reflector spacing G is 0.05 λ

2304 MHz
Wavelength is 5.12 in.
Side length S is 6 × D, dipole to vertex distance
Reflector length L is 4.0 λ
Reflector spacing G is 0.05 λ

the simple feed of a dipole is lost if more than two elements are used.

A dipole radiator is usually employed with a corner reflector. This requires a balun between the coaxial line and the balanced feed-point impedance of the antenna. Baluns are easily constructed of coaxial line on the lower VHF bands, but become more difficult at the higher frequencies. This problem may be overcome by using a ground-plane corner reflector, which can be used for vertical polarization. A ground-plane corner with monopole driven element is shown in **Fig 20**. The corner reflector and a $^1/_4$ λ radiator are mounted on the ground plane, permitting direct connection to a coaxial line if the proper spacing is used. The effective aperture is reduced, but at the higher frequencies, second- or third-mode radiator spacing and larger reflectors can be employed to obtain more gain and offset the loss in effective aperture. A J antenna could be used to maintain the aperture area and provide a match to a coaxial line.

For vertical polarization work, four 90° corner reflectors built back-to-back (with common reflectors) could be used for scanning 360° of horizon with modest gain. Feed-line switching could be used to select the desired sector.

TROUGH REFLECTORS

To reduce the overall dimensions of a large corner reflector the vertex can be cut off and replaced with a plane reflector. Such an arrangement is known as a *trough reflector*. See **Fig 21**. Performance similar to that of the large corner reflector can thereby be had, provided that the dimensions of S and T as shown in Fig 21 do not exceed the limits indicated in the figure. This antenna

provides performance very similar to the corner reflector, and presents fewer mechanical problems because the plane center portion is relatively easy to mount on the mast. The sides are considerably shorter, as well.

The gain of both corner reflectors and trough reflectors may be increased by stacking two or more and arranging them to radiate in phase, or alternatively by

Angle α	Value of S for maximum gain	Gain	Value of T
90°	1.5 λ	13.5 dB	1λ - 1.25 λ
60°	1.75 λ	15 dB	1.0 λ
45°	2.0 λ	16 dB	1.9 λ

Fig 21—The trough reflector. This is a useful modification of the corner reflector. The vertex has been cut off and replaced by a simple plane section. The tabulated data shows the gain obtainable for greater values of S than those covered in Table 2, assuming that the reflector is of adequate size.

Fig 20—A ground-plane corner reflector antenna for vertical polarization, such as FM communications or packet radio. The dimension ½ λ in the front view refers to data in Table 2.

adding further collinear dipoles (fed in phase) within a wider reflector. Not more than two or three radiating units should be used, because the great virtue of the simple feeder arrangement would then be lost.

HORN ANTENNAS FOR THE MICROWAVE BANDS

Horn antennas were briefly introduced in the section on coupling energy into and out of waveguides. For amateur purposes, horns begin to show usable gain with practical dimensions in the 902 MHz band.

It isn't necessary to feed a horn with waveguide. If only two sides of a pyramidal horn are constructed, the antenna may be fed at the apex with a two-conductor transmission line. The impedance of this arrangement is on the order of 300 to 400 Ω. A 60° two-sided pyramidal horn with 18 inch sides is shown in **Fig 22**. This antenna has a theoretical gain of 15 dBi at 1296 MHz, although the feed system detailed in **Fig 23** probably degrades this value somewhat. A $^1/_4$ λ, 150-Ω matching section made from two parallel lengths of twin-lead connects to a bazooka balun made from RG-58 cable and a brass tube. This matching system was assembled strictly for the purpose of demonstrating the two-sided horn in a 50-Ω system. In a practical installation the horn would be fed with open-wire line and matched to 50 Ω at the station equipment.

Fig 22—An experimental two-sided pyramidal horn constructed in the ARRL laboratory. A pair of muffler clamps allows mounting the antenna on a mast. This model has sheet-aluminum sides, although window screen would work as well. Temporary elements could be made from cardboard covered with aluminum foil. The horizontal spreaders are Plexiglas rod. Oriented as shown here, the antenna radiates horizontally polarized waves.

PARABOLIC ANTENNAS

When an antenna is located at the focus of a parabolic reflector (dish), it is possible to obtain considerable gain. Furthermore, the beamwidth of the radiated energy will be very narrow, provided all the energy from the driven element is directed toward the reflector. This section was written by Paul M. Wilson, W4HHK.

Gain is a function of parabolic reflector diameter, surface accuracy and proper illumination of the reflector by the feed. Gain may be found from

$$G = 10 \log k \left(\frac{\pi D}{\lambda} \right)^2 \qquad \text{(Eq 1)}$$

where
  G = gain over an isotropic antenna, dBi (subtract 2.15 dB for gain over a dipole)
  k = efficiency factor, usually about 55%
  D = dish diameter in feet
  λ = wavelength in feet

See **Table 3** for parabolic antenna gain for the bands 420 MHz through 10 GHz and diameters of 2 to 30 feet.

A close approximation of beamwidth may be found from

$$\psi = \frac{70\lambda}{D} \qquad \text{(Eq 2)}$$

where
  ψ = beamwidth in degrees at half-power points (3 dB down)
  D = dish diameter in feet
  λ = wavelength in feet

At 420 MHz and higher, the parabolic dish becomes a practical antenna. A simple, single feed point eliminates phasing harnesses and balun requirements. Gain is dependent on good surface accuracy, which is more difficult to achieve with increasing frequency. Surface

Fig 23—Matching system used to test the horn. Better performance would be realized with open wire line. See text.

Table 3
Gain, Parabolic Antennas*

	Dish Diameter (Feet)						
Frequency	2	4	6	10	15	20	30
420 MHz	6.0	12.0	15.5	20.0	23.5	26.0	29.5
902	12.5	18.5	22.0	26.5	30.0	32.5	36.0
1215	15.0	21.0	24.5	29.0	32.5	35.0	38.5
2300	20.5	26.5	30.0	34.5	38.0	40.5	44.0
3300	24.0	30.0	33.5	37.5	41.5	43.5	47.5
5650	28.5	34.5	38.0	42.5	46.0	48.5	52.0
10 GHz	33.5	39.5	43.0	47.5	51.0	53.5	57.0

*Gain over an isotropic antenna (subtract 2.1 dB for gain over a dipole antenna). Reflector efficiency of 55% assumed.

Fig 24—Details of the parabolic curve, $Y^2 = 4SX$. This curve is the locus of points that are equidistant from a fixed point, the focus (F), and a fixed line (AB) that is called the *directrix*. Hence, FP = PC. The focus (F) is located at coordinates S,0.

errors should not exceed $^1/_8$ λ in amateur work. At 430 MHz $^1/_8$ λ is 3.4 inches, but at 10 GHz it is 0.1476 inch! Mesh can be used for the reflector surface to reduce weight and wind loading, but hole size should be less than $^1/_{12}$ λ. At 430 MHz the use of 2-inch hole diameter poultry netting (chicken wire) is acceptable. Fine mesh aluminum screening works well as high as 10 GHz.

A support form may be fashioned to provide the proper parabolic shape by plotting a curve (**Fig 24**) from

$$Y^2 = 4SX$$

as shown in the figure.

Optimum illumination occurs when power at the reflector edge is 10 dB less than that at the center. A circular waveguide feed of correct diameter and length for the frequency and correct beamwidth for the dish focal length to diameter (f/D) ratio provides optimum illumination at 902 MHz and higher. This, however, is impractical at 432 MHz, where a dipole and plane reflector are often used. An f/D ratio between 0.4 and 0.6 is considered ideal for maximum gain and simple feeds.

The focal length of a dish may be found from

$$f = \frac{D^2}{16d} \qquad \text{(Eq 3)}$$

where

f = focal length
D = diameter
d = depth distance from plane at mouth of dish to vertex (see Fig 17)

The units of focal length f are the same as those used to measure the depth and diameter. **Table 4** gives the subtended angle at focus for dish f/D ratios from 0.2 to 1.0. A dish, for example, with a typical f/D of 0.4 requires a 10-dB beamwidth of 130°. A circular waveguide feed with a diameter of approximately 0.7 λ provides nearly optimum illumination, but does not uniformly illuminate the reflector in both the magnetic (TM) and electric (TE) planes. **Fig 25** shows data for plotting radiation patterns from circular guides. The waveguide feed aperture can be modified to change the beamwidth.

One approach used successfully by some experimenters is the use of a disc at a short distance behind the aperture as shown in **Fig 26**. As the distance between the aperture and disc is changed, the TM plane patterns become alternately broader and narrower than with an unmodified aperture. A disc about 2 λ in diameter appears to be as effective as a much larger one. Some experimenters have noted a 1 to 2 dB increase in dish gain with this modified feed. Rectangular waveguide feeds can also be used, but dish illumination is not as uniform as with round guide feeds.

The circular feed can be made of copper, brass, aluminum or even tin in the form of a coffee or juice can, but the latter must be painted on the outside to prevent rust or corrosion. The circular feed must be within a proper size (diameter) range for the frequency being used.

This feed operates in the dominant circular waveguide mode known as the TE_{11} mode. The guide must be large enough to pass the TE_{11} mode with no attenuation, but smaller than the diameter that permits the next higher TM_{01} mode to propagate. To support the desirable TE_{11} mode in circular waveguide, the cutoff frequency, F_C, is given by

$$F_C (TE_{11}) = \frac{6917.26}{d \text{ (inches)}} \qquad \text{(Eq 4)}$$

where

F_C = cutoff frequency in MHz for TE_{11} mode
d = waveguide inner diameter

Circular waveguide will support the TM_{01} mode having a cutoff frequency

$$F_C (TM_{01}) = \frac{9034.85}{d \text{ (inches)}} \qquad \text{(Eq 5)}$$

The wavelength in a waveguide always exceeds the free-space wavelength and is called guide wavelength, λ_g. It is related to the cutoff frequency and operating frequency by the equation

$$\lambda_g = \frac{11802.85}{\sqrt{f_0{}^2 - f_C{}^2}} \qquad \text{(Eq 6)}$$

where

λ_g = guide wavelength, inches
f_0 = operating frequency, MHz
f_C = TE_{11} waveguide cutoff frequency, MHz

An inside diameter range of about 0.66 to 0.76 l is

Fig 25—This graph can be used in conjunction with Table 4 for selecting the proper diameter waveguide to illuminate a parabolic reflector.

Table 4
f/D Versus Subtended Angle at Focus of a
Parabolic Reflector Antenna

f/D	Subtended Angle (Deg.)	f/D	Subtended Angle (Deg.)
0.20	203	0.65	80
0.25	181	0.70	75
0.30	161	0.75	69
0.35	145	0.80	64
0.40	130	0.85	60
0.45	117	0.90	57
0.50	106	0.95	55
0.55	97	1.00	52
0.60	88		

Taken from graph "f/D vs Subtended Angle at Focus," page 170 of the 1966 *Microwave Engineers' Handbook and Buyers Guide.* Graph courtesy of K. S. Kelleher, Aero Geo Astro Corp, Alexandria, Virginia

Table 5
Circular Waveguide Dish Feeds

Freq. (MHz)	Inside Diameter Circular Waveguide Range (in.)
915	8.52-9.84
1296	6.02-6.94
2304	3.39-3.91
3400	2.29-2.65
5800	1.34-1.55
10,250	0.76-0.88

Fig 26—Details of a circular waveguide feed.

suggested. The lower frequency limit (longer dimension) is dictated by proximity to the cutoff frequency. The higher frequency limit (shorter dimension) is dictated by higher order waves. See **Table 5** for recommended inside diameter dimensions for the 902- to 10,000-MHz amateur bands.

The probe that excites the waveguide and makes the transition from coaxial cable to waveguide is $^1/_4$ λ long and spaced from the closed end of the guide by $^1/_4$ guide wavelength. The length of the feed should be two to three guide wavelengths. The latter is preferred if a second probe is to be mounted for polarization change or for polaplexer work where duplex communication (simultaneous transmission and reception) is possible because of the isolation between two properly located and oriented probes. The second probe for polarization switching or polaplexer work should be spaced $^3/_4$ guide wavelength from the closed end and mounted at right angles to the first probe.

The feed aperture is located at the focal point of the dish and aimed at the center of the reflector. The feed mounts should permit adjustment of the aperture either side of the focal point and should present a minimum of blockage to the reflector. Correct distance to the dish center places the focal point about 1 inch inside the feed aperture. The use of a nonmetallic support minimizes blockage. PVC pipe, fiberglass and Plexiglas are commonly used materials. A simple test by placing a material in a microwave oven reveals if it is satisfactory up to 2450 MHz. PVC pipe has tested satisfactorily and appears to work well at 2300 MHz. A simple, clean looking mount for a 4-foot dish with 18 inches focal length, for example, can be made by mounting a length of 4-inch PVC pipe using a PVC flange at the center of the dish. At 2304 MHz the circular feed is approximately 4 inches ID, making a snug fit with the PVC pipe. Precautions should be taken to keep rain and small birds from entering the feed.

Never look into the open end of a waveguide when power is applied, or stand directly in front of a dish while transmitting. Tests and adjustments in these areas should be done while receiving or at extremely low levels of transmitter power (less than 0.1 watt). The US Government has set a limit of 10 mW/cm^2 averaged over a 6-minute period as the safe maximum. Other authorities believe even lower levels should be used. Destructive thermal heating of body tissue results from excessive exposure. This heating effect is especially dangerous to the eyes. The accepted safe level of 10 mW/cm^2 is reached in the near field of a parabolic antenna if the level at $2D^2/\lambda$ is 0.242 mW/cm^2. The equation for power density at the far-field boundary is

$$\text{Power density} = \frac{137.8\,P}{D^2}\ \text{mW/cm}^2 \qquad (\text{Eq } 7)$$

where
   P = average power in kilowatts
   D = antenna diameter in feet
   λ = wavelength in feet

New commercial dishes are expensive, but surplus ones can often be purchased at low cost. Some amateurs build theirs, while others modify UHF TV dishes or circular metal snow sleds for the amateur bands. **Fig 27** shows a dish using the homemade feed just described.

Fig 27—Coffee-can 2304 MHz feed described in text and Fig 26 mounted on a 4-ft dish.

Fig 29—Detailed look at the hub assembly for the ZL1BJQ dish. Most of the structural members are made from ¾-inch T section.

Fig 28—Aluminum framework for a 23-foot dish under construction by ZL1BJQ.

Photos showing a highly ambitious dish project under construction by ZL1BJQ appear in **Figs 28** and **29**. Practical details for constructing this type of antenna are given in Chapter 19. Dick Knadle, K2RIW, described modern UHF antenna test procedures in February 1976 *QST* (see Bibliography). Also see Chapter 19.

OMNIDIRECTIONAL ANTENNAS FOR VHF AND UHF

Local work with mobile stations requires an antenna with wide coverage capabilities. Most mobile work is on FM, and the polarization used with this mode is generally vertical. Some simple vertical systems are described below. Additional material on antennas of this type is presented in Chapter 16, Mobile and Maritime Antennas.

Ground-plane Antennas for 144, 222 and 440 MHz

For the FM operator living in the primary coverage area of a repeater, the ease of construction and low cost of a $^1/_4$ λ ground-plane antenna make it an ideal choice. Three different types of construction are detailed in Figs 30 through 43; the choice of construction method depends upon the materials at hand and the desired style of antenna mounting.

The 144-MHz model shown in **Fig 30** uses a flat piece of sheet aluminum, to which radials are connected with machine screws. A 45° bend is made in each of the radials. This bend can be made with an ordinary bench vise. An SO239 chassis connector is mounted at the center of the aluminum plate with the threaded part of the connector facing down. The vertical portion of the

Fig 30—These drawings illustrate the dimensions for the 144-MHz ground-plane antenna. The radials are bent down at a 45° angle.

Fig 31—Dimensional information for the 222-MHz ground-plane antenna. Lengths for A, B, C and D are the total distances measured from the center of the SO-239 connector. The corners of the aluminum plate are bent down at a 45° angle rather than bending the aluminum rod as in the 144-MHz model. Either method is suitable for these antennas.

Frequency (MHz)	A (Inches)	B (Inches)
146	19 -5/16″	18 -11/16″
225	12 -5/8″	12″
445	6 -3/8″	5 -3/4″

**Fig 32—Simple ground-plane antenna for the 144-, 222-
and 440-MHz bands. The vertical element and radials
are ³/₃₂- or ¹/₁₆-in. brass welding rod. Although ³/₃₂-in. rod
is preferred for the 144-MHz antenna, #10 or #12
copper wire can also be used.**

**Fig 33—A 440-MHz ground-plane constructed using
only an SO-239 connector, no. 4-40 hardware and
¹/₁₆-in. brass welding rod.**

antenna is made of #12 copper wire soldered directly to the center pin of the SO-239 connector.

The 222-MHz version, **Fig 31**, uses a slightly different technique for mounting and sloping the radials. In this case the corners of the aluminum plate are bent down at a 45° angle with respect to the remainder of the plate. The four radials are held to the plate with machine screws, lock washers and nuts. A mounting tab is included in the design of this antenna as part of the aluminum base. A compression type of hose clamp could be used to secure the antenna to a mast. As with the 144-MHz version, the vertical portion of the antenna is soldered directly to the SO-239 connector.

A very simple method of construction, shown in **Figs 32** and **33**, requires nothing more than an SO-239

connector and some no. 4-40 hardware. A small loop formed at the inside end of each radial is used to attach the radial directly to the mounting holes of the coaxial connector. After the radial is fastened to the SO-239 with no. 4-40 hardware, a large soldering iron or propane torch is used to solder the radial and the mounting hardware to the coaxial connector. The radials are bent to a 45° angle and the vertical portion is soldered to the center pin to complete the antenna. The antenna can be mounted by passing the feed line through a mast of ¾-inch ID plastic or aluminum tubing. A compression hose clamp can be used to secure the PL-259 connector, attached to the feed line, in the end of the mast. Dimensions for the 144-, 222- and 440-MHz bands are given in Fig 32.

If these antennas are to be mounted outside it is wise to apply a small amount of RTV sealant or similar material around the areas of the center pin of the connector to prevent the entry of water into the connector and coax line.

The J-Pole Antenna

The J-Pole is a half-wave antenna that is end-fed at its bottom. Since the radiator is longer than that of a $1/4$-wave ground-plane antenna, the vertical lobe is compressed down toward the horizon and it has about 1.5 dB of gain compared to the ground-plane configuration. The stub-matching section used to transform the high impedance seen looking into a half-wave to 50 Ω coax is shorted at the bottom, making the antenna look like the letter "J," and giving the antenna its name.

Rigid copper tubing, fittings and assorted hardware can be used to make a really rugged J-pole antenna for 2 meters. When copper tubing is used, the entire assembly can be soldered together, ensuring electrical integrity, and making the whole antenna weatherproof. This

Fig 34—At A, exploded assembly diagram of all-copper J-Pole antenna. At B, detail of clamp assemblies. Both clamp assemblies are the same.

Item	Qty	Part or Material Name
1	1	¾-inch × 10 foot length of rigid copper tubing (enough for 2 antennas, 60 inches per antenna)
2	1	½-inch × 10 ft length of rigid copper tubing (enough for 6 antennas, 20 inches per antenna)
3	2	¾-inch copper pipe clamps
4	2	½-inch copper pipe clamps
5	1	½-inch copper elbow
6	1	¾ × ½-inch copper tee
7	1	¾-inch copper end cap
8	1	½-inch copper end cap
9	1	½ × 1¼-inch copper nipple (Make from item 2. See text)
10	1	¾ × 3 ¼-inch copper nipple (Make from item 1. See text)
11	1	Your choice of coupling to mast fitting (¾ × 1 inch NPT used at KD8JB)
12	6	# 8-32 × ½-inch brass machine screws (round, pan, or binder head)
13	6	# 8 brass flat washers
14	6	# 8-32 brass hex nuts

material came from an article by Michael Hood, KD8JB, in *The ARRL Antenna Compendium, Vol. 4*.

No special hardware or machined parts are used in this antenna, nor are insulating materials needed, since the antenna is always at dc ground. Best of all, even if the parts aren't on sale, the antenna can be built for less than $15. If you only build one antenna, you'll have enough tubing left over to make most of a second antenna.

Construction

Copper and brass is used exclusively in this antenna. These metals get along together, so dissimilar metal corrosion is eliminated. Both metals solder well, too. See **Fig 34**. Cut the copper tubing to the lengths indicated. Item 9 is a $1^1/_4$-inch nipple cut from the 20-inch length of $^1/_2$-inch tubing. This leaves $18^3/_4$ inches for the $^1/_4$-matching stub. Item 10 is a $3^1/_4$-inch long nipple cut from the 60-inch length of $^3/_4$-inch tubing. The $^3/_4$-wave element should measure $56^3/_4$-inches long. Remove burrs from the ends of the tubing after cutting, and clean the mating surfaces with sandpaper, steel wool, or emery cloth.

After cleaning, apply a very thin coat of flux to the mating elements and assemble the tubing, elbow, tee, end caps and stubs. Solder the assembled parts with a propane torch and rosin-core solder. Wipe off excess solder with a damp cloth, being careful not to burn yourself. The copper tubing will hold heat for a long time after you've finished soldering. After soldering, set the assembly aside to cool.

Flatten one each of the $^1/_2$-inch and $^3/_4$-inch pipe clamps. Drill a hole in the flattened clamp as shown in Fig 34A. Assemble the clamps and cut off the excess metal from the flattened clamp using the unmodified clamp as a template. Disassemble the clamps.

Assemble the $^1/_2$-inch clamp around the $^1/_4$-wave element and secure with two of the screws, washers, and nuts as shown in Fig 34B. Do the same with the $^3/_4$-inch clamp around the $^3/_4$-wave element. Set the clamps initially to a spot about 4 inches above the bottom of the "J" on their respective elements. Tighten the clamps only finger tight, since you'll need to move them when tuning.

Tuning

The J-Pole can be fed directly from 50-Ω coax through a choke balun (3 turns of the feed coax rolled into a coil about 8 inches in diameter and held together with electrical tape). Before tuning, mount the antenna vertically, about 5 to 10 feet from the ground. A short TV mast on a tripod works well for this purpose. When tuning VHF antennas, keep in mind that they are sensitive to nearby objects—such as your body. Attach the feed line to the clamps on the antenna, and make sure all the nuts and screws are at least finger tight. It really doesn't matter to which element (¾-wave element or stub) you attach the coaxial center lead. The author has done it both ways with no variation in performance. Tune the antenna by moving the two feed-point clamps equal distances a small amount each time until the SWR is minimum at the desired frequency. The SWR will be close to 1:1.

Final Assembly

The final assembly of the antenna will determine its long-term survivability. Perform the following steps with care. After adjusting the clamps for minimum SWR, mark the clamp positions with a pencil and then remove the feed line and clamps. Apply a very thin coating of flux to the inside of the clamp and the corresponding surface of the antenna element where the clamp attaches. Install the clamps and tighten the clamp screws.

Solder the feed line clamps where they are attached to the antenna elements. Now, apply a small amount of solder around the screw heads and nuts where they contact the clamps. Don't get solder on the screw threads! Clean away excess flux with a non-corrosive solvent. After final assembly and erecting/mounting the antenna in the desired location, attach the feed line and secure with the remaining washer and nut. Weather-seal this joint with RTV. Otherwise, you may find yourself repairing the feed line after a couple years.

On-the-Air Performance

Years ago, prior to building the first J-Pole antenna for this station, the author used a standard $^1/_4$-wave ground plane vertical antenna. While he had no problem working various repeaters around town with a $^1/_4$-wave antenna, simplex operation left a lot to be desired. The J-Pole performs just as well as a Ringo Ranger, and significantly better than the $^1/_4$-wave ground-plane vertical.

Practical 6-Meter Yagis

Boom length often proves to be the deciding factor when one selects a Yagi design. **Table 6** shows three 6-meter Yagis designed for convenient boom lengths (6, 12 and 22 feet). The 3-element, 6-foot boom design has 8.0 dBi gain in free space; the 12 foot boom, 5-element version has 10.1 dBi gain, and the 22-foot, 7 element Yagi has a gain of 11.3 dBi. All antennas exhibit better than 22 dB front-to-rear ratio and cover 50 to 51 MHz with better than 1.7:1 SWR.

Half-element lengths and spacings are given in the table. Elements can be mounted to the boom as shown in **Fig 35**. Two muffler clamps hold each aluminum plate to the boom, and two U bolts fasten each element to the plate,

Fig 35—The element to boom clamp. U bolts are used to hold the element to the plate, and 2-in. galvanized muffler clamps hold the plates to the boom.

which is 0.25 inches thick and 4 × 4 inches square. Stainless steel is the best choice for hardware, however, galvanized hardware can be substituted. Automotive muffler clamps do not work well in this application, because they are not galvanized and quickly rust once exposed to the weather. Please note that the element lengths shown in Table 6 are half the overall element lengths. See page 20-7 to 20-11 in Chapter 20 for practical details of telescoping aluminum elements.

The driven element is mounted to the boom on a Bakelite or G-10 fiberglass plate of similar dimension to the other mounting plates. A 12-inch piece of Plexiglas rod is inserted into the driven element halves. The Plexiglas allows the use of a single clamp on each side of the element and also seals the center of the elements against moisture. Self-tapping screws are used for electrical connection to the driven element.

Refer to **Fig 36** for driven-element and hairpin match details. A bracket made from a piece of aluminum is used to mount the three SO239 connectors to the driven element plate. A 4:1 transmission-line balun connects the two element halves, transforming the 200 Ω resistance at the hairpin match to 50 Ω at the center connector. Note

Fig 36—This shows how the driven element and feed system are attached to the boom. The phasing line is coiled and taped to the boom. The center of the hairpin loop may be connected to the boom electrically and mechanically if desired.
Phasing-line lengths:
For cable with 0.80 velocity factor – 7 ft, 10³/₈ in.
For cable with 0.66 velocity factor – 6 ft, 5³/₄ in.

Table 6
Optimized 6-Meter Yagi Designs

	Spacing Between Elements inches	Seg 1 OD* Length inches	Seg2 OD* Length inches	Midband Gain F/R
306-06				
OD		0.750	0.625	
Refl.	0	36	23.500	7.9 dBi
D.E.	24	36	16.000	27.2 dB
Dir. 1	66	36	15.500	
506-12				
OD		0.750	0.625	
Refl.	0	36	24.000	10.1 dBi
D.E.	24	36	17.125	24.7 dB
Dir. 1	12	36	19.375	
Dir. 2	44	36	18.250	
Dir. 3	58	36	15.375	

	Spacing Between Elements inches	Seg 1 OD* Length inches	Seg2 OD* Length inches	Midband Gain F/R
706-22				
OD		0.750	0.625	
Refl.	0	36	25.000	11.3 dBi
D.E.	27	36	17.250	29.9 dB
Dir. 1	16	36	18.500	
Dir. 2	51	36	15.375	
Dir. 3	54	36	15.875	
Dir. 4	53	36	16.500	
Dir. 5	58	36	12.500	

*See pages 20-7 to 20-11 for telescoping aluminum tubing details.

that the electrical length of the balun is λ/2, but the physical length will be shorter due to the velocity factor of the particular coaxial cable used. The hairpin is connected directly across the element halves. The exact center of the hairpin is electrically neutral and should be fastened to the boom. This has the advantage of placing the driven element at dc ground potential.

The hairpin match requires no adjustment as such. However, you may have to change the length of the driven element slightly to obtain the best match in your preferred portion of the band. Changing the driven-element length will not adversely affect antenna performance. *Do not adjust the lengths or spacings of the other elements—they are optimized already*. If you decide to use a gamma match, add 3 inches to each side of the driven element lengths given in the table for all antennas.

High-Performance Yagis for 144, 222 and 432 MHz

This construction information is presented as an introduction to the three high-performance VHF/UHF Yagis that follow. All were designed and built by Steve Powlishen, K1FO. For years the design of long Yagi antennas seemed to be a mystical black art. The problem of simultaneously optimizing 20 or more element spacings and element lengths presented an almost unsolvable set of simultaneous equations. With the unprecedented increase in computer power and widespread availability of antenna analysis software, we are now able to quickly examine many Yagi designs and determine which approaches work and which designs to avoid.

At 144 MHz and above, most operators desire Yagi antennas two or more wavelengths in length. This length (2λ) is where most classical designs start to fall apart in terms of gain per boom length, bandwidth and pattern quality. Extensive computer and antenna range analysis has proven that the best possible design is a Yagi that has both varying element spacings and varying element lengths.

This design approach starts with closely spaced directors. The director spacings gradually increase until a constant spacing of about 0.4 λ is reached. Conversely, the director lengths start out longest with the first director and decrease in length in a decreasing rate of change until they are virtually constant in length. This method of construction results in a wide gain bandwidth. A bandwidth of 7% of the center frequency at the −1 dB forward-gain points is typical for these Yagis even when they are longer than 10 λ. The log-taper design also reduces the rate of change in driven-element impedance vs frequency. This allows the use of simple dipole driven elements while still obtaining acceptable driven-element SWR over a wide frequency range. Another benefit is that the resonant frequency of the Yagi changes very little as the boom length is increased.

The driven-element impedance also changes moderately with boom length. The tapered approach creates a Yagi with a very clean radiation pattern. Typically, first side lobe levels of ~17 dB in the E plane, ~15 dB in the H plane, and all other lobes at ~20 dB or more are possible on designs from 2 λ to more than 14 λ.

The actual rate of change in element lengths is determined by the diameter of the elements (in wavelengths). The spacings can be optimized for an individual boom length or chosen as a best compromise for most boom lengths.

The gain of long Yagis has been the subject of much debate. Recent measurements and computer analysis by both amateurs and professionals indicates that given an optimum design, doubling a Yagi's boom length will result in a maximum theoretical gain increase of about 2.6 dB. In practice, the real gain increase may be less because of escalating resistive losses and the greater possibility of construction error. **Fig 37** shows the maximum possible gain per boom length expressed in decibels, referenced to an isotropic radiator. The actual number of directors does not play an important part in determining the gain vs boom length as long as a reasonable number of directors are used. The use of more directors per boom length will normally give a wider gain bandwidth, however, a point exists where too many directors will adversely affect all performance aspects.

While short antennas (< 1.5 λ) may show increased gain with the use of quad or loop elements, long Yagis (> 2 λ) will not exhibit measurably greater forward gain or pattern integrity with loop-type elements. Similarly, loops used as driven elements and reflectors will not significantly change the properties of a long log-taper Yagi. Multiple-dipole driven-element assemblies will also not result in any significant gain increase per given boom length when compared to single-dipole feeds.

Once a long-Yagi director string is properly tuned, the reflector becomes relatively non critical. Reflector spacings between 0.15 λ and 0.2 λ are preferred. The spacing can be chosen for best pattern and driven element impedance. Multiple-reflector arrangements will not significantly increase the forward gain of a Yagi which has its directors properly optimized for forward gain. Many multiple-reflector schemes such as tri-reflectors and corner reflectors have the disadvantage of lowering the driven element impedance compared to a single optimum-length reflector. The plane or grid reflector, shown in **Fig 38**, may however reduce the intensity of unwanted rear lobes. This can be used to reduce noise pickup on EME or satellite arrays. This type of reflector will usually increase the driven-element impedance compared to a single reflector. This sometimes makes driven-element matching easier. Keep in mind that even for EME, a plane reflector will add considerable wind load and weight for

Fig 37—This chart shows maximum gain per boom length for optimally designed long Yagi antennas.

Fig 38—Front and side views of a plane-reflector antenna.

only a few tenths of a decibel of receive signal-to-noise improvement.

Yagi Construction

Normally, aluminum tubing or rod is used for Yagi elements. Hard-drawn enamel-covered copper wire can also be used on Yagis above 420 MHz. Resistive losses are inversely proportional to the square of the element diameter and the square root of its conductivity.

Element diameters of less than $^3/_{16}$ inch or 4 mm should not be used on any band. The size should be chosen for reasonable strength. Half-inch diameter is suitable for 50 MHz, $^3/_{16}$ to $^3/_8$ inch for 144 MHz and $^3/_{16}$ inch is recommended for the higher bands. Steel, including stainless steel and unprotected brass or copper wire, should not be used for elements.

Boom material may be aluminum tubing, either square or round. High-strength aluminum alloys such as 6061-T6 or 6063-T651 offer the best strength-to-weight advantages. Fiberglass poles have been used (where available as surplus). Wood is a popular low-cost boom material. The wood should be well seasoned and free from knots. Clear pine, spruce and Douglas fir are often used. The wood should be well treated to avoid water absorption and warping.

Elements may be mounted insulated or uninsulated, above or through the boom. Mounting uninsulated elements through a metal boom is the least desirable method unless the elements are welded in place. The Yagi elements will oscillate, even in moderate winds. Over several years this element oscillation will work open the boom holes. This will allow the elements to move in the boom. This will create noise (in your receiver) when the wind blows, as the element contact changes. Eventually the element-to-boom junction will corrode (aluminum oxide is a good insulator). This loss of electrical contact between the boom and element will reduce the boom's effect and change the resonant frequency of the Yagi.

Noninsulated elements mounted above the boom will perform fine as long as a good mechanical connection is made. Insulating blocks mounted above the boom will also work, but they require additional fabrication. One of the most popular construction methods is to mount the elements through the boom using insulating shoulder washers. This method is lightweight and durable. Its main disadvantage is difficult disassembly, making this method of limited use for portable arrays.

If a conductive boom is used, element lengths must be corrected for the mounting method used. The amount of correction is dependent upon the boom diameter in

Fig 39—Yagi element correction vs boom diameter. Curve A is for elements mounted through a round or square conductive boom, with the elements in mechanical contact with the boom. Curve B is for insulated elements mounted through a conductive boom, and for elements mounted on top of a conductive boom (elements make electrical contact with the boom). The patterns were corrected to computer simulations to determine Yagi tuning. The amount of element correction is not affected by element diameter.

Fig 40—Measured E-plane pattern for the 22-element Yagi. Note: This antenna pattern is drawn on a linear dB grid, rather than on the standard ARRL log-periodic grid, to emphasize low sidelobes.

wavelengths. See **Fig 39**. Elements mounted through the boom and not insulated require the greatest correction. Mounting on top of the boom or through the boom on insulated shoulder washers requires about half of the through-the-boom correction. Insulated elements mounted at least one element diameter above the boom require no correction over the free-space length.

The three following antennas have been optimized for typical boom lengths on each band.

A HIGH-PERFORMANCE 432-MHz YAGI

This 22-element, 6.1-λ, 432-MHz Yagi was originally designed for use in a 12-Yagi EME array built by K1FO. A lengthy evaluation and development process preceded its construction. Many designs were considered and then analyzed on the computer. Next, test models were constructed and evaluated on a home-made antenna range. The resulting design is based on WlEJ's computer-optimized spacings.

The attention paid to the design process has been worth the effort. The 22-element Yagi not only has exceptional forward gain (17.9 dBi), but has an unusually clean radiation pattern. The measured E-plane pattern is

shown in **Fig 40**. Note that a 1-dB-per-division axis is used to show pattern detail. A complete description of the design process and construction methods appears in December 1987 and January 1988 *QST*.

Like other log-taper Yagi designs, this one can easily be adapted to other boom lengths. Versions of this Yagi have been built by many amateurs. Boom lengths ranged between 5.3 λ (20 elements) and 12.2 λ (37 elements).

The size of the original Yagi (169 inches long, 6.1 λ) was chosen so the antenna could be built from small-diameter boom material (7/8-inch and 1 inch round 6061-T6 aluminum) and still survive high winds and ice loading. The 22-element Yagi weighs about 3.5 pounds and has a wind load of approximately 0.8 square feet. This allows a high-gain EME array to be built with manageable wind load and weight. This same low wind load and weight lets the tropo operator add a high-performance 432-MHz array to an existing tower without sacrificing antennas on other bands.

Table 7 lists the gain and stacking specifications for the various length Yagis. The basic Yagi dimensions are shown in **Table 8**. These are free-space element lengths for 3/16-inch-diameter elements. Boom corrections for the element mounting method must be added in. The element-length correction column gives the length that must be added to keep the Yagi's center frequency optimized for use at 432 MHz. This correction is required to use the same spacing pattern over a wide range of boom lengths. Although any length Yagi will work well, this design is at its best when made with 18 elements or more (4.6 λ). Element material of less than 3/16-inch diameter is not recommended because resistive losses will reduce the gain by about 0.1 dB, and wet-weather performance will be worse.

Quarter-inch-diameter elements could be used if all elements are shortened by 3 mm. The element lengths are intended for use with a slight chamfer (0.5 mm) cut into the element ends. The gain peak of the array is centered at 437 MHz. This allows acceptable wet-weather performance, while reducing the gain at 432 MHz by only 0.05 dB.

The gain bandwidth of the 22-element Yagi is 31 MHz (at the –1 dB points). The SWR of the Yagi is less than 1.4: 1 between 420 and 440 MHz. **Fig 41** is a network analyzer plot of the driven-element SWR vs frequency. These numbers indicate just how wide the frequency response of a log-taper Yagi can be, even with a simple dipole driven element. In fact, at one antenna gain contest, some ATV operators conducted gain vs frequency measurements from 420 to 440 MHz. The 22-element Yagi beat all entrants including those with so-called broadband feeds.

To peak the Yagi for use on 435 MHz (for satellite use), you may want to shorten all the elements by 2 mm. To peak it for use on 438 MHz (for ATV applications), shorten all elements by 4 mm. If you want to use the Yagi

Table 7
Specifications for 432-MHz Yagi Family

No. of Ele.	Boom length(λ)	Gain (dBi)*	F/B ratio (dB)	DE imped (Ω)	Beamwidth E/H (°)	Stacking E/H (inches)
15	3.4	15.67	21	23	30/32	53/49
16	3.8	16.05	19	23	29/31	55/51
17	4.2	16.45	20	27	28/30	56/53
18	4.6	16.8	25	32	27/29	58/55
19	4.9	17.1	25	30	26/28	61/57
20	5.3	17.4	21	24	25.5/27	62/59
21	5.7	17.65	20	22	25/26.5	63/60
22	6.1	17.9	22	25	24/26	65/62
23	6.5	18.15	27	30	23.5/25	67/64
24	6.9	18.35	29	29	23/24	69/66
25	7.3	18.55	23	25	22.5/23.5	71/68
26	7.7	18.8	22	22	22/23	73/70
27	8.1	19.0	22	21	21.5/22.5	75/72
28	8.5	19.20	25	25	21/22	77/75
29	8.9	19.4	25	25	20.5/21.5	79/77
30	9.3	19.55	26	27	20/21	80/78
31	9.7	19.7	24	25	19.6/20.5	81/79
32	10.2	19.8	23	22	19.3/20	2/80
33	10.6	9.9	23	23	19/19.5	83/81
34	11.0	20.05	25	22	18.8/19.2	84/82
35	11.4	20.2	27	25	18.5/19.0	85/83
36	11.8	20.3	27	26	18.3/18.8	86/84
37	12.2	20.4	26	26	18.1/18.6	87/85
38	12.7	20.5	25	25	18.9/18.4	88/86
39	13.1	20.6	25	23	18.7/18.2	89/87
40	13.5	20.8	26	21	17.5/18	90/88

*Gain is approximate real gain based on gain measurements made on six different-length Yagis.

Table 8

Free-Space Dimensions for 432-MHz Yagi Family

*Element correction is the amount to shorten or lengthen all elements when building a Yagi of that length. Element lengths are for $^3/_{16}$-inch diameter material.

Ele. No.	Element Position (mm from reflector)	Element Length (mm)	Element Correction*
Refl	0	340	
DE	104	334	
D1	146	315	
D2	224	306	
D3	332	299	
D4	466	295	
D5	622	291	
D6	798	289	
D7	990	287	
D8	1196	285	
D9	1414	283	
D10	1642	281	−2
D11	1879	279	−2
D12	2122	278	−2
D13	2373	277	−2
D14	2629	276	−2
D15	2890	275	−1
D16	3154	274	−1
D17	3422	273	−1
D18	3693	272	0
D19	3967	271	0
D20	4242	270	0
D21	4520	269	0
D22	4798	269	0
D23	5079	268	0
D24	5360	268	+1
D25	5642	267	+1
D26	5925	267	+1
D27	6209	266	+1
D28	6494	266	+1
D29	6779	265	+2
D30	7064	265	+2
D31	7350	264	+2
D32	7636	264	+2
D33	7922	263	+2
D34	8209	263	+2
D35	8496	262	+2
D36	8783	262	+2
D37	9070	261	+3
D38	9359	261	+3

Fig 41—SWR performance of the 22-element Yagi in dry weather.

Fig 42—Element-mounting detail. Elements are mounted through the boom using plastic insulators. Stainless steel push-nut retaining rings hold the element in place.

on FM between 440 MHz and 450 MHz, shorten all the elements by 10 mm. This will provide 17.6 dBi gain at 440 MHz, and 18.0 dBi gain at 450 MHz. The driven element may have to be adjusted if the element lengths are shortened.

Although this Yagi design is relatively broadband, it is suggested that close attention be paid to copying the design exactly as built. Metric dimensions are used because they are convenient for a Yagi sized for 432 MHz.

Element holes should be drilled within ±2 mm. Element lengths should be kept within ±0.5 mm. Elements can be accurately constructed if they are first rough cut with a hack saw and then held in a vise and filed to the exact length.

The larger the array, the more attention you should pay to making all Yagis identical. Elements are mounted on shoulder insulators and run through the boom (see **Fig 42**). The element retainers are stainless-steel push nuts. These are made by several companies, including Industrial Retaining Ring Co in Irvington, New Jersey, and AuVeco in Ft Mitchell, Kentucky. Local industrial hardware distributors can usually order them for you. The element insulators

Fig 43—Several views of the driven element and T match.

340 mm

All Elements
3/16" Diam 6061-T6

Clamp,
0.030" Alum
3/8" Wide

62 mm

62 mm

15 mm

38 mm

38 mm

Solder
Lug

T Wire: 122 mm
Length of
No. 12 Wire

T Wire 140 mm Length of No. 12 Wire
Make STRAIGHT PORTION of
T Wire 122 mm Long; Form and
Solder to N-Connector

1"

Note: T Wires are Parallel to Driven Element

Balun: Make from UT-141 Copper-Shielded Coax

5 mm
Dielectric

233 mm
Shield

5 mm
Dielectric

19 mm

Centerline of Driven Element to Rear
Face of N-Connector Bracket

Solder

Centerline of
N Connector
Above Boom

15 mm

Balun

Side View

Solder Lug Attached to Bottom Screw
on Connector, Bent 90° and Soldered
to UT-141 Shield

Fig 44—Details of the driven element and T match for the 22-element Yagi. Lengths are given in millimeters to allow precise duplication of the antenna. See text.

Front Boom Section
7/8"OD × 0.049" Wall
6061-T6 Tubing
1530 mm (60-1/4") Long

Center Boom Section
1"OD × 0.058" Wall
6061-T6 Tubing

Double Up Boom Where Mast Clamp
Mounts. Use 12" of 7/8"OD × 0.049
6061-T6

NO. 8-32 Screw
(2 places)

Center Mast Clamp
Between D10 and D11

Slot and Use Hose
Clamp (2 places)

Rear Boom Section
7/8'OD × 0.049" Wall
6061-T6 Tubing
1580 mm (62-5/8")
Long

412 mm
(55-9/16")

1415 mm
(55-11/16")

1475 mm
(58-1/16")

4302 mm
(169-5/16")

BOOM LAYOUT

Fig 45—Boom-construction information for the 22-element Yagi Lengths are given in millimeters to allow precise duplication of the antenna. See text.

Fig 46—Boom-construction information for the 33-element Yagi. Lengths are given in millimeters to allow precise duplication of the antenna.

are not critical. Teflon or black polyethylene are probably the best materials. The Yagi in the photographs is made with black Delryn insulators, available from C3i in Washington, DC.

The driven element uses a UG-58A/U connector mounted on a small bracket. The UG58A/U should be the type with the press-in center pin. UG-58s with center pins held in by "C" clips will usually leak water. Some connectors use steel retaining clips, which will rust and leave a conductive stripe across the insulator. The T-match wires are supported by the UT-141 balun. RG-303/U or RG-142/U Tefloninsulated cable could be used if UT-141 cannot be obtained. **Fig 43A** and Fig 42B show details of the driven-element construction. Driven element dimensions are given in **Fig 44**.

Dimensions for the 22-element Yagi are listed in **Table 9**. **Fig 45** details the Yagi's boom layout. Element material can be either $^3/_{16}$ inch 6061-T6 aluminum rod or hard aluminum welding rod.

A 24-foot-long, 10.6-λ, 33-element Yagi was also built. The construction methods used were the same as the 22-element Yagi. Telescoping round boom sections of 1, $1^1/_8$, and $1^1/_4$ inches in diameter were used. A boom support is required to keep boom sag acceptable. At 432 MHz, if boom sag is much more than two or three inches, H-plane pattern distortion will occur. Greater amounts of boom sag will reduce the gain of a Yagi. **Table 10** lists the proper dimensions for the antenna when built with the previously given boom diameters. The boom layout is shown in **Fig 46**, and the driven element is described in **Fig 47**. The 33-element Yagi exhibits the same clean pattern traits as the 22-element Yagi (see **Fig 48**). Measured gain of the 33-element Yagi is 19.9 dBi at 432 MHz. A measured gain sweep of the 33-element Yagi gave a –1 dB gain bandwidth of 14 MHz with the –1 dB points at 424.5 MHz and 438.5 MHz.

A HIGH-PERFORMANCE 144MHZ YAGI

This 144MHz Yagi design uses the latest log-tapered element spacings and lengths. It offers near theoretical gain per boom length, an extremely clean pattern and wide bandwidth. The design is based upon the spacings used in a 4.5-λ 432-MHz computerdeveloped design by W1EJ. It is quite similar to the 432MHz Yagi described elsewhere in this chapter. Refer to that project for additional construction diagrams and photographs.

Mathematical models do not always directly translate into real working examples. Although the computer design provided a good starting point, the author, Steve Powlishen, K1FO, built several test models before the final working Yagi was obtained. This hands-on tuning included changing the element-taper rate in order to obtain the flexibility that allows the Yagi to be built with different boom lengths.

The design is suitable for use from 1.8 λ (10 elements) to 5.1 λ (19 elements). When elements are added to a Yagi, the center frequency, feed impedance and front-to-back ratio will range up and down. A modern tapered design will minimize this effect and allow the builder to select any desired boom length. This Yagi's design capabilities per boom length are listed in **Table 11**.

The gain of any Yagi built around this design will be within 0.1 to 0.2 dB of the maximum theoretical gain at the design frequency of 144.2 MHz. The design is intentionally peaked high in frequency (calculated gain peak is about 144.7 MHz). It has been found that by doing this, the SWR bandwidth and pattern at 144.0 to 144.3 MHz will be better, the Yagi will be less affected by weather and its performance in arrays will be more predictable. This design starts to drop off in performance if built with fewer than 10 elements. At less than 2 λ, more traditional designs perform well.

Table 12 gives free-space element lengths for $^1/_4$ inch-diameter elements. The use of metric notation allows for much easier dimensional changes during the design stage. Once you become familiar with the metric system, you'll probably find that construction is easier without the burden of cumbersome English fractional units. For $^3/_{16}$ inch-diameter elements, lengthen all parasitic elements by 3 mm. If $^3/_8$ inch diameter elements are used, shorten all of the

Table 9
Dimensions for the 22-Element 432-MHz Yagi

Element Number	Element Position (mm from reflector)	Element Length (mm)	Boom Diam (in)
Refl	30	346	
DE	134	340	
D1	176	321	
D2	254	311	7/8
D3	362	305	
D4	496	301	
D5	652	297	
D6	828	295	
D7	1020	293	
D8	1226	291	
D9	1444	289	
D10	1672	288	
D11	1909	286	
D12	2152	285	1
D13	2403	284	
D14	2659	283	
D15	2920	281	
D16	3184	280	
D17	3452	279	7/8
D18	3723	278	
D19	3997	277	
D20	4272	276	

Table 10
Dimensions for the 33-Element 432-MHz Yagi

Element Number	Element Position (mm from reflector)	Element Length (mm)	Boom Diam (in)
REF	30	348	
DE	134	342	
D1	176	323	
D2	254	313	
D3	362	307	
D4	496	303	1
D5	652	299	
D6	828	297	
D7	1020	295	
D8	1226	293	
D9	1444	291	
D10	1672	290	
D11	1909	288	
D12	2152	287	$1^1/_8$
D13	2403	286	
D14	2659	285	
D15	2920	284	
D16	3184	284	
D17	3452	283	
D18	3723	282	1¼
D19	3997	281	
D20	4272	280	
D21	4550	278	
D22	4828	278	
D23	5109	277	$1^1/_8$
D24	5390	277	
D25	5672	276	
D26	5956	275	
D27	6239	274	
D28	6524	274	1
D29	6809	273	
D30	7094	273	
D31	7380	272	

directors and the reflector by 6 mm. The driven element will have to be adjusted for the individual Yagi if the 12-element design is not adhered to.

For the 12-element Yagi, $^1/_4$-inch diameter elements were selected because smaller-diameter elements become rather flimsy at 2 meters. Other diameter elements can be used as described previously. The 2.5-λ boom was chosen because it has an excellent size and wind load vs gain and pattern trade-off. The size is also convenient; three 6-foot-long pieces of aluminum tubing can be used without any waste. The relatively large-diameter boom sizes ($1^1/_4$ and $1^3/_8$ inches) were chosen, as they provide an extremely rugged Yagi that does not require a boom support. The 12-element 17-foot-long design has a calculated wind survival of close to 120 mph! The absence of a boom support also makes vertical polarization possible.

Longer versions could be made by telescoping smaller-size boom sections into the last section. Some sort of boom support will be required on versions longer than 22 feet. The elements are mounted on shoulder insulators and mounted through the boom. However, elements may

Fig 47—Details of the driven element and T match for the 33-element Yagi. Lengths are given in millimeters to allow precise duplication of the antenna.

Table 11
Specifications for the 144-MHz Yagi Family

No. of Ele.	Boom Length(λ)	Gain (dBd)	DE Imped (Ω)	FB Ratio (dB)	Beamwidth E/H (°)	Stacking E/H (°)
10	1.8	11.4	27	17	39/42	10.2/9.5
11	2.2	12.0	38	19	36/40	11.0/10.0
12	2.5	12.5	28	23	34/37	11.7/10.8
13	2.9	13.0	23	20	32/35	12.5/11.4
14	3.2	13.4	27	18	31/33	12.8/12.0
15	3.6	13.8	35	20	30/32	13.2/12.4
16	4.0	14.2	32	24	29/30	13.7/13.2
17	4.4	14.5	25	23	28/29	14.1/13.6
18	4.8	14.8	25	21	27/28.5	14.6/13.9
19	5.2	15.0	30	22	26/27.5	15.2/14.4

be mounted, insulated or uninsulated, above or through the boom, as long as appropriate element length corrections are made. Proper tuning can be verified by checking the depth of the nulls between the main lobe and first side lobes. The nulls should be 5 to 10 dB below the first side-lobe level at the primary operating frequency. The boom layout for the 12-element model is shown in **Fig 49**. The actual corrected element dimensions for the 12-element 2.5-λ Yagi are shown in **Table 13**.

The design may also be cut for use at 147 MHz. There is no need to change element spacings. The element lengths should be shortened by 17 mm for best operation between 146 and 148 MHz. Again, the driven element will have to be adjusted as required.

The driven-element size ($1/2$-inch diameter) was chosen to allow easy impedance matching. Any reasonably sized driven element could be used, as long as appropriate length and T-match adjustments are made. Different

Table 12
Free-Space Dimensions for the 144-MHz Yagi Family
Element diameter is ¼ inch

Element No.	Element Position (mm from reflector)	Element Length
Refl.	0	1038
DE	312	955
D1	447	956
D2	699	932
D3	1050	916
D4	1482	906
D5	1986	897
D6	2553	891
D7	3168	887
D8	3831	883
D9	4527	879
D10	5259	875
D11	6015	870
D12	6786	865
D13	7566	861
D14	8352	857
D15	9144	853
D16	9942	849
D17	10744	845

driven-element dimensions are required if you change the boom length. The calculated natural driven-element impedance is given as a guideline. A balanced T-match was chosen because it's easy to adjust for best SWR and provides a balanced radiation pattern. A 4:1 half-wave coaxial balun is used, although impedance-transforming quarter-wave sleeve baluns could also be used. The cal-

Fig 48—E-plane pattern for the 33-element Yagi. This pattern is drawn on a linear dB grid scale, rather than the standard ARRL log-periodic grid, to emphasize low sidelobes.

Fig 49—Boom layout for the 12-element 144-MHz Yagi. Lengths are given in millimeters to allow precise duplication.

955 mm

83 mm 9.5 mm

No. 8 Screw
Nut and
Lockwasher

Driven Element 0.5" Dia (12.5 mm) × 0.035"
Wall Aluminum Tube

Shorting Strap
Make from
0.032" Aluminum

Attach Balun Ends
to T Bars

T Bars Supported on
3/4" High Delryn Insulators

40 mm

12.5 mm

Flatten Ends of
'T' Tubes

50 mm

381 mm

386 mm

T Bars
3/8" × 0.035"
Aluminum
Tubing

Inches = mm × 0.0394

Driven Element Detail 12—Element 144 MHz Yagi

(A)

Driven Element   Side View

Front of
Yagi

22 m

Material 0.062" Aluminum
Connector Bracket

3/4" Long × 3/8" Dia
Delryn Insulator

Balun Center Conductors
Attach to T Bars

Balun

Balun Shield is Grounded

Hole Pattern
for UG—58A/U

No. 19 Hole
(2 places)

32 mm

21 mm

42 mm

64 mm

22 mm

44 mm

7 mm

50 mm

64 mm

7 mm

No. 21 Hole for T Bar
Insulators (2 places)

(B)

Solder Lugs

Balun

Shield

Shield 664 mm

750 mm

Material: RG—142/U or RG—303/U Teflon—Insulated Coaxial Cable

Ant18—50

(C)

Fig 50—Driven-element detail for the 12-element 144-MHz Yagi. Lengths are given in millimeters to allow precise duplication.

Table 13
Dimensions for the 12-Element 2.5-λ Yagi

Element Number	Element Position (mm from reflector)	Element Length (mm)	Boom Diam (in)
Refl.	0	1044	
DE	312	955	
D1	447	962	1¼
D2	699	938	
D3	1050	922	
D4	1482	912	
D5	1986	904	
D6	2553	898	1³/₈
D7	3168	894	
D8	3831	889	
D9	4527	885	1¼
D10	5259	882	

Fig 51—H- and E-plane pattern for the 12-element 144-MHz Yagi.

Table 14
Free-Space Dimensions for the 222-MHz Yagi Family

Element diameter is ³/₁₆-inch.

Element No.	Element Position (mm from reflector)	Element Length (mm)
Refl.	0	676
DE	204	647
D1	292	623
D2	450	608
D3	668	594
D4	938	597
D5	1251	581
D6	1602	576
D7	1985	573
D8	2395	569
D9	2829	565
D10	3283	562
D11	3755	558
D12	4243	556
D13	4745	554
D14	5259	553
D15	5783	552
D16	6315	551
D17	6853	550
D18	7395	549
D19	7939	548
D20	8483	547

culated natural impedance will be useful in determining what impedance transformation will be required at the 200-Ω balanced feed point. Chapter 26, Coupling the Line to the Antenna, contains information on calculating folded-dipole and T-match driven-element parameters. A balanced feed is important for best operation on this antenna. Gamma matches can severely distort the pattern balance. Other useful driven-element arrangements are the Delta match and the folded dipole, if you're willing to sacrifice some flexibility. **Fig 50** details the driven-element dimensions.

A noninsulated driven element was chosen for mounting convenience. An insulated driven element may also be used. A grounded driven element may be less affected by static build-up. On the other hand, an insulated driven element allows the operator to easily check his feed lines for water or other contamination by the use of an ohmmeter from the shack.

Fig 51 shows computer-predicted E- and H-plane radiation patterns for the 12-element Yagi. The patterns are plotted on a l-dB-per-division linear scale instead of the usual ARRL polar-plot graph. This expanded scale plot is used to show greater pattern detail. The pattern for the 12-element Yagi is so clean that a plot done in the standard ARRL format would be almost featureless, except for the main lobe and first sidelobes.

The excellent performance of the 12-element Yagi is demonstrated by the reception of Moon echoes from several of the larger 144MHz EME stations with only one 12-element Yagi. Four of the 12-element Yagis will make an excellent starter EME array, capable of working many EME QSOs while being relatively small in size. The advanced antenna builder can use the information in Table 11 to design a dream array of virtually any size.

A HIGH-PERFORMANCE 222-MHz YAGI

Modern tapered Yagi designs are easily applied to 222 MHz. This design uses a spacing progression that is in between the 12-element 144-MHz design, and the 22-element 432-MHz design presented elsewhere in this chapter. The result is a design with maximum gain per boom length, a clean, symmetrical radiation pattern, and wide bandwidth. Although it was designed for weak-signal work (tropospheric scatter and EME), the design is

Table 15
Specifications for the 222-MHz Yagi Family

No of Ele.	Boom Length(λ)	Gain (dBd)	FB Ratio (dB)	DE Imped (Ω)	Beamwidth E/H (°)	Stacking E/H (feet)
12	2.4	12.3	22	23	37/39	7.1/6.7
13	2.8	12.8	19	28	33/36	7.8/7.2
14	3.1	13.2	20	34	32/34	8.1/7.6
15	3.5	13.6	24	30	30/33	8.6/7.8
16	3.9	14.0	23	23	29/31	8.9/8.3
17	4.3	14.35	20	24	28/30.5	9.3/8.5
18	4.6	14.7	20	29	27/29	9.6/8.9
19	5.0	15.0	22	33	26/28	9.9/9.3
20	5.4	15.3	24	29	25/27	10.3/9.6
21	5.8	15.55	23	24	24.5/26.5	10.5/9.8
22	6.2	15.8	21	23	24/26	10.7/10.2

suited to all modes of 222-MHz operation, such as packet radio, FM repeater operation and control links.

The spacings were chosen as the best compromise for a 3.9-λ 16-element Yagi. The 3.9-λ design was chosen, like the 12-element 144-MHz design, because it fits perfectly on a boom made from three 6-foot-long aluminum tubing sections. The design is quite extensible, and models from 12 elements (2.4 λ) to 22 elements (6.2 λ) can be built from the dimensions given in **Table 14**. Note that free-space lengths are given. They must be corrected for the element-mounting method. Specifications for various boom lengths are shown in **Table 15**.

Construction

Large-diameter ($1\frac{1}{4}$- and $1\frac{3}{8}$-inch diameter) boom construction is used, eliminating the need for boom supports. The Yagi can also be used vertically polarized. Three-sixteenths-inch-diameter aluminum elements are used. The exact alloy is not critical; 6061-T6 was used, but hard aluminum welding rod is also suitable. Quarter-inch-diameter elements could also be used if all elements

are shortened by 3 mm. Three-eighths-inch-diameter elements would require 10-mm shorter lengths. Elements smaller than $\frac{3}{16}$ inch-diameter are not recommended. The elements are insulated and run through the boom. Plastic shoulder washers and stainless steel retainers are used to hold the elements in place. The various pieces needed to build the Yagi may be obtained from C3i in Washington, DC. **Fig 52** details the boom layout for the 16-element Yagi. **Table 16** gives the dimensions for the 16-element Yagi as built. The driven element is fed with a T match and a 4:1 balun. See **Fig 53** for construction details. See the 432-MHz Yagi project elsewhere in this chapter for additional photographs and construction diagrams.

The Yagi has a relatively broad gain and SWR curve, as is typical of a tapered design, making it usable over a wide frequency range. The example dimensions are intended for use at 222.0 to 222.5 MHz. The 16-element Yagi is quite usable to more than 223 MHz. The best compromise for covering the entire band is to shorten all parasitic elements by 4 mm. The driven element will have to be adjusted in length for best match. The position of the T-wire shorting straps may also have to be moved.

The aluminum boom provides superior strength, is lightweight, and has a low wind-load cross section. Aluminum is doubly attractive, as it will long outlast wood and fiberglass. Using state-of-the-art designs, it is unlikely that significant performance increases will be achieved in the next few years. Therefore, it's in your best interest to build an antenna that will last many years. If suitable wood or fiberglass poles are readily available, they may be used without any performance degradation, at least when the wood is new and dry. Use the free-space element lengths given in Table 16 for insulated-boom construction.

The pattern of the 16-element Yagi is shown in **Fig 54**. Like the 144-MHz Yagi, a l-dB-per-division plot is used to detail the pattern accurately. This 16-element design makes a good building block for EME or tropo DX arrays. Old-style narrow-band Yagis often perform

Fig 52—Boom layout for the 16-element 222-MHz Yagi. Lengths are given in millimeters to allow precise duplication.

Table 16

Dimensions for 16-Element 3.9-λ 222-MHz Yagi

Element Number	Element Position (mm from reflector)	Element Length (mm)	Boom Diam (in)
Refl.	0	683	
DE	204	664	
D1	292	630	
D2	450	615	
D3	668	601	1 1/4
D4	938	594	
D5	1251	588	
D6	1602	583	
D7	1985	580	
D8	2395	576	
D9	2829	572	1 3/8
D10	3283	569	
D11	3755	565	
D12	4243	563	
D13	4745	561	1 1/4
D14	5259	560	

unpredictably when used in arrays. The theoretical 3.0-dB stacking gain is rarely observed. The 16-element Yagi (and other versions of the design) reliably provides stacking gains of nearly 3 dB. (The spacing dimensions listed in Table 15 show just over 2.9 dB stacking gain.) This has been found to be the best compromise between gain, pattern integrity and array size. Any phasing line losses will subtract from the possible stacking gain. Mechanical misalignment will also degrade the performance of an array.

(A)

(B)

Fig 54—H- and E-plane patterns for the 16-element 222-MHz Yagi at A. The driven-element T-match dimensions were chosen for the best SWR compromise between wet and dry weather conditions. The SWR vs frequency curve shown at B demonstrates the broad frequency response of the Yagi design.

Fig 53—Driven-element detail for the 16-element 222-MHz Yagi. Lengths are given in millimeters to allow precise duplication.

A 144 MHz 2-Element Quad

The basic 2-element quad array for 144 MHz is shown in **Fig 55**. The supporting frame is 1×1-inch wood, of any kind suitable for outdoor use. Elements are #8 aluminum wire. The driven element is 1λ (83 inches) long, and the reflector five percent longer (87 inches). Dimensions are not critical, as the quad is relatively broad in frequency response.

The driven element is open at the bottom, its ends fastened to a plastic block. The block is mounted at the bottom of the forward vertical support. The top portion of the element runs through the support and is held firmly by a screw running into the wood and then bearing on the aluminum wire. Feed is by means of 50-Ω coax, connected to the driven-element loop.

The reflector is a closed loop, its top and bottom portions running through the rear vertical support. It is held in position with screws at the top and bottom. The loop can be closed by fitting a length of tubing over the element ends, or by hammering them flat and bolting them together as shown in the sketch.

The elements in this model are not adjustable, though this can easily be done by the use of stubs. It would then be desirable to make the loops slightly smaller to compensate for the wire in the adjusting stubs. The driven element stub would be trimmed for length and the point of connection for the coax would be adjustable for best match. The reflector stub can be adjusted for maximum gain or maximum F/B ratio, depending on the builder's requirements.

In the model shown only the spacing is adjusted, and this is not particularly critical. If the wooden supports are made as shown, the spacing between the elements can be adjusted for best match, as indicated by an SWR meter connected in the coaxial line. The spacing

Fig 55—Mechanical details of a 2-element quad for 144 MHz. The driven element, L1, is one wavelength long; reflector L2 is 5% longer. With the transmission line connected as shown here, the resulting radiation is horizontally polarized. Sets of elements of this type can be stacked horizontally and vertically for high gain with broad frequency response. Recommended bay spacing is $^1/_2\ \lambda$ between adjacent element sides. The example shown may be fed directly with 50-Ω coax.

has little effect on the gain (from 0.15 to 0.25 λ), so the variation in impedance with spacing can be used for matching. This also permits use of either 50- or 75-Ω coax for the transmission line.

A Portable 144 MHz 4-Element Quad

Element spacing for quad antennas found in the literature ranges from 0.14 λ to 0.25 λ. Factors such as the number of elements in the array and the parameters to be optimized (F/B ratio, forward gain, bandwidth, etc), determine the optimum element spacing within this range. The 4-element quad antenna described here was designed for portable use, so a compromise between these factors was chosen. This antenna, pictured in **Fig 56**, was designed and built by Philip D'Agostino, W1KSC.

Based on several experimentally determined correction factors related to the frequency of operation and the wire size, optimum design dimensions were found to be as follows.

$$\text{Reflector length (ft)} = \frac{1046.8}{f_{MHz}} \qquad \text{(Eq 8)}$$

$$\text{Driven element (ft)} = \frac{985.5}{f_{MHz}} \qquad \text{(Eq 9)}$$

$$\text{Directors (ft)} = \frac{937.3}{f_{MHz}} \qquad \text{(Eq 10)}$$

Cutting the loops for 146 MHz provides satisfactory performance across the entire 144MHz band.

Fig 56—The 4-element 144-MHz portable quad, assembled and ready for operation. Sections of clothes closet poles joined with pine strips make up the mast. (*Photo by Adwin Rusczek, W1MPO*)

Fig 57—The complete portable quad, broken down for travel. Visible in the foreground is the driven element. The pine box in the background is a carrying case for equipment and accessories. A hole in the lid accepts the mast, so the box doubles as a base for a short mast during portable operation. (*W1MPO photo*)

Materials

The quad was designed for quick and easy assembly and disassembly, as illustrated in **Fig 57**. Wood (clear trim pine) was chosen as the principal building material because of its light weight, low cost, and ready availability. Pine is used for the boom and element supporting arms. Round wood clothes closet poles comprise the mast material. Strips connecting the mast sections are made of heavier pine trim. Elements are made of no. 8 aluminum wire. Plexiglas is used to support the feed point. **Table 17** lists the hardware and other parts needed to duplicate the quad.

Construction

The elements of the quad are assembled first. The mounting holes in the boom should be drilled to accommodate $1^1/_2$ inch no. 8 hardware. Measure and mark the locations where the holes are to be drilled in the element spreaders, **Fig 58**. Drill the holes in the spreaders just

Table 17

Parts List for the 144 MHz 4-element Quad

Boom: $3/_4 \times 3/_4 \times 48$-in. pine

Driven element support (spreader):
  $1/_2 \times 3/_4 \times 21^1/_4$ in. pine

Driven element feed point strut: $1/_2 \times 3/_4 \times 7^1/_2$ in. pine

Reflector support (spreader): $1/_2 \times 3/_4 \times 22^1/_2$ in. pine

Director supports (spreaders):
  $1/_2 \times 3/_4 \times 20^1/_4$ in. pine, 2 req'd

Mast brackets: $3/_4 \times 1^1/_2 \times 12$ in. heavy pine trim, 4 req'd

Boom to mast bracket: $1/_2 \times 1^5/_8 \times 5$ in. pine

Element wire: Aluminum ground wire
  (Radio Shack no. 15-035)

Wire clamps: $1/_4$in. electrician's copper or zinc plated
  steel clamps, 3 req'd

Boom hardware:
  6 no. 8-32 $\times$ $1^1/_2$ in. stainless steel machine screws
  6 no. 8-32 stainless steel wing nuts
  12 no. 8 stainless steel washers

Mast hardware:
  8 hex bolts, $1/_4$-20 $\times$ $3^1/_2$ in.
  8 hex nuts, $1/_4$-20
  16 flat washers

Mast material: $1^5/_{16}$ in. $\times$ 6 ft wood clothes closet poles,
  3 req'd

Feed point support plate: $3^1/_2 \times 2^1/_2$ in. Plexiglas sheet

Wood preparation materials:
  Sandpaper, clear polyurethane, wax

Feed line: 52-W RG-8 or RG-58 cable

Feed line terminals: Solder lugs for no. 8 or larger
  hardware, 2 req'd

Miscellaneous hardware:
  4 small machine screws, nuts, washers; 2 flat-head
  wood screws

large enough to accept the #8 wire elements. It is important to drill all the holes straight so the elements line up when the antenna is assembled.

Construction of the wire elements is easiest if the directors are made first. A handy jig for bending the elements can be made from a piece of 2 × 3-inch wood cut to the side length of the directors. It is best to start with about 82 inches of wire for each director. The excess can be cut off when the elements are completed. (The total length of each director is 77 inches.) Two bends should initially be made so the directors can be slipped into the spreaders before the remaining corners are bent. See **Fig 59**. Electrician's copper-wire clamps can be used to join the wires after the final bends are made, and they facilitate adjustment of element length. The reflector is made the same way as the directors, but the total length is 86 inches.

The driven element, total length 81 inches, requires special attention, as the feed attachment point needs to be adequately supported. An extra hole is drilled in the driven element spreader to support the feed-point strut, as shown in **Fig 60**. A Plexiglas plate is used at the feed point to support the feed-point hardware and the feed line. The feed-point support strut should be epoxied to the spreader, and a wood screw used for extra mechanical strength.

For vertical polarization, locate the feed point in the center of one side of the driven element, as shown in Fig 60. Although this arrangement places the spreader supports at voltage maxima points on the four loop conductors, D'Agostino reports no adverse effects during operation. However, if the antenna is to be left exposed to the weather, the builder may wish to modify the design to provide support for the loops at current maxima points, such as shown in Fig 60. (The element of Fig 60 should be rotated 90° for horizontal polarization.)

Orient the driven element spreader so that it mounts properly on the boom when the antenna is assembled. Bend the driven element the same way as the reflector and directors, but do not leave any overlap at the feed point. The ends of the wires should be $^3/_4$ inch apart where they mount on the Plexiglas plate. Leave enough excess that small loops can be bent in the wire for attachment to the coaxial feed line with stainless steel hardware.

Drill the boom as shown in **Fig 61**. It is a good idea to use hardware with wing nuts to secure the element spreaders to the boom. After the boom is drilled, clean all the wood parts with denatured alcohol, sand them, and give them two coats of glossy polyurethane. After the polyurethane dries, wax all the wooden parts.

The boom to mast attachment is made next. Square the ends of a 6-foot section of clothes closet pole (a miter box is useful for this). Drill the center holes in both the boom

Fig 59—Illustration showing how the aluminum element wires are bent. The adjustment clamp and its location are also shown.

Fig 58—Dimensions for the pine element spreaders for the 144-MHz 4-element quad.

Fig 60—Layout of the driven element of the 144-MHz quad. The leads of the coaxial cable should be stripped to ½ in. and solder lugs attached for easy connection and disconnection. See text regarding impedance at loop support points.

Fig 61—Detail of the boom showing hole center locations and boom to mast connection points.

Fig 62—Boom to mast plate for the 144-MHz quad. The screw hole in the center of the plate should be countersunk so the wood screw attaching it to the mast does not interfere with the fit of the boom.

Fig 63—Mast coupling connector details for the portable quad. The plates should be drilled two at a time to ensure the holes line up.

Fig 64—Typical SWR curve for the 144MHz portable quad. The large wire diameter and the quad design provide excellent bandwidth.

attachment piece and one end of the mast section (**Fig 62**). Make certain that the mast hole is smaller than the flat-head screw to be used to ensure a snug fit. Accurately drill the holes for attachment to the boom as shown in Fig 62.

Countersink the hole for the flat-head screw to provide a smooth surface for attachment to the boom. Apply epoxy cement to the surfaces and screw the boom attachment piece securely to the mast section. One 6 foot mast is used for attachment to the other mast sections.

Two additional 6-foot mast sections are prepared next. This brings the total mast height to 18 feet. It is important to square the ends of each pole so the mast stands straight when assembled. Mast-section connectors are made of pine as shown in **Fig 63**. Using $3^{1}/_{2} \times {}^{1}/_{4}$-inch hex bolts, washers, and nuts, sections may be attached as needed, for a total height of 6, 12 or 18 feet. Drill the holes in two connectors at a time. This ensures good align-

ment of the holes. A drill press is ideal for this job, but with care a hand drill can be used if necessary.

Line up two mast sections end to end, being careful that they are perfectly straight. Use the predrilled connectors to maintain pole straightness, and drill through the poles, one at a time. If good alignment is maintained, a straight 18-foot mast section can be made. Label the connectors and poles immediately so they are always assembled in the same order.

When assembling the antenna, install all the elements on the boom before attaching the feed line. Connect the coax to the screw connections on the driven element support plate and run the cable along the strut to the boom. From there, the cable should be routed directly to the mast and down. Assemble the mast sections to the desired height. The antenna provides good performance, and has a reasonable SWR curve over the entire 144 MHz band (**Fig 64**).

Building Quagi Antennas

The Quagi antenna was designed by Wayne Overbeck, N6NB. He first published information on this antenna in 1977 (see Bibliography). There are a few tricks to Quagi building, but nothing very difficult or complicated is involved. In fact, Overbeck mass produced as many as 16 in one day. **Tables 18** and **19** give the dimensions for Quagis for various frequencies up to 446 MHz.

For the designs of Tables 18 and 19, the boom is *wood* or any other nonconductor (such as, fiberglass or Plexiglas). If a metal boom is used, a new design and new element lengths will be required. Many VHF antenna builders go wrong by failing to follow this rule: If the original uses a metal boom, use the same size and shape metal boom when you duplicate it. If it calls for a wood boom, use a nonconductor. Many amateurs dislike wood booms, but in a salt air environment they outlast aluminum (and surely cost less). Varnish the boom for added protection.

The 144-MHz version is usually built on a 14 foot, 1 × 3 inch boom, with the boom tapered to 1 inch at both ends. Clear pine is best because of its light weight, but construction grade Douglas fir works well. At 222 MHz the boom is under 10 feet long, and most builders use 1 × 2 or (preferably) $^3/_4 × 1^1/_4$ inch pine molding stock. At 432 MHz, except for long-boom versions, the boom should be $^1/_2$ inch thick or less. Most builders use strips of $^1/_2$-inch exterior plywood for 432 MHz.

The quad elements are supported at the current maxima (the top and bottom, the latter beside the feed point) with Plexiglas or small strips of wood. See **Fig 65**. The quad elements are made of #12 copper wire, commonly used in house wiring. Some builders may elect to use #10 wire on 144 MHz and #14 on 432 MHz, although this changes the resonant frequency slightly. Solder a type N connector (an SO-239 is often used at 144 MHz) at the midpoint of the driven element bottom side, and close the reflector loop.

Table 19

432MHz, 15-Element, Long Boom Quagi Construction Data

Element Lengths, Inches	Interelement Spacing, Inches
R—28	R-DE7
DE—26⁵/₈	DE-D1—5¹/₄
D1—11³/₄	D1-D2—11
D21—¹¹/₁₆	D2-D3—5⁷/₈
D3—11⁵/₈	D3-D4—8³/₄
D4—11⁹/₁₆	D4-D5—8³/₄
D5—11¹/₂	D5-D6—8³/₄
D6—11⁷/₁₆	D6-D7—12
D7—11³/₈	D7-D8—12
D8—11⁵/₁₆	D8-D9—11¹/₄
D9—11⁵/₁₆	D9-D10—11¹/₂
D10—11¹/₄	D10-D11—9³/₁₆
D11—11³/₁₆	D11-D12—12³/₈
D12—11¹/₈	D12-D13—1-³/₄
D13—11¹/₁₆	

Boom: 1 × 2in. × 12-ft Douglas fir, tapered to ⁵/₈ in. at both ends.
Driven element: #12 TW copper wire loop in square configuration, fed at bottom center with type N connector and 52-Ω coax.
Reflector: #12 TW copper wire loop, closed at bottom.
Directors: ¹/₈ in. rod passing through boom.

Table 18

Dimensions, Eight-Element Quagi

Element Lengths	144.5 MHz	147 MHz	Frequency 222 MHz	432 MHz	446 MHz
Reflector[1]	86⁵/₈"	85"	56³/₈"	28"	27¹/₈"
Driven[2]	82"	80"	53½"	26⁵/₈"	25⁷/₈"
Directors	35¹⁵/₁₆" to 35" in ³/₁₆" steps	35⁵/₁₆" to 34³/₈" in ³/₁₆" steps	23³/₈" to 23¾" in ¹/₈" steps	11¾" to 11⁷/₁₆" in ¹/₁₆" steps	11³/₈" to 11¹/₁₆" in ¹/₁₆" steps
Spacing					
R-DE	21"	20½"	13⁵/₈"	7"	6.8"
DE-D1	15¾"	15³/₈"	10¼"	5¼"	5.1"
D1-D2	33"	32½"	21½"	11"	10.7"
D2-D3	17½"	17¹/₈"	11³/₈"	5.85"	5.68"
D3-D4	26.1"	25⁵/₈"	17"	8.73"	8.46"
D4-D5	26.1"	25⁵/₈"	17"	8.73"	8.46"
D5-D6	26.1"	25⁵/₈"	17"	8.73"	8.46"
Stacking Distance Between Bays	11'	10' 10"	7' 1½"	3'7"	3' 5⁵/₈"

[1] All #12 TW (electrical) wire, closed loops.
[2] All #12 TW wire loops, fed at bottom.

The directors are mounted through the boom. They can be made of almost any metal rod or wire of about $1/8$-inch diameter. Welding rod or aluminum clothesline wire works well if straight. (The designer uses $1/8$-inch stainless-steel rod obtained from an aircraft surplus store.)

A TV type U bolt mounts the antenna on a mast. A single machine screw, washers and a nut are used to secure the spreaders to the boom so the antenna can be quickly "flattened" for travel. In permanent installations two screws are recommended.

Construction Reminders

Based on the experiences of Quagi builders, the following hints are offered. First, remember that at 432 MHz even a $1/8$-inch measurement error results in performance deterioration. Cut the loops and elements as carefully as possible. No precision tools are needed, but accuracy is nec-

Fig 65—A close-up view of the feed method used on a 432-MHz Quagi. This arrangement produces a low SWR and gain in excess of 13 dBi with a 4-ft 10-in. boom! The same basic arrangement is used on lower frequencies, but wood may be substituted for the Plexiglas spreaders. The boom is ½-in. exterior plywood.

essary. Also make sure to get the elements in the right order. The longest director goes closest to the driven element.

Finally, remember that a balanced antenna is being fed with an unbalanced line. Every balun the designer tried introduced more trouble in terms of losses than the feed imbalance caused. Some builders have tightly coiled several turns of the feed line near the feed point to limit line radiation. In any case, the feed line should be kept at right angles to the antenna. Run it from the driven element directly to the supporting mast and then up or down perpendicularly for best results.

QUAGIS FOR 1296 MHz

The Quagi principle has recently been extended to the 1296-MHz band, where good performance is extremely difficult to obtain from homemade conventional Yagis. **Fig 66** shows the construction and **Table 20** gives the design information for antennas with 10, 15 and 25 elements.

At 1296 MHz, even slight variations in design or building materials can cause substantial changes in performance. The 1296 MHz antennas described here work every time—but only if the same materials are used and the antennas are built *exactly* as described. This is not to discourage experimentation, but if modifications to these 1296-MHz antenna designs are contemplated, consider building one antenna as described here, so a reference is available against which variations can be compared.

The Quagis (and the cubical quad) are built on $1/4$-inch thick Plexiglas booms. The driven element and reflector (and also the directors in the case of the cubical quad) are made of insulated #18 AWG solid copper bell wire, available at hardware and electrical supply stores. Other types and sizes of wire work equally well, but the dimensions vary with the wire diameter. Even removing the insulation usually necessitates changing the loop lengths.

Quad loops are approximately square (**Fig 67**), although the shape is relatively uncritical. The element lengths, however, *are* critical. At 1296 MHz, variations

Fig 66—A view of the 10-element version of the 1296-MHz Quagi. It is mounted on a 30-in. Plexiglas boom with a 3 × 3-in. square of Plexiglas to support the driven element and reflector. Note how the driven element is attached to a standard UG-290 BNC connector. The elements are held in place with silicone sealing compound.

of $^1/_{16}$ inch alter the performance measurably, and a $^1/_8$ inch departure can cost several decibels of gain. The loop lengths given are *gross* lengths. Cut the wire to these lengths and then solder the two ends together. There is a $^1/_8$-inch overlap where the two ends of the reflector (and director) loops are joined, as shown in Fig 67.

The driven element is the most important of all. The #18 wire loop is soldered to a standard UG-290 chassis-mount BNC connector as shown in the photographs. This exact type of connector must be used to ensure unifor-

mity in construction. Any substitution may alter the driven element electrical length. One end of the 9$^1/_4$ inch driven loop is pushed as far as it can go into the center pin, and is soldered in that position. The loop is then shaped and threaded through small holes drilled in the Plexiglas support. Finally, the other end is fed into one of the four mounting holes on the BNC connector and soldered. In most cases, the best SWR is obtained if the end of the wire just passes through the hole so it is flush with the opposite side of the connector flange.

Table 20

Dimensions, 1296-MHz Quagi Antennas

Note: All lengths are gross lengths. See text and photos for construction technique and recommended overlap at loop junctions. All loops are made of #18 AWG solid-covered copper bell wire. The Yagi type directors are $^1/_{16}$-in. brass brazing rod. See text for a discussion of director taper.

Feed: Direct with 52-Ω coaxial cable to UG-290 connector at driven element; run coax symmetrically to mast at rear of antenna.

Boom: 1$^1/_4$-in. thick Plexiglas, 30 in. long for 10-element quad or Quagi and 48 in. long for 15-element Quagi; 84 in. for 25-element Quagi.

10-Element Quagi for 1296 MHz

Element	Length, Inches	Construction	Element	Interelement Spacing, In.
Reflector	9.5625	Loop	R-DE	2.375
Driven	9.25	Loop	DE-D1	2.0
Director 1	3.91	Brass rod	D1-D2	3.67
Director 2	3.88	Brass rod	D2-D3	1.96
Director 3	3.86	Brass rod	D3-D4	2.92
Director 4	3.83	Brass rod	D4-D5	2.92
Director 5	3.80	Brass rod	D5-D6	2.92
Director 6	3.78	Brass rod	D6-D7	4.75
Director 7	3.75	Brass rod	D7-D8	3.94
Director 8	3.72	Brass rod		

15-Element Quagi for 1296 MHz

The first 10 elements are the same lengths as above, but the spacing from D6 to D7 is 4.0 in.; 07 to D8 is also 4.0 in.

Director 9	3.70		D8-D9	3.75
Director 10	3.67		D9-D10	3.83
Director 11	3.64		D10-D11	3.06
Director 12	3.62		D11-D12	4.125
Director 13	3.59		D12-D13	4.58

25-Element Quagi for 1296 MHz

The first 15 elements use the same element lengths and spacings as the 15-element model. The additional directors are evenly spaced at 3.0-in. intervals and taper in length successively by 0.02 in. per element. Thus, D23 is 3.39 in.

Fig 67—These photos show the construction method used for the 1296-MHz quad type parasitic elements. The two ends of the #18 bell wire are brought together with an overlap of $^1/_8$ in. and soldered.

Loop Yagis for 1296 MHz

Described here are loop Yagis for the 1296-MHz band. The loop Yagi fits into the quad family of antennas, as each element is a closed loop with a length of approximately 1 λ. Several versions are described, so the builder can choose the boom length and frequency coverage desired for the task at hand. Mike Walters, G3JVL, brought the original loop-Yagi design to the amateur community in the 1970s. Since then, many versions have been developed with different loop and boom dimensions. Chip Angle, N6CA, developed the antennas shown here.

Three sets of dimensions are given. Good performance can be expected if the dimensions are carefully followed. Check all dimensions before cutting or drilling anything. The 1296-MHz version is intended for weak-signal operation, while the 1270-MHz version is optimized for FM and mode L satellite work. The 1283-MHz antenna provides acceptable performance from 1280 to 1300 MHz.

These antennas have been built on 6- and 12-foot booms. Results of gain tests at VHF conferences and by individuals around the country show the gain of the 6-foot model to be about 18 dBi, while the 12-foot version provides about 20.5 dBi. Swept measurements indicate that gain is about 2 dB down from maximum gain at ±30 MHz from the design frequency. The SWR, however, deteriorates within a few megahertz on the low side of the design center frequency.

The Boom

The dimensions given here apply only to a ¾-inch OD boom. If a different boom size is used, the dimensions must be scaled accordingly. Many hardware stores

Fig 68—Loop Yagi boom-to-mast plate details are given at A. At B, the mounting of the antenna to the mast is detailed. A boom support for long antennas is shown at C. The arrangement shown in D and E may be used to rear-mount antennas up to 6 or 7 ft long.

Fig 69—Boom drilling dimensions. These dimensions must be carefully followed and the same materials used if performance is to be optimum. Element spacings are the same for all directors after D6—use as many as necessary to fill the boom.

Fig 70—Parasitic elements for the loop Yagi are made from aluminum sheet, the driven element from copper sheet. The dimensions given are for ¼-in. wide by 0.0325-in. thick elements only. Lengths specified are hole to hole distances; the holes are located ¹/₈ in. from each element end.

Fig 71—Element-to-boom mounting details.

carry aluminum tubing in 6- and 8-foot lengths, and that tubing is suitable for a short Yagi. If a 12-foot antenna is planned, find a piece of more rugged boom material, such as 6061-T6 grade aluminum. Do not use anodized tubing. The 12foot antenna must have additional boom support to minimize boom sag. The 6 foot version can be rear mounted. For rear mounting, allow $4^1/_2$ inches of boom behind the last reflector to eliminate SWR effects from the support.

The antenna is attached to the mast with a gusset plate. This plate mounts at the boom center. See **Fig 68**. Drill the plate mounting holes perpendicular to the element mounting holes (assuming the antenna polarization is to be horizontal).

Elements are mounted to the boom with no. 4-40 machine screws, so a series of no. 33 (0.113inch) holes must be drilled along the center of the boom to accommodate this hardware. **Fig 69** shows the element spacings for different parts of the band. Dimensions should be followed as closely as possible.

Parasitic Elements

The reflectors and directors are cut from 0.032-inch thick aluminum sheet and are $^1/_4$ inch wide. **Fig 70** indicates the lengths for the various elements. These lengths apply only to elements cut from the specified material. For best results, the element strips should be cut with a shear. If the edges are left sharp, birds won't sit on the elements.

Drill the mounting holes as shown in Fig 70 after carefully marking their locations. After the holes are drilled, form each strap into a circle. This is easily done by wrapping the element around a round form. (A small juice can works well.)

Mount the loops to the boom with no. 4-40 × 1-inch machine screws, lock washers and nuts. See **Fig 71**. It is best to use only stainless steel or plated-brass hardware. Although the initial cost is higher than for ordinary plated-steel hardware, stainless or brass hardware will not rust and need replacement after a few years. Unless the antenna

is painted, the hardware will definitely deteriorate.

Driven Element

The driven element is cut from 0.032-inch copper sheet and is $^1/_4$ inch wide. Drill three holes in the strap as detailed in Fig 69. Trim the ends as shown and form the strap into a loop similar to the other elements. This antenna is like a quad; if the loop is fed at the top or bottom, it is horizontally polarized.

Driven element mounting details are shown in **Fig 72**. A mounting fixture is made from a $^1/_4$-20 × 1$^1/_4$ inch brass bolt. File the bolt head to a thickness of $^1/_8$ inch. Bore a 0.144-inch (no. 27 drill) hole lengthwise through the center of the bolt. A piece of 0.141 inch semi-rigid Hardline (UT-141 or equivalent) mounts through this hole and is soldered to the driven loop feed point. The point at which the UT-141 passes through the copper loop and brass mounting fixture should be left unsoldered at this time to allow for matching adjustments when the antenna is completed, although the range of adjustment is not very large.

The UT-141 can be any convenient length. Attach the connector of your choice (preferably type N). Use a short piece of low-loss RG-8 size cable (or $^1/_2$-inch Hardline) for the run down the boom and mast to the main feed line. For best results, the main feed line should be the lowest loss 50-Ω cable obtainable. Good $^7/_8$-inch Hardline has 1.5 dB of loss per 100 feet and virtually eliminates the need for remote mounting of the transmit converter or amplifier.

Tuning the Driven Element

If the antenna is built carefully to the dimensions given, the SWR should be close to 1:1. Just to be sure, check the SWR if you have access to test equipment. Be sure the signal source is clean, however; wattmeters respond to "dirty" signals and can give erroneous readings. If problems are encountered, recheck all dimensions. If they look good, a minor improvement may be realized by changing the shape of the driven element. Slight bending of reflector 2 may also improve the SWR. When the desired match has been obtained, solder the point where the UT-141 jacket passes through the loop and brass bolt.

Tips for 1296-MHz Antenna Installations

Construction practices that are common on lower fre-

Fig 72—Driven-element details. See Fig 70 and the text for additional information.

quencies cannot be used on 1296 MHz. This is the most important reason why all who venture to these frequencies are not equally successful. First, when a proven design is used, copy it exactly¾don't change *anything*. This is especially true for antennas.

Use the best feed line you can get. Here are some realistic measurements of common coaxial cables at 1296 MHz (loss per 100 feet).

RG-8, 213, 214: 11 dB
$^1/_2$ in. foam/copper Hardline: 4 dB
$^7/_8$ in. foam/copper Hardline: 1.5 dB

Mount the antennas to keep feed line losses to an absolute minimum. Antenna height is less important than keeping the line losses low. *Do not* allow the mast to pass through the elements, as is common on antennas for lower frequencies. Cut all U-bolts to the minimum length needed; $^1/_4$ λ at 1296 MHz is only a little over 2 inches. Avoid any unnecessary metal around the antenna.

Trough Reflectors for 432 and 1296 MHz

Dimensions are given in **Fig 73** for 432- and 1296-MHz trough reflectors. The gain to be expected is 16 dBi and 15 dBi, respectively. A very convenient arrangement, especially for portable work, is to use a metal hinge at each angle of the reflector. This permits the reflector to be folded flat for transit. It also permits experiments to be carried out with different apex angles.

A housing is required at the dipole center to prevent the entry of moisture and, in the case of the 432-MHz antenna, to support the dipole elements. The dipole may be moved in and out of the reflector to get either minimum SWR or, if this cannot be measured, maximum gain. If a two-stub tuner or other matching device is used, the dipole may be placed to give optimum gain and the match-ing device adjusted to give optimum match. In the case of the 1296-MHz antenna, the dipole length can be adjusted by means of the brass screws at the ends of the elements. Locking nuts are essential.

The reflector should be made of sheet aluminum for 1296 MHz, but can be constructed of wire mesh (with twists parallel to the dipole) for 432 MHz. To increase the gain by 3 dB, a pair of these arrays can be stacked so the reflectors are barely separated (to prevent the formation of a slot radiator by the edges). The radiating dipoles must then be fed in phase, and suitable feeding and matching must be arranged. A two-stub tuner can be used for matching either a single- or double-reflector system.

Dimensions in Inches

Band	A	p	q	r	w	t	u	v	Tube 1 Brass or Copper	Tube 2 Brass or Copper	Gain
432	120	100	50	7 – 1/2	60	6 – 1/2	1/4	12 – 3/4	1 – 1/2" ID 1/16" Wall	5/8" OD 1/16" Wall	16 dBi
1296	45	36	9 – 1/2	2 – 1/2	20	2 – 1/8	1/8	4 – 1/4	3/4" ID	3/8" OD 20 s.w.g.	15 dBi

Fig 73—Practical construction information for trough reflector antennas for 432 and 1296 MHz.

A Horn Antenna for 10 GHz

The horn antenna is the easiest antenna for the beginner on 10 GHz to construct. It can be made out of readily available flat sheet brass. Because it is inherently a broadband structure, minor constructional errors can be tolerated. The one drawback is that horn antennas become physically cumbersome at gains over about 25 dBi, but for most line-of-sight work this much gain is rarely necessary. This antenna was designed by Bob Atkins, KA1GT, and appeared in *QST* for April and May, 1987.

Horn antennas are usually fed by waveguide. When operating in its normal frequency range, waveguide propagation is in the TE_{10} mode. This means that the electric (E) field is across the short dimension of the guide and the magnetic (H) field is across the wide dimension. This is the reason for the E-plane and H-plane terminology shown in **Fig 74**.

There are many varieties of horn antennas. If the waveguide is flared out only in the H-plane, the horn is called an H-plane sectoral horn. Similarly, if the flare is only in the E-plane, an Eplane sectoral horn results. If the flare is in both planes, the antenna is called a pyramidal horn.

For a horn of any given aperture, directivity (gain along the axis) is maximum when the field distribution across the aperture is uniform in magnitude and phase. When the fields are not uniform, side lobes that reduce the directivity of the antenna are formed. To obtain a uniform distribution, the horn should be as long as possible with minimum flare angle. From a practical point of view, however, the horn should be as short as possible, so there is an obvious conflict between performance and convenience.

Fig 75 illustrates this problem. For a given flare angle and a given side length, there is a path-length difference from the apex of the horn to the center of the aperture (L), and from the apex of the horn to the edge of the aperture (L'). This causes a phase difference in the field across the aperture, which in turn causes formation of side lobes, degrading directivity (gain along the axis) of the antenna. If L is large this difference is small, and the field is almost uniform. As L decreases however, the phase difference increases and directivity suffers. An optimum (shortest possible) horn is constructed so that this phase difference is the maximum allowable before side lobes become excessive and axial gain markedly decreases.

The magnitude of this permissible phase difference is different for E-plane and H-plane horns. For the E-plane horn, the field intensity is quite constant across the aperture. For the H-plane horn, the field tapers to zero at the edge. Consequently, the phase difference at the edge of the aperture in the E-plane horn is more critical and should be held to less than 90° ($^1/_4$ λ). In an H-plane horn,

the allowable phase difference is 144° (0.4 λ). If the aperture of a pyramidal horn exceeds one wavelength in both planes, the Eplane and Hplane patterns are essentially independent and can be analyzed separately.

The usual direction for orienting the waveguide feed is with the broad face horizontal, giving vertical polarization. If this is the case, the H-plane sectoral horn has a narrow horizontal beamwidth and a very wide vertical beamwidth. This is not a very useful beam pattern for most amateur applications. The E-plane sectoral horn has a narrow vertical beamwidth and a wide horizontal beamwidth. Such a radiation pattern could be useful in a beacon system where wide coverage is desired.

The most useful form of the horn for general applications is the optimum pyramidal horn. In this configuration the two beamwidths are almost the same. The E-plane (vertical) beamwidth is slightly less than the H-plane (horizontal), and also has greater side lobe intensity.

Fig 74—10-GHz antennas are usually fed with waveguide. See text for a discussion of waveguide propagation characteristics.

Fig 75—The path-length (phase) difference between the center and edge of a horn antenna is δ.

Building the Antenna

A 10-GHz pyramidal horn with 18.5 dBi gain is shown in **Fig 76**. The first design parameter is usually the required gain, or the maximum antenna size. These are of course related, and the relationships can be approximated by the following:

L = H-plane length (λ) = 0.0654 × gain   (Eq 1)
A = H-plane aperture (λ) = 0.0443 × gain   (Eq 2)
B = E-plane aperture (λ) = 0.81 A   (Eq 3)

where

gain is expressed as a *ratio*; 20 dBi gain = 100
L, A and B are dimensions shown in **Fig 77.**

From these equations, the dimensions for a 20-dBi gain horn for 10.368 GHz can be determined. One wavelength at 10.368 GHz is 1.138 inches. The length (L) of such a horn is 0.0654 × 100 = 6.54 λ. At 10.368 GHz, this is 7.44 inches. The corresponding H-plane aperture (A) is 4.43 λ (5.04 inches), and the E-plane aperture (B), 4.08 inches.

The easiest way to make such a horn is to cut pieces from brass sheet stock and solder them together. Fig 77 shows the dimensions of the triangular pieces for the sides and a square piece for the waveguide flange. (A standard commercial waveguide flange could also be used.) Because the E-plane and H-plane apertures are different, the horn opening is not square. Sheet thickness is unimportant; 0.02 to 0.03 inch works well. Brass sheet is often available from hardware or hobby shops.

Note that the triangular pieces are trimmed at the apex to fit the waveguide aperture (0.9 × 0.4 inch). This necessitates that the length, from base to apex, of the smaller triangle (side B) is shorter than that of the larger (side A). Note that the length, S, of the two different sides of the horn must be the same if the horn is to fit together! For such a simple looking object, getting the parts to fit together properly requires careful fabrication.

The dimensions of the sides can be calculated with simple geometry, but it is easier to draw out templates on a sheet of cardboard first. The templates can be used to build a mock antenna to make sure everything fits together properly before cutting the sheet brass.

First, mark out the larger triangle (side A) on cardboard. Determine at what point its width is 0.9 inch and draw a line parallel to the base as shown in Fig 77. Measure the length of the side S; this is also the length of the sides of the smaller (side B) pieces.

Mark out the shape of the smaller pieces by first drawing a line of length B and then constructing a second line of length S. One end of line S is an end of line B, and the other is 0.2 inch above a line perpendicular to the center of line B as shown in Fig 76. (This procedure is much more easily followed than described.) These smaller pieces are made slightly oversize (shaded area in Fig 77) so you can construct the horn with solder seams on the outside of the horn during assembly.

Fig 76—This pyramidal horn has 18.5 dBi gain at 10 GHz. Construction details are given in the text.

Fig 77—Dimensions of the brass pieces used to make the 10-GHz horn antenna. Construction requires two of each of the triangular pieces (side A and side B).

Cut out two cardboard pieces for side A and two for side B and tape them together in the shape of the horn. The aperture at the waveguide end should measure 0.9 × 0.4 inch and the aperture at the other end should measure 5.04 × 4.08 inches.

If these dimensions are correct, use the cardboard templates to mark out pieces of brass sheet. The brass sheet should be cut with a bench shear if one is available, because scissors type shears tend to bend the metal. Jig the pieces together and solder them on the *outside* of the seams. It is important to keep both solder and rosin from contaminating the inside of the horn; they can absorb RF and reduce gain at these frequencies.

Assembly is shown in **Fig 78**. When the horn is completed, it can be soldered to a standard waveguide flange, or one cut out of sheet metal as shown in Fig 77. The transition between the flange and the horn must be smooth. This antenna provides an excellent performance-to-cost ratio (about 20 dBi gain for about five dollars in parts).

Fig 78—Assembly of the 10-GHz horn antenna.

Periscope Antenna Systems

One problem common to all who use microwaves is that of mounting an antenna at the maximum possible height while trying to minimize feed-line losses. The higher the frequency, the more severe this problem becomes, as feeder losses increase with frequency. Because parabolic dish reflectors are most often used on the higher bands, there is also the difficulty of waterproofing feeds (particularly waveguide feeds). Inaccessibility of the dish is also a problem when changing bands. Unless the tower is climbed every time and the feed changed, there must be a feed for each band mounted on the dish. One way around these problems is to use a periscope antenna system (sometimes called a "flyswatter antenna").

The material in this section was prepared by Bob Atkins, KA1GT, and appeared in *QST* for January and February 1984. **Fig 79** shows a schematic representation of a periscope antenna system. A plane reflector is mounted at the top of a rotating tower at an angle of 45°. This reflector can be elliptical with a major to minor axis ratio of 1.41, or rectangular. At the base of the tower is mounted a dish or other type of antenna such as a Yagi, pointing straight up. The advantage of such a system is that the feed antenna can be changed and worked on eas-

ily. Additionally, with a correct choice of reflector size, dish size, and dish to reflector spacing, feed losses can be made small, increasing the effective system gain. In fact, for some particular system configurations, the gain of the overall system can be greater than that of the feed antenna alone.

Gain of a Periscope System

Fig 80 shows the relationship between the effective gain of the antenna system and the distance between the reflector and feed antenna for an elliptical reflector. At first sight, it is not at all obvious how the antenna system can have a higher gain than the feed alone. The reason lies in the fact that, depending on the feed to reflector spacing, the reflector may be in the near field (Fresnel) region of the antenna, the far field (Fraunhöffer) region, or the transition region between the two.

In the far field region, the gain is proportional to the reflector area and inversely proportional to the distance between the feed and reflector. In the near field region, seemingly strange things can happen, such as decreasing gain with decreasing feed to reflector separation. The reason for this gain decrease is that, although the reflec-

Fig 79—The basic periscope antenna. This design makes it easy to adjust the feed antenna.

tor is intercepting more of the energy radiated by the feed, it does not all contribute in phase at a distant point, and so the gain decreases.

In practice, rectangular reflectors are more common than elliptical. A rectangular reflector with sides equal in length to the major and minor axes of the ellipse will, in fact, normally give a slight gain increase. In the far field region, the gain will be proportional to the area of the reflector. To use Fig 80 with a rectangular reflector, R^2 may be replaced by A / π, where A is the projected area of the reflector. The antenna pattern depends in a complicated way on the system parameters (spacing and size of the elements), but **Table 21** gives an approximation of what to expect. R is the radius of the projected circular area of the elliptical reflector (equal to the minor axis radius), and b is the length of the side of the projected square area of the rectangular reflector (equal to the length of the short side of the rectangle).

For those wishing a rigorous mathematical analysis of this type of antenna system, several references are given in the Bibliography at the end of this chapter.

Mechanical Considerations

There are some problems with the physical construction of a periscope antenna system. Since the antenna gain of a microwave system is high and, hence, its beamwidth narrow, the reflector must be accurately aligned. If the reflector does not produce a beam that is horizontal, the

Fig 80—Gain of a periscope antenna using a plane elliptical reflector (after Jasik—see Bibliography).

Table 21
Radiation Patterns of Periscope Antenna Systems

	Elliptical Reflector	Rectangular Reflector
3-dB beamwidth, degrees	60 λ/2R	52 λ/b
6-dB beamwidth, degrees	82 λ/2R	68 λ/b
First minimum, degrees from axis	73 λ/2R	58 λ/b
First maximum, degrees from axis	95 λ/2R	84 λ/b
Second minimum, degrees from axis	130 λ/2R	116 λ/b
Second maximum, degrees from axis	156 λ/2R	142 λ/b
Third minimum, degrees from axis	185 λ/2R	174 λ/b

Fig 81—Commercial periscope antennas, such as this one, are often used for point-to-point communication.

useful gain of the system will be reduced. From the geometry of the system, an angular misalignment of the reflector of X degrees in the vertical plane will result in an angular misalignment of 2X degrees in the vertical alignment of the antenna system pattern. Thus, for a dish pointing straight up (the usual case), the reflector must be at an angle of 45° to the vertical and should not fluctuate from factors such as wind loading.

The reflector itself should be flat to better than $^1/_{10}$ λ for the frequency in use. It may be made of mesh, provided that the holes in the mesh are also less than $^1/_{10}$ λ in diameter. A second problem is getting the support mast to rotate about a truly vertical axis. If the mast is not vertical, the resulting beam will swing up and down from the horizontal as the system is rotated, and the effective gain at the horizon will fluctuate. Despite these problems, amateurs have used periscope antennas successfully on the bands through 10 GHz. Periscope antennas are used frequently in commercial service, though usually for point-to-point transmission. Such a commercial system is shown in **Fig 81**.

Circular polarization is not often used for terrestrial work, but if it is used with a periscope system there is an important point to remember. The circularity sense changes when the signal is reflected. Thus, for right hand circularity with a periscope antenna system, the feed arrangement on the ground should produce left hand circularity. It should also be mentioned that it is possible (though more difficult for amateurs) to construct a periscope antenna system using a parabolically curved reflector. The antenna system can then be regarded as an offset fed parabola. More gain is available from such a system at the added complexity of constructing a parabolically curved reflector, accurate to $^1/_{10}$ λ.

BIBLIOGRAPHY

Source material and more extended discussion of topics covered in this chapter can be found in the references given below and in the textbooks listed at the end of Chapter 2, Antenna Fundamentals.

B. Atkins, "Periscope Antenna Systems," The New Frontier, *QST*, Jan and Feb 1984.

B. Atkins, "Horn Antennas for 10 GHz," The New Frontier, *QST*, Apr and May 1987.

J. Drexler, "An Experimental Study of a Microwave Periscope," *Proc. IRE*, Correspondence, Vol 42, Jun 1954, p 1022.

D. Evans and G. Jessop, *VHF-UHF Manual*, 3rd ed. (London: RSGB), 1976.

N. Foot, "WA9HUV 12foot Dish for 432 and 1296 MHz," The World Above 50 Mc., *QST*, Jun 1971, pp 98-101, 107.

N. Foot, "Cylindrical Feed Horn for Parabolic Reflectors," *Ham Radio*, May 1976.

G. Gobau, "Single-Conductor Surface-Wave Transmission Lines," *Proc. IRE*, Vol 39, Jun 1951, pp 619-624; also see *Journal of Applied Physics*, Vol 21 (1950), pp 1119-1128.

R. E. Greenquist and A. J. Orlando, "An Analysis of Passive Reflector Antenna Systems," *Proc. IRE*, Vol 42, Jul 1954, pp 1173-1178.

G. A. Hatherell, "Putting the G Line to Work," *QST*, Jun 1974, pp 11-15, 152, 154, 156.

D. L. Hilliard, "A 902MHz Loop Yagi Antenna," *QST*, Nov 1985, pp 30-32.

W. C. Jakes, Jr., "A Theoretical Study of an Antenna-Reflector Problem," *Proc. IRE*, Vol 41, Feb 1953, pp 272-274.

H. Jasik, *Antenna Engineering Handbook*, 1st ed. (New York: McGraw-Hill, 1961).

R. T. Knadle, "UHF Antenna Ratiometry," *QST*, Feb 1976, pp 22-25.

T. Moreno, *Microwave Transmission Design Data* (New York: McGraw- Hill, 1948).

W. Overbeck, "The VHF Quagi," *QST*, Apr 1977, pp 11-14.

W. Overbeck, "The Long-Boom Quagi," *QST*, Feb 1978, pp 20-21.

W. Overbeck, "Reproducible Quagi Antennas for 1296 MHz," *QST*, Aug 1981, pp 11-15.

G. Southworth, *Principles and Applications of Waveguide Transmission* (New York: D. Van Nostrand Co, 1950).

P. P. Viezbicke, "Yagi Antenna Design," *NBS Technical Note 688* (U. S. Dept. of Commerce/National Bureau of Standards, Boulder, CO), Dec 1976.

D. Vilardi, "Easily Constructed Antennas for 1296 MHz," *QST*, Jun 1969.

D. Vilardi, "Simple and Efficient Feed for Parabolic Antennas," *QST*, Mar 1973.

Radio Communication Handbook, 5th ed. (London: RSGB, 1976).

Antenna Systems for Space Communications

When we consider amateur space communications, we usually think about two basic modes: satellite and earth-moon-earth (EME—also referred to as *moonbounce*). At their essence, both modes communicate using one of the Earth's satellites—our natural satellite (the Moon) or one of a variety of manmade satellites.

There are two main differences between these satellites. The first is one of distance. The Moon is about 250,000 miles from Earth, while man-made satellites can be as far as 36,000 miles away. This 7:1 difference in distance makes a huge difference in the signals that arrive at the satellite, since transmission loss varies as the square of the distance. In other words, the signal arriving at the Moon is 20 dB weaker than that arriving at a geo-synchronous satellite 25,000 miles high, due to distance alone.

The second difference between the Moon and a man-made satellite is that the Moon is a *passive reflector*—and not a very good one at that, since it has a craggy and rather irregular surface, at least when compared to a flat mirror-like surface that would make an ideal reflector. Signals scattered by the Moon's irregular surface are thus weaker than for better reflecting surfaces. By comparison, a man-made satellite is an *active* system, where the satellite receives the signal coming from Earth, amplifies it and then retransmits the signal (usually at a different frequency) using a high-gain antenna. Think of a satellite as an ideal reflector, with gain.

The net result of these differences between a man-made satellite and the Earth's natural satellite is that moonbounce (EME) operation challenges the station builder considerably more than satellite operation, particularly in the area of antennas. Successful EME requires high transmitting power, superb receiver sensitivity and excellent operators capable of pulling weak signals out of the noise. This chapter will first explore antennas suitable for satellite operations and then describe techniques needed for EME work.

Common Ground

There are areas of commonality between satellite and EME antenna requirements, of course. Both require consideration of the effects of polarization and elevation angle, along with the azimuth directions of transmitted and received signals.

On the HF bands, signal polarization is generally of little concern, since the original polarization sense is lost after the signal passes through the ionosphere. At HF, vertical antennas receive sky-wave signals emanating from horizontal antennas, and vice versa. It is not beneficial to provide a means of varying the polarization at HF. With satellite communications, however, because of polarization changes, a signal that would disappear into the noise on one antenna may be S9 on one that is not sensitive to polarization direction. Elevation angle is also important from the standpoint of tracking and avoiding indiscriminate ground reflections that may cause nulls in signal strength.

Antennas for Satellite Work

We have amateur satellites providing links from 2 meters and up, and these provide opportunities to use antennas of many types—from the very simple to some pretty complex ones. This section was written by Dick Jansson, WD4FAB. It covers descriptions of a wide range of satellite antennas and points operators to source material for construction of many of them.

Antennas for LEO Satellites

Antenna design and construction requirements for use with Amateur satellites vary from low-gain antennas for low-earth-orbit (LEO) satellites to higher-gain antennas for the high-altitude elliptical-orbit satellites. You can operate the FM LEO satellites with a basic dual-band VHF/UHF FM transceiver or even a good FM H-T, as some amateurs have managed. Assuming that the transceiver is reasonably sensitive, you can even use a good "rubber duck" antenna. Some amateurs manage to work the FM birds with H-Ts and a multi-element directional antenna such as the popular Arrow Antenna, **Fig 1**. Of course, this means they must aim their antennas at the satellites, even as they cross overhead.

High-quality omnidirectional antennas for LEO service come in quite a number of forms and shapes. M^2 Enterprises has their EB-144 and EB-432 Eggbeater antennas, which have proven to be very useful and do not require any rotators for control. See **Fig 2**. The turnstile-over-reflector antenna has been around for a long time, as shown in **Fig 3**. Other operators have done well using low-gain Yagi antennas, such as those shown in **Fig 4**.

For even better performance, at the modest cost of a single, simple TV antenna rotator, check out the fixed-elevation *Texas Potato Masher* antenna by K5OE, **Fig 5.** This antenna provides a dual-band solution for medium-gain directional antennas for LEO satellites. This is a considerable improvement over omnidirectional antennas and does not require an elevation rotator for good performance.

There are still two LEO satellites that work on the 10-meter band, RS-15 and the newly resurrected AO-7. Both have 10-meter downlinks in the range of 29.3 to 29.5 MHz. Low-gain 10-meter antennas, such as dipoles or long-wire antennas, are used to receive these satellites.

Antennas for High-Altitude Satellites

The high-altitude, Phase-3 satellites, such as AO-10 (and the late AO-13), have been around for quite a number of years. The greater distances to the Phase-3 satellites mean that more transmitted power is needed to access them and weaker signals are received on the ground. Successful stations usually require ground-station antennas with significant gain (12 dBi or more), such as a set of high-gain Yagi antennas. See **Fig 6**. Note the use of two Yagi antennas mounted on each boom to provide *circular polarization*, usually referred to as CP.

Fig 1—The hand-held "Arrow" gain antenna is popular for LEO FM operations. (*Photo courtesy* The AMSAT Journal, *Sept/Oct 1998.*)

Fig 2—Eggbeater antennas are popular for base station LEO satellite operations. This EB-432 eggbeater antenna for 70 cm is small enough to put in an attic. Antenna gain pattern is helped with the radials placed below the antenna.

Fig 3—The Turnstile Over Reflector antenna has served well for LEO satellite service for a number of years.

Fig 5—Jerry Brown, K5OE, uses his Texas Potato Masher antennas to work LEO satellites.

Fig 4—Simple ground plane and Yagi antennas can be used for LEO satellite contacts.

Fig 6—Dick Jansson, WD4FAB, used these 2-meter and 70-cm crossed Yagi's in RHCP for AO-10 and AO-13 operations. The satellite antennas are shown mounted above a 6-meter long-boom Yagi.

CIRCULAR POLARIZATION

Linearly polarized antennas are horizontal or vertical in terms of the antenna's position relative to the surface of the Earth, a reference that loses its meaning in space. The need to use circularly polarized (CP) antennas for space communications is well established. If spacecraft antennas used linear polarization, ground stations would not be able to maintain polarization alignment with the spacecraft because of changing orientations. The ideal antenna for random satellite polarizations is one with a circularly polarized radiation pattern.

There are two commonly used methods for obtaining circular polarization. One is with crossed linear elements such as dipoles or Yagis, as Fig 6 shows. The second popular CP method uses a helical antenna, described below. Other methods also exist, such as with the omnidirectional quadrifilar helix, **Fig 7**.

Polarization *sense* is a critical factor, especially in EME and satellite work. The IEEE standard uses the term "clockwise circular polarization" for a *receding* wave. Amateur technology follows the IEEE standard, calling clockwise polarization for a receding wave as right-hand, or RHCP. Either clockwise or a counter-clockwise (LHCP) sense can be selected by reversing the phasing harness of a crossed-Yagi antenna, see **Fig 8**. The sense of a helical antenna is fixed, determined by its physical construction.

Fig 7—W3KH suggests that quadrifilar antennas can serve well for omnidirectional satellite-station antenna service.

Fig 8—Evolution of the circularly polarized Yagi. The simplest form of crossed Yagi, A, is made to radiate circularly by feeding the two driven elements 90° out of phase. Antenna B has the driven elements fed in phase, but has the elements of one bay mounted $^1/_4$ λ forward from those of the other. Antenna C offers elliptical (circular) polarization using separate booms. The elements in one set are perpendicular to those of the other and are $^1/_4$ λ forward from those of the other.

See **Fig 9** for construction details.

In working through a satellite with a circularly polarized antenna, it is often convenient to have the capability of switching polarization sense. This is because the sense of the received signal of some of the LEO satellites reverses when the satellite passes its nearest point to you. If the received signal has right-hand circular polarization as the satellite approaches, it may have left-hand circularity as the satellite recedes. There is a sense reversal in EME work, as well, because of a phase reversal of the signal as it is reflected from the surface of the moon. A signal transmitted with right-hand circularity will be returned to the Earth with left-hand circularity. Similarly, the polarization is reversed as it is reflected from a dish antenna, so that for an overall RHCP performance, the feed antenna for the dish needs to be LHCP.

Crossed Linear Antennas

Dipoles radiate linearly polarized signals, and the polarization direction depends on the orientation of the antenna. It two dipoles are arranged for horizontal and vertical dipoles, and the two outputs are combined with the correct phase difference (90°), a circularly polarized

wave results. Because the electric fields are identical in magnitude, the power from the transmitter will be equally divided between the two fields. Another way of looking at this is to consider the power as being divided between the two antennas; hence the gain of each is decreased by 3 dB when taken alone in the plane of its orientation.

A 90° phase shift must exist between the two antennas and the simplest way to obtain this shift is to use two feed lines to a coplanar pair of crossed-Yagi antennas. One feed-line section is $^1/_4$ λ longer than the other, as shown in Fig 8A. These separate feed lines are then paralleled to a common transmission line to the transmitter or receiver. Therein lies one of the headaches of this system. Assuming negligible coupling between the crossed antennas, the impedance presented to the common transmission line by the parallel combination is one half that of either section alone. (This is not true when there is mutual coupling between the antennas, as in phased arrays.) A practical construction method for implementing a RHCP/LHCP coplanar switched system is shown in **Fig 10**.

Another example of a coplanar crossed-Yagi antenna is shown in **Fig 11**. With this phasing-line method, any mismatch at one antenna will be magnified by the extra $^1/_4$ λ of transmission line. This upsets the current balance between the two antennas, resulting in a loss of polarization circularity. Another factor to consider is the attenuation of the cables used in the harness, along with the

Fig 9—Construction details of a co-planar crossed-Yagi antenna.

Fig 10—Co-planar crossed Yagi, circularly polarized antenna with switchable polarization phasing harness.

connectors. Good low-loss coaxial line should be used. Type-N or BNC connectors are preferable to the UHF variety.

Another method to obtain circular polarization is to use equal-length feed lines and place one antenna $^1/_4$ λ ahead of the other. This offset pair of Yagi-crossed antennas is shown in Fig 8B. The advantage of equal-length feed lines is that identical load impedances will be presented to the common feeder, as shown in **Fig 12**, which shows a fixed circularity sense feed. To obtain a switchable sense feed with the offset Yagi pair, you can use a connection like that of **Fig 13**, although you must compensate for the extra phase added by the relay and connectors.

Fig 8C diagrams a popular method of mounting two separate off-the-shelf Yagis at right angles to each other. The two Yagis may be physically offset by $^1/_4$ λ and fed in parallel, as shown in Fig 8C, or they may be mounted with no offset and fed 90° out of phase. Neither of these arrangements on two separate booms produces true circular polarization. Instead, *elliptical* polarization results from such a system. **Fig 14** is a photo of this type of mounting of Yagis on two booms for elliptical operation.

Helical Antennas

As mentioned, the second method to create a circularly polarized signal is by means of a helical antenna. The axial-mode helical antenna was introduced by Dr John Kraus, W8JK, in the 1940s. **Fig 15** shows examples of S-band (2400-MHz), V-band (145-MHz), and U-band (435-MHz) helical antennas, all constructed by WD4FAB for satellite service.

This antenna has two characteristics that make it

Fig 11—This VHF crossed Yagi design by KH6IJ (Jan 1973 *QST*) illustrates the co-planar, fixed-circularity Yagi.

Fig 12—Offset crossed-Yagi circularly polarized antenna-phasing harness with fixed polarization.

especially interesting and useful in many applications. First, the helix is circularly polarized. As discussed earlier, circular polarization is simply linear polarization that continually rotates as it travels through space. In the case of a helical antenna, this rotation is about the axis of the antenna. This can be pictured as the second hand of a watch moving at the same rate as the applied frequency, where the position of the second hand can be thought of as the instantaneous polarization of the signal.

The second interesting property of the helical antenna is its predictable pattern, gain and impedance characteristics over a wide frequency range. This is one of the few antennas that has both broad bandwidth and high gain. The benefit of this property is that, when used for narrow-band applications, the helical antenna is very forgiving of mechanical inaccuracies.

Probably the most common amateur use of the helical antenna is in satellite communications, where the spinning of the satellite antenna system (relative to the earth) and the effects of Faraday rotation cause the polarization of the satellite signal to be unpredictable. Using a linearly polarized antenna in this situation results in deep fading, but with the helical antenna (which responds equally to linearly polarized signals), fading is essentially eliminated.

This same characteristic makes helical antennas useful in polarization-diversity systems. The advantages of circular polarization have been demonstrated on VHF voice schedules over non-optical paths, in cases where linearly polarized beams did not perform satisfactorily.

Another use for the helical antenna is the transmission of color ATV signals. Many beam antennas (when adjusted for maximum gain) have far less bandwidth than the required 6 MHz, or have non-uniform gain over this frequency range. The result is significant distortion of the transmitted and received signals, affecting color reproduction and other features. This problem becomes more aggravated over non-optical paths. The helix exhibits maximum gain (within 1 dB) more than 20 MHz anywhere above 420 MHz.

The helical antenna can be used to advantage with multimode rigs, especially above 420 MHz. Not only does the helix give high gain over an entire amateur band, but it also allows operation on FM, SSB and CW without the need for separate vertically and horizontally polarized antennas.

Helical Antenna Basics

The helical antenna is an unusual specimen in the antenna world, in that its physical configuration gives a

Fig 13—Offset crossed-Yagi circularly polarized antenna-phasing harness with switchable polarization.

Fig 14—An example of offset crossed-Yagi circularly polarized antennas with fixed polarization. This example is a pair of M² 23CM22EZA antennas, for L band (1269 MHz), mounted on an elevation boom. (*WD4FAB photo.*)

Fig 15—At top, a seven-turn LHCP helical antenna for S-band dish feed for AO-40 service. This helical antenna uses a cupped reflector and has a preamplifier mounted directly to the antenna feed point. At bottom, a pair of helical antennas for AO-10 service on 2 meters and 70 cm. The 2-meter helical antenna is not small! (*WD4FAB photos.*)

hint to its electrical performance. A helix looks like a large air-wound coil with one of its ends fed against a ground plane, as shown in **Fig 16**. The ground plane is a screen of 0.8 λ to 1.1 λ diameter (or on a side for a square ground plane). The circumference (C_λ) of the coil form must be between 0.75 λ and 1.33 λ for the antenna to radiate in the axial mode. The coil should have at least three turns to radiate in this mode. The ratio of the spacing between turns (in wavelengths), S_λ to C_λ, should be in the range of 0.2126 to 0.2867. This ratio range results from the requirement that the pitch angle, α, of the helix be between 12° and 16°, where:

$$\alpha = \arctan \frac{S_\lambda}{C_\lambda} \qquad \text{(Eq 1)}$$

Fig 16—The basic helical antenna and design equations.

These constraints result in a single main lobe along the axis of the coil. This is easily visualized from Fig 15A. The winding of the helix comes away from the cupped reflector with a counterclockwise winding direction for a LHCP. (The winding can also be a clockwise—this results in a RHCP polarization sense.)

A helix with a C_λ of 1λ has a wave propagating from one end of the coil (at the ground plane), corresponding to an instantaneous dipole "across" the helix. The electrical rotation of this dipole produces circularly polarized radiation. Because the wave is moving along the helix conductor at nearly the speed of light, the rotation of the electrical dipole is at a very high rate, and true circular polarization results.

The IEEE definition, in simple terms, is that when viewing the antenna from the feed-point end, a clockwise wind results in right-hand circular polarization (RHCP), and a counterclockwise wind results in left-hand circular polarization (LHCP). This is important, because when two stations use helical antennas over a nonreflective path, both must use antennas with the same polarization sense. If antennas of opposite sense are used, a signal loss of at least 20 dB results from the cross polarization alone.

As mentioned previously, circularly polarized antennas can be used in communications with any linearly polarized antenna (horizontal or vertical), because circularly polarized antennas respond equally to all linearly polarized signals. The gain of a helix is 3 dB less than the theoretical gain in this case, because the linearly polarized antenna does not respond to linear signal components that are orthogonally polarized relative to it.

The response of a helix to all polarizations is indicated by a term called *axial ratio*, also known as *circularity*. Axial ratio is the ratio of amplitude of the polarization that gives maximum response to the amplitude of the polarization that gives minimum response. An ideal circularly polarized antenna has an axial ratio of 1.0. A well-designed practical helix exhibits an axial ratio of 1.0 to 1.1. The axial ratio of a helix is:

$$AR = \frac{2n + 1}{2n} \qquad \text{(Eq 2)}$$

where:

AR = axial ratio
n = the number of turns in the helix

Axial ratio can be measured in two ways. The first is to excite the helix and use a linearly polarized antenna with an amplitude detector to measure the axial ratio directly. This is done by rotating the linearly polarized antenna in a plane perpendicular to the axis of the helix and comparing the maximum and minimum amplitude values. The ratio of maximum to minimum is the axial ratio.

The impedance of the helix is easily predicted. The terminal impedance of a helix is unbalanced, and is defined by:

$$Z = 140 \times C_\lambda \qquad \text{(Eq 3)}$$

where Z is the impedance of the helix in ohms.

The gain of a helical antenna is determined by its physical characteristics. Gain can be calculated from:

$$\text{Gain (dBi)} = 11.8 + 10\log\left(C_\lambda^2\, nS_\lambda\right) \qquad \text{(Eq 4)}$$

In practice, helical antennas do not deliver the gain in Eq 4 for antennas with turns count greater than about twelve. There will be more discussions in this area when practical antennas are discussed.

The beamwidth of the helical antenna (in degrees) at the half-power points is:

$$BW = \frac{52}{C_\lambda \sqrt{nS_\lambda}} \qquad \text{(Eq 5)}$$

The diameter of the helical antenna conductor should be between 0.006 λ and 0.05 λ, but smaller diameters have been used successfully at 144 MHz. The previously noted diameter of the ground plane (0.8 λ to 1.1 λ) should not be exceeded if you desire a clean radiation pattern. As the ground plane size is increased, the sidelobe levels also increase. Cupped ground planes have been used according to Kraus, as in Fig 15. (The ground plane need not be solid; it can be in the form of a spoked wheel or a frame covered with hardware cloth or screen.)

50-Ω Helix Feed

Joe Cadwallader, K6ZMW, presented this feed method in June 1981 *QST*. Terminate the helix in an N connector mounted on the ground screen at the periphery of the helix. See **Fig 17**. Connect the helix conductor to the N connector as close to the ground screen as possible (**Fig 18**). Then adjust the first quarter turn of the helix to a close spacing from the reflector.

This modification goes a long way toward curing a deficiency of the helix—the 140-Ω nominal feed-point

Fig 17—End view and side view of peripherally fed helix.

Fig 18—Wrong and right ways to attach helix to a type N connector for 50-Ω feed.

Fig 19—End view and side view of peripherally fed helix with metal strip added to improve transformer action.

impedance. The traditional λ/4 matching section has proved difficult to fabricate and maintain. But if the helix is fed at the periphery, the first quarter turn of the helix conductor (leaving the N connector) acts much like a transmission line—a single conductor over a perfectly conducting ground plane. The impedance of such a transmission line is:

$$Z_0 = 138 \log \frac{4h}{d} \qquad \text{(Eq 6)}$$

where:

Z_0 = line impedance in ohms
h = height of the center of the conductor above the ground plane
d = conductor diameter (in the same units as h).

The impedance of the helix is 140 Ω a turn or two away from the feed point. But as the helix conductor swoops down toward the feed connector (and the ground plane), h gets smaller, so the impedance decreases. The 140-Ω nominal impedance of the helix is transformed to a lower value. For any particular conductor diameter, an optimum height can be found that will produce a feed-point impedance equal to 50 Ω. The height should be kept very small, and the diameter should be large. Apply power to the helix and measure the SWR at the operating frequency. Adjust the height for an optimum match.

Typically, the conductor diameter may not be large enough to yield a 50-Ω match at practical (small) values of h. In this case, a strip of thin brass shim stock or flashing copper can be soldered to the first quarter turn of the helix conductor (**Fig 19**). This effectively increases the conductor diameter, which causes the impedance to decrease further yet. The edges of this strip can be slit every $^1/_2$ inch or so, and the strip bent up or down (toward or away from the ground plane) to tune the line for an optimum match.

This approach yields a perfect match to nearly any coax. The usually wide bandwidth of the helix (70% for less than 2:1 SWR) will be reduced slightly (to about 40%) for the same conditions. This reduction is not enough to be of any consequence for most amateur work. The improvements in performance, ease of assembly and adjustment are well worth the effort in making the helix more practical to build and tune.

ANTENNAS FOR AO-40 OPERATIONS

Antennas for successful operations on AO-40 come in many shapes and sizes. AO-40 has provided amateurs the opportunity to broadly experiment with antennas.

Fig 20 shows the satellite antennas at WD4FAB. The Yagi antennas are used for the U- and L-band AO-40 uplinks and the V-band AO-10 downlink, while the S-band dish antenna is for the AO-40 downlink. These satellite antennas are tower mounted at 63 feet (19 meters) to avoid pointing into the many nearby trees and suffering from the resulting "green attenuation." Of course, satellite antennas do not always need to be mounted high on a tower if dense foliage is not a problem. If satellite antennas are mounted lower down, feed-line length and losses can reduced.

Another benefit, however, to tower mounting of satellite antennas is that they can be used for terrestrial ham communications and contests. The fact that the antennas are set up for CP does not really degrade these other operating activities.

Experience with AO-40 has clearly shown the advan-

Fig 20—Details of WD4FAB's tower cluster of satellite antennas including a home-brew elevation rotator. Top to bottom: M² 436-CP30, a CP U-band antenna; two M² 23CM22EZA antennas in a CP array for L band; "FABStar" dish antenna with helix feed for S band; M² 2M-CP22, a CP V-band antenna (only partially shown.) To left of dish antenna is a NEMA4 equipment box with an internal 40-W L-band amplifier, and also hosts externally mounted preamplifiers. (*WD4FAB photo*)

Fig 21—Domenico, I8CVS, has this cluster of satellite antennas for AO-40. Left to right: array of 4 × 23-element Yagi horizontally polarized for L band; 1.2-meter dish with 3-turn helix feed for S band; 15-turn RHCP helical antenna for U band; 60-cm dish for X band. All microwave preamplifiers and power amplifiers are homebrew and are mounted on this antenna cluster. (*I8CVS photo.*)

tages of using RHCP antennas for both the uplink and downlink communications. The antennas shown in Fig 20 are a single-boom RHCP Yagi antenna for U band, a pair of closely spaced Yagi antennas phased for RHCP for L band (see Fig 14), and a helix-fed dish antenna for S band. The antenna gain requirements for U band can easily be met with the gain of a 30-element crossed Yagi. Antennas of this size have boom lengths of 4 to 4¹/₂ wavelengths. The enterprising constructor can build a Yagi antenna from one of several references, however most of us prefer to purchase well-tested antennas from commercial sources as M² or Hy-Gain. In the past, KLM (now out of business) had offered a 40-element CP Yagi for U-band satellite service, and many of these are still in satisfactory use today.

U-band uplink requirements for AO-40 have clearly demonstrated the need for gain less than 16 to 17 dBic RHCP, with an RF power of less than 50 W PEP at the antenna (≈ 2,500 W-PEP EIRP with a RHCP antenna) depending upon the *squint angle*. (The squint angle is the angle at which the main axis of the satellite is pointed away from your antenna on the ground. If the squint angle is less than half of the half-power beamwidth, the ground station will be within the spacecraft antenna's nominal beam width.)

A gain of 16 to 17 dBic RHCP can be obtained from a 30-element crossed Yagi, AO-13 type antenna, and is

good news, considering that the satellite may be over 60,000 km (37,000 miles) from your station. Success on the U-band uplinks to AO-40 is easier than those for L band at wider squint angles more than 20°. At squint angles less than 10°, U-band uplink operation can even be done with 1-5 W power outputs to a RHCP antenna (≈ 200 W-PEP EIRP with RHCP). These lower levels mean that smaller antennas can be used. In practice, these uplinks will produce downlink signals that are 10 to 15 dB above the noise floor, or S7 signals over an S3 noise floor. The beacon will give a downlink S9 signal for these same conditions.

WD4FAB's experience with the AO-40 L-band uplink has demonstrated that 40 W-PEP delivered to an antenna with a gain of ≈ 19dBic (3,000 W-PEP EIRP with RHCP) is needed for operations at the highest altitudes of AO-40 and with squint angles ≤ 15°. This is the pretty com-

pact L-band antenna arrangement with two 22-element antennas in a RHCP array shown in Fig 14 and 20. Other operators have experience that using a 1.2-meter L-band dish antenna and 40 W of RF power (6,100 W-PEP EIRP with RHCP) can also provide a superb uplink for squint angles even up to 25°. A dish antenna can have a practical gain of about 21 to 22 dBic. These uplinks will provide

Fig 22—Wilfred Carey, ZS6JT, constructed this cluster of satellite and EME antennas. Left to right: 2 × 23-element offset feed Yagi for U band; 1.64-meter dish with 2¹/₄-turn helix feed for S band; 2 × 11-element coplanar feed Yagi for V band. (*ZS6JT photo.*)

the user a downlink that is 10 to 18 dB above the transponder noise floor. In more practical terms, this is an S7 to 8 signal over a S3 transponder noise floor, a very comfortable armchair copy.

Using the L-band uplink for AO-40, instead of the U-band uplink, allows the use of Yagi antennas that more manageable, since their size for a given gain is only one third of those for U-band. With L band there is a narrower difference between using a dish antenna and a Yagi, since a 21- to 22-dBic dish antenna would be only about 1.2 meters (4 feet) in diameter. However, some of us may not have such "real estate" available on our towers and may seek a lower wind-loading solution offered by Yagis. Long-boom rod-element Yagi, or loop-Yagi antennas are commercially offered by M² and DEM, although this band is about the highest for practical Yagis. The example shown in Fig 20 is a pair of rod-element Yagi antennas from M² in a CP arrangement with a gain of 18 to 19 dBic.

Other amateurs have successful AO-40 operation with different arrangements. **Fig 21** shows I8CVS's 4 × 23-element linear array for a 1270 MHz, a 1.2-meter solid dish for 2400 MHz, a 15-turn helical antenna for 435 MHz, and a 60-cm dish for 10,451 MHz. This arrangement clearly shows the advantage and accessibility of having a roof-mounted antenna.

Fig 22 shows ZS6JT's setup, with a 1.64-meter home-built mesh dish for 2400 MHz and two home-built crossed Yagi antennas, one for 435 MHz and the other for 145 MHz. Note that in these examples, the antennas permit terrestrial communication as well as satellite service. Two of these stations have also maintained the capability to operate the LEO satellites with U- and V-band antennas.

A number of amateurs have taken advantage of the availability of surplus C-band TVRO dishes, since most users of satellite television have moved up to the more

Fig 23—Robert Suding, WØLMD, modified this 4-foot dish antenna with a patch feed for S band and an Az-El mount. (*WØLMD photo.*)

Fig 24—WØLMD graduated to this 8-foot dish with patch feed for S band for AO-40. On the left is a helical antenna for L band and on the right is a 2 × 9-element offset-feed Yagi for U band. A home-brew Az-El mount is provided. (*WØLMD photo.*)

convenient K band using 0.5-meter dishes. Some examples of these dish conversions for satellite communications are shown in **Fig 23**, a WØLMD 4-foot dish with patch feed and Az-El mount. **Fig 24** shows a WØLMD 8-foot dish with patch feed, Az-El mount, a U-band Yagi, and an L-band helical antenna.

Fig 25 is a WØLMD 10-foot dish with tri-band patch feed and Az-El mount; and **Fig 26** is also a WØLMD

Fig 25—WØLMD increased to this 10-foot dish for AO-40 operations, with a triband patch feed for U, L, and S bands on an Az-El mount. (*WØLMD photo.*)

Fig 27—Clair E. Cessna, K6LG, has this 10-foot dish with S-band patch feed. This dish uses the original polar-mounting system and offsets the patch feed to compensate for AO-40's deviation from the Clarke belt. (*K6LG photo.*)

Fig 26—WØLMD found the ultimate in this 14-foot dish for AO-40, with a triband patch feed and Az-El mount. (*WØLMD photo.*)

Fig 28—K5GNA's "circularized" mesh modification of an MMDS dish antenna with a helix-CP feed and DEP preamp. The dish modification reduces the spillover loss by making the antenna fully circular. (*K5OE photo.*)

14-foot dish with tri-band patch feed and Az-El mounting. Other operators, like K6LG, have been able to use TVRO dishes, **Fig 27**, with multiband patch feeds and still use, within limits, their polar-mounting system, as will be explained later.

Other hams have taken advantage of other surplus dish situations. **Fig 28** shows modified MMDS dishes, by K5GNA, and **Fig 29**, by K5OE, both using helix feeds. **Fig 30** shows a 75-cm high modified PrimeStar offset feed dish, by WD4FAB, using a longer helical feed antenna

because of the higher f/D ratio of this dish configuration. This dish provides 5 dB of Sun noise, which is good performance. These efforts have rewarded their users with superb service on AO-40. Many have experimented with different feed and mounting systems. These experiments will be further illustrated.

One very popular spun-aluminum dish antenna seen in use on AO-40 has been the G3RUH-ON6UG 60-cm unit with its S-band patch feed, **Fig 31**. A kit, complete with a CP-patch feed is available from SSB-USA and has a gain of 21 dBic. It provides a 2.5-dB Sun noise signal. Surplus dishes have not been the only source for antennas for AO-40 operations, since some ingenious operators have even turned to the use of cardboard boxes. See **Figs 32** to **35**.

Fig 31—G3RUH's 60-cm spun-aluminum dish with CP-patch feed is available as a kit. This antenna has been popular with many AO-40 operators all over the world.

Fig 29—Mesh modification of an MMDS dish antenna by Jerry Brown, K5OE, with a helix-CP feed and DEM preamplifier mounted directly to the helix feed point. (*K5OE photo*.)

Fig 30—PrimeStar offset-fed dish with WD4FAB's helix-feed antenna. NØNSV was so pleased with the modification that he renamed the dish "FABStar," and made a new label! (*NØNSV photo*.)

Fig 32—A complete satellite station with the tracking laptop, FT-847 transceiver, and both downlink and uplink cardboard-box antennas.

Parabolic Reflector Antennas

The satellite S-band downlinks have become very popular for a variety of reasons:

- Good performance with physically small downlink antennas
- Availability of good-quality downconverters
- Availability of preamps at reasonable prices.

A number of people advocate S-band operation, including Bill McCaa, KØRZ, who led the team that designed and built the AO-13 S-band transponder and James Miller, G3RUH, who operates one of the AO-40 command stations. Ed Krome, K9EK, and James Miller have published a number of articles detailing construction of preamps, downconverters and antennas for S band.

Some access AO-40's S-band downlink using compact S-band helical antennas. See **Fig 36**. With the demise of AO-40's S1 transmitter and its high-gain downlink antenna, enthusiasts have had to employ high-gain parabolic-dish antennas to use AO-40's S2 downlink, with its lower-gain helical antenna.

WØLMD notes that like a bulb in a flashlight, the

Fig 33—The completed high-performance corner-reflector uplink antenna for U band. Note how the box corners hold the reflectors and dipole feed in place. The rear legs set the antenna elevation to 20°—this gives good coverage at the design latitude but will need modification for other stations.

Fig 35—Side view of the downlink pyramidal horn showing the elevation control supports and how the downconverter is attached to the horn. The downconverter is pulled forward by the tape to align the probe wire parallel to the rear surface of the horn.

Fig 34—Front view of the downlink pyramidal horn showing how it is mounted in the support carton. Notice the coax probe at the back of the horn.

Fig 36—WD4FAB's example of a 16-turn S-band helical antenna for AO-40. This is about the maximum length of any practical helix. Note the SSB UEK2000 downconverter mounted behind the reflector of the antenna. (*WD4FAB photo*.)

parabolic reflector or dish antenna must have a feed source looking into the surface of the dish. Some dishes are designed so that the feed source is mounted directly in front of the dish. This is referred to as a *center-fed dish*. Other dishes are designed so that the feed source is off to one side, referred to as an *off-center-fed dish*, or just offset-fed dish, as shown in Fig 30. The offset-fed dish may be considered a side section of a center-fed dish. The center-fed dish experiences some signal degradation due to blockage of the feed system, but this is usually an insignificantly small amount. The offset-fed dish is initially more difficult to aim, since the direction of reception is not the center axis, as it is for center-fed dishes.

The basic design precepts of parabolic-dish antennas are covered in more detail in the EME Antenna section of this chapter. Dish antenna properties specific to satellite operations are covered here. The dish's parabola can be designed so the focus point is closer to the surface of the dish, referred to a *short-focal-length* dish, or further away from the dish's surface, referred to as a *long-focal-length* dish. To determine the exact focal length, measure the diameter of the dish and the depth of the dish.

$$f = \frac{D^2}{16d} \qquad \text{(Eq 7)}$$

The focal length divided by the diameter of the dish gives the *focal ratio*, commonly shown as f/D. Center-fed dishes usually have short-focal ratios in the range of f/D = 0.3 to 0.45. Offset-fed dishes usually have longer focal lengths, with f/D = 0.45 to 0.80. If you attach two small mirrors to the outer front surface of a dish and then point the dish at the Sun, you can easily find the focus point of the dish. Put the reflector of the patch or helix feed just beyond this point of focus.

An alternate method for finding a dish's focal length is suggested by W1GHZ (ex-N1BWT), who provides a computer program called *HDL_ANT*, available at: **www.w1ghz.org/10g/10g_home.htm**. The method literally measures a solid-surface dish by the dimensions of the bowl of water that it will form when properly positioned. (See: **www.qsl.net/n1bwt/chap5.pdf**.) WD4FAB used this method on the dish of Fig 30, carefully leveling the bowl, plugging bolt holes, and filling it with water to measure the data needed by the W1GHZ Web-site calculation.

While many of us enjoy building our own antennas, surplus-market availability of these small dish antennas makes their construction unproductive. Many AO-40 operators have followed the practices of AO-13 operators using a surplus MMDS linear-screen parabolic reflector antenna, Figs 28 and 29. These grid-dish antennas are often called *barbeque dishes*. K5OE and K5GNA have shown how to greatly improve these linearly polarized reflectors by adapting them for the CP service desired for AO-40. Simple methods can be used to *circularize* a linear dish and to further add to its gain using simple methods to

Fig 37—Prototype 1.2-meter dish by Rick Fletcher, KG6IAL, using a dual-band (L and S) patch-feed antenna for AO-40. See text. This kit dish is covered with ¹/₄-inch mesh. (*KG6IAL photo*.)

increase the dish area and feed efficiency.

Another approach is the construction of a kit-type dish antenna, just becoming available in 1.2-meter and 1.8-meter diameters. This ingenious design by KG6IAL is available from his Web site **www.teksharp.com/**. **Fig 37** shows the prototype of the 1.2-meter dish with an f/D of 0.30. The 1.2-meter dish is fed with a dual-band patch feed for L and S bands. The 1.8-meter dish is designed for up to three bands using a tri-band patch feed for the U, L and S bands. This dish will permit U-band operation. A Central States VHF Society measurement on a similar sized dish (by WØLMD) with a patch feed showed a gain of about 17.1 dBic (actual measurement was 12.0 dBd linearly fed). This performance along with a small V-band (145 MHz) Yagi would permit a very modest satellite antenna assembly for all of the VHF/UHF LEO satellites, as well as AO-40.

The ingenuity of the design of the KG6IAL antenna is that it is constructed of robust, ¹/₈-inch-thick aluminum sheet that is numerically machined for the parabolic shape of the ribs. The backsides of the ribs are stiffened by a bent flange edge. The panel mesh is attached by using small tie-wraps or small aluminum wire through the mesh and holes provided along the parabolic edge. KG6IAL used ¹/₄-inch mesh in the prototype antenna to reduce wind loading. A single formed conduit post is provided in the kit for mounting the patch-feed assembly. The post extends rearward to permit the attachment of a counterweight, if needed.

AO-40 has also provided some additional challenges to the ham operator. Besides its well-known S-band downlink, AO-40 also has a K-band downlink in the range of

24.05 GHz. This quite low-powered transmitter has provided a substantial challenge to some operators, such as N1JEZ, K5OE, W5LUA, G3WDG and others. N1JEZ documented his work in *QST* while K5OE shows his K-band work on his Web site and in the *Proceedings of the AMSAT Space Symposium*. See **Fig 38**.

Parabolic Dish Antenna Construction

In the USA large numbers of dishes can be obtained either free or at low cost. But in some parts of the world dishes are not so plentiful, so hams make their own. **Fig 39** shows G3RUH's S-band dish antenna. There are three parts to the dish antenna—the parabolic reflector, the boom and the feed. There are as many ways to construct this as there are constructors. You need not slavishly replicate every nuance of the design. The only critical dimensions occur in the feed system. After construction, you will have a 60-cm diameter S-band RHCP dish antenna with a gain of about 20 dBi and a 3-dB beamwidth of 18°. Coupled with the proper downconverter, performance will be more than adequate for S-band downlink.

The parabolic reflector used for the original antenna was intended to be a lampshade. Several of these aluminum reflectors were located in department-store surplus. The dish is 585 mm in diameter and 110 mm deep, corresponding to an f/D ratio of 585/110/16 = 0.33 and a focal length of 0.33 × 585 = 194 mm. The f/D of 0.33 is a bit too concave for a simple feed to give optimal performance but the price was right, and the under-illumination keeps ground noise pickup to a minimum. The reflector already had a 40-mm hole in the center with three 4-mm holes around it in a 25-mm radius circle.

The boom passes through the center of the reflector and is made from 12.7-mm square aluminum tube. The boom must be long enough to mount to the rotator boom on the backside of the dish. The part of the boom extending through to the front of the dish must be long enough

Fig 39—Detail of 60-cm S-band dish antenna with feed.

Fig 38—K5OE found this K-band dish on the Web and has set it up for the AO-40 K-band downlink. (*K5OE photo.*)

to mount the feed at the focus. If you choose to mount the downconverter or a preamp near the feed, some additional length will be necessary. Carefully check the requirements for your particular setup.

A 3-mm thick piece of aluminum, 65 mm in diameter, supports the boom at the center of the reflector. Once the center mounting plate is installed, the center boom is attached using four small angle brackets—two on each side of the reflector. See Fig 39 for details of reflector and boom assembly.

A small helix is used for the S-band antenna feed. The reflector for the helix is made from a 125-mm square piece of 1.6-mm thick aluminum. The center of the reflector has a 13-mm hole to accommodate the square center boom described above. The type-N connector is mounted to the reflector about 21.25 mm from the middle. This distance from the middle is, of course, the radius of a helical antenna for S-band. Mount the N connector with spacers so that the back of the connector is flush with the reflector surface. The helix feed assembly is shown in **Fig 40**.

Copper wire, or tubing, about 3.2 mm in diameter is used to form the helix. Wind four turns around a 40-mm diameter form. The turns are wound counterclockwise. This is because the polarization sense is reversed from RHCP when reflected from the dish surface. The wire helix will spring out slightly when winding is complete.

Once the helix is wound, carefully stretch it so that the turns are spaced 28 mm (±1 mm). Make sure the finished spacing of the turns is nice and even. Cut off the first half turn. Carefully bend the first quarter turn about 10° so it will be parallel to the reflector surface once the helix is

attached to the N connector. This quarter turn will form part of the matching section.

Cut a strip of brass, 0.2 mm thick and 6 mm wide, and match the curvature of the first quarter turn of the helix, using a paper pattern. Be careful to get this pattern and subsequent brass cutting done exactly right. Using a large soldering iron and working on a heatproof surface, solder the brass strip to the first $^1/_4$ turn of the helix. Unless you are experienced at this type of soldering, getting the strip attached just right will require some practice. If it doesn't turn out right, just dismantle, wipe clean and try again.

After tack soldering the end of the helix to the type-N connector, the first $^1/_4$ turn, with its brass strip in place, should be 1.2 mm above the reflector at its start (at the N connector) and 3.0 mm at its end. Be sure to line up the helix so its axis is perpendicular to the reflector. Cut off any extra turns to make the finished helix have $2^1/_4$ turns total. Once you are satisfied, apply a generous amount of solder at the point the helix attaches to the N connector. Remember this is all that supports the helix.

Once the feed assembly is completed, pass the boom through the middle hole and complete the mounting by any suitable method. The middle of the helix should be at the geometric focus of the dish. In the figures shown here, the feed is connected directly to the downconverter and then the downconverter is attached to the boom. You may require a slightly different configuration depending on whether you are attaching a downconverter, preamp or just a cable with connector. Angle brackets may be used to secure the feed to the boom in a manner similar to the boom-to-reflector mounting. Be sure to use some method of waterproofing if needed for your preamp and/or downconverter.

Dish Feeds

WØLMD describes in **www.ultimatecharger.com/** that feeding a dish has two major factors that determine the efficiency. Like a flashlight bulb, the feed source should evenly illuminate the entire dish, and none of the feed energy should spillover outside the dish's reflecting surface. No feed system is perfect in illuminating a dish. Losses affect the gain from either under-illuminating or over-illuminating the dish (spillover losses). Typical dish efficiency is 50%. That's 3 dB of lost gain. A great feed system for one dish can be a real lemon on another. A patch feed system is very wide angle, but a helix feed system is narrow angle.

WØLMD has experimented with helical feeds for low f/D antennas ("deep" dishes) shown in **Fig 41**. A short-focal-ratio center-fed dish requires a wide-angle feed system to fully illuminate the dish, making the CP patch the preferred feed system. When used with an offset-fed dish, a patch-type feed system will result in a considerable spillover, or over-illumination loss, with an increased sensitivity to off-axis QRM, due to the higher f/D of this dish. Offset-fed

Fig 40—Details of helix feed for S-band dish antennas. The type-N connector is fixed with three screws and is mounted on a 1.6-mm spacer to bring the PTFE molding flush with the reflector. An easier mounting can be using a smaller TNC connector. Reflectors should be 95 to 100 mm in diameter.

Fig 41—WØLMD's dual helix-dish feed for U and S bands. This early experimental feed was found to be wanting and he then turned to patch feeds for dishes. (*WØLMD photo.*)

Fig 42—K5OE's helix feed for his MMDS S-band dish antenna. (*K5OE photo.*)

dishes do much better when fed with a helix antenna.

A helix feed is simplicity personified. Mount a type N connector on a flat reflector plate and solder a couple of turns wire to the inner terminal. Designs are anywhere from 2 to 6 turns. The two-turn helices are used for very short-focal-length dishes in the f/D = 0.3 region, and the 6-turn helices are used with longer-focal-length (f/D ~ 0.6) dishes, typically offset-fed dishes. Since AO-40 is right circular and the dish reflection will reverse the polarity, the helix should be wound left circular, looking forward from the connector. Helix feeds work poorly on the short-focal-length dishes but really perform well on the longer-focal-length offset-fed dishes. K5OE shows us the helix feed for his modified MMDS dish in **Fig 42**. This design employs the cupped reflector of W8JK.

A Helix Feed for an Offset-Dish Antenna

This section describes WD4FAB's surplus PrimeStar offset-fed dish antenna with a 7-turn helical feed antenna, shown in Fig 30. This S-band antenna can receive Sun noise 5 dB above sky noise. (Don't try to receive Sun noise with the antenna looking near the horizon, since terrestrial noise will be greater than 5 dB, at least in a big-city environment.) WD4FAB received the dish from NØNSV, who renamed the finished product the "FABStar."

The dish's reflector is a bit out of the ordinary, with the shape of a horizontal ellipse. It is still a single paraboloid, illuminated with an unusual feed horn. At 2401 MHz (S band) we can choose to under-illuminate the sides of the dish while properly feeding the central section, or over-illuminate the center while properly feeding the sides. WD4FAB chose to under-illuminate. The W1GHZ water-bowl measurements showed this to be a dish with a focal point of 500.6 mm and requiring a feed for an f/D = 0.79. The total illumination angle of the feed is 69.8° in the ver-

tical direction and a feed horn with a 3-dB beamwidth of 40.3°. At 50% efficiency this antenna was calculated to provide a gain of 21.9 dBi. A 7-turn helical feed antenna was estimated to provide the needed characteristics for this dish and is shown in **Fig 43**.

The helix is basically constructed as described for the G3RUH parabolic dish above. A matching section for the first $\lambda/4$ turn of the helix is spaced from the reflector at 2 mm at the start and 8 mm at the end of that fractional turn. Modifications of the G3RUH design include the addition of a cup reflector, a design feature used by the originator of the helical antenna, John Kraus, W8JK. For the reflector, a 2-mm thick circular plate is cut for a 94 mm (0.75 λ) diameter with a thin aluminum sheet metal cup, formed with a depth of 47 mm. Employment of the cup enhances the performance of the reflector for a dish feed, as shown by K5OE. (See the K5OE material on the CD-ROM accompanying this book.)

The important information for this 7-turn helical antenna is:

- Boom: 12.7-mm square tube or "C" channel.
- Element: $1/8$-inch diameter copper wire or tubing.

Close wind the element on a circular 1.50-inch tube or rod; the finished winding is 40 mm in diameter and spaced to a helical angle of 12.3°, or 28 mm spacing. These dimensions work out for an element circumference of 1.0 λ about the center of the wire.

When WD4FAB tackled this antenna, he felt that the small number of helical element supports used by G3RUH would be inadequate, in view of the real-life bird traffic on the antennas at his QTH. He chose to use PTFE (Teflon) support posts every $1/2$ turn. This closer spacing of posts permitted a careful control of the helix-winding diameter and spacing and also made the antenna very

Fig 43—Seven-turn LHCP helix feed for an offset dish, long f/D, antenna, with DEM preamp. (*WD4FAB photo.*)

Fig 45—Rain cover for preamp using a two-liter soft-drink bottle with aluminum foil tape for protection from sun damage. (*WD4FAB photo.*)

Fig 44—Mounting details of seven-turn helix and preamp. (*WD4FAB photo.*)

robust. He set up a fixture on the drill press to uniformly predrill the holes for the element spacers and boom. Attachment of the reflector is through three very small aluminum angle brackets on the element side of the boom.

Mounting of the helix to the dish requires modification of the dish's receiver-mounting boom. **Fig 44** shows these modifications using a machined mount. NM2A constructed one of these antennas and showed that a machine shop is not needed for this construction. He made a "Z" shaped mount from aluminum-angle plate and then used a spacer from a block of acrylic sheet. The key here is to get the dish focal point at the 1.5-turn point of the feed antenna, which is also at about the lip of the reflector cup.

The W1GHZ data for this focal point is 500.6 mm from the bottom edge of the dish and 744.4 mm from the top edge. A two-string measurement of this point can confirm the focal point, as shown by Wade in his writ-

ings. When mounting this feed antenna the constructor must be cautious to aim the feed at the beam-center of the dish, and not the geometric center, as the original microwave horn antenna was constructed. Taking the illumination angle information noted above, the helical feed antenna should be aimed 5.5° down from the geometric center of the dish.

As illustrated in Fig 44, a DEM preamp was directly mounted to the feed helix, using a TNC female connector on the helix, chosen for this case, since N connectors are quite large for this antenna. A male chassis connector should be mounted on the preamp so that the preamp can be directly connected to the antenna without any adaptors. This photo also illustrates how the reflector cup walls were riveted to the reflector plate.

Exposed connectors must be protected from rainwater. Commonly materials such as messy Vinyl Mastic Pads (3M 2200) or Hand Moldable Plastic (Coax Seal) are used. Since this is a tight location for such mastic applications, a rain cover was made instead from a 2-liter soft-drink bottle, **Fig 45**. Properly cutting off the top of the bottle allows it to be slid over the helix reflector cup and secured with a large hose clamp. You must provide UV protection for the plastic bottle and that was done with a wrapping of aluminum foil pressure-sensitive adhesive tape.

There are many methods for mounting this dish antenna to your elevation boom. You must give consideration to the placement of the dish to reduce the wind loading and off-balance to the rotator system. In WD4FAB's FABStar installation, the off-balance issue was not a major factor, as the dish was placed near the center of the elevation boom, between the pillow-block bearing supports. Since there is already a sizeable aluminum plate for these bearings, the dish was located to "cover" part of that plate, so as to not add measurably to the existing wind-loading area of the overall assembly.

A mounting bracket provided with the stock dish clamps to the end of a standard 2-inch pipe stanchion (actual measure: 2.38 inches in diameter). This bracket was turned around on the dish and clamped to the leg of a welded-pipe Tee assembly. See **Fig 46**. Pipe-reducing fittings were machined and fitted in the Tee-top bar, which was sawn in half for clamping over the $1^1/_2$ inch pipe used for the elevation boom. Bolts were installed through drilled holes and used to clamp this assembly.

Patch Feeds for Dish Antennas

Patch feeds are almost as simple as helix feeds. A patch is typically an N connector on a flat reflector plate with a tuned flat-metal plate soldered to the inner terminal. Sometimes the flat plate is square; sometimes it is rectangular; sometimes it is round. It could have two feed points, 90° out of phase for circular polarization, as used in the construction of the AO-40 U-band antennas. Some patches are rectangular with clipped corners to create a circular radiation pattern.

On 2401 MHz, the plate is 57 mm square and spaced 3 mm away from the reflector. The point of attachment is about halfway between the center and the edge. A round patch for 2401 MHz is about 66 mm in diameter. These patches work well on the shorter focal length center-fed

Fig 46—Welded pipefitting mount bracket for FABStar dish antenna. (*WD4FAB photo.*)

MMDS and TVRO dishes. G3RUH made a CP patch feed for these short f/D dishes, shown in Fig 31 and **Fig 47**.

Robert, WØLMD, has done a considerable amount of experimenting with patch feeds for his dish antennas. One tri-band feed is shown in **Fig 48**. These are circular patches that have CP properties through the arrangement of the feed point and a small piston-variable capacitor that is offset from the feed point. **Fig 49** shows some of the many patches that Robert has created for his trials.

A No-Tune Dual-Band Feed for Mode L/S

Jerry, K5OE, notes that the AO-40 transponder has two uplink receivers active most of the time for CW/SSB activity. Most operators use U band at 435 MHz (70 cm). Also available, however, are two L-band (23-cm) receivers: L1 at 1269 MHz and L2 at 1268 MHz. The reasons for going to L band can be varied, but there is no arguing the benefits in reduced antenna size and AGC suppression. The types of L-band antennas are varied as well. Many use helices. Others use beams and arrays of beams. Still others use dishes, small and large.

K5OE recently acquired an old UHF TV dish measuring 1.2 meters in diameter. He wanted to use it both to receive on S band at 2401 MHz (13cm) and to transmit on the uplink on L band. He covered it with aluminum mesh and built a dual-helix feed for it, but was unhappy with the L-band performance. It seems the concentric helices interacted with each other substantially. Having had good success with patch feeds on S band, he designed, built and installed a dual-patch feed on a 1.5-meter solid dish for Field Day 2002. This arrangement worked superbly on uplink (with 25 W), but was embarrassingly deaf on receive. This second dual-band feed failure led him to experiment for months with different configurations, leading ultimately to the design presented here. The project goals were:

- Good performance on both S-band receive and L-band uplink.
- An easy-to-produce model using common hardware and simple hand tools.

Patches are better than helices as dish feeds. This revelation came to K5OE while doing investigation and

Fig 47—Details of CP-patch feed for short f/D dish antennas by G3RUH and ON6UG.

Fig 48—A triband (U, L and S bands) patch-CP feed for large dish antennas for AO-40 service. (*WØLMD photo.*)

Fig 49—Some of the many experimental CP-patch-feed antennas by WØLMD. (*WØLMD photo.*)

Fig 50—The 1.2-meter dish with dual-band patch feed installed. (*K5OE photo; courtesy of* The AMSAT Journal.)

experimenting with helix antennas. In the middle of this investigative foray, he saw the radiation pattern for the G3RUH patch feed published on James Miller's web site. When he modeled that pattern and input it into the W1GHZ feed pattern program, it produced an amazing 72% efficiency. The best helix he ever modeled has about 60% efficiency. I8CVS recently ran his own antenna range tests of a design similar to the G3RUH patch and produced a similarly impressive pattern.

Then K5OE came across the *truncated corners* square patch design popularized by K3TZ. This AO-40 design here is attributed to 7N1JVW, JF6BCC and JG1IIK. There are references in the literature going back over a decade for this now-common commercial design. The first model K5OE built outperformed his best helix-in-cup design by a full S unit (delta over the noise) on his FT-100 portable setup. Compared to a helix, the patch simply has better illumination efficiency with less spillover from side lobes.

Patch theory is beyond the scope of this article, but can be summarized as building a shape that resonates at the desired frequency, compensated in size by the capacitive inductance between itself and the reflector. A patch can be practically any shape since it basically acts like a parallel-plate transmission line. Current in the patch flows from the feed point to the outer edge(s), where all the radiation occurs. The reputed, but often disputed, circularity of the truncated corner patch is accomplished by effectively designing two antennas into the patch element (of two different diagonal lengths) and feeding them 90º out of phase.

For K5OE's 1.2-meter dish, shown in **Fig 50**, com-

putations predicted 21-dBi gain on L band and almost 27 dBi on S band, with an assumed 50% efficiency:

$$G = 10\log_{10}\left[\eta A\left(\frac{4\pi}{\lambda^2}\right)\right] \qquad \text{(Eq 8)}$$

where

   η = efficiency
   λ = wavelength in meters.
   A = aperture of the dish in meters = $\pi \times r^2$
   r = dish radius in meters = diameter/2 in meters = 0.6 meters

   At 1269 MHz, λ= 300/1269 = 0.236 meters:

$$G = 10\log_{10}\left[0.50 \times \left(3.14 \times 0.6^2\right) \times \frac{4 \times 3.14}{0.236^2}\right] = 21.1\,\text{dBi}$$

At 2401.5 MHz, $\lambda = 300/2401.5 = 0.125$ meters:

$$G = 10\log_{10}\left[0.50 \times \left(3.14 \times 0.6^2\right) \times \frac{4 \times 3.14}{0.125^2}\right] = 26.6\,dB^2$$

Where does the feed get mounted? The *focal point* is where the parabolic shape of the dish concentrates the reflected signal. In K5OE's case the antenna was placed flat on the garage floor to measure the depth:

$$f = D^2 / 16d \qquad\qquad (Eq\ 9)$$

where

    D = diameter of the dish in inches
    d = depth of the dish in inches
    f = 48^2 / (16 × 7.25) = 19.8 inches (50.5 cm)

This is just one example of countless combinations of hardware and patch designs. Inherent in this design, however, are five key design and construction features developed from building and empirical testing of a number of patch feeds.

1. The specified dimensions are critical for no-tune operation. **Fig 51** shows the dimensions necessary to build the dual-feed patch. (K5OE recommends you reproduce this sketch accurately on graph paper. When you cut your patches you can lay them on the paper template for checking.) Repeat: These dimensions are critical. Even a 0.5-mm error will throw your resonance off considerably—patches are not broadband.

2. The reflector must be rigid. Spacing between the driven element (patch) and the reflector affects the resonant frequency. K5OE found 0.025-inch aluminum sheet and 26-gauge copper sheet acceptable for a single S-band patch feed, but too flimsy for an L-band reflector. Use more rigid material or provide additional stiffening for the L-band reflector, as shown in Figs **52**, **53** and **54**.

3. The patches must be electrically isolated from each other. A metallic center support works for a single patch but creates harmonic-coupling problems when patches are stacked for multiband use. The use of nylon machine screws and nuts helps solve the vexing problem of the S-band patch coupling to the L-band patch.

4. The "straight corners" of the truncated corner patch must be kept clear of any nearby metal. This includes the edges of the feed support or cup, if used. See Fig 54.

5. Feeding the patches at 90° to each other minimizes the electromagnetic interaction between the two antenna fields.

One final design issue deals with the first harmonic of the L-band antenna. You must significantly reduce the potentially destructive effect from the 1269-MHz signal's second harmonic. Severe desense of your receive signal could occur and potentially even overload and damage the first active device in your system. Sensitive preamps and downconverters without a pre-RF-amplifier filter will need an external filter. K5OE has used a G3WDG stub filter rated at 100-dB rejection with good success ahead of his preamp. His current setup, however, uses a AIDC-3731AA downconverter with its internal combline filter providing adequate filtering. Using the downconverter directly at the

Fig 51—Dual-band patch feed dimensions, in millimeters. (*K5OE diagram; courtesy of* The AMSAT Journal.)

Fig 52—Assembly of the L band reflector. (*K5OE photo; courtesy of* The AMSAT Journal.)

Fig 53—The support, L-band reflector and patch. (*K5OE photo; courtesy of* The AMSAT Journal.)

Fig 54—The completed dual-band patch feed. (*K5OE photo; courtesy of* The AMSAT Journal.)

feed point has a noise figure (NF) of 1.0 dB, compared to the cumulative NF of 1.6 dB using a filter and a preamp.

Construction of the feed begins with selection of material for both the electrical parts (the antennas) and the mechanical parts (the support structure). The L-band antenna is constructed using a 6×6-inch double-sided circuit board for the reflector and a piece of 26-gauge copper sheet for the driven element (patch). A flanged female type-N connector is used for the feed connection. The S-band antenna is constructed of two pieces of 26-gauge copper sheeting and the feed connection is made with a short piece of UT-141 (0.141-inch copper-clad semirigid coax) terminated in a male SMA fitting. Fig 52 illustrates the assembly of the L-band reflector with the nylon-center support bolt, the L-band N-connector, and the S-band semirigid coax terminated onto an SMA-to-N adapter through the

circuit board.

The support structure began life as a paint can, measuring 155 mm in diameter. It was cut down to a 15-mm depth. Cut a hole in the middle of the bottom of the can and trim the PC board to fit inside the can bottom. Use stainless-steel $^3/_8$-inch 4-40 bolts, washers and nuts to secure the PC board to the can bottom. A $1^1/_2$-inch 6-32 nylon bolt is secured through the center of the PC board with two nylon nuts to provide the 6-mm spacing for the L-band patch. Fig 53 shows the L-band patch in position and ready to be soldered to the N-connector. Note the hole through the L-band patch allowing the S-band UT-141 coax to pass (without making contact).

The remainder of the antenna is then assembled in order: First the L-band patch is secured with two nylon nuts and soldered to the N-connector. Then the S-band reflector is secured with one nylon nut to provide 3-mm spacing, and the UT-141 coax shield is soldered to the S-band reflector. Finally, the S-band patch is secured with a single nylon nut (3-mm spacing) and soldered to the center conductor of the UT-141 coax. To summarize the overall order of assembly: L-band reflector, two nylon nuts, L-band patch, two nylon nuts, S-band reflector, one nylon nut, S-band patch, and one nylon nut.

An electrical check with an ohmmeter of the completed feed should show the two reflectors connected, with the patches isolated from the reflectors and from each other. Fig 54 shows the completed feed. Note how the sides of the support are cut out to avoid proximity to the L-band patch and how the L-band and S-band patches are at 90° to each other. **Fig 55** shows the back of the feed, complete with an angle support for the downconverter. The flanged N-connector is for the L-band coax and the male-N adapter is secured from the other side of the feed with the SMA fitting on the UT-141 coax.

For those who are tempted to tune the patch, K5OE recommends doing it with the feed installed on the antenna—since the dish surface affects the feed-point impedance slightly. The feed-point impedance, and thus the resonant frequency, can be changed quite a bit by adjustment of the spacing of just the straight corners. There is no need to change the spacing at the center or the feed—just a slight up or down bending of the straight corners will change the tuning. Do this carefully: a little bit goes a long way. This patch design is very repeatable and will work adequately (an SWR below 1.5:1) with no adjustments.

The antenna performs to the calculated predictions above. On receive, this antenna is 4 S units better than K5OE's 45-cm dish and 3 S units above his 65-cm dish (both other dishes have similar patch feeds and the same downconverter). It also clearly outperforms his previous dual-helix arrangement on the 1.2-meter dish, but he was unable to do a side-by-side comparison.

On transmit, it does equally well, with a decent signal into the satellite with only 10 W measured at the

Fig 55—Rear of the completed feed. (K5OE photo; courtesy of *The AMSAT Journal*.)

Fig 56—The portable 435-MHz helix assembled and ready for operation. (*WØCY photo.*)

antenna. The L band is noticeably improved over the helix predecessor. At low squint angles K5OE finds the L-band uplink to be about 1 S unit weaker than his U-band uplink. He later added a small plastic hat to extend over the top of the patches to keep the rain and bird droppings off—both detune the patches when built up between the patch and the reflector.

Though simple and effective, this is merely one way to construct a dual feed. Cookie-tin lids also make excellent supports. Tin snips are a good investment and much easier to use than a hacksaw. Use a flat file to remove burrs from the edges of the patches. Use stainless-steel hardware, most notably $^3/_8$-inch 4-40 machine bolts and nuts for the antenna hardware and $^1/_2$-inch 6-32 for the support-structure connections to the support arms ($^1/_2$-inch aluminum tubing). The copper sheet is much easier to solder to than aluminum. Once completed, the feed received a few coats of white enamel paint to protect the copper and to minimize the visual reflections.

This is not the only dual-band antenna on AO-40. There are many varied, innovative designs available, including G6LVB's simple and effective 1.2-meter homebrew stressed *chicken wire* dish with a dual-G3RUH helix feed. G3WDG has a 3-meter dish with L/S-band helices and a K-band (1.3-cm) feed horn, and WØLMD has developed some popular dual- and tri-band "round" patch feeds. (See the Notes and References, as well as the CD-ROM bundled with this book.)

For additional information on constructing antennas, feeds and equipment techniques for use at microwave frequencies, see *The ARRL UHF/Microwave Experimenter's Manual* and *The ARRL UHF/Microwave Projects Manual*. Both of these books have a wealth of information for the experimenter.

PORTABLE HELIX FOR 435 MHZ

Helical antennas for 435 MHz are excellent uplinks for U-band satellite communications. The true circular polarization afforded by the helix minimizes signal *spin fading* that is so predominant in these applications. The antenna shown in **Fig 56** fills the need for an effective portable uplink antenna for OSCAR operation. Speedy assembly and disassembly and light weight are among the benefits of this array. This antenna was designed by Jim McKim, WØCY.

As mentioned previously, the helix is about the most tolerant of any antenna in terms of dimensions. The dimensions given here should be followed as closely as possible, however. Most of the materials specified are available in any well supplied do-it-yourself hardware or building supply store. The materials required to construct the portable helix are listed in **Table 1**.

The portable helix consists of eight turns of $^1/_4$-inch soft-copper tubing spaced around a 1-inch fiberglass tube or maple dowel rod 4 feet, 7 inches long. Surplus aluminum jacket Hardline can be used instead of the copper tubing if necessary. The turns of the helix are supported by 5-inch lengths of $^1/_4$-inch maple dowel mounted through the 1-inch rod in the center of the antenna. **Fig 57A** shows the overall dimensions of the antenna. Each of these support dowels has a V-shaped notch in the end to locate the tubing, as shown in Fig 57B.

The rod in the center of the antenna terminates at the feed-point end in a 4-foot piece of 1-inch ID galva-

Table 1

Parts List for the Portable 435-MHz Helix

Qty	Item
1	Type N female chassis mount connector
18 feet	$1/4$-in. soft copper tubing
4 feet	1-inch ID galvanized steel pipe
1	5 feet × 1-inch fiberglass tube or maple dowel
14	5-inch pieces of $1/4$-inch maple dowel (6 feet total)
1	$1/8$-inch aluminum plate, 10 inches diameter
3	2 × $3/4$-inch steel angle brackets
1	30 × 30-inch (round or square) aluminum screen or hardware cloth
8 feet	$1/2$ × $1/2$ × $1/2$-inch aluminum channel stock or old TV antenna element stock
3	Small scraps of Teflon or polystyrene rod (spacers for first half turn of helix)
1	$1/8$ × 5 × 5-inch aluminum plate (boom-to-mast plate)
4	1½-inch U bolts (boom-to-mast mounting)
3 feet	#22 bare copper wire (helix turns to maple spacers)

Assorted hardware for mounting connector, aluminum plate and screen, etc.

nized steel pipe. The pipe serves as a counterweight for the heavier end of the antenna. The 1-inch rod material inside the helix must be nonconductive. Near the point where the nonconductive rod and the steel pipe are joined, a piece of aluminum screen or hardware cloth is used as a reflector screen.

If you have trouble locating the $1/4$-inch soft copper tubing, try a refrigeration supply house. The perforated aluminum screening can be cut easily with tin snips. This material is usually supplied in 30 × 30-inch sheets, making this size convenient for a reflector screen. Galvanized $1/4$-inch hardware cloth or copper screen could also be used for the screen, but aluminum is easier to work with and is lighter.

A $1/8$-inch-thick aluminum sheet is used as the support plate for the helix and the reflector screen. Surplus rack panels provide a good source of this material. **Fig 58** shows the layout of this plate.

Fig 59 shows how aluminum channel stock is used to support the reflector screen. (Aluminum tubing also works well for this. Discarded TV antennas provide plenty of this material if the channel stock is not available.) The screen is mounted on the bottom of the 10-inch aluminum center plate. The center plate, reflector screen and channel stock are connected together with plated hardware or pop rivets. This support structure is very sturdy. Fiberglass tubing is the best choice for the center rod material although maple dowel can be used.

Mount the type-N connector on the bottom of the center plate with appropriate hardware. The center pin should be exposed enough to allow a flattened end of the copper tubing to be soldered to it. Tin the end of the tubing after it is flattened so that no moisture can enter it. If the helix is to be removable from the ground-plane screen, do not solder the copper tubing to the connector. Instead, prepare a small block of brass, drilled and tapped at one side for a 6-32 screw. Drill another hole in the brass block to accept the center pin of the type-N connector, and solder this connection. Now the connection to the copper tubing helix can be made in the field with a 6-32 screw instead of with a soldering iron.

Fig 57—At A, the layout of the portable 435-MHz helix is shown. Spacing between the first 5-inch winding-support dowel and the ground plane is $1/2$ inch; all other dowels are spaced 3 inches apart. At B, the detail of notching the winding-support dowels to accept the tubing is shown. As indicated, drill a $1/16$-inch hole below the notch for a piece of small wire to hold the tubing in place.

Fig 58—The ground plane and feed-point support assembly are shown. The circular piece is a 10-inch diameter, $^1/_8$-inch thick piece of aluminum sheet. (A square plate may be used instead.) Three 2 × $^3/_4$-inch angle brackets are bolted through this plate to the backside of the reflector screen to support the screen on the pipe. The type-N female chassis connector is mounted in the plate 4 inches from the 1-inch diameter center hole.

Fig 59—At top, the method of reinforcing the reflector screen with aluminum channel stock is shown. In this version of the antenna, the three angle brackets of Fig 58 have been replaced with a surplus aluminum flange assembly. (*WØCY photo*.) At bottom, this helix view shows the details of a $^1/_4$-turn matching transformer, as discussed in the text. (*K9EK photo*.)

Refer to Fig 57A. Drill the fiberglass or maple rod at the positions indicated to accept the 5-inch lengths of $^1/_2$-inch dowel. (If maple doweling is used, the wood must be weatherproofed as described below before drilling.) Drill a $^1/_{16}$-inch hole near the notch of each 5-inch dowel to accept a piece of #22 bare copper wire. (The wire is used to keep the copper tubing in place in the notch.) Sand the ends of the 5-inch dowels so the glue will adhere properly, and epoxy them into the main support rod.

Begin winding the tubing in a clockwise direction from the reflector screen end. First drill a hole in the flattened end of the tubing to fit over the center pin of the type-N connector. Solder it to the connector, or put the screw into the brass block described earlier. Carefully proceed to bend the tubing in a circular winding from one support to the next.

See the earlier section entitled "50-Ω Helix Feed" and Figs 19 and 20 to see how the first half-turn of the helix tubing must be positioned close above the reflector assembly. **Fig 59B** shows also an excellent example by K9EK on matching his U-band helical antenna to a 52-Ω feed line. It is important to maintain this spacing, since extra capacitance between the tubing and ground is required for impedance-matching purposes.

Insert a piece of #22 copper wire in the hole in each support as you go. Twist the wire around the tubing and the support dowel. Solder the wire to the tubing and to itself to keep the tubing in the notches. Continue in this way until all eight turns have been wound. After winding the helix, pinch the far end of the tubing together and solder it closed.

Weatherproofing the Wood

A word about preparing the maple doweling is in order. Wood parts must be protected from the weather to ensure long service life. A good way to protect wood is to boil it in paraffin for about half an hour. Any holes to be drilled in the wooden parts should be drilled after the paraffin is applied, since epoxy does not adhere well to wood after it has been coated with paraffin. The small dowels can be boiled in a saucepan. Caution must be exercised here—the wood can be scorched if the paraffin is too hot. Paraffin is sold for canning purposes at most grocery stores. Wood parts can also be protected with three or four coats of spar varnish. Each coat must be allowed to dry fully before another coat is applied.

The fiberglass tube or wood dowel must fit snugly

with the steel pipe. The dowel can be sanded or turned down to the appropriate diameter on a lathe. If fiberglass is used, it can be coupled to the pipe with a piece of wood dowel that fits snugly inside the pipe and the tubing. Epoxy the dowel splice into the pipe for a permanent connection.

Drill two holes through the pipe and dowel and bolt them together. The pipe provides a solid mount to the boom of the rotator, as well as most of the weight needed to counterbalance the antenna. More weight can be added to the pipe if the assembly is "front-heavy." (Cut off some of the pipe if the balance is off in the other direction.)

The helix has a nominal impedance of about 105 Ω in this configuration. By varying the spacing of the first half turn of tubing, a good match to 52-Ω coax should be obtainable. When the spacing has been established for the first half turn to provide a good match, add pieces of polystyrene or Teflon rod stock between the tubing and the reflector assembly to maintain the spacing. These can be held in place on the reflector assembly with silicone sealant. Be sure to seal the type-N connector with the same material.

Exposed Antenna Relays and Preamplifiers

For stations using crossed Yagi antennas for CP operation, one feature that has been quite helpful for communicating through most of the LEO satellites, has been the ability to switch polarization from RHCP to LHCP. In some satellite operation this switchable CP ability has been essential. Operation through AO-40 has not shown a great need for such CP agility, since if the satellite is seriously off-pointed the signals are not particularly useable. When AO-40's squint angle is less than 25° the need for LHCP has not been observed. For those using helical antennas or helical-fed dish antennas, we just would not have the choice to switch CP unless an entirely new antenna is added to the cluster for that purpose. Not many of us have the luxury of that kind of space available on our towers.

For stations with switchable-circularity Yagi antennas, experience with exposed circularity switching relays and preamplifiers mounted on antennas have shown that they are prone to failure caused by an elusive mechanism known as *diurnal pumping*. Often these relays are covered with a plastic case, and the seam between the case and PC board is sealed with a silicone sealant. Preamps may also have a gasket seal for the cover, while the connectors can easily leak air. None of these methods create a true hermetic seal and as a result the day/night temperature swings pump air and moisture in and out of the relay or preamp case. Under the right conditions of temperature and moisture content, moisture from the air will condense inside the case when the outside air cools down. Condensed water builds up inside the case, promoting extensive corrosion and unwanted electrical conduction, seriously degrading component performance in a short time.

A solution for those antennas with "sealed" plastic relays, such as the KLM CX series; you can avoid prob-

Fig 60—KLM 2M-22C antenna CP switching relay with relocated balun. The protective cover is needed for rain protection, be sure to use a polystyrene kitchen box, see text. (*WD4FAB photo.*)

Fig 61—A NEMA4 box is used to shelter the L-band electronics and power supply. The box flanges are convenient for mounting preamplifiers. The box is shown inverted since it is on a tilt-over tower. (*WD4FAB photo.*)

lems by making the modifications shown in **Fig 60**. Relocate the 4:1 balun as shown and place a clear polystyrene plastic refrigerator container over the relay. Notch the container edges for the driven element and the boom so the container will sit down over the relay, sheltering it from the elements. Bond the container in place with a few dabs of RTV adhesive sealant. Position the antenna in an "X" orientation, so neither set of elements is parallel to the ground. The switcher board should now be canted at an angle, and one side of the relay case should be lower than the other. An example for the protective cover for an S-band preamp can be seen in the discussion on feeds for parabolic antennas.

For both the relay and preamp cases, carefully drill a 3/32-inch hole through the low side of the case to provide the needed vent. The added cover keeps rainwater off the

relay and preamp, and the holes will prevent any buildup of condensation inside the relay case. Relays and preamplifiers so treated have remained clean and operational over periods of years without problems.

Another example for the protection of remotely, tower-mounted equipment is shown in Fig 50, illustrating the equipment box and mast-mounted preamplifiers at the top of WD4FAB's tower. The commercial NEMA4-rated equipment box, detailed in **Fig 61** (shown inverted), is used to protect the 23-cm power amplifier and its power supply, as well as a multitude of electrical connections. This steel box is very weather resistant, with an exceptionally good epoxy finish, but it is not sealed and so it will not trap moisture to be condensed with temperature changes. Be sure to use a box with at least a NEMA3 rating for rainwater and dust protection. The NEMA4 rating is just a little better protection than the NEMA3 rating. Using a well-rated equipment box is very well worth the expense of the box. As you can see, the box also provides some pretty good flanges to mount the mast-mounted preamplifiers for three bands. This box is an elegant solution for the simple need of rain shelter for your equipment. See **Fig 62**.

Elevation Control

Satellite antennas need to have elevation control to point up to the sky. This is the "El" part of Az-El control of satellite antennas. Generally, elevation booms for CP satellite antennas need to be non-conducting so that the boom does not affect the radiation pattern of the antenna. In the example shown next, the elevation boom center section is a piece of extra-heavy-wall $1^1/_2$-inch pipe (for greater strength) coupled with a tubular fiberglass-epoxy boom extension on the 70-cm end and a home-brew long extension on the 2-meter end. This uses large PVC pipe reinforced with four braces of Phillystran non-metallic guy cable. (PVC pipe is notoriously flexible, but the Phillystran cables make a quite stiff and strong boom of the PVC pipe.) For smaller installations, a continuous piece of fiberglass-epoxy boom can be placed directly through the elevation rotator.

Elevation boom motion needs to be powered, and one solution by WD4FAB, shown in **Fig 63**, uses a surplus jackscrew drive mechanism. I8CVS has also built his own robust elevation mechanism. See **Fig 64**. Note in each of these applications the methods used to provide bearings for the elevation mechanism. In WD4FAB's case, the elevation axis is a piece of heavy-duty $1^1/_2$-inch pipe,

Fig 62—Protection for tower-mounted equipment need not be elaborate. Be sure to dress the cables as shown so that water drips off the cable jacket before it reaches the enclosure. One hazard for such open-bottom enclosures is that of animals liking the cable insulation as a delicacy. Flying insects also like to build their houses in these enclosures.

Fig 63—WD4FAB's homebrew elevation rotator drive using a surplus-store drive screw mechanism. Note also the large journal bearing supporting the elevation axis pipe shaft. (*WD4FAB photo.*)

($1^{15}/_{16}$-inch OD) and large 2 inch journal bearings are used for the motion. I8CVS uses a very large hinge to allow his motion.

Robust commercial solutions for Az-El rotators have given operators good service over the years. **See Fig 65.** Manufacturers such as Yaesu and M² are among these

Fig 64—I8CVS's homebrew elevation mechanism using a very large, industrial hinge as the pivot and a jackscrew drive. (*I8CVS photo.*)

suppliers. One operator, VE5FP, found a solution for his Az-El needs by using two low-cost, lightweight TV rotators. See Fig 65B.

CONVERTED C-BAND TVRO DISHES

In working with larger, converted C-band TVRO dishes for AO-40, some operators have used only the polar mount with its jack-screw mechanism. See **Fig 66**. This dish is called *Big Ugly Dish* or just "BUD" by their users. Only using the polar mount mechanism limits the operator in the range of motion, as previously discussed. WØLMD provides for a greater degree of articulation of these dishes through several mechanisms. One of these is a sector-gear elevation drive, shown in **Fig 67**.

For the azimuth motion of our satellite antennas, most use motorized rotator drives, mainly the commercial sources previously mentioned. Most antennas are tower-mounted, allowing the placement of the rotator inside the tower. For the large wind loads of satellite antennas, these commercial rotators become rather expensive.

High loads are also prominent with the use of BUD

Fig 65—At left, Yaesu Az-El antenna-rotator mounting system is shown. Note that antenna loads must be more carefully balanced on this rotator than in the previously shown systems. At right, VE5FP has a solution for his Az-El rotators by bolting two of them together in his "An Inexpensive Az-El Rotator System", *QST*, December 1998.

Fig 66—A TVRO dish-drive system is shown on its polar mount, using a protected drive-screw mechanism. (*WØLMD photo.*)

Fig 67—A modified TVRO dish mount is shown using an Az-El mount and a sector-gear drive for the elevation. (*WØLMD photo.*)

Fig 68—WØLMD constructed a very robust and low-cost Az drive mechanism. (*WØLMD photo.*)

antennas, and WØLMD has again engineered some very robust mechanisms using combinations of motorcycle-chain drives, V-belt drives and gear-head motors, as seen in **Fig 68**. An overall view of one of his BUD antennas is shown in **Fig 69**, showing the Az drive with an El drive that uses a jackscrew mechanism.

Operators through the years have employed many methods for the control of their antenna positions, ranging from true *arm-strong* manual positioning, to manual operation of the powered antenna azimuth and elevation rotators, to fully automated computer control of the rotators. While computer control of the rotators is not essential, life is greatly assisted with their use. For many years, one of the keystone control units for rotators has been the *Kansas City Tracker* (KCT) board installed in your computer. Most satellite-tracking programs can connect to

the KCT with ease. One difficulty with the KCT unit is that they are 8-bit digital units, providing positioning precision of 0.35° in elevation and 1.41° in azimuth. For the larger dishes, with their narrow beamwidths, these values of precision are unacceptable. There are other options to replace the KCT unit.

A recent trend for amateur antenna control has been evolving in the form of a standalone controller that translates computer antenna-position information into controller commands with an understanding of antenna-position limits. These boxes, represented by the *EasyTrak* unit, **Fig 70**, from the Tucson Amateur Packet Radio (TAPR) group, have made this capability readily available for many amateurs. This unit is a 10-bit encoder, providing precisions of 0.09° in elevation and 0.35° in azimuth. The computer can also control the operation of your station transceiver through the radio interface provided in *EasyTrak*; you will not need any other radio interface.

Other position readout and control options are available. For many years ham operators have employed synchros, or *selsyns*, for their position readouts. These are

Fig 69—A completed TVRO dish Az-El mounting system is shown, using a jackscrew elevation drive. (*WØLMD photo.*)

Fig 71—WØLMD has experimented with highly precise optical encoders for his antenna position systems. See text. (*WØLMD photo.*)

Fig 70—The EasyTrak automated antenna rotator and radio controller by TAPR. (*WD4FAB photo.*)

specialized transformers, using principles developed over sixty years ago and employed in such devices as surplus "radio compass" steering systems for aircraft. While the position readout of these devices can be quite precise, in general they only provide a visual position indication, one that is not easily adapted to computer control. I8CVS employs such a system at his station and his elevation synchro can be seen in Fig 64, using a weighted arm on the synchro to provide a constant reference to the Earth's gravity vector.

The more up-to-date, computer-friendly position readout methods used these days are usually based on preci-

sion potentiometers or digital code wheels. **Fig 71** shows such a digital code-wheel system employed by WØLMD. He notes that such systems, while providing a very high precision of angular position, they are not absolute systems and that once calibrated, they must be continually powered so they do not lose their calibration. Precision potentiometers, on the other hand, provide an absolute position reference, but with a precision that is limited to the quality of the potentiometer, typically 0.5% (0.45° in El and 1.80° in Az) to 1.0%. So the choices have their individual limits, unless a lot of money is spent for very precise commercial systems.

NOTES AND REFERENCES, SATELLITE ANTENNAS

AO-40 frequencies, "Official Transponder Frequency Bandplan for P-3D"; **www.amsat-dl.org/p3dqrg. html**.

Brown, Gerald R., K5OE, "A Helix Feed for Surplus MMDS, Antennas" *Proceedings of the 2001AMSAT-NA Symposium*, October 2001, pp 89-94, also: **members.aol.com/k5oe**.

Brown, Jerry, K5OE, "A K-Band Receiver for AO-40", *Proceedings for the AMSAT-NA Space Symposium, 2002.*

Brown, Gerald R., K5OE, "Build This No-Tune Dual-Band Feed for Mode L/S" *The AMSAT Journal*, Vol 26, No 1, Jan/Feb 2003.

Brown, Gerald R., K5OE, "Dual-Band Dish Feeds for 13/ 23 cm," *Proceedings of the 2002AMSAT-NA Symposium*, October 2002, pp 123-131.

Brown, Jerry, K5OE, **members.aol.com/k5oe/** MMDS Dishes.

Brown, Gerald R., K5OE, "Patch Feeds," **members.aol. com/k5oe**.

Brown, Jerry, K5OE, "The Texas Potato Masher: A Medium-Gain Directional Satellite Antenna For

LEOs," *The AMSAT Journal*, Vol 22, No. 1, Jan/Feb 1999.

Jansson, Dick, WD4FAB, *QST*, Sep 2002, "Product Review", "M² 23CM22EZA 1.2 GHz Antenna", p 59.

Kingery, Mike, KE4AZN, "Setting Up for AO-40 L-Band Uplink," *The AMSAT Journal*, May/Jun 2002, pp 14-16, also: **web.infoave.net/~mkmk518/**.

Koehler, Jim, VE5FP, "An Inexpensive Az-El Rotator System", *QST*, Dec 1998.

Kraus, John D., "The Helical Antenna", Chapter 7, *Antennas*, McGraw-Hill Book Company, 1988.

Kraus, John D., W8JK, "16-12, Patch or Microstrip Antennas," *Antennas,* 1988, pp 745-749.

Krome, Ed, K9EK, "Development of a Portable Mode S Ground Station." *The AMSAT Journal*, Vol 16, No. 6, Nov/Dec 1993, pp 25-28.

Krome, Ed, K9EK, "S band Reception: Building the DEM Converter and Preamp Kits," *The AMSAT Journal*, Vol 16, No. 2, Mar/Apr 1993, pp 4-6.

Krome, Ed., K9EK, *Mode S—The Book*, p 96, 109.

Krome, Ed, K9EK, "Mode S: Plug and Play!" *The AMSAT Journal*, Vol 14, No. 1, Jan 1991, pp 21-23, 25.

Long, Howard, G6LVB, "My Shack Configuration— Spring 2002": **www.g6lvb.com/g6lvb_shack_spring_ 2002.htm**.

McCaa, William D., K0RZ, "Hints on Using the AMSAT-OSCAR 13 Mode S Transponder," *The AMSAT Journal*, Vol 13, No. 1, Mar 1990, pp 21-22.

MacAllister, Andy, W5ACM, "Field Day 2002," *73 Amateur Radio Today,* Sept. 2002, pp 48-52.

Miller, James, G3RUH, "Mode S — Tomorrow's Downlink?" *The AMSAT Journal*, Vol 15, No. 4, Sep/Oct 1992, pp 14-15.

Miller, James S., G3RUH, "'Patch' Feed For S-Band Dish Antennas"; **www.jrmiller.demon.co.uk/products/ patch.html**.

Miller, James, G3RUH, "A 60-cm S-Band Dish Antenna," *The AMSAT Journal*, Vol 16 No. 2, Mar/Apr 1993, pp 7-9.

Miller, James, G3RUH, "Small is Best," *The AMSAT Journal*, Vol 16, No. 4, Jul/Aug 1993, p 12.

Monteiro, Anthony, "Work OSCAR 40 with Cardboard-box Antennas!," *QST*, Mar 2003, pp 57-62.

Orban Microwave, "The Basics of Patch Antennas: **www.orbanmicrowave.com/antenna_application_ notes.htm**.

Seguin, Mike, N1JEZ, "OSCAR 40 on 24GHz", *QST*, Dec 2002, pp 55-56.

Seydler, Robert, K5GNA,"Modifications of the AIDC 3731 Downconverters", **members.aol.com/k5gna/ AIDC3731modifications.doc**.

Suckling, Charles, G3WDG, "K-Band Results From AO-40": **www.g3wdg.free-online.co.uk/kband.htm**.

Suckling, Charles, G3WDG "Notch Filters for AO-40 Mode L/S": **www.g3wdg.free-online.co.uk.notch.htm**.

Suding, Dr. Robert, WØLMD, "Converting TVRO Dish & Dishes For Amateurs" **www.ultimatecharger.com/ dish.html**.

Thiel, David & Smith, Staphani, *Switched Parasitic Antennas for Cellular Communications*, Artech House, 2002, "Chapter 3, Patch Antennas," pp 79-96.

Wade, Paul, N1BWT (W1GHZ), *Online Microwave Antenna Handbook*, "Chapter 4, Parabolic Dish Antennas," **www.w1ghz.cx/antbook/chap4.pdf**, Mar. 98. (See CD-ROM bundled with this book.)

Zibrat,Timothy S, K3TZ, "2.4 GHz Patch Design": **www.qsl.net/k3tz/**.

Antenna Systems for EME Communications

This section was updated by David Hallidy, K2DH. As mentioned earlier, the tremendous path loss incurred over an EME circuit places stringent requirements on Earth-station performance. Low-noise receiving equipment, maximum available power and high-gain antenna arrays are required for successful EME operation. Although it is possible to copy some of the better-equipped stations with a low-gain antenna, it is unlikely that such an antenna can provide reliable two-way communications. Antenna gain of at least 20 dBi is required for reasonable EME success. Generally speaking, more antenna gain yields the most noticeable improvement in station performance, since the increased gain improves both the received and transmitted signals.

VHF/UHF EME ANTENNAS

Several types of antennas for 2 meters and 70 cm are popular among EME enthusiasts. Perhaps the most popular antenna for 144-MHz work is an array of either 4 or 8 long-boom (14 to 15 dBi gain) Yagis. The 4-Yagi array provides approximately 20 dB gain, and an 8-Yagi array gives an approximate 3 dB increase over the 4-antenna array. **Fig 72** shows the computed response at a 30° tilt above the horizon for a stack of four 14-element 2-meter Yagis, each with a boomlength of 3.1 λ (22 feet).

At 432 MHz, EME enthusiasts often use 8 or 16 long-boom Yagis in an array. Such Yagis are commercially available or they can be constructed from readily available materials. Chapter 18, VHF and UHF Antenna Systems,

has details on some popular Yagi designs.

The main disadvantage of Yagi arrays is that the polarization plane of the individual Yagis cannot be conveniently changed. One way around this is to use cross-polarized Yagis and a relay switching system to select the desired polarization, as described in the previous section. This represents a considerable increase in system complexity to select the desired polarization. Some amateurs have gone so far as to build complicated mechanical systems to allow constant polarization adjustment of all the Yagis in a large array. **Fig 73** shows the K1FO 70-cm EME 16-Yagi array with full polarization control, described in *The ARRL Antenna Compendium, Vol 3*. This 432-MHz EME array uses open-wire phasing lines to minimize feed-line losses. **Fig 74** shows the computed response for this array, which employs rugged but lightweight 14-element Yagis on 3.1 λ (7.1 foot) booms. Feed-line losses are not explicitly accounted for in the *EZNEC Professional* computer model, but are estimated to be less than 0.25 dB.

Polarization shift of EME signals at 144 MHz is fairly rapid, and the added complexity of a relay-controlled cross-polarized antenna system or a mechanical polarization adjustment scheme is probably not worth the effort. At 432 MHz, however, where the polarization shifts at a much slower rate, an adjustable polarization system does offer a definite advantage over a fixed one.

The Yagi antenna system used by Ed Stallman, N5BLZ, is shown in **Fig 75**. His system employs twelve 144-MHz long-boom 17-element Yagi antennas. The monster 48-Yagi 2-meter array of Gerald Williamson, K5GW, is shown in **Fig 76**, and the huge 48-Yagi 70-cm EME array of Frank Potts, NC1I, is shown in **Fig 77**.

Although not as popular as Yagis, Quagi antennas (made from both quad and Yagi elements) are sometimes used for EME work. Slightly more gain per unit boom length is possible as compared to the conventional Yagi,

at the expense of some robustness. Additional information on the Quagi is presented in Chapter 18, VHF and UHF Antenna Systems.

The collinear array is an older type of antenna for EME work. A 40-element collinear array has approximately

Fig 73—K1FO's variable polarization 16 × 14-element (3.6-λ boom lengths) 432-MHz EME array shown at 2° elevation and vertical polarization. (See *The ARRL Antenna Compendium, Vol 3*.)

Fig 72—*EZNEC Pro* elevation pattern for four 14-element 2-meter Yagis (3.6-λ boom lengths) at an elevation angle of 30° above the horizon. The computed system gain is 21.5 dBi, suitable for 2-meter EME. This assumes that the phasing system is made of open-wire transmission lines so that feed-line losses can be kept below 0.25 dB.

Fig 74—Computed elevation response for K1FO 16-Yagi 432-MHz array shown in Fig 73. (The *EZNEC Pro* model required 2464 segments!) With assumed phasing harness feed-line losses of 0.25 dB, the overall gain exceeds 27.5 dBi.

the same frontal area as an array of four Yagis, but produces approximately 1 to 2 dB less gain. One attraction to a collinear array is that the depth dimension is considerably less than the long-boom Yagis. An 80-element collinear is marginal for EME communications, providing approximately 19 dB gain. As with Yagi and Quagi antennas, the collinear cannot be adjusted easily for polarity changes. From a construction standpoint, there is little difference in complexity and material costs between the collinear and Yagi arrays.

DISH ANTENNAS FOR EME

On 2 meters the minimum antenna gain for reliable

EME communications is about 20 dBi. While a few amateurs have had access to parabolic dishes large enough for EME work at 144 and 222 MHz, at those frequencies an array of four long Yagis is equal in gain to a dish 24 feet in diameter! To achieve truly high-gain performance from a dish on 2 meters would require a reflector diameter of nearly 96 feet (providing 32 dBi gain). Such undertakings are generally beyond amateur means, so there has been little work done with dishes at low frequencies, except for the occasional expedition to one of the large radio telescopes that have accommodated amateur EME work.

Microwave Parabolic Dish Antennas

The major problems associated with parabolic dish antennas are mechanical ones. A dish of about 16 feet in diameter is the minimum size required for successful EME operation on 432 MHz. With wind and ice loading, structures of this size place a real strain on the mounting and positioning system. Extremely rugged mounts are required for large dish antennas, especially when used in windy locations. **Fig 78** shows the impressive 7-meter diameter

Fig 75—The EME array used at N5BLZ consists of twelve long-boom 144-MHz Yagis. The tractor, lower left, really puts this array into perspective! (*Photo courtesy N5BLZ.*)

Fig 76—K5GW's huge 48-Yagi 2-meter EME array. (*Photo courtesy K5GW.*)

Fig 77—NC1I's magnificent 48-Yagi 70-cm EME array. (*Photo courtesy NC1I.*)

dish built by David Wardley, ZL1BJQ.

Several aspects of parabolic dish antennas make the extra mechanical problems worth the trouble, however. For example, the dish antenna is inherently broadband, and may be used on several different amateur bands by simply changing the feed. An antenna that is suitable for 432 MHz work will most likely be usable on several of the higher amateur bands too. Increased gain is available as the frequency of operation is increased.

Another advantage of a dish is the flexibility of the feed system. The polarization of the feed, and therefore the polarization of the antenna, can be changed with little difficulty. It is a relatively easy matter to devise a system to rotate the feed remotely from the shack to change polarization. Because polarization changes can account for as much as 30 dB of signal attenuation, the rotatable feed can make the difference between consistent communications and no communications at all. Further information on Parabolic Antennas can be found in Chapter 18, VHF and UHF Antenna Systems as well as in the section below.

A 12-FOOT STRESSED HOMEBREW PARABOLIC DISH

Very few antennas evoke as much interest among UHF amateurs as the parabolic dish, and for good reason. First, the parabola and its cousins—Cassegrain, hog horn and Gregorian—are probably the ultimate in high-gain antennas. One of the highest-gain antennas in the world (148 dB) is a parabola. This is the 200-inch Mt. Palomar telescope. (The very short wavelength of light rays causes such a high gain to be realizable.)

Second, the efficiency of the parabola does not change as size increases. With Yagis and collinear arrays, the losses in the phasing harness increase as the array size increases. The corresponding component of the parabola is lossless air between the feed horn and the reflecting surface. If there are a few surface errors, the efficiency of the system stays constant regardless of antenna size. This project was presented by Richard Knadle, K2RIW, in August 1972 *QST*.

Some amateurs reject parabolic antennas because of the belief that they are all heavy, hard-to-construct, have large wind-loading surfaces and require precise surface accuracy. However, with modern construction techniques, a prudent choice of materials and an understanding of accuracy requirements, these disadvantages can be largely overcome. A parabola may be constructed with a 0.6 f/D (focal length/diameter) ratio, producing a rather flat dish, which makes it easy to surface and allows the use of recent advances in high-efficiency feed horns. This results in greater gain for a given dish size over conventional designs.

Such an antenna is shown in **Fig 79**. This parabolic dish is lightweight, portable, easy to build, and can be used for 432 and 1296-MHz mountain topping, as well as on 2304, 3456 and 5760 MHz. Disassembled, it fits into the trunk of a car, and can be assembled in 45 minutes.

The usually heavy structure that supports the surface of most parabolic dish antennas has been replaced in this design by aluminum spokes bent into a near parabolic shape by string. These strings serve the triple function of guying the focal point, bending the spokes and reducing the error at the dish perimeter (as well as at the center) to nearly zero. By contrast, in conventional designs, the dish perimeter (which has a greater surface area than the center) is farthest from the supporting center hub. For these reasons, it often has the greatest error. This error becomes more severe when the wind blows.

Here, each of the spokes is basically a cantilevered beam with end loading. The equations of beam bending

Fig 78—ZL1BJQ's homemade 7-meter (23-foot) parabolic dish, just prior to adding $1/2$-inch wire mesh. (*Photo courtesy ZL1BJQ.*)

Fig 79—A 12-foot stressed parabolic dish set up for satellite signals near 2280 MHz. A preamplifier is shown taped below the feed horn. The dish was designed by K2RIW, standing at the right. From *QST*, August 1972.

predict a near-perfect parabolic curve for extremely small deflections. Unfortunately the deflections in this dish are not that small and the loading is not perpendicular. For these reasons, mathematical prediction of the resultant curve is quite difficult. A much better solution is to measure the surface error with a template and make the necessary correction by bending each of the spokes to fit. This procedure is discussed later.

The uncorrected surface is accurate enough for 432 and 1296-MHz use. Trophies taken by this parabola in antenna-gain contests were won using a completely natural surface with no error correction. By placing the transmission line inside the central pipe that supports the feed horn, the area of the shadows or blockages on the reflector surface is much smaller than in other feeding and supporting systems, thus increasing gain. For 1296 MHz, a back-fire feed horn may be constructed to take full advantage of this feature. At 432 MHz, a dipole and reflector assembly produces 1.5 dB additional gain over a corner-reflector feed system. Because the preamplifier is located right at the horn on 2300 MHz, a conventional feed horn may be used.

Construction

Table 2 is a list of materials required for construction. Care must be exercised when drilling holes in the connecting center plates so assembly problems will not be experienced later. See **Fig 80**. A notch in each plate allows them to be assembled in the same relative positions. The two plates should be clamped together and drilled at the

Fig 80—Center plate details. Two center plates are bolted together to hold the spokes in place.

same time. Each of the 18$\frac{1}{2}$-inch diameter aluminum spokes has two no. 28 holes drilled at the base to accept no. 6-32 machine screws that go through the center plates. The 6-foot long spokes are cut from standard 12-foot lengths of tubing. A fixture built from a block of aluminum assures that the holes are drilled in exactly the same position in each spoke. The front and back center plates constitute an I-beam type of structure that gives the dish center considerable rigidity.

A side view of the complete antenna is shown in **Fig 81**. Aluminum alloy (6061-T6) is used for the spokes, while 2024-T3 aluminum alloy sheet, $\frac{1}{8}$ inch thick, is used for the center plates. (Aluminum has approximately three times the strength-to-weight ratio of wood, and aluminum cannot warp or become water logged.) The end of each of the 18 spokes has an eyebolt facing the dish focal point, which serves a dual purpose:

1) To accept the #9 galvanized fence wire that is routed through the screw eyes to define the dish perimeter, and

2) To facilitate rapid assembly by accepting the S hooks which are tied to the end of each of the lengths of 130-pound test Dacron fishing string.

The string bends the spokes into a parabolic curve; the dish may be adapted for many focal lengths by tightening or slackening the strings. Dacron was chosen because it has the same chemical formula as Mylar. This is a low-stretch material that keeps the dish from changing shape. The galvanized perimeter wire has a 5-inch overlap area that is bound together with baling wire after the spokes have been hooked to the strings.

The aluminum window screening is bent over the perimeter wire to hold it in place on the back of the spokes. Originally, there was concern that the surface perturbations (the spokes) in front of the screening might decrease the gain. The total spoke area is so small, however, that

---

Table 2

Materials List for the 12-Foot Stressed Parabolic Dish

1) Aluminum tubing, 12 ft × $\frac{1}{2}$ in. OD × 0.049-in. wall, 6061-T6 alloy, 9 required to make 18 spokes.

2) Octagonal mounting plates 12 × 12 × $\frac{1}{8}$ in., 2024-T3 alloy, 2 required.

3) 1$\frac{1}{4}$ in. ID pipe flange with setscrews.

4) 1$\frac{1}{4}$ in. × 8 ft TV mast tubing, 2 required.

5) Aluminum window screening, 4 × 50 ft.

6) 130-pound test Dacron trolling line.

7) 38 ft #9 galvanized fence wire (perimeter).

8) Two hose clamps, 1$\frac{1}{2}$ in.; two U bolts; $\frac{1}{2}$ × 14 in. Bakelite rod or dowel; water-pipe grounding clamp; 18 eye bolts; 18 S hooks.

Fig 81—Side view of the stressed parabolic dish.

Diagram labels:
- U Bolts
- 12' 3"
- 7' 6-1/4"
- 1/2" X 14" Bakelite Rod Support
- Hose Clamp Over Rubber Sheet to Prevent Slippage
- Transmission Line
- 1296 MHz Dual Mode Feed Horn
- 6'
- 6' 6"
- 7' 2"
- 130 Pound Test Dacron Trolling Line
- S Hook
- Screw Eye

this fear proved unfounded.

Placing the aluminum screening in front of the spokes requires the use of 200 pieces of baling wire to hold the screening in place. This would increase the assembly time by at least an hour. For contest and mountaintop operation (when the screening is on the back of the spokes) no fastening technique is required other than bending the screen to overlap the wire perimeter.

The Parabolic Surface

A 4-foot wide roll of aluminum screening 50 feet long is cut into appropriate lengths and laid parallel, with a 3-inch overlap between the top of the unbent spokes and hub assembly. The overlap seams are sewn together on one half of the dish using heavy Dacron thread and a sailmaker's curved needle. Every seam is sewn twice; once on each edge of the overlapped area. The seams on the other half are left open to accommodate the increased overlap that occurs when the spokes are bent into a parabola. The perimeter of the screening is then trimmed. Notches are cut in the 3-inch overlap to accept the screw eyes and S hooks.

The first time the dish is assembled, the screening strips are anchored to the inside surface of the dish and the seams sewn in this position. It is easier to fabricate the surface by placing the screen on the back of the dish frame

with the structure inverted. The spokes are sufficiently strong to support the complete weight of the dish when the perimeter is resting on the ground.

The 4-foot wide strips of aluminum screening conform to the compound bend of the parabolic shape very easily. If the seams are placed parallel to the E-field polarization of the feed horn, minimum feedthrough will occur. This feedthrough, even if the seams are placed perpendicular to the E field, is so small that it is negligible. Some constructors may be tempted to cut the screening into pie-shaped sections. This procedure will increase the seam area and construction time considerably. The dish surface appears most pleasing from the front when the screening perimeter is slipped between the spokes and the perimeter wire, and is then folded back over the perimeter wire. In disassembly, the screening is removed in one piece, folded in half, and rolled.

The Horn and Support Structure

The feed horn is supported by $1^{1}/_{4}$-inch aluminum television mast. The Hardline that is inserted into this tubing is connected first to the front of the feed horn, which then slides back into the tubing for support. A setscrew assures that no further movement of the feed horn occurs. During antenna-gain competition the setscrew is omit-

Fig 82—Backfire type 1296-MHz feed horn, linear polarization only. The small can is a Quaker State oil container; the large can is a 50-pound shortening container (obtained from a restaurant, Gold Crisp brand). Brass tubing, $^{1}/_{2}$-inch OD extends from UG-23 connector to dipole. Center conductor and dielectric are obtained from $^{3}/_{8}$-inch Alumafoam coaxial cable. The dipole is made from 3/32-inch copper rod. The septum and 30° section are made from galvanized sheet metal. Styrofoam is used to hold the septum in position. The primary gain is 12.2 dBi.

ted, allowing the $^{1}/_{2}$-inch semirigid CATV transmission line to move in or out while adjusting the focal length for maximum gain. The TV mast is held firmly at the center plates by two setscrews in the pipe flange that is mounted on the rear plate. At 2300 MHz, the dish is focused for best gain by loosening these setscrews on the pipe flange and sliding the dish along the TV mast tubing. (The dish is moved instead of the feed horn.)

The fishing strings are held in place by attaching them to a hose clamp that is permanently connected to the TV tubing. A piece of rubber sheet under the hose clamp prevents slippage and keeps the hose clamp from cutting the fishing string. A second hose clamp is mounted below the first as extra protection against slippage.

The high-efficiency 1296-MHz dual mode feed horn, detailed in **Fig 82**, weighs 5$^{3}/_{4}$ pounds. This weight causes some bending of the mast tubing, but this is corrected by a $^{1}/_{2}$-inch diameter bakelite support, as shown in Fig 81. This support is mounted to a pipe grounding clamp with a no. 8-32 screw inserted in the end of the rod. The bakelite rod and grounding clamp are mounted midway between the hose clamp and the center plates on the mast. A double run of fishing string slipped over the notched upper end of the bakelite rod counteracts bending.

The success of high-efficiency parabolic antennas is primarily determined by feed horn effectiveness. The multiple diameter of this feed horn may seem unusual. This patented dual-mode feed, designed by Dick Turrin, W2IMU, achieves efficiency by launching two different kinds of waveguide modes simultaneously. This causes the dish illumination to be more constant than conventional designs.

Illumination drops off rapidly at the perimeter, reduc-

ing spillover. The feed backlobes are reduced by at least 35 dB because the current at the feed perimeter is almost zero; the phase center of the feed system stays constant across the angles of the dish reflector. The larger diameter section is a phase corrector and should not be changed in length. In theory, almost no increase in dish efficiency can be achieved without increasing the feed size in a way that would increase complexity, as well as blockage.

The feed is optimized for a 0.6 f/D dish. The dimensions of the feeds are slightly modified from the original design in order to accommodate the cans. Either feed type can be constructed for other frequencies by changing the scale of all dimensions.

Multiband Use

Many amateurs construct multiband antenna arrays by putting two dishes back to back on the same tower. This is cost inefficient. The parabolic reflector is a completely frequency independent surface, and studies have shown that a 0.6 f/D surface can be steered seven beamwidths by moving the feed horn from side to side before the gain diminishes by 1 dB. Therefore, the best dual-band antenna can be built by mounting separate horns side by side. At worst, the antenna may have to be moved a few degrees (usually less than a beamwidth) when switching between horns, and the unused horn increases the shadow area only slightly. In fact, the same surface can function simultaneously on multiple frequencies, making crossband duplex operation possible with the same dish.

Order of Assembly

1) A single spoke is held upright behind the rear center plate with the screw eye facing forward. Two no. 6-

32 machine screws are pushed through the holes in the rear center plate, through the two holes of the spoke, and into the corresponding holes of the front center plate. Lock washers and nuts are placed on the machine screws and hand tightened.

2) The remaining spokes are placed between the machine screw holes. Make sure that each screw eye faces forward. Machine screws, lock washers and nuts are used to mount all 18 spokes.

3) The no. 6-32 nuts are tightened using a nut driver.

4) The mast tubing is attached to the spoke assembly, positioned properly, and locked down with the setscrews on the pipe flange at the rear center plate. The S hooks of the 18 Dacron strings are attached to the screw eyes of the spokes.

5) The ends of two pieces of fishing string (which go over the bakelite rod support) are tied to a screw eye at the forward center plate.

6) The dish is laid on the ground in an upright position and #9 galvanized wire is threaded through the eyebolts. The overlapping ends are lashed together with baling wire.

7) The dish is placed on the ground in an inverted position with the focus downward. The screening is placed on the back of the dish and the screening perimeter is fastened as previously described.

8) The extension mast tubing (with counterweight) is connected to the center plate with U bolts.

9) The dish is mounted on a support and the transmission line is routed through the tubing and attached to the horn.

Parabola Gain Versus Errors

How accurate must a parabolic surface be? This is a frequently asked question. According to the Rayleigh limit for telescopes, little gain increase is realized by making the mirror accuracy greater than $\pm\, {}^1\!/_8\, \lambda$ peak error. John Ruze of the MIT Lincoln Laboratory, among others, has derived an equation for parabolic antennas and built models to verify it. The tests show that the tolerance loss can be predicted within a fraction of a decibel, and less than 1 dB of gain is sacrificed with a surface error of $\pm {}^1\!/_8\, \lambda$. (A ${}^1\!/_8\, \lambda$ is 3.4 inches at 432 MHz, 1.1 inches at 1296 MHz and 0.64 inch at 2300 MHz.)

Some confusion about requirements of greater than ${}^1\!/_8$-λ accuracy may be the result of technical literature describing highly accurate surfaces. Low sidelobe levels are the primary interest in such designs. Forward gain is a much greater concern than low sidelobe levels in amateur work; therefore, these stringent requirements do not apply.

When a template is held up against a surface, positive and negative ($\pm$) peak errors can be measured. The graphs of dish accuracy requirements are frequently plotted in terms of RMS error, which is a mathematically derived function much smaller than $\pm$ peak error (typically ${}^1\!/_3$). These small RMS accuracy requirements have discouraged many constructors who confuse them with $\pm$ peak errors.

Fig 83 may be used to predict the resultant gain of various dish sizes with typical errors. There are a couple of surprises, as shown in **Fig 84**. As the frequency is increased for a given dish, the gain increases 6 dB per octave until the tolerance errors become significant. Gain deterioration then increases rapidly. Maximum gain is realized at the frequency where the tolerance loss is 4.3 dB. Notice that at 2304 MHz, a 24-foot dish with ±2-inch peak errors has the same gain as a 6-foot dish with ±1-inch peak errors. This is quite startling, when it is realized that a 24-foot dish has 16 times the area of a 6-foot dish. Each time the diameter or frequency is doubled or halved, the gain changes by 6 dB. Each time all the errors are halved, the frequency of maximum gain is doubled. With this information, the gain of other dish sizes with other tolerances can be predicted.

These curves are adequate for predicting gain, assuming a high-efficiency feed horn is used (as described earlier), which realizes 60% aperture efficiency. At frequencies below 1296 MHz where the horn is large and causes considerable blockage, the curves are somewhat optimistic. A properly built dipole and splasher feed will have about 1.5 dB less gain when used with a 0.6 f/D dish than the dual-mode feed system described.

The worst kind of surface distortion is where the surface curve in the radial direction is not parabolic but gradually departs in a smooth manner from a perfect parabola. The decrease in gain can be severe, because a large area is involved. If the surface is checked with a template, and if reasonable construction techniques are employed, deviations are controlled and the curves represent an upper limit to the gain that can be realized.

If a 24-foot dish with ±2-inch peak errors is being used with 432 and 1296-MHz multiple feed horns, the constructor might be discouraged from trying a 2300-MHz feed because there is 15 dB of gain degradation. The dish will still have 29 dBi of gain on 2300 MHz, however, making it worthy of consideration.

The near-field range of this 12-foot stressed dish (actually 12 feet 3 inches) is 703 feet at 2300 MHz. By using the sun as a noise source and observing receiver noise power, it was found that the antenna had two main lobes about 4° apart. The template showed a surface error (insufficient spoke bending at ${}^3\!/_4$ radius), and a correction was made. A recheck showed one main lobe, and the solar noise was almost 3 dB stronger.

Other Surfacing Materials

The choice of surface materials is a compromise between RF reflecting properties and wind loading. Aluminum screening, with its very fine mesh (and weight of 4.3 pounds per 100 square feet) is useful beyond 10 GHz because of its very close spacing. This screening is easy to roll up and is therefore ideal for a portable dish. This close spacing causes the screen to be a 34% filled aperture, bring-

Fig 83—Gain deterioration versus reflector error. By Richard Knadle, K2RIW.

ing the wind force at 60 mph to more than 400 *pounds* on this 12-foot dish. Those considering a permanent installation of this dish should investigate other surfacing materials.

Hexagonal 1-inch poultry netting (chicken wire), which is an 8% filled aperture, is nearly ideal for 432-MHz operation. It weighs 10 pounds per 100 square feet, and exhibits only 81 pounds of force with 60 mph winds. Measurement on a large piece reveals 6 dB of feedthrough at 1296 MHz, however. Therefore, on 1296 MHz, one fourth of the power will feed through the surface material. This will cause a loss of only 1.3 dB of forward gain. Since the low-wind loading material will provide a 30-dBi gain potential, it is still a very good tradeoff.

Poultry netting is very poor material for 2300 MHz and above, because the hole dimensions approach $^1/_2\,\lambda$. As with all surfacing materials, minimum feedthrough occurs when the E-field polarization is parallel to the longest dimension of the surfacing holes.

Hardware cloth with $^1/_2$-inch mesh weighs 20 pounds per 100 square feet and has a wind loading characteristic of 162 pounds with 60 mph winds. The filled aperture is 16%, and this material is useful to 2300 MHz.

A rather interesting material worthy of investigation

is $^1/_4$-inch reinforced plastic. It weighs only 4 pounds per 100 square feet. The plastic melts with many universal solvents such as lacquer thinner. If a careful plastic-melting job is done, what remains is the $^1/_4$-inch spaced aluminum wires with a small blob of plastic at each junction to hold the matrix together.

There are some general considerations to be made in selecting surface materials:

1) Joints of screening do not have to make electrical contact. The horizontal wires reflect the horizontal wave. Skew polarizations are merely a combination of horizontal and vertical components which are thus reflected by the corresponding wires of the screening. To a horizontally polarized wave, the spacing and diameter of only the horizontal wires determine the reflection coefficient (see **Fig 85**). Many amateurs have the mistaken impression that screening materials that do not make electrical contact at their junctions are poor reflectors.

2) By measuring wire diameter and spacings between the wires, a calculation of percentage of aperture that is filled can be made. This will be one of the major determining factors of wind pressure when the surfacing material is dry.

Fig 84—Parabolic-antenna gain versus size, frequency and surface errors. All curves assume 60% aperture efficiency and 10-dB power taper. Graph by K2RIW for ham bands, using display technique of J. Ruze, British IEE.

Fig 85—Surfacing material quality.

A Parabolic Template

At and above 2300 MHz (where high surface accuracy is required), a parabolic template should be constructed to measure surface errors. A simple template may be constructed (see **Fig 86**) by taking a 12-foot 3-inch length of 4-foot wide tar paper and drawing a parabolic shape on it with chalk. The points for the parabolic shape

are calculated at 6-inch intervals and these points are connected with a smooth curve. For those who wish to use the template with the surface material installed, the template should be cut along the chalk line and stiffened by cardboard or a wood lattice frame. Surface error measurements should take place with all spokes installed and deflected by the fishing lines, as some bending of the center plates does take place. **Fig 87** shows the 12-foot stressed dish built by Franco Marcelo, N2UO.

Variations

All the possibilities of the stressed parabolic antenna have not been explored. For instance, a set of fishing lines or guy wires can be set up behind the dish for error correction, as long as this does not cause permanent bending of the aluminum spokes. This technique also protects the dish against wind loading from the rear. An extended piece of TV mast is an ideal place to hang a counterweight and attach the rear guys. This strengthens the structure considerably.

EME USING SURPLUS TVRO DISH ANTENNAS

Since the 1990s, there has been a significant change

Fig 86—Parabolic template for 12-foot, 3-inch dish.

$$X^2 = 4fZ \text{ (Parabola)}$$
$$f = \text{Focal Length} = 7'2''$$

Z

f Focus

One-Half Parabolic Curve

10-7/16"

X

5'

6' 1-1/2"

X	Z	(to Nearest 1/16")	X	Z
0.5'	1/8"		3.5'	5-1/8"
1.0'	7/16"		4.0'	6-11/16"
1.5'	15/16"		4.5'	8-1/2"
2.0'	1-11/16"		5.0'	10-7/16"
2.5'	2-5/8"		5.5'	12-11/16"
3.0'	3-3/4"		6.0'	15-1/16"

Fig 87—N2UO's homemade 12-foot stressed dish. (*Photo courtesy N2UO.*)

in the systems people use to watch satellite TV broadcasts. Formerly, C-band satellite receivers were used, along with parabolic dish antennas in the 3- to 5-meter diameter range. Now, Ku-band (12-GHz) receivers are the norm, with their associated small (usually 18-inch) dish antennas. This has provided a large body of surplus C-band dishes, which can be used for EME—certainly on the bands at 33 cm and above, and for the larger dishes (5 meters), even at 70 cm. Many times, these dishes and their mounts can be had for the asking, so they truly become an inexpensive way to build a multi-band EME antenna.

This updated article, first presented by David Hallidy, K2DH (ex-KD5RO) in the ARRL *UHF/Microwave Projects Manual*, describes the use of a 3-meter (10-foot) TVRO antenna in such an application. (Also see earlier in this chapter the section describing converted C-Band TVRO Dishes for satellite work.)

Background

Calculations show that a 3-meter dish will have about 30 dBi gain at 1296 MHz. With a state-of-the-art LNA (Low-Noise Amplifier or preamp) at the feed, an efficient feed horn illuminating the dish surface, and 200 W at 1296 MHz, lunar echoes should be easily detected and many stations can be worked. The biggest challenges to such a system are assembling the dish to its mount and steering it to track the Moon. As much as possible, the KISS ("Keep It Simple, Stupid") principle was used to accomplish this task.

In 1987, WA5TNY, KD5RO, KA5JPD, and W7CNK proved that such an EME system could work, even as high as 3.4 and 5.7 GHz, to provide the first EME contacts on those bands. An additional advantage to this (or any) small

dish is its ability to be mounted to a trailer and taken out on EME expeditions. It can also be easily disassembled and stored, if necessary.

As can be seen from **Fig 88**, the entire setup is very simple, using a standard amateur tower as the main support for the dish.

Azimuth Drive

In azimuth, direct drive of the main rotating shaft was selected, and a small prop-pitch motor was used. These motors, while not as plentiful as they were some years ago, still turn up with some regularity at flea markets for very little money. The beauty of the prop-pitch motor is that it turns slowly, is reversible, provides very high torque, and requires no braking system (the gear reduction, on the order of 4000:1, provides the necessary braking). Prop-pitch motors are dc motors, and were designed to vary the pitch of propeller blades at start-up, take-off and landing of older large airplanes. Thus, they can be run at different speeds merely by varying the dc voltage to the motor, and can be reversed by reversing the polarity of the dc voltage. By mounting a thrust bearing of the appropriate size at the top of the tower, and mounting the motor directly below it at the end of the rotating shaft that turns the antenna, a simple direct-drive system can be constructed.

The dc power supply and control relays are located in a weatherproof box on the side of the tower, next to the motor. This system requires only 9 V dc at about 5 A to adequately start, turn and stop the prop-pitch motor, and this voltage turns the antenna through 360° of rotation in about $2^{1}/_{2}$ minutes. Azimuth position sensing is also a simple task. See **Fig 89**. A linear multi-turn potentiometer is driven by the rotating shaft, using a simple friction drive.

A strip of rubber is attached to the rotating shaft and a wheel is connected to the shaft of the pot. The pot is then mounted so that it presses against the rubber strip, and as the shaft turns so does the pot. If a ten-turn pot is used, and the system is aligned such that the pot is at the center of its rotation when the antenna is pointed approximately south, the pot will not rotate past the end at either extreme of the antenna's rotation (CW/CCW north), and absolute alignment is a simple task of calibrating the change in resistance (change in voltage, when the pot is fed from a constant voltage source) with degrees of rotation (see the discussion on Position Readout for details).

Elevation Drive

The elevation drive is also very simple. Most (nearly all) TVRO setups have a means of moving the dish across the sky to align it with various satellites. To do this, most companies use a device called a *Linear Actuator*. This is a dc motor to which is attached a long lead screw that pulls (or pushes) the outer shell of the actuator in or out to make it longer or shorter. The movable end of the actuator is attached to the dish and the motor end is fixed to the mount. The dish rests on pivots, which allow it to move as the actuator extends/retracts. To convert this type of mount (called a *Polar Mount*) to an Az/El mount is usually very simple.

Fig 90 shows how this can be done. Simply breaking the welds that held the mount in a polar fashion allows the mount to be turned on its side and used to pivot the dish vertically with the linear actuator. Another feature of linear actuators is that they also have some means of feeding their relative position to the satellite receiver. This is usually just a multi-turn potentiometer geared to the lead screw. All we have to do is connect this pot to a readout system, and we can calibrate the lift of the actuator in degrees. We thus have a simple means of rotating the dish and elevating it—but how do we know that it's pointed at the Moon?

Position Readout

Readout of the position of the antenna, in both azimuth and elevation is also a relatively simple task. On the

Fig 88—View of K2DH's (ex-KD5RO) complete TVRO antenna installation. (*K2DH photo.*)

Fig 89—Azimuth rotation systems, showing prop-pitch motor and position sensor.

Fig 90—Elevation system, showing modified TVRO mount.

surplus market there are available Digital Volt Meters (DVMs) using LED or LCD displays that can do this job nicely, and that have more precision than is probably necessary for a dish (or Yagi array) of small size. As mentioned earlier, a multi-turn potentiometer on the elevation-drive mechanism can be used to readout elevation, and the same technique can be used for azimuth readout—a potentiometer coupled to the main rotating shaft that turns the antenna.

When using a pot for readout, the most important thing to know is how many degrees of antenna position change occur (in Az or El) for each turn of the pot. This then can be used to calibrate a voltmeter to read volts directly as degrees—for example, 3.60 V could correspond to 360° azimuth (Clockwise North), and 9.0 V could correspond

Fig 91—Schematic diagram of the dish control system. The Datel DM-LX3 is a digital meter, used to indicate azimuth and elevation angles.

to 90° elevation (straight up).

A resistance bridge circuit is best used in this application, since it is less sensitive to changes in the supply voltage. The only thing to be careful about is that the DVM must have both the positive (high) and negative (low) inputs isolated from ground (assuming the power supply used to power the DVM is grounded). You could also use a pair of small, cheap Digital Multi-Meters (DMMs), which can sometimes be found for under $10. Because they are battery powered, the isolation issue just discussed is eliminated.

Please see **Fig 91** for a complete schematic of the azimuth, elevation and readout electronics for this antenna-drive system. Also note that while this discussion is geared towards the use of a small dish, the same positioning and readout systems could be used in a Yagi array for 2 meters or 70 cm.

Now that we know where the dish is pointed, how do we know where the Moon is? There are several software programs available to the Amateur for tracking celestial bodies such as the Moon, the Sun, certain stars (usable as noise sources), and even Amateur Satellites. Programs by W9IP, VK3UM, F1EHN and others can be obtained very reasonably and these work well to provide highly accurate position information for tracking.

Feeding the Surplus TVRO Dish

An area that needs particular attention when attempting EME with a small dish is an efficient feed system. An efficient feed system can be a real challenge with TVRO dishes, because many are "deep"—that is, their f/D (focal length to Diameter ratio) is small.

The satellite TV industry used deep dishes because they tend to be quieter, picking up less Earth noise due to spillover effects. A deep dish has a short focal length, and therefore, the feed is relatively close to the surface of the dish. To properly illuminate the reflector out to its edges, a feed horn of relatively wide beamwidth must be used. The feeds designed several years ago by Barry Malowanchuk, VE4MA, are intended for use with just such dishes, and have the advantage of being adjustable to optimize their pattern to the dish in use.

The feed that was used with this dish was modeled after VE4MA's 1296-MHz feed, and a version was even scaled for use at 2304 MHz that worked as well as the original. See **Fig 92** and also see the Notes and References section at the end of this chapter. (Also see the earlier section in the satellite portion of this chapter describing patch feeds for small dishes.)

SHF EME CHALLENGES

The challenges met when successfully building a station for EME at 900 MHz to 5.7 GHz only become more significant on the SHF bands at 10 GHz and above. Absolute attention to detail is the primary requirement, and this extends to every aspect of the EME antenna sys-

Fig 92—View of feed, showing coffee-can feed horn and hybrid coupler.

tem. The dish surface is probably the most difficult problem to solve. As was discussed earlier in this chapter, the shape and accuracy of the reflector contribute directly to the overall gain of the antenna.

But where slight errors in construction can be tolerated at the lower frequencies, the same cannot be said at millimetric wavelengths. Those who have attempted EME on 10 and 24 GHz have discovered that the weight of the dish reflector itself will distort its shape enough to lower the gain to the point where echoes are degraded. Stiffening structures at the back of such dishes are often found necessary. **Fig 93** illustrates the back struts added by Al Ward, W5LUA, to strengthen his dish.

Pointing accuracy is also paramount—a 16-foot dish at 10 GHz has a beamwidth about equal to the diameter of the Moon—0.5°. This means that the echo degradation due to the Moon's movement away from where the dish is pointed is almost immediate, and autotracking systems become more of a necessity than a luxury. At these frequencies, most amateurs actually peak their antennas on

Fig 93—Strengthening struts W5LUA added to the back of his dish to hold down distortion. (*Photo courtesy W5LUA.*)

Moon Noise—the black-body Radiation from the Moon that becomes the dominant source of noise in space.

At these frequencies, the elevation of the Moon above the horizon also plays a role in the ability to communicate, since tropospheric absorption due to water vapor is greatest at low elevation angles (the signal must pass through a greater portion of the troposphere than when the Moon is highly elevated). It is beyond the abilities of most Amateurs to construct their own dishes for these frequencies, so surplus dishes for Ku-band satellite TV (typically 3 meters in diameter) are usually employed, as have high-performance dishes designed for millimetric radar and point-to-point communications at 23 and 38 GHz.

NOTES AND REFERENCES, EME ANTENNAS

W. Allen, "A Mode J Helix," *AMSAT Newsletter*, Jun 1979, pp 30-31.

D. J. Angelakos and D. Kajfez, "Modifications on the Axial-Mode Helical Antenna," *Proc. IEEE*, Apr 1967, pp 558-559.

A. L. Bridges, "Really Zap OSCAR With this Helical Antenna," *73*, in three parts, Jul, Aug and Sep 1975.

K. R. Carver, "The Helicone—A Circularly Polarized Antenna with Low Sidelobe Level," *Proc. IEEE*, Apr 1967, p 559.

M. R. Davidoff, "A Simple 146-MHz Antenna for Oscar Ground Stations," *QST*, Sep 1974, pp 11-13.

M. R. Davidoff, *The Radio Amateur's Satellite Handbook* (Newington: ARRL, 1998-2000).

D. DeMaw, "The Basic Helical Beam," *QST*, Nov 1965, pp 20-25, 170.

D. Evans and G. Jessop, *VHF-UHF Manual, 3rd ed.* (London: RSGB), 1976.

N. Foot, "WA9HUV 12-Foot Dish for 432 and 1296 MHz," The World Above 50 Mc., *QST*, Jun 1971, pp 98-101, 107.

N. Foot, "Cylindrical Feed horn for Parabolic Reflectors," *Ham Radio*, May 1976.

O. J. Glasser and J. D. Kraus, "Measured Impedances of Helical Beam Antennas," *Journal of Applied Physics*, Feb 1948, pp 193-197.

D. Hallidy, "Microwave EME Using A Ten-Foot TVRO Antenna," *The ARRL UHF/Microwave Projects Manual*, 1994 pp 10-9 to 10-13.

G. R. Isely and W. G. Smith, "A Helical Antenna for Space Shuttle Communications," *QST*, Dec 1984, pp 14-18.

H. Jasik, *Antenna Engineering Handbook*, 1st ed. (New York: McGraw-Hill, 1961).

R. T. Knadle, "A Twelve-Foot Stressed Parabolic Dish," *QST*, Aug 1972, pp 16-22.

J. D. Kraus, "Helical Beam Antenna," *Electronics*, Apr 1947, pp 109-111.

J. D. Kraus and J. C. Williamson, "Characteristics of Helical Antennas Radiating in the Axial Mode," *Journal of Applied Physics*, Jan 1948, pp 87-96.

J. D. Kraus, "Helical Beam Antenna for Wide Band Applications," *Proc of the IRE*, Oct 1948, pp 1236-1242.

J. D. Kraus, *Antennas* (New York: McGraw-Hill Book Co., 1950).

J. D. Kraus, "A 50-Ohm Input Impedance for Helical Beam Antenna," *IEEE Transactions on Antennas and Propagation*, Nov 1977, p 913.

J. D. Kraus, *Big Ear* (Powell, OH: Cygnus-Quasar Books, 1976).

T. S. M. MacLean, "Measurements on High-Gain Helical Aerial and on Helicals of Triangular Section," *Proc. of IEE* (London), Jul 1964, pp 1267-1270.

D. M. Mallozzi, "The Tailored Helical," *AMSAT Newsletter*, Mar 1978, pp 8-9.

B. Malowanchuk, "Use of Small TVRO Dishes for EME," *Proceedings of the 21st Conference of The Central States VHF Society*, 1987 pp 68-77.

B. Malowanchuk, "Selection of An Optimum Dish Feed," *Proceedings of the 23rd Conference of The Central States VHF Society*, 1989 pp 35-43.

M. W. Maxwell, *Reflections—Transmission Lines and Antennas* (Newington, CT: ARRL, 1990) [out of print].

T. Moreno, *Microwave Transmission Design Data* (New York: McGraw-Hill, 1948).

K. Nose, "Crossed Yagi Antennas for Circular Polarization," *QST*, Jan 1973, pp 11-12.

K. Nose, "A Simple Az-El Antenna System for Oscar," *QST*, Jun 1973, pp 11-12.

S. Powlishen, K1FO, "432-MHz EME 1990s Style," Parts 1 and 2, *Communications Quarterly*, Oct 1990, pp 29-39; Oct 1991, pp 33-48.

S. Powlishen, K1FO, "Rear-Mount Yagi Arrays for 432-MHz EME: Solving the EME Polarization Problem," *The ARRL Antenna Compendium, Vol 3* (Newington:

ARRL, 1992), pp 79-98.

C. Richards, "The 10 Turn Chopstick Helical (Mk2) for OSCAR 10 432 MHz Uplink," *Radio Communication*, Oct 1984, pp 844-845.

S. Sander and D. K. Cheng, "Phase Center of Helical Beam Antennas," *IRE National Convention Record Part 6*, 1958, pp 152-157.

E. A. Scott and H. E. Banta, "Using the Helical Antenna at 1215 Mc.," *QST*, Jul 1962, pp 14-16.

R. Soifer, W2RS, "More 'QRP' EME on 144 MHz," *QST*, Oct 1990, pp 36-38.

G. Southworth, *Principles and Applications of Waveguide Transmission* (New York: D. Van Nostrand Co., 1950).

B. Sykes, "Circular Polarization and Crossed-Yagi Antennas," Technical Topics, *Radio Communication*, Feb 1985, p 114.

H. E. Taylor and D. Fowler, "A V-H-F Helical Beam Antenna," *CQ*, Apr 1949, pp 13-16.

G. Tillitson, "The Polarization Diplexer—A Polaplexer," *Ham Radio*, Mar 1977.

P. P. Viezbicke, "Yagi Antenna Design," *NBS Technical Note 688* (U. S. Dept. of Commerce/National Bureau of Standards, Boulder, CO), Dec 1976.

D. Vilardi, "Easily Constructed Antennas for 1296 MHz," *QST*, Jun 1969.

D. Vilardi, "Simple and Efficient Feed for Parabolic Antennas," *QST*, Mar 1973.

J. L. Wong and H. E. King, "Broadband Quasi-Tapered Helical Antenna," *IEEE Transactions on Antennas and Propagation*, Jan 1979, pp 72-78.

Chapter 20

Antenna Materials and Accessories

This chapter contains information on materials amateurs use to construct antennas—what types of material to look for in a particular application, tips on working with and using various materials. Chapter 21 contains information on where to purchase these materials.

Basically, antennas for MF, HF, VHF and the lower UHF range consist simply of one or more conductors that radiate (or receive) electromagnetic waves. However, an antenna system must also include some means to support those conductors and maintain their relative positions—the boom for a Yagi antenna and the halyards for a wire

dipole, for example. In this chapter we'll look at materials for those applications, too. Structural supports such as towers, masts, poles, etc. are discussed in Chapter 22.

There are two main types of material used for antenna conductors, wire and tubing. Wire antennas are generally simple and therefore easier to construct, although some arrays of wire elements can become rather complex. When tubing is required, aluminum tubing is used most often because of its light weight. Aluminum tubing is discussed in a subsequent section of this chapter.

Wire Antennas

Although wire antennas are relatively simple, they can constitute a potential hazard unless properly constructed. Antennas should never be run under or over public utility (telephone or power) lines. Several amateurs have lost their lives by failing to observe this precaution.

The National Electric Code® of the National Fire Protection Association contains a section on amateur stations in which a number of recommendations are made concerning minimum size of antenna wire and the manner of bringing the transmission line into the station. Chapter 1 contains more information about this code. The code in itself does not have the force of law, but it is frequently made a part of local building regulations, which are enforceable. The provisions of the code may also be written into, or referred to, in fire and liability insurance documents.

The RF resistance of copper wire increases as the size of the wire decreases. However, in most types of antennas that are commonly constructed of wire (even quite small wire), the radiation resistance will be much higher than the RF resistance, and the efficiency of the antenna will still be adequate. Wire sizes as small as #30, or even

smaller, have been used quite successfully in the construction of "invisible" antennas in areas where more conventional antennas cannot be erected. In most cases, the selection of wire for an antenna will be based primarily on the physical properties of the wire, since the suspension of wire from elevated supports places a strain on the wire.

WIRE TYPES

Wire having an enamel coating is preferable to bare wire, since the coating resists oxidation and corrosion. Several types of wire having this type of coating are available, depending on the strength needed. "Soft-drawn" or annealed copper wire is easiest to handle; unfortunately, it stretches considerably under stress. Soft-drawn wire should be avoided, except for applications where the wire will be under little or no tension, or where some change in length can be tolerated. (For example, the length of a horizontal antenna fed at the center with open-wire line is not critical, although a change in length may require some readjustment of coupling to the transmitter.)

"Hard-drawn" copper wire or copper-clad steel wire

(also known as Copperweld™) is harder to handle, because it has a tendency to spiral when it is unrolled. These types of wire are ideal for applications where significant stretch cannot be tolerated. Care should be exercised in using this wire to make sure that kinks do not develop—the wire will have a far greater tendency to break at a kink. After the coil has been unwound, suspend the wire a few feet above ground for a day or two before using it. The wire should not be recoiled before it is installed.

Several factors influence the choice of wire type and size. Most important to consider are the length of the unsupported span, the amount of sag that can be tolerated, the stability of the supports under wind pressure, and whether or not an unsupported transmission line is to be suspended from the span. **Table 1** shows the wire diam, current-carrying capacity and resistance of various sizes of copper wire. **Table 2** shows the maximum rated working tensions of hard-drawn and copper-clad steel wire of various sizes. These two tables can be used to select the appropriate wire size for an antenna.

Table 1
Copper-Wire Table

Wire Size AWG (B&S)	Dia in Mils[1]	Dia in mm	Turns per Linear Inch Enamel	Feet per Pound Bare	Ohms per 1000 ft 25°C	Cont.-duty current[2] Single Wire in Open Air
1	289.3	7.348	—	3.947	0.1264	—
2	257.6	6.544	—	4.977	0.1593	—
3	229.4	5.827	—	6.276	0.2009	—
4	204.3	5.189	—	7.914	0.2533	—
5	181.9	4.621	—	9.980	0.3195	—
6	162.0	4.115	—	12.58	0.4028	—
7	144.3	3.665	—	15.87	0.5080	—
8	128.5	3.264	7.6	20.01	0.6405	73
9	114.4	2.906	8.6	25.23	0.8077	—
10	101.9	2.588	9.6	31.82	1.018	55
11	90.7	2.305	10.7	40.12	1.284	—
12	80.8	2.053	12.0	50.59	1.619	41
13	72.0	1.828	13.5	63.80	2.042	—
14	64.1	1.628	15.0	80.44	2.575	32
15	57.1	1.450	16.8	101.4	3.247	—
16	50.8	1.291	18.9	127.9	4.094	22
17	45.3	1.150	21.2	161.3	5.163	—
18	40.3	1.024	23.6	203.4	6.510	16
19	35.9	0.912	26.4	256.5	8.210	—
20	32.0	0.812	29.4	323.4	10.35	11
21	28.5	0.723	33.1	407.8	13.05	—
22	25.3	0.644	37.0	514.2	16.46	—
23	22.6	0.573	41.3	648.4	20.76	—
24	20.1	0.511	46.3	817.7	26.17	—
25	17.9	0.455	51.7	1031	33.00	—
26	15.9	0.405	58.0	1300	41.62	—
27	14.2	0.361	64.9	1639	52.48	—
28	12.6	0.321	72.7	2067	66.17	—
29	11.3	0.286	81.6	2607	83.44	—
30	10.0	0.255	90.5	3287	105.2	—
31	8.9	0.227	101	4145	132.7	—
32	8.0	0.202	113	5227	167.3	—
33	7.1	0.180	127	6591	211.0	—
34	6.3	0.160	143	8310	266.0	—
35	5.6	0.143	158	10480	335	—
36	5.0	0.127	175	13210	423	—
37	4.5	0.113	198	16660	533	—
38	4.0	0.101	224	21010	673	—
39	3.5	0.090	248	26500	848	—
40	3.1	0.080	282	33410	1070	—

[1]A mil is 0.001 inch.
[2]Max wire temp of 212° F and max ambient temp of 135° F.

Table 2
Stressed Antenna Wire

American Wire Gauge	Recommended Tension[1] (pounds)		Weight (pounds per 1000 feet)	
	Copper-clad steel[2]	Hard-drawn copper	Copper-clad steel[2]	Hard-drawn copper
4	495	214	115.8	126.0
6	310	130	72.9	79.5
8	195	84	45.5	50.0
10	120	52	28.8	31.4
12	75	32	18.1	19.8
14	50	20	11.4	12.4
16	31	13	7.1	7.8
18	19	8	4.5	4.9
20	12	5	2.8	3.1

[1]Approximately one-tenth the breaking load. Might be increased 50% if end supports are firm and there is no danger of ice loading.
[2]Copperweld,™ 40% copper.

Wire Tension

If the tension on a wire can be adjusted to a known value, the expected sag of the wire (**Fig 1**) may be determined before installation using Table 2 and the nomograph of **Fig 2**. Even though there may be no convenient method to determine the tension in pounds, calculation of the expected sag for practicable working tensions is often desirable. If the calculated sag is greater than allowable it may be reduced by any one or a combination of the following:

1) Providing additional supports, thereby decreasing the span
2) Increasing the tension in the wire if less than recommended
3) Decreasing the size of the wire

Instructions for Using the Nomograph

1) From Table 2, find the weight (pounds/1000 feet) for the particular wire size and material to be used.
2) Draw a line from the value obtained above, plotted on the weight axis, to the desired span (feet) on the span axis, Fig 2. Note in Fig 1 that the span is one half the distance between the supports.
3) Choose an operating tension level (in pounds) consistent with the values presented in Table 2 (preferably less than the recommended wire tension).
4) Draw a line from the tension value chosen (plotted on the tension axis) through the point where the work axis crosses the original line constructed in step 2, and continue this new line to the sag axis.
5) Read the sag in feet on the sag axis.

Example:

Weight = 11 pounds/1000 feet
Span = 210 feet
Tension = 50 pounds
Answer: Sag = 4.7 feet

These calculations do not take into account the weight of a feed line supported by the antenna wire.

Wire Splicing

Wire antennas should preferably be made with unbroken lengths of wire. In instances where this is not feasible, wire sections should be spliced as shown in **Fig 3**. The enamel insulation should be removed for a distance of about 6 inches from the end of each section by scraping with a knife or rubbing with sandpaper until the copper underneath is bright. The turns of wire should be brought up tight around the standing part of the wire by twisting with broad-nose pliers.

The crevices formed by the wire should be completely filled with rosin-core solder. An ordinary soldering iron or gun may not provide sufficient heat to melt solder outdoors; a propane torch is desirable. The joint should be heated sufficiently so the solder flows freely into the joint when the source of heat is removed momentarily. After the joint has cooled completely, it should be wiped clean with a cloth, and then sprayed generously with acrylic to prevent corrosion.

Fig 1—The half span and sag of a long-wire antenna.

Fig 2—Nomograph for determining wire sag. (John Elengo, Jr, K1AFR)

Fig 3—Correct method of splicing antenna wire. Solder should be flowed into the wraps after the connection is completed. After cooling, the joint should be sprayed with acrylic to prevent oxidation and corrosion.

ANTENNA INSULATION

To prevent loss of RF power, the antenna should be well insulated from ground, unless of course it is a shunt-fed system. This is particularly important at the outer end or ends of wire antennas, since these points are always at a comparatively high RF potential. If an antenna is to be installed indoors (in an attic, for instance) the antenna may be suspended directly from the wood rafters without additional insulation, if the wood is permanently dry. Much greater care should be given to the selection of proper insulators when the antenna is located outside where it is exposed to wet weather.

Insulator Leakage

Antenna insulators should be made of material that will not absorb moisture. The best insulators for antenna use are made of glass or glazed porcelain. Depending on the type of material, plastic insulators may be suitable. The length of an insulator relative to its surface area is indicative of its comparative insulating ability. A long thin insulator will have less leakage than a short thick insulator. Some antenna insulators are deeply ribbed to increase the surface leakage path without increasing the physical length of the insulator. Shorter insulators can be used at low-potential points, such as at the center of a dipole. If such an antenna is to be fed with open-wire line and used on several bands, however, the center insulator should be the same as those used at the ends, because high RF potential may exist across the center insulator on some bands.

Insulator Stress

As with the antenna wire, the insulator must have sufficient physical strength to support the stress of the antenna without danger of breakage. Long elastic bands or lengths of nylon fishing line provide long leakage paths and make satisfactory insulators within their limits to resist mechanical strain. They are often used in antennas of the "invisible" type mentioned earlier.

For low-power work with short antennas not subject to appreciable stress, almost any small glass or glazed-porcelain insulator will do. Homemade insulators of Lucite rod or sheet will also be satisfactory. More care is required in the selection of insulators for longer spans and higher transmitter power.

For a given material, the breaking tension of an insulator will be proportional to its cross-sectional area. It should be remembered, however, that the wire hole at the end of the insulator decreases the effective cross-sectional area. For this reason, insulators designed to carry heavy strains are fitted with heavy metal end caps, the eyes being formed in the metal cap, rather than in the insulating material itself. The following stress ratings of antenna insulators are typical:

$^5/_8$ in. square by 4 in. long—400 lb
1 in. diameter by 7 or 12 in. long—800 lb
$1^1/_2$ in. diameter by 8, 12 or 20 in. long, with special metal end caps—5000 lb

These are rated breaking tensions. The actual working tensions should be limited to not more than 25% of the breaking rating.

The antenna wire should be attached to the insulators as shown in **Fig 4**. Care should be taken to avoid sharp angular bends in the wire when it is looped through the insulator eye. The loop should be generous enough in size that it will not bind the end of the insulator tightly. If the

length of the antenna is critical, the length should be measured to the outward end of the loop, where it passes through the eye of the insulator. The soldering should be done as described earlier for the wire splice.

Strain Insulators

Strain insulators have their holes at right angles, since they are designed to be connected as shown in **Fig 5**. It can be seen that this arrangement places the insulating material under compression, rather than tension. An insulator connected this way can withstand much greater stress. Furthermore, the wire will not collapse if the insulator breaks, since the two wire loops are inter-locked. Because the wire is wrapped around the insulator, however, the leakage path is reduced drastically, and the capacitance between the wire loops provides an additional leakage path. For this reason, the use of the strain insulator is usually confined to such applications as breaking up resonances in guy wires, where high levels of stress prevail, and where the RF insulation is of less importance. Such insulators might be suitable for use at low-potential points on an antenna, such as at the center of a dipole. These insulators may also be fastened in the conventional manner if the wire will not be under sufficient tension to break out the eyes.

Insulators for Ribbon-Line Antennas

Fig 6A shows the sketch of an insulator designed to be used at the ends of a folded dipole or a multiple dipole made of ribbon line. It should be made approximately as shown, out of Lucite or bakelite material about $1/4$ inch thick. The advantage of this arrangement is that the strain of the antenna is shared by the conductors and the plastic webbing of the ribbon, which adds considerable strength. After soldering, the screw should be sprayed with acrylic.

Fig 6B shows a similar arrangement for suspending one dipole from another in a stagger-tuned dipole system. If better insulation is desired, these insulators can be wired to a conventional insulator.

PULLEYS AND HALYARDS

Pulleys and halyards commonly used to raise and lower a wire antenna must also be capable of taking the

Fig 4—When fastening antenna wire to an insulator, do not make the wire loop too snug. After the connection is complete, flow solder into the turns. Then when the joint has cooled completely, spray it with acrylic.

Fig 5—Conventional manner of fastening wire to a strain insulator. This method decreases the leakage path and increases capacitance, as discussed in the text.

Fig 6—At A, an insulator for the ends of folded dipoles, or multiple dipoles made of 300-ohm ribbon. At B, a method of suspending one ribbon dipole from another in a multiband dipole system.

same strain as the antenna wire and insulators. Unfortunately, little specific information on the stress ratings of most pulleys is available. Several types of pulleys are readily available at almost any hardware store. Among these are small galvanized pulleys designed for awnings and several styles and sizes of clothesline pulleys. Heavier and stronger pulleys are those used in marine work. The factors that determine how much stress a pulley will handle include the diameter of the shaft, how securely the shaft is fitted into the sheath and the size and material of the frame.

Another important factor to be considered in the selection of a pulley is its ability to resist corrosion. Galvanized awning pulleys are probably the most susceptible to corrosion. While the frame or sheath usually stands up well, these pulleys usually fail at the shaft. The shaft rusts out, allowing the grooved wheel to break away under tension.

Most good-quality clothesline pulleys are made of alloys which do not corrode readily. Since they are designed to carry at least 50 feet of line loaded with wet clothing in stiff winds, they should be adequate for normal spans of 100 to 150 feet between stable supports. One type of clothesline pulley has a 4-inch diameter plastic wheel with a ¼-inch shaft running in bronze bearings. The sheath is made of cast or forged corrosion-proof alloy. Some look-alike low-cost pulleys of this type have an aluminum shaft with no bearings. For antenna work, these cheap pulleys are of little long-term value.

Marine pulleys have good weather-resisting qualities, since they are usually made of bronze, but they are comparatively expensive and are not designed to carry heavy loads. For extremely long spans, the wood-sheathed pulleys used in "block and tackle" devices and for sail hoisting should work well.

Halyards

Table 3 shows the recommended maximum tensions for various sizes and types of line and rope suitable for hoisting halyards. Probably the best type for general amateur use for spans up to 150 or 200 feet is ¼-inch nylon rope. Nylon is somewhat more expensive than ordinary rope of the same size, but it weathers much better. Nylon also has a certain amount of elasticity to accommodate gusts of wind, and is particularly recommended for antennas using trees as supports. A disadvantage of new nylon rope is that it stretches by a significant percentage. After an installation with new rope, it will be necessary to repeatedly take up the slack created by stretching. This process will continue over a period of several weeks, at which time most of the stretching will have taken place. Even a year after installation, however, some slack may still arise from stretching.

Most types of synthetic rope are slippery, and some types of knots ordinarily used for rope will not hold well. **Fig 7** shows a knot that should hold well, even in nylon rope or plastic line.

For exceptionally long spans, stranded galvanized steel sash cord makes a suitable support. Cable advertised as "wire rope" usually does not weather well. A boat winch, sold at marinas and at Sears, is a great convenience in antenna hoisting (and usually a necessity with metal halyards).

Table 3
Approximate Safe Working Tension for Various Halyard Materials

Material	Dia, In.	Tension, Lb
Manila hemp rope	1/4	120
	3/8	270
	1/2	530
	5/8	800
Polypropylene rope	1/4	270
	3/8	530
	1/2	840
Nylon rope	1/4	300
	3/8	660
	1/2	1140
7×11 galvanized sash cord	1/16	30
	1/8	125
	3/16	250
	1/4	450
High-strength stranded galvanized steel guy wire	1/8	400
	3/16	700
	1/4	1200
Rayon-filled plastic clothesline	7/32	60 to 70

Fig 7—This is one type of knot that will hold with smooth rope, such as nylon. Shown at A, the knot for splicing two ends. B shows the use of a similar knot in forming a loop, as might be needed for attaching an insulator to a halyard. Knot A is first formed loosely 10 or 12 in. from the end of the rope; then the end is passed through the eye of the insulator and knot A. Knot B is then formed and both knots pulled tight. (Richard Carruthers, K7HDB)

Antennas of Aluminum Tubing

Aluminum is a malleable, ductile metal with a mass density of 2.70 grams per cubic centimeter. The density of aluminum is approximately 35% that of iron and 30% that of copper. Aluminum can be polished to a high brightness, and it will retain this polish in dry air. In the presence of moisture, aluminum forms an oxide coating (Al_2O_3) that protects the metal from further corrosion. Direct contact with certain metals, however (especially ferrous metals such as iron or steel), in an outdoor environment can bring about galvanic corrosion of aluminum and its alloys. Some protective coating should be applied to any point of contact between two dissimilar metals. Much of this information about aluminum and aluminum tubing was prepared by Ralph Shaw, K5CAV.

Aluminum is non-toxic; it is used in cooking utensils and to hold and cover "TV dinners" and other frozen foods, so it is certainly safe to work with. The ease with which it can be drilled or sawed makes it a pleasure to work with. Aluminum products lend themselves to many and varied applications.

Aluminum alloys can be used to build amateur antennas, as well as for towers and supports. Light weight and high conductivity make aluminum ideal for these applications. Alloying lowers the conductivity ratings, but the tensile strength can be increased by alloying aluminum with one or more metals such as manganese, silicon, copper, magnesium or zinc. Cold rolling can be employed to further increase the strength.

A four-digit system is used to identify aluminum alloys, such as 6061. Aluminum alloys starting with a 6 contain di-magnesium silicide (Mg_2Si). The second digit indicates modifications of the original alloy or impurity limits. The last two digits designate different aluminum alloys within the category indicated by the first digit.

In the 6000 series, the 6061 and 6063 alloys are a commonly used for antenna applications. Both types have good resistance to corrosion and medium strength. A further designation like T-6 denotes thermal treatment (heat tempering). More information on the available aluminum alloys can be found in **Table 4**.

SELECTING ALUMINUM TUBING

Table 5 shows the standard sizes of aluminum tubing that are stocked by most aluminum suppliers or distributors in the United States and Canada. Note that all tubing comes in 12-foot lengths (local hardware stores sometimes stock 6- and 8-foot lengths) and larger-diameter sizes may be available in lengths up to 24 feet. Note also that any diameter tubing will fit snugly into the next larger size, if the larger size has a 0.058-inch wall thickness. For example, $5/8$-inch tubing has an outside diameter of 0.625 inch. This will fit into $3/4$-inch tubing with a 0.058-inch wall, which has an inside diameter of 0.634 inch.

Table 4
Aluminum Numbers for Amateur Use

Common Alloy Numbers

Type	Characteristic
2024	Good formability, high strength
5052	Excellent surface finish, excellent corrosion resistance, normally not heat treatable for high strength
6061	Good machinability, good weldability
6063	Good machinability, good weldability
7075	Good formability, high strength

Common Tempers

Type	Characteristics
T0	Special soft condition
T3	Hard
T6	Hardest, possibly brittle
TXXX	Three digit tempers—usually specialized high strength heat treatments, similar to T6

General Uses

Type	Uses
2024-T3	Chassis boxes, antennas, anything that will be bent or
7075-T3	Flexed repeatedly
6061-T6	Tubing and pipe; angle channel and bar stock
6063-T832	Tubing and pipe; angle channel and bar stock

A clearance of 0.009 inch is just right for a slip fit or for slotting the tubing and then using hose clamps. Always get the next larger size and specify a 0.058-inch wall to obtain the 0.009-inch clearance.

A little figuring with Table 5 will give you all the information you need to build a beam, including what the antenna will weigh. The 6061-T6 type of aluminum has a relatively high strength and has good workability. It is highly resistant to corrosion and will bend without taking a "set."

SOURCES FOR ALUMINUM

Aluminum can be purchased new, and suppliers are listed in Chapter 21. But don't overlook the local metal scrap yard. The price varies, but between 35 and 60 cents per pound is typical for scrap aluminum. Some aluminum items to look for include aluminum vaulting poles, tent poles, tubing and fittings from scrapped citizen's band antennas, and aluminum angle stock. The scrap yard may even have a section or two of triangular aluminum tower.

Aluminum vaulting poles are 12 or 14 feet long and range in diameter from $1^1/2$ to $1^3/4$ inches. These poles are suitable for the center-element sections of large 14-MHz beams or as booms for smaller antennas. Tent poles range in length from 2½ to 4 feet. The tent poles are

Table 5
Aluminum Tubing Sizes
6061-T6 (61S-T6) Round Aluminum Tube In 12-Foot Lengths

Tubing Diameter	Wall Thickness		ID, Inches	Approximate Weight	
	Inches	Stubs Ga.		Pounds Per Foot	Pounds Per Length
3/16 in.	0.035	(#20)	0.117	0.019	0.228
	0.049	(#18)	0.089	0.025	0.330
1/4 in.	0.035	(#20)	0.180	0.027	0.324
	0.049	(#18)	0.152	0.036	0.432
	0.058	(#17)	0.134	0.041	0.492
5/16 in.	0.035	(#20)	0.242	0.036	0.432
	0.049	(#18)	0.214	0.047	0.564
	0.058	(#17)	0.196	0.055	0.660
3/8 in.	0.035	(#20)	0.305	0.043	0.516
	0.049	(#18)	0.277	0.060	0.720
	0.058	(#17)	0.259	0.068	0.816
	0.065	(#16)	0.245	0.074	0.888
7/16 in.	0.035	(#20)	0.367	0.051	0.612
	0.049	(#18)	0.339	0.070	0.840
	0.065	(#16)	0.307	0.089	1.068
1/2 in.	0.028	(#22)	0.444	0.049	0.588
	0.035	(#20)	0.430	0.059	0.708
	0.049	(#18)	0.402	0.082	0.984
	0.058	(#17)	0.384	0.095	1.040
	0.065	(#16)	0.370	0.107	1.284
5/8 in.	0.028	(#22)	0.569	0.061	0.732
	0.035	(#20)	0.555	0.075	0.900
	0.049	(#18)	0.527	0.106	1.272
	0.058	(#17)	0.509	0.121	1.452
	0.065	(#16)	0.495	0.137	1.644
3/4 in.	0.035	(#20)	0.680	0.091	1.092
	0.049	(#18)	0.652	0.125	1.500
	0.058	(#17)	0.634	0.148	1.776
	0.065	(#16)	0.620	0.160	1.920
	0.083	(#14)	0.584	0.204	2.448
7/8 in.	0.035	(#20)	0.805	0.108	1.308
	0.049	(#18)	0.777	0.151	1.810
	0.058	(#17)	0.759	0.175	2.100
	0.065	(#16)	0.745	0.199	2.399
1 in.	0.035	(#20)	0.930	0.123	1.476
	0.049	(#18)	0.902	0.170	2.040
	0.058	(#17)	0.884	0.202	2.424
	0.065	(#16)	0.870	0.220	2.640

Tubing Diameter	Wall Thickness		ID, Inches	Approximate Weight	
	Inches	Stubs Ga.		Pounds Per Foot	Pounds Per Length
	0.083	(#14)	0.834	0.281	3.372
1 1/8 in.	0.035	(#20)	1.055	0.139	1.668
	0.058	(#17)	1.009	0.228	2.736
1 1/4 in.	0.035	(#20)	1.180	0.155	1.860
	0.049	(#18)	1.152	0.210	2.520
	0.058	(#17)	1.134	0.256	3.072
	0.065	(#16)	1.120	0.284	3.408
	0.083	(#14)	1.084	0.357	4.284
1 3/8 in.	0.035	(#20)	1.305	0.173	2.076
	0.058	(#17)	1.259	0.282	3.384
1 1/2 in.	0.035	(#20)	1.430	0.180	2.160
	0.049	(#18)	1.402	0.260	3.120
	0.058	(#17)	1.384	0.309	3.708
	0.065	(#16)	1.370	0.344	4.128
	0.083	(#14)	1.334	0.434	5.208
	*0.125	1/8 in.	1.250	0.630	7.416
	*0.250	1/4 in.	1.000	1.150	14.832
1 5/8 in.	0.035	(#20)	1.555	0.206	2.472
	0.058	(#17)	1.509	0.336	4.032
1 3/4 in.	0.058	(#17)	1.634	0.363	4.356
	0.083	(#14)	1.584	0.510	6.120
1 7/8 in.	0.058	(#17)	1.759	0.389	4.668
2 in.	0.049	(#18)	1.902	0.350	4.200
	0.065	(#16)	1.870	0.450	5.400
	0.083	(#14)	1.834	0.590	7.080
	*0.125	1/8 in.	1.750	0.870	9.960
	*0.250	1/4 in.	1.500	1.620	19.920
2 1/4 in.	0.049	(#18)	2.152	0.398	4.776
	0.065	(#16)	2.120	0.520	6.240
	0.083	(#14)	2.084	0.660	7.920
2 1/2 in.	0.065	(#16)	2.370	0.587	7.044
	0.083	(#14)	2.334	0.740	8.880
	*0.125	1/8 in.	2.250	1.100	12.720
	*0.250	1/4 in.	2.000	2.080	25.440
3 in.	0.065	(#16)	2.870	0.710	8.520
	*0.125	1/8 in.	2.700	1.330	15.600
	*0.250	1/4 in.	2.500	2.540	31.200

*These sizes are extruded. All other sizes are drawn tubes.

usually tapered; they can be split on the larger end and then mated with the smaller end of another pole of the same diameter. A small stainless-steel hose clamp (sometimes also available at scrap yards!) can be used to fasten the poles at this junction. A 14- or 21-MHz element can be constructed from several tent poles in this fashion. If a longer continuous piece of tubing is available, it can be used for the center section to decrease the number of junctions and clamps.

Other aluminum scrap is sometimes available, such as US Army aluminum mast sections designated AB-85/GRA-4 (J&H Smith Mfg). These are 3 foot sections with a 1 5/8 inch diameter. The ends are swaged so they can be assembled one into another. These are ideal for making a portable mast for a 144-MHz beam or for Field Day applications.

CONSTRUCTION WITH ALUMINUM TUBING

Most antennas built for frequencies of 14 MHz and above are made to be rotated. Constructing a rotatable antenna requires materials that are strong, lightweight and easy to obtain. The materials required to build a suitable antenna will vary, depending on many factors. Perhaps the most important factor that determines the type of hardware needed is the weather conditions normally encountered.

High winds usually don't cause as much damage to an antenna as does ice, especially ice along with high winds. Aluminum element and boom sizes should be selected so the various sections of tubing will telescope to provide the necessary total length.

The boom size for a rotatable Yagi or quad should be selected to provide stability to the entire system. The best diameter for the boom depends on several factors; most important are the element weight, number of elements and overall length. Tubing of 1-¼-inch diameter can easily support three-element 28-MHz arrays and perhaps a two-element 21-MHz system. A 2-inch diameter boom will be adequate for larger 28-MHz antennas or for harsh weather conditions, and for antennas up to three elements on 14 MHz or four elements on 21 MHz. It is not recommended that 2-inch diameter booms be made any longer than 24 feet unless additional support is given to reduce both vertical and horizontal bending forces. Suitable rein-forcement for a long 2-inch boom can consist of a truss or a truss and lateral support, as shown in **Fig 8**.

A boom length of 24 feet is about the point where a 3-inch diameter begins to be very worthwhile. This dimension provides a considerable improvement in overall mechanical stability as well as increased clamping surface area for element hardware. Clamping surface area is extremely important if heavy icing is common and rotation of elements around the boom is to be avoided. Pinning an element to the boom with a large bolt helps in this regard. On smaller diameter booms, however, the elements sometimes work loose and tend to elongate the pinning holes in both the element and the boom. After some time the elements shift their positions slightly (sometimes from day to day!) and give a rather ragged appearance to the system, even though this doesn't generally harm the

Fig 8—A long boom needs both vertical and horizontal support. The cross bar mounted above the boom can support a double truss to help keep the antenna in position.

electrical performance.

A 3-inch diameter boom with a wall thickness of 0.065 inch is satisfactory for antennas up to about a five-element, 14-MHz array that is spaced on a 40-foot long boom. A truss is recommended for any boom longer than 24 feet.

There is no RF voltage at the center of a parasitic element, so no insulation is required in mounting elements that are centered on the boom (driven elements excepted). This is true whether the boom is metal or a nonconducting material. Metal booms have a small "shortening effect" on elements that run through them. With materials sizes commonly employed, this is not more than one percent of the element length, and may not be noticeable in many applications. It is just perceptible with $1/2$-inch tubing booms used on 432 MHz, for example. Design-formula lengths can be used as given, if the matching is adjusted in the frequency range one expects to use. The center frequency of an all-metal array will tend to be 0.5 to 1 percent higher than a similar system built of wooden supporting members.

Element Assembly

While the maximum safe length of an antenna element depends to some extent on its diameter, the only laws that specify the minimum diameter of an element are the laws of nature. That is, the element must be rugged enough to survive whatever weather conditions it will encounter.

Fig 9 shows tapered Yagi element designs that will survive winds in excess of 80 mi/h. With a $1/4$-inch thick-ness of radial ice, these designs will withstand winds up to approximately 60 mi/h. (Ice increases the wind area but does not increase the strength of the element.) More rugged designs are shown in **Fig 10**. With no ice loading, these elements will survive in 120-mi/h winds, and in winds exceeding 85 mi/h with $1/4$ inch of radial ice. If you lose an antenna made with elements like these, you'll have plenty of company among your neighbors with commercially made antennas!

Figs 9 and 10 show only half elements. When the element is assembled, the largest size tubing for each element should be double the length shown in the drawing, with its center being the point of attachment to the boom. These designs are somewhat conservative, in that they are self-resonant slightly below the frequency indicated for each design. Telescoping the outside end sections to shorter lengths for resonance will increase the survival wind speeds. Conversely, lengthening the outside end sections will reduce the survival wind speeds. [See Bibliography listing for David Leeson (W6NL, ex-W6QHS) at the end of this chapter.]

Fig 11 shows several methods of fastening antenna element sections together. The slot and hose clamp method shown in Fig 11A is probably the best for joints where adjustments are required. Generally, one adjustable joint per element half is sufficient to tune the antenna. Stainless-steel hose clamps (beware—some "stainless

Fig 9—Half-element designs for Yagi antennas. The other side of the element is identical, and the center section should be a single piece twice as long as the length shown here for the largest diameter section. Use 0.058-in.-wall aluminum tubing throughout. Broken lines indicate double tubing thickness, where one tube is inserted into another. The overlap insertion depth into a tube two sizes larger, where shown, should be at least two inches. Maximum survival wind speeds without ice are shown adjacent to each design; values enclosed in parentheses are survival speeds for ¼ inch of radial ice.

28 MHz
36″   67″   Approx Length
5/8″   1/2″   OD
96 (68) mi/hr

24.9 MHz
48″   68″   Approx Length
5/8″   1/2″   OD
85 (61) mi/hr

21 MHz
24″   36″   79″   Approx Length
3/4″   5/8″   1/2″   OD
86 (61) mi/hr

18.1 MHz
42″   36″   83″   Approx Length
3/4″   5/8″   1/2″   OD
83 (59) mi/hr

14 MHz
48″   48″   42″   72″   Approx Length
7/8″   3/4″   5/8″   1/2″   OD
82 (60) mi/hr

Fig 10—A more rugged schedule of taper proportions for Yagi half-elements than Fig 9. See the Fig 9 caption for details. Table 5 gives details of aluminum tubing sizes.

28 MHz
24″   18″   62″   Approx Length
3/4″   5/8″   1/2″   OD
125 (88) mi/hr

24.9 MHz
36″   18″   63″   Approx Length
3/4″   5/8″   1/2″   OD
123 (87) mi/hr

21 MHz
30″   36″   18″   57″   Approx Length
7/8″   3/4″   5/8″   1/2″   OD
124 (90) mi/hr

18.1 MHz
24″   24″   36″   24″   55″   Approx Length
1″   7/8″   3/4″   5/8″   1/2″   OD
123 (89) mi/hr

14 MHz
1−1/8″ OD Tubing Inside
48″   24″   20″   42″   20″   59″   Approx Length
1−1/4″   1″   7/8″   3/4″   5/8″   1/2″   OD
122 (89) mi/hr

Fig 11—Methods of connecting telescoping tubing sections to build beam elements. See text for a discussion of each method.

Table 6
Hose-Clamp Diameters

| Size No. | Clamp Diameter (In.) | |
	Min	Max
06	$7/16$	$7/8$
08	$7/16$	1
10	$1/2$	$1 1/8$
12	$5/8$	$1 1/4$
16	$3/4$	$1 1/2$
20	$7/8$	$1 3/4$
24	$1 1/8$	2
28	$1 3/8$	$2 1/4$
32	$1 5/8$	$2 1/2$
36	$1 7/8$	$2 3/4$
40	$2 1/8$	3
44	$2 5/16$	$3 1/4$
48	$2 5/8$	$3 1/2$
52	$2 7/8$	$3 3/4$
56	$3 1/8$	4
64	$3 1/2$	$4 1/2$
72	4	5
80	$4 1/2$	$5 1/2$
88	$5 1/8$	6
96	$5 5/8$	$6 1/2$
104	$6 1/8$	7

steel" models do not have a stainless screw and will rust) are recommended for longest antenna life. **Table 6** shows available hose-clamp sizes.

Figs 11B, 11C and 11D show possible fastening methods for joints that do not require adjustment. At B, machine screws and nuts hold the elements in place. At C, sheet metal screws are used. At D, rivets secure the tubing. If the antenna is to be assembled permanently, rivets are the best choice. Once in place, they are permanent. They will never work free, regardless of vibration or wind. If aluminum rivets with aluminum mandrels are used, they will never rust. In addition, there is no danger of dissimilar-metal corrosion with aluminum rivets and aluminum antenna elements. If the antenna is to be disassembled and moved periodically, either B or C will work. If machine screws are used, however, take all possible precautions to keep the nuts from vibrating free. Use lock washers, lock nuts and flexible sealant such as silicone bathtub sealant to keep the hardware in place.

Very strong elements can be made by using a double thickness of tubing, made by telescoping one size inside another for the total length. This is usually done at the center of an element where more element strength is desired at at the boom support point, as in the 14-MHz element in Fig 10. Other materials can be used as well, such as wood dowels, fiberglass rods, and so forth.

In each case where a smaller diameter length of tubing is telescoped inside a larger diameter one, it's a good idea to coat the inside of the joint with Penetrox or a similar substance to ensure a good electrical bond. Antenna elements have a tendency to vibrate when they are mounted on a tower, and one way to dampen the vibrations is by running a piece of clothesline rope through the length of the element. Cap or tape the end of the element to secure the clothesline. If mechanical requirements dictate (a U-bolt going through the center of the element,

for instance), the clothesline may be cut into two pieces.

Antennas for 50 MHz need not have elements larger than $1/2$-inch diameter, although up to 1 inch is used occasionally. At 144 and 220 MHz the elements are usually $1/8$ to $1/4$ inch in diameter. For 420 MHz, elements as small as $1/16$ inch diameter work well, if made of stiff rod. Aluminum welding rod of $3/32$ to $1/8$ inch diameter is fine for 420-MHz arrays, and $1/8$ inch or larger is good for the 220-MHz band. Aluminum rod or hard-drawn wire works well at 144 MHz.

Tubing sizes recommended in the paragraph above are usable with most formula dimensions for VHF/UHF antennas. Larger diameters broaden the frequency response; smaller ones sharpen it. Much smaller diameters than those recommended will require longer elements, especially in 50-MHz arrays.

Element Taper and Electrical Length

The builder should be aware of one important aspect of telescoping or tapered elements. When the element diameters are tapered, as shown in Figs 9 and 10, the electrical length is not the same as it would be for a cylindrical element of the same total length. Length corrections for tapered elements are discussed in Chapter 2.

Other Materials for Antenna Construction

Wood is very useful in antenna work. It is available in a great variety of shapes and sizes. Rug poles of wood or bamboo make fine booms. Bamboo is quite satisfactory for spreaders in quad antennas.

Round wood stock (doweling) is found in many hardware stores in sizes suitable for small arrays. Wood is good for the framework of multibay arrays for the higher bands, as it keeps down the amount of metal in the active area of the array. Square or rectangular boom and frame materials can be cut to order in most lumber yards if they are not available from the racks in suitable sizes.

Wood used for antenna construction should be well seasoned and free of knots or damage. Available materials vary, depending on local sources. Your lumber dealer can help you better than anyone else in choosing suitable materials. Joining wood members at right angles can be done with gusset plates, as shown in **Fig 12**. These can be made of thin outdoor-grade plywood or Masonite. Round materials can be handled in ways similar to those used with metal components, with U clamps and with other hardware.

In the early days of Amateur Radio, hardwood was used as insulating material for antennas, such as at the center and ends of dipoles, or for the center insulator of a driven element made of tubing. Wood dowels cut to length were the most common source. To drive out moisture and prevent the subsequent absorption of moisture into the wood, it was treated before use by boiling it in paraffin. Of course today's technology has produced superior materials for insulators in terms of both strength and insulating qualities. However, the technique is worth consideration in an emergency situation or if low cost is a prime requirement. "Baking" the wood in an oven for a short period at 200° F should drive out any moisture. Then treatment as described in the next paragraph should prevent moisture absorption. The use of wood insulators should be avoided at high-voltage points if high power is being used.

All wood used in outdoor installations should be protected from the weather with varnish or paint. A good grade of marine spar varnish or polyurethane varnish will offer protection for years in mild climates, and one or more seasons in harsh climates. Epoxy-based paints also offer good protection.

Plastics

Plastic tubing and rods of various sizes are available from many building-supplies stores. The uses for the available plastic materials are limited only by your imagination. Some amateurs have built beam antennas for VHF using wire elements run inside thin PVC plumbing pipe. The pipe gives the elements a certain amount of physical strength. Other hams have built temporary antennas by wrapping plastic pipe with aluminum foil or other conductive material. Plastic

Fig 12—Wood members can be joined at right angles using gusset plates.

Fig 13—Plastic plumbing parts can be used as antenna center and end insulators.

plumbing pipe fittings can also be used to enclose baluns and as the center insulator or end insulators of a dipole, as shown in **Fig 13**. Plastic or Teflon rod can be used as the core of a loading coil for a mobile antenna (**Fig 14**) but the material for this use should be selected carefully. Some plastics become quite warm in the presence of a strong RF field, and the loading-coil core might melt or catch fire!

Fiberglass

Fiberglass poles are the preferred material for spreaders for quad antennas. They are lightweight, they withstand harsh weather well, and their insulating qualities are excellent. One disadvantage of fiberglass poles is that they may be crushed rather easily. Fracturing occurs at the point where the pole is crushed, causing it to lose its strength. A crushed pole is next to worthless. Some amateurs have repaired crushed poles with fiberglass cloth and epoxy, but the original strength is

Fig 14—A mobile-antenna loading coil wound on a polystyrene rod.

nearly impossible to regain.

Fiberglass poles can also be used to construct other types of antennas. Examples are helically wound Yagi elements or verticals, where a wire is wound around the pole.

CONCLUSION

The antenna should be put together with good quality hardware. Stainless steel is best for long life. Rust will quickly attack plated steel hardware, making nuts difficult, if not impossible, to remove. If stainless-steel muffler clamps and hose clamps are not available, the next best thing is to have them plated. If you can't have them plated, at least paint them with a good zinc-chromate primer and a finish coat or two.

Galvanized steel generally has a longer life than plated steel, but this depends on the thickness of the galvanizing coat. Even so, in harsh climates rust will usually develop on galvanized fittings in a few years. For the ultimate in long-term protection, galvanized steel should be further protected with zinc-chromate primer and then paint or enamel before exposing it to the weather.

Good quality hardware is expensive initially, but if you do it right the first time, you won't have to take the antenna down in a few years and replace the hardware. When the time does come to repair or modify the antenna, nothing is more frustrating than fighting rusty hardware at the top of the tower.

Basically any conductive material can be used as the radiating element of an antenna. Almost any insulating material can be used as an antenna insulator. The materials used for antenna construction are limited mainly by physical considerations (required strength and resistance to outdoor exposure) and by the availability of materials. Don't be afraid to experiment with radiating materials and insulators.

BIBLIOGRAPHY

Source Material and more extended discussion of topics covered in this chapter can be found in the reference given below.

J. J. Elengo, Jr., "Predicting Sag in Long Wire Antennas," *QST*, Jan 1966, pp 57-58.

D. B. Leeson, *Physical Design of Yagi Antennas* (Newington, CT: ARRL).

Antenna Products Suppliers

Antenna Manufacturers Products

Finding parts can be the most difficult aspect of an antenna project. Suppliers of aluminum exist in most major metropolitan areas. They can be found in the Yellow Pages of the phone book. Some careful searching of the Yellow Pages may also reveal sources of other materials and accessories. If you live away from a metropolitan area, try using telephone books for the nearest large metropolitan area; they may be available in the reference section of your local library.

Many dealers and distributors will ship their products by freight or by mail. Tables 1 through 7 list several categories of antenna products and some suppliers of them. Company names have been abbreviated where necessary. Table 8 is an address list arranged alphabetically by company name.

Product lines change often; we recommend that you

Table 1
VHF/UHF/Microwave Antenna Suppliers

Manufacturer	Yagi	Quad	Loop Yagi	Vertical	Mobile	HT	Microwave	Helical	Satellite
Antennaco	✓								
Ant Specialists				✓	✓				
Austin Antenna				✓	✓	✓			
Butternut				✓					
Centurion						✓			
Comet				✓	✓	✓			
Create Design	✓								
Cubex		✓							
Cushcraft	✓		✓	✓	✓				✓
Diamond	✓		✓	✓	✓				
Down East	✓		✓				✓		✓
Eur-AM				✓	✓	✓			
Force 12	✓			✓					
Hustler	✓			✓	✓				
Hy-Gain (MFJ)	✓			✓					✓
Kilo-Tec				✓					
Lakeview				✓	✓	✓			
Larsen				✓	✓				
M²	✓	✓		✓					
Maldol					✓				
MFJ	✓			✓	✓	✓			
Mosley	✓			✓					
Pro-Am Valor					✓				
RadioShack				✓	✓	✓			
Radio Works					✓				
Sommer	✓								
Spectrum Intl	✓		✓				✓	✓	✓
Tennadyne	LPDA								
Tonna	✓						✓		

request current catalogs from those manufacturers who interest you. In addition, all indications of sales policies and prices for catalogs are given for general information only and are subject to change without notice.

Antenna products for repeaters are listed separately, in Chapter 17.

Table 2
HF Antenna Suppliers

Manufacturer	Yagi	Quad	LPDA	Vertical	Dipole	Mobile	Small Xmtg	Active (RX only)
Alpha Delta				✓	✓	✓		
B & W				✓	✓			
Bilal							✓	
Butternut/Bencher	✓			✓			✓	
Create Design	✓		✓	✓	✓		✓	
Cubex		✓						
Cushcraft	✓		✓	✓	✓			
Flytecraft				✓		✓		
Force 12	✓		✓	✓	✓	✓	✓	
GAP				✓				
Gem Quad		✓						
Grove					✓	✓		✓
High Sierra				✓	✓	✓		
Hustler				✓		✓		
Hy-Gain (MFJ)	✓			✓	✓			
Lakeview/Hamstick						✓		
Lightning Bolt		✓						
M²	✓				✓			
MFJ	✓	✓	✓	✓	✓	✓	✓	✓
Mosley	✓			✓	✓			
Palomar								✓
Pro-Am Valor						✓		
Roadrunner						✓		
Sommer	✓			✓				
Spi-Ro				✓	✓			
Tennadyne			✓					
Texas Radio					✓	✓		
Radio Works				✓	✓			
Van Gorden				✓	✓			
W1JC					✓		✓	
W9INN					✓			

Table 3
Antenna Parts

Manufacturer	Hardware	Insulators	Traps	Aluminum Tubing	Wire	Transmission Lines
Alexanderson AeroPlane Co				✓		
Barker & Williamson		✓	✓			
Cable X-Perts	✓	✓			✓	✓
Hy-Gain (MFJ)	✓	✓				
Metal & Cable, Inc	✓			✓	✓	
Ocean State Electronics	✓	✓			✓	✓
Spi-Ro		✓	✓		✓	✓
Texas Towers				✓	✓	✓
Radio Works	✓	✓			✓	✓
Van Gorden	✓	✓			✓	✓
The Wireman	✓	✓			✓	✓
W1JC		✓			✓	
W9INN					✓	

Table 4
Suppliers of Quad Antenna Parts

Company	Material Size
Cubex Co., Inc.	$1^{1}/_{4}$-$^{1}/_{2}$ in. × 13 ft; $1^{1}/_{2}$ in. × 13 ft cast spiders, boom-to-mast mounts.
Lightning Bolt	Custom-made fiberglass spreaders; any length.
Max-Gain Systems, Inc.	Quad spreaders; fiberglass insulators.

Table 5
Towers, Masts and Accessories

Towers
Aluma
Champion Radio
Create Design
Force 12
Glen Martin Engineering
Heights Tower
Hy-Gain (MFJ)
National Tower
RadioShack (masts only)
Rohn
Rotating Tower Systems
Tashjian Towers Corporation
Texas Tower
Trylon
Universal Manufacturing
US Tower

Climbing and Safety Equipment
Champion Radio Products
ONV
Texas Towers

Rotators
Create Design
Hy-Gain (MFJ)
M^2
RadioShack
The Rotor Doctor
Yaesu

Stacking Frames
(Unless otherwise noted these frames are for use in stacking the manufacturer's own antennas in pairs or in quads. These stacking kits are for VHF or UHF antennas only.)
C3i
Cushcraft
Down East
IIX
Spectrum International

Combiners, Power Dividers and Phasing Harnesses
Byers
C3i
Down East
Spectrum International
Tonna

Table 6
Transmission Lines

Source	Coax	Hardline	Ladder Line
Belden	✓	✓	
Cable X-Perts	✓	✓	✓
International Wire & Cable	✓		
Nemal	✓	✓	
The Radio Works	✓	✓	✓
W1JC			✓
W9INN			✓
The Wireman	✓	✓	✓

Antenna Products Suppliers 21-3

Table 7
Transmission Line Instruments and Accessories

Matching Networks
Ameritron
Barker & Williamson
Cubex
ICOM (mobile & fixed)
Kenwood
MFJ
Nye
SGC
Ten-Tec
Texas Radio (mobile only)
Vectronics
XMatch

Ferrite Cores and Rods
Amidon
Palomar
The Wireman

Filters—TVI (Low Pass & High Pass)
K-Com
MFJ

Lightning Arresters
Alpha Delta
Ameritron
Comet
Cushcraft
Hy-Gain (MFJ)
Polyphaser
Radioware
Rohn
The Wireman
Zero Surge Inc

Switches (Manual, Coax)
Alpha Delta
Barker & Williamson
MFJ

Switches (Remote, Coax)
Ameritron
MFJ

SWR and Wattmeters
Autek
Bird
Coaxial Dynamics
MFJ
Nye
Palomar
RF Parts
Texas Radio

Table 8
Suppliers Addresses

We have made every effort to ensure that this list is complete and accurate as of mid 2003. The ARRL takes no responsibility for errors or omissions. Similarly, a listing here does not represent an endorsement of a manufacturer or products by the ARRL. Refer to the product reviews in *QST* for descriptions of particular products that interest you. To the best of our knowledge the suppliers listed are willing to sell products to amateurs by mail unless indicated otherwise. This listing will be updated with each edition of *The Antenna Book* and *The ARRL Handbook* in the TISFIND manufacturer database. Check ads in *QST* and other Amateur Radio publications for any changes to this information. Suppliers who wish to be listed or update their information are urged to contact the editors.

Advanced Composites
1154 S. 300 W.
Salt Lake City, UT 84101
801-467-1204
fax 801-467-4367
e-mail
info@advancedcomposites.com

Advanced Specialties
114 Essex Street
Lodi, NJ 07644
USA
Tel: 800-926-9426
Email: advanspec@aol.com
http://advancedspec.freeyellow.
com/

AEA—Div. Tempo Research
Corporation
1221 Liberty Way
Vista, CA 92083
760-598-9677
fax 760-598-4898
e-mail tempo@inetworld.com
web www.aea-wireless.com

AFT
132 Boulevard Dauphinot
F-51100 Reims, France
+33 326 070 047
fax +33 326 023 654
e-mail Antennes-ft@wanadoo.fr
web www.f9ft.com

Alexander Aeroplane Co
PO Box 909
Griffin, GA 30224
800-831-2949; 404-229-2329

Alan Broadband Company
(Zap Checker)
93 Arch Street
Redwood City, CA 94062
USA
Tel: 888-369-9627 (orders)
650-369-9627
Fax: 650-369-3788
Email: ABCom@prodigy.net
http://www.alanbroadband.com/

Alpha Delta Communications
PO Box 620
Manchester, KY 40962
606-598-2029
fax 606-598-4413

Aluma Tower Co, Inc
PO Box 2806-AL
Vero Beach, FL 32961-2806
772-567-3423
fax 772-567-3432
e-mail atc-t@alumatower.com
web www.alumatower.com/
index.html

Amateur Electronic Supply
5710 W Good Hope Rd
Milwaukee, WI 53223
800-558-0411
web www.aesham.com/

Ameritron Division
116 Willow Road
Starkville, MS 39759
662-323-8211 (Tech)
fax 662-323-6551
e-mail
ameritron@ameritron.com
web www.ameritron.com/
ameritron

Amidon Associates, Inc.
1510 E. Edinger Avenue, Unit B
Santa Ana CA 92705
800-898-1883; 714-547-4494
fax 714-547-4433
e-mail sales@amidon-
inductive.com
web www.amidon-
inductive.com/

Antennaco Inc
102 Armory Road
PO Box 218
Milford, NH 03055-0218
603-673-3153
fax 603-673-4347

Allen Telecom Group
Antenna Specialists Mobile
Division
30500 Bruce Industrial Parkway
Cleveland, OH 44139-3996
USA
440-349-8400
fax 440-349-8404
web www.antenna.com/

Array Solutions
350 Gloria Rd
Sunnyvale, Tx 75182
USA
Tel: 972-203-8810
Fax: 972-203-8811
Email: wx0b@arrysolutions.com
http://www.arraysolutions.com

ASA Antenna Sales
PO Box 3461
Myrtle Beach, SC 29578
800-772-2681

Associated Radio
Communications
8012 Conser
Overland Park, KS 66204
913-381-5900; 800-497-1457
fax 913-648-3020
e-mail assocrad@tfs.net
web www.associatedradio.com

Austin Amateur Radio Supply
5310 Cammeron Road
Austin, TX 78723
800-423-2604; 512-454-2994
fax 512-454-3069

Austin Antenna, Ltd
10 Main St
Gonic, NH 03839
603-336-6339
fax 603-335-1756

Autek Research
PO Box 7556
Wesley Chapel, FL 33544
813-994-2199
e-mail
Mailbox@autekresearch.com
web www.autekresearch.com/
index.htm

Barker & Williamson Co
603 Cidco Rd
Cocoa, FL 32926
321-639-2545
fax 321-639-2545
e-mail
custsrvc@bwantennas.com
web www.bwantennas.com

Barry Electronics Corp
540 Broadway
New York, NY 10012
212-925-7000
fax 212-925-7001

Belden Wire & Cable
PO Box 1980
Richmond, IN 47374
317-983-5257
fax 317-983-5257
web www.belden.com

Bencher Inc.
831 North Central Avenue
Wood Dale, IL 60191
630-238-1183
fax 630-238-1186
e-mail bencher@bencher.com
web www.bencher.com/

Bilal Company
137 Manchester Dr
Florissant, CO 81816
719-687-0650
web www.isotronantennas.com/

Bird Electronics Corporation
30303 Aurora Rd.
Solon, OH 44139
866-695-4569
e-mail sales@bird-
technologies.com
web www.bird-electronic.com/

Brian Beezley, K6STI
3532 Linda Vista Dr
San Marcos, CA 92069
619-599-4962
e-mail k6sti@n2.net

Burghardt Amateur Center, Inc.
710 10th Street SW
PO Box 73
Watertown, SD 57201
800-927-4261
605-886-7314 (Service)
605-886-6914 (Fax-back
product info)
fax 605-886-3444
e-mail burghart@daknet.com
web www.burghardt-
amateur.com/

Butternut Electronics Co
See Bencher Inc.

Byers Chassis Kits
5120 Harmony Grove Road
Dover, PA 17315
717-292-4901
(6p-9p EST M-F, 8a-4p Sat)
717-292-4901 (24 hrs)

Cable X-Perts Inc.
225 Larkin Drive Suite #6
Wheeling, IL 60090-7209
800-828-3340 (orders only)
847-520-3003 (Tech. Info.)
fax 847-520-3444
e-mail cxp@cablexperts.com
web www.cablexperts.com/

CAL-AV Labs, Inc.
1802 w. Grant road, Ste. 116
Tucson, AZ 85745
USA
Tel: 520-624-1300
888-815-0400 (orders only)
Fax: 520-624-1311
Email: info@cal-av.com
http://www.cal-av.com/

Cardwell Condenser Corp
80 East Montauk Hwy
Lindenhurst, NY 11757
516-957-7200
fax 516-957-7203
web www.cardwellcondenser.com

C.A.T.S.
Formerly known as: Rotor Doctor
7368 SR 105
Pemberville, OH 43450
419-353-2287
fax 419-354-7746
 e-mail mailto:craig@rotor-doc.com
web www.rotordoc.com

C-Comm
6115 15th NW
Seattle, WA 98107
206-784-7337; 800-426-6528
fax 206-784-0541

C3i
1401 K Street NW Suite 900
Washington DC 20005
(800) 224-5137
fax (202) 362-8481
e-mail info@C3iusa.com
web www.c3iusa.com/
corpover.html

Centurion International
PO Box 82846
Lincoln, NE 68501-2846
402-467-4491
fax 800-848-3825

Champion Radio Products
Box 572
Woodinville, WA 98072
425-485-7913
206-890-4188 Cell Phone
fax 360-668-1447
e-mail championradio@aol.com
web www.championradio.com/

Coaxial Dynamics
15210 Industrial Parkway
Cleveland, Ohio 44135-3308
800-262-9425
fax 216-267-3142
e-mail cdi-sales@coaxial.com
web www.coaxial.com/
home_frames.htm

Comet North America Inc.
394 Wards Corner Road
Suite 130
Cincinnati, Ohio, 45140
513-831-5000
fax 513-831-7889
e-mail
info@CometNorthAmerica.com
web www.cometnorthamerica.com/

Comet Antenna
See NCG

Comm-Pute
7946 State Street
Midvale, UT 84047
801-567-9944
fax 801-567-9494
e-mail bobwood@xmission.com
web www.comm-pute.com/

Communication Headquarters Inc.
3832 Oleander Drive
Wilmington, NC 28403
910-791-8885
800-688-0073 (orders)
fax 910-452-3891 (orders)
web www.chq-inc.com/

Communications Data Corp
1051 Main St
St Joseph, MI 49085
269-982-0404
fax 269-982-0433
e-mail mailto:did@gtm.net

Comtelco Industries Inc
501 Mitchell Rd
Glendale Heights, IL 60139
800-634-4622; 708-7790-9894
fax 708-798-9799

Create
4-8 Asano-Cho
Kawasaki-Ku
Kawasaki-City, Japan
044 (333) 6681
fax 044 (333) 6598
e-mail email@cd-corp.com

Cubex Co.
228 Hibiscus St, #9
Jupiter, FL 33458
561-748-2830
fax 561-748-2831
e-mail CubexCo@aol.com
web www.cubex.com/

Cushcraft Corp
48 Perimeter Rd.
Manchester, NH 03108
603-627-7877
e-mail sales@cushcraft.com
web www.cushcraft.com/

Dave's Hobby Shop
600 Main St.
Van Buren, AK 72956
USA
Tel: 479-471-0750
Web www.daveswebshop.com

Davis RF Co
See Radioware (distributor)
PO Box 730
Carlisle, MA 01741
978-371-1356
978-369-1738
800-328-4773 (Orders only)
fax 978-369-3484
e-mail davisrfinc@aol.com
web www.davisRF.com

Diamond Antennas
See RF Parts

Down East Microwave
954 Rt 519
Frenchtown, NJ 08825
908-996-3584
fax 908-996-3702
web downeastmicrowave.com/

Dressler Hochfrequenztechnik
GMBH
Werther Strasse 14-16
W-5190 Stolberg
Germany

DX Engineering
POB 440
Peninsula, Ohio 44264
USA
Fax: 330-657-2168
Email:
dxengineering@dxengineering.com
http://www.dxengineering.com/

EDCO - Electronic Distributors
Company
325 Mill Street
Vienna, VA 22180
703-938-8105
fax 703-938-6911
e-mail web www.elecdist.com/
index.html

EUR-AM Antennas
PO Box 225
Moultonboro, NH 03254-0225
603-476-5113
fax 603-476-5113
e-mail info@eur-am.com
web www.eur-am.com/

EZ Hang, Inc.
8645 Tower Dr.
Code C
Laurel, MD 20723
Tel: 540-286-0176
Fax: 202-260-3797
http://www.ezhang.com

Fluidmotion Incorporated
14135 233rd Place SE
Issaquah, WA 98027
425-456-0200; 800-885-8700
fax 425-391-6031
e-mail sales@steppir.com
web www.steppir.com/

Flytecraft
PO Box 3141
Simi Valley, CA 93093
805-583-8173

Force 12
PO Box 1349
Paso Robles, CA 93447
800-248-1985
805-227-1680 (Tech)
fax 805-227-1684
e-mail
mailto:force12e@lightlink.com
web force12inc.com/

GAP Antenna Products
99 North Willow St
Fellsmere, FL 32948
772-571-9922
Email: contact@gapantenna.com
web www.gapantenna.com

Gem Quad Products Ltd
PO Box 291
Boissevain, MB R0K 0E0
Canada
204-534-6184
fax 204-534-6492
e-mail
mailto:gemquad@escape.ca
web www.escape.ca/~gemquad/

GLA Systems
PO Box 425
Caddo Mills, TX 75135
903-527-4163
800-588-2841
fax 214-381-2895
web www.texasbugcatcher.com/

Grove Enterprises Inc.
PO Box 98
Brasstown, NC 28902
800-438-8155 (orders)
704-837-9200 (BBS)
fax 704-837-2216
e-mail nada@grove.net
web www.grove-ent.com/

Ham Radio Outlet
1702 W. Camelback Rd
Phoenix, AZ 85015
web www.hamradio.com/
800-444-4799 Mid Atlantic
800-444-9476 Mountain
800-444-0047 New England
800-644-4476 Northeast
800-444-7927 Southeast
800-854-6046 West

The Ham Station
220 North Fulton Avenue
PO Box 6522
Evansville, IN 47719-0522
800-729-4373 (orders)
812-422-0231 (Tech)
812-422-0252 (Service)
fax 812-422-4253
e-mail sales@hamstation.com
web www.hamstation.com/

Hamtronics, Inc
65-Q Moul Rd
Hilton, NY 14468
716-392-9430
fax 716-392-9420
web www.hamtronics.com

Hamware.de
Int'l: Klaus Bemmerer
Tel: +49 4371 869145
e-mail service@hamware.de
Web www.hamware.de
US: Dillon RF Systems
Email dillonel@mtaonline.net

Heights Tower Systems
1529 Gulf Beach Hwy
Pensacola, FL 32507
850-455-1210
fax 850-455-4355
e-mail info@heightstowers.com
web www.heightstowers.com/

Hi-Q Antennas
21085 Cielo Vista Way
Wildomar, CA 92595
909-674-4862
fax 909-245-2031
e-mail sales@hiqantennas.com
web www.hiqantennas.com/

High Sierra Antennas
Box 2389
Nevada City, CA 95959
888-273-3415; 530-273-3415
fax 530-273-7561
e-mail heath@hsantennas.com
web www.hsantennas.com

Hustler Antennas
see New-Tronics Antenna Corp.

Hy-Gain (also see MFJ)
308 Industrial Park Road
Starkville, MS 39759
800-647-1800 (Sales)
662-323-9358 (Tech)
fax 662-323-6551
web www.hy-gain.com/

ICOM America, Inc.
2380 116th Ave, NE, Suite S
Bellevue,WA 98004
USA
Tel: 800 872-4266
Fax: 425 454-1509
Web www.icomamerica.com

Industrial Communications
Engineers (ICE)
Array Solutions
350 Gloria Rd.
Sunnyvale, TX 75182
972-203-2008; 800-423-2666
fax 972-203-8811
e-mail wx0b@arraysolutions.com
web www.iceradioproducts.com/

IIX Equipment, Ltd
PO Box 9
Oak Lawn, IL 60454
708-423-0605
fax 708-423-1691
web www.w9iix.com/

International Radio
13620 Tyee Road
Umpqua, OR 97486
541-459-5623 9AM-1PM PDT,
Tues-Sat
fax 541-459-5632
e-mail inrad@rosenet.net
web www.qth.com/inrad/

Kenwood USA Corporation
3975 Johns Creek Court,
Suite 300
Suwanee, GA 30024
USA
Tel: 678 474-4700
Fax: 678 474-4730
Web www.kenwoodusa.com

KØXG Systems
1117 Highland Park Drive
Bettendorf, IA 52722
USA
Tel: 563 355-7451
Email KØXG@ KØXG.com
Web www.k0xg.com

Kilo-Tec
PO Box 10
Oakview, CA 93022
805-646-9645

K-Com
PO Box 82
Randolph OH 44265
330-325-2110
fax 330-325-2525
e-mail k-com@worldnet.att.net
web www.k-comfilters.com/
howtoget.asp

Lakeview Co Inc
3620-9A Whitehall Rd
Anderson, SC 29626
(864) 226-6990
fax (864) 225-4565
 web www.hamstick.com

Larsen Electronics, Inc
See Radial/Larsen

LDG Electronics
1445 Parran Road
St Leonard, MD 20685
877-890-3003 Toll-Free Orders
410-586-2177 Tech Support
fax 410-586-8475
e-mail ldg@ldgelectronics.com
web www.ldgelectronics.com

Lentini Communications
21 Garfield St
Newington, CT 06111
860-666-6227
800-666-0908 (outside CT)
fax 860-667-3561
e-mail radio@lentinicomm.com
web www.lentinicomm.com

Roy Lewallen, W7EL
PO Box 6658
Beaverton, OR 97007
503-646-2885
fax 503-671-9046
e-mail w7el@eznec.com
web www.eznec.com

Lightning Bolt Antennas
RD #2, RT 19
Volant, PA 16156
724-530-7396
fax 724-530-6796
e-mail lbaquads@ztrain.com
web
www.lightningboltantennas.com/

M2 Antenna Systems Inc.
4202 N. Selland
Fresno CA, 93722
559-432-8873
fax 559-432-3059
e-mail wyatt@m2inc.com
web www.m2inc.com/

M/A-COM, Inc
(an AMP Company)
1011 Pawtucket Blvd
PO Box 3295
Lowell, MA 01853-3295
508-442-4500
fax 508-442-4436
e-mail sales@macom.com
web www.amp.com

Maldol USA
4711 NE 50th St
Seattle, WA 98105
Answerfax 206-525-1896
fax 206-524-7826
e-mail transtec@cyberquest.com

Glen Martin Engineering
13620 Old Highway 40
Boonville, MO 65233
660-882-2734; 800-486-1223
fax 660-882-7200
web www.glenmartin.com

The Mast Company
Henry Pollock - K4TMC
P.O. Box 1932
Raleigh, NC 27602
Email: k4tmc@aol.com
http://www.geocities.com/tmastco/

MCM Electronics
650 Congress Park Dr
Centerville, OH 45459-4072
800-543-4330
fax 800-765-6960
web www.i-mcm.com

Memphis Amateur Electronics
1465 Wells Station Rd
Memphis, TN 38108
901-683-9125; 800-238-6168
fax 901-682-7165

Metal and Cable Corp, Inc
9241 Ravenna Road, Unit C-10
PO Box 117
Twinsburg, OH 44087
330-425-8455
fax 330-425-3504
web www.metal-cable.com/

MFJ Enterprises
300 Industrial Park Rd
Starkville, MS 39759
662-323-5869
Email
mfjcustserv@mfjenterprises.com
web www.mfjenterprises.com/

MGS (Max-Gain Systems, Inc.)
221 Greencrest Court
Marietta, GA 30068-3825
770-973-6251 (before 9 PM
eastern)
fax 815) 461-7730
e-mail info@mgs4u.com
web www.mgs4u.com/

Michigan Radio
26014 Groesbeck Hwy
Warren, MI 48089
810-771-4711
800-TRU-HAMM (800-878-4266)
Orders only
810-771-4712 (Service)
fax 810-771-6546
web www.michiganradio.com/

Mirage Communications
116 Willow Road
Starkville, MS 39759
662-323-8287
fax 662-323-6551
web www.mirageamp.com/

James Millen Electronics
PO Box 4215BV
Andover, MA 01810-4215
978-975-2711
fax 978-474-8949
e-mail info@jamesmillenco.com
web www.jamesmillenco.com/
millen/millmain.htm

Mosley Electronics
1325 Style Master Drive
Union, MO 63084
800-325-4016 (Orders)
800-9MOSLEY (966-7539)
314-994-7872 (Technical)
fax 314-994-7873
web www.mosley-electronics.com/

Multi-band Antennas (originally
Spider Antennas)
7131 Ownesmouth Avenue -
Suite 563C
Canoga Park, CA 91303
818-341-5460
web www.spiderantenna.com/

Multi-tech Industries, Inc. (MTI)
(formally Radio Switch)
64 South Main Street
PO Box 159
Marlboro, NJ 07746-0159
800-431-3223; 732-431-0550
732-462-6100
fax 732-409-6695
e-mail multitech@sprynet.com
web www.multi-tech-industries.com

National RF, Inc.
7969 Engineer Road, Suite 102
San Diego, CA 92111
858-565-1319
fax 858-571-5909
web www.nationalrf.com/

National Tower Co
PO Box 15417
Shawnee Mission, KS 66285
800-762-5049; 913-888-8864

**NCG Companies—Comet
Antenna
1275 North Grove St
Anaheim, CA 92806
714-630-4541; 800-962-2611
fax 714-630-7024
web www.cometantenna.com
web www.natcommgroup.com/**

Nemal Electronics Inc.
12240 NE 14th Avenue
North Miami, FL 33161
305-893-3924; 305-849-0900
800-522-2253
fax 305-895-8178
e-mail info@nemal.com
web www.nemal.com/

New-Tronics Antenna Corp. -
Hustler
1 Newtronics Place
Mineral Wells, TX 76067-9563
877-994-9499 Sales
940-325-1386 Service
fax 940-328-1409
e-mail sales@new-tronics.com
web www.new-tronics.com/main/
index.html

Nittany Scientific
1733 West 12600 South
Suite 420
Riverton, UT 84065
Phone/fax (801) 446-1426
e-mail sales@nittany-
scientific.com
web www.nittany-scientific.com/

William M. Nye Co
PO Box 1877
Priest River, ID 83856
208-448-1762
fax 208-448-1832

Ocean State Electronics
PO Box 1458
6 Industrial Dr
Westerly, RI 02891
401-596-3080; 800-866-6626
fax 401-596-3590
web www.oselectronics.com

ONV Safety Belt Co.
Box 404
Ramsey, NJ 07446
800-345-5634; 201-327-2462
fax 201-327-2462

OptiBeam
Thomas Schmenger DF2BO
Rastatter Straße 37
D-75179 Pforzheim
Tel./Fax: (0049) 07231 / 45 31 53
Email: Info@optibeam.de

OptiBeam NorthAmerica
Array Solutions
350 Gloria Rd
Sunnyvale, Tx 75182 USA
Tel: 972-203-8810
Fax: 972-203-8811
Email: wx0b@arrysolutions.com
http://www.arraysolutions.com

Orion now sold by M²

Outbacker Antenna Sales
330 Cedar Glen Circle
Chattanooga, TN 37412
615-899-3390
fax 615-899-6536

Palomar Engineers
PO Box 462222
Escondido, CA 92046
619-747-3343
fax 619-747-3346
e-mail palomar@compuserve.com
web www.palomar-engineers.com/

Palstar, Inc.
9676 N Looney Rd
P O Box 1136-1482
Piqua, Ohio 45356
USA
Tel: 937-773-6255
Fax: 937-773-8003
Email: Palstar@erinet.com
http://www.palstarinc.com/

Phillystran, Inc
151 Commerce Dr
Montgomeryville, PA 18936
215-368-6611
fax 215-362-7956
web www.phillystran.com/

PolyPhaser Corp
2225 Park Place
PO Box 9000
Minden, NV 89423-9000
702-782-2511
fax 702-782-4476
e-mail info@polyphaser.com
web www.polyphaser.com

**Quicksilver Radio Products
30 Tremont St.
Meriden, CT 06450
USA
Tel: 203-440-4468
http://www.qsradio.com**

Radiall/Larsen Antenna Technolo-
gies
3611 NE 112th Avenue
Vancouver, WA 98682
800-ANTENNA (800-268-3662)
360-944-7551
FAX 360-944-7556
fax 800-525-6749
e-mail info@radiallarsen.com
web www.radialllarsen.com/
default.htm

Radio Bookstore (Radioware)
PO Box 209
Rindge, NH 03461-0209
603-899-6957
800-457-7373 (10am-6pm EST)
fax 603-899-6826
e-mail radware@radio-ware.com
web www.radiobooks.com/

Radio Center USA
1242 Howell
N. Kansas City, MO 64116
816-459-8832; 800-821-7323

Radio City
2663 County Rd I
Mounds View, MN 55112
612-786-4475; 800-426-2891
fax 612-786-6513
web www.radioinc.com

Radio Engineers/Technitron (see
National RF, Inc.)

Radio Shack
(Contact your local store)

Radio Switch Corp
See Multi-tech Industries

Radio Works
PO Box 6159
Portsmouth, VA 23703
757-484-0140
800-280-8327 (Orders)
fax 757-483-1873
e-mail jim@radioworks.com
web radioworks.com/

Raibeam Antennas, Int'l
5638 West Alice Avenue
Glendale, AZ 85302
800-530-1913 (orders)
602-931-9135
e-mail wa7rai@raibeam.com
web www.raibeam.com/

RF Parts Co
435 South Pacific St
San Marcos, CA 92069
760-744-0700; 800-737-2787
760-744-0750 (Tech)
fax 760-744-1943; 888-744-1943
e-mail rfp@rfparts.com
web www.rfparts.com

RF TEC Manufacturing
256 Commerce Rd, Suite 517
Peachtree, GA 30269
770-251-2235
fax 770-502-9827
web www.rftec.com/

Roadrunner Resonator
1850 Swanson, #A20
Lake Havasu, AZ 86403
520-453-7211

**ROHN Industries, Inc.
PO Box 2000
Peoria, IL 61656
309-697-4400
fax 309-697-5612
e-mail mail@rohnnet.com
web www.rohnnet.com/
Index.htm**

Ross Distributing Co
78 South State St
Preston, ID 83263
208-852-0830
fax 208-852-0833
web www.rossdist.com

Rotating Tower Sytems, Inc.
Box 44
Prosper, TX 75058
214-347-2560

Rotor Doctor
See C.A.T.S.

SGC Inc
13737 SE 26th St
Bellevue, WA 98005
425-746-6310
fax 425-746-6384
e-mail sgc@sgcworld.com
web www.sgcworld.com/

Shoestring Antennas
PO Box 425
Keyport, WA 98345
360-697-5399
fax 360-697-8416
e-mail jacksa@juno.com
web www.qth.com/shoestring/

Sky-Pole Manufacturing, Inc
1922 Placentia Ave
Costa Mesa, CA 92627
949-548-5596
fax 949-548-5598

Sommer Antennas
PO Box 710
Geneva, FL 32732
407-349-9114
fax 407-349-2485
e-mail sommer1@ix.netcom.com
web www.sommerantennas.com

Spectrum International, Inc
PO Box 1084
Concord, MA 01742
508-263-2145
fax 508-263-7008

Spi-Ro Manufacturing, Inc.
P.O. Box 189
Jonesborough, TN 37659
800-728-7594
423-913-1615 Tech Support
fax 423-913-2131
e-mail mailto:contact@spiromfg.com
web www.spiromfg.com/

Surplus Sales of Nebraska
1502 Jones St
Omaha, NE 68102-3112
402-346-4750
800-244-4567 (Orders only)
fax 402-346-2939
e-mail grinnell@surplussales.com
web www.surplussales.com/

Tarheel Antennas
913 Old Honeycutt Rd
Fuquay-Varina, NC 27256
919-552-8788
fax 919-552-4970
e-mail tarheelantennas@aol.com
web www.tarheelantennas.com/

Tashjian Towers Corporation
(used to be Tri-Ex Towers)
2183 S Highland Ave.
Sanger, CA 93657
559-495-0307
559-284-9707 Mobile
fax 559-495-0557
e-mail tashjian@MSN.com
web www.karltashjian.com/

Telex Communications, Inc
Hy-Gain (see MFJ)

Ten-Tec, Inc
1185 Dolly Parton Parkway
Sevierville, TN 37862
865-453-7172
865-428-0364 (Repairs)
fax 865-428-4483
web www.tentec.com/

Tennadyne Corp
PO Box 34202
San Antonio, TX 78265-4202
210-599-9064
fax 210-599-9064
(same as voice)
e-mail tennadyn@satx.net
web www.tennadyne.com/

Teri Software
PO Box 277
Lincoln, TX 78948
979-542-7952
e-mail
support@antennamodel.com
web www.antennamodel.com

Texas Radio Products
5 E Upshaw
Temple, TX 76501
817-771-1188

Texas Towers
1108 Summit Ave, Suite 4
Plano, TX 75074
800-272-3467
972-422-7306 (Tech)
fax 972-881-0776
e-mail sales@texastowers.com
web www.texastowers.com/

T.G.M. Communications
121 Devon Street
Stratford, Ontario, N5A 2Z8
Canada
519-271-5928
e-mail tgmc@sympatico.ca
web www3.sympatico.ca/tgmc/
index.html

TIC General
PO Box 1 - 1110 Airport Rd
Thief River Falls, MN 56701
218-681-1119
fax 218-681-8509

Timewave Technology, Inc.
1025 Selby Ave, Suite 101
St Paul, MN 55104
USA
Tel: 651-489-5080
Email: sales@timewave.com
http://www.timewave.com

Traffie Technology
421 Jones Hill Road
Ashby, MA 01431-1801
888-599-BEAM (888-599-2326)
978-386-7900
fax 978-386-7900 (same as voice)

Trylon Manufacturing Co, Ltd
21 South Field Dr
PO Box 186
Elmira, Ontario
N3B 2Z6 Canada
519-669-5421
fax 519-669-8912
e-mail info@trylon.com
web www.trylon.com/home.asp

Tucker Electronics and Computers
1717 Reserve St.
PO Box 551419
Garland, TX 75355-1419
800-527-4642 (Test equipment
and catalog requests)
214-348-8800 (x332)
fax 214-340-5460
web www.tucker.com/

Unadilla Antenna Manufacturing
PO Box 4215
Andover, MA 01810-4215
978-975-2711
978-475-7831 (Office)
fax 978-474-8949
e-mail info@unadilla.com
web www.unadilla.com/

Universal Manufacturing Co
43900 Groesbeck Hwy
Clinton Township, MI 48036
810-463-2560
fax 810-463-2964

Universal Radio
6830 Americana Parkway
Reynoldsburg, OH 43068-4113
USA
Tel: 800-431-3939 (Orders)
614-866-4267 (Technical Info)
Fax: 614-866-2339
Email: dx@universal-radio.com
http://www.universal-radio.com/

US Tower Corp
1220 Marcin St
Visalia, CA 93291
559-733-2438
fax 559-733-7194
web www.ustower.com

Valor Enterprises
1711 Commerce Drive
PO Box 601
Piqua, OH 45356-0601
513-778-0074; 800-543-2197
fax 513-778-0259
web www.valorantenna.com/

Van Gorden Engineering
PO Box 21305
South Euclid, OH 44121

Van Valzah Co
38 W 111 Horseshoe Dr
Batavia, IL 60515-9730
708-406-9210

Vectronics
300 Industrial Park Road
Starkville, MS 39759
800-363-2922; 662-323-5800
fax 662-323-6551
e-mail jshurden@vectronics.com
web www.vectronics.com

XMatch
Paul Schrader, N4XM
7001 Briscoe Lane
Louisville, KY 40228
web http://n4xm.myiglou.com/

XX Towers
814 Hurricane Hill Road
Mason, NH 03048
603-878-1102
fax 603-878-4200
e-mail kc1xx@kc1xx.mv.com
web www.xxtowers.com/

W1JC—TV Evans
113 Stratton Brook Rd
Simsbury, CT 06070
860-658-5579
web pages.prodigy.com/w1jc

W3FF Antennas
2390 Templeton Dr.
Redding, CA 96002
USA
Tel: 530-226-8446
Email: sales@buddipole.com
http://www.buddipole.com

W7FG Vintage Manuals
3300 Wayside Drive
Bartlesville, OK 74006
USA
Tel: 800-807-6146 (orders)
918-333-3754
Email: w7fg@eigen.net
http://www.w7fg.com/

W9INN Antennas
PO Box 393
Mt Prospect, IL 60056
847-394-3414

Wacom Products
PO Box 21145
Waco, TX 76702
716-549-4700
e-mail sales@txrx.com

WBØW, Inc
PO Box 8547
Saint Joseph, MO 64508
USA
Tel: 816-364-2691
Email: WB0W@WB0W.com

The Wireman Inc.
261 Pittman Road
Landrum, SC 29356-9544
800-727-WIRE (800-727-9473)
Orders only
864-895-4195 Technical
fax 803-895-5811
e-mail N8UG@earthlink.net
web thewireman.com/

Yaesu U.S.A. (Vertex Standard)
10900 Walker St.
Cypress, CA 90630
714-827-7600
e-mail
amateurtech@vxstdusa.com
web www.yaesu.com/amateur/
amateur.html

YagiStress
Kurt Andress, K7NV
2835 Wade Street
Minden, NV 89423
702-267-5290
e-mail K7NV@contesting.com
web yagistress.freeyellow.com/

Zero Surge Inc
944 State Rt 12
Frenchtown, NJ 08825
908-996-7700
fax 908-996-7773
e-mail zerosurge1@aol.com
web www.zerosurge.com/

Antenna Supports

A prime consideration in the selection of a support for an antenna is that of structural safety. Building regulations in many localities require that a permit be obtained in advance of the erection of certain structures, often including antenna poles or towers. In general, localities having such requirements also have building safety codes that must be observed. Such regulations may govern the method and materials used in construction of, for example, a self-supporting tower. Checking with your local government building department before putting up a tower may save a good deal of difficulty later, because a tower would have to be taken down or modified if not approved by the building inspector on safety grounds.

Municipalities have the right and duty to enforce any reasonable regulations having to do with the safety of life or property. The courts generally have recognized, however, that municipal authority does not extend to aesthetic questions. The fact that someone may object to the mere presence of a pole, tower or other antenna structure because in his opinion it detracts from the beauty of the neighborhood is not grounds for refusing to issue a permit for a safe structure to be erected. Since the introduction of PRB-1 (federal preemption of unnecessarily restrictive antenna ordinances), this principle has been borne out in many courts. Permission for erecting amateur towers is more easily obtained than in the recent past because of this legislation.

Even where local regulations do not exist or are not enforced, the amateur should be careful to select a location and a type of support that contribute as much safety as possible to the installation. If collapse occurs, the chances of personal injury or property damage should be minimized by careful choice of design and erection methods. A single injury can be far more costly than the price of a more rugged support, in terms of both monetary loss and damage to the public respect for amateur radio.

This chapter has been reviewed and rewritten by Kurt Andress, K7NV.

TREES AS ANTENNA SUPPORTS

From the beginning of Amateur Radio, trees have been used widely for supporting wire antennas. Trees cost noth-

Fig 1—A method of counter weighting to minimize antenna movement and avoid its breaking from tree movement in the wind. The antenna may be lowered without climbing the tree by removing the counter-weight and tying additional rope at the bottom end of the halyard. Excess rope may be left at the counter-weight for this purpose, as the knot at the lower end of the halyard will not pass through the pulley.

ing to use, and often provide a means of supporting a wire antenna at considerable height. As antenna supports, trees are unstable in the presence of wind, except in the case of very large trees used to support antennas well down from the top branches. As a result, tree-supported antennas must be constructed much more sturdily than is necessary with stable supports. Even with rugged construction, it is unlikely that an antenna suspended from a tree, or between trees, will stand up indefinitely. Occasional repair or replacement usually must be expected.

There are two general methods of securing a pulley to a tree. If the tree can be climbed safely to the desired level, a pulley can be attached to the trunk of the tree, as shown in **Fig 1**. To clear the branches of the tree, the antenna end of the halyard can be tied temporarily to the tree at the pulley level. Then the remainder of the halyard is coiled up, and the coil thrown out horizontally from this level, in the direction in which the antenna runs. It may help to have the antenna end of the halyard weighted.

After attaching the antenna to the halyard, the other end is untied from the tree, passed through the pulley, and brought to ground along the tree trunk in as straight a line as possible. The halyard need only be long enough to reach the ground after the antenna has been hauled up. (Additional rope can be tied to the halyard when it becomes necessary to lower the antenna.)

The other method consists of passing a line over the tree from ground level, and using this line to haul a pulley up into the tree and hold it there. Several ingenious methods have been used to accomplish this. The simplest method employs a weighted pilot line, such as fishing line or mason's chalk line. By grasping the line about two feet from the weight, the weight is swung back and forth, pendulum style, and then heaved with an under-hand motion in the direction of the treetop.

Several trials may be necessary to determine the optimum size of the weight for the line selected, the distance between the weight and the hand before throwing, and the point in the arc of the swing where the line released. The weight, however, must be sufficiently large to carry the pilot line back to ground after passing over the tree. Flipping the end of the line up and down so as to put a traveling wave on the line often helps to induce the weight to drop down if the weight is marginal. The higher the tree, the lighter the weight and the pilot line must be. A glove should be worn on the throwing hand, because a line running swiftly through the bare hand can cause a severe burn.

If there is a clear line of sight between ground and a particularly desirable crotch in the tree, it may eventually be possible to hit the crotch after a sufficient number of tries. Otherwise, it is best to try to heave the pilot line completely over the tree, as close to the centerline of the tree as possible. If it is necessary to retrieve the line and start over again, the line should be drawn back very slowly; otherwise the swinging weight may wrap the line

around a small limb, making retrieval impossible.

Stretching the line out straight on the ground before throwing may help to keep the line from snarling, but it places extra drag on the line, and the line may snag on obstructions overhanging the line when it is thrown. Another method is to make a stationary reel by driving eight nails, arranged in a circle, through a 1-inch board. After winding the line around the circle formed by the nails, the line should reel off readily when the weighted end of the line is thrown. The board should be tilted at approximately right angles to the path of the throw.

Other devices that have been used successfully to pass a pilot line over a tree are a bow and arrow with heavy thread tied to the arrow, and a short casting rod and spinning reel used by fishermen. The Wrist Rocket slingshot made from surgical rubber tubing and a metal frame has proved highly effective as an antenna-launching device. Still another method that has been used where sufficient space is available is flying a kite to sufficient altitude, walking around the tree until the kite string lines up with the center of the tree, and paying out string until the kite falls to the earth. This method can be used to pass a line over a patch of woods between two higher supports, which may be impossible using any other method.

The pilot line can be used to pull successively heavier lines over the tree until one of adequate size to take the strain of the antenna has been reached. This line is then used to haul a pulley up into the tree after the antenna halyard has been threaded through the pulley. The line that holds the pulley must be capable of withstanding considerable chafing where it passes through the crotch, and at points where lower branches may rub against the standing part. For this reason, it may be advisable to use galvanized sash cord or stranded guy wire for raising the pulley.

Larger lines or cables require special attention when they must be spliced to smaller lines. A splice that minimizes the chances of coming undone when coaxed through the tree crotch must be used. One type of splice is shown in **Fig 2**.

Fig 2—In connecting the halyard to the pilot line, a large knot that might snag in the crotch of a tree should be avoided, as shown.

Fig 3—A weighted line thrown over the antenna can be used to pull the antenna to one side of overhanging obstructions, such as tree branches, as the antenna is pulled up. When the obstruction has been cleared, the line can be removed by releasing one end.

Fig 4—The cleat eliminates the need to untie a knot that may be weather hardened.

The crotch in which the line first comes to rest may not be sufficiently strong to stand up under the tension of the antenna. If, however, the line has been passed over (or close to) the center line of the tree, it will usually break through the lighter crotches and come to rest in a stronger one lower in the tree.

Needless to say, any of the suggested methods should be used with due respect to persons or property in the immediate vicinity. A child's sponge-rubber ball (baseball size) makes a safe weight for heaving a heavy thread line or fishing line.

If the antenna wire snags in the lower branches of the tree when the wire is pulled up, or if other trees interfere with raising the antenna, a weighted line thrown over the antenna and slid to the appropriate point is often helpful in pulling the antenna wire to one side to clear the interference as the antenna is being raised. This is shown in **Fig 3**.

Wind Compensation

The movement of an antenna suspended between supports that are not stable in the wind can be reduced by the use of heavy springs, such as screen-door springs under tension, or by a counterweight at the end of one halyard. This is shown in Fig 1. The weight, which may be made up of junkyard metal, window sash weights, or a galvanized pail filled with sand or stone, should be adjusted experimentally for best results under existing conditions. **Fig 4** shows a convenient way of fastening the counterweight to the halyard. It eliminates the necessity for untying a knot in the halyard, which may have hardened under tension and exposure to the weather.

TREES AS SUPPORTS FOR VERTICAL WIRE ANTENNAS

Trees can often be used to support vertical as well as horizontal antennas. If the tree is tall and has overhanging branches, the scheme of **Fig 5** may be used. The top end of the antenna is secured to a halyard passed over the limb, brought back to ground level, and fastened to the trunk of the tree.

Fig 5—Counterweight for a vertical antenna suspended from an overhanging tree branch.

MAST MATERIALS

Where suitable trees are not available, or a more stable support is desired, light-duty guyed masts are suitable for wire antennas of reasonable span length. At one time, most amateur masts were constructed of lumber, but the TV industry has brought out metal masts that are inexpensive and much more durable than wood. However, there are some applications where wood is necessary or desirable.

A Ladder Mast

A temporary antenna support is sometimes needed for an antenna system for antenna testing, site selection, emergency exercises or Field Day. Ordinary aluminum extension ladders are ideal candidates for this service. They are strong, light, extendable, weatherproof and easily transported. Additionally, they are readily available and can be returned to normal use once the project is concluded. A ladder tower will support a lightweight triband beam and rotator.

With patience and ingenuity one person can erect this assembly. One of the biggest problems is holding the base down while "walking" the ladder to a vertical position. The ladder can be guyed with $1/4$-inch polypropylene rope. Rope guys are arranged in the standard fashion with three at each level. If help is available, the ladder can be walked up in its retracted position and extended after the antenna and rotator are attached. The lightweight pulley system on most extension ladders is not strong enough to lift the ladder extension. This mechanism must be replaced (or augmented) with a heavy-duty pulley and rope. Make sure when attaching the guy ropes that they do not foul the operation of the sliding upper section of the ladder.

There is one hazard in this system that must be avoided: Do not climb or stand on the ladder when it is being extended—even as much as one rung. Never stand on the ladder and attempt to raise or lower the upper section. Do all the extending and retracting with the heavy-duty rope and pulley!

If the ladder is to be raised by one person, use the following guidelines. First, make sure the rung-latching mechanism operates properly before beginning. The base must be hinged so that it does not slip along the ground during erection. The guy ropes should be tied and positioned in such a way that they serve as safety constraints in the event that control of the assembly is lost. Have available a device (such as another ladder) for supporting the ladder during rest periods. (See **Fig 6**.)

After the ladder is erect and the lower section guys tied and tightened, raise the upper portion one rung at a time. Do not raise the upper section higher than it is designed to go; safety is far more important than a few extra feet of height.

For a temporary installation, finding suitable guy anchors can be an exercise in creativity. Fence posts, trees,

Fig 6—Walking the ladder up to its vertical position. Keith, VE2AQU, supports the mast with a second ladder while Chris, VE2FRJ, checks the ropes. (*Photo by Keith Baker, VE2XL.*)

and heavy pipes are all possibilities. If nothing of sufficient strength is available, anchor posts or pipes can be driven into the soil. Sandy soil is the most difficult to work with because it does a very poor job of holding anchors. A discarded car axle can be driven into the ground as an anchor, as its mass and strength are substantial. A chain and car-bumper jack can be used to remove the axle when the operation is done.

Above all else, keep the tower and antenna away from power lines. Make sure that nothing can touch the lines if the assembly falls. Disassemble by reversing the process. Ladder towers are handy for "quickie" antenna supports, but as with any improvisation of support materials, care must be taken to ensure safe construction.

The A-Frame Mast

A light and relatively inexpensive mast is shown in **Fig 7**. In lengths up to 40 feet it is very easy to erect and will stand the pull of ordinary wire antenna systems. The lumber used is 2×2-inch straight-grained pine (which many lumber yards know as hemlock) or even fir stock. The uprights can be as long as 22 feet each (for a mast slightly over 40 feet high) and the cross pieces are cut to fit. Four pieces of 2×2 lumber, each 22 feet long, provides more than enough. The only other materials required are five $1/4$-inch carriage bolts $5^1/2$ inches long, a few spikes, about 300 feet of stranded or solid galvanized wire for guying, enough glazed porcelain compression ("egg") insulators to break up the guys into sections, and the usual pulley and halyard rope. If the strain insulators are put in every 20 feet, approximately 15 of them will be enough.

After selecting and purchasing the lumber—which should be straight-grained and knot-free—sawhorses or boxes should be set up and the mast assembled as shown

in **Fig 8**. At this stage it is wise to give the mast a coat of primer and a coat of outside white latex paint.

After the coat of paint is dry, attach the guys and rig the pulley for the antenna halyard. The pulley anchor should be at the point where the top stays are attached so

Fig 7—The A-frame mast is lightweight and easily constructed and erected.

Fig 8—Method of assembling the A-frame mast on sawhorses.

the backstay will assume the greater part of the load tension. It is better to use wire wrapped around the mast with a small through-bolt to prevent sliding down than to use eyebolts.

If the mast is to stand on the ground, a couple of stakes should be driven to keep the bottom from slipping. At this point the mast may be "walked up" by a helper. If it is to go on a roof, first stand it up against the side of the building and then hoist it, from the roof, keeping it vertical. The whole assembly is light enough for two men to perform the complete operation—lifting the mast, carrying it to its permanent berth, and fastening the guys with the mast vertical. It is entirely practical to put up such a mast on a flat area of roof that would be too small to erect a regular tower installation, one that had to be raised vertically on the same spot.

TV Mast Material

TV mast is available in 5- and 10-foot lengths, $1^1/_4$ inches diameter, in both steel and aluminum. These sections are crimped at one end to permit sections to be joined together. A form that is usually more convenient is the telescoping mast available from many electronic supply houses. The masts may be obtained with three, four or five 10-foot sections, and come complete with guying rings and a means of locking the sections in place after they have been extended. These masts are inherently more suitable for guyed mast installations than the non-telescoping type because the diameters of the sections increase toward the bottom of the mast. For instance, the top section of a 50-foot mast is $1^1/_4$ inches diameter, and the bottom section is $2^1/_2$ inches diameter.

Guy rings are provided at 10-foot intervals, but guys may not be required at every point. Guying is essential at the top and at least one other place near the center of the mast. If the mast has any tendency to whip in the wind, or to bow under the load of a horizontal wire antenna, additional guys should be added at the appropriate points.

MAST GUYING

Three guy wires in each set are usually adequate for a mast. These should be spaced equally round the mast. The required number of sets of guys depends on the height of the mast, its natural sturdiness (or stiffness), and the required antenna tension. A 30-foot-high mast usually requires two sets of guys, and a 50-foot mast needs at least three sets. One guy of the top set should be anchored to a point directly opposing the force exerted by the wire antenna. The other two guys of the same set should be spaced 120° with respect to the first, as shown in the inset in Fig 7.

Generally, the top guys should be anchored at distances from the base of the mast at least 60% of the mast height. The distance of the guy anchors from the mast determines the guy loads and the vertical load compressing the mast. At a 60% distance, the load on the guy wire

opposite the wire antenna is approximately twice the antenna tension. The compression in the mast will be 1.66 times the antenna tension. With the anchors out 80% of the mast height, the guy tension will be 1.6 times larger than the antenna load and the mast compression will be 1.25 times larger.

Whenever possible, the largest available anchor spacing should be used. The additional compression on the mast, due to closer anchor spacing, increases the tendency of the mast to buckle. Buckling occurs when the compression on the unsupported spans between guys become too great for the unsupported length. The section then bows out laterally and will usually fold over, collapsing the mast. Additional sets of guys reduce the tendency for the mast to buckle under the compression by decreasing the unsupported span lengths and stabilizing the mast, keeping it in a straight line.

A natural phenomenon, called *vortex shedding*, can occur when the wind passes over the sections of a guyed mast. For every section size, shape, and length, there is a wind speed that can cause the sections to oscillate mechanically. When all the sections of an antenna support mast are close to the same size and length, it is possible for all of the mast sections to vibrate simultaneously between the guys. To reduce the potential for this, you can place the guys at locations along the mast that will result in different span lengths. This creates different mechanical resonant frequencies for each span, eliminating the possibility of all sections oscillating at the same time.

When determining the guy locations along the mast to treat this problem, you also need to consider the mast buckling requirements. Since the compression in the mast is greatest in the bottom span, and the least in the top span, the guys should be placed to make the bottom span the shortest and the top span the longest. A general guide for determining the different span lengths is to make the unguyed lengths change by 10 to 20%.

Example: For a 30-foot high mast with three guy sets, the equal-guy locations would be every 10 feet. We can make the center span, 10 feet long, and then make the lower span 15% shorter and the top span 15% longer. While this is not an exact technical method to determine the best solution, the approach will create different mechanical resonant frequencies for the spans, with the span lengths approximately adjusted for the varying buckling requirements.

You can eliminate electrical resonance from conductive guy materials that might cause distortion of the antenna radiation pattern by breaking each guy into non-resonant lengths using strain insulators (see **Figs 9** and **10**). This subject is covered in detail later in this chapter.

Guy Material

When used within their safe load ratings, you may use any of the halyard materials listed in Chapter 20 for the mast guys. Nonmetallic materials have the advantage

Fig 9—Simple lever for twisting solid guy wires when attaching strain insulators.

Fig 10—Stranded guy wire should be attached to strain insulators by means of standard cable clamps made to fit the size of wire used.

that there is no need to break them up into sections to avoid unwanted resonant interactions. All of these materials are subject to *stretching*, however, which causes mechanical problems in permanent installations. At rated working loads, dry manila rope stretches about 5%, while nylon rope stretches about 20%. Usually, after a period of wind load and wet/dry cycles, the lines will become fairly stable and require less frequent adjustment.

Solid galvanized steel wire is also widely used for guying. This wire has approximately twice the load ratings of similar sizes of copper-clad wire, but it is more susceptible to corrosion. Stranded galvanized wire sold for guying TV masts is also suitable for light-duty applications, but is also susceptible to corrosion. It is prudent to inspect the guys every six months for signs of deterioration or damage.

Guy Anchors

Figs 11 and **12** show two different kinds of guy anchors. In Fig 11, one or more pipes are driven into the ground at right angles to the guy wire. If a single pipe proves to be inadequate, another pipe can be added in tandem, as shown, and connected with a galvanized steel cable. Heavy-gauge galvanized pipe is preferred for corrosion resistance. Steel fence posts may be used in the same manner. Fig 12 shows a *dead-man* type of

Fig 11—Driven guy anchors. One pipe is usually sufficient for a small mast. For added strength, a second pipe may be added, as shown.

Fig 12—Buried *dead-man* guy anchor (see text).

anchor. The buried anchor may consist of one or more pipes 5 or 6 feet long, or scrap automobile parts, such as bumpers or wheels. The anchors should be buried 3 or 4 feet in the ground. The cable connecting the dead-man to the guys should be galvanized wire rope, like EHS guy cable. You should coat the buried part of the cable with roofing tar, and thoroughly dry it prior to burial to enhance resistance to corrosion.

Also available are some heavy auger-type anchors that screw into the earth. These anchors are usually heavier than required for guying a mast, although they may be more convenient to install. You should conduct annual inspections of the anchors by digging several inches below grade around the anchor to inspect for corrosion.

Trees and buildings may also be used as guy anchors if they are located appropriately. Care should be exercised, however, to make sure that the tree is of adequate size and that any fastening to a building can be made sufficiently secure.

Guy Tension

Many troubles encountered in mast guying are a result of pulling the guy wires too tight. Guy-wire tension should never be more than necessary to correct for obvious bowing or movement under wind pressure. Approximately 10% to 15% of the working load is sufficient. In most cases, the tension needed does not require the use of turnbuckles, with the possible exception of the guy opposite a wire antenna. If any great difficulty is experienced in eliminating bowing from the mast, the guy tension should be reduced or additional sets of guys are required. The mast should be checked periodically, especially after large wind events, to ensure the guys and anchors have not stretched or moved, allowing the mast to get away from the required straight alignment.

ERECTING A MAST OR OTHER SUPPORT

Masts less than 30 feet high usually can be simply walked up after blocking the bottom end securely. Blocking must be done so that the base can neither slip along the ground nor upend when the mast is raised. An assistant should be stationed at each guy wire, and may help by pulling the proper guy wire as the mast nears the vertical position. Halyards can be used in the same manner.

As the mast is raised, it may be helpful to follow the underside of the mast with a scissors rest (**Fig 13**), should a pause in the hoisting become necessary. The rest may also be used to assist in the raising if an assistant mans each leg.

As the mast nears the vertical position, those holding the guy wires should be ready to temporarily fasten the guys to prevent the mast from falling. The guys can then be adjusted until the mast is perfectly straight.

For masts over 30 feet long, a *gin pole* of some form may be required, as shown in Fig 13. Several turns of

Fig 13—Pulling on a gin line fastened slightly above the center point of the mast and on the halyards can assist in erecting a tall mast. The tensions should be just enough to keep the mast in as straight a line as possible. The "scissors" may be used to push on the under side and to serve as a rest if a pause in raising becomes necessary.

rope are wound around a point on the mast above center. The ends of the rope are then brought together and passed over a tree limb. The rope should be pulled as the mast is walked up to keep the mast from bending at the center. If a tree is not available, a post, such as a 2 × 4, temporarily erected and guyed, can be used. After the mast has been erected, the assisting rope can be removed by walking one end around the mast (inside the guy wires).

Telephone poles and towers are much sturdier supports. Such supports may require no guying, but they are not often used solely for the support of wire antennas because of their relatively high cost. For antenna heights in excess of 50 feet, however, they are usually a most practical form of support.

Tower And Antenna Selection and Installation

The selection of a tower, its height, and the type of antennas and rotator is probably one of the more complex issues faced by station builders. All aspects of the tower, antenna, and rotator system are interrelated, and you should consider the overall system before making any decisions regarding specific system components.

Perhaps the most important consideration for many amateurs is the effect of the antenna system on the surrounding environment. If plenty of space is available for a tower installation and if there is little chance of causing esthetic distress on the part of family members or the neighbors, the amateur is indeed fortunate. Often, the primary considerations are purely financial. For most, however, the size of the property, the effect of the system on others, local ordinances, and the proximity of power lines and poles influence the selection of the tower/ antenna system considerably.

The amateur must consider the practical limitations for installation. Some points for consideration are given below:

1) A tower should not be installed in a position where it could fall onto a neighbor's property.
2) The antenna must be located in such a position that it cannot possibly tangle with power lines, either during normal operation or if the structure should fall.
3) Sufficient yard space must be available to position a guyed tower properly. The guy anchors should be between 60% and 80% of the tower height in distance from the base of the tower on level ground—sloping terrain may require larger areas.
4) Provisions must be made to keep children from climbing the support. (Poultry netting around the tower base will serve this need.)
5) Local ordinances should be checked to determine if any legal restrictions affect the proposed installation.

Other important considerations are (1) the total dollar amount to be invested, (2) the size and weight of the antenna desired, (3) the climate, and (4) the ability of the owner to climb a fixed tower.

Most tower manufacturers provide catalogues or data packages that represent engineered tower configurations. These are provided as a convenience for users to help determine the most suitable tower configurations. The most commonly used design specifications for towers are EIA (Electronic Industries Assoc.) RS-222 and UBC (Uniform Building Code). These specifications define how the tower, antenna, and guy loads are determined and applied to the system, and establish general design criteria for the analysis of the tower. Local authorities often require the review and approval of the installation by a state licensed Professional Engineer (P.E.) to obtain building permits. All local authorities in the United States do not subscribe to the same design standards, so often the manufacturers' general-purpose engineering is not applicable.

One of the first things you need to determine in the tower selection process is the type of specification required by the local authorities, if any. Then, you must determine the *Basic Wind Speed* appropriate for the site. The *Basic Wind Speed* used in most specifications is the average wind speed for one mile of wind passing across the structure. It will be a lower value than the peak readings from an anemometer (wind gauge) installed at the site. For example, a Basic Wind Speed of 70 mph could have a maximum value of 80 mph and a minimum of 60 mph, equally distributed during the passage of the mile of wind. Basic wind speeds can be found in tables or maps contained in the appropriate specifications. Often, the basic wind speed used for the location may be obtained from the local permit authority. Check out the Web site at **www.championradio.com**, which contains EIA basic wind speed tables for every county in the USA. UBC speeds are available at almost every local library.

Antenna manufacturers also provide antenna data to assist in the selection process. Unfortunately, antenna mechanical designs do not always follow the same design standards used for towers. Proper antenna selection often means that you must determine the antenna surface areas yourself to avoid overloading the tower. More discussion about this follows later in this chapter.

It is often very helpful to the novice tower installer to visit other local amateurs who have installed towers. Look over their hardware and ask questions. If possible, have a few local experienced amateurs look over your plans—before you commit yourself. They may be able to offer a great deal of help. If someone in your area is planning to install a tower and antenna system, be sure to offer your assistance. There is no substitute for experience when it comes to tower work, and your experience there may prove invaluable to you later.

THE TOWER

Towers for supporting antennas come in a variety of different types. Each type has its own set of benefits and limitations, or conditions and requirements. Often, you can choose a particular tower type by considering issues other than pure mechanical performance. Understanding how each type of tower functions, and what its respective requirements are, are the first steps in making the best tower selection for your own situation.

Guyed Towers

The most common variety of tower is the *guyed tower* made of identical stacked sections, supported by guy cables attached to ground anchors placed symmetrically around the tower. These towers are the most economical, in terms of feet per dollar investment, and are more efficient for carrying antenna loads than non-guyed towers.

The guys resist the lateral loads on the system created by the wind. Since the guys slope down to the ground, horizontal loads due to the wind result in vertical loads applied to the tower at each tower/guy connection. The tower becomes a compression member, trying to resist the column compression generated by the guy reactions. A tower in compression can buckle, so the distance between guy connections along the tower is important.

Tower Bases for Guyed Towers

Another important phenomenon in a guyed tower is stretching of the guy cables. All guys stretch under load and when the wind blows the elongated guys allow the tower to lean over somewhat. If the tower base is buried in the concrete footing—as is commonly done in amateur installations—the bending stress at the tower base can become a significant factor. Towers that have been installed with tapered pier-pin bases much more freely absorb tower leaning, and they are far less sensitive to guy-elongation problems.

The tapered pier-pin tower installation is not without some drawbacks. These installations often require torque-arm guy brackets or six-guy torque-arm assemblies to control tower rotation due to antenna torque. They also require temporary guys when they are being installed to hold the base steady until the permanent guys are mounted. Some climbers also don't like the flexing when they start to climb these types of towers.

On the positive side, pier-pin base towers have all structural members above the concrete footing, eliminating concerns about hidden corrosion that can occur with buried towers. Most decisions regarding the type of base installation are made according to the preference of the tower builder/maintainer. While either type of base configuration can be successfully used, you would be wise to do the stress calculations (or have a professional engineer do them) to ensure safety, particularly when large antenna loads are contemplated and particularly if guys

that can easily stretch are used, such as Phillystran guys.

The configuration shown in **Fig 14A** is taken from an older (1983) Unarco-Rohn catalog. This configuration has the top set of guys placed at the top of the tower with the lower set halfway up the tower. This configuration is best for most amateur installations, which usually have the antennas mounted on a rotatable mast extending

Fig 14—The proper method of installation of a guyed tower. At A, the method recommended for most amateur installations. At B, the method shown in later Rohn catalogs. This places considerable strain on the top section of the tower when large antennas are mounted on the tower.

out the top of the tower—thereby placing the maximum lateral loads when the wind blows at the top of the tower (and the bottom of the rotating mast).

The configuration shown in Fig 14B is from a newer (1998) Rohn catalog. It has 5 feet of unsupported tower extending above the top guy set. The lower guy set is approximately halfway between the top guys and the base. The newer configurations are tailored for commercial users who populate the top region of the tower with fixed arrays and/or dishes. The installation in Fig 14B cannot safely withstand the same amount of horizontal top load as can the configuration shown in Fig 14A, simply because the guys start farther down from the top of the tower.

An overhead view of a guyed tower is given in Fig 14C. Common practice is to use equal angular spacings of 120° between guy wires. If you must deviate from this spacing, the engineering staff of the tower manufacturer or a civil engineer should be contacted for advice.

Amateurs should understand that most catalogs show generic examples of tower configurations that work within the cited design specifications. They are by no means the only solution for any specific tower/antenna configuration. You can usually substantially change the load capability of any given tower by varying the size and number of guys. Station builders are encouraged to utilize the services of professional engineers to get the most out of their guyed towers. Those interested in more generic information about guyed tower behavior can find it at **www.freeyellow.com/members3/yagistress/**.

Unguyed Towers

Another commonly used type of tower is not normally guyed—these are usually referred to as *freestanding* or *self-supporting* towers. Unguyed towers come in three different styles.

One style is comprised of stacked lengths of identical tower sections, just like those used for guyed towers. The only difference is that no guys are used. Manufacturers provide the recommended configurations and allowable loads for this type of installation in their catalogs. Unguyed towers are vastly less capable of supporting antenna loads than their guyed counterparts, but have great utility for light-duty applications—when configured within their capabilities.

The second style utilizes different tower section sizes, varying from large sections at the base and tapering down to smaller sections at the top. This style is more much more efficient for freestanding applications, because the tower is sized for the varying bending loads along the tower length, and is shown in **Fig 15**.

The third style of unguyed towers is commonly called a *crank-up tower*. It is a freestanding tower with telescoping sections that can be extended or retracted with a winch, cable, and pulley mechanism. This allows the tower to be raised and lowered for maintenance and antenna work. It is usually necessary to retract such tow-

Fig 15—Typical freestanding (unguyed) tower. Arrows indicate the directions of the forces acting upon the structure. See text for discussion.

ers for moderate to heavy winds. Some consider this a disadvantage because they can't operate their antennas at full height when it is windy. Two different forms of the crank-up style, freestanding tower are shown in **Fig 16**. Fig 16A shows the tubular version; Fig 16B shows the triangular space-frame version.

Some crank-up towers are used with guys and are only retracted for maintenance and antenna work. These towers are specially designed with locking mechanisms between the tower sections to carry the vertical compression created by the guys. *Do not* use guys with normal crank-up towers (those that have no locking devices between sections)! The increased tower compression will be carried by the hoisting cable, which will eventually cause it to fail.

Never climb a crank-up tower unless it is properly nested, with all load removed from the hoisting cable. For general antenna work, this can be accomplished by completely retracting it until the cable becomes loose. When servicing the rotator, the tower must be left partially extended. In this case every tower section must be

Fig 16—Two examples of *crank-up* towers.

(A)   (B)

Fig 17—Fold-over or tilting base. There are several different kinds of hinged sections permitting different types of installation. Great care should be exercised when raising or lowering a tilting tower.

Freestanding towers are quite popular, and are often the best solutions for sites with limited space and ascetic concerns. When cranked down, a telescoping tower can maintain a low-profile system, out of sight of the neighbors and family.

Tilt-Over Towers

Some towers have another convenience feature—a hinged section that permits the owner to fold over all or a portion of the tower. The primary benefit is in allowing antenna work to be done close to ground level, without the necessity of removing the antenna and lowering it for service. **Fig 17** shows a hinged base used with stacked, guyed tower sections. The hinged section can be designed for portions of the tower above the base. These are usually referred to as *guyed tilt-over towers*, where a conventional guyed tower can be tilted over for installing and servicing antennas. Many crank-up towers come with optional tilt-over base fixtures that are equipped with a winch and cable system for tilting the fully nested tower from horizontal to vertical positions.

Misuse of hinged sections during tower erection is a dangerously common practice among radio amateurs. Unfortunately, these episodes can end in accidents. If you do not have a good grasp of the fundamentals of physics, it might be wise to avoid hinged towers or to consult an expert if there are any questions about safely installing and using such a tower. It is often far easier (and safer) to erect a regular guyed tower or self-supporting tower with gin pole and climbing belt than it is to try to walk up an unwieldy hinged tower.

blocked with heavy timber or thick-wall tubes, installed through the tower bracing, until all sections are resting on the blocks and the hoisting cable becomes slack. Safely installing the blocks in an extended crank-up tower can be challenging. The object is to get all the blocks installed without a climber having to scale the unblocked tower, risking loss of limbs should the hoisting cable fail. An extension ladder, capable of reaching the required block elevations is the safest approach. If the necessary equipment or expertise is not available, the tower can be retracted, antennas removed, and leaned over, with the base tilt-over assembly, before extending it to access the rotator. Failure to properly block the tower before climbing can result in serious injury should the cable slip or break!

All freestanding towers share some unique characteristics. Each must support antenna and tower loads only by virtue of the bending strength of the tower sections and the tower footing connection to earth. Because of the large overturning moment at the tower base, freestanding towers require larger concrete footings than guyed towers. They are usually more expensive for the same load capability compared to guyed towers, simply because they require larger heavier tower sections and a larger footing to get the job done. The telescoping mechanisms in crank-up tower require more maintenance too.

The AB-577 Military Surplus Tower

Another light duty tower has found acceptance among many amateurs. Available from assorted military surplus dealers is the AB-577 system. This was designed to be a portable, rapid deployment antenna support for field communications. It is a guyed mast that goes up somewhat like a crank-up. The system consists of several short sections of aluminum tubing, with special end connections for joining

Fig 18—Installation of surplus AB-577 tower with tribander at 45 feet at K7NV. (*Photo by Kurt Andress, K7NV.*)

Fig 19—Plans for installing concrete base for Wilson ST-77B tower. Although the instructions and dimensions vary from tower to tower, this is representative of the type of concrete base specified by most manufacturers.

them. These can be erected from the base fixture, which has a crank-up type winch-driven elevator platform. The tubing sections are installed in the base fixture and connected to the section above it with an over-center locking *Marmon*-style clamp. Then, the elevator platform is raised with the winch and the new tube is locked in place, high on the base fixture. Then the elevator is lowered to accept the next section. While the tower is extended, the supporting guys are adjusted via the unique *snubber* assemblies at the anchor connection. One person can erect this system, even in windy conditions, when special care is given to keeping the guys properly adjusted during each extension.

The standard AB-577 system, with 3 sets of guys, will support a modest triband Yagi at 45 feet. **Fig 18A** shows an installation with a Hy-Gain TH7DX at 45 feet.

TOWER BASES

Tower manufacturers can provide customers with detailed plans for properly constructing tower bases. **Fig 19** is an example of one such plan. This plan calls for a hole that is $3^{1}/_{2} \times 3^{1}/_{2} \times 6$ feet. Steel reinforcement bars are lashed together and placed in the hole. The bars are positioned so that they will be completely embedded in the concrete, yet will not contact any metallic object in the base itself. This is done to minimize the possibility of a

direct discharge path for lightning through the base. Should such a lightning discharge occur, the concrete base could be damaged.

Providing suitable paths for the discharge of lightning energy safely for towers is a complex subject. Several companies offer products and guidance. The basic requirements for providing controlled discharge paths for lightning-induced current is to supply a low-impedance grid of conductors from the tower and feed lines to a field of interconnected ground rods around the base of the tower. Generally, the tower, station, and electrical service grounds need to be connected to prevent damaging potential differences from developing between the various components in the system.

A strong wooden form is constructed around the top of the hole. The hole and the wooden form are filled with concrete so that the resultant block will be 4 inches above grade. The anchor bolts are embedded in the concrete, and aligned with the plywood template, before it hardens. The template serves to align the anchor bolts to properly mate with the tower itself. Once the concrete has

Fig 20—Another example of a concrete base (Tri-Ex LM-470).

cured, the tower base is installed on the anchor bolts and the base connection is adjusted to bring the tower into vertical alignment.

For a tower that bolts to a flat base plate mounted to the footing bolts (as shown in Fig 19), you can bolt the first tower section on the base plate to ensure that the base is level and properly aligned. Use temporary guys to hold things exactly vertical while the concrete cures. (The use of such temporary guys also works well when you place the first tower section in the base hole and plumb it vertically before pouring in the concrete.) Manufacturers can provide specific, detailed instructions for the proper mounting procedure. **Fig 20** shows a slightly different design for a tower base.

The one assumption so far is that *normal* soil is predominant in the area in which the tower is to be installed. Normal soil is a mixture of clay, loam, sand and small rocks. More conservative design parameters for the tower base should be adopted (usually, using more concrete) if the soil is sandy, swampy or extremely rocky. If there are any doubts about the soil, the local agricultural extension office can usually provide specific technical information about the soil in a given area. When this information is in hand, contact the engineering department of the tower manufacturer or a civil engineer for specific recommendations with regard to compensating for any special soil characteristics.

TOWER INSTALLATION

The installation of a tower is not difficult when the proper techniques are used. A guyed tower, in particular, is not hard to erect, because each of the individual sec-

tions is relatively lightweight and can be handled with only a few helpers and some good quality rope.

The Gin Pole and Tips on Tower Building

An essential piece of hardware for working on towers is a *gin pole*. This section came from the ARRL book *Simple and Fun Antennas for Hams*. The dictionary describes a gin pole as "a device for moving heavy objects." See **Fig 21**, which shows a drawing of the Rohn "Erection Fixture" EF2545. This gin pole was designed to work with the nominal 10-foot long sections of Rohn 25 or 45 towers.

We're going to assume in the following discussion that you are installing Rohn 45, which weighs about 70 pounds. This is a lot of weight, and you must refrain from adding to that during installation. That means, for example, that you *do not* attempt to lift a 10-foot section with the guy wires attached! Neither should you attempt to lift the top section with the rotator and rotor shelf installed. The gin pole (and your ground crew) will not appreciate all that strain.

The main working part of the gin pole is the pulley

Fig 21—Drawing of Rohn "Erection Fixture" EF2545, also known commonly as a "gin pole."

mounted at the top of the 12-foot long heavy-wall aluminum tubing. This pulley has a rope going down to the ground crew through the center of the aluminum tube. At the base of the tower, the pull rope should be run through a *snatch block* attached to the tower just above ground level. This block allows the pull rope to be pulled out horizontally away from the tower base. That helps protect ground crew should a tool be dropped by the people on the tower.

An adjustable, sliding clamp towards the bottom of the aluminum tubing is clamped to the tower using a swinging L-bracket-type clamp with two clamping bolts. These have T-bar handles that can be tightened by hand. In fact, this gin pole can be moved and deployed without any tools. The clamp is positioned on the top of the tower section onto which the next tower section is to be installed. Once clamped to the top of the tower, you would loosen the T-bar handle that tightens the clamp against the sliding aluminum tube and slide the tubing up to its maximum extent.

In practice, the following steps are taken as each 10-foot section of tower is installed, one-by-one. We're assuming here that the gin pole starts out on the ground, with at least one person belted in at the top of the tower. We're also assuming that the pull rope has been threaded through the aluminum tube and the top pulley, with a knot tied to prevent it from falling back down the tube.

1. The clamp holding the aluminum tubing is loosened so that the pulley on the tube can be lowered to where it is just above the bottom clamp. Then the T-bar handle for the tube clamp is tightened.
2. The climber lowers a tag rope for the ground crew to tie to the gin-pole pull rope. (This tag rope has been looped through a temporary pulley clipped to the top of the tower. It is also used to pull up tools and other materials.) The ground crew then pulls the gin pole up to the climber, using the tag line rope. Friction of the rope against the top of the pulley-head assembly will prevent the gin-pole assembly from slipping down. [Note that some climbers prefer to "walk" the gin-pole up the tower rather than having it pulled up from the ground below. They free up their hands for climbing and temporarily holding the gin pole by using their belt lanyard looped around the tower as they climb.]
3. Once the gin-pole head reaches the top of the tower, the climber clamps the gin pole clamp securely to the top of the tower.
4. The T-bar handle for the tube clamp is loosened, and the aluminum tube is extended to its maximum height, as shown in Fig 21. Make sure you have tied the free end of the rope coming through the top pulley temporarily to the top of the tower, or else you'll have to lower the gin pole and go through this step again.
5. The free end of the pulley rope is then dropped to the ground, often using a weight such as a medium Cres-

cent wrench or perhaps a hammer to keep the rope from waving about as it dangles down the tower, tangling with every imaginable thing as it proceeds downwards. It's amazing how even a tiny breeze can make an unweighted rope dance like that.

6. The ground crew then ties the free end of the rope *above* the balance point of the tower. For Rohn 25 or 45 there are eight horizontal cross braces per section. You want the crew to tie the rope to the fifth horizontal brace from the bottom. Please remember that you want the bottoms of the tower sections' legs to be pointed downwards, not flipped over, when the bottom of these legs approach you at the top of the tower section the climber is standing on.
7. Once the bottom of the rising tower section is just above the top of the legs of the bottom tower section, the climber guides the tower down onto the top of the three legs, while calling out to the ground crew instructions about *slowly lowering* the new section down onto the legs. See **Fig 22**, which shows the climber guiding the new section of Rohn HBX tower onto the previous section's legs. This process is considerably easier to accomplish if each section of tower has been put together on the ground to make sure that the legs fit together easily. There's nothing more frustrating that trying to manually force-fit tower sections together at the top of a tower.

It seems that freight companies don't always handle heavy tower sections very gently and legs easily get bent out of alignment. A careful installer numbers tower sections in the order they've been test-fitted together on the ground, marking them with a laundry marker pen. You should also spray a small amount of WD-40 up inside mating tower legs after test-assembling them to help prevent galling and to ease fitting sections together. [Don't do this to excess—WD-40 is slippery and messy when it runs out of the bottom of tower legs.]

Fig 22—Climber is guiding the new section onto the top of the existing one. The gin pole attached to the left leg is bearing the weight, as the climber gives verbal instructions to the ground crew pulling on the gin-pole rope. (*Photo courtesy Mike Hammer, N2VR.*)

Another caution: Make sure before you start installing any tower that the correct ends of the bottom

section's legs, "male" rather than "female," are pointed upwards. A prominent amateur (who will go unnamed) had to have Rohn make and send him a special "gender-bender" flange to turn females into males, since he had installed the base upside-down in the concrete base. You don't want to do that.

8. Once the new tower section has been guided down onto the male ends, the six pinning bolts are inserted and tightened with nuts. Note that Rohn uses two different sized bolts, with the larger diameter one on the bottom.

9. If this section of tower is one where guy wires are to be placed, they can be brought up using the gin pole rope and positioned on the tower. The maximum spacing for Rohn 25 is 30 feet between guy-wire sets, and 40 feet for Rohn 45. Thirty feet of unguyed Rohn 25 tower is wobbly, though safe. Many installers prefer to come down off the tower when setting guy-wire tension, since they do not like to be on a wobbly tower when the ground crew is moving around yanking on guy wires. Many also greatly prefer working on Rohn 45 tower, which is substantially more secure feeling and easier to stand on, with its legs 18 inches apart, while Rohn 25 legs are only 12 inches apart.

10. Finally, you reposition the gin pole for the next section of tower. The T-bar at the clamp is loosened, the tube is dropped down to the level of the clamp, and the climber walks the gin pole up to the top of the section just installed and clamps it there, ready to pull up the next tower section.

Tower Safety

One of the most important aspects of any tower installation project is the safety of all persons involved. See Chapter 1 for details on important safety issues. The use of hard hats is highly recommended for all assistants helping from the ground. Helpers should always stand clear of the tower base to prevent being hit by a dropped tool or hardware. Each person working on the tower must use a good climber's safety belt.

When climbing the tower, if more than one person is involved, one should climb into position before the other begins climbing. The same procedure is required for climbing down a tower after the job is completed. The purpose is to have the non-climbing person stand still so as not to drop any tools or objects on the climbing person, or unintentionally obstruct his movements. When two persons are working on top of a tower, only one should change position (unbelt and move) at a time.

For most installations, a good-quality ¹/₂-inch diameter Manila hemp rope can adequately handle the workload for the hoisting tasks. The rope must be periodically inspected to assure that no tearing or chafing has developed, and if the rope should get wet from rain, it should be hung out to dry at the first opportunity. The knots used for connecting hoisting lines and hardware are critical to executing any safe installation, and special attention should be given to this detail for any work party.

Here is an important point regarding safety—the person who climbs the tower should be in charge of what happens with the ground crew. Not only does the person on the tower have a better overall view of the situation below, but also any confusion on the ground can result in serious injury to the climber.

GUY WIRES

In typical guyed tower installations, guy wires may experience loads in excess of 1000 pounds. Since the guys are the primary means of carrying the horizontal wind loads, great care should be taken in their selection and installation.

Guys come in a variety of materials and constructions. Normally, the tower manufacturer or professional engineer will specify the size and type of cable to be used. The most common type of cable used for tower guying is the EHS (Extra High Strength) galvanized steel cable. The EHS cables are very stiff and are the highest strength

Table 1
Guy Cable Comparisons

Cable	Nominal Dia. Inches	Breaking Strength Lbs	Weight Lbs/100'	Elongation Inches/100'	%Elongation
³/₁₆" 1 × 7 EHS	0.188	3990	7.3	6.77	0.56%
¹/₄" 1 × 7 EHS	0.250	6700	12.1	3.81	0.32%
HPTG6700	0.220	6700	3.1	13.20	1.10%
HPTG8000	0.290	8000	3.5	8.90	0.74%
⁵/₁₆" 1 × 7 EHS	0.313	11200	20.5	2.44	0.20%
HPTG11200	0.320	11200	5.5	5.45	0.45%
³/₈" Fiberglass Rod	0.375	13000	9.7	5.43	0.45%

EHS steel cable information is taken from ASTM A 475-89, the industry standard specification for steel wire rope. The HPTG listings are for *Phillystran* aramid cables, and are based on the manufacturers' data sheets. The elongation (stretch) values are for 100 feet of cable with a 3000-pound load.

cables in the wire rope family. Other steel cables are made to be more flexible for running around pulleys. While these are easier to work with when assembling, they are not as strong as the EHS type, and should be avoided for tower guying. Non-conductive guys, such as *Phillystran* or *pultruded* fiberglass rod have become popular for eliminating resonant interaction with antennas.

Do not attempt to use cheaper cables that don't meet or exceed the criteria for those specified for your installation. Using the wrong cable, or failing to install the cable properly can have disastrous results! **Table 1** shows data for several cables commonly used for tower guying. It is important to note that the minimum breaking strength of the various cables are independent of their elongation (stretch) under load.

Guy Cable Installation

Figs 23 and **24** show methods for tensioning and safety wiring guy-wire turnbuckles. **Fig 25** shows the traditional method for fixing the end of a steel guy wire. A thimble is used to prevent the wire from breaking because of a sharp bend at the point of intersection. Conventional wisdom strongly recommends the use of thimbles that are at least one wire size larger than the cable to provide a more gentle wire bend radius. Three cable clamps follow to hold the wire securely. Be sure to follow the note in Fig 25 for which part of the clip bears against the live (loaded) cable. As a final backup measure, the individual strands of the free end are unraveled and wrapped around the guy wire. It is a lot of work, but it is necessary to ensure a safe and permanent connection.

Fig 26 shows the use of a device that replaces the clamps and twisted strands of wire. These devices are known as *dead ends*, *preformed guy grips*, or *Big Grips* and are commonly used on electrical power poles. They are far more convenient to use than are clamps, and are the recommended method for terminating Phillystran and

Fig 24—A length of guy cable is used to assure that the turnbuckles remain in place after they are tightened. This procedure is an absolute requirement in guyed tower systems. (*Photo by N4QX*)

Fig 25—Traditional method for securing the end of a guy wire.

Fig 23—Proper tension can be placed on the guy wires with the aid of a block-and-tackle system. (*Photo by K1WA*)

Fig 26—Alternative method for attaching guy wires using *dead ends*. The dead end on the right is completely assembled (the end of the guy wire extends beyond the grip for illustrative purposes). On the left, one side of the dead end is partially attached to the guy wire. In front, a thimble is used where a sharp bend might cause the guy wire or dead end to break.

fiberglass-rod guys. When using the guy grips, it is imperative that the recommended end sleeves are installed over the free end of the grip to prevent ice and falling hardware from sliding down the guy and unraveling the grip connection to the guy. The guy wires must be cut to the proper length. The dead end of each wire is installed into the object to which the guy wire is being attached (use a thimble, if needed to eliminate sharp cable bends). One side of the dead end is then wrapped around the guy wire. The other side of the dead end follows. Using dead ends saves time and trouble, more than making up for their slightly higher cost.

When using the non-conductive guy materials, it is highly recommended that a 25-foot length of EHS steel cable be used at the bottom for connection to the anchor. This serves a valuable purpose. The steel cable is more resistant to damage from ground activity and brush fires, and it is the preferred material for measuring cable pre-tension with commonly available devices.

Fig 27 shows two different methods for attaching guy wires to towers. At Fig 27A, the guy wire is simply looped around the tower leg and terminated in the usual manner. At Fig 27B, a *guy bracket*, with *torque arms* has been added. Even if the torque arms are not required, it is preferred to use the guy bracket to distribute the load from the tower/guy connection to all three tower legs, instead of just one. The torque bracket is more effective resisting torsional loads on the tower than the simpler installation. Rohn offers another guy attachment bracket, called a *Torque Arm Assembly*, that allows six guys to be connected between the bracket and anchors. This is by far the best method of stabilizing a tower against high torque loads, and is recommended for installations with large antennas.

There are two types of commonly used guy anchors. **Fig 28A** depicts an *earth screw*. These are usually 4 to 6 feet long. The screw blade at the bottom typically measures 6 to 8 inches diameter. Fig 28B illustrates two people installing the anchor. The shaft is tilted so that it will be in line with the mean angle of all the guys connecting to the anchor. Earth screws are suitable for use in normal soil where permitted by local building codes. Information about *screw anchors* is available from the manufacturers of these devices. Information from a supplier specializing in this type of anchor can be found at **www.abchance.com**.

The alternative to earth screws is the concrete block anchor. Fig 28C shows the installation of this type of anchor; it is suitable for any soil condition, with the possible exception of a bed of lava rock or coral. Consult the instructions from the manufacturer, or your tower designer, for the precise anchor configuration.

Turnbuckles and associated hardware are used to attach guy wires to anchors and to provide a convenient method for adjusting tension. **Fig 29A** shows a turnbuckle with a single guy wire attached to the eye of the anchor. Turnbuckles are usually fitted with either two eyes, or one eye and one jaw. The eyes are the oval ends, while the jaws are U-shaped with a bolt through each tip.

Fig 27—Two methods of attaching guy wires to tower. See text for discussion.

Fig 28—Two standard types of guy anchors. The earth screw shown at A is easy to install and widely available, but may not be suitable for use in certain soils. The concrete anchor is more difficult to install properly, but it is suitable for use with a wide variety of soil conditions and will satisfy most building code requirements.

Fig 29—Variety of means available for attaching guy wires and turnbuckles to anchors.

Fig 29B shows two turnbuckles attached to the eye of an anchor. The procedure for installation is to remove the bolt from the jaw, pass the jaw over the eye of the anchor and reinstall the bolt through the jaw, through the eye of the anchor and through the other side of the jaw.

If two or more guy wires are attached to one anchor, *equalizer plates* should be installed (Fig 29C). In addition to providing a convenient point to attach the turnbuckles, the plates pivot slightly to equalize the various guy loads and produce a single load applied to the anchor. Once the installation is complete, a safety wire should be passed through the turnbuckles in a figure-eight fashion to prevent the turnbuckles from turning and getting out of adjustment (Fig 29D).

All guyed towers require the guys to be installed with a certain amount of pre-tension. The tower manufacturer or designer specifies the required pre-tension values,

which are usually 10% of the cable breaking strength. Pre-tension is necessary to eliminate looseness in the cable caused by the spiral wire construction and to eliminate excessive dynamic guy and tower motion under wind loading. The recommended method for adjusting the guys is to use a cable tension-measuring device such as the popular *Loos Guy Wire Tensioner*. The guy is gripped with a special clamp, such as the *Klein Cable Grip*, which is connected to the anchor below the eye (or equalizer plate) with a block and tackle arrangement (Fig 23) or a ratcheting come-along. Then the turnbuckle is adjusted to take up the load, the cable grip is released and the final guy tension is adjusted and checked.

When you adjust the guys at each level, you should check the tower for vertical alignment and straightness. This is often done with a transit from two ground points located 90° from each other.

Resonance in Guy Wires

If guy wires are resonant at or near the operating frequency, they can receive and reradiate RF energy. By behaving as parasitic elements, the guy wires may alter and thereby distort the radiation pattern of a nearby antenna. For low frequencies where a dipole or other simple antenna is used, this is generally of little or no consequence. But at the higher frequencies where a unidirectional antenna is installed, it is desirable to avoid pattern distortion if at all possible. The symptoms of re-radiating guy wires are usually a lower front to back ratio and a lower front to side ratio than the antenna is capable of producing. The gain of the antenna and the feed-point impedance will usually not be significantly affected, although sometimes changes in SWR can be noted as the antenna is rotated. (Of course other conductors in the vicinity of the antenna can also produce these same symptoms.)

The amount of re-radiation from a guy wire depends on two factors—its resonant frequency, and the degree of coupling to the antenna. Resonant guy wires near the antenna will have a greater effect on performance than those that are farther away. Therefore, the upper portion of the top level of guy wires should warrant the most attention with horizontally polarized arrays. The lower guy wires are usually closer to horizontal than the top level, but by virtue of their increased distance from the antenna, are not coupled as tightly to the antenna.

To avoid resonance, the guys should be broken up by means of egg or strain insulators. **Fig 30** shows wire lengths that fall within 10% of $1/2$-λ resonance (or a multiple of $1/2$ λ) for all the HF amateur bands. Unfortunately, no single length greater than about 14 feet avoids resonance in all bands. If you operate just a few bands, you can locate greater lengths from Fig 30 that will avoid resonance. For example, if you operate only the 14-, 21- and 24-MHz bands, guy wire lengths of 27 feet or 51 feet would be suitable, along with any length less than 16 feet.

Fig 30—The black bars indicate ungrounded guy wire lengths to avoid for the eight HF amateur bands. This chart is based on resonance within 10% of any frequency in the band. Grounded wires will exhibit resonance at odd multiples of a quarter wavelength. (*By Jerry Hall, K1TD*.)

THE RIGHT TOWER FOR YOUR ANTENNA

Most manufacturers rate their towers in terms of the maximum allowable antenna load that can safely be carried at a specific wind speed. Ensuring that the specific antennas you plan to install meet the tower's design criteria, however, may not always be a straightforward task.

For most towers, the manufacturer assumes that the allowable antenna load is a horizontal force applied at the top of the tower. The allowable load represents a defined amount of exposed antenna area, at a specified wind velocity. Most tower manufacturers rate the load in terms of *Flat Projected Area* (FPA). This is simply the equivalent area of a flat rectangular surface at right angles to the wind. The FPA is not related to the actual shape of the antenna itself, only its rectangular projected area. Some manufacturers provide separate FPAs for antennas made from cylindrical sections and those made from rectangular sections.

In the realm of antenna manufacturers, however, you may encounter another wind load rating called the *Effective Projected Area* (EPA). This attempts to take into account the actual shape of antenna elements. The problem is that there is no agreed-upon standard for the conversion from EPA to load numbers. Different manufacturers may use different conversion factors.

Since most tower manufacturers have provided FPA figures for their towers—allowing us in effect to ignore design-specification details—it would be easiest for us to work only with FPA values for our antennas. This would be fine, if indeed we had good FPA figures for the specific antennas we plan to use! Unfortunately, FPAs are rarely specified for commercially built amateur antennas. Instead, most antenna manufacturers provide effective areas in their specification sheets. You may need to contact the antenna manufacturer directly for the FPA antenna area or for the antenna dimensions so that you can do your own FPA calculations.

Determining Antenna Areas

The method for determining the flat projected area of an antenna is quite simple. We'll use a Yagi antenna as an example. There are two worst-case areas that should be considered here. The first is the FPA of all the elements when the wind blows in the direction along the boom; that is, at right angles to the elements. The second FPA for a Yagi is when the wind is at right angles to the boom. One of these two orientations produces the worst-case exposed antenna area—all other wind angles present lower exposed areas. The idea is to take the highest of the FPAs for these two wind directions and call that the FPA of the antenna structure. See **Fig 31A**.

The element FPA is calculated by multiplying each element's dimension of length by its diameter and then

$$Fc = AP \; SIN^2(Angle) \; COS(Angle)$$

$$Fr = AP \; SIN^2(Angle)$$

$$Fd = AP \; SIN^3(Angle)$$

(A) Wind

Angle

(B) Wind

Ae, Fe1, Fb1, Fe2, Ab, Fb2, Fe3, Fe4

Antenna Area vs Azimuth

Projected Area (SqFt)

Azimuth Angle (Deg)

·········· Elements (Ae)   – – – – Boom (Ab)   ——— Total

(C)

Fig 31—Description of how loads are developed on a Yagi. At A, Fr is the resultant force from the wind load on a generalized member. Fd is the load acting downwind (drag) that creates the load on the tower. Fc is the lateral component of the wind load. The term A is the flat projected area (FPA), which is the broadside area normal to the wind. The term P is the wind pressure. At B, Ae is the total element area, while Ab is the total boom area. All the loads due to the wind act normal to the antenna sections—the force on element #1 (Fe1) acts along the axis of the boom, for example. At C, a plot of the *effective FPA* as a function of the azimuthal wind direction for a Yagi, ignoring drag coefficients. The Yagi in this example has 9.0 square feet of element FPA and 6.0 square feet of boom FPA. The worst-case FPAs occur with the beam pointed in the wind and with the boom broadside to the wind. To determine the actual tower loading, the actual drag coefficients and wind pressures must be used.

summing the FPAs for all elements. The boom's FPA is computed by multiplying the boom's length by its diameter.

The reason for considering two potential peak-load orientations becomes clear when different frequency antennas are stacked on a mast or tower. Some antennas produce peak loads when the elements are broadside to the wind. This is typical of low-frequency Yagis, where the elements are long lengths of aluminum tubing. On

the other hand, the boom can dominate the surface area computations in higher-frequency Yagis.

The fundamentals responsible for the need to examine both potential FPAs for Yagis relates to how wind flows over a structure and develops loads. Called *The Cross-Flow Principle*, this was introduced to the communications industry by Dick Weber, K5IU, in 1993. The principle is based on the fact that the loads created by wind flowing across an antenna member only produce forces that are normal to (or perpendicular to) the major axis of the member. The resultant and component load calculations for this method are shown in Fig 31A.

For a Yagi, this means that wind forces on the elements act in-line with the boom, while forces on the boom act in-line with the elements. Fig 31B shows a force diagram for a typical Yagi. Fig 31C shows the FPA for a Yagi rotated through 90° of azimuth.

Antenna Placement on the Mast/Tower

Another important consideration is where the antenna(s) will be placed on the tower. As mentioned before, most generic tower specifications assume that the entire antenna load is applied at the top of the tower. Most amateur installations have a tubular mast extending above the tower top, turned by a rotator mounted down inside the tower. Multiple Yagi antennas are often placed on the mast above the tower top, and you must make sure that both the tower and the mast can withstand the wind forces on the antennas.

For freestanding towers, you can determine how a proposed antenna configuration compares to the tower manufacturer's rating by using an *Equivalent Moment* method. The method computes the bending moment generated at the base of the tower by wind loads on the tower's rated antenna area located right at the top of the tower and compares that to the case when the antenna is mounted on a mast sticking out of the top of the tower.

The exact value of wind pressure is not important, so long as it is the same for both comparisons. The wind load on the tower itself can be ignored because it is the same in both comparisons and the drag coefficients for the antennas can also be ignored if all calculations are performed using flat projected antenna areas, as we've recommended previously.

Keep in mind that this approach does not calculate *actual* loads and moments relevant to any specific tower design standard, but it does allow equivalent comparisons when the wind pressure is constant and all the antenna areas are of the same type. An example is in order.

Fig 32A shows a generic tower configuration, with a concentrated antenna load at the top of the tower. We'll assume that the tower manufacturer rates this tower at 20 square feet of flat projected antenna area. Fig 32B shows a typical amateur installation with a rotating mast and an antenna mounted 7 feet above the top of the tower. To make the calculations easy, we select a wind pressure

Fig 32—At A, a 70-foot tower rated for 20 square feet of antenna load at the top. At B, the same tower with a 2-inch OD × 20-foot long mast, with an antenna mounted 7 feet above the top of the tower. Both configurations produce the same tower load.

of 1 pound per square foot (1 psf). This makes the tower base moment calculation for Fig 32A:

Antenna load = 20 feet^2 × 1 psf = 20 pounds
Base moment = 70 feet × 20 pounds =
    1400 foot-pounds.

This is the target value for the comparison. An equivalent configuration would produce the same base moment. For the configuration in Fig 32B, we assume a tubular 2-inch diameter mast that is 20 feet long, mounted 5 feet down inside the tower. Note that the lattice structure of the tower allows the wind to "see" the whole length

of the mast and that we can consider the force distributed along the mast as being a single force concentrated at the mast's center. The flat projected area of the mast by itself, without the antenna, is:

Mast area = 20 feet × 2 inches / 12 inches/foot =
    3.33 square feet

The center of the mast is located at a height of 75 feet. Using the same 1-psf-wind load, the base bending moment due to the mast alone is:

Base moment (due to mast) = 3.33 feet^2 × 1 psf ×
    75 feet = 249.75 foot-pounds

Including the mast in the configuration reduces the allowable antenna load. The remaining target base moment left for the antenna is found by subtracting the moment due to the mast from the original target value:

New base target moment = 1400 - 249.75 foot-pounds
    = 1150.25 foot-pounds.

The antenna in Fig 32B is located at a height of 77 feet. To obtain the allowable antenna area at this elevation we divide the new base target moment by the antenna height, yielding an allowable antenna load of:

1150.25 foot-pounds / 77 feet = 14.94 pounds.

Since we chose a wind load of 1 psf, the allowable antenna FPA has been reduced to 14.94 square feet from 20 square feet. If the projected area of the antenna we are planning to mount in the new configuration is less than or equal to this value, we have satisfied the requirements of the original design. You can use this equivalent-moment method to evaluate different configurations, even ones involving multiple antennas on the mast or situations with additional antennas placed along the tower below the tower top.

For guyed towers, the analyses become much more rigorous to solve. Because the guys and their behaviors are such a significant portion of the tower support mechanism, these designs can become very sensitive to antenna load placements. A general rule of thumb for guyed towers is never to exceed the original tower-top load rating, regardless of distributed loads along its length. Once you redistribute the antenna load placements along a guyed tower, you should do a fresh analysis, just to be sure.

You can run evaluations using the above method for antennas placed on the mast above a guyed tower top. The use of the Equivalent-Moment method for antennas mounted below the top of a guyed tower, however, can become quite suspect, since many generic tower designs have their intermediate guys sized for zero antenna loads lower down the tower. The proper approach in this case is to have a qualified mechanical engineer check the configuration, to see if guy placement and strength is adequate for the additional antennas down the tower.

Mounting the mast and antenna as shown in Fig 32B

increases tower loads in the region of the mast. You should investigate these loads to ensure that the tower bracing in that area is sufficient. Now we will consider the problem of bending the rotating mast.

Mast Strength

When you mount antennas on a mast above the tower top, you should examine the bending loads on the mast to ensure that it will be strong enough. This section explains how to perform mast stress calculations for a single sustained wind speed. This procedure does not include height, exposure and gust-response factors found in most tower design standards.

Here are some fundamental formulas and values used to calculate the bending stress in a mast mounted in the top of a tower. The basic formula for wind pressure is:

$$P = .00256 \, V^2 \qquad \text{(Eq 1)}$$

where

P is the wind pressure is in pounds per square foot (psf)
V = wind speed in miles per hour (mph)

This assumes an air density for standard temperature and atmospheric pressure at sea level. The wind speed is not the Basic Wind Speed discussed in other sections of this chapter. It is simply a steady state (static) wind velocity.

The formula for calculating the force created by the wind on a structure is:
$$F = P \times A \times C_d \qquad \text{(Eq 2)}$$

where

P = the wind pressure from Eq (1)
A = the flat projected area of the structure (square feet)
C_d = drag coefficient for the shape of the structure's members.

The commonly accepted *drag coefficient* for long cylindrical members like the tubing used for the mast and antenna is 1.20. The coefficient for a flat plate is 2.0.

The formula used to find the *bending stress* in a simple beam like our mast is:

$$\sigma = \frac{M \times c}{I} \qquad \text{(Eq 3)}$$

where

σ = the stress in pounds per square inch (psi)
M = *bending moment* at the base of the mast (inch-pounds)
c = ½ of the mast outside diameter (inches)
I = *moment of inertia* of the mast section (inches⁴)

In this equation you must make sure that all values are in the same units. To arrive at the mast stress in pounds per square inch (psi), the other values need to be in inches

and pounds also. The equation used to find the moment of inertia for the round tubing mast section is:

$$I = \frac{\pi}{4}(R^4 - r^4) \qquad \text{(Eq 4)}$$

where

I = Moment of Inertia of the section (inches⁴)
R = Radius of tube outside diameter (inches)
r = Radius of tube inside diameter (inches)

This value describes the distribution of material about the mast *centroid*, which determines how it behaves under load. The equation used to compute the *bending moment* at the base of the mast (where it is supported by the tower) is:

$$M = (F_M \times L_M) + (F_A \times L_M) \qquad \text{(Eq 5)}$$

where

F_M = wind force from the mast (pounds)
L_M = Distance from tower top to center of mast (inches)
F_A = Wind force from the antenna (pounds)
L_A = Distance from tower top to antenna attachment (inches)

L_M is the distance to the center of the portion of the mast extending above the tower top. Additional antennas can be added to this formula by including their F × L. In the installation shown in Fig 32B, a wind speed of 90 mph, and a mast that is 2 inches OD, with a 0.250-inch wall thickness, the steps for calculating the mast stress are:

1. Calculate the wind pressure for 90 mph, from Eq 1:

$P = .00256 \, V^2 = .00256 \times (90)^2 = 20.736$ psf

2. Determine the flat projected area of the mast. The portion of the mast above the tower is 15 feet long and has an outside diameter of 2 inches, which is 2/12 feet.

Mast FPA, A_M = 15 feet × (2 inches / 12 inches/feet) = 2.50 square feet.

3. Calculate the wind load on the mast, from Eq 2:

Mast Force, $F_M = P \times A \times C_d =$
20.736 psf × 2.50 feet² × 1.20 = 62.21 pounds

4. Calculate the wind load on the antenna: From Eq 2

Antenna Force, $F_A = P \times A \times C_d = 20.736$ psf × 14.94 feet² × 1.20 = 371.76 pounds

5. Calculate the mast *Bending Moment*, from Eq 5:

$M = (F_M \times L_M) + (F_A \times L_A)$
= (62.21 pounds × 90 inches) + (371.76 pounds × 84 inches) = 36827 inch-pounds

where L_M = 7.5 feet × 12 inches/foot = 90 inches and L_A = 7.0 feet × 12 inches/foot = 84 inches.

6. Calculate the mast *Moment of Inertia*, from Eq 4:

$$I = \frac{\pi}{4}(R^4 - r^4) = \frac{\pi}{4}(1.0^4 - 0.75^4) = 0.5369 \text{ inches}^4$$

where, for a 2.0-inch OD and 0.250-inch wall thickness tube, R= 1.0 and r = 0.75.

7. Calculate the mast *Bending Stress*, from Eq 3:

$$\sigma = \frac{M \times c}{I} = \frac{36827 \text{ inch-pounds} \times 1.0 \text{ inches}}{0.5369} = 68592 \text{ psi}$$

If the yield strength of the mast material is greater than the calculated bending stress, the mast is considered safe for this configuration and wind speed. If the calculated stress is higher than the mast yield strength, a stronger alloy, or a larger mast, or one with a thicker wall is required.

There are many different materials and manufacturing processes for tubing that may be used for a mast. Yield strengths range from 25,000 psi to nearly 100,000 psi. Knowing the minimum yield strength of the material used for a mast is an important part of determining if it will be safe. Using unknown materials renders efforts from the preceding calculations useless!

When evaluating a mast with multiple antennas attached to it, special care should be given to finding the worst-case condition (wind direction) for the system. What may appear to be the worst load case, by virtue of the combined flat projected antenna areas, may not always be the exposure that creates the largest mast bending moment. Masts with multiple stacked antennas should always be examined to find the exposure that produces the largest mast bending moment. The antenna flat projected areas at 0° and 90° azimuths are particularly useful for this evaluation.

ANTENNA INSTALLATION

All antenna installations are different in some respects. Therefore, thorough planning is the most important first step in installing any antenna. Before anyone climbs the tower, the whole process should be discussed to be sure each crewmember understands what is to be done. And remember that the person on the tower is in charge! Coordinate beforehand what signals and commands are used: "Up" or "Up Slowly" for raising something from the ground; "Down" or "Down Slowly" for the opposite.

"Watch Out!" or 'Watch Out Below!" works for dropped hardware or tools to alert the ground crew below. Remember, once someone is on the tower, no one should be allowed to stand near the base of the tower!

Consider what tools and parts must be assembled and what items must be taken up the tower, and plan alternative actions for possible trouble spots. Extra trips up and down the tower can be avoided by careful planning.

If done properly, the actual work of getting the antenna into position can be executed quite easily with only one person at the top of the tower. The ground crew should do all the heavy work and leave the person on the tower free to guide the antenna into position. Because the ground crew does all the lifting, a large pulley, preferably on a gin pole placed at the top of the tower, is essential. Local radio clubs often have gin poles available for use by their members. Stores that sell tower materials frequently rent gin poles as well.

A gin pole should be placed along the side of the tower so the pulley is no more than 2 feet above the top of the tower (or the point at which the antenna is to be placed). Normally this height is sufficient to allow the antenna to be positioned easily. An important reason that the pulley is placed at this level is that there can be considerable strain on the gin pole when the antenna is pulled away from the tower to maneuver past guy wires.

Sometime the mast to which the antenna will be mounted is used as a place to hang the pulley. You should take care that you don't end up bending the mast by placing the pulley too high on the mast. It may be necessary to back-guy the mast on the opposite side of the tower from which the antenna is raised.

The rope (halyard) through the pulley must be somewhat longer than twice the tower height so that the ground crew can raise the antenna from ground level. The rope should be ½ or ⅝ inch diameter for both strength and ease of handling. Smaller diameter rope is less easily manipulated; it has a tendency to jump out of the pulley track and foul pulley operation.

The first person to climb the tower should carry an end of the halyard so that the gin pole can be lifted and secured to the tower. Those climbing the tower must have safety belts. Belts provide safety and convenience; it is simply impossible to work effectively while hanging onto the tower with one hand.

Once positioned, the gin pole and pulley allow parts and tools to be sent up the tower. A useful trick for sending up small items like bolts and pliers is for a ground crew member to slide them through the rope strands where they are held by the rope for the trip to the top of the tower. Items that might be dislodged by contact with the tower should either be taped or tied to the halyard. Ever present is the hazard of falling tools or hardware. It is foolish to stand near a tower when someone is working above. Ground crew member should wear hard-hats as extra insurance.

Raising the Antenna Alongside the Tower

A technique that can save much effort in raising the antenna is outlined here. First, the halyard is passed through the gin-pole pulley or the pulley mounted to the mast, and the leading end of the rope is returned to the ground crew, where it is tied to the antenna. The assembled antenna should be placed in a clear area of the yard (or the roof) so the boom points toward the tower. The halyard is then passed *under* the front elements of the beam to a position past the midpoint of the antenna, where it is securely tied

to the boom (**Fig 33A**).

Note that once the antenna is installed, the tower worker must be able to reach and untie the halyard from the boom; the rope must be tied less than an arm's length along the boom from the mounting point. If necessary, a large loop may be placed around the first element located beyond the midpoint of the boom, with the knot tied near the center of the antenna. The rope may then be untied easily after completion of the installation. The halyard should be tied temporarily to the boom at the front of the antenna by means of a short piece of light rope or twine.

While the antenna is being raised, the ground crew does all the pulling. As soon as the front of the antenna reaches the top of the mast, the person atop the tower unties the light rope and prevents the front of the antenna from falling, as the ground crew continues to lift the antenna (Fig 33B). When the center of the antenna is even with the top of the tower, the tower worker puts one bolt through the mast and the antenna-mounting bracket on the boom. The single bolt acts as a pivot point and the ground crew continues to lift the back of the antenna with the halyard (Fig 33C). After the antenna is horizontal, the tower worker secures the rest of the mounting bolts and unties the halyard. By using this technique, the tower worker performs no heavy lifting.

Avoiding Guy Wires

Although the same basic methods of installing a Yagi apply to any tower, guyed towers pose a special problem. Steps must be taken to avoid snagging the antenna on the guy wires. With proper precautions, however, even large antennas can be pulled to the top of a tower, even if the

Fig 33—Raising a Yagi antenna alongside the tower. At A the Yagi is placed in a clear area, with the boom pointing toward the tower. The halyard is passed under the elements, then is secured to the boom beyond the midpoint. B shows the antenna approaching the top of the mast. The person on the tower guides it after the lifting rope has been untied from the front of the antenna. At C the antenna is pulled into a horizontal position by the ground crew. The tower worker inserts the pivot bolt and secures it. Note: A short piece of rope is tied around the halyard and the boom at the front of the antenna to stabilize the beam as it is being raised. The tower worker removes it when the boom reaches him at the top of the tower.

Fig 34—Building a Yagi partway down the tower. At A, the boom is lashed temporarily to the tower and elements are added, starting at the bottom. At B, the temporary rope securing the boom to the tower is removed and the boom is rotated 90° so that the elements are vertical. At C, the boom is rotated another 90°, "weaving through" guy wires if necessary, until the elements are parallel with the ground, whereupon the boom is secured to the tower.

mast is guyed at several levels.

Sometimes one of the top guys can provide a *track* to support the antenna as it is pulled upward. Insulators in the guys, however, may obstruct the movement of the antenna. A better track made with rope is an alternative. One end of the rope is secured outside the guy anchors. The other end is passed over the top of the tower and back down to an anchor near the first anchor. So arranged, the rope forms a narrow V-track strung outside the guy wires. Once the V-track is secured, the antenna may simply be pulled up, resting on the track.

Another method is to tie a rope to the back of the antenna (but within reach of the center). The ground crews then pull the antenna out away from the guys as the antenna is raised. With this method, some crewmembers are pulling up the antenna to raise it while others are pulling down and out to keep the beam clear of the guys. Obviously, the opposing crews must act in coordination to avoid damaging the antenna. The beam is especially vulnerable when it begins to tip into the horizontal posi-

tion. If the crew continues to pull out and down against the antenna, the boom can be broken. Another problem with this approach is that the antenna may rotate on the axis of the boom as it is raised. To prevent such rotation, long lengths of twine may be tied to outer elements, one piece on each side of the boom. Ground personnel may then use these *tag lines* to stabilize the antenna. Where this is done, provisions must be made for untying the twine once the antenna is in place.

A third method is to tie the halyard to the center of the antenna. A crewmember, wearing a safety belt, walks the antenna up the tower as the crew on the ground raises it. Because the halyard is tied at the balance point, the tower worker can rotate the elements around the guys. A tag line can be tied to the bottom end of the boom so that a ground worker can help move the antenna around the guys. The tag line must be removed while the antenna is still vertical.

A fourth method is to build the antenna on the tower and then swing it into position. (See also the section below on the PVC Mount.) Building the Yagi on the tower works particularly well for Yagis mounted partway up the tower, as you might do in a stacked array. The technique works best when the vertical spacing between the guys is greater than the length of the Yagi boom.

Fig 34 illustrates the steps involved. A pull rope through a gin-pole or tower-mounted pulley is secured to the boom at the final balance point and the ground crew raises the boom in a vertical position up the tower. A tie rope is used to temporarily secure the upper end of the boom to keep it stable while the boom is being raised. The tower person removes the tie-rope once the boom is raised to the right level and has been temporarily secured to the tower.

The elements are then brought up one at a time and mounted to the boom. It helps if you have a 2- or 3-foot long *spotting mast* temporarily attached to the boom to form a 90° frame of reference. This allows the ground crew to spot from below so that the elements are all lined up in the same plane. After all the elements are mounted and aligned properly, the temporary rope securing the boom to the tower is released, suspending the antenna on the pull rope. The tower person then rotates the boom 90° so that the elements are vertical. Next the elements are rotated 90° into the tower so that they are parallel to the ground. The ground crew then moves the boom up or down using the pull rope to the final point where it is mounted to the tower.

A modification of this technique also works for building a medium-sized Yagi on the top of the tower. This technique will work if the length of the gin pole at maximum safe extension is long enough. See **Fig 35**.

As usual, the gin-pole pull rope is attached to the balance point of the boom and the boom is pulled up the tower in the vertical position, using a rope to temporarily tie the pull rope to the top end of the boom for stability.

Fig 35—Building a Yagi at the top of the tower. The length of the gin pole must be longer than $1/2$ the boom so that the boom can be hoisted upwards to the place where it is mounted to the mast. Usually the boom is initially lashed to the tower slanted slightly from vertical so that the top element ends up *behind* the gin pole. The elements are mounted at the bottom end of the boom first to provide stability. Then the element at the top of the boom is mounted and the boom is moved upwards using the gin-pole hoist rope so that the next-to-top element may be mounted, again behind the gin pole. This process is repeated until all elements are mounted (save possibly the middle element if it can be reached easily from the tower once the beam has been mounted to the mast). Then the boom is tilted to the final position, weaving the elements to clear guy wires if necessary.

The boom is temporarily secured to the tower with rope in the vertical position so that the top end is just higher than the top of the tower. In order to clear the gin pole when the elements are mounted and the boom is raised higher to mount the next element, you must tilt the boom slightly so that the element mounted to the top end of the boom will be *behind* the mast. This is very important!

The elements are first mounted to the bottom side of the boom to provide weight down below for stability. Then the top-most element is mounted to the boom. The tower person removes the temporary rope securing the boom to the tower and the ground crew uses the pull rope

to move the mast vertically upwards to the point where the next element from the top can be mounted. Once all the elements are mounted and aligned in the same plane (with perhaps the center element closest to the mast-to-boom bracket left on the ground until later), the temporary securing rope is removed. The boom is now swung so that the elements can be maneuvered to clear the top guy wires. Once the elements are horizontal the boom is secured to the mast and the center element is mounted.

Using a Tram

Another method to get a large Yagi to the top of the tower safely is a *tram*. A tram supports the antenna *under* the tram wire, using a pulley riding on the tram wire. The antenna can thus move more freely—without the friction it would have riding on top of a track rope, as described previously. This puts considerably less strain on the tram wire itself and on the mast to which it is tied on the tower. Some installers prefer to use a wire-rope tramline for its reduced sag.

The tram method uses an easily constructed fixture mounted to the boom of the Yagi to stabilize it from rotating away from the desired attitude as the antenna is raised. A guy-wire cable or heavy rope is fixed to the mast about two feet above the point where the antenna will mount to the mast. A come-along is often used at the ground end to tension the tram wire properly. It is often necessary to back-guy the mast to make sure it doesn't get bent, since the horizontal forces acting on the mast can be considerable in any tram (or track) operation. (Note that the tram technique works well for side-mounted antennas also, where back-guying is not necessary if you are reasonably close to a guy set, as is usually the case.)

Fig 36 is a photograph of a tram fixture built by Kurt Andress, K7NV. This consists of a pulley riding on top of the tramline. This pulley is attached using a caribiner or shackle to two equal-length wires connected to the boom to make an inverted-V shaped *sling*. The two sling wires are secured to the boom using angle irons and muffler clamps so that the antenna is perfectly balanced in the horizontal plane. Balance is very important to make sure the antenna rises properly on the tram without having the boom rotate downward on one end or the other.

The hoisting rope running through the tower-mounted gin-pole pulley (and used by the ground crew to pull the antenna up to the tower on the tram line) is attached to a 2-foot piece of angle iron. This is attached to the boom with a

Fig 36—Photo of the tram system used by Kurt Andress, K7NV. (*Photo by K7NV.*)

muffler clamp. Note that the angle iron is rotated slightly from horizontal so that the plane of the elements is tilted upwards—this allows the elements to clear the guy wires as the antenna is raised. (While the antenna is close to the ground, the angle iron is adjusted so that the elements remain horizontal. Once they are clear of the ground, the angle iron is readjusted to align the elements in the proper direction to clear the guy wires on the tower.) The force of the pull rope along the angle iron also stabilizes the antenna from yawing from side-to-side. Note in Fig 36 that the angle iron is mounted just off-center from where the boom-to-mast plate will be attached so that it clears the mast as the antenna nears the top of the tower. **Fig 37** diagrams how the tram and hoisting line are rigged to the mast.

The tower person directs the activity of the ground crew below and guides the antenna to the mast. Once the end of the pull rope reaches the mast, the tower man ties the boom temporarily to the mast so that he can undo the pull rope from the tram-fixture angle iron and retie it around the boom. Then the antenna can be raised to the point where it can be mounted to the mast.

This technique has been employed to raise Yagis with booms as long as 42 feet at the N6RO contest station on towers as high as 130 feet. As with the track, the tram system requires a good deal of open real estate. While it sounds complicated to set up, you can raise some rather large antennas in less than an hour, once you get the hang of the operation.

THE PVRC MOUNT

The methods described above for hoisting antennas are sometimes not satisfactory for really large, heavy arrays. The best way to handle large Yagis is to assemble them on top of the tower. One way to do this easily is by using the *PVRC Mount*. Many members of the Potomac Valley Radio Club have successfully used this method to install large antennas. Simple and ingenious, the idea involves offsetting the boom from the mast to permit the boom to tilt 360° and rotate axially 360°. This permits the entire length of the boom to be brought alongside the tower, allowing the elements to be attached one by one. (It also allows any part of the antenna to be brought alongside the tower for antenna maintenance.)

See **Figs 38** through **42**. The mount itself consists of a short length of pipe of the same diameter as the rotating mast (or greater), a steel plate, eight U bolts and four pinning bolts. The steel plate is the larger, horizontal one shown in Fig 38. Four U bolts attach the plate to the rotating mast, and four attach the horizontal pipe to the plate. The horizontal pipe provides the offset between the antenna boom and the tower. The antenna boom-to-mast plate is mounted at the outer end of the short pipe. Four bolts are used to ensure that the antenna ends up parallel to the ground, two pinning each plate to the short pipe. When the mast plate pinning bolts are removed and the

Fig 37—At A, bird's-eye view of tram system used to bring large Yagi antennas from the ground to the top of the tower. At B, side view of rigging used for tramline and hoisting line, along with the sling and tram fixture used to hold the Yagi on the tramline.

four U bolts loosened, the short pipe and boom plate can be rotated through 360°, allowing either half of the boom to come alongside the tower.

First assemble the antenna on the ground. Carefully mark all critical dimensions, and then remove the antenna elements from the boom. Once the rotator and mast have been installed on the tower, a gin pole is used to bring the mast plate and short pipe to the top of the tower. There, the top crew unpins the horizontal pipe and tilts the antenna boom plate to place it in the vertical plane. The boom is attached to the boom plate at the final balance point of the assembled antenna. It is important that the boom be rotated axially so the bottom side of the boom is closest to the tower.

This will allow the boom to be tilted without the elements striking the tower.

During installation it may be necessary to loosen one guy wire temporarily to allow for tilting of the boom. As a safety precaution, a temporary guy should be attached to the same leg of the tower just low enough so the assembled antenna will clear it.

The elements are assembled on the boom, starting with those closest to the center of the boom, working out alternately to the farthest director and reflector. This procedure must be followed. If all the elements are put first on one half of the boom, it will be dangerous (if not impossible) to put on the remaining elements. By start-

Fig 38—The PVRC mount, boom plate, mast and rotator ready to go. The mast and rotator are installed on the tower first.

Fig 40—Working at the 70-foot level. A gin pole makes pulling up and mounting the boom to the boom plate a safe and easy procedure.

Fig 39—Close-up of the PVRC mount. The long pipe (horizontal in this photo) is the rotating mast. The U bolts in the vertical plate at the left are ready to accept the antenna boom. The heads of two locking pins (bolts) are visible at the midline of the boom plate. The other two pins help secure the horizontal pipe to the large steel mast plate. (The head of the bolt nearest the camera blends in with the right hand leg of the U bolt behind it.)

ing at the middle and working outward, the balance point of the partly assembled antenna will never be so far removed from the tower that tilting of the boom becomes impossible.

When the last element is attached, the boom is brought parallel to the ground, the horizontal pipe is pinned to the mast plate, and the mast plate U bolts tightened. At this point, all the antenna elements will be positioned vertically. Next, loosen the U bolts that hold the boom and rotate the boom axially 90°, bringing the elements parallel to the ground. Tighten the boom bolts and double check all the hardware.

Many long-boom Yagis employ a truss to prevent boom sag. With the PVRC mount, the truss must be attached to a pipe that is independent of the rotating mast. A short length of pipe is attached to the boom as close as possible to the balance point. The truss then moves with the boom whenever the boom is tilted or twisted.

A precaution: Unless you have a really strong rotator, you should consider using this mount mainly for assembling the antenna on the tower. The offset between the boom and the mast with this assembly can generate high torque loads on the rotator. Mounting the boom as close as possible to the mast will minimize the torque when the antenna is pointed into the wind.

Fig 41—Mounting the last element prior to positioning the boom in a horizontal plane.

Fig 42—The U bolts securing the short pipe to the mast plate are loosened and the boom is turned to a horizontal position. This puts the elements in a vertical plane. Then the pipe U bolts are tightened and pinning bolts secured. The boom U bolts are then loosened and the boom turned axially 90°.

THE TOWER ALTERNATIVE

A cost saving alternative to the ground-mounted tower is the roof-mounted tripod. Units suitable for small HF or VHF antennas are commercially available. Perhaps the biggest problem with a tripod is determining how to fasten it securely to the roof.

One method of mounting a tripod on a roof is to nail 2 × 6 boards to the undersides of the rafters. Bolts can be extended from the leg mounts through the roof and the 2 × 6s. To avoid exerting too much pressure on the area of the roof between rafters, place another set of 2 × 6s on top of the roof (a mirror image of the ones in the attic). Installation details are shown in **Figs 43** through **46**.

The 2 × 6s are cut 4 inches longer than the outside distance between two rafters. Bolts are cut from a length of ¼-inch-threaded rod. Nails are used to hold the boards in place during installation, and roofing tar is used to seal the area to prevent leaks.

Find a location on the roof that will allow the antenna to turn without obstruction from such things as trees, TV antennas and chimneys. Determine the rafter locations. (Chimneys and vent pipes make good reference points.) Now the tower is set in place atop three 2 × 6s. A plumb line run from the top center of the tower can be used to center it on the peak of the roof. Holes for the mounting bolts can now be drilled through the roof.

Before proceeding, the bottom of the 2 × 6s and the area of the roof under them should be given a coat of roofing tar. Leave about ⅛ inch of clear area around the holes to ensure easy passage of the bolts. Put the tower back in place and insert the bolts and tighten them. Apply tar to the bottom of the legs and the wooden supports, including the bolts. For added security the tripod can be guyed. Guys should be anchored to the frame of the house.

If a rotator is to be mounted above the tripod, pressure will be applied to the bearings. Wind load on the antenna will be translated into a "pinching" of one side of the bearings. Make sure that the rotator is capable of handling this additional stress.

ROTATOR SYSTEMS

There are not that many choices when it comes to antenna rotators for the amateur antenna system. Making the correct decision as to how much capacity the rotator must have is very important to ensure trouble-free operation. Manufacturers generally provide an antenna surface-area rating to help the purchase choose a suitable rotator. The maximum antenna area is linked to the rotator's torque capability.

Some rotator manufacturers provide additional information to help you select the right size of rotator for the antennas you plan to use. Hy-Gain provides an *Effective Moment* value. Yaesu calls theirs a *K-Factor*. Both of these ratings are torque values in foot-pounds. You can compute the effective moment of your antenna by multiplying the antenna turning radius by its weight. So long

Fig 44—This cutaway view illustrates how the tripod tower is secured to the roof rafters. The leg to be secured to the crosspiece is placed on the outside of the roof. Another cross member is fastened to the underside of the rafters. Bolts, inserted through the roof and the two cross pieces, hold the inner cross member in place because of pressure applied. The inner crosspiece can be nailed to the rafter for added strength.

Fig 43—This tripod tower supports a rotary beam antenna. In addition to saving yard space, a roof-mounted tower can be more economical than a ground-mounted tower. A ground lead fastened to the lower part of the frame is for lightning protection. The rotator control cable and the coaxial line are dressed along two of the legs. (*Photo courtesy of Jane Wolfert.*)

Fig 45—Three lengths of 2 × 6 wood mounted on the outside of the roof and reinforced under the roof by three identical lengths provide a durable means for anchoring the tripod. A thick coat of roofing tar guards against weathering and leaks.

Fig 46—The strengthened anchoring for the tripod. Bolts are placed through two 2 × 6s on the underside of the roof and through the 2 × 6 on the top of the roof, as shown in Fig 43.

as the effective moment rating of the rotator is greater than or equal to the antenna value, the rotator can be expected to provide a useful service life.

There are basically four grades of rotators available to the amateur. The lightest-duty rotator is the type typically used to turn TV antennas. Without much difficulty, these rotators will handle a small 3-element tribander array (14, 21 and 28 MHz) or a single 21- or 28-MHz monoband three-element antenna. The important consideration with a TV rotator is that it lacks braking or holding capability. High winds turn the rotator motor via the gear train in a reverse fashion. Broken gears sometimes result.

The next grade up from the TV class of rotator usually includes a braking arrangement, whereby the antenna is held in place when power is not applied to the rotator. Generally speaking, the brake prevents gear damage on windy days. If adequate precautions are taken, this group of rotators is capable of holding and turning stacked monoband arrays, or up to a five-element 14-MHz system. The next step up in rotator strength is more expensive. This class of rotator will turn just about anything the most demanding amateur might want to install.

A description of antenna rotators would not be complete without the mention of the *prop pitch* class. The prop pitch rotator system consists of a surplus aircraft propeller blade pitch motor coupled to an indicator system and a power supply. There are mechanical problems of installation, however, resulting mostly from the size and weight of these motors. It has been said that a prop pitch rotator system, properly installed, is capable of turning a house. Perhaps in the same class as the prop pitch motor (but with somewhat less capability) is the electric motor of the type used for opening garage doors. These have been used successfully in turning large arrays.

Proper installation of the antenna rotator can provide many years of trouble-free service; sloppy installation can cause problems such as a burned out motor, slippage, binding and casting breakage. Most rotators are capable of accepting mast sizes of different diameters, and suitable precautions must be taken to shim an undersized mast to ensure dead-center rotation. It is very desirable to mount the rotator inside and as far below the top of the tower as possible. The mast absorbs the torsion developed by the antenna during high winds, as well as during starting and stopping.

Some amateurs have used a long mast from the top to the base of the tower. Rotator installation and service can be accomplished at ground level. A mast length of 10 feet or more between the rotator and the antenna will add greatly to the longevity of the entire system by allowing the mast to act as a torsion shock absorber. Another benefit of mounting the rotator 10 feet or more below the antenna is that any misalignment among the rotator, mast and the top of the tower is less significant. A tube at the top of the tower (a sleeve bearing) through

Fig 47—Rotator loop for UHF Yagi array. The feed coax is bundled with a control cable for the polarization relay. The coax/control-cable loop is taped to the rotating mast and to the top of the tower with vinyl electric tape to allow the array to be rotated.

which the mast protrudes almost completely eliminates any lateral forces on the rotator casing. All the rotator must do is support the downward weight of the antenna system and turn the array.

While the normal weight of the antenna and the mast is usually not more than a couple of hundred pounds, even with a large system, one can ease this strain on the rotator by installing a thrust bearing at the top of the tower. The bearing is then the component that holds the weight of the antenna system, and the rotator need perform only the rotating task.

Don't forget to provide a loop of coax to allow your beam to rotate properly. Make sure you position the rotator loop so that it doesn't snag on anything. **Fig 47** shows a rotator loop for an elliptically polarized UHF Yagi array. Note that the coax loop is taped to the rotating mast above the top of the tower and to the tower itself.

Indicator Alignment

A problem often encountered in amateur installations is that of misalignment between the direction indicator in the rotator control box and the heading of the antenna. With a light duty rotator, this happens frequently when the wind blows the antenna to a different heading. With no brake, the force of the wind can move the gear train and motor of the rotator, while the indicator remains fixed. Such rotator systems have a mechanical stop to prevent continuous rotation during operation, and provision is usually included to realign the indicator against the mechanical stop from inside the shack. During installation, the antenna must be oriented correctly for the mechanical stop position, which is usually north.

In larger rotator systems with an adequate brake, indicator misalignment is caused by mechanical slippage in the antenna boom-to-mast hardware. Many texts suggest that the boom be pinned to the mast with a heavy-duty bolt and the rotator be similarly pinned to the mast. There is a trade-off here. If there is sufficient wind to cause slippage in the couplings without pins, with pins the wind could break a rotator casting. The slippage will act as a clutch release, which may prevent serious damage to the rotator. On the other hand, the amateur might not like to climb the tower and realign the system after each heavy windstorm.

BIBLIOGRAPHY

Source material and more extended discussions of the topics covered in this chapter can be found in the references listed below and in the texts listed at the end of Chapter 2.

L. H. Abraham, "Guys for Guys Who Have To Guy," *QST*, Jun 1955.

K. Baker, "A Ladder Mast," *QST*, Jun 1981, p 24.

W. R. Gary, "Toward Safer Antenna Installations," *QST*, Jan 1980, p 56.

S. F. Hoerner, "Fluid Dynamic Drag," published by author, Bricktown, New Jersey, 1965, pp 1-10.

C. L. Hutchinson, "A Tree-Mounted 30-Meter Ground-Plane Antenna," *QST*, Sep 1984, pp 16-18.

C. L. Hutchinson, R. D. Straw, *Simple and Fun Antennas for Hams* (Newington: ARRL, 2002).

M. P. Keown and L. L. Lamb, "A Simple Technique for Tower-Section Separation," *QST*, Sep 1979, pp 37-38.

P. O'Dell, "The Ups and Downs of Towers," *QST*, Jul 1981, p 35.

S. Phillabaum, "Installation Techniques for Medium and Large Yagis," *QST*, Jun 1979, p 23.

C. J. Richards, "Mechanical Engineering in Radar and Communications" (London: Van Nostrand Reinhold Co., 1969) pp 162-165.

D. Weber "Determination of Yagi Wind Loads Using the Cross-Flow Principle," *Communications Quarterly*, Spring 1993.

A. B. White, "A Delayed Brake Release for the Ham-II," *QST*, Aug 1977, p 14.

B. White, E. White and J. White, "Assembling Big Antennas on Fixed Towers," *QST*, Mar 1982, pp 28-29

L. Wolfert, "The Tower Alternative," *QST*, Nov 1980, p 36.

W. C. Young., "Roark's Formulas for Stress & Strain" (New York: McGraw-Hill Co., 1989), pp 67, 96

Structural Standards for Steel Antenna Towers and Antenna Supporting Structures, TIA/EIA Standard TIA/EIA-222-F, Electronic Industries Association, Mar 1996. May be purchased from Telecommunications Industry Association (TIA), Standards and Technology Department, 2500 Wilson Boulevard, Arlington VA, 22201 or Global Engineering Documents, 15 Inverness Way East, Englewood, CO, 80112-5704, 1-800-854-7179.

Radio Wave Propagation

Because radio communication is carried on by means of electromagnetic waves traveling through the Earth's atmosphere, it is important to understand the nature of these waves and their behavior in the propagation medium. Most antennas will radiate the power applied to them efficiently, but no antenna can do all things equally well, under all circumstances. Whether you design and build your own antennas, or buy them and have them put up by a professional,

you'll need propagation know-how for best results, both during the planning stages and while operating your station.

For station planning, this chapter contains detailed new information on elevation angles from transmitting locations throughout the world to important areas throughout the world. With this information in hand, you can design your own antenna installation for optimum capabilities possible within your budget. See the CD-ROM in back of this book.

The Nature of Radio Waves

You probably have some familiarity with the concept of electric and magnetic fields. A radio wave is a combination of both, with the energy divided equally between them. If the wave could originate at a point source in free space, it would spread out in an ever-growing sphere, with the source at the center. No antenna can be designed to do this, but the theoretical *isotropic antenna* is useful in explaining and measuring the performance of practical antennas we *can* build. It is, in fact, the basis for any discussion or evaluation of antenna performance.

Our theoretical spheres of radiated energy would expand very rapidly at the same speed as the propagation of light, approximately 186,000 miles or 300,000,000 meters per second. These values are close enough for practical purposes, and are used elsewhere in this book. If one wishes to be more precise, light propagates in a vacuum at the speed of 299.7925 meters per microsecond, and slightly slower in air.

The path of a *ray* traced from its source to any point on a spherical surface is considered to be a straight line—a radius of the sphere. An observer on the surface of the sphere would think of it as being flat, just as the Earth seems flat to us. A radio wave far enough from its source to appear flat is called a *plane wave*. From here on, we will be discussing primarily plane waves.

It helps to understand the radiation of electromagnetic energy if we visualize a plane wave as being made up of electric and magnetic forces, as shown in **Fig 1**. The nature of wave propagation is such that the electric and magnetic lines of force are always perpendicular. The plane containing the sets of crossed lines represents the wave front. The direction of travel is always perpendicular to the wave front; *forward* or *backward* is determined by the relative directions of the electric and magnetic forces.

The speed of travel of a wave through anything but a vacuum is always less than 300,000,000 meters per second. How much less depends on the medium. If it is air, the reduction in propagation speed can be ignored in most discussions of propagation at frequencies below 30 MHz. In the VHF range and higher, temperature and moisture content of the medium have increasing effects on the communication range, as will be discussed later. In solid insulating materials the speed is considerably less. In distilled water (a good insulator) the speed is $1/9$ that in free space. In good conductors the speed is so low that the opposing fields set up by the wave front occupy practically the same space as the wave itself, and thus cancel it out. This is the reason for "skin effect" in conductors at high frequencies, making metal enclosures good shields for electrical circuits working at radio frequencies.

Fig 1—Representation of the magnetic and electric fields of a vertically polarized plane wave traveling along the ground. The arrows indicate instantaneous directions of the fields for a wave traveling perpendicularly out of the page toward the reader. Reversal of the direction of one set of lines reverses the direction of travel. There is no change in direction when both sets are reversed. Such a dual reversal occurs in fact once each half cycle.

Phase and Wavelength

Because the velocity of wave propagation is so great, we tend to ignore it. Only $^{1}/_{7}$ of a second is needed for a radio wave to travel around the world—but in working with antennas the *time* factor is extremely important. The wave concept evolved because an alternating current flowing in a wire (antenna) sets up moving electric and magnetic fields. We can hardly discuss antenna theory or performance at all without involving travel time, consciously or otherwise.

Waves used in radio communication may have frequencies from about 10,000 to several billion Hz. Suppose the frequency is 30 MHz. One cycle, or period, is completed in 1/30,000,000 second. The wave is traveling at 300,000,000 meters per second, so it will move only 10 meters during the time that the current is going through one complete period of alternation. The electromagnetic field 10 meters away from the antenna is caused by the current that was flowing one period earlier in time. The field 20 meters away is caused by the current that was flowing two periods earlier, and so on.

If each period of the current is simply a repetition of the one before it, the currents at corresponding instants in each period will be identical. The fields caused by those currents will also be identical. As the fields move outward from the antenna they become more thinly spread over larger and larger

surfaces. Their amplitudes decrease with distance from the antenna but they do not lose their identity with respect to the instant of the period at which they were generated. They are, and they remain, *in phase*. In the example above, at intervals of 10 meters measured outward from the antenna, the phase of the waves at any given instant is identical.

From this information we can define both *wave front* and *wavelength*. Consider the wave front as an imaginary surface. On every part of this surface, the wave is in the same phase. The wavelength is the distance between two wave fronts having the same phase at any given instant. This distance must be measured perpendicular to the wave fronts along the line that represents the direction of travel. The abbreviation for wavelength is the Greek letter lambda, λ, which is used throughout this book.

The wavelength will be in the same length units as the velocity when the frequency is expressed in the same time units as the velocity. For waves traveling in free space (and near enough for waves traveling through air) the wavelength is

$$\lambda_{meters} = \frac{299.7925}{F(MHz)} \qquad \text{(Eq 1)}$$

There will be few pages in this book where phase, wavelength and frequency do not come into the discussion. It is essential to have a clear understanding of their meaning in order to understand the design, installation, adjustment or use of antennas, matching systems or transmission lines in detail. In essence, *phase* means *time*. When something goes through periodic variations, as an alternating current does, corresponding instants in succeeding periods are *in phase*.

The points A, B and C in **Fig 2** are all in phase. They are corresponding instants in the current flow, at 1-λ intervals. This is a conventional view of a sine-wave alternating current, with time progressing to the right. It also represents a *snapshot* of the intensity of the traveling fields, if distance is substituted for time in the horizontal axis. The distance between A and B or between B and C is one wavelength. The field-intensity distribution follows the sine curve, in both amplitude and polarity, corresponding exactly to the time variations in the current that produced the fields. Remember that this is an *instantaneous* picture—the wave moves outward, much as a wave created by a rock thrown into water does.

Polarization

A wave like that in Fig 1 is said to be *polarized* in the direction of the electric lines of force. The polarization here is vertical, because the electric lines are perpendicular to the surface of the Earth. It is one of the laws of electromagnetics that electric lines touching the surface of a perfect conductor must do so perpendicularly, or else they would have to generate infinite currents in the conductor, an obvious impossibility. Most ground is a rather good conductor at frequencies below about 10 MHz, so waves at these

Fig 2—The instantaneous amplitude of both fields (electric and magnetic) varies sinusoidally with time as shown in this graph. Since the fields travel at constant velocity, the graph also represents the instantaneous distribution of field intensity along the wave path. The distance between two points of equal phase such as A-B and B-C is the length of the wave.

frequencies, traveling close to good ground, are mainly vertically polarized. Over partially conducting ground there may be a forward tilt to the wave front; the tilt in the electric lines of force increases as the energy loss in the ground becomes greater.

Waves traveling in contact with the surface of the Earth, called *surface waves*, are of little practical use in amateur communication. This is because as the frequency is raised, the distance over which they will travel without excessive energy loss becomes smaller and smaller. The surface wave is most useful at low frequencies and through the standard AM broadcast band. The surface wave will be covered later. At high frequencies a wave reaching a receiving antenna has had little contact with the ground, and its polarization is not necessarily vertical.

If the electric lines of force are horizontal, the wave is said to be *horizontally polarized*. Horizontally and vertically polarized waves may be classified generally under *linear polarization*. Linear polarization can be anything between horizontal and vertical. In free space, "horizontal" and "vertical" have no meaning, since the reference of the seemingly horizontal surface of the Earth has been lost.

In many cases the polarization of waves is not fixed, but rotates continually, somewhat at random. When this occurs the wave is said to be *elliptically polarized*. A gradual shift in polarization in a medium is known as *Faraday rotation*. For space communication, circular polarization is commonly used to overcome the effects of Faraday rotation. A circularly polarized wave rotates its polarization through 360° as it travels a distance of one wavelength in the propagation medium. The direction of rotation as viewed from the transmitting antenna defines the direction of circularity—right-hand (clockwise) or left-hand (counterclockwise). Linear and circular polarization may be considered as special cases of elliptical polarization.

Field Intensity

The energy from a propagated wave decreases with distance from the source. This decrease in strength is caused by the spreading of the wave energy over ever-larger spheres as the distance from the source increases.

A measurement of the strength of the wave at a distance from the transmitting antenna is its *field intensity*, which is synonymous with *field strength*. The strength of a wave is measured as the voltage between two points lying on an electric line of force in the plane of the wave front. The standard of measure for field intensity is the voltage developed in a wire that is 1 meter long, expressed as volts per meter. (If the wire were 2 meters long, the voltage developed would be divided by two to determine the field strength in volts per meter.)

The voltage in a wave is usually low, so the measurement is made in millivolts or microvolts per meter. The voltage goes through time variations like those of the current that caused the wave. It is measured like any other ac voltage—in terms of the effective value or, sometimes, the peak value. It is fortunate that in amateur work it is not necessary to measure actual field strength, as the equipment required is elaborate. We need to know only if an adjustment has been beneficial, so relative measurements are satisfactory. These can be made easily with home-built equipment.

Wave Attenuation

In free space, the field intensity of the wave varies inversely with the distance from the source, once you are in the radiating far field of the antenna. If the field strength at 1 mile from the source is 100 millivolts per meter, it will be 50 millivolts per meter at 2 miles, and so on. The relationship between field intensity and power density is similar to that for voltage and power in ordinary circuits. They are related by the impedance of free space, which is approximately 377 Ω. A field intensity of 1 volt per meter is therefore equivalent to a power density of

$$P = \frac{E^2}{Z} = \frac{1\,(\text{volt/m})^2}{377\,\Omega} = 2.65\,\text{mW/m}^2 \qquad \text{(Eq 2)}$$

Because of the relationship between voltage and power, the power density therefore varies with the square root of the field intensity, or inversely with the *square* of the distance. If the power density at 1 mile is 4 mW per square meter, then at a distance of 2 miles it will be 1 mW per square meter.

It is important to remember this so-called *spreading loss* when antenna performance is being considered. Gain can come only from narrowing the radiation pattern of an antenna, which concentrates the radiated energy in the desired direction. There is no "antenna magic" by which the total energy radiated can be increased.

In practice, attenuation of the wave energy may be much greater than the inverse-distance law would indicate. The wave does not travel in a vacuum, and the receiving antenna seldom is situated so there is a clear line of sight.

The Earth is spherical and the waves do not penetrate its surface appreciably, so communication beyond visual distances must be by some means that will bend the waves around the curvature of the Earth. These means involve additional energy losses that increase the path attenuation with distance, above that for the theoretical spreading loss in a vacuum.

Bending of Radio Waves

Radio waves and light waves are both propagated as electromagnetic energy. Their major difference is in wavelength, since radio-reflecting surfaces are usually much smaller in terms of wavelength than those for light. In material of a given electrical conductivity, long waves penetrate deeper than short ones, and so require a thicker mass for good reflection. Thin metal however is a good reflector of even long-wavelength radio waves. With poorer conductors, such as the Earth's crust, long waves may penetrate quite a few feet below the surface.

Reflection occurs at any boundary between materials of differing dielectric constant. Familiar examples with light are reflections from water surfaces and window panes. Both water and glass are transparent for light, but their dielectric constants are very different from that of air. Light waves, being very short, seem to bounce off both surfaces. Radio waves, being much longer, are practically unaffected by glass, but their behavior upon encountering water may vary, depending on the purity of that medium. Distilled water is a good insulator; salt water is a relatively good conductor.

Depending on their wavelength (and thus their frequency), radio waves may be reflected by buildings, trees, vehicles, the ground, water, ionized layers in the upper atmosphere, or at boundaries between air masses having different temperatures and moisture content. Ionospheric and atmospheric conditions are important in practically all communication beyond purely local ranges.

Refraction is the bending of a ray as it passes from one medium to another at an angle. The appearance of bending of a straight stick, where it enters water at an angle, is an example of light refraction known to us all. The degree of bending of radio waves at boundaries between air masses increases with the radio frequency. There is slight atmospheric bending in our HF bands. It becomes noticeable at 28 MHz, more so at 50 MHz, and it is much more of a factor in the higher VHF range and in UHF and microwave propagation.

Diffraction of light over a solid wall prevents total darkness on the far side from the light source. This is caused largely by the spreading of waves around the top of the wall, due to the interference of one part of the beam with another. The dielectric constant of the surface of the obstruction may affect what happens to our radio waves when they encounter terrestrial obstructions—but the radio *shadow area* is never totally dark. See Chapter 3, The Effects of Ground, for more information on diffraction.

The three terms, reflection, refraction and diffraction, were in use long before the radio age began. Radio propagation is nearly always a mix of these phenomena, and it may not be easy to identify or separate them while they are happening when we are on the air. This book tends to rely on the words *bending* and *scattering* in its discussions, with appropriate modifiers as needed. The important thing to remember is that any alteration of the path taken by energy as it is radiated from an antenna is almost certain to affect on-the-air results—which is why this chapter on propagation is included in an antenna book.

GROUND WAVES

As we have already seen, radio waves are affected in many ways by the media through which they travel. This has led to some confusion of terms in earlier literature concerning wave propagation. Waves travel close to the ground in several ways, some of which involve relatively little contact with the ground itself. The term *ground wave* has had several meanings in antenna literature, but it has come to be applied to any wave that stays close to the Earth, reaching the receiving point without leaving the Earth's lower atmosphere. This distinguishes the ground wave from a *sky wave*, which utilizes the ionosphere for propagation between the transmitting and receiving antennas.

The ground wave could be traveling in actual contact with the ground, as in Fig 1, where it is called the *surface wave*. Or it could travel directly between the transmitting and receiving antennas, when they are high enough so they can "see" each other—this is commonly called the *direct wave*. The ground wave also travels between the transmitting and receiving antennas by reflections or diffractions off intervening terrain between them. The ground-influenced wave may interact with the direct wave to create a vector-summed resultant at the receiver antenna.

In the generic term ground wave, we also will include ones that are made to follow the Earth's curvature by bending in the Earth's lower atmosphere, or *troposphere*, usually no more than a few miles above the ground. Often called *tropospheric bending*, this propagation mode is a major factor in amateur communications above 50 MHz.

THE SURFACE WAVE

The surface wave travels in contact with the Earth's surface. It can provide coverage up to about 100 miles in the standard AM broadcast band during the daytime, but attenuation is high. As can be seen from **Fig 3**, the attenuation increases with frequency. The surface wave is of little value in amateur communication, except possibly at 1.8 MHz. Vertically polarized antennas must be used, which tends to limit amateur surface-wave communication to where large vertical systems can be erected.

THE SPACE WAVE

Propagation between two antennas situated within line of sight of each other is shown in **Fig 4**. Energy traveling directly between the antennas is attenuated to about the same degree as in free space. Unless the antennas are very high or

Fig 3—Typical HF ground-wave range as a function of frequency.

Fig 4—The ray traveling directly from the transmitting antenna to the receiving antenna combines with a ray reflected from the ground to form the space wave. For a horizontally polarized signal a reflection as shown here reverses the phase of the ground-reflected ray.

quite close together, an appreciable portion of the energy is reflected from the ground. This reflected wave combines with direct radiation to affect the actual signal received.

In most communication between two stations on the ground, the angle at which the wave strikes the ground will be small. For a horizontally polarized signal, such a reflection reverses the phase of the wave. If the distances traveled by both parts of the wave were the same, the two parts would arrive out of phase, and would therefore cancel each other. The ground-reflected ray in Fig 4 must travel a little further, so the phase difference between the two depends on the lengths of the paths, measured in wavelengths. The wavelength in use is important in determining the useful signal strength in this type of communication.

If the difference in path length is 3 meters, the phase difference with 160-meter waves would be only 360° × 3/160 = 6.8°. This is a negligible difference from the 180° shift caused by the reflection, so the effective signal strength over the path would still be very small because of cancellation of the two waves. But with 6-meter radio waves the phase length would be 360° × 3/6 = 180°. With the addi-

tional 180° shift on reflection, the two rays would add. Thus, the space wave is a negligible factor at low frequencies, but it can be increasingly useful as the frequency is raised. It is a dominant factor in local amateur communication at 50 MHz and higher.

Interaction between the direct and reflected waves is the principle cause of *mobile flutter* observed in local VHF communication between fixed and mobile stations. The flutter effect decreases once the stations are separated enough so that the reflected ray becomes inconsequential. The reflected energy can also confuse the results of field-strength measurements during tests on VHF antennas.

As with most propagation explanations, the space-wave picture presented here is simplified, and practical considerations dictate modifications. There is always some energy loss when the wave is reflected from the ground. Further, the phase of the ground-reflected wave is not shifted exactly 180°, so the waves never cancel completely. At UHF, ground-reflection losses can be greatly reduced or eliminated by using highly directive antennas. By confining the antenna pattern to something approaching a flashlight beam, nearly all the energy is in the direct wave. The resulting energy loss is low enough that microwave relays, for example, can operate with moderate power levels over hundreds or even thousands of miles. Thus we see that, while the space wave is inconsequential below about 20 MHz, it can be a prime asset in the VHF realm and higher.

VHF/UHF PROPAGATION BEYOND LINE OF SIGHT

From Fig 4 it appears that use of the space wave depends on direct line of sight between the antennas of the communicating stations. This is not literally true, although that belief was common in the early days of amateur communication on frequencies above 30 MHz. When equipment became available that operated more efficiently and after antenna techniques were improved, it soon became clear that VHF waves were actually being bent or scattered in several ways, permitting reliable communication beyond visual distances between the two stations. This was found true even with low power and simple antennas. The average communication range can be approximated by assuming the waves travel in straight lines, but with the Earth's radius increased by one-third. The distance to the *radio horizon* is then given as

$$D_{miles} = 1.415 \sqrt{H_{feet}} \qquad \text{(Eq 3)}$$

or

$$D_{km} = 4.124 \sqrt{H_{meters}} \qquad \text{(Eq 4)}$$

where H is the height of the transmitting antenna, as shown in **Fig 5**. The formula assumes that the Earth is smooth out to the horizon, so any obstructions along the path must be taken into consideration. For an elevated receiving antenna the communication distance is equal to D + D1, that is, the sum of the distances to the horizon of both

Fig 5—The distance D to the horizon from an antenna of height H is given by equations in the text. The maximum line-of-sight distance between two elevated antennas is equal to the sum of their distances to the horizon as indicated here.

antennas. Radio horizon distances are given in graphic form in **Fig 6**. Two stations on a flat plain, one with its antenna 60 feet above ground and the other 40 feet, could be up to about 20 miles apart for strong-signal line-of-sight communication (11 + 9 mi). The terrain is almost never completely flat, however, and variations along the way may add to or subtract from the distance for reliable communication. Remember that energy is absorbed, reflected or scattered in many ways in nearly all communication situations. The formula or the chart will be a good guide for estimating the potential radius of coverage for a VHF FM repeater, assuming the users are mobile or portable with simple, omnidirectional antennas. Coverage with optimum home-station equipment, high-gain directional arrays, and SSB or CW is quite a different matter. A much more detailed method for estimating coverage on frequencies above 50 MHz is given later in this chapter.

For maximum use of the ordinary space wave it is important to have the antenna as high as possible above nearby buildings, trees, wires and surrounding terrain. A hill that rises above the rest of the countryside is a good location for an amateur station of any kind, and particularly so for extensive coverage on the frequencies above 50 MHz. The highest point on such an eminence is not necessarily the best location for the antenna. In the example shown in **Fig 7**, the hilltop would be a good site in all directions. But if maximum performance to the right is the objective, a point just below the crest might do better. This would involve a trade-off with reduced coverage in the opposite direction. Conversely, an antenna situated on the left side, lower down the hill, might do well to the left, but almost certainly would be inferior in performance to the right.

Selection of a home site for its radio potential is a complex business, at best. A VHF enthusiast dreams of the highest hill. The DX-minded HF ham may be more attracted by a dry spot near a salt marsh. A wide saltwater horizon, especially from a high cliff, just smells of DX. In shopping for ham radio real estate, a mobile or portable rig for the frequencies you're most interested in can provide useful clues.

ANTENNA POLARIZATION

If effective communication over long distances were the only consideration, we might be concerned mainly with

Fig 6—Distance to the horizon from an antenna of given height. The solid curve includes the effect of atmospheric retraction. The optical line-of-sight distance is given by the broken curve.

Fig 7—Propagation conditions are generally best when the antenna is located slightly below the top of a hill on the side facing the distant station. Communication is poor when there is a sharp rise immediately in front of the antenna in the direction of communication.

radiation of energy at the lowest possible angle above the horizon. However, being engaged in a residential avocation often imposes practical restrictions on our antenna projects. As an example, our 1.8 and 3.5-MHz bands are used primarily for short-distance communication because they serve that purpose with antennas that are not difficult or expensive to put up. Out to a few hundred miles, simple wire

antennas for these bands do well, even though their radiation is mostly at high angles above the horizon. Vertical systems might be better for long-distance use, but they require extensive ground systems for good performance.

Horizontal antennas that radiate well at low angles are most easily erected for 7 MHz and higher frequencies—horizontal wires and arrays are almost standard practice for work on 7 through 29.7 MHz. Vertical antennas, such as a single omnidirectional antenna of multiband design, are also used in this frequency range. An antenna of this type may be a good solution to the space problem for a city dweller on a small lot, or even for the resident of an apartment building.

High-gain antennas are almost always used at 50 MHz and higher frequencies, and most of them are horizontal. The principal exception is mobile communication with FM through repeaters, discussed in Chapter 17, Repeater Antenna Systems. The height question is answered easily for VHF enthusiasts—the higher the better.

The theoretical and practical effects of height above ground at HF are treated in detail in Chapter 3, The Effects of Ground. Note that it is the height in *wavelengths* that is important—a good reason to think in the metric system, rather than in feet and inches.

In working locally on any amateur frequency band, best results will be obtained with the same polarization at both stations, except on rare occasions when polarization shift is caused by terrain obstructions or reflections from buildings. Where such a shift is observed, mostly above 100 MHz or so, horizontal polarization tends to work better than vertical. This condition is found primarily on short paths, so it is not too important. Polarization shift may occur on long paths where tropospheric bending is a factor, but here the effect tends to be random. Long-distance communication by way of the ionosphere produces random polarization effects, so polarization matching is of little or no importance. This is fortunate for the HF mobile enthusiast, who will find that even his short, inductively loaded whips work very well at all distances other than local.

Because it responds to all plane polarizations equally, circular polarization may pay off on circuits where the arriving polarization is random, but it exacts a 3-dB penalty when used with a single-plane polarization of any kind. Circular systems find greatest use in work with orbiting satellites. It should be remembered that "horizontal" and "vertical" are meaningless terms in space, where the plane-Earth reference is lost.

Polarization Factors Above 50 MHz

In most VHF communication over short distances, the polarization of the space wave tends to remain constant. Polarization discrimination is high, usually in excess of 20 dB, so the same polarization should be used at both ends of the circuit. Horizontal, vertical and circular polarization all have certain advantages above 50 MHz, so there has never been complete standardization on any one of them.

Horizontal systems are popular, in part because they tend to reject man-made noise, much of which is vertically polarized. There is some evidence that vertical polarization shifts to horizontal in hilly terrain, more readily than horizontal shifts to vertical. With large arrays, horizontal systems may be easier to erect, and they tend to give higher signal strengths over irregular terrain, if any difference is observed.

Practically all work with VHF mobiles is now handled with vertical systems. For use in a VHF repeater system, the vertical antenna can be designed to have gain without losing the desired omnidirectional quality. In the mobile station a small vertical whip has obvious aesthetic advantages. Often a telescoping whip used for broadcast reception can be pressed into service for the 144-MHz FM rig. A car-top mount is preferable, but the broadcast whip is a practical compromise. Tests with at least one experimental repeater have shown that horizontal polarization can give a slightly larger service area, but mechanical advantages of vertical systems have made them the almost unanimous choice in VHF FM communication. Except for the repeater field, horizontal is the standard VHF system almost everywhere.

In communication over the Earth-Moon-Earth (EME) route the polarization picture is blurred, as might be expected with such a diverse medium. If the moon were a flat target, we could expect a 180° phase shift from the moon reflection process. But it is not flat. This plus the moon's *libration* (its slow oscillation, as viewed from the Earth), and the fact that waves must travel both ways through the Earth's entire atmosphere and magnetic field, provide other variables that confuse the phase and polarization issue. Building a huge array that will track the moon, and give gains in excess of 20 dB, is enough of a task that most EME enthusiasts tend to take their chances with phase and polarization problems. Where rotation of the element plane has been tried it has helped to stabilize signal levels, but it is not widely employed.

PROPAGATION OF VHF WAVES

The wave energy of VHF stations does not simply disappear once it reaches the radio horizon. It is scattered, but it can be heard to some degree for hundreds of miles, well beyond line-of-sight range. Everything on Earth, and in the regions of space up to at least 100 miles, is a potential forward-scattering agent.

Tropospheric scatter is always with us. Its effects are often hidden, masked by more effective propagation modes on the lower frequencies. But beginning in the VHF range, scatter from the lower atmosphere extends the reliable range markedly if we make use of it. Called *troposcatter*, this is what produces that nearly flat portion of the curves that will be described later (in the section where you can compute reliable VHF coverage range). With a decent station, you can consistently make troposcatter contacts out to 300 miles out on the VHF and even UHF bands, especially if you don't mind weak signals and something less than 99% reliability. As long ago as the early 1950s, VHF enthusiasts found that VHF contests could be won with high power, big antennas and a good ear for signals deep in the noise. They still can.

Ionospheric scatter works much the same as the tropo version, except that the scattering medium is higher up, mainly the E region of the ionosphere but with some help from the D and F layers too. Ionospheric scatter is useful mainly above the MUF, so its useful frequency range depends on geography, time of day, season, and the state of the Sun. With near maximum legal power, good antennas and quiet locations, ionospheric scatter can fill in the skip zone with marginally readable signals scattered from ionized trails of meteors, small areas of random ionization, cosmic dust, satellites and whatever may come into the antenna patterns at 50 to 150 miles or so above the Earth. It's mostly an E-layer business, so it works all E-layer distances. Good antennas and keen ears help.

Transequatorial propagation (TE) was an amateur 50-MHz discovery in the years 1946-1947. Amateurs of all continents observed it almost simultaneously on three separate north-south paths. These amateurs tried to communicate at 50 MHz, even though the predicted MUF was around 40 MHz for the favorable daylight hours. The first success came at night, when the MUF was thought to be even lower. A remarkable research program inaugurated by amateurs in Europe, Cyprus, Zimbabwe and South Africa eventually provided technically sound theories to explain the then-unknown mode.

It has been known for years that the MUF is higher and less seasonally variable on transequatorial circuits, but the full extent of the difference was not learned until amateur work brought it to light. As will be explained in a later section in more detail, the ionosphere over equatorial regions is higher, thicker and more dense than elsewhere. Because of its more constant exposure to solar radiation, the equatorial belt has high nighttime-MUF possibilities. TE can often work marginally at 144 MHz, and even at 432 MHz on occasion. The potential MUF varies with solar activity, but not to the extent that conventional F-layer propagation does. It is a late-in-the-day mode, taking over about when normal F-layer propagation goes out.

The TE range is usually within about 4000 km (2500 miles) either side of the geomagnetic equator. The Earth's magnetic axis is tilted with respect to the geographical axis, so the TE belt appears as a curving band on conventional flat maps of the world. See **Fig 8**. As a result, TE has a different latitude coverage in the Americas from that from Europe to Africa. The TE belt just reaches into the southern continental US. Stations in Puerto Rico, Mexico and even the northern parts of South America encounter the mode more often than those in favorable US areas. It is no accident that TE was discovered as a result of 50-MHz work in Mexico City and Buenos Aires.

Within its optimum regions of the world, the TE mode extends the usefulness of the 50-MHz band far beyond that of conventional F-layer propagation, since the practical TE MUF runs around 1.5 times that of normal F_2. Both its seasonal and diurnal characteristics are extensions of what is considered normal for 50-MHz propagation. In that part of the Americas south of about 20° North latitude, the existence of TE affects the whole character of band usage, especially in years of high solar activity.

Fig 8—Transequatorial spread-F propagation takes place between stations equidistant across the geomagnetic equator. Distances up to 8000 km (5000 miles) are possible on 28 through 432 MHz. Note that the geomagnetic equator is considerably south of the geographic equator in the Western Hemisphere. (*Figure courtesy of The ARRL Handbook.*)

Weather Effects on VHF/UHF Tropospheric Propagation

Changes in the dielectric constant of the medium can affect propagation. Varied weather patterns over most of the Earth's surface can give rise to boundaries between air masses of very different temperature and humidity characteristics. These boundaries can be anything from local anomalies to air-circulation patterns of continental proportions.

Under stable weather conditions, large air masses can retain their characteristics for hours or even days at a time. See **Fig 9**. Stratified warm dry air over cool moist air, flowing slowly across the Great Lakes region to the Atlantic Seaboard, can provide the medium for east-west communication on 144 MHz and higher amateur frequencies over as much as 1200 miles. More common, however, are communication distances of 400 to 600 miles under such conditions.

A similar inversion along the Atlantic Seaboard as a result of a tropical storm air-circulation pattern may bring VHF and UHF openings extending from the Maritime Provinces of Canada to the Carolinas. Propagation across the Gulf of Mexico, sometimes with very high signal levels, enlivens the VHF scene in coastal areas from Florida to Texas. The California coast, from below the San Francisco Bay Area to Mexico, is blessed with a similar propagation aid during the warmer months. Tropical storms moving west, across the Pacific below the Hawaiian Islands, may provide a transpacific long-distance VHF medium. Amateurs first exploited this on 144, 220 and 432 MHz, in 1957. It has been used fairly often in the summer months since, although not yearly.

The examples of long-haul work cited above may occur infrequently, but lesser extensions of the minimum operating range are available almost daily. Under minimum conditions there may be little more than increased signal strength over paths that are workable at any time.

There is a diurnal effect in temperate climates. At sunrise the air aloft is warmed more rapidly than that near the Earth's surface, and as the Sun goes lower late in the day the upper air is kept warm, while the ground cools. In fair, calm weather such sunrise and sunset temperature inversions can improve signal strength over paths beyond line of sight as much as 20 dB over levels prevailing during the hours of high sun. The diurnal inversion may also extend the operating range for a given strength by some 20 to 50%. If you would be happy with a new VHF antenna, try it first around sunrise!

There are other short-range effects of local atmospheric and topographical conditions. Known as *subsidence*, the flow of cool air down into the bottom of a valley, leaving warm air aloft, is a familiar summer-evening pleasure. The daily inshore-offshore wind shift along a seacoast in summer sets up daily inversions that make coastal areas highly favored as VHF sites. Ask any jealous 144-MHz operator who lives more than a few miles inland.

Tropospheric effects can show up at any time, in any season. Late spring and early fall are the most favored periods, although a winter warming trend can produce strong and stable inversions that work VHF magic almost equal to that of the more familiar spring and fall events.

Fig 9—Upper air conditions that produce extended-range communication on the VHF bands. At the top is shown the US Standard Atmosphere temperature curve. The humidity curve (dotted) is what would result if the relative humidity were 70%, from ground level to 12,000 feet elevation. There is only slight refraction under this standard condition. At the bottom is shown a sounding that is typical of marked refraction of VHF waves. Figures in parentheses are the "mixing ratio" —grams of water vapor per kilogram of dry air. Note the sharp break in both curves at about 3500 feet.

Regions where the climate is influenced by large bodies of water enjoy the greatest degree of tropospheric bending. Hot, dry desert areas see little of it, at least in the forms described above.

Tropospheric Ducting

Tropospheric propagation of VHF and UHF waves can influence signal levels at all distances from purely local to something beyond 4000 km (2500 miles). The outer limits are not well known. At the risk of over simplification, we will divide the modes into two classes—extended local and long distance. This concept must be modified depending on the frequency under consideration, but in the VHF range the extended-local effect gives way to a form of propagation much like that of microwaves in a waveguide, called *ducting*. The transition distance is ordinarily somewhere around 200 miles. The difference lies in whether the atmospheric condition producing the bending is localized or continental in scope. Remember, we're concerned here with frequencies in the VHF range, and perhaps up to 500 MHz. At 10 GHz, for example, the scale is much smaller.

In VHF propagation beyond a few hundred miles, more than one weather front is probably involved, but the wave is propagated between the inversion layers and ground, in the main. On long paths over the ocean (two notable examples are California to Hawaii and Ascension Island to Brazil), propagation is likely to be between two atmospheric layers. On such circuits the communicating station antennas must be in the duct, or capable of propagating strongly into it. Here again, we see that the positions and radiation angles of the antennas are important. As with microwaves in a waveguide, the low-frequency limit for the duct is critical. In long-distance ducting it is also very variable. Airborne equipment has shown that duct capability exists well down into the HF region in the stable atmosphere west of Ascension Island. Some contacts between Hawaii and Southern California on 50 MHz are believed to have been by way of tropospheric ducts. Probably all contact over these paths on 144 MHz and higher bands is because of duct propagation.

Amateurs have played a major part in the discovery and eventual explanation of tropospheric propagation. In recent years they have shown that, contrary to beliefs widely held in earlier times, long-distance communication using tropospheric modes is possible to some degree on all amateur frequencies from 50 to at least 10,000 MHz.

RELIABLE VHF COVERAGE

In the preceding sections we discussed means by which amateur bands above 50 MHz may be used intermittently for communication far beyond the visual horizon. In emphasizing distance we should not neglect a prime asset of the VHF band: reliable communication over relatively short distances. The VHF region is far less subject to disruption of local communication than are frequencies below 30 MHz. Since much amateur communication is essentially local in nature, our VHF assignments can carry a great load,

and such use of the VHF bands helps solve interference problems on lower frequencies.

Because of age-old ideas, misconceptions about the coverage obtainable in our VHF bands persist. This reflects the thoughts that VHF waves travel only in straight lines, except when the DX modes described above happen to be present. However, let us survey the picture in the light of modern wave-propagation knowledge and see what the bands above 50 MHz are good for on a day-to-day basis, ignoring the anomalies that may result in extensions of normal coverage.

It is possible to predict with fair accuracy how far you should be able to work consistently on any VHF or UHF band, provided a few simple facts are known. The factors affecting operating range can be reduced to graph form, as described in this section. The information was originally published in November 1961 *QST* by D. W. Bray, K2LMG (see the Bibliography at the end of this chapter).

To estimate your station's capabilities, two basic numbers must be determined: station gain and path loss. Station gain is made up of seven factors: receiver sensitivity, transmitted power, receiving antenna gain, receiving antenna height gain, transmitting antenna gain, transmitting antenna height gain and required signal-to-noise ratio. This looks complicated but it really boils down to an easily made evaluation of receiver, transmitter, and antenna performance. The other number, path loss, is readily determined from the nomogram, **Fig 10**. This gives path loss over smooth Earth, for 99% reliability.

For 50 MHz, lay a straightedge from the distance between stations (left side) to the appropriate distance at the right side. For 1296 MHz, use the full scale, right center. For 144, 222 and 432, use the dot in the circle, square or triangle, respectively. Example: At 300 miles the path loss for 144 MHz is 214 dB.

To be meaningful, the losses determined from this nomograph are necessarily greater than simple free-space path losses. As described in an earlier section, communication beyond line-of-sight distances involves propagation modes that increase the path attenuation with distance.

VHF/UHF Station Gain

The largest of the eight factors involved in station design is receiver sensitivity. This is obtainable from **Fig 11**, if you know the approximate receiver noise figure and transmission-line loss. If you can't measure noise figure, assume 3 dB for 50 MHz, 5 for 144 or 222, 8 for 432 and 10 for 1296 MHz, if you know your equipment is working moderately well. These noise figures are well on the conservative side for modern solid-state receivers.

Line loss can be taken from information in Chapter 24 for the line in use, if the antenna system is fed properly. Lay a straightedge between the appropriate points at either side of Fig 11, to find effective receiver sensitivity in decibels below 1 watt (dBW). Use the narrowest bandwidth that is practical for the emission intended, with the receiver you will be using. For CW, an average value for effective work

Fig 10—Nomogram for finding the capabilities of stations on amateur bands from 50 to 1300 MHz. Either the path loss for a given distance or vice versa may be found if one of the two factors is known.

is about 500 Hz. Phone bandwidth can be taken from the receiver instruction manual, but it usually falls between 2.1 to 2.7 kHz.

Antenna gain is next in importance. Gains of amateur antennas are often exaggerated. For well-designed Yagis the gain (over isotropic) run close to 10 times the boom length in wavelengths. (Example: A 24-foot Yagi on 144 MHz is 3.6 wavelengths long; 3.6 x 10 = 36, and 10 $\log_{10}$ 36 = 15.5 dBi in free space.) Add 3 dB for stacking, where used properly. Add 4 dB more for ground reflection gain. This varies in amateur work, but averages out near this figure.

We have one more plus factor—antenna height gain, obtained from **Fig 12**. Note that this is greatest for short distances. The left edge of the horizontal center scale is for 0 to 10 miles, the right edge for 100 to 500 miles. Height gain for 10 to 30 feet is assumed to be zero. For 50 feet the height gain is 4 dB at 10 miles, 3 dB at 50 miles, and 2 dB at 100 miles. At 80 feet the height gains are roughly 8, 6 and 4 dB for these distances. Beyond 100 miles the height gain is nearly uniform for a given height, regardless of distance.

Transmitter power output must be stated in decibels above 1 watt. If you have 500 W output, add 10 log (500/1),

or 27 dB, to your station gain. The transmission-line loss must be subtracted from the station gain. So must the required signal-to-noise ratio. The information is based on CW work, so the additional signal needed for other modes must be subtracted. Use a figure of 3 dB for SSB. Fading losses must be accounted for also. It has been shown that for distances beyond 100 miles, the signal will vary plus or minus about 7 dB from the average level, so 7 dB must be subtracted from the station gain for high reliability. For distances under 100 miles, fading diminishes almost linearly with distance. For 50 miles, use –3.5 dB for fading.

What It All Means

Add all the plus and minus factors to get the station gain. Use the final value to find the distance over which you can expect to work reliably from the nomogram, Fig 10. Or work it the other way around: Find the path loss for the distance you want to cover from the nomogram and then figure out what station changes will be needed to overcome it.

The significance of all this becomes more obvious when we see path loss plotted against frequency for the various bands, as in **Fig 13**. At the left this is done for 50% reliability. At the right is the same information for 99% reliability.

Fig 11—Nomogram for finding effective receiver sensitivity.

For near-perfect reliability, a path loss of 195 dB (easily encountered at 50 or 144 MHz) is involved in 100-mile communication. But look at the 50% reliability curve: The same path loss takes us out to well over 250 miles. Few amateurs demand near-perfect reliability. By choosing our times, and by accepting the necessity for some repeats or occasional loss of signal, we can maintain communication out to distances far beyond those usually covered by VHF stations.

Working out a few typical amateur VHF station setups with these curves will show why an understanding of these factors is important to any user of the VHF spectrum. Note that path loss rises very steeply in the first 100 miles or so. This is no news to VHF operators; locals are very strong, but stations 50 or 75 miles away are much weaker. What happens beyond 100 miles is not so well known to many of us.

From the curves of Fig 13, we see that path loss levels off markedly at what is the approximate limit of working range for average VHF stations using wideband modulation modes. Work out the station gain for a 50-W station with an average receiver and antenna, and you'll find that it comes out around 180 dB. This means you'd have about a 100-mile

working radius in average terrain, for good but not perfect reliability. Another 10 dB may extend the range to as much as 250 miles. Just changing from AM phone to SSB and CW makes a major improvement in daily coverage on the VHF bands.

A bigger antenna, a higher one if your present beam is not at least 50 feet up, an increase in power to 500 W from 50 W, an improvement in receiver noise figure if it is presently poor—any of these things can make a big improvement in reliable coverage. Achieve all of them, and you will have very likely tripled your sphere of influence, thanks to that hump in the path-loss curves. This goes a long way toward explaining why using a 10-W packaged station with a small antenna, fun though it may be, does not begin to show what the VHF bands are really good for.

Terrain at VHF/UHF

The coverage figures derived from the above procedure are for average terrain. What of stations in mountainous country? Although an open horizon is generally desirable for the VHF station site, mountain country should not be

Fig 12—Nomogram for determining antenna-height gain.

Fig 13—Path loss versus distance for amateur frequencies above 50 MHz. At A are curves for 50% of the time; at B, for 99%. The curves at A are more representative of Amateur Radio requirements.

considered hopeless. Help for the valley dweller often lies in the optical phenomenon known as *knife-edge diffraction.* A flashlight beam pointed at the edge of a partition does not cut off sharply at the partition edge, but is diffracted around it, partially illuminating the shadow area. A similar effect is observed with VHF waves passing over ridges; there is a shadow effect, but not a complete blackout. If the signal is strong where it strikes the mountain range, it will be heard well in the bottom of a valley on the far side. (See Chapter 3, The Effects of Ground, for a more thorough discussion of the theory of diffraction.)

This is familiar to all users of VHF communications equipment who operate in hilly terrain. Where only one ridge lies in the way, signals on the far side may be almost as good as on the near side. Under ideal conditions (a very high and sharp-edged obstruction near the midpoint of a long-enough path so that signals would be weak over average terrain), knife-edge diffraction may yield signals even stronger than would be possible with an open path.

The obstruction must project into the radiation patterns of the antennas used. Often mountains that look formidable to the viewer are not high enough to have an appreciable

effect, one way or the other. Since the normal radiation pattern from a VHF array is several degrees above the horizontal, mountains that are less than about three degrees above the horizon, as seen from the antenna, are missed by the radiation from the array. Moving the mountains out of the way would have substantially no effect on VHF signal strength in such cases.

Rolling terrain, where obstructions are not sharp enough to produce knife-edge diffraction, still does not exhibit a complete shadow effect. There is no complete barrier to VHF propagation—only attenuation, which varies widely as the result of many factors. Thus, even valley locations are usable for VHF communication. Good antenna systems, preferably as high as possible, the best available equipment, and above all, the willingness and ability to work with weak signals may make outstanding VHF work possible, even in sites that show little promise by casual inspection.

AURORAL PROPAGATION

The Earth has a *magnetosphere* or magnetic field surrounding it. NASA scientists have described the magnetosphere as a sort of protective "bubble" around the Earth that shields us from the solar wind. Under normal circumstances, there are lots of electrons and protons moving in our magnetosphere, traveling along magnetic lines of force that trap them and keep them in place, neither bombarding the earth nor escaping into outer space.

Sudden bursts of activity on the Sun are sometimes accompanied by the ejection of charged particles, often from so-called Coronal Mass Ejections (CME) because they originate from the Sun's outer coronal region. These charged particles can interact with the magnetosphere, compressing and distorting it. If the orientation of the magnetic field contained in a large blast of solar wind or in a CME is aligned opposite to that of the Earth's magnetic field, the magnetic bubble can partially collapse and the particles normally trapped there can be deposited into the Earth's atmosphere along magnetic lines near the North or South poles. This produces a visible or radio *aurora*. An aurora is visible if the time of entry is after dark.

The visible aurora is, in effect, fluorescence at E-layer height—a curtain of ions capable of refracting radio waves in the frequency range above about 20 MHz. D-region absorption increases on lower frequencies during auroras. The exact frequency ranges depend on many factors: time, season, position with relation to the Earth's auroral regions, and the level of solar activity at the time, to name a few.

The auroral effect on VHF waves is another amateur discovery, this one dating back to the 1930s. The discovery came coincidentally with improved transmitting and receiving techniques then. The returning signal is diffused in frequency by the diversity of the auroral curtain as a refracting (scattering) medium. The result is a modulation of a CW signal, from just a slight burbling sound to what is best described as a "keyed roar." Before SSB took over in VHF work, voice was all but useless for auroral paths. A sideband signal suffers, too, but its narrower bandwidth helps to retain some degree of understandability. Distortion induced by a given set of auroral conditions increases with the frequency in use. 50-MHz signals are much more intelligible than those on 144 MHz on the same path at the same time. On 144 MHz, CW is almost mandatory for effective auroral communication.

The number of auroras that can be expected per year varies with the geomagnetic latitude. Drawn with respect to the Earth's magnetic poles instead of the geographical ones, these latitude lines in the US tilt upward to the northwest. For example, Portland, Oregon, is 2° farther north (geographic latitude) than Portland, Maine. The Maine city's geomagnetic latitude line crosses the Canadian border before it gets as far west as its Oregon namesake. In terms of auroras intense enough to produce VHF propagation results, Portland, Maine, is likely to see about 10 times as many per year. Oregon's auroral prospects are more like those of southern New Jersey or central Pennsylvania.

The antenna requirements for auroral work are mixed. High gain helps, but the area of the aurora yielding the best returns sometimes varies rapidly, so sharp directivity can be a disadvantage. So could a very low radiation angle, or a beam pattern very sharp in the vertical plane. Experience indicates that few amateur antennas are sharp enough in either plane to present a real handicap. The beam heading for maximum signal can change, however, so a bit of scanning in azimuth may turn up some interesting results. A very large array, such as is commonly used for moonbounce (with azimuth-elevation control), should be worthwhile.

The incidence of auroras, their average intensity, and their geographical distribution as to visual sightings and VHF propagation effects all vary to some extent with solar activity. There is some indication that the peak period for auroras lags the sunspot-cycle peak by a year or two. Like sporadic E, an unusual auroral opening can come at any season. There is a marked diurnal swing in the number of auroras. Favored times are late afternoon and early evening, late evening through early morning, and early afternoon, in about that order. Major auroras often start in early afternoon and carry through to early morning the next day.

HF Sky-Wave Propagation

As described earlier, the term *ground wave* is commonly applied to propagation that is confined to the Earth's lower atmosphere. Now we will use the term *sky wave* to describe modes of propagation that use the Earth's ionosphere. First, however, we must examine how the Earth's ionosphere is affected by the Sun.

THE ROLE OF THE SUN

Everything that happens in radio propagation, as with all life on Earth, is the result of radiation from the Sun. The variable nature of radio propagation here on Earth reflects the ever-changing intensity of ultraviolet and X-ray radiation, the primary ionizing agents in solar energy. Every day, solar nuclear reactions are turning hydrogen into helium, releasing an unimaginable blast of energy into space in the process. The total power radiated by the Sun is estimated at 4×10^{23} kW—that is, the number four followed by 23 zeroes. At its surface, the Sun creates about 60 *megawatts* per square meter. That is a very potent transmitter!

The Solar Wind

The Sun is constantly ejecting material from its surface in all directions into space, making up the so-called *solar wind*. Under relatively quiet solar conditions the solar wind blows around 200 miles per second—675,000 miles per hour—taking away about two million tons of solar material each second from the Sun. You needn't worry—the Sun is not going to shrivel up anytime soon. It's big enough that it will take many billions of years before that happens.

A 675,000 mile/hour wind sounds like a pretty stiff breeze, doesn't it? Lucky for us, the density of the material in the solar wind is very small by the time it has been spread out into interplanetary space. Scientists calculate that the density of the particles in the solar wind is less than that of the best vacuum they've ever achieved on Earth. Despite the low density of the material in the solar wind, the effect on the Earth, especially its magnetic field, is very significant.

Before the advent of sophisticated satellite sensors, the Earth's magnetic field was considered to be fairly simple, modeled as if the Earth were a large bar magnet. The axis of this hypothetical bar magnet is oriented about 11° away from the geographic north-south pole. We now know that the solar wind alters the shape of the Earth's magnetic field significantly, compressing it on the side facing the Sun and elongating it on the other side—in the same manner as the tail of a comet is stretched out radially in its orientation from the Sun. In fact, the solar wind is also responsible for the shape of a comet's tail.

Partly because of the very nature of the nuclear reactions going on at the Sun itself, but also because of variations in the speed and direction of the solar wind, the interactions between the Sun and our Earth are incredibly complex. Even scientists who have studied the subject for years do not completely understand everything that happens on the Sun. Later in this chapter, we'll investigate the effects of the solar wind when conditions on the Sun are *not* "quiet." As far as amateur HF skywave propagation is concerned, the results of disturbed conditions on the Sun are not generally beneficial.

Sunspots

The most readily observed characteristic of the Sun, other than its blinding brilliance, is its tendency to have grayish black blemishes, seemingly at random times and at random places, on its fiery surface. (See **Fig 14**.) There are written records of naked-eye sightings of *sunspots* in the Orient back to more than 2000 years ago. As far as is known, the first indication that sunspots were recognized as part of the Sun was the result of observations by Galileo in the early 1600s, not long after he developed one of the first practical telescopes.

Galileo also developed the projection method for observing the Sun safely, but probably not before he had suffered severe eye damage by trying to look at the Sun di-

Fig 14—Much more than sunspots can be seen when the sun is viewed through selective optical filters. This photo was taken through a hydrogen-alpha filter that passes a narrow light segment at 6562 angstroms. The bright patches are active areas around and often between sunspots. Dark irregular lines are filaments of activity having no central core. Faint magnetic field lines are visible around a large sunspot group near the disc center. (*Photo courtesy of Sacramento Peak Observatory, Sunspot, New Mexico*).

rectly. (He was blind in his last years.) His drawings of sunspots, indicating their variable nature and position, are the earliest such record known to have been made. His reward for this brilliant work was immediate condemnation by church authorities of the time, which probably set back progress in learning more about the Sun for generations.

The systematic study of solar activity began about 1750, so a fairly reliable record of sunspot numbers goes back that far. (There are some gaps in the early data.) The record shows clearly that the Sun is always in a state of change. It never looks exactly the same from one day to the next. The most obvious daily change is the movement of visible activity centers (sunspots or groups thereof) across the solar disc, from east to west, at a constant rate. This movement was soon found to be the result of the rotation of the Sun, at a rate of approximately four weeks for a complete round. The average is about 27.5 days, the Sun's *synodic* rotation speed, viewed from the perspective of the Earth, which is also moving around the Sun in the same direction as the Sun's rotation.

Sunspot Numbers

Since the earliest days of systematic observation, our traditional measure of solar activity has been based on a count of sunspots. In these hundreds of years we have learned that the average number of spots goes up and down in cycles very roughly approximating a sine wave. In 1848, a method was introduced for the daily measurement of sunspot numbers. That method, which is still used today, was devised by the Swiss astronomer Johann Rudolph Wolf. The observer counts the total number of spots visible on the face of the Sun and the number of groups into which they are clustered, because neither quantity alone provides a satisfactory measure of sunspot activity. The observer's sunspot number for that day is computed by multiplying the number of groups he sees by 10, and then adding to this value the number of individual spots. Where possible, sunspot data collected prior to 1848 have been converted to this system.

As can readily be understood, results from one observer to another can vary greatly, since measurement depends on the capability of the equipment in use and on the stability of the Earth's atmosphere at the time of observation, as well as on the experience of the observer. A number of observatories around the world cooperate in measuring solar activity. A weighted average of the data is used to determine the *International Sunspot Number* or ISN for each day. (Amateur astronomers can approximate the determination of ISN values by multiplying their values by a correction factor determined empirically.)

A major step forward was made with the development of various methods for observing narrow portions of the Sun's spectrum. Narrowband light filters that can be used with any good telescope perform a visual function very similar to the aural function of a sharp filter added to a communications receiver. This enables the observer to see the actual area of the Sun doing the radiating of the ionizing energy, in addition

to the sunspots, which are more a by-product than a cause. The photo of Fig 14 was made through such a filter. Studies of the ionosphere with instrumented probes, and later with satellites, manned and unmanned, have added greatly to our knowledge of the effects of the Sun on radio communication.

Daily sunspot counts are recorded, and monthly and yearly averages determined. The averages are used to see trends and observe patterns. Sunspot records were formerly kept in Zurich, Switzerland, and the values were known as *Zurich Sunspot Numbers*. They were also known as Wolf sunspot numbers. The official international sunspot numbers are now compiled at the Sunspot Index Data Center in Bruxelles, Belgium.

The yearly means (averages) of sunspot numbers from 1700 through 2002 are plotted in **Fig 15**. The cyclic nature of solar activity becomes readily apparent from this graph. The duration of the cycles varies from 9.0 to 12.7 years, but averages approximately 11.1 years, usually referred to as the 11-year solar cycle. The first complete cycle to be observed systematically began in 1755, and is numbered Cycle 1. Solar cycle numbers thereafter are consecutive. Cycle 23 began in October, 1996.

The "Quiet" Sun

For more than 60 years it has been well known that radio propagation phenomena vary with the number and size of sunspots, and also with the position of sunspots on the surface of the Sun. There are daily and seasonal variations in the Earth's ionized layers resulting from changes in the amount of ultraviolet light received from the Sun. The 11-year sunspot cycle affects propagation conditions because there is a direct correlation between sunspot activity and ionization.

Fig 15—Yearly means of smoothed sunspot numbers from data for 1700 through 2002. This plot clearly shows that sunspot activity takes place in cycles of approximately 11 years duration. There is also a longer-term periodicity in this plot, the Gleissberg 88-year cycle. Cycle 1, the first complete cycle to be examined by systematic observation, began in 1755.

Activity on the surface of the Sun is changing continually. In this section we want to describe the activity of the so-called *quiet Sun*, meaning those times when the Sun is not doing anything more spectacular than acting like a "normal" thermonuclear ball of flaming gases. The Sun and its effects on Earthly propagation can be described in *statistical* terms—that's what the 11-year solar cycle does. You may experience vastly different conditions on any particular day compared to what a long-term average would suggest.

An analogy may be in order here. Have you ever gazed into a relatively calm campfire and been surprised when suddenly a flaming ember or a large spark was ejected in your direction? The Sun can also do unexpected and sometimes very dramatic things. Disturbances of propagation conditions here on Earth are caused by disturbed conditions on the Sun. More on this later.

Individual sunspots may vary in size and appearance, or even disappear totally, within a single day. In general, larger active areas persist through several rotations of the Sun. Some active areas have been identified over periods up to about a year. Because of these continual changes in solar activity, there are continual changes in the state of the Earth's ionosphere and resulting changes in propagation conditions. A short-term burst of solar activity may trigger unusual propagation conditions here on Earth lasting for less than an hour.

Smoothed Sunspot Numbers (SSN)

Sunspot data are averaged or smoothed to remove the effects of short-term changes. The sunspot values used most often for correlating propagation conditions are *Smoothed Sunspot Numbers* (SSN), often called 12-month running average values. Data for 13 consecutive months are required to determine a smoothed sunspot number.

Long-time users have found that the upper HF bands are reliably open for propagation only when the average number of sunspots is above certain minimum levels. For example, between mid 1988 to mid 1992 during Cycle 22, the SSN stayed higher than 100. The 10-meter band was open then almost all day, every day, to some part of the world. However, by mid 1996, few if any sunspots showed up on the Sun and the 10-meter band consequently was rarely open. Even 15 meters, normally a workhorse DX band when solar activity is high, was closed most of the time during the low point in Cycle 22. So far as propagation on the upper HF bands is concerned, the higher the sunspot number, the better the conditions.

Each smoothed number is an average of 13 monthly means, centered on the month of concern. The 1st and 13th months are given a weight of 0.5. A monthly mean is simply the sum of the daily ISN values for a calendar month, divided by the number of days in that month. We would commonly call this value a monthly average.

This may all sound very complicated, but an example should clarify the procedure. Suppose we wished to calculate the smoothed sunspot number for June 1986. We would require monthly mean values for six months prior and six months after this month, or from December 1985 through December 1986. The monthly mean ISN values for these months are

Dec	85	17.3	Jul	86	18.1
Jan	86	2.5	Aug	86	7.4
Feb	86	23.2	Sep	86	3.8
Mar	86	15.1	Oct	86	35.4
Apr	86	18.5	Nov	86	15.2
May	86	13.7	Dec	86	6.8
Jun	86	1.1			

First we find the sum of the values, but using only one-half the amounts indicated for the first and 13th months in the listing. This value is 166.05. Then we determine the smoothed value by dividing the sum by 12: 166.05/12 = 13.8. (Values beyond the first decimal place are not warranted.) Thus, 13.8 is the smoothed sunspot number for June 1986. From this example, you can see that the smoothed sunspot number for a particular month cannot be determined until six months afterwards.

Generally the plots we see of sunspot numbers are averaged data. As already mentioned, smoothed numbers make it easier to observe trends and see patterns, but sometimes this data can be misleading. The plots tend to imply that solar activity varies smoothly, indicating, for example, that at the onset of a new cycle the activity just gradually increases. But this is definitely not so! On any one day, significant changes in solar activity can take place within hours, causing sudden band openings at frequencies well above the MUF values predicted from smoothed sunspot number curves. The durations of such openings may be brief, or they may recur for several days running, depending on the nature of the solar activity.

Solar Flux

Since the late 1940s an additional method of determining solar activity has been put to use—the measurement of *solar radio flux*. The quiet Sun emits radio energy across a broad frequency spectrum, with a slowly varying intensity. Solar flux is a measure of energy received per unit time, per unit area, per unit frequency interval. These radio fluxes, which originate from atmospheric layers high in the Sun's chromosphere and low in its corona, change gradually from day to day, in response to the activity causing sunspots. Thus, there is a degree of correlation between solar flux values and sunspot numbers.

One solar flux unit equals 10^{-22} joules per second per square meter per hertz. Solar flux values are measured daily at 2800 MHz (10.7 cm) at The Dominion Radio Astrophysical Observatory, Penticton, British Columbia, where daily data have been collected since 1991. (Prior to June 1991, the Algonquin Radio Observatory, Ontario, made the measurements.) Measurements are also made at other observatories around the world, at several frequencies. With some variation, the daily measured flux values increase with

increasing frequency of measurement, to at least 15.4 GHz. The daily 2800 MHz Penticton value is sent to Boulder, Colorado, where it is incorporated into WWV propagation bulletins (see later section). Daily solar flux information can be of some value in determining current propagation conditions, as sunspot numbers on a given day do not relate directly to maximum usable frequency. Solar flux values are much more reliable for this purpose, when it is averaged over time, as will be discussed later in the section on computer-prediction programs.

Correlating Sunspot Numbers and Solar Flux Values

Based on historical data, an exact mathematical relationship does not exist to correlate sunspot data and solar flux values. Comparing daily values yields almost no correlation. Comparing monthly mean values (often called monthly averages) produces a degree of correlation, but the spread in data is still significant. This is indicated in **Fig 16**, a scatter diagram plot of monthly mean sunspot numbers versus the monthly means of solar flux values adjusted to one astronomical unit. (This adjustment applies a correction for differences in distance between the Sun and the Earth at different times of the year.)

A closer correlation exists when smoothed (12-month running average) sunspot numbers are compared with smoothed (12-month running average) solar flux values adjusted to one astronomical unit. A scatter diagram for smoothed data appears in **Fig 17**. Note how the plot points establish a better defined pattern in Fig 17. The correlation is still no better than a few percent, for records indicate a given smoothed sunspot number does not always correspond with the same smoothed solar flux value, and vice versa.

Fig 16—Scatter diagram or X-Y plot of monthly mean sunspot numbers and monthly mean 2800MHz solar flux values. Data values are from February 1947 through February 1987. Each "+" mark represents the intersection of data for a given month. If the correlation between sunspot number and flux values were consistent, all the marks would align to form a smooth curve.

Table 1 illustrates some of the inconsistencies that exist in the historical data. Smoothed or 12-month running average values are shown.

Even though there is no precise mathematical relationship between sunspot numbers and solar flux values, it is helpful to have some way to convert from one to the other. The primary reason is that sunspot numbers are valuable as a long-term link with the past, but the great usefulness of solar flux values are their immediacy, and their direct bearing on our field of interest. (Remember, a smoothed sunspot number will not be calculated until six months after the fact.)

The following mathematical approximation has been derived to convert a smoothed sunspot number to a solar flux value.

Fig 17—Scatter diagram of smoothed, or 12-month running averages, sunspot numbers versus 2800MHz solar flux values. The correlation of smoothed values is better than for monthly means, shown in Fig 16.

Table 1

Selected Historical Data Showing Inconsistent Correlation Between Sunspot Number and Solar Flux

Month	Smoothed Sunspot Number	Smoothed Solar Flux Value
May 1953	17.4	75.6
Sept 1965	17.4	78.5
Jul 1985	17.4	74.7
Jun 1969	106.1	151.4
Jul 1969	105.9	151.4
Dec 1982	94.6	151.4
Aug 1948	141.1	180.5
Oct 1959	141.1	192.3
Apr 1979	141.1	180.4
Aug 1981	141.1	203.3

$$F = 63.75 + 0.728\,S + 0.00089\,S^2 \qquad \text{(Eq 5)}$$

where

F = solar flux number

S = smoothed sunspot number

A graphic representation of this equation is given in **Fig 18**. Use this chart to make conversions graphically, rather than by calculations. With the graph, solar flux and sunspot number conversions can be made either way. The equation has been found to yield errors as great as 10% when historical data was examined. (Look at the August 1981 data in Table 1.) Therefore, conversions should be rounded to the nearest whole number, as additional decimal places are unwarranted. To make conversions from flux to sunspot number, the following approximation may be used.

$$S = 33.52\sqrt{85.12 + F} - 408.99 \qquad \text{(Eq 6)}$$

THE IONOSPHERE

There will be inevitable "gray areas" in our discussion of the Earth's atmosphere and the changes wrought in it by the Sun and by associated changes in the Earth's magnetic field. This is not a story that can be told in neat equations, or values carried out to a satisfying number of decimal places. The story must be told, and understood—with its well-known limitations—if we are to put up good antennas and make them serve us well.

Thus far in this chapter we have been concerned with what might be called our "above-ground living space"—that portion of the total atmosphere wherein we can survive without artificial breathing aids, or up to about 6 km

Fig 18—Chart for conversions between smoothed International Sunspot Numbers and smoothed 2800MHz solar flux. This curve is based on the mathematical approximation given in the text.

(4 miles). The boundary area is a broad one, but life (and radio propagation) undergo basic changes beyond this zone. Somewhat farther out, but still technically within the Earth's atmosphere, the role of the Sun in the wave-propagation picture is a dominant one.

This is the *ionosphere*—a region where the air pressure is so low that free electrons and ions can move about for some time without getting close enough to recombine into neutral atoms. A radio wave entering this rarefied atmosphere, a region of relatively many free electrons, is affected in the same way as in entering a medium of different dielectric constant—its direction of travel is altered.

Ultraviolet (UV) radiation from the Sun is the primary cause of ionization in the outer regions of the atmosphere, the ones most important for HF propagation. However, there are other forms of solar radiation as well, including both hard and soft x-rays, gamma rays and extreme ultraviolet (EUV). The radiated energy breaks up, or *photoionizes*, atoms and molecules of atmospheric gases into electrons and positively charged ions. The degree of ionization does not increase uniformly with distance from the Earth's surface. Instead there are relatively dense regions (layers) of ionization, each quite thick and more or less parallel to the Earth's surface, at fairly well-defined intervals outward from about 40 to 300 km (25 to 200 miles). These distinct layers are formed due to complex photochemical reactions of the various types of solar radiation with oxygen, ozone, nitrogen and nitrous oxide in the rarefied upper atmosphere.

Ionization is not constant within each layer, but tapers off gradually on either side of the maximum at the center of the layer. The total ionizing energy from the Sun reaching a given point, at a given time, is never constant, so the height and intensity of the ionization in the various regions will also vary. Thus, the practical effect on long-distance communication is an almost continuous variation in signal level, related to the time of day, the season of the year, the distance between the Earth and the Sun, and both short-term and long-term variations in solar activity. It would seem from all this that only the very wise or the very foolish would attempt to predict radio propagation conditions, but it is now possible to do so with a fair chance of success. It is possible to plan antenna designs, particularly the choosing of antenna heights, to exploit known propagation characteristics.

Ionospheric Layer Characteristics

The lowest known ionized region, called the *D layer* (or the *D region*), lies between 60 and 92 km (37 to 57 miles) above the Earth. In this relatively low and dense part of the atmosphere, atoms broken up into ions by sunlight recombine quickly, so the ionization level is directly related to sunlight. It begins at sunrise, peaks at local noon and disappears at sundown. When electrons in this dense medium are set in motion by a passing wave, collisions between particles are so frequent that a major portion of their energy may be used up as heat, as the electrons and disassociated ions recombine.

The probability of collisions depends on the distance an electron travels under the influence of the wave—in other words, on the wavelength. Thus, our 1.8- and 3.5-MHz bands, having the longest wavelengths, suffer the highest daytime absorption loss as they travel through the D layer, particularly for waves that enter the medium at the lowest angles. At times of high solar activity (peak years of the solar cycle) even waves entering the D layer vertically suffer almost total energy absorption around midday, making these bands almost useless for communication over appreciable distances during the hours of high sun. They "go dead" quickly in the morning, but come alive again the same way in late afternoon. The diurnal (daytime) D-layer effect is less at 7 MHz (though still marked), slight at 14 MHz and inconsequential on higher amateur frequencies.

The D region is ineffective in bending HF waves back to Earth, so its role in long-distance communication by amateurs is largely a negative one. It is the principal reason why our frequencies up through the 7-MHz band are useful mainly for short-distance communication during the high-sun hours.

The lowest portion of the ionosphere useful for long-distance communication by amateurs is the *E layer* (also known as the *E region*) about 100 to 115 km (62 to 71 miles) above the Earth. In the E layer, at intermediate atmospheric density, ionization varies with the Sun angle above the horizon, but solar ultraviolet radiation is not the sole ionizing agent. Solar X-rays and meteors entering this portion of the Earth's atmosphere also play a part. Ionization increases rapidly after sunrise, reaches maximum around noon local time, and drops off quickly after sundown. The minimum is after midnight, local time. As with the D layer, the E layer absorbs wave energy in the lower-frequency amateur bands when the Sun angle is high, around mid-day. The other varied effects of E-region ionization will be discussed later.

Most of our long-distance communication capability stems from the tenuous outer reaches of the Earth's atmosphere known as the *F layer*. At heights above 100 miles, ions and electrons recombine more slowly, so the observable effects of the Sun develop more slowly. Also, the region holds its ability to reflect wave energy back to Earth well into the night. The *maximum usable frequency* (MUF) for F-layer propagation on east-west paths thus peaks just after noon at the midpoint, and the minimum occurs after midnight. We'll examine the subject of MUF in more detail later.

Judging what the F layer is doing is by no means that simple, however. The layer height may be from 160 to more than 500 km (100 to over 310 miles), depending on the season of the year, the latitudes, the time of day and, most capricious of all, what the Sun has been doing in the last few minutes and in perhaps the last three days before the attempt is made. The MUF between Eastern US and Europe, for example, has been anything from 7 to 70 MHz, depending on the conditions mentioned above, plus the point in the long-term solar-activity cycle at which the check is made.

During a summer day the F layer may split into two layers. The lower and weaker F_1 *layer*, about 160 km (100 miles) up, has only a minor role, acting more like the E than the F_2 *layer*. At night the F_1 region disappears and the F_2 region height drops somewhat.

Propagation information tailored to amateur needs is transmitted in all information bulletin periods by the ARRL Headquarters station, W1AW. Finally, solar and geomagnetic field data, transmitted hourly and updated eight times daily, are given in brief bulletins carried by the US Time Standard stations, WWV and WWVH, and also on Internet Web sites. But more on these services later.

Bending in the Ionosphere

The degree of bending of a wave path in an ionized layer depends on the density of the ionization and the length of the wave (inversely related to its frequency). The bending at any given frequency or wavelength will increase with increased ionization density and will bend away from the region of most-intense ionization. For a given ionization density, bending increases with wavelength (that is, it decreases with frequency).

Two extremes are thus possible. If the intensity of the ionization is sufficient and the frequency is low enough, even a wave entering the layer perpendicularly will be reflected back to Earth. Conversely, if the frequency is high enough or the ionization decreases to a low-enough density, a condition is reached where the wave angle is not affected enough by the ionosphere to cause a useful portion of the wave energy to return to the Earth. The frequency at which this occurs is called the vertical-incidence *critical frequency.* Each region in the ionosphere has a critical frequency associated with it, and this critical frequency will change depending on the date, time and state of the 11-year solar cycle.

Fig 19 shows a simplified graph of the electron density (in electrons per cubic meter) versus height in the ionosphere (in km) for a particular set of daytime and nighttime conditions. Free electrons are what return the signals you launch into the ionosphere back down to the Earth at some distance from your transmitter—The more free electrons in the ionosphere, the better propagation will be, particularly at higher frequencies.

Electron-density profiles are extremely complicated and vary greatly from one location to the next, depending on a bewildering variety of factors. Of course, this sheer variability makes it all the more interesting and challenging for hams to work each other on ionospheric HF paths!

The following discussion about sounding the ionosphere provides some background information about the scientific instruments used to decipher the highly intricate mechanisms behind ionospheric HF propagation.

SOUNDING THE IONOSPHERE

For many years scientists have *sounded* the ionosphere to determine its communication potential at various elevation angles and frequencies. The word "sound" stems from

Fig 19—Typical electron densities for nighttime and daytime conditions in the various ionospheric regions.

Fig 20—Very simplified ionogram from a vertical-incidence sounder. The lowest trace is for the E region; the middle for the F_1 and the upper trace for the F_2 region.

an old idea—one that has nothing to do with the audio waves that we can hear as "sounds." Long ago, sailors sounded the depths beneath their boats by dropping weighted ropes, calibrated in fathoms, into the water. In a similar fashion, the instrument used to probe the height of the ionosphere is called an *ionosonde*, or ionospheric sounder. It measures distances to various layers by launching a calibrated electronic signal directly up into the ionosphere.

Radar uses the same techniques as ionospheric sounding to detect targets such as airplanes. An ionosonde sends precisely timed pulses into the ionosphere over a range of MF and HF frequencies. The time of reception of an echo reflected from a region in the ionosphere is compared to the time of transmission. The time difference is multiplied by the speed of light to give the apparent distance that the wave has traveled from the transmitter to the ionosphere and back to the receiver. (It is an *apparent* or *virtual distance* because the speed of a wave slows very slightly in the ionosphere, just as the speed of propagation through any medium other than a vacuum slows down because of that medium.)

Another type of ionosonde sweeps the frequency of transmission, from low to high. This is called an "FM-CW," or more colorfully, a "chirp" sounder. Since a received echo takes time to travel from the transmitter up to the reflection point and then back again to the receiver, the echo will be at a lower frequency than the still-moving frequency of the transmitter. The frequency difference is an indication of the height of the echo's reflection off the various ionospheric layers.

Vertical-Incidence Sounders

Most ionosondes are *vertical-incidence sounders*, bouncing their signals perpendicularly off the various ion-

ized regions above it by launching signals straight up into the ionosphere. The ionosonde frequency is swept upwards until echos from the various ionospheric layers disappear, meaning that the critical frequencies for those layers have been exceeded, causing the waves to disappear into space.

Fig 20 shows a highly simplified ionogram for a typical vertical-incidence sounder. The echos at the lowest height at the left-hand side of the plot show that the E region is about 100 km high. The F_1 region shown in the middle of the plot varies from about 200 to 330 km in this example, and the F_2 region ranges from just under 400 km to almost 600 km in height. You can see that the F_1 and F_2 ionospheric regions take a "U" shape, indicating that the electron density varies throughout the layer. In this example, the peak in electron density is at a virtual height of the F_2 region of about 390 km, the lowest point in the F_2 curve.

Scientists can derive a lot of information from a vertical-incidence ionogram, including the critical frequencies for each region, where raising the frequency any higher causes the signals to disappear into space. In Fig 20, the E-region critical frequency (abbreviated f_oE) is about 4.1 MHz. The F_1-region critical frequency (abbreviated f_oF_1) is 4.8 MHz. The F2-region critical frequency (abbreviated f_oF_2) is this simplified diagram is 6.8 MHz.

The observant reader may well be wondering what the subscripted "o" in the abbreviations f_oE, f_oF_1 and f_oF_2 mean. The abbreviation "o" means "ordinary." When an electromagnetic wave is launched into the ionosphere, the Earth's magnetic field splits the wave into two independent waves— the "ordinary" (o) and the "extraordinary" (x) components. The ordinary wave reaches the same height in the ionosphere whether the Earth's magnetic field is present or not, and hence is called "ordinary." The extraordinary wave, however, is greatly affected by the presence of the Earth's magnetic field, in a very complex fashion.

Fig 21 shows an example of an actual ionogram from the vertical Lowell Digisonde at Millstone Hill in Massa-

Fig 21—Actual vertical-incidence ionogram from the Lowell Digisonde, owned and operated at Millstone Hill in Massachusetts by MIT. The ordinary (o) and extraordinary (x) traces are shown for heights greater than about 300 km. At the upper left are listed the computer-determined ionospheric parameters, such as f_oF_2 of 9.24 MHz and f_oF_1 at 4.66 MHz.

Fig 22—Computer simulation of the f_oF_2 contours for 25 November 1998, for an SSN of 85 and a quiet planetary A_p index of 5. Note the two regions of high f_oF_2 values off the upper and lower west coast of Africa. These are the "equatorial anomalies," regions of high electronic density in the F_2 region that often allow chordal-hop north-south propagation. See also Fig 8. (*PropLab Pro simulation, courtesy of Solar Terrestrial Dispatch.*)

chusetts, owned and operated by the Massachusetts Institute of Technology. This ionogram was made on June 18, 2000, and shows the conditions during a period of very high solar activity. The black-and-white rendition in Fig 21 of the actual color ionogram unfortunately loses some information. However, you can still see that a real ionogram is a lot more complicated looking than the simple simulated one in Fig 20.

The effects of noise and interference from other stations are shown by the many speckled dots appearing in the ionogram. The critical frequencies for various ionospheric layers are listed numerically at the left-hand side of the plot and the signal amplitudes are color-coded by the color bars at the right-hand side of the plot. The x-axis is the frequency, ranging from 1 to 11 MHz.

Compared to the simplified ionogram in Fig 20, Fig 21 shows another trace that appears on the plot from about 5.3 to 9.8 MHz, a trace shifted to the right of the darker ordinary trace. This second trace is the extraordinary (x) wave mentioned above. Since the x and o waves are created by the Earth's magnetic field, the difference in the ordinary and extraordinary traces is about $1/2$ the *gyro frequency*, the frequency at which an electron will spiral down a particular magnetic field line. The electron gyro frequency is different at various places around the Earth, being related to the Earth's complicated and changing magnetic field. The extraordinary trace always has a higher critical frequency than the ordinary trace on a vertical-incidence ionogram, and it is considerably weaker than the ordinary trace, especially at frequencies below about 4 MHz because of heavy absorption.

The Big Picture Overhead

There are about 150 vertical-incidence ionosondes around the world. Ionosondes are located on land, even on a number of islands. There are gaps in sounder coverage, however, mainly over large expanses of open ocean. The compilation of all available vertical-incidence data from the worldwide network of ionospheric sounders results in global f_oF_2 maps, such as the map shown in **Fig 22**, a simulation from the highly sophisticated *PropLab Pro* computer program.

This simulation is for 1300 UTC, several hours after East Coast sunrise on Nov 25, 1998, with a high level of solar activity of 85 and a planetary A_p index of 5, indicating calm geomagnetic conditions. The contours of f_oF_2 peak over the ocean off the west coast of Africa at 38 MHz. Over the southern part of Africa, f_oF_2 peaks at 33 MHz.

These two "humps" in f_oF_2 form what is known as the "equatorial anomaly" and are caused by upwelling "fountains" of high electron concentration located in daylight areas about ±20° from the Earth's magnetic dip equator. The equatorial anomaly is important in transequatorial propagation. Those LU stations in Argentina that you can hear on 28 MHz from the US in the late afternoon, even during low portions of the solar cycle when other stations to the south are not coming through, are benefiting from transequatorial propagation, sometimes called "chordal hop" propagation, because signals going through this area remain in the ionosphere without lossy intermediate hops to the ground.

From records of f_oF_2 profiles, the underlying electron densities along a path can be computed. And from the electron density profiles computerized "ray tracing" may be done

throughout the ionosphere to determine how a wave propagates from a transmitter to a particular receiver location. *PropLab Pro* can do complex ray tracings that explicitly include the effect of the Earth's magnetic field, even taking into effect ionospheric stormy conditions.

Oblique-Angle Ionospheric Sounding

A more elaborate form of ionospheric sounder is the *oblique ionosonde*. Unlike a vertical-incidence ionospheric sounder, which sends its signals directly overhead, an oblique sounder transmits its pulses obliquely through the ionosphere, recording echos at a receiver located some distance from the transmitter. The transmitter and distant receiver are precisely coordinated in GPS-derived time in modern oblique sounders.

Interpretation of ionograms produced by oblique sounders is considerably more difficult than for vertically incident ones. An oblique ionosonde purposely transmits over a continuous range of elevation angles simultaneously and hence cannot give explicit information about each elevation angle it launches. **Fig 23** shows a typical HF oblique-sounder ionogram for the path from Hawaii to California in March of 1973, during a period of medium-level sunspot activity. The y-axis is calibrated in time delay, in milliseconds. Longer distances involve longer time delays between the start of a transmitted pulse and the reception of the echo. The x-axis in this ionogram is the frequency, just like a vertical-incidence ionogram. Note that the frequency range for this plot extends to 32 MHz, while vertical-incidence ionograms usually don't sweep higher than about 12 MHz.

Six possible modes are shown in this ionogram: $1F_2$, $2F_2$, $3F_2$, $4F_2$ and $5F_2$. These involve multiple modes of propagation (commonly called *hops*) between the ionosphere and reflections from the Earth. For example, at an operating frequency of 14 MHz, there are three modes open during the mid-morning: $2F_2$, $3F_2$ and $4F_2$. We'll discuss multiple hops later in more detail.

The lowest mode, $1F_2$ in Fig 23, employs a single F_2 hop to cover the 3900-km long path from Hawaii to California, but it is only open on 28-MHz. (Note that 3900 km is close to the maximum possible single-hop length for the F_2 region. We'll look at this in more detail later too.) In general, each mode that involves more than a single hop is weaker than a single hop. For example, you can see that the received $5F_2$ echo is weak and broken up because of the accumulation of losses at each ground-level reflection in its five hops, with absorption in the ionosphere all along its complicated path to the receiver.

The trace labeled "FOT" is the *frequency of optimum traffic*, considered the most reliable frequency for communications on this particular circuit and date/time. In this example, the FOT would be near the 21-MHz amateur band.

Another interesting point in Fig 23 is labeled "High Angle Ray." This refers to the Pedersen ray. Before we go into more details about the Pedersen high-angle wave, we need to examine how launch angles affect the way waves are propagated through the ionosphere.

Fig 24 shows a highly simplified situation, with a single ionospheric layer and a smooth Earth. This illustrates several important facts about antenna design for long-distance communication. In Fig 24, Wave #1 is launched at the lowest elevation angle (that is, most nearly horizontal to the horizon). Wave #1 manages to travel from the transmitter to the receiving location at point C in a single hop.

Wave #2 is launched at a higher elevation angle than Wave #1, and penetrates further into the ionospheric layer before it is refracted enough to return to Earth. The ground distance covered from the transmitter to point B is less for

Fig 23—HF oblique-sounder ionogram. This is a typical chirpsounder measurement on a 2500-mile path from Hawaii to southern California during midmorning in March at a medium level of solar activity. Six possible modes (hops) are shown. The "FOT" is the frequency of optimum traffic, considered most reliable for this path/time.

Fig 24—Very simplified smooth-Earth/ionosphere diagram showing how the ground range from transmitter to receiver can vary as the elevation angle is gradually raised. The Pedersen wave, launched at a relatively high angle, has the same ground range as the low-angle wave #1, but is weaker because it travels for a long distance in the ionosphere.

Wave #2 than for lower-angle Wave #1. Wave #3 is launched at a still-higher elevation angle. Like Wave #2 before it, Wave #3 penetrates further into the ionosphere and covers less ground downrange than #2.

Now, we see something very interesting happening for Wave #4, whose launch elevation angle is still higher than #3. Wave #4 penetrates even higher into the ionosphere than #3, reaching the highest level of ionization in our theoretical ionospheric layer, where it is finally refracted sufficiently to bend down to Earth. Wave #4 manages to arrive at the same point B as Wave #2, which was launched at a much lower elevation angle.

In other words, in the sequence from #1 to #3 we have been continually *increasing* the elevation launch angle and the ground range covered from the transmitter to the return of the signal back to Earth has been continually *decreasing*. However, starting with Wave #4, the ground range starts to *increase* with increased elevation angle. A further increase in the elevation angle causes Wave #5 to travel for an even longer distance through the ionosphere, exiting finally at point C, the same ground distance as lowest-angle Wave #1.

Finally, increasing the elevation angle even further results in Wave #6 being lost to outer space because the ionization in the layer is insufficient to bend the wave back to Earth. In other words, Wave #6 has exceeded the *critical angle* for this hypothetical ionospheric layer and this frequency of operation.

Both Waves #4 and #5 in Fig 24 are called "high-angle" or Pedersen waves. Because Wave #5 has traveled a greater distance through the ionosphere, it is always weaker than Wave #1, the one launched at the lowest elevation angle. Pedersen waves are usually not very stable, since small changes in elevation angle can result in large changes in the ground range that these high-angle waves cover.

SKIP DISTANCE

Fig 24 shows that we can communicate with the point on the Earth labeled "A" (where Wave #3 arrives), but not any closer to our transmitter site. When the critical angle is less than 90° (that is, directly overhead) there will always be a region around the transmitting site where an ionospherically propagated signal cannot be heard, or is heard weakly. This area lies between the outer limit of the ground-wave range and the inner edge of energy return from the ionosphere. It is called the *skip zone*, and the distance between the originating site and the beginning of the ionospheric return is called the skip distance. This terminology should not to be confused with ham jargon such as "the skip is in," referring to the fact that a band is open for sky-wave propagation.

The signal may often be heard to some extent within the skip zone, through various forms of scattering (discussed in detail later), but it will ordinarily be marginal in strength. When the skip distance is short, both ground-wave and sky-wave signals may be received near the transmitter. In such instances the sky wave frequently is stronger than the ground wave, even as close as a few miles from the transmitter. The

ionosphere is an efficient communication medium under favorable conditions. Comparatively, the ground wave is not.

If the radio wave leaves the Earth at a radiation angle of zero degrees, just at the horizon, the maximum distance that may be reached under usual ionospheric conditions in the F_2 region is about 4000 km (2500 miles).

MULTI-HOP PROPAGATION

As mentioned previously in the discussion about Fig 24, the Earth itself can act as a reflector for radio waves, resulting a multiple hops. Thus, a radio signal can be reflected from the reception point on the Earth back into the ionosphere, reaching the Earth a second time at a still more-distant point. This effect is illustrated in **Fig 25**, where a single ionospheric layer is depicted, although this time we show both the layer and the Earth beneath it as curved rather than flat. The wave identified as "Critical Angle" travels from the transmitter via the ionosphere to point A, in the center of the drawing, where it is reflected upwards and travels through the ionosphere to point B, at the right. This shows a two-hop signal.

As in the simplified case in Fig 24, the distance at which a ray eventually reaches the Earth depends on the launch elevation angle at which it left the transmitting antenna. You have some control of the launch angle by adjusting the height of the antennas you use, as described in Chapter 3, The Effects of Ground.

The information in Fig 25 is greatly simplified. On actual communication paths the picture is complicated by many factors. One is that the transmitted energy spreads over a considerable area after it leaves the antenna. Even with an antenna array having the sharpest practical beam pattern, there is what might be described as a *cone of radiation* centered on the wave lines (rays) shown in the drawing. The reflection/refraction in the ionosphere is also highly variable, and is the cause of considerable spreading and scattering.

Fig 25—Behavior of waves encountering a simple curved ionospheric layer over a curved Earth. Rays entering the ionized region at angles above the critical angle are not bent enough to be returned to Earth, and are lost to space. Waves entering at angles below the critical angle reach the Earth at increasingly greater distances as the launch angle approaches the horizontal. The maximum distance that may normally be covered in a single hop is 4000 km. Greater distances are covered with multiple hops.

Under some conditions it is possible for as many as four or five signal hops to occur over a radio path, as illustrated by the oblique ionogram in Fig 23. But no more than two or three hops is the norm. In this way, HF communication can be conducted over thousands of miles.

An important point should be recognized with regard to signal hopping. A significant loss of signal occurs with each hop. The D and E layers of the ionosphere absorb energy from signals as they pass through, and the ionosphere tends to scatter the radio energy in various directions, rather than confining it in a tight bundle. The roughness of the Earth's surface also scatters the energy at a reflection point.

Assuming that both waves do reach point B in Fig 25, the low-angle wave will contain more energy at point B. This wave passes through the lower layers just twice, compared to the higher-angle route, which must pass through these layers four times, plus encountering an Earth reflection. Measurements indicate that although there can be great variation in the relative strengths of the two signals—the one-hop signal will generally be from 7 to 10 dB stronger. The nature of the terrain at the mid-path reflection point for the two-hop wave, the angle at which the wave is reflected from the Earth, and the condition of the ionosphere in the vicinity of all the refraction points are the primary factors in determining the signal-strength ratio.

The loss per hop becomes significant at greater distances. It is because of these losses that no more than four or five propagation hops are useful; the received signal becomes too weak to be usable over more hops. Although modes other than signal hopping also account for the propagation of radio waves over thousands of miles, backscatter studies of actual radio propagation have displayed signals with as many as five

hops. So the hopping mode is arguably the most prevalent method for long-distance communication.

Fig 26 shows another way of looking at propagation—a *geographic area* look. Fig 26 shows 15-meter signal levels across the US as they propagate from a transmitting station in San Francisco. This simulation of propagation conditions is for the month of November, with a medium level of solar activity (SSN = 50) at 22 UTC. Fig 26 was created using the *VOAAREA* software program, part of the *VOACAP* software suite. Transmitter power is assumed to be 1500 W, with 3-element Yagis, 55 feet high, at the transmitter and at each receiving location.

From the transmitter out to about 50 miles, signals are moderate, at about S5 on an S meter. Beyond that coverage area to almost $1/3$ of the way across the country (to Colorado), there is a large and distinctive skip zone, where only very weak signals return to Earth (S1 or less). Beyond Colorado, signals rapidly build up to S9+10 dB across the middle of the US, falling to S9 and then to S7 in the vicinity of Chicago, Illinois. Beyond Chicago, the signals drop to S5 in a swath from Michigan and part of Ohio down to Alabama. All along the US East Coast, signals come back strong at S9.

The reason why the signals in Fig 26 drop down to S5 in the Midwest is that the necessary elevation angles to cover this region in a single F2 hop are extremely low even at a moderate level of solar activity. To achieve launch angles as low as 1° requires either very high antenna heights or a high mountaintop location. Beyond the Midwest, out to the US East Coast, two F2 hops are required, with higher elevation angles and hence greater antenna gain for moderate antenna heights.

Non-Hopping Propagation Modes

Present propagation theory holds that for communication distances of many thousands of kilometers, signals do not always hop in relatively short increments from ionosphere-to-Earth-to-ionosphere and so forth along the entire path. Instead, the wave is thought to propagate *inside* the ionosphere throughout some portion of the path length, tending to be *ducted* in the ionized layer.

As was shown in Fig 24, the high-angle Pedersen ray can also penetrate an ionospheric layer farther than lower-angle rays. In the less-densely ionized upper edge of the layer, the amount of refraction is less, nearly equaling the curvature of the layer itself as it encircles the Earth.

Non-hopping theory of long-distance propagation is further supported by studies of travel times for signals that go completely around the world. The time required is significantly less than would be necessary to hop between the Earth and the ionosphere 10 or more times while circling the Earth.

Propagation between two points thousands of kilometers apart may in fact consist of a combination of ducting and hopping. It may involve combinations of refractions from the E layer and the F layer. Despite all the complex factors involved, most long-distance propagation can be seen to follow certain general rules. Thus, much commercial and military point-to-point communication over long distances

Fig 26—Modified *VOAAREA* plot for 21.2 MHz from San Francisco to the rest of the US, annotated with signal levels in S units, as well as signal contours in dBW (dB below a watt). Antennas are assumed to be 3-element Yagis at 55 feet above flat ground; the transmitter power is 1500 W; the month is November with SSN = 50, a moderate level of solar activity, at 22 UTC. The most obvious feature is the large "skip zone" centered on the transmitter in San Francisco, extending almost a $1/3$ of the distance across the US.

employs antennas designed to make maximum use of known radiation angles and layer heights, even on paths where multihop propagation is assumed.

In amateur work, however, we usually try for the lowest practical radiation angle, hoping to keep reflection losses to a minimum. Years of amateur experience have shown this to be a decided advantage under all usual conditions.

The geometry of propagation by means of the F_2 layer limits our maximum distance along the Earth's surface to about 4000 km (2500 miles) for a single hop. For higher radiation angles, this same distance may require two or more hops (with higher reflection loss). And fewer hops are better, in most cases. If you have a nearby neighbor who consistently outperforms you on the longer paths, a radiation angle difference in his favor is probably the reason.

MAXIMUM USABLE FREQUENCY

The vertical-incidence critical frequency is the *maximum usable frequency* for local sky-wave high-angle communication. It is also useful in the selection of optimum working frequencies and the determination of the maximum usable frequency for distant points at a given time. The abbreviation "MUF" for maximum usable frequency will be used hereafter.

In geographic middle latitudes, the vertical-incident critical frequency ranges between about 1 and 4 MHz for the E layer, and between 2 and 13 MHz for the F_2 layer. The lowest figures are for nighttime conditions in the lowest years of the solar cycle. The highest are for the daytime hours in the years of high solar activity. These are average figures. Critical frequencies have reached as high as 20 MHz briefly during exceptionally high solar activity in the middle latitudes. As was pointed out earlier in Fig 22, $f_o F_2$ levels approaching 40 MHz are possible at low latitudes.

While vertical-incidence critical frequencies are interesting from a scientific point of view, hams are far more concerned about how we can exploit propagation conditions to communicate, preferably at long distances. The MUF for a 4000-km (2500 miles) distance is about 3.5 times the vertical-incidence critical $f_o F_2$ frequency existing at the path midpoint. For one-hop signals, if a uniform ionosphere is assumed, the MUF decreases with shorter distances along the path. This is true because the higher-frequency waves must be launched at higher elevation angles for shorter ranges, and at these launch angles they are not bent sufficiently to reach the Earth. Thus, a lower frequency (where more bending occurs) must be used.

Precisely speaking, a maximum usable frequency or MUF is defined for communication between two specific points on the Earth's surface, for the conditions existing at the time, including the minimum elevation angle that the station can launch at the frequency in use. (This practical form of MUF is sometimes called the *operational MUF*). At the same time and for the same conditions, the MUF from either of these two points to a third point may be different.

Table 2
Time and Frequency Stations Useful for Propagation Monitoring

Call	Frequency (MHz)	Location
WWV	2.5, 5, 10, 15, 20	Ft Collins, Colorado
WWVH	Same as WWV but no 20	Kekaha, Kauai, Hawaii
CHU	3.330, 7.335, 14.670	Ottawa, Ontario, Canada
RID	5.004, 10.004, 15.004	Irkutsk, USSR*
RWM	4.996, 9.996, 14.996	Novosibirsk, USSR
VNG	2.5, 5, 8.634, 12.984, 16	Lyndhurst, Australia
BPM	5, 5.43, 9.351, 10, 15	Xiang, China
BSF	15	Taoyuan, Taiwan
JJY	2.5, 5, 8, 10, 15	Tokyo, Japan
LOL	5, 10, 15	Buenos Aires, Argentina

*The call, taken from an international table, may not be the one used during actual transmission. Locations and frequencies appear to be accurate as provided.

Therefore, the MUF cannot be expressed broadly as a single frequency, even for any given location at a particular time. The ionosphere is never uniform, and in fact at a given time and for a fixed distance, the MUF changes significantly with changes in compass direction for almost any point on the Earth. Under usual conditions, the MUF will always be highest in the direction toward the Sun—to the east in the morning, to the south at noon (from northern latitudes), and to the west in the afternoon and evening.

For the strongest signals at the greatest distance, especially where the limited power levels of the Amateur Radio Service are concerned, it is important to work fairly near the MUF. It is at these frequencies where signals suffer the least loss. The MUFs can be estimated with sufficient accuracy by using the prediction charts that appear on the ARRL Web site (**www.arrl.org/qst/propcharts/**) or by using a computer prediction program. The CD-ROM bundled in the back of this book contains detailed and summary tables for more than 175 transmitting locations around the world. (See section on "What HF Bands Are Open—Where and When?" later in this chapter.)

MUFs can also be observed, with the use of a continuous coverage communications receiver. Frequencies up to the MUFs are in round-the-clock use today. When you "run out of signals" while tuning upward in frequency from your favorite ham band, you have a pretty good clue as to which band is going to work well, right then. Of course, it helps to know the direction to the transmitters whose signals you are hearing. Shortwave broadcasters know what frequencies to use, and you can hear them anywhere, if conditions are good. Time-and-frequency stations are also excellent indicators, since they operate around the clock. See **Table 2**. WWV is also a reliable source of propagation data, hourly, as discussed in more detail later in this chapter.

The value of working near the MUF is two-fold. Under undisturbed conditions, the absorption loss decreases proportional to the square of a change in frequency. For example, the absorption loss is four times higher at 14 MHz than it is at 28 MHz. Perhaps more important, the hop distance is considerably greater as the MUF is approached. A transcontinental contact is thus much more likely to be made on a single hop on 28 MHz than on 14 MHz, so the higher frequency will give the stronger signal most of the time. The strong-signal reputation of the 28-MHz band is founded on this fact.

LOWEST USABLE FREQUENCY

There is also a lower limit to the range of frequencies that provide useful communication between two given points by way of the ionosphere. *Lowest usable frequency* is abbreviated LUF. If it were possible to start near the MUF and work gradually lower in frequency, the signal would decrease in strength and eventually would disappear into the ever-present "background noise." This happens because signal absorption increases proportional to the square of the lowering of the frequency. The frequency nearest the point where reception became unusable would be the LUF. It is not likely that you would want to work at the LUF, although reception could be improved if the station could increase power by a considerable amount, or if larger antennas could be used at both ends of the path.

For example, when solar activity is very high at the peak of a solar cycle, the LUF often rises higher than 14 MHz on the morning Eastern US-to-Europe path on 20 meters. Just before sunrise in the US, the 20-meter band will be first to open to Europe, followed shortly by 15 meters, and then 10 meters as the Sun rises further. By mid-morning, however, when 10 and 15 meters are both wide open, 20 meters will become very marginal to Europe, even when both sides are running maximum legal power levels. By contrast, stations on 10 meters can be worked readily with a transmitter power of only 1 or 2 watts, indicating the wide range between the LUF and the MUF.

Frequently, the *window* between the LUF and the MUF for two fixed points is very narrow, and there may be no amateur frequencies available inside the window. On occasion the LUF may be higher than the MUF between two points. This means that, for the highest possible frequency that will propagate through the ionosphere for that path, the absorption is so great as to make even that frequency unusable. Under these conditions it is impossible to establish amateur sky-wave communication between those two points, no matter what frequency is used. (It would normally be possible, however, to communicate between either point and other points on some frequency under the existing conditions.) Conditions when amateur sky-wave communication is impossible between two fixed points occur commonly for long distances where the total path is in darkness, and for very great distances in the daytime during periods of low solar activity.

Fig 27 shows a typical propagation prediction from

Fig 27—Propagation prediction chart for East Coast of US to Europe. This appeared in December 1994 *QST*, where an average 2800-MHz (10.7-cm) solar flux of 83 was assumed for the mid-December to mid-January period. On 10% of these days, the highest frequency propagated was predicted at least as high as the uppermost curve (the Highest Possible Frequency, or HPF, approximately 21 MHz), and for 50% of the days as high as the middle curve, the MUF. The broken lines show the Lowest Usable Frequency (LUF) for a 1500-W CW transmitter.

the ARRLWeb members-only site (**www.arrl.org/qst/propcharts/**, previously from the "How's DX" column in *QST*). In this instance, the MUF and the LUF lines are blurred together at about 10 UTC, meaning that the statistical likelihood of any amateur frequency being open for that particular path at that particular time was not very good. Later on, after about 11 UTC, the gap between the MUF and LUF increased, indicating that the higher bands would be open on that path.

DISTURBED IONOSPHERIC CONDITIONS

So far, we have discussed the Earth's ionosphere when conditions at the Sun are undisturbed. There are three general types of major disturbances on the Sun that can affect radio propagation here on the Earth. On the air, you may hear people grousing about *Solar Flares*, *Coronal Holes* or *Sudden Disappearing Filaments*, especially when propagation conditions are not good. Each of these disturbances causes both electromagnetic radiation and ejection of material from the Sun.

Solar Flares

Solar flares are cataclysmic eruptions that suddenly release huge amounts of energy, including sustained, high-energy bursts of radiation from VLF to X-ray frequencies and vast amounts of solar material. Most solar flares occur around the peak of the 11-year solar cycle.

The first Earthly indication of a huge flare is often a visible brightness near a sunspot group, along with increases in UV, X-ray radiation and VHF radio noise. If the geometry between the Sun and Earth is right, intense X-ray radiation takes eight minutes, traveling the 93 million miles to Earth at the speed of light. The sudden increase in X-ray

energy can immediately increase RF absorption in the Earth's lowest ionospheric layers, causing a phenomenon known as a *Sudden Ionospheric Disturbance* (SID).

An SID affects all HF communications on the sunlit side of the Earth. Signals in the 2 to 30-MHz range may disappear entirely, and even most background noise may cease in extreme cases. When you experience a big SID, your first inclination may be to look outside to see if your antenna fell down! SIDs may last up to an hour before ionospheric conditions temporarily return to normal.

Between 45 minutes and 2 hours after an SID begins, particles from the mass eruption on the Sun may begin to arrive. These high-energy particles are mainly protons and they can penetrate the ionosphere at the Earth's magnetic poles, where intense ionization can occur, with attendant absorption of HF signals propagating through the polar regions. This is called a *Polar Cap Absorption* (PCA) event and it may last for several days. A PCA results in spectacular auroral displays at high latitudes.

Coronal Holes

As described earlier in the section dealing with auroral propagation at VHF, a second major solar disturbance is a so-called "coronal hole" in the Sun's outer layer (the *corona*). Temperatures in the corona can be more than four million °C over an active sunspot region but more typically are about two million °C. A coronal hole is an area of somewhat lower temperature. Solar-terrestrial scientists have a number of competing theories about how coronal holes are formed.

Matter ejected through this "hole" takes the form of a *plasma*, a highly ionized gas made up of electrons, protons and neutral particles, traveling at speeds up to 1,000 km per second (2 million miles per hour). The plasma becomes part of the solar wind and can affect the Earth's magnetic field, but only if the Sun-Earth geometry is right. A plasma has a very interesting and somewhat bizarre ability. It can lock-in the orientation of the magnetic field where it originates and carry it outwards into space. However, unless the locked-in magnetic field orientation is aligned properly with the Earth's magnetic field, even a large plasma mass may not severely disrupt our magnetosphere, and thence our ionosphere.

Presently, we don't have the ability to predict very long in advance when the Sun might erupt in a disturbance that results in Earthly propagation problems. The SOHO satellite can help determine whether a mass ejection is heading towards Earth, and the ACE satellite about 1 million miles away from Earth can give about an hour's warning whether the imbedded magnetic field in a mass ejection from the Sun might impact the Earth's magnetosphere, causing propagation problems for hams.

Statistically, coronal holes tend to occur most often during the declining phase of the 11-year solar cycle and they can last for a number of solar rotations. This means that a coronal hole can be a "recurring coronal hole," disrupting communications for several days about the same time each month for as long as a year, or even more.

Sudden Disappearing Filaments

A sudden disappearing filament (SDF) is the third major category of solar disturbance that can affect propagation. SDFs take their names from the manner in which they suddenly arch upward from the Sun's surface, spewing huge amounts of matter as plasma out into space in the solar wind. They tend to occur mostly during the rising phase of the 11-year solar cycle.

IONOSPHERIC STORMS

When the conditions are right, a flare, coronal hole or an SDF can launch a plasma cloud into the solar wind, resulting in an *ionospheric storm* here on Earth. Unlike a hurricane or a winter Nor'easter storm in New England, an ionospheric storm is not something we can see with our eyes or feel on our skins. We can't easily measure things occurring in the ionosphere some 200 miles overhead. However, we can see the indirect effects of an ionospheric storm on magnetic instruments located on the Earth's surface, because disturbances in the ionosphere are closely related to the Earth's magnetic field. The term *Geomagnetic Storm* ("Geo" means "Earth" in Greek) is used almost synonymously with ionospheric storm.

During a ionospheric storm, we may experience extraordinary radio noise and interference, especially at HF. You may hear solar radio emissions as increases of noise at VHF. A geomagnetic storm generally adds noise and weakens or disrupts ionospheric propagation for several days. Transpolar signals at 14 MHz or higher may be particularly weak, with a peculiar hollow sound or flutter—even more than normal for transpolar signals.

Depending on the severity of the disturbance to the Earth's geomagnetic field and the consequent disturbance of the ionosphere, propagation may be disrupted completely or it might be at least degraded for a period of time that ranges from a day to three or four days before returning to normal propagation conditions.

What can we do about the solar disturbances and related disturbed ionospheric propagation on Earth? The truth is that we are powerless faced with the truly awesome forces of solar disturbances like flares, coronal holes or sudden disappearing filaments. Perhaps there is some comfort, however, in understanding what has happened to cause our HF bands to be so poor. And as a definite consolation, conditions on the VHF bands are often exceptionally good just when HF propagation is remarkably poor due to solar disturbances. VHF operators enthusiastically look forward to conditions when they can engage in auroral communications—exactly the kind of conditions that have HF operators scratching their heads, wondering where the ionosphere went.

ELEVATION ANGLES FOR HF COMMUNICATION

It was shown in connection with Fig 25 that the distance at which a ray returns to Earth depends on the eleva-

Fig 28—Distance plotted against wave angle (one-hop transmission) for the nominal range of heights for the E and F2 layers, and for the F1 layer.

tion angle at which it left the Earth (also known by other names: takeoff, launch or wave angle). Chapter 3, The Effects of Ground, in this book deals with the effects of local terrain, describing how the elevation angle of a horizontally polarized antenna is determined mainly by its height above the ground.

Although it is not shown specifically in Fig 25, propagation distance also depends on the layer height at the time, as well as the elevation angle. As you can probably imagine, the layer height is a very complex function of the state of the ionosphere and the Earth's geomagnetic field. There is a large difference in the distance covered in a single hop, depending on the height of the E or the F_2 layer. The maximum single-hop distance by the E layer is about 2000 km (1250 miles) or about half the maximum distance via the F_2 layer. Practical communicating distances for single-hop E or F layer work at various wave angles are shown in graphic form in **Fig 28**.

Actual communication experience usually does not fit the simple patterns shown in Fig 25. Propagation by means of the ionosphere is an enormously complicated business (which makes it all the more intriguing and challenging to radio amateurs, of course), even when the Sun is not in a disturbed state. Until the appearance of sophisticated computer models of the ionosphere, there was little definitive information available to guide the radio amateur in the

design of his antenna systems for optimal performance over all portions of the 11-year solar cycle. Elevation angle information that had appeared for many years in *The ARRL Antenna Book* was measured for only one transmitting path, during the lowest portion of Solar Cycle 17 in 1934.

The *IONCAP* Computer Propagation Model

Since the 1960s several agencies of the US government have been working on a detailed computer program that models the complex workings of the ionosphere. The program has been dubbed *IONCAP*, short for "Ionospheric Communications Analysis and Prediction Program." *IONCAP* was originally written for a mainframe computer, but later versions have been rewritten to allow them to be run by high-performance personal computers. *IONCAP* incorporates a detailed database covering almost three complete solar cycles. The program allows the operator to specify a wide range of parameters, including detailed antenna models for multiple frequency ranges, noise models tailored to specific local environments (from low-noise rural to noisy residential QTHs), minimum elevation angles suitable for a particular location and antenna system, different months and UTC times, maximum levels of multipath distortion, and finally solar activity levels, to name the most significant of a bewildering array of options.

While *IONCAP* has a well-justified reputation for being very *unfriendly* to use, due to its mainframe, non-interactive background, it is also the one ionospheric model most highly regarded for its accuracy and flexibility, both by amateurs and professionals alike. It is the program used for many years to produce the long-term MUF charts formerly included in the "How's DX" monthly column of *QST* and now available on the Members Only ARRLWeb page.

IONCAP is not well suited for short-term forecasts of propagation conditions based on the latest solar indices received from WWV. It is an excellent tool, however, for long-range, detailed planning of antenna systems and short-wave transmitter installations, such as that for the Voice of America, or for radio amateurs. See the section later in this chapter describing other computer programs that can be used for short-term, interactive propagation predictions.

IONCAP/VOACAP Parameters

The elevation-angle statistical information contained in this section was compiled from thousands of *VOACAP* runs (an improved version of *IONCAP* developed by scientists from VOA, the Voice of America). These runs were done for a number of different transmitting locations throughout the world to important DX locations throughout the world.

Some assumptions were needed for setting *VOACAP* parameters. The transmitting and receiving sites were all assumed to be located on flat ground, with "average" ground conductivity and dielectric constant. Each site was assumed to have a clear shot to the horizon, with a minimum elevation angle less than or equal to 1°. Electrical noise at each

Table 3

Boston, Massachusetts, to All of Europe

Elev	80 m	40 m	30 m	20 m	17 m	15 m	12 m	10 m
1	4.1	9.6	4.6	1.7	2.1	4.4	5.5	7.2
2	0.8	2.3	7.2	1.4	2.8	2.8	3.7	5.3
3	0.3	0.7	4.3	3.1	2.4	2.2	4.4	7.9
4	0.5	4.1	8.7	11.6	12.2	9.4	8.1	3.9
5	4.6	4.8	7.5	12.7	14.3	13.1	9.2	11.2
6	7.1	8.9	5.5	9.2	9.6	12.2	9.2	7.2
7	8.5	6.9	7.2	4.6	7.9	7.4	10.0	5.9
8	5.1	7.0	5.4	3.2	5.9	7.4	4.8	6.6
9	3.3	5.6	3.2	3.1	2.1	3.9	8.1	9.2
10	1.0	4.0	7.9	6.3	5.1	3.7	11.1	6.6
11	1.9	3.8	9.7	10.2	7.2	5.4	3.7	7.9
12	5.6	3.4	4.8	8.5	6.9	7.4	4.8	6.6
13	11.0	3.0	2.4	4.1	5.9	4.6	3.3	2.6
14	7.6	4.8	2.0	2.7	3.8	3.9	6.3	5.9
15	5.3	7.9	2.0	1.5	2.4	1.7	1.5	2.0
16	2.8	6.4	3.8	2.9	1.5	1.3	2.6	2.6
17	5.0	3.4	4.5	3.1	1.0	1.5	0.0	0.0
18	4.2	2.0	3.1	3.1	2.0	2.2	1.8	1.3
19	5.7	1.4	1.4	2.3	1.3	0.7	0.0	0.0
20	6.6	1.4	1.2	1.8	1.1	1.3	0.7	0.0
21	4.4	1.4	0.5	0.8	0.7	0.7	0.4	0.0
22	2.3	2.4	1.0	1.1	0.6	1.3	0.7	0.0
23	1.3	1.8	0.1	0.3	0.1	0.0	0.0	0.0
24	0.6	1.0	0.5	0.5	0.4	0.7	0.0	0.0
25	0.3	0.8	0.3	0.1	0.4	0.0	0.0	0.0
26	0.0	0.5	0.7	0.2	0.1	0.4	0.0	0.0
27	0.1	0.1	0.1	0.2	0.1	0.2	0.0	0.0
28	0.0	0.3	0.1	0.2	0.0	0.2	0.0	0.0
29	0.1	0.0	0.2	0.0	0.0	0.0	0.0	0.0
30	0.0	0.1	0.0	0.0	0.0	0.0	0.0	0.0
31	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0
32	0.0	0.0	0.1	0.0	0.0	0.0	0.0	0.0
33	0.1	0.0	0.0	0.0	0.0	0.0	0.0	0.0
34	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0
35	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0

Percentage of time a particular frequency band is open on this specific propagation path.

Percentage of Time 40 Meters is Open, At or Below Each Elevation Angle
Boston to World

Europe ———
So. America —— — ——
Africa —·—·—·—·
Japan — — — — —
Oceana ·············
So. Asia ——·——·——

receiving location was also assumed to be very low.

Transmitting and receiving antennas for the 3.5 to 30-MHz frequency range were specified to be isotropic-type antennas, but with +6 dBi gain, representing a good amateur antenna on each frequency band. These theoretical antennas radiate uniformly from the horizon, up to 90° directly overhead. With response patterns like this, these are obviously not real-world antennas. They do, however, allow the computer program to explore all possible modes and elevation angles.

Looking at the Elevation-Angle Statistical Data

Table 3 shows detailed statistical elevation informa-

Fig 29—The cumulative distribution function showing the total percentage of time that 40 meters is open, at or below each elevation angle, from Boston to the world. For example, 50% of the time the band is open to Europe from Boston, it is at 10° or less. The angles for DX work are indeed low.

Percentage of Time 80 Meters is Open, At or Below Each Elevation Angle
Boston to World

Europe	Japan
So. America	Oceania
Africa	So. Asia

Fig 30—The cumulative distribution function showing the total percentage of time that 80 meters is open, at or below each elevation angle, from Boston to the world. For example, 50% of the time the band is open to Europe from Boston, it is at 13° or less.

Fig 31—Overlay of signals and elevation angles, together with hop-mode information. This is for one month, October, at one level of solar activity, SSN=70, for the path from Newington, CT, to London, England. The mode of propagation does not closely follow the elevation angle. From 15 to 19 UTC the mode is 3F2 hops, and the elevation angle is approximately 12°. The same elevation angle is required from 23 to 03 UTC, but here the mode is 2F2 hops.

tion for the path from Boston, Massachusetts, near ARRL HQ in Newington, Connecticut, to all of Europe. The data incorporated into Table 3 shows the percentage of time versus elevation angle for all HF bands from 80 meters to 10 meters, over all portions of the 11-year solar cycle. The CD-ROM accompanying this book contains more tables such as this for more than 150 transmitting sites around the world. These tables are used by the *HFTA* program (and earlier *YT* program) and can also be imported into many programs, such as word processors or spreadsheets. Six important areas throughout the world are covered, one per table: all of Europe (from London, England, to Kiev, Ukraine), the Far East (centered on Japan), South America (Paraguay), Oceania (Melbourne, Australia), Southern Africa (Zambia) and South Asia (New Delhi, India).

You may be surprised to see in Table 3 that angles lower than 10° dominate the possible range of incoming angles for this moderate-distance path from New England to Europe. In fact, 1.7% of all the times when the 20-meter band is open to Europe, the takeoff angle is as low as 1°. You should recognize that very few real-world 20-meter antennas achieve much gain at such an extremely low angle—unless they just happen to be mounted about 400 feet high over flat ground or else are located on the top of a tall, steep mountain.

The situation is even more dramatic on 40 and 80 meters. **Fig 29** shows the "cumulative distribution function" of the total percentage of time (derived from Table 3) when 40 meters is open from Boston to the rest of the world, plotted against the elevation angle. For example, into Europe from Boston, 50% of the time when the band is open, it is at 10° or less. Into Japan from Boston, the statistics are even more revealing: 50% of the time when the band is open,

the angle is 6° or less, and 90% of the time the angle is 13° or less!

Fig 30 shows the same sort of information for 80 meters from Boston to the world. For 50% of the time from Boston to Europe the elevation angle is 13° or less; at the 90% level the angle is 20° or less. For the path to Japan on 80 meters from Boston, 50% of the time the angle is 8° or less; at the 90% level, the angle is 13° or less. Now, to achieve peak gain on 80 meters at an elevation angle of 8° over flat land, a horizontally polarized antenna must be 500 feet high. You can begin to see why verticals can do very well on long-distance contacts on 80 meters, even when they are mounted over poorly conducting, rocky ground. Clearly, low angles are very important for successful DXing.

The Ionosphere Controls Propagation

You should always remember that it is the *ionosphere* that controls the elevation angles, *not* the transmitting antenna. The elevation response of a particular antenna only determines how strong or weak a signal is, at whatever angle (or angles) the ionosphere is supporting at that particular instant, for that propagation path and for that frequency.

If only one propagation mode is possible at a particular time, and if the elevation angle for that one mode happens to be 5°, then your antenna will have to work satisfactorily at that very low angle or else you won't be able to communicate. For example, if your low dipole has a gain of −10 dBi at 5°, compared to your friend's Yagi on a mountain top with +10 dBi gain at 5°, then you will be down 20 dB compared to his signal. It's not that the elevation angle is somehow *too low*—the real problem here is that you don't have *enough gain* at that particular angle where the ionosphere is supporting propagation. Many "flatlanders" can

vividly recall the times when their mountain-top friends could easily work DX stations, while they couldn't even hear a whisper.

Looking at the Data—Further Cautions

A single propagation mode is quite common at the opening and the closing of daytime bands like 20, 15 or 10 meters, when the elevation angle is often lower (but not always) than when the band is wide open. The lower-frequency bands tend to support multiple propagation modes simultaneously. For example, **Fig 31** plots the signal strength (in dBμV) and the elevation angle for the dominant mode (with the strongest signal) over a 24-hour period from Newington to London in October, for a medium-level SSN = 70. The morning opening at 10 UTC starts out with a two-hop $2F_2$ mode (labeled 2F) at an elevation angle of 6°. By 11 UTC the mode has changed to a three-hop $3F_2$ (labeled 3F) at a 12° elevation angle. The band starts to close down with weaker signals after about 23 UTC. Note that this path actually supports both $2F_2$ and $3F_2$ modes most of the time. Either mode may be stronger than the other, depending on the particular time of day.

It is tempting to think that two-hop signals always occur at lower elevation launch angles, while three-hop signals require higher elevation angles. In reality, the detailed workings of the ionosphere are enormously complicated. From 22 UTC to 03 UTC, the elevation angles are higher than 11° for $2F_2$ hops. During much of the morning and early afternoon in Newington (from 11 to 13 UTC, and from 15 to 19 UTC), the angles are also higher than 11°. However, $3F_2$ hops are involved during these periods of time. The number of hops is not directly related to the elevation angles needed—changing layer heights account for this.

Note that starting around 15 UTC, the mid-morning 20-meter "slump" (down some 10 dB from peak signal level) is caused by higher levels of mainly E-layer absorption when the Sun is high overhead. This condition favors higher elevation angles, since signals launched at lower angles must travel for a longer time through the lossy lower layer.

How does the situation change with different levels of solar activity? **Fig 32** overlays predicted signals and elevation angles for three levels of solar activity in October, again for the Newington-London path. Fig 32 shows the mid-morning slump dramatically when the solar activity is at

Fig 33—10-meter graph of the percentage of all openings versus elevation angles, together with overlay of elevation patterns over flat ground for three 10-meter antenna systems. Stacked antennas have wider "footprints" in elevation angle coverage for this example from New England to Europe.

Fig 32—October 20-meter signals and elevation angles for the full range of solar activity, from W1 to England. The elevation angle does not closely follow the level of solar activity. What is important in designing a station capable of covering all levels of solar activity is to have flexibility in antenna elevation pattern response — to cover a wide range of possible angles.

Fig 34—15-meter graph of the percentage of all openings versus elevation angles, together with overlay of elevation patterns over flat ground for two 15-meter antenna systems. Like 10 meters, 15-meter stacked antennas have wider footprints in elevation angle coverage for this example from New England to Europe.

20 m, W1 to Europe
% of Openings, All SSN, Months

Fig 35—20-meter graph of the percentage of all openings from New England to Europe versus elevation angles, together with overlay of elevation patterns over flat ground for three 20-meter antenna systems.

40 m, W1 to Europe
% of Openings, All SSN, Months

Fig 36—40-meter graph of the percentage of all openings from New England to Europe versus elevation angles, together with overlays of elevation patterns over flat ground for a 100-foot high dipole and a large 4-element Yagi at 160 feet. Achieving gain at very low elevation angles requires very high heights above ground.

80 m, W1 to Europe
% of Openings, All SSN, Months

Fig 37—80-meter graph of the percentage of all openings from New England to Europe versus elevation angles, together with overlay of elevation patterns over flat ground for dipoles at two different heights. The 200-foot-high dipole clearly covers the necessary elevation angles better than does the 100-foot-high dipole, although a Four Square vertical array located over saltwater is even better for all angles needed.

a very high level, represented by SSN = 160. At 15 UTC, the signal level drops 35 dB from peak level, and the elevation angle rises all the way to 24°. By the way, as a percentage of all possible openings, the 24° angle occurs only rarely, 0.5% of the time. It barely shows up as a blip in Table 3. Elevation angles are *not* closely related to the level of solar activity.

IONCAP/VOACAP demonstrates that elevation angles do not follow neat, easily identified patterns, even over a 24-hour period—much less over all portions of the solar cycle. Merely looking at the percentage of all openings versus elevation angle, as shown in Table 3, does not tell the whole story, although it is probably the most statistically valid approach to station design, and possibly the most emotionally satisfying approach too. Neither is the whole story revealed by looking only at a snapshot of elevation angles versus time for one particular month, or for one solar activity level.

What is important to recognize is that the most effective antenna system will be one that can cover the *full range* of elevation angles, over the whole spectrum of solar activity, even if the actual angle in use at any one moment in time may not be easy to determine. For this particular path, from New England to all of Europe, an ideal antenna would have equal response over the full range of angles from 1° to 28°. Unfortunately, real-world antennas have a tough time covering such a wide range of elevation angles equally well.

Antenna Elevation Patterns

Figs 33 through **37** show overlays of the same sort of elevation angle information listed in Table 3, together with the elevation response patterns for typical antennas for the HF amateur bands 80, 40, 20, 15 and 10 meters. For example, Fig 34 shows an overlay for 20 meters, with three different types of 20-meter antennas. These are a 4-element Yagi at 90 feet, a 4-element Yagi at 120 feet and a large stack of four 4-element Yagis located at 120, 90, 60 and 30 feet. Each antenna is assumed to be mounted over flat ground. Placement on a hill with a long slope in the direction of interest would lower the required elevation angle by the amount of the hill's slope. For example, if a 10° launch angle is desired, and the antenna is placed on a hill with a slope of –5°, the antenna itself should be designed for a height that would optimize the response at 15° over flat ground—one wavelength high.

In Fig 35, the large stack of four 20-meter Yagis over flat ground comes closest to being ideal, but even this large array will not work well for that very small percentage of time when the angle needed is higher than about 20°. Some hams might conclude that the tiny percentage of time when the angles are very high doesn't justify an antenna tailored for that response. However, when that new DX country pops up on a band, or when a rare multiplier shows up in a contest, doesn't it always seem that the desired signal only comes in at some angle your antenna doesn't cover well? What do you do then, if your only antenna happens to be a large stack?

The answer to this, perhaps unique, high-angle problem lies in switching to using only the top antenna in the stack. In this example, the second elevation lobe of the 120-foot high antenna would cover the angles from 20° to 30° well, much better than the stack does. Note that the top antenna by itself would not be ideal for all conditions. It is simply too high much of the time when the elevation angles are higher than about 12°. The experience of many amateurs on the US East Coast with high 20-meter antennas bears this out—they find that 60 to 90-foot high antennas are far more consistent performers into Europe.

ONE-WAY PROPAGATION

On occasion a signal may be started on the way back toward the Earth by reflection from the F region, only to come down onto the top of the E region and be reflected back up again. This set of conditions is one possible explanation for the often-reported phenomenon called *one-way skip*. The reverse path may not necessarily have the same multilayer characteristic. The effect is more often a difference in the signal strengths, rather than a complete lack of signal in one direction, and many times there may be local noises that mask signals at one end of the path. It is important to remember these sorts of possibilities when a long-distance test with a new antenna system yields apparently conflicting results. Even many tests, on paths of different lengths and headings, may provide data that are difficult to understand. Communication by way of the ionosphere is not always a source of consistent answers to antenna questions.

Fig 37 shows the 80-meter path from New England to Europe with three different antennas. A really high dipole at a height of 200 feet above flat ground would certainly be an impressive antenna. But it would still be overshadowed dramatically by a Four-Square vertical array, at least at the low elevation angles needed often on this path. This is predicated on the Four Square being located over salt water, which provides a virtually perfect RF ground. At an elevation angle of 7°, the Four Square has 7 dB more gain than the 200-foot high dipole.

SHORT OR LONG PATH?

Propagation between any two points on the Earth's surface is usually by the shortest direct route—the *great-circle path* found by stretching a string tightly between the two points on a globe. If an elastic band going completely around the globe in a straight line is substituted for the string, it will show another great-circle path, going "the long way around." The long path may serve for communication over the desired circuit when conditions are favorable along the longer route. There may be times when communication is possible over the long path but not possible at all over the short path. Especially if there is knowledge of this potential at both ends of the circuit, long-path communication may work very well. Cooperation is almost essential, because both the aiming of directional antennas and the timing of the attempts must be right for any worthwhile result. The *IONCAP/VOACAP* computations in the preceding tables were made for short-path azimuths only.

Sunlight is a required element in long-haul communication via the F layer above about 10 MHz. This fact tends to define long-path timing and antenna aiming. Both are essentially the reverse of the "normal" for a given circuit. We know also that salt-water paths work better than over-land ones. This can be significant in long-path work.

We can better understand several aspects of long-path propagation if you become accustomed to thinking of the Earth as a ball. This is easy if you use a globe frequently. A

Fig 38—K5ZI's computer-generated azimuthal-equidistant projection centered on Newington, Connecticut. (See Bibliography for ordering information.) Land masses and information showing long paths to Perth and Tokyo have been added. Notice that the paths in both cases lie almost entirely over water, rather than over land masses.

flat map of the world, of the azimuthal-equidistant projection type, is a useful substitute. The ARRL World Map is one, centered on Wichita, Kansas. A similar world map prepared by K5ZI and centered on Newington, Connecticut, is shown in **Fig 38**. These help to clarify paths involving those areas of the world.

Long-Path Examples

There are numerous long-path routes well known to DX-minded amateurs. Two long paths that work frequently and well when 28 MHz is open from the northeastern US are New England to Perth, Western Australia, and New England to Tokyo. Although they represent different beam headings and distances, they share some favorable conditions. By the long path, Perth is close to halfway around the world; Tokyo is about three-quarters of the way. On 28 MHz, both areas come through in the early daylight hours, Eastern Time, but not necessarily on the same days. Both paths are at their best around the equinoxes. (The sunlight is more uniformly distributed over transequatorial paths at these times.) Probably the factor that most favors both is the nature of the first part of the trip at the US end. To work Perth by way of long path, northeastern US antennas are aimed southeast, out over salt water for thousands of miles—the best low-loss start a signal could have. It is salt water essentially all the way, and the distance, about 13,000 miles, is not too much greater than the "short" path.

The long path to Japan is more toward the south, but still with no major land mass at the early reflection points. It is much longer, however, than that to Western Australia. Japanese signals are more limited in number on the long path than on the short, and signals on the average somewhat weaker, probably because of the greater distance.

On the short path, an amateur in the Perth area is looking at the worst conditions—away from the ocean, and out across the huge land mass of North America, unlikely to provide strong ground reflections. The short paths to both Japan and Western Australia, from most of the eastern half of North America, are hardly favorable. The first hop comes down in various western areas likely to be desert or mountains, or both, and not favored as reflection points.

A word of caution: Don't count on the long-path signals always coming in on the same beam heading. There can be notable differences in the line of propagation via the ionosphere on even relatively short distances. There can be more variations on long path, especially on circuits close to halfway around the world. Remember, for a point exactly halfway around, all directions of the compass represent great-circle paths.

FADING

When all the variable factors in long-distance HF communication are taken in account, it is not surprising that signals vary in strength during almost every contact beyond the local range. In VHF communication we can also encounter some fading at distances greater than just to the visible horizon. These are mainly the result of changes in the temperature and moisture content of the air in the first few thousand feet above the ground.

On paths covered by HF ionospheric modes, the causes of fading are very complex—constantly changing layer height and density, random polarization shift, portions of the signal arriving out of phase, and so on. The energy arriving at the receiving antenna has components that have been acted upon differently by the ionosphere. Often the fading is very different for small changes in frequency. With a signal of a wideband nature, such as high-quality FM, or even double-sideband AM, the sidebands may have different fading rates from each other, or from the carrier. This causes severe distortion, resulting in what is termed *selective fading*. The effects are greatly reduced (but still present to some extent) when single-sideband (SSB) is used. Some immunity from fading during reception (but not to the distortion induced by selective fading) can be had by using two or more receivers on separate antennas, preferably with different polarizations, and combining the receiver outputs in what is known as a *diversity* receiving system.

OTHER PROPAGATION MODES

In propagation literature there is a tendency to treat the various propagation modes as if they were separate and distinct phenomena. This they may be at times, but often there is a shifting from one to another, or a mixture of two or more kinds of propagation affecting communication at one time. In the upper part of the usual frequency range for F-region work, for example, there may be enough tropospheric bending at one end (or both ends) to have an appreciable effect on the usable path length. There is the frequent combination of E and F-region propagation in long-distance work. And in the case of the E region, there are various causes of ionization that have very different effects on communication. Finally, there are weak-signal variations of both tropospheric and ionospheric modes, lumped under the term "scatter." We look at these phenomena separately here, but in practice we have to deal with them in combination, more often than not.

Sporadic E (E$_s$)

First, note that this is *E-subscript-s*, a usefully descriptive term, wrongly written "Es" so often that it is sometimes called "ease," which is certainly not descriptive. *Sporadic E* is ionization at E-layer height, but of different origin and communication potential from the E layer that affects mainly our lower amateur frequencies.

The formative mechanism for sporadic E is believed to be wind shear. This explains ambient ionization being distributed and compressed into a ledge of high density, without the need for production of extra ionization. Neutral winds of high velocity, flowing in opposite directions at slightly different altitudes, produce shears. In the presence of the Earth's magnetic field, the ions are collected at a particular altitude, forming a thin, overdense layer. Data from rockets entering E$_s$ regions confirm the electron density, wind velocities and height parameters.

The ionization is formed in clouds of high density, lasting only a few hours at a time and distributed randomly. They vary in density and, in the middle latitudes in the Northern Hemisphere, move rapidly from southeast to northwest. Although E_s can develop at any time, it is most prevalent in the Northern Hemisphere between May and August, with a minor season about half as long beginning in December (the summer and winter solstices). The seasons and distribution in the Southern Hemisphere are not so well known. Australia and New Zealand seem to have conditions much like those in the US, but with the length of the seasons reversed, of course. Much of what is known about E_s came as the result of amateur pioneering in the VHF range.

Correlation of E_s openings with observed natural phenomena, including sunspot activity, is not readily apparent, although there is a meteorological tie-in with high-altitude winds. There is also a form of E_s, mainly in the northern part of the north temperate zone, that is associated with auroral phenomena.

At the peak of the long E_s season, most commonly in late June and early July, ionization becomes extremely dense and widespread. This extends the usable range from the more common "single-hop" maximum of about 1400 miles to "double-hop" distances, mostly 1400 to 2500 miles. With 50-MHz techniques and interest improving in recent years, it has been shown that distances considerably beyond 2500 miles can be covered. There is also an E_s "link-up" possibility with other modes, believed to be involved in some 50-MHz work between antipodal points, or even long-path communication beyond 12,500 miles.

When E_s is particularly strong and widespread, even the HF bands can suddenly go *short skip* producing exceptionally strong signals from distances that would normally be in the no-signal "skip zone." Editor N6BV distinctly remembers a spectacular 20-meter E_s opening in September 1994, during the "Hiram Percy Maxim/125" anniversary celebration, when he was living in New Hampshire. Signals on 20 meters were 30 to 40 dB over S9 from all along the Eastern Seaboard, from W2 to W4. One exasperated W3 complained that he had been calling in the huge pileup for 20 minutes. N6BV glanced at the S meter and saw that the W3 was 20 dB over S9, normally a very strong 20-meter SSB signal, but not when almost everybody else was 40 dB over S9!

Such short-skip conditions caused by Sporadic E are more common on 10 meters than they are on 15 or 20 meters. They can result in excellent transAtlantic 10-meter openings during the summer months—when 10 meters is not normally open for F_2 ionospheric propagation.

The MUF for E_s is not known precisely. It was long thought to be around 100 MHz, but in the last 25 years or so there have been thousands of 144-MHz contacts during the summer E_s season. Presumably, the possibility also exists at 222 MHz. The skip distance at 144 MHz does average much longer than at 50 MHz, and the openings are usually brief and extremely variable.

Fig 39—Schematic of a simple backscatter path. Stations A and B are too close to make contact via normal F-layer ionospheric refraction. Signals scattered back from a distant point on the Earth's surface (S), often the ocean, may be accessible to both A and B to create a backscatter circuit. (*Courtesy of The ARRL Handbook*.)

The terms "single" and "double" hop may not be accurate technically, since it is likely that cloud-to-cloud paths are involved. There may also be "no-hop" E_s. At times the very high ionization density produces critical frequencies up to the 50-MHz region, with no skip distance at all. It is often said that the E_s mode is a great equalizer. With the reflecting region practically overhead, even a simple dipole close to the ground may do as well over a few hundred miles as a large stacked antenna array designed for low-angle radiation. It's a great mode for low power and simple antennas on 28 and 50 MHz.

HF Scatter Modes

The term "skip zone" (where no signals are heard) should not be taken too literally. Two stations communicating over a single ionospheric hop can be heard to some degree by other stations at almost any point along the way, unless the two are running low power and using simple antennas. Some of the wave energy is *scattered* in all directions, including back to the starting point and farther.

Backscatter functions like a sort of HF ionospheric radar. **Fig 39** shows a schematic for a simple backscatter path. The signal launched from point A travels through the ionosphere back to earth at Point S, the scattering point. Here, the rough terrain of the land scatters signals in many directions, one of which propagates a weak signal back through the ionosphere to land at point B. Point B would normally be in the no-signal skip zone between A and S. Because backscatter signals arrive from multiple directions, through various paths through the ionosphere, they have a characteristic "hollow" sound, much like you get when you talk into a paper tube with its many internal reflections.

Because backscatter involves mainly scattering from the Earth at the point where the strong ionospherically propagated signal comes down, it is a part of HF over-the-horizon radar techniques. (The infamous 1970s-era "woodpecker" was an over-the-horizon HF radar.) Amateurs using sounding techniques have shown that you can tell to what part of the world a band is usable (single-hop F) by probing

the backscatter with a directive antenna and high transmitter power, even when the Earth contact point is open ocean. In fact, that's where the mode is at its best, because ocean waves can be efficient backscatter reflectors.

Backscatter is very useful on 28 MHz, particularly when that band seems dead simply because nobody is active in the right places. The mode keeps the 10-meter band lively in the low years of the solar cycle, thanks to the never-say-die attitude of some users. The mode is also an invaluable tool of 50-MHz DX aspirants, in the high years of the sunspot cycle, for the same reasons. On a high-MUF morning, hundreds of 6-meter beams may zero in on a hot spot somewhere in the Caribbean or South Atlantic, where there is no land, let alone other 6-meter stations—keeping in contact while they wait for the band to open to a place where there is somebody.

Sidescatter is similar to backscatter, except the ground scatter zone is off the direct line between participants. A typical example, often observed during the lowest years of the solar cycle, is communication on 28 MHz between the eastern US (and adjacent areas of Canada) and much of the European continent. Often, this may start as "backscatter chatter" between Europeans whose antennas are turned toward the Azores. Then suddenly the North Americans join the fun, perhaps for only a few minutes, but sometimes much longer, with beams also pointed toward the Azores. Duration of the game can be extended, at times, by careful reorientation of antennas at both ends, as with backscatter. The secret, of course, is to keep hitting the highest-MUF area of the ionosphere and the most favorable ground-reflection points.

The favorable route is usually, but not always, south of the great-circle heading (for stations in the Northern Hemisphere). There can also be sidescatter from the auroral regions. Sidescatter signals are stronger than backscatter signals using the same general area of ground scattering.

Sidescatter signals have been observed frequently on the l4-MHz band, and can take place on any band where there is a large window between the MUF and the LUF. For sidescatter communications to occur, the thing to look for is a common area to which the band is open from both ends of the path (the Azores, in the above example), when there is no direct-path opening. It helps if the common area is in the open ocean, where there is less scattering loss than over land.

GRAY-LINE PROPAGATION

The *gray line*, sometimes called the *twilight zone*, is a band around the Earth between the Sunlit portion and darkness. Astronomers call this the *terminator*. The terminator is a somewhat diffused region because the Earth's atmo-

Fig 40—The gray line or terminator is a transition region between daylight and darkness. One side of the Earth is coming into sunrise, and the other is just past sunset.

sphere tends to scatter the light into the darkness. **Fig 40** illustrates the gray line. Notice that on one side of the Earth, the gray line is coming into daylight (sunrise), and on the other side it is coming into darkness (sunset).

Propagation along the gray line is very efficient, particularly on the lower bands, especially on 80 or 160 meters, so greater distances can be covered than might be expected for the frequency in use. One major reason for this is that the D layer, which absorbs HF signals, disappears rapidly on the sunset side of the gray line, and has not yet built up on the sunrise side.

The gray line runs generally north and south, but varies as much as 23° either side of the north-south line. This variation is caused by the tilt of the Earth's axis relative to its orbital plane around the Sun. The gray line will be exactly north and south at the equinoxes (March 21 and September 21). On the first day of Northern Hemisphere summer, June 21, it is tilted to the maximum of 23° one way, and on December 21, the first day of winter, it is tilted 23° the other way.

To an observer on the Earth, the direction of the terminator is always at right angles to the direction of the Sun at sunrise or sunset. It is important to note that, except at the equinoxes, the gray-line direction will be different at sunrise from that at sunset. This means you can work different areas of the world in the evening than you worked in the morning.

It isn't necessary to be located inside the twilight zone in order to take advantage of gray-line propagation. The effects can be used to advantage before sunrise and after sunset. This is because the Sun "rises" earlier and "sets" later on the ionospheric layers than it does on the Earth below.

What HF Bands Are Open—Where and When?

The CD-ROM included at the back of this book includes summary and detailed propagation predictions for more than 150 transmitting locations around the world. This propagation data was calculated using *CapMAN*, an upgraded variety of the mainframe propagation program *IONCAP*. The predictions were done for default antennas and powers that are representative of a "big-gun" station. Of course, not everyone has a big-gun station in his/her backyard, but this represents what the ultimate possibilities are, statistically speaking. After all, if the bands aren't open for the big guns, they are unlikely to be open for the "little pistols" too.

Let's see how propagation is affected if the smoothed sunspot number is 0 (corresponding to a smoothed solar flux of about 65), which is classified as a "Very Low" level of solar activity. And we'll examine the situation for a sunspot number of 100 (a smoothed solar flux of 150), which is typical of a "Very High" portion of the solar cycle.

Five-Band Summary Predictions

Tables 4 and **5** are Summary tables showing the pre-dicted signal levels (in S units) from Boston, Massachusetts, to the rest of the world for the month of January. The Boston transmitting site is representative of the entire New England area of the USA. The target geographic receiving regions for the major HF bands from 80 through 10 meters are tabulated versus UTC (Universal Coordinated Time) in hours. Table 4 represents a Very Low level of solar activity, while Table 5 is for a Very High level of solar activity.

Each transmitting location is organized by six levels of solar activity over the whole 11-year solar cycle:

- VL (Very Low: SSN between 0 to 20)
- LO (Low: SSN between 20 to 40)
- ME (Medium: SSN between 40 to 60)
- HI (High: SSN between 60 to 100)
- VH (Very High: SSN between 100 to 150)
- UH (Ultra High: SSN greater than 150)

The receiving geographic regions for each frequency band are abbreviated:

Table 4
Printout of summary propagation table for Boston to the rest of the world, for a Very Low level of solar activity in the month of January. The abbreviations for the target geographic areas are: EU = Europe, FE = Far East, SA = South America, AF = Africa, AS = south Asia, OC = Oceania, and NA = North America.

Jan., MA (Boston), for SSN = Very Low, Sigs in S-Units. By N6BV, ARRL.

UTC	\<80 Meters\> EU	FE	SA	AF	AS	OC	NA	\<40 Meters\> EU	FE	SA	AF	AS	OC	NA	\<20 Meters\> EU	FE	SA	AF	AS	OC	NA	\<15 Meters\> EU	FE	SA	AF	AS	OC	NA	\<10 Meters\> EU	FE	SA	AF	AS	OC	NA	UTC
0	9	-	9+	9	9	-	9+	9	8	9+	9+	9	2	9+	-	8	9+	7	4	8	9+	-	-	-	-	-	-	1	-	-	-	-	-	-	2	0
1	9	-	9+	9	9	-	9+	9	6	9+	9+	9+	6	9+	-	4	9	4	2	6	9+	-	-	-	-	-	-	1	-	-	-	-	-	-	2	1
2	9	-	9+	9+	8	1	9+	9	6	9+	9+	9	8	9+	-	1	8	1	2	3	9+	-	-	-	-	-	-	1	-	-	-	-	-	-	2	2
3	9	-	9+	9+	8	6	9+	9	6	9+	9+	9	8	9+	-	-	8	2	2	-	9+	-	-	-	-	-	-	1	-	-	-	-	-	-	2	3
4	9	-	9+	9+	1	8	9+	9	8	9+	9+	9	9	9+	-	1	8	7	2	-	9+	-	-	-	-	-	-	1	-	-	-	-	-	-	2	4
5	9	-	9+	9+	-	9	9+	9	8	9+	9+	8	9	9+	-	1	9	8	2	-	9	-	-	-	-	-	-	1	-	-	-	-	-	-	2	5
6	9+	-	9+	9+	-	9	9+	7	8	9+	9+	8	9	9+	-	1	9+	8	-	-	9	-	-	-	-	-	-	1	-	-	-	-	-	-	2	6
7	9	7	9+	9	-	9	9+	7	8	9+	9	8	9	9+	-	1	9+	1	-	1	8	-	-	-	-	-	-	1	-	-	-	-	-	-	2	7
8	9	8	9+	9	-	9	9+	8	9	9+	9	8	9+	9+	-	1	9+	-	-	5	9	-	-	-	-	-	-	1	-	-	-	-	-	-	2	8
9	8	8	9+	7	6	9	9+	8	9	9+	9	9	9+	9+	-	-	9	1	-	7	9	-	-	-	-	-	-	1	-	-	-	-	-	-	2	9
10	5	8	9+	4	6	9	9+	9	9	9+	9	9	9+	9+	-	3	9	5	-	6	9	-	-	-	-	-	-	1	-	-	-	-	-	-	2	10
11	3	8	9+	-	5	9	9+	8	9	9+	7	9	9+	9+	5	-	9+	9	5	1*	8	-	-	-	-	-	-	1	-	-	-	-	-	-	2	11
12	1	8	9	-	4	9	9+	7	9	9+	4	8	9	9+	9	5	9+	9+	9	2*	8	-	-	5	6	-	-	1	-	-	-	-	-	-	2	12
13	-	6	1	-	-	7	9+	6	8	9+	1	8	9	9+	9+	9	9+	9	9	7	8	4	-	9+	9	7	-	1	-	-	-	-	-	-	1	13
14	-	-	-	-	-	1	9+	5	7	8	-	8	8	9+	9+	9	9+	9	9	9	9+	7	2*	9+	9	9	-	8	-	-	5	-	-	-	1	14
15	-	-	-	-	-	-	9+	4	6	5	-	6	7	9+	9+	9	9+	9	9	9	9+	7	5	9+	9	2	2	5	-	-	5	-	-	-	-	15
16	-	-	-	-	-	-	9+	5	6	4	2	5	4	9+	9+	8	9+	9+	9	9	9+	5	1	9+	8	2*	2	9	-	-	5	-	-	-	1	16
17	-	-	-	-	-	-	9+	6	5	5	5	6	1	9+	9+	5	9+	9+	3	9	9+	-	-	9+	9	-	3	9+	-	-	5	-	-	-	1	17
18	1	-	-	-	-	-	9+	8	6	6	7	6	-	9+	9+	6	9+	9+	4	9	9+	-	-	9+	9	-	7	9+	-	-	5	-	-	-	1	18
19	3	-	-	2	-	-	9+	9	7	8	8	8	-	9+	6	6	9+	9+	6	9	9+	-	-	9+	9	-	9	9+	-	-	2	-	-	-	1	19
20	5	-	7	5	-	-	9+	9	8	9+	9	8	4	9+	1	7	9+	9+	8	9	9+	-	-	9+	4	-	9	9	-	-	-	-	-	-	1	20
21	8	3	9	8	6	-	9+	9	8	9+	9+	9	7	9+	-	8	9+	9	8	9	9+	-	-	9+	-	-	9	6	-	-	-	-	-	-	1	21
22	9	3	9+	9	8	-	9+	9	8	9+	9+	9	5	9+	-	9+	9+	9	8	9	9+	-	-	9	-	-	7	1	-	-	-	-	-	-	1	22
23	9	2	9+	9	9	-	9+	9	8	9+	9+	9	4	9+	-	9+	9+	9	5	9	9+	-	1	6	-	-	2	3	-	-	-	-	-	-	2	23
	EU	FE	SA	AF	AS	OC	NA	EU	FE	SA	AF	AS	OC	NA	EU	FE	SA	AF	AS	OC	NA	EU	FE	SA	AF	AS	OC	NA	EU	FE	SA	AF	AS	OC	NA	

Jan., MA (Boston), for SSN = Very High, Sigs in S-Units. By N6BV, ARRL.

UTC	80 Meters							40 Meters							20 Meters							15 Meters							10 Meters							UTC
	EU	FE	SA	AF	AS	OC	NA	EU	FE	SA	AF	AS	OC	NA	EU	FE	SA	AF	AS	OC	NA	EU	FE	SA	AF	AS	OC	NA	EU	FE	SA	AF	AS	OC	NA	
0	9+	-	9+	9+	8	-	9+	9+	5	9+	9+	9	-	9+	1	9+	9+	9+	9+	9	9+	-	9	9+	2	2	9+	9+	-	1	8	-	-	8	9+	0
1	9+	-	9+	9+	8	-	9+	9+	4	9+	9+	9	2	9+	1	9	9+	8	9+	9+	9+	-	3	9	-	7	9+	9	-	-	-	-	-	4	2	1
2	9+	-	9+	9+	7	-	9+	9+	4	9+	9+	9	7	9+	1	9	9+	8	9	9+	9+	-	-	3	-	-	7	9	-	-	-	-	-	-	2	2
3	9+	-	9+	9+	1	2	9+	9+	4	9+	9+	9	9	9+	-	7	9+	7	8	9+	9	-	-	-	-	-	-	-	-	-	-	-	-	-	2	3
4	9+	-	9+	9+	-	7	9+	9+	5	9+	9+	8	9	9+	-	5	9+	9	9	9	9+	-	-	1	-	-	-	-	-	-	-	-	-	-	2	4
5	9+	-	9+	9+	-	8	9+	9+	6	9+	9+	7	9	9+	-	5	9+	9	9	5	9+	-	-	-	-	-	-	-	-	-	-	-	-	-	2	5
6	9+	-	9+	9+	-	8	9+	9+	7	9+	9+	7	9	9+	-	8	9+	8	9	5	9+	-	-	-	-	-	-	-	-	-	-	-	-	2	6
7	9+	-	9+	9+	-	8	9+	9	8	9+	9+	7	9+	9+	-	9	9+	-	7	9	9+	-	-	1	-	-	-	-	-	-	-	-	-	2	7
8	9	7	9+	9	-	8	9+	9	8	9+	9+	8	9+	9+	-	9	9+	-	4	9+	9+	-	-	1	-	-	-	2	-	-	-	-	-	2	8
9	8	7	9+	7	-	8	9+	9	9	9+	9	8	9+	9+	-	6	9+	-	1	9+	9+	-	-	-	-	-	-	1	-	-	-	-	-	2	9
10	5	8	9+	2	3	8	9+	9	9	9+	8	8	9	9+	4	-	9+	9+	1	5	9	-	-	-	-	-	-	-	-	-	-	-	-	2	10
11	1	8	9+	-	4	9	9+	8	9	9+	5	8	9	9+	9+	4*	9+	9+	7	-	8	-	-	9	9	-	-	-	-	-	-	-	-	2	11
12	-	7	8	-	1	9	9+	6	9	9+	1	8	9	9+	9+	9	9+	9	9	1*	9+	9	8*	9+	9+	9	5*	-	-	2*	9	9	1	1*	2	12
13	-	-	-	-	-	2	9+	4	8	8	-	7	9	9+	9+	9	9+	9	9	9+	9+	9+	7	9+	9+	9+	3*	9	9	5*	9+	9+	9	6*	2	13
14	-	-	-	-	-	-	9+	2	7	4	-	5	8	9+	9+	9	9+	8	9	9	9+	9+	9	9+	9+	9+	9	9+	9	6*	9+	9+	9	1*	1	14
15	-	-	-	-	-	-	9	1	5	-	-	4	5	9+	9+	9	9+	9	9	9	9+	9+	9+	9+	9+	9+	9	9+	9	5	9+	9+	6	6	8	15
16	-	-	-	-	-	-	8	3	4	-	-	3	1	9+	9+	8	9	9	9	9	9+	9+	9+	9+	9+	9	9+	9+	9	8	9+	9+	-	8	9	16
17	-	-	-	-	-	-	8	5	3	-	2	4	-	9+	9+	8	9+	9+	9	9	9+	9+	9	9+	9+	1*	9+	9+	-	8	9+	9+	-	8	9+	17
18	-	-	-	-	-	-	9	7	4	2	5	5	-	9+	9+	9	9+	9+	9	9	9+	9+	9	9+	9+	1	9+	9+	-	7	9+	9+	-	9+	9+	18
19	1	-	-	1	-	-	9+	8	5	6	8	7	-	9+	9+	9	9+	9+	9	9	9+	-	9+	9+	9+	2	9	9+	-	6	9+	9+	-	9+	9+	19
20	4	-	2	5	-	-	9+	9	6	9	9	8	-	9+	9+	9	9+	9+	9	9	9+	-	8	9+	9+	3	9	9+	-	1	9+	9	-	9	9+	20
21	7	-	8	7	1	-	9+	9+	7	9+	9+	8	1	9+	8	9	9+	9+	9	9	9+	-	6	9+	9+	3	9	9+	-	-	9+	5*	-	9+	9+	21
22	9	2	9+	9	8	-	9+	9+	7	9+	9+	9	4	9+	2	9+	9+	9+	9	9	9+	-	9+	9+	9	1	9+	9+	-	5	9+	4*	-	9	6	22
23	9	-	9+	9	8	-	9+	9+	7	9+	9+	9	-	9+	1	9+	9+	9+	9	9	9+	-	9+	9+	6	-	9	9+	-	7	9+	2*	-	9	2	23
	EU	FE	SA	AF	AS	OC	NA	EU	FE	SA	AF	AS	OC	NA	EU	FE	SA	AF	AS	OC	NA	EU	FE	SA	AF	AS	OC	NA	EU	FE	SA	AF	AS	OC	NA	

- EU All of Europe
- FE The Far East, centered on Japan
- SA South America, centered on Paraguay
- AF All of Africa, centered on Zambia
- AS South Asia, centered on India
- OC Oceania, centered on Sydney, Australia
- NA North America, all across the USA

These propagation files show the highest predicted signal strength (in S-units) throughout the generalized receiving area, for a 1500-W transmitter and rather good antennas on both sides of the circuit. The standard antennas are:

- 100-foot high inverted-V dipoles for 80 and 40 meters
- 3-element Yagi at 100 feet for 20 meters
- 4-element Yagi at 60 feet for 15 and 10 meters.

For example, Summary Table 4 shows that in January during a period of Very Low solar activity, 15 meters is open to somewhere in Europe from Boston for only 4 hours, from 13 to 16 UTC, with a peak signal level between S4 and S7. Now look at Table 5, where 15 meters is predicted to be open to Europe during a period of Very High solar activity for 7 hours, from 12 to 18 UTC, with peak signals ranging from S9 to S9+.

Both Tables 4 and 5 represent *snapshots* of predicted signal levels to generalized receiving locations—that is, they are computed for a particular month, from a particular transmitting location, and for a particular level of solar activity. These tables provide summary information that is particularly valuable for someone planning for an operating event such as a DXpedition or a contest.

What happens if you don't have a big-gun station with high antennas or the 1500-W power assumed in the analyses above? You can discount the S-Meter readings to reflect a smaller station:

- Subtract 2 S units for a dipole instead of a Yagi at same height on 20/15/10 meters.
- Subtract 3 S units for a dipole at 50 feet instead of a Yagi at 100 feet on 20 meters.
- Subtract 1 S unit for a dipole at 50 feet rather than a dipole at 100 feet on 40/80 meters.
- Subtract 3 S units for 100 W rather than 1500 W.
- Subtract 6 S units for 5 W (QRP) rather than 1500 W.

For example, Table 4 predicts an S7 signal into Boston from Europe on 15 meters at 14 UTC. If a European station is using a dipole at 50 feet, with 100 W of power, what

20 Meters: Jan., MA (Boston), for SSN = Very High, Sigs in S-Units. By N6BV, ARRL.

UTC -->

Zone	00	01	02	03	04	05	06	07	08	09	10	11	12	13	14	15	16	17	18	19	20	21	22	23
KL7 = 01	9+	9+	9+	7	-	-	-	-	-	-	-	-	-	-	-	3	9+	9+	9+	9+	9+	9+	9+	9+
VO2 = 02	9+	9	9	9	9	9	8	7	5	3	2	1	5	9+	9+	9+	9+	9+	9+	9+	9+	9+	8	9+
W6 = 03	9+	9+	9+	7	7	1	1	5	8	8	3	-	-	1	9	9+	9+	9+	9+	9	9	9+	9+	9+
W0 = 04	9+	9+	9+	8	5	5	5	5	3	2	1	-	-	9+	9+	9+	9+	9+	9+	9+	9+	9+	9+	9+
W3 = 05	4	2	2	2	2	2	2	3	3	3	3	2	1	1	8	9+	9+	9+	9+	9+	9+	9+	9+	9
XE1 = 06	9+	9+	7	9	9+	9+	9+	9+	9+	9+	9	8	9+	9+	9+	9+	9	9	9	9+	9+	9+	9+	9+
TI = 07	9+	9+	8	9	9	9	9	9	9	9+	9	9+	9+	9+	9+	9+	9	8	9	9	9+	9+	9+	9+
VP2 = 08	9+	9+	9+	9+	9+	9+	9+	9+	9+	8	9	9+	9+	9+	9+	9+	9	9+	9+	9+	9+	9+	9+	9+
P4 = 09	9+	9+	9+	9+	9+	9+	9+	9+	9+	9+	9+	9+	9+	9+	9	9	9	9	9+	9+	9+	9+	9+	9+
HC = 10	9+	8	9+	9	9	9	9	9	7	3	1	7	9+	9+	9	5	5	5	7	8	9+	9+	9+	9+
PY1 = 11	9+	9+	9+	9	9	9+	9+	9	8	6	9	9+	8	2	1	-	-	1	4	8	9	9+	9+	9+
CE = 12	9+	9+	9+	9+	9+	9+	9+	9+	9	8	8	9+	9	8	2	1	1	-	1	3	7	9	9+	9+
LU = 13	9+	9+	9+	9+	9+	9+	9+	9+	8	8	8	9+	8	4	2	1	-	1	4	8	9	9+	9+	9+
G = 14	-	-	-	-	-	-	-	-	-	-	-	9+	9+	9+	9+	9+	9+	9+	9+	9+	9+	8	2	-
I = 15	-	-	-	-	-	-	-	-	-	-	4	9	9	9	9	9	9	9+	9+	9	8	2	-	-
UA3 = 16	1	1	1	-	-	-	-	-	-	-	-	8	9	9+	9+	9+	9	8	5	-	-	-	-	1
UN = 17	1	-	-	8	7	7	7	1	-	-	-	2	9	9	9	6	-	-	2	4	8	9	5	4
UA9 = 18	6	7	6	6	9	9	9	7	4	1	-	-	8	8	6	6	5	6	7	8	9	9	8	7
UA0 = 19	9+	9	9	6	5	5	8	8	8	4	-	-	2	6	8	8	7	4	4	7	9	9	9+	9+
4X = 20	8	6	3	1	-	3	4	-	-	-	1	8	8	8	8	9	9	9+	9	9	8	7	7	7
HZ = 21	9+	9	4	3	8	8	2	-	-	-	1	7	8	9	8	8	9	9	9	9	9	9	9	9
VU = 22	7	5	8	7	6	7	5	-	-	-	-	6	9	9	9	9	3	2	2	2	8	8	9	8
JT = 23	9	9+	9	5	7	8	8	6	3	-	-	2*	8	8	5	6	8	8	8	8	9	7	5	6
VS6 = 24	9	9	9	5	4	5	7	8	6	1	-	1*	5	7	1	1	1	1	4	2	-	-	-	9
JA1 = 25	9	9	8	7	5	5	8	9	9	6	-	1	1	2	7	7	6	2	-	-	7	9	9+	9
HS = 26	9	9	6	4	2	-	-	2	1	-	-	2*	9	9	9	9	8	7	5	4	5	-	1*	1
DU = 27	9	8	7	-	-	-	5	7	7	1	-	-	1*	9	9	7	6	4	5	3	1*	1*	8	9
YB = 28	9	8	1	-	-	-	-	-	-	-	-	4*	8	9	9	9	8	8	9	9	9	9	9+	9+
VK6 = 29	3*	4*	-	-	-	-	-	-	5	3	-	-	-	5	9	9	9	8	9	9	9	9	9	8
VK3 = 30	1*	-	-	-	-	-	1	3	9	9	4	-	-	9+	9	8	2	1	-	-	1	2*	5*	4*
KH6 = 31	9	9+	9+	9+	8	2	2	6	4	-	-	-	-	-	-	-	9	9	8	7	6	4	6	7
KH8 = 32	-	2	9	9	9	5	5	9	9+	9+	5	-	-	9+	9	9	8	5	3	1	-	-	-	-
CN = 33	-	-	-	-	-	-	-	-	-	-	9	9+	9	9	8	9	9	9+	9+	9+	9+	9+	9+	7
SU = 34	9	8	3	3	-	1	4	-	-	-	2	7	8	8	8	8	9	9	9+	9+	9+	9+	8	8
6W = 35	9+	8	-	-	2	7	5	-	-	-	9+	9+	8	5	4	3	7	9	9+	9+	9+	9+	9+	9+
D2 = 36	9+	9+	5	3	9	9	8	-	-	-	3	-	-	-	-	4	4	7	8	9	9+	9+	9+	9+
5Z = 37	9+	9	2	4	8	8	1	-	-	-	2	-	-	3	5	5	7	8	9	9	9+	9+	9+	9+
ZS6 = 38	9+	9+	9+	8	7	8	9	6	-	-	-	-	-	-	1*	1	2	6	8	9	9+	9+	9+	9+
FR = 39	9+	8	2	1	4	1	-	-	-	-	-	-	-	2*	3*	1*	1	3	8	9	9+	9+	9+	9+
FJL = 40	9+	9+	7	4	7	8	7	1	-	-	-	1*	8	9	9	9	9	9	9	9+	9+	9+	9+	9+
Zone	00	01	02	03	04	05	06	07	08	09	10	11	12	13	14	15	16	17	18	19	20	21	22	23

UTC -->

Expected signal levels using 1500 W and 3-element Yagis at 100 feet at each station.

Fig 41—The 20-meter page from Detailed propagation-prediction for the month of January, during Very High solar conditions, from Boston to 40 CQ Zones throughout the world. There are similar pages for each month/SSN level for 160, 80, 40, 20, 15 and 10 meters. These Detailed tables are very useful for planning DX work.

would this do to the predicted signal level in Boston? You would compute: S7 – 2 S units (for a dipole instead of Yagi) – 3 S units (100 W rather than 1500 W) = an S2 signal in Boston. A QRP station with a 4-element 15-meter Yagi at 60 feet would yield: S7 – 6 S units = an S1 signal in Boston.

More Detailed Predictions

Let's now look at table in **Fig 41**, which is the Detailed 20-meter page for the same conditions in Table 5: January at a Very High level of solar activity from Boston to the world. There are six such pages per month/SSN level, covering 160, 80, 40, 20, 15 and 10 meters.

In a Detailed prediction table, the world is divided into the 40 CQ Zones, with a particular sample location in each zone. For example, Zone 14 in Western Europe is represented by a location in London, England (call sign G), while Zone 25 is represented by a location in Tokyo, Japan (call sign JA1). Note that Zones with large ham populations are highlighted with dark shadowing for easy identification. For example, Zones 3, 4 and 5 cover the USA, while Zones 14,

15 and 16 cover the majority of Europe. Zone 25 covers the big ham population in Japan.

Let's revisit the example above for computing the signal strength for a station in London, but this time on 20 meters. Again, we'll assume that the G station has a dipole at 50 feet and 100 W of transmitter power. At 14 UTC in Zone 14, the table in Fig 40 predicts a very healthy signal for the reference big-gun station, at S9+. This is a signal at least S9 + 10 dB. Here, we're going to round off the plus 10 dB to 2 S units, giving a fictional 11 S units to start. We discount this for the smaller station: S11 – 3 S units (for a dipole at 50 feet instead of a 3-element Yagi at 100 feet) – 3 S units (100 W rather than 1500 W) = S5 signal in Boston. This is a respectable signal and will probably get through, in the absence of stronger signals calling the Boston station at the same time, of course.

Here's another example of how to use the Detailed propagation-prediction tables. Let's say that at 1230 UTC in January you work a VU2 station in New Delhi on 15 meters from Boston, where the local time is 7:30 AM.

You need a 20-meter contact also for the 5-Band DXCC award, so you quickly check the table in Fig 40 for Zone 22 (VU) and find that the predicted signal strength is S9. Your new VU2 friend is willing to jump to 20 meters and so you QSY to make the contact.

But perhaps you are late leaving for work and so you ask your new VU2 friend to make a schedule with you later that evening. Again, you consult the Detailed prediction table for 20 meters and find that signals are predicted to be S8 or stronger from 20 to 23 UTC, dropping to S7 at 00 UTC. You quickly ask your new friend whether he minds waking up at 4:30 AM his time to make a schedule with you at 2300 UTC, because New Delhi is 5½ hours ahead of UTC. You determined this using the program *GeoClock*, which is included with the software on the CD-ROM in the back of this book and which you run in the background on *Windows*. Luckily, he's a very gracious fellow and agrees to meet you on a specific frequency at that time.

The Detailed propagation-prediction tables give you all the information needed to plan your operations to maximize your enjoyment chasing DX. You can use these tables to plan a 48-hour contest next month, or next year—or you can use them to plan a schedule with your ham cousin on the West Coast on Saturday afternoon.

THE PROPAGATION BIG PICTURE

A newcomer to the HF bands could easily be overwhelmed with the sheer amount of data available in the Summary (and particularly the Detailed) prediction tables on the CD-ROM included with this book. So here's a long-term, "big-picture" view of HF propagation that might help answer some common questions. For example, what month really is the best for working DX around the clock? Or what level of solar activity is necessary to provide an opening between your QTH and somewhere in the South Pacific?

Table 6 is a table showing the number of hours in a day during each month when each major HF band is open to the same receiving areas shown in Tables 4 and 5. The listing is for New England, for three levels of solar activity: Very Low, Medium and Very High. The number of hours are separated in Table 6 by slashes. (Versions of Table 6 for other areas around the US are on the CD-ROM that accompanies this book in **Fig6Tab.PDF**.)

Let's examine the conditions for New England to Europe on 15 meters for October. The entry shows "7/11/17," meaning that for a Very Low level of solar activity, 15 meters is open for 7 hours; for a Medium level, it is open for 11 hours and for a Very High level of solar activity it is open for 17 hours a day.

Even for a Very Low level of solar activity, the month with the most hours available per day from Boston to somewhere in Europe is October, with 7 hours, followed by the next largest month of March, with 6 hours. For a Very High level of solar activity, however, the 15-meter band is open to Europe for 18 hours in April, followed by 17 hours available in September and October. Arguably, the CQ World Wide Contest Committee picked the very best month for higher-frequency propagation when they chose October for the Phone portion of that contest.

You can easily see that even at a Very High level of solar activity, the summer months are not very good to work DX, particularly on east-west paths. For example, the 10-meter band is very rarely open from New England to Europe after the month of April, even when solar activity is at the highest levels possible. Things pick up after September, even for a Medium level of solar activity. Again, October looks like the most fruitful month in terms of the number of hours 10 meters is open to Europe under all levels of solar conditions.

Ten meters is open more regularly on north-south paths, such as from New England to South America or to southern Africa. It is open as much as 10 hours a day during March and October to deep South America, and 7 hours a day in October to Africa—even during the lowest parts of the solar cycle. (Together with the sporadic-E propagation that 10 meters enjoys during the summer, this band can often be a lot of fun even during the sunspot doldrums. You just have to *be operating* on the band, rather than avoiding it because you know the sunspots are "spotty!")

Now, look at the 20-meter band in Table 6. From New England, twenty is open to somewhere in South America for 24 hours a day, no matter the level of solar activity. Note that Table 6 doesn't predict the level of signals available; it just shows that the band is open with a signal strength greater than 0 on the S meter. Look back at Summary Table 4 for the predicted signal strengths in January at a Very Low level of solar activity. There, you can see that the signal strength from New England into deep South America is always S8 or greater for a big gun station. A lot of the time during the night the band sounds dead, simply because everyone is either asleep or operating on a lower frequency.

For the 40-meter band in Table 6, during the month of January the band is open to Europe for 24 hours a day, whatever the level of solar activity is. Look now at Table 4, and you'll see that the predicted level for Very Low solar activity varies from S4 to S9. Local QRM or QRN would probably disrupt communications on 40 meters in Europe for stateside signals weaker than perhaps S3 or S4. Even though you might well be able to hear Europeans from New England during the day, they probably won't hear you because of local conditions, including local S9+ European stations and atmospheric noise from nearby thunderstorms. New England stations with big antennas can often hear Europeans on 40 meters as early as noontime, but must wait until the late afternoon before the Europeans can hear them above their local noise and QRM.

Let's say that you want to boost your country total on 80 meters by concentrating on stations in the South Pacific. The best months would be from November to

Table 6

The number of hours per day when a particular band is open to the target geographic areas in Table 4, as related to the level of solar activity (Very Low, Medium and Very High). This table is customized for Boston to the rest of the world. Some paths are open 24 hours a day, plus or minus QRM and local QRN, no matter what the level of solar activity is. See CD-ROM for other transmitting locations.

```
MA (Boston)
Hours Open to Each Region for Very-Low/Medium/Very-High SSNs

80 Meters:
Month  Europe    Far East  So. Amer.  Africa    So. Asia  Oceania   No. Amer.
Jan    17/17/16   5/ 4/ 3  17/17/16   16/16/15   8/ 7/ 5  11/10/ 9  24/24/24
Feb    17/16/15   3/ 3/ 2  17/16/16   15/15/14   6/ 4/ 4  10/ 9/ 9  24/24/24
Mar    15/15/14   3/ 2/ 1  16/16/15   15/13/13   4/ 4/ 3   9/ 8/ 7  24/24/24
Apr    13/13/12   1/ 0/ 0  16/16/14   13/13/13   3/ 3/ 1   9/ 8/ 7  24/24/24
May    12/11/10   0/ 0/ 0  16/15/14   12/11/10   2/ 1/ 1   7/ 6/ 6  24/24/24
Jun    10/ 9/ 8   0/ 0/ 0  14/14/14   11/10/10   1/ 1/ 0   6/ 5/ 5  24/24/24
Jul    11/11/ 9   0/ 0/ 0  15/14/14   11/11/11   2/ 1/ 1   7/ 6/ 5  24/24/24
Aug    13/11/11   0/ 0/ 0  16/16/14   13/12/11   3/ 2/ 1   7/ 7/ 6  24/24/24
Sep    14/13/11   2/ 1/ 0  17/16/14   13/13/12   4/ 4/ 2   9/ 8/ 8  24/24/24
Oct    15/15/13   3/ 2/ 1  17/17/16   14/14/13   5/ 4/ 4   9/ 9/ 7  24/24/24
Nov    17/17/15   4/ 4/ 2  17/17/16   16/15/14   8/ 7/ 4  11/10/ 9  24/24/24
Dec    19/18/17   7/ 6/ 4  18/18/17   16/16/16  11/ 9/ 7  12/11/11  24/24/24

40 Meters:
Month  Europe    Far East  So. Amer.  Africa    So. Asia  Oceania   No. Amer.
Jan    24/24/24  15/16/15  24/24/21   21/20/19  21/21/19  19/18/15  24/24/24
Feb    24/24/21  13/11/11  24/23/20   20/19/18  19/19/17  16/15/14  24/24/24
Mar    23/22/19  10/ 9/ 7  24/21/18   19/17/17  17/17/13  13/13/13  24/24/24
Apr    21/19/18   8/ 6/ 4  22/20/18   17/16/15  16/11/ 8  13/13/11  24/24/24
May    19/17/17   5/ 4/ 3  22/18/17   17/16/14   9/ 8/ 5  12/11/10  24/24/24
Jun    17/15/13   4/ 2/ 2  22/18/16   16/15/14   7/ 5/ 5  11/10/ 9  24/24/24
Jul    18/16/15   5/ 4/ 2  24/18/17   17/15/14   8/ 7/ 5  12/11/10  24/24/24
Aug    19/17/16   7/ 5/ 4  24/19/18   18/16/15  11/10/ 6  13/12/11  24/24/24
Sep    22/21/17   9/ 8/ 5  23/20/18   18/17/16  14/11/ 7  13/13/12  24/24/24
Oct    24/23/20  12/11/ 8  24/23/19   20/18/17  17/16/14  16/13/13  24/24/24
Nov    24/24/22  14/13/12  24/24/20   21/19/18  21/20/17  17/17/13  24/24/24
Dec    24/24/24  18/19/22  24/24/21   23/21/19  24/23/22  21/19/18  24/24/24
```

February in terms of the number of hours per day when the 80-meter band is open to Oceania. You can see by reading across the line for each month that the level of solar activity is not hugely important on 80 meters to any location. Common experience (backed by the statistical information in Table 6) is that the 80-meter band is open only marginally longer when sunspots are low.

This is true to a greater extent on 40 meters. Thus you may hear the generalization that the low bands tend to be better during periods of low solar activity, while the upper HF bands (above 10 MHz) tend to be better when the sun is more active.

Table 6 can give you a good handle on what months are the most productive for DXing and contesting. It should be no surprise to most veteran operators that the fall and winter months are the best times to work DX.

```
20 Meters:
Month  Europe     Far East   So. Amer.  Africa     So. Asia   Oceania    No. Amer.
Jan    13/16/22   15/22/22   24/24/24   20/21/21   18/20/22   18/23/22   24/24/24
Feb    12/18/23   13/21/24   24/24/24   22/22/24   15/21/24   18/23/24   24/24/24
Mar    15/18/24   17/20/24   24/24/24   22/24/24   18/21/24   16/24/24   24/24/24
Apr    15/20/24   19/22/24   24/24/24   21/24/24   19/22/24   18/24/24   24/24/24
May    19/23/24   22/24/24   24/24/24   23/24/24   23/24/24   21/24/24   24/24/24
Jun    22/24/24   24/24/24   24/24/24   24/24/24   24/24/24   24/24/24   24/24/24
Jul    19/24/24   24/24/24   24/24/24   21/24/24   24/24/24   23/24/24   24/24/24
Aug    15/20/24   20/24/24   24/24/24   20/24/24   20/24/24   19/24/24   24/24/24
Sep    16/19/24   17/21/24   24/24/24   21/24/24   18/21/24   17/24/24   24/24/24
Oct    15/21/24   16/20/24   24/24/24   22/24/24   19/22/24   17/24/24   24/24/24
Nov    14/20/23   14/22/24   24/24/24   20/24/24   17/21/24   19/23/24   24/24/24
Dec    11/17/24   13/22/24   24/24/24   17/23/24   12/22/24   16/24/24   24/24/24


15 Meters:
Month  Europe     Far East   So. Amer.  Africa     So. Asia   Oceania    No. Amer.
Jan    4/ 6/ 7    2/ 9/13    12/15/16   9/13/13    3/ 4/ 7    9/12/13    24/15/16
Feb    4/ 7/12    4/10/14    13/18/23   11/13/16   3/ 7/13    8/13/15    22/16/19
Mar    6/ 9/14    2/13/15    14/21/24   13/17/22   5/11/17    10/14/17   15/16/23
Apr    0/10/18    3/13/18    15/23/24   15/18/24   9/15/19    11/15/21   16/16/24
May    1/13/16    6/10/19    17/20/24   14/18/24   13/17/18   10/16/19   20/19/24
Jun    0/ 2/16    0/ 9/15    16/21/24   14/18/24   5/15/18    10/12/20   24/22/22
Jul    0/ 2/16    0/ 5/18    15/19/24   12/18/24   0/12/18    4/12/20    24/22/21
Aug    0/ 2/14    0/ 8/17    14/18/22   13/16/22   0/12/17    6/10/19    22/19/21
Sep    1/10/17    6/13/17    14/16/24   13/17/22   9/14/17    9/14/17    16/16/22
Oct    7/11/17    10/13/17   12/16/22   12/15/22   7/12/17    12/13/15   18/15/22
Nov    5/ 8/14    8/11/14    12/16/22   11/14/17   3/ 7/16    10/13/15   20/16/21
Dec    3/ 6/ 9    2/10/13    12/15/23   8/13/15    2/ 4/12    9/12/14    24/15/18

10 Meters:
Month  Europe     Far East   So. Amer.  Africa     So. Asia   Oceania    No. Amer.
Jan    0/ 1/ 4    0/ 1/ 8    6/11/13    0/ 7/10    0/ 1/ 3    0/ 3/11    23/24/24
Feb    0/ 2/ 7    0/ 2/10    8/12/14    0/ 9/13    0/ 3/ 5    0/ 7/13    24/24/24
Mar    0/ 0/ 8    0/ 1/10    10/14/20   1/11/14    0/ 0/ 8    0/ 7/13    23/24/24
Apr    0/ 0/ 8    0/ 0/ 8    7/14/21    0/12/17    0/ 0/13    0/ 5/11    18/24/24
May    0/ 0/ 0    0/ 0/ 1    7/12/20    1/10/17    0/ 1/12    0/ 2/11    17/20/22
Jun    0/ 0/ 0    0/ 0/ 0    7/11/18    0/ 3/17    0/ 0/ 0    0/ 0/ 2    21/19/23
Jul    0/ 0/ 0    0/ 0/ 0    2/ 9/19    0/ 2/18    0/ 0/ 7    0/ 0/ 6    16/16/24
Aug    0/ 0/ 0    0/ 0/ 0    2/10/17    0/ 1/16    0/ 0/10    0/ 0/ 8    17/17/24
Sep    0/ 0/ 8    0/ 1/10    7/13/18    0/11/16    0/ 0/10    0/ 2/ 9    19/24/24
Oct    0/ 5/ 9    0/ 2/11    10/12/16   7/12/14    0/ 5/ 9    0/ 8/12    24/24/24
Nov    0/ 4/ 8    0/ 3/11    9/12/15    5/10/13    0/ 3/ 6    4/10/12    24/24/24
Dec    0/ 3/ 6    0/ 1/ 8    8/11/13    1/ 8/12    0/ 1/ 4    2/ 7/12    23/23/24
```

Do-It-Yourself Propagation Prediction

Very reliable methods of determining the MUF for any given radio path have been developed over the last 50 years. As discussed previously, these methods are all based on the smoothed sunspot number (SSN) as the measure of solar activity. It is for this reason that smoothed sunspot numbers hold so much meaning for radio amateurs and others concerned with radio-wave propagation—they are the link to past (and future) propagation conditions.

Early on, the prediction of propagation conditions required tedious work with numerous graphs, along with charts of frequency contours overlaid, or overprinted, on world maps. The basic materials were available from an agency of the US government. Monthly publications pro-
vided the frequency-contour data a few months in advance. Only rarely did amateurs try their hand at predicting propagation conditions using these hard-to-use methods.

Today's powerful PCs have given the amateur wonderful tools to make quick-and-easy HF propagation predictions, whether for a contest or a DXpedition. The summary and detailed prediction tables described earlier in this chapter were generated using *CAPMan*, a modernized version of the mainframe *IONCAP* program, on a PC.

While tremendously useful to setting up schedules and for planning strategy for contests, both the Summary and Detailed prediction tables located on the CD-ROM accompanying this book show signal strength. They do not show

Table 7
Features and Attributes of Propagation Prediction Programs

	ASAPS V. 4	CAPMan	VOACAP Windows	ACE-HF	W6ELProp V. 2.70	WinCAP Wizard 2	PropLab Pro
User Friendliness	Good	Good	Good	Excellent	Good	Good	Poor
Operating System	Windows	DOS	Windows	Windows	Windows	Windows	DOS
Uses k or A index	No	Yes	No	No	Yes	Yes	Yes
User library of QTHs	Yes	Yes	Yes	Yes-RX	Yes	Yes	No
Bearings, distances	Yes	Yes	Yes	Yes	Yes	Yes	Yes
MUF calculation	Yes	Yes	Yes	Yes	Yes	Yes	Yes
LUF calculation	Yes	Yes	Yes	Yes	No	Yes	Yes
Wave angle calculation	Yes	Yes	Yes	Yes	Yes	Yes	Yes
Vary minimum wave angle	Yes	Yes	Yes	Yes	Yes	Yes	Yes
Path regions and hops	Yes	Yes	Yes	Yes	Yes	Yes	Yes
Multipath effects	Yes	Yes	Yes	Yes	No	Yes	Yes
Path probability	Yes	Yes	Yes	Yes	Yes	Yes	Yes
Signal strengths	Yes	Yes	Yes	Yes	Yes	Yes	Yes
S/N ratios	Yes	Yes	Yes	Yes	No	Yes	Yes
Long-path calculation	Yes	Yes	Yes	Yes	Yes	Yes	Yes
Antenna selection	Yes	Yes	Yes	Yes	Indirectly	Isotropic	Yes
Vary antenna height	Yes	Yes	Yes	Yes	Indirectly	No	Yes
Vary ground characteristics	Yes	Yes	Yes	Yes	No	No	No
Vary transmit power	Yes	Yes	Yes	Yes	Indirectly	Yes	Yes
Graphic displays	Yes	Yes	Yes	Yes	Yes	Yes	2D/3D
UT-day graphs	Yes	Yes	Yes	Yes	Yes	Yes	Yes
Area Mapping	No	Yes	Yes	Yes	Yes	No	Yes
Documentation	Yes	Yes	On-line	Yes	Yes	Yes	Yes
Price class	$275+	$89	free†	$99	free§	$29.95+	$150††

Price classes are for late 2003 and subject to change.
†Available on the World Wide Web: **elbert.its.bldrdoc.gov/hf.html**
§Available on the World Wide Web at: **www.qsl.net/w6elprop/**
+ Shipping and handling extra.
††Available on the World Wide Web: **www.spacew.com/www/proplab.html**

other information that is also in the underlying databases used to generate them. They don't, for example, show the dominant elevation angles and neither do they show reliability statistics. You may want to run propagation-prediction software yourself to get into the really "nitty-gritty" details.

Modern programs are designed for quick-and-easy predictions of propagation parameters. See **Table 7** for a listing of a number of popular programs. The basic input information required is the smoothed sunspot number (SSN) or smoothed solar flux, the date (month and day), and the latitudes and longitudes at the two ends of the radio path. The latitude and longitude, of course, are used to determine the great-circle radio path. Most commercial programs tailored for ham use allow you to specify locations by the call sign. The date is used to determine the latitude of the Sun, and this, with the sunspot number, is used to determine the properties of the ionosphere at critical points on the path.

Of course, just because a computer program predicts that a band will be open on a particular path, it doesn't follow that the Sun and the ionosphere will always cooperate! A sudden solar flare can result in a major geomagnetic storm, taking out HF communication anywhere from hours to days. There is still art, as well as a lot of science, in predicting propagation. In times of quiet geomagnetic activity, however, the prediction programs are good at forecasting band openings and closings.

Obtaining Sunspot Number/Solar Flux Data

After you have chosen and then set up a computer program for evaluation of a particular path, you will still need the sunspot number or solar flux level for the period in question. A caution must be stated here—for best accuracy and consistency, use the average of solar flux values taken from actual observations, perhaps from WWV/WWVH, over the previous three or four days. Many amateur packet systems archive WWV flux numbers (plus planetary k_p and A_p indices). Solar flux numbers can vary dramatically from day to day, but the Earth's ionosphere is relatively slow to respond to instantaneous changes in solar radiation. This caveat also

Fig 42—Smoothed sunspot number, with predictions, from 1940 to 2040. This was extrapolated based on data from 1840 to 1983. Cycle 22 actually peaked in Nov 1989, at a monthly smoothed sunspot number of 158. Propagation on the higher frequencies throughout the peak of Cycle 22 was good to excellent, since the monthly smoothed sunspot number stayed at 100 or above from July 1988 through May 1992. (*Courtesy of Naval Ocean Systems Center,* San Diego.*)*

Fig 43—Effective Sunspot Number (SSN$_e$) produced by NWRA. Note large drop in effective SSN due to a geomagnetic storm commencing Oct 1, 2002. (*Courtesy of Northwest Research Associates.*)

holds for sunspot numbers derived, using Fig 18, from WWV/WWVH solar flux numbers.

Fig 42 shows a graph produced in the early 1980s of smoothed sunspot numbers for Solar Cycles 17 through 21, with predictions for Cycles 22 through 26. The graph covers a period of 100 years, from 1940 to 2040, and may be used for making long-term or historical calculations. Just remember that the graph shows smoothed numbers. The solar activity at any given time can be significantly lower or significantly higher than the graph indicates. In fact, Cycle 22 peaked at the end of 1989, as predicted, but with a monthly smoothed sunspot level of 158, quite a bit higher than predicted. Cycle 23 peaked in early 2002 at a level of about 115, a considerably higher level than the predicted value.

WWV PROPAGATION DATA

For the most current data on what the Sun is doing, National Institute of Standards and Technology stations WWV and WWVH broadcast information on solar activity at 18 and 45 minutes past each hour, respectively. These propagation bulletins give the solar flux, geomagnetic A-Index, Boulder K-Index, and a brief statement of solar and geomagnetic activity in the past and coming 24-hour periods, in that order. The solar flux and A-Index are changed daily with the 2118 UT bulletin, the rest every three hours—0018, 0318, 0618 UT and so on. On the Web, up-to-date WWV information can be found at: **ftp:// ftp.sel.noaa.gov/pub/latest/wwv.txt** or on the NOAA Web page **www.sec.noaa.gov/**.

Some other useful Web sites are: **dx.qsl.net/propaga- tion/, www.dxlc.com/solar**, **hfradio.org/propagation. html**. The Solar Terrestrial Dispatch page contains a wealth of propagation-related information: **www.spacew.com/**. You

may also access propagation information on your local PacketCluster. Use the command SH/WWV/*n*, where *n* is the number of spots you wish to see (five is the default).

Another excellent method for obtaining an "equivalent sunspot number" (SSN$_e$) is to go to the Space Weather site of Northwest Research Services: **www.nwra-az.com/spawx/ ssne24.html**. NWRA compares real-time ionospheric sounder data around the world with predictions using various levels of SSN looking for the best match. They thus "back into" the actual effective sunspot number. **Fig 43** is a typical NWRA graph, which covers the week ending 6 October 2002. Note the sudden decrease in SSN$_e$ after a geomagnetic storm depressed SSN$_e$ by more than 50%.

The A-Index

The WWV/WWVH A-Index is a daily figure for the state of activity of the Earth's magnetic field. It is updated with the 2118/2145 UT bulletin. The A-Index tells you mainly how yesterday was, but it is very revealing when charted regularly, because geomagnetic disturbances nearly always recur at four-week intervals.

The K-Index

The K-Index (new every three hours) reflects Boulder readings of the Earth's geomagnetic field in the hours just preceding the bulletin data changes. It is the nearest thing to current data on radio propagation available. With new data every three hours, K-Index trend is important. Rising is bad news; falling is good, especially related to propagation on paths involving latitudes above 30° north. Because this is a Boulder, Colorado, reading of geomagnetic activity, it may not correlate closely with conditions in other areas.

The K-Index is also a timely clue to aurora possibilities. Values of 4, and rising, warn that conditions associated with

Fig 44—Plot of the estimated planetary k index, K_p, for the last four days. (*Courtesy NOAA/SEC.*)

auroras and degraded HF propagation are present in the Boulder area at the time of the bulletin's preparation. A NOAA Web site that carries up-to-date planetary K_p data is: **www.sel.noaa.gov/ftpmenu/plots/2003_plots/kp.html**. **Fig 44** is a graph from this Web site for four days starting 27 April 2003 to 30 April 2003. This was a period of significant geomagnetic activity, indicated by K_p indices of 5 and 4.

BIBLIOGRAPHY

Source material and more extended discussion of topics covered in this chapter can be found in the references given below.

E. V. Appleton and W.R. Piggott, "Ionospheric Absorption Measurements during a Sunspot Cycle," *J. Atmos. Terr. Phys.*, Vol 3, p 141, 1954.

D. Bilitiza, *International Reference Ionosphere (IRI 90)*, National Space Science Data Center, Greenbelt, MD, 1990.

D. Bray, "Method of Determining VHF/HF Station Capabilities," *QST*, Nov 1961.

A. Brekke, "Physics of the Upper Polar Atmosphere," (John Wiley and Sons: New York, 1997).

R. R. Brown, "Demography, DXpeditions and Magneto-Ionic Theory," *The DX Magazine*, Vol. X, No. 2, p 44, Mar/Apr 1998.

R. R. Brown, *The Little Pistol's Guide to HF Communication* (Sacramento: WorldRadio Books, 1996).

R. R. Brown, "Signal Ducting on the 160 Meter Band," *Communications Quarterly*, p 65, Spring 1998.

R. R. Brown, "Unusual Low-Frequency Signal Propagation at Sunrise," *Communications Quarterly*, p 67, Fall 1998.

R. R. Brown,, "Atmospheric Ozone, a Meteorological Factor in Low-Frequency and 160 Meter Propagation," *Communications Quarterly*, Spring 1999.

K. Davies, *Ionospheric Radio* (London: Peter Peregrinus Ltd, 1990). Excellent technical reference.

R. Garcia, S. Solomon, S. Avery, G. C. Reid, "Transport of Nitric Oxide and the D-Region Winter Anomaly," *J. Geophys. Res.*, Vol 92, p 977, 1987.

J. Hall, "Propagation Predictions and Personal Computers," Technical Correspondence, *QST*, Dec 1990, pp 58-59 (description of *IONCAP* as used for ARRL. publications).

E . Harper, *Rhombic Antenna Design* (New York: D. Van Nostrand Co, Inc, 1941).

H. Hertz, *Electric Waves*, translated by D. E. Jones (London: MacMillan, 1893).

R. D. Hunsucker, *Radio Techniques for Probing the Terrestrial Ionosphere* (New York: Springer-Verlag).

R. D. Hunsucker, J. K. Hargreaves, *The High Latitude Ionosphere and Its Effects on Radio Propagation* (Cambridge: Cambridge University Press, 2003).

W. D. Johnston, Computer-calculated and computer-drawn great-circle maps are offered. An 11×14-inch map is custom made for your location. Write to K5ZI, PO Box 640, Organ, NM 88052, tele 505-382-7804.

T.L. Killeen, R.M. Johnsson, "Upper Atmospheric Waves, Turbulence, and Winds: Importance for Mesospheric and Thermospheric Studies," **earth.agu.org/revgeophys/killee00/killee00.html**.

J. L. Lynch, "The Maunder Minimum," *QST*, Jul 1976, pp 24-26.

J. C. Maxwell, *A Treatise on Electricity and Magnetism*, Vols I and II (Oxford: Oxford University Press, 1873).

M. W. Maxwell, *Reflections—Transmission Lines and Antennas* (Newington, CT: ARRL, 1990) [out of print].

M. W. Maxwell, *Reflections II—Transmission Lines and Antennas* (Sacramento, CA: 2001).

L. F. McNamara, *The Ionosphere: Communications, Surveillance, and Direction Finding* (Malabar, FL: Krieger Publishing Company, 1991). Another excellent technical reference on propagation.

L. F. McNamara, *Radio Amateur's Guide to the Ionosphere* (Malabar, FL: Krieger Publishing Company, 1994). Excellent, quite-readable text on HF propagation.

A. K. Paul, "Medium Scale Structure of the F Region," *Radio Science*, Volume 24, No. 3, p. 301, 1989.

W. R. Piggott, K. Rawer, "URSI Handbook of Ionogram Interpretation and Reduction," Report UAG-50. World Data Center A for Solar-Terrestrial Physics, Boulder, CO, 1975.

E. Pocock, "Sporadic-E Propagation at VHF: A Review of Progress and Prospects," *QST*, Apr 1988, pp 33-39.

E. Pocock, "Auroral-E Propagation at 144 MHz," *QST*, Dec 1989, pp 28-32.

E. Pocock, "Propagation Forecasting During Solar Cycle 22," *QST*, Jun 1989, pp 18-20.

G. C. Reid, "Ion Chemistry of the D-region," *Advances in Atomic and Molecular Physics*, Vol 12, Academic Press, 1976.

R. B. Rose, "MINIMUF: A Simplified MUF-Prediction Program for Microcomputers," *QST*, Dec 1982, pp 36-38

M. L. Salby, "Fundamentals of Atmospheric Physics," (Academic Press: Boulder, CO, 1996).

S. C. Shallon, W6EL: *MINIPROP PLUS*, a commercially prepared program written for Amateur Radio users; 11058 Queensland St, Los Angeles, CA 90034-3029.

R. D. Straw, *All the Right Angles* (New Bedford, PA: LTA, 1993). Out of print.

R. D. Straw, "*ASAPS* and *CAPMAN*: HF Propagation-Prediction Software for the IBM PC," *QST*, Dec 1994, pp 79-81.

R. D. Straw, "Heavy-Duty HF Propagation-Prediction/ Analysis Software," Part 1: *QST*, Sep 1996, pp 28-32; Part 2: *QST*, Oct 1996, pp 28-30.

Antenna and Transmission-Line Measurements

The principal quantities measured on transmission lines are line current or voltage, and standing-wave ratio (SWR). You make measurements of current or voltage to determine the power input to the line. SWR measurements are useful in connection with the design of coupling circuits and the adjustment of the match between the antenna and transmission line, as well as in the adjustment of these matching circuits.

For most practical purposes a relative measurement is sufficient. An uncalibrated indicator that shows when the largest possible amount of power is being put into the line is just as useful, in most cases, as an instrument that measures the power accurately. It is seldom necessary to know the actual number of watts going into the line unless the overall efficiency of the system is being investigated. An instrument that shows when the SWR is close to 1:1 is all you need for most impedance-matching adjustments. Accurate measurement of SWR is necessary only in studies of antenna characteristics such as bandwidth, or for the design of some types of matching systems, such as a stub match.

Quantitative measurements of reasonable accuracy demand good design and careful construction in the measuring instruments. They also require intelligent use of the equipment, including a knowledge not only of its limitations but also of stray effects that often lead to false results. Until you know the complete conditions of the measurements, a certain amount of skepticism regarding numerical data resulting from amateur measurements with simple equipment is justified. On the other hand, purely qualitative or relative measurements are easy to make and are reliable for the purposes mentioned above.

LINE CURRENT AND VOLTAGE

A current or voltage indicator that can be used with coaxial line is a useful piece of equipment. It need not be elaborate or expensive. Its principal function is to show when the maximum power is being taken from the transmitter; for any given set of line conditions (length, SWR, etc). This will occur when you adjust the transmitter coupling for maximum current or voltage into the transmission line. Although the final-amplifier plate or collector current meter is frequently used for this purpose, it is not always a reliable indicator. In many cases, particularly with a screen-grid tube in the final stage, minimum loaded plate current does not occur simultaneously with maximum power output.

RF VOLTMETER

You can put together a germanium diode in conjunc-

Fig 1—RF voltmeter for coaxial line.
C1, C2—0.005- or 0.01-µF ceramic.
D1—Germanium diode, 1N34A.
J1, J2—Coaxial fittings, chassis-mounting type.
M1—0-1 milliammeter (more sensitive meter may be used if desired; see text).
R1—6.8 kΩ, composition, 1 W for each 100 W of RF power.
R2—680 Ω, ¹/₂ or 1 W composition.
R3—10 kΩ, ¹/₂ W (see text).

tion with a low-range milliammeter and a few resistors to form an RF voltmeter suitable for connecting across the two conductors of a coaxial line, as shown in **Fig 1**. It consists of a voltage divider, R1-R2, having a total resistance about 100 times the Z_0 of the line (so the power consumed will be negligible) with a diode rectifier and milliammeter connected across part of the divider to read relative RF voltage. The purpose of R3 is to make the meter readings directly proportional to the applied voltage, as nearly as possible, by swamping the resistance of D1, since the diode resistance will vary with the amplitude of the current through the diode.

You may construct the voltmeter in a small metal box, indicated by the dashed line in the drawing, and fitted with coax receptacles. R1 and R2 should be carbon-composition resistors. The power rating for R1 should be 1 W for each 100 W of carrier power in the matched line; separate 1- or 2-W resistors should be used to make up the total power rating required, to the total resistance as given. Any type of resistor can be used for R3; the total resistance should be such that about 10 V dc will be developed across it at full scale. For example, a 0-1 milliammeter would require 10 kΩ, a 0-500 microammeter would take 20 kΩ, and so on. For comparative measurements only, R3 may be a variable resistor so the sensitivity can be adjusted for various power levels.

In constructing such a voltmeter, you should exercise care to prevent inductive coupling between R1 and the loop formed by R2, D1 and C1, and between the same loop and the line conductors in the assembly. With the lower end of R1 disconnected from R2 and grounded to the enclosure, but without changing its position with respect to the loop, there should be no meter indication when full power is going through the line.

If more than one resistor is used for R1, the units should be arranged end-to-end with very short leads. R1 and R2 should be kept $\frac{1}{2}$ inch or more from metal surfaces parallel to the body of the resistor. If you observe these precautions the voltmeter will give consistent readings at frequencies up to 30 MHz. Stray capacitance and stray coupling limit the accuracy at higher frequencies but do not affect the utility of the instrument for comparative measurements.

Calibration

You may calibrate the meter for RF voltage by comparison with a standard such as an RF ammeter. This requires that the line be well matched so the impedance at the point of measurement is equal to the actual Z_0 of the line. Since in that case $P = I^2 Z_0$, the power can be calculated from the current. Then $E = \sqrt{PZ_0}$. By making current and voltage measurements at a number of different power levels, you can obtain enough points to draw a calibration curve for your particular setup.

Fig 2—A convenient method of mounting an RF ammeter for use in a coaxial line. This is a metal-case instrument mounted on a thin bakelite panel. The cutout in the metal clears the edge of the meter by about $\frac{1}{8}$ inch.

RF AMMETERS

Although they are not as widely available as they used to be, if you can find one on the surplus market or at a hamfest, an RF ammeter is a good way to gauge output power. You can mount an RF ammeter in any convenient location at the input end of the transmission line, the principal precaution being that the capacitance to ground, chassis, and nearby conductors should be low. A bakelite-case instrument can be mounted on a metal panel without introducing enough shunt capacitance to ground to cause serious error up to 30 MHz. When installing a metal-case instrument on a metal panel, you should mount it on a separate sheet of insulating material so that there is $\frac{1}{8}$ inch or more separation between the edge of the case and the metal.

A 2-inch instrument can be mounted in a $2 \times 4 \times 4$-inch metal box, as shown in **Fig 2**. This is a convenient arrangement for use with coaxial line. Installed this way, a good quality RF ammeter will measure current with an accuracy that is entirely adequate for calculating power in the line. As discussed above in connection with calibrating RF voltmeters, the line must be closely matched by its load so the actual impedance is resistive and equal to Z_0. The scales of such instruments are cramped at the low end, however, which limits the range of power that can be measured by a single meter. The useful current range is about 3 to 1, corresponding to a power range of about 9 to 1.

SWR Measurements

On parallel-conductor lines it is possible to measure the standing-wave ratio by moving a current (or voltage) indicator along the line, noting the maximum and minimum values of current (or voltage) and then computing the SWR from these measured values. This cannot be done with coaxial line since it is not possible to make measurements of this type inside the cable. The technique is, in fact, seldom used with open lines because it is not only inconvenient but sometimes impossible to reach all parts of the line conductors. Also, the method is subject to considerable error from antenna currents flowing on the line.

Present-day SWR measurements made by amateurs practically always use some form of *directional coupler* or RF-bridge circuit. The indicator circuits themselves are fundamentally simple, but they require considerable care in construction to ensure accurate measurements. The requirements for indicators used only for the adjustment of impedance-matching circuits, rather than actual SWR measurement, are not so stringent, and you can easily make an instrument for this purpose.

BRIDGE CIRCUITS

Two commonly used bridge circuits are shown in **Fig 3**. The bridges consist essentially of two voltage dividers in parallel, with a voltmeter connected between the junctions of each pair of *arms*, as the individual elements are called. When the equations shown to the right of each circuit are satisfied there is no potential difference between the two junctions, and the voltmeter indicates zero voltage. The bridge is then said to be in *balance*.

Taking Fig 3A as an illustration, if R1 = R2, half the applied voltage, E, will appear across each resistor. Then if $R_S = R_X$, $^1/_2 E$ will appear across each of these resistors and the voltmeter reading will be zero. Remember that a matched transmission line has essentially a purely resistive input impedance. Suppose that the input terminals of such a line are substituted for R_X. Then if R_S is a resistor equal to the Z_0 of the line, the bridge will be balanced.

If the line is not perfectly matched, its input impedance will not equal Z_0 and hence will not equal R_S, since you chose the latter to be equal to Z_0. There will then be a difference in potential between points X and Y, and the voltmeter will show a reading. Such a bridge therefore can be used to show the presence of standing waves on the line, because the line input impedance will be equal to Z_0 only when there are no standing waves.

Considering the nature of the incident and reflected components of voltage that make up the actual voltage at the input terminals of the line, as discussed in Chapter 24, it should be clear that when $R_S = Z_0$, the bridge is always in balance for the incident component. Thus the voltmeter does not respond to the incident component at any time but reads only the reflected component (assuming that R2 is very small compared with the voltmeter

Fig 3—Bridge circuits suitable for SWR measurement. At A, Wheatstone type using resistance arms. At B, capacitance-resistance bridge ("Micromatch"). Conditions for balance are independent of frequency in both types.

impedance). The incident component can be measured across either R1 or R2, if they are equal resistances. The standing-wave ratio is then

$$SWR = \frac{E1+E2}{E1-E2} \tag{Eq 1}$$

where E1 is the incident voltage and E2 is the reflected voltage. It is often simpler to normalize the voltages by expressing E2 as a fraction of E1, in which case the formula becomes

$$SWR = \frac{1+k}{1-k} \tag{Eq 2}$$

where k = E2/E1.

The operation of the circuit in Fig 3B is essentially the same, although this circuit has arms containing reactance as well as resistance.

It is not necessary that R1 = R2 in Fig 3A; the bridge can be balanced, in theory, with any ratio of these two resistances provided R_S is changed accordingly. In practice, however, the accuracy is highest when the two are equal; this circuit is most commonly used.

A number of types of bridge circuits appear in **Fig 4**, many of which have been used in amateur products or amateur construction projects. All except that at G can have the generator and load at a common potential. At G, the generator and detector are at a common potential. You may interchange the positions of the detector and trans-

De Sauty/Wein (Micromatch)
(A)

Balance $Z = \dfrac{R C1}{C2}$

Christie/Wheatstone (Antenna — Scope)
(B)

Balance $Z = \dfrac{R2\ R3}{R1}$

Maxwell (Universal)
(C)

Balance R1 Z=R2 R3=L/C

No Discontinuity: $R2 \to \infty$,
$R3 \to 0$, R1=Z

Carey — Foster
(Twin — Lamp, Monomatch Mickey — Match)
(D)

Balance $M = C\ R2\ Z$
$L = M(1 + R1/R2)$

No Discontinuity: $R1 + R2 = Z = \sqrt{L/C}$

Bruene (Collins Radio)
(E)
Balance (Approx.) $Z\ C1\ L_S = M\ R\ (C1+C2)$
$(2\pi f\ L_S \gg R)$
$(L_P = M\ \text{Approx})$

Max. 1% Error: $2\pi f\ L_S \geq 7R$

Phase — Compensated
(F)
Balance: $Z\ R1\ C1 = M = L_P$
$L_S = R1\ R2\ (C1+C2)$

(G)

(H)

Starr's "Hybrid Coil"

Balance: R=Z
(The Differential Capacitor Can Balance Parallel Reactance.)

ANT0921

Fig 4—Various types of SWR indicator circuits and commonly known names of bridge circuits or devices in that they have been used. Detectors (D) are usually semiconductor diodes with meters, isolated with RF chokes and capacitors. However, the detector may be a radio receiver. In each circuit, Z represents the load being measured. (*This information provided by David Geiser, WA2ANU*)

mitter (or generator) in the bridge, and this may be advantageous in some applications.

The bridges shown at D, E, F and H may have one terminal of the generator, detector and load common. Bridges at A, B, E, F, G and H have constant sensitivity over a wide frequency range. Bridges at B, C, D and H may be designed to show no discontinuity (impedance lump) with a matched line, as shown in the drawing. Discontinuities with A, E and F may be small.

Bridges are usually most sensitive when the detector bridges the midpoint of the generator voltage, as in G or H, or in B when each resistor equals the load impedance. Sensitivity also increases when the currents in each leg are equal.

Resistance Bridge

The basic bridge configuration shown in Fig 3B may be home constructed and is reasonably accurate for SWR measurement. A practical circuit for such a bridge is given in **Fig 5** and a representative layout is shown in **Fig 6**. Properly built, a bridge of this design can be used for measurement of SWRs up to about 15:1 with good accuracy.

You should observe these important construction points:
1) Keep leads in the RF circuit short, to reduce stray inductance.
2) Mount resistors two or three times their body diameter away from metal parts, to reduce stray capacitance.
3) Place the RF components so there is as little inductive and capacitive coupling as possible between the bridge arms.

In the instrument shown in Fig 6, the input and line connectors, J1 and J2, are mounted fairly close together so the standard resistor, R_S, can be supported with short leads directly between the center terminals of the connectors. R2 is mounted at right angles to R_S, and a shield partition is used between these two components and the others.

The two 47-kΩ resistors, R5 and R6 in Fig 5, are voltmeter multipliers for the 0-100 microammeter used as an indicator. This is sufficient resistance to make the voltmeter linear (that is, the meter reading is directly proportional to the RF voltage) and no voltage calibration curve is needed. D1 is the rectifier for the reflected volt-

Fig 5—Resistance bridge for SWR measurement. Capacitors are disc ceramic. Resistors are 1/2-watt composition except as noted below.
D1, D2—Germanium diode, high back resistance type (1N34A, 1N270, etc.).
J1, J2—Coaxial connectors, chassis-mounting type.
M1—0-100 dc microammeter.
R1, R2—47 Ω, 1/2-W composition (see text).
R3—See text.
R4—50-kΩ volume control.
R_s—Resistance equal to line Z_0 (1/2 or 1 W composition).
S1—SPDT toggle.

Fig 6—A 2 × 4 × 4-inch aluminum box is used to house this SWR bridge, which uses the circuit of Fig 5. The variable resistor, R4, is mounted on the side. The bridge components are mounted on one side plate of the box and a subchassis formed from a piece of aluminum. The input connector is at the top in this view. R_s is connected directly between the two center posts of the connectors. R2 is visible behind it and perpendicular to it. One terminal of D1 projects through a hole in the chassis so the lead can be connected to J2. R1 is mounted vertically to the left of the chassis in this view, with D2 connected between the junction of R1-R2 and a tie point.

age and D2 is for the incident voltage. Because of manufacturing variations in resistors and diodes, the readings may differ slightly with two multipliers of the same nominal resistance value, so a correction resistor, R3, is included in the circuit. You should select its value so that the meter reading is the same with S1 in either position, when RF is applied to the bridge with the line connection open. In the instrument shown, a value of 1000 Ω was required in series with the multiplier for reflected voltage; in other cases different values probably would be needed and R3 might have to be put in series with the multiplier for the incident voltage. You can determine this by experiment.

The value used for R1 and R2 is not critical, but you should match the two resistors within 1% or 2% if possible. Keep the resistance of R_S as close as possible to the actual Z_0 of the line you use (generally 50 or 75 Ω). Select the resistor by actual measurement with an accurate resistance bridge, if you have one available.

R4 is for adjusting the incident-voltage reading to full scale in the measurement procedure described below. Its use is not essential, but it offers a convenient alternative to exact adjustment of the RF input voltage.

Testing

Measure R1, R2 and R_S with a reliable digital ohmmeter or resistance bridge after completing the wiring. This will ensure that their values have not changed from the heat of soldering. Disconnect one side of the microammeter and leave the input and output terminals of the unit open during such measurements to avoid stray shunt paths through the rectifiers.

Check the two voltmeter circuits as described above, applying enough RF (about 10 V) to the input terminals to give a full-scale reading with the line terminals open. If necessary, try different values for R3 until the reading is the same with S1 in either position.

With J2 open, adjust the RF input voltage and R4 for full-scale reading with S1 in the incident-voltage position. Then switch S1 to the reflected-voltage position. The reading should remain at full scale. Next, short-circuit J2 by touching a screwdriver between the center terminal and the frame of the connector to make a low-inductance short. Switch S1 to the incident-voltage position and readjust R4 for full scale, if necessary. Then throw S1 to the reflected-voltage position, keeping J2 shorted, and the reading should be full scale as before. If the readings differ, R1 and R2 are not the same value, or there is stray coupling between the arms of the bridge. You must read the reflected voltage at full scale with J2 either open or shorted, when the incident voltage is set to full scale in each case, to make accurate SWR measurements.

The circuit should pass these tests at all frequencies at which it is to be used. It is sufficient to test at the lowest and highest frequencies, usually 1.8 or 3.5 and 28 or 50 MHz. If R1 and R2 are poorly matched but the bridge construction is otherwise good, discrepancies in the readings will be substantially the same at all frequencies. A difference in behavior at the low and high ends of the frequency range can be attributed to stray coupling between bridge arms, or stray inductance or capacitance in the arms.

To check the bridge for balance, apply RF and adjust R4 for full scale with J2 open. Then connect a resistor identical with R_S (the resistance should match within 1% or 2%) to the line terminals, using the shortest possible leads. It is convenient to mount the test resistor inside a cable connector (PL-259), a method of mounting that also minimizes lead inductance. When you connect the test resistor the reflected-voltage reading should drop to zero. The incident voltage should be reset to full scale by means of R4, if necessary. The reflected reading should be zero at any frequency in the range to be used. If a good null is obtained at low frequencies but some residual current shows at the high end, the trouble may be the inductance of the test resistor leads, although it may also be caused by stray coupling between the arms of the bridge itself.

If there is a constant low (but not zero) reading at all frequencies the problem is poor matching of the resistance values. Both effects can be present simultaneously. You should make sure you obtain a good null at all frequencies before using your bridge.

Bridge Operation

You must limit the RF power input to a bridge of this type to a few watts at most, because of the power-dissipation ratings of the resistors. If the transmitter has no provision for reducing power output to a very low value—less than 5 W—a simple power-absorber circuit can be made up, as shown in **Fig 7**. Lamp DS1 tends to maintain constant current through the resistor over a fairly

Fig 7—Power-absorber circuit for use with resistance-type SWR bridges when the transmitter has no special provisions for power reduction. For RF powers up to 50 W, DS1 is a 117-V 40-W incandescent lamp and DS2 is not used. For higher powers, use sufficient additional lamp capacity at DS2 to load the transmitter to about normal output; for example, for 250 W output DS2 may consist of two 100-W lamps in parallel. R1 is made from three 1-W 68-Ω resistors connected in parallel. P1 and P2 are cable-mounting coaxial connectors. Leads in the circuit formed by the lamps and R1 should be kept short, but convenient lengths of cable may be used between this assembly and the connectors.

wide power range, so the voltage drop across the resistor also tends to be constant. This voltage is applied to the bridge, and with the constants given is in the right range for resistance-type bridges.

To make a measurement, connect the unknown load to J2 and apply sufficient RF voltage to J1 to give a full-scale incident-voltage reading. Use R4 to set the indicator to exactly full scale. Then throw S1 to the reflected voltage position and note the meter reading. The SWR is then found by using these readings in Eq 1.

For example, if the full-scale calibration of the dc instrument is 100 µA and the reading with S2 in the reflected-voltage position is 40 µA, the SWR is

$$SWR = \frac{100+40}{100-40} = \frac{140}{60} = 2.33:1$$

Instead of calculating the SWR value, you could use the voltage curve in **Fig 8**. In this example the ratio of reflected to forward voltage is 40/100 = 0.4, and from Fig 8 the SWR value is about 2.3:1.

You may calibrate the meter scale in any arbitrary units, so long as the scale has equal divisions. It is the ratios of the voltages, and not the actual values, that determine the SWR.

ANT0924

Fig 8—Chart for finding voltage standing-wave ratio when the ratio of reflected-to-forward voltage or reflected-to-forward power is known.

AVOIDING ERRORS IN SWR MEASUREMENTS

The principal causes of inaccuracies within the bridge are differences in the resistances of R1 and R2, stray inductance and capacitance in the bridge arms, and stray coupling between arms. If the checkout procedure described above is followed carefully, the bridge in Fig 5 should be amply accurate for practical use. The accuracy is highest for low standing-wave ratios because of the nature of the SWR calculation; at high ratios the divisor in the equation above represents the difference between two nearly equal quantities, so a small error in voltage measurement may mean a considerable difference in the calculated SWR.

The standard resistor R_S must equal the actual Z_0 of the line. The actual Z_0 of a sample of line may differ by a few percent from the nominal figure because of manufacturing variations, but this has to be tolerated. In the 50- to 75-Ω range, the RF resistance of a composition resistor of $^1/_2$- or 1-W rating is essentially identical with its dc resistance.

Common-Mode Currents

As explained in Chapter 26, there are two ways in which unwanted *common-mode* (sometimes called *antenna*) currents can flow on the outside of a coaxial line—currents radiated onto the line because of its spatial relationship to the antenna and currents that result from the direct connection between the coax outer conductor and (usually) one side of the antenna. The radiated current usually will not be troublesome if the bridge and the transmitter (or other source of RF power for operating the bridge) are shielded so that any RF currents flowing on the outside of the line cannot find their way into the bridge. This point can be checked by inserting an additional section of line ($^1/_8$ to $^1/_4$ electrical wavelength preferably) of the same Z_0. The SWR indicated by the bridge should not change except for a slight decrease because of the additional line loss. If there is a marked change, you may need better shielding.

Parallel-type currents caused by the connection to the antenna without using a common-mode choke balun will change the SWR with variations in line length, even though the bridge and transmitter are well-shielded and the shielding is maintained throughout the system by the use of coaxial fittings. Often, merely moving the transmission line around will cause the indicated SWR to change. This is because the outside of the coax becomes part of the antenna system—being connected to the antenna at the feed point. The outside shield of the line thus constitutes a load, along with the desired load represented by the antenna itself. The SWR on the line then is determined by the composite load of the antenna and the outside of the coax. Since changing the line length (or position) changes one component of this composite load, the SWR changes too.

The remedy for such a situation is to use a good balun

or to detune the outside of the line by proper choice of length. Note that this is not a *measurement error*, since what the instrument reads is the actual SWR on the line. However, it is an undesirable condition since the line is usually operating at a higher SWR than it should—and would if the parallel-type current on the outside of the coax were eliminated.

Spurious Frequencies

Off-frequency components in the RF voltage applied to the bridge may cause considerable error. The principal components of this type are harmonics and low-frequency subharmonics that may be fed through the final stage of the transmitter driving the bridge. The antenna is almost always a fairly selective circuit, and even though the system may be operating with a very low SWR at the desired frequency, it is almost always mismatched at harmonic and subharmonic frequencies. If such spurious frequencies are applied to the bridge in appreciable amplitude, the SWR indication will be very much in error. In particular, it may not be possible to obtain a null on the bridge with any set of adjustments of the matching circuit. The only remedy

Fig 9—Methods of determining ¹/₄ and ¹/₂-λ line lengths. At A, ¹/₄-λ open-circuited line; at B, ¹/₄-λ shorted and ¹/₂-λ open-circuited line.

is to filter out the unwanted components by increasing the selectivity of the circuits between the transmitter final amplifier and the bridge.

MEASURING LINE LENGTH

The following material is taken from information in September 1985 *QST* by Charlie Michaels, W7XC (see Bibliography).

There is a popular myth that one may prepare an open quarter-wave line by connecting a loop of wire to one end and trimming the line to resonance (as indicated by a dip meter). This actually yields a line with capacitive reactance equal to the inductive reactance of the loop: a 4-inch wire loop yields a line 82.8° line at 18 MHz; a 2-inch loop yields an 86° line. As the loop size is reduced, line length approaches—but never equals—90°.

To make a quarter-wave open line, parallel connect a coil and capacitor that resonate at the required frequency (see **Fig 9A**). After adjusting the network to resonance, do not make further network adjustments. Open the connection between the coil and capacitor and series connect the line to the pair. Start with a line somewhat longer than required, and trim it until the circuit again resonates at the desired frequency. For a shorted quarter-wave line or an open half-wave line, connect the line in parallel with the coil and capacitor (see Fig 9B).

Another method to accurately measure a coaxial transmission line length uses one of the popular "SWR analyzers," portable hand-held instruments with a tunable low-power signal generator and an SWR bridge. While an SWR analyzer cannot compute the very high values of SWR at the input of a shorted quarter-wave line at the fundamental frequency, most include another readout showing the magnitude of the impedance. This is very handy for finding a low-impedance dip, rather than a high-impedance peak.

At the operating frequency, a shorted quarter-wave line results in a high-impedance open-circuit at the input to that line. At twice the frequency, where the line is now one-half wave long electrically, the instrument shows a low-impedance short-circuit. However, when you are pruning a line to length by cutting off short pieces at the end, it is inconvenient to have to install a short before measuring the response. It is far easier to look for the dip in impedance when a quarter-wave line is terminated in an open circuit.

Again, the strategy is to start with a line physically a little longer than a quarter-wave length. A good rule of thumb is to cut the line 5% longer to take into account the variability in the velocity factor of a typical coax cable. Compute this using:

Length (feet) = 0.25 × 1.05 × VF × 984/Freq = VF/Freq

where

Freq is in MHz

VF is the velocity factor in %.

Plug the coax connector installed at one end of the line into the SWR analyzer and find the frequency for the

impedance dip. Prune the line by snipping off short pieces at the end. Once you've pruned the line to the desired frequency, connect the short at the end of the line and recheck for a short circuit at twice the fundamental frequency. Seal the shorted end of the coax and you're done.

REFLECTOMETERS

Low-cost *reflectometers* that do not have a guaranteed wattmeter calibration are not ordinarily reliable for accurate numerical measurement of standing-wave ratio. They are, however, very useful as aids in the adjustment of matching networks, since the objective in such adjustment is to reduce the reflected voltage or power to zero. Relatively inexpensive devices can be used for this, since only good bridge balance is required, not actual calibration of SWR. Bridges of this type are usually frequency-sensitive that is, the meter response increase with increasing frequency for the same applied voltage. When matching and line monitoring, rather than SWR measurement, is the principal use of the device, this is not a serious handicap.

Various simple reflectometers, useful for matching and monitoring, have been described from time to time in *QST* and in *The ARRL Handbook*. Because most of these are frequency sensitive, it is difficult to calibrate them accurately for power measurement, but their low cost and suitability for use at moderate power levels, combined with the ability to show accurately when a matching circuit has been properly adjusted, make them a worthwhile addition to the amateur station.

The Tandem Match—An Accurate Directional Wattmeter

Most SWR meters are not very accurate at low power levels because the detector diodes do not respond to low voltage in a linear fashion. This design uses a compensating circuit to cancel diode nonlinearity. It also provides peak detection for SSB operation and direct SWR readout that does not vary with power level. The following information is condensed from an article by John Grebenkemper, KI6WX, in January 1987 *QST*.

DESIGN PRINCIPLES

Directional wattmeters for Amateur Radio use consist of three basic elements: a directional coupler, a detector and a signal-processing and display circuit. A directional coupler samples forward and reflected-power components on a transmission line. An ideal directional coupler would provide signals proportional to the forward and reflected voltages (independent of frequency), which could then be used to measure forward and reflected power over a wide frequency range. The best contemporary designs work over two decades of frequency.

The detector circuit provides a dc output voltage proportional to the ac input voltage. Most directional watt-meters use a single germanium diode as the detector element. A germanium, rather than silicon, diode is used to minimize diode nonlinearity at low power levels. Diode non-linearity still causes SWR measurement errors unless it is compensated ahead of the display circuit. Most directional wattmeters do not work well at low power levels because of diode nonlinearity.

The signal-processing and display circuits compute and display the SWR. There are a number of ways to perform this function. Meters that display only the forward and reflected power require the operator to compute the SWR manually. Many instruments require that the operator adjust the meter to a reference level while measuring forward power, then switch to measure reflected power on a special scale that indicates SWR. Meters that directly compute the SWR using analog signal-processing circuits have been described by Fayman, Perras,

Table 1
Performance Specifications for the Tandem Match

Power range: 1.5 to 1500 W
Frequency range: 1.8 to 54 MHz
Power accuracy: Better than ± 10% (± 0.4 dB)
SWR accuracy: Better than ± 5%
Minimum SWR: Less than 1.05:1
Power display: Linear, suitable for use with either analog or digital meters
Calibration: Requires only an accurate voltmeter

Fig 10—The Tandem Match uses a pair of meters to display net forward power and true SWR simultaneously.

ANT0926

Fig 11—Block diagram of the Tandem Match.

Leenerts and Bailey (see the Bibliography at the end of this chapter).

The next section takes a brief look at several popular circuits that accomplish the functions above and compares them to the circuits used in the Tandem Match. The design specifications of the Tandem Match are shown in **Table l**, and a block diagram is shown in **Fig 11**.

CIRCUIT DESCRIPTION

A directional coupler consists of an input port, an output port and a coupled port. The device takes a portion of the power flowing from the input port to the output port and directs it to the coupled port, but *none* of the power flowing from the output port to the input port is directed to the coupled port.

There are several terms that define the performance of a directional coupler:

1) *Insertion loss* is the amount of power that is lost as the signal flows from the input port to the output port. Insertion loss should be minimized so the coupler doesn't dissipate a significant amount of the transmitted power.

2) *Coupling factor* is the amount of power (or voltage) that appears at the coupled port relative to the amount of power (or voltage) transferred from the input port to the output port. The "flatness" (with frequency) of the coupling factor determines how accurately the directional wattmeter can determine forward and reflected power over a range of frequencies.

3) *Isolation* is the amount of power (or voltage) that appears at the coupled port relative to the amount of power (or voltage) transferred from the output port to the input port.

4) *Directivity* is the isolation less the coupling factor. Directivity dictates the minimum measurable SWR. A directional coupler with 20 dB of directivity measures a 1:1 SWR as l.22:l, but one with 30 dB measures a 1:1 SWR as 1.07:1.

The directional coupler most commonly used in amateur radio was first described in 1959 by Bruene in *QST* (see Bibliography). The coupling factor was fairly flat (±l dB), and the directivity was about 20 dB for a Bruene coupler measured from 3 to 30 MHz. Both factors limit the accuracy of the Bruene coupler for measuring low values of power and SWR. It is a simple directional coupler, however, and it works well over a wide frequency range if great precision is not required.

The coupler used in the Tandem Match (see **Fig 12**) consists of a pair of toroidal transformers connected in tandem. The configuration was patented by Carl G. Sontheimer and Raymond E. Fredrick (US Patent no. 3,426,298, issued February 4, 1969). It has been described by Perras, Spaulding (see Bibliography) and others. With coupling factors of 20 dB or greater, this coupler is suitable for sampling both forward and reflected power.

The configuration used in the Tandem Match works well over the frequency range of 1.8 to 54 MHz, with a

Fig 12—Simplified diagram of the Tandem Match directional coupler. At A, a schematic of the two transformers. At B, an equivalent circuit.

nominal coupling factor of 30 dB. Over this range, insertion loss is less than 0.1 dB. The coupling factor is flat to within ± 0.1 dB from 1.8 to 30 MHz, and increases to only ±0.3 dB at 50 MHz. Directivity exceeds 35 dB from 1.8 to 30 MHz and exceeds 26 dB at 50 MHz.

The low-frequency limit of this directional coupler is determined by the inductance of the transformer secondary windings. The inductive reactance should be greater than 150 Ω (three times the line characteristic impedance) to reduce insertion loss. The high-frequency limit of this directional coupler is determined by the length of the transformer windings. When the winding length approaches a significant fraction of a wavelength, coupler performance deteriorates.

The coupler described here may overheat at 1500 W on 160 meters (because of the high circulating current in the secondary of T2). The problem could be corrected by using a larger core or one with greater permeability. A larger core would require longer windings; that option would decrease the high-frequency limit.

Fig 13—Simplified diagram of the detector circuit used in the Tandem Match. The output voltage, V_o is approximately equal to the input voltage. D1 and D2 must be a matched pair (see text). The op amp should have a low offset voltage (less than 1 mV), a low leakage current (less than 1 nA), and be stable over time and temperature. The resistor and capacitor in the feedback path assure that the op amp will be stable.

Fig 14—Simplified diagrams of the log circuit at A and the antilog circuit at B.

Fig 15—Schematic diagram for the Tandem Match directional wattmeter. Parts identified as RS are from RadioShack. For other parts sources, see Table 3. See Fig 17 for construction of 50-Ω loads at J1 and J2.

D1, D2—Matched pair 1N5711, or equivalent.
D3, D4—Matched pair 1N5711, or equivalent.
D6, D7—1N34A.
D8-D14—1N914.
FB—Ferrite bead, Amidon FB-73-101 or equiv.

J1, J2—SO-239 connector.
J3, J4—Open-circuit jack.
M1, M2—50 μA panel meter, RS 270-1751.
Q1, Q3, Q4—2N2222 or equiv.
Q2—2N2907 or equiv.

ANT0930

Except as indicated, decimal
values of capacitance are
In microfarads (μ F); others
are in picofarads (pF);
resistances are in ohms;
k= 1,000 , M= 1,000,000

* 4 - 200 Ω , 2%, 1/2 W
    NONINDUCTIVE RESISTORS
    MOUNTED ON REAR OF SO-239

LM334, LM336

R1, R2, R5—100 kΩ, 10-turn, cermet Trimpot.
R3, R4—10 kΩ, 10-turn, cermet Trimpot.
U1-U3—TLC27L4 or TLC27M4 quad op amp
  (Texas Instruments).
U4—TLC27L2 or TLC27M2 dual op amp.

U5-U7—CA3146 quad transistor array.
U8—LM334 adjustable current source.
U9-U10—LM336 2.5-V reference diode. See text.

Detector Circuits

Most amateur directional wattmeters use a germanium diode detector to minimize the forward voltage drop. Detector voltage drop is still significant, however, and an uncompensated diode detector does not respond to small signals in a linear fashion. Many directional wattmeters compensate for diode nonlinearity by adjusting the meter scale.

The effect of underestimating detected power worsens at low power levels. Under these conditions, the ratio of the forward power to the reflected power is overestimated because the reflected power is always less than the forward power. This results in an instrument that underestimates SWR, particularly as power is reduced. A directional wattmeter can be checked for this effect by measuring SWR at several power levels: the SWR should be independent of power level.

The Tandem Match uses a feedback circuit to compensate for diode nonlinearity. A simplified diagram of the compensated detector is shown in **Fig 13**. When used with the 30-dB directional coupler, the output voltage of this circuit tracks the square root of power over a range from 10 mW to 1.5 kW. The compensated diode detector tracks the peak input voltage down to 30 mV, while an uncompensated germanium-diode detector shows significant errors at peak inputs of 1 V and less. More information about compensated detectors appears in Grebenkemper's *QEX* article, "Calibrating Diode Detectors" (see Bibliography).

The compensation circuit uses the voltage across a feedback diode, D2, to compensate for the voltage drop across the detector diode, D1. (The diodes must be a matched pair.) The average current through D1 is determined by the detector diode load resistor, R1. The peak current through this diode is several times larger than the average current; therefore, the current through D2 must be several times larger than the average current through D1 to compensate adequately for the peal voltage drop across D1. This is accomplished by making the feedback-diode load resistor, R2, several times smaller than R1. The voltage at the output of the compensated detector approximates the peak RF voltage at the input. For Schottky barrier diodes and a 1 MΩ detector-diode load resistor, a 5:1 ratio of R1 to R2 is nearly optimal.

Signal-Processing and Display Circuits

The signal-processing circuitry calculates and displays transmission-line power and SWR. When measuring forward power, most directional wattmeters display the actual forward power present in the transmission line, which is the sum of forward and reflected power if a match exists at the input end of the line. Transmission-line forward power is very close to the net forward power (the actual power delivered to the line) so long as the SWR is low. As the SWR increases, however, forward power becomes an increasingly poor measure of the power delivered to the load. At an SWR of 3:1, a forward power reading of 100 W implies that only 75 W is delivered to the load (the reflected power is 25 W), assuming the transmission-line loss is zero.

The Tandem Match differs from most wattmeters in that *it displays the net forward power, rather than the sum of forward and reflected power.* This is the quantity that must be optimized to result in maximum radiated power (and which concerns the FCC).

The Tandem Match directly computes and displays the transmission-line SWR on a linear scale. As the displayed SWR is not affected by changes in transmitter power, a matching network can be simply adjusted to minimize SWR. Transmatch adjustment requires only a few watts.

The heart of the Tandem Match signal-processing circuit is the analog logarithm and antilogarithm circuitry shown in **Fig 14**. The circuit is based on the fact that collector current in a silicon transistor is proportional to the exponential (antilog) of its base-emitter voltage over a range of collector currents from a few nanoamperes to a few milliamperes when the collector-base voltage is zero (see Gibbons and Horn reference in the Bibliography). Variations of this circuit are used in the squaring circuits to convert voltage to power and in the divider circuit used to compute the SWR. With good op amps, this circuit will work well for input voltages from less than 100 mV to greater than 10 V.

(For the Tandem Match, "good" op amps are quad-packaged, low-power-consumption, unity-gain-stable parts with input bias less than 1 nA and offset voltage less than 5 mV. Op amps that consume more power than those shown may require changes to the power supply.)

CONSTRUCTION

The schematic diagram for the Tandem Match is shown in **Fig 15** (see pages 14 and 15). The circuit is designed to operate from batteries and draw very little power. Much of the circuitry is of high impedance, so take care to isolate it from RF fields. House it in a metal case. Most problems in the prototype were caused by stray RF in the op-amp circuitry.

Directional Coupler

The directional coupler is constructed in its own small ($2^3/_4 \times 2^3/_4 \times 2^1/_4$-inch) aluminum box (see **Fig 16**). Two pairs of S0-239 connectors are mounted on opposite sides of the box. A piece of PC board is run diagonally across the box to improve coupler directivity. The pieces of RG-8X coaxial cable pass through holes in the PC board.

(Note: Some brands of "mini 8" cable have extremely low breakdown voltage ratings and are unsuitable to carry even 100 W when the SWR exceeds 1:1. See the subsequent section, "High-Power Operation," for details of a coupler made with RG-8 cable.)

Begin by constructing T1 and T2, which are identi-

Fig 16—Construction details for the directional coupler.

Fig 17—The parallel load resistors mounted on an SO-239 connector. Four 200-Ω, 2%, $^1/_2$-W resistors are mounted in parallel to provide a 50-Ω detector load.

cal except for their end connections. Refer to Fig 16. The primary for each transformer is the center conductor of a length of RG-8X coaxial cable. Cut two cable lengths sufficient for mounting as shown in the figure. Strip the cable jacket, braid and dielectric as shown. The cable braid is used as a Faraday shield between the transformer windings, so it is only grounded at one end. *Important— connect the braid only at one end or the directional-coupler circuit will not work properly!* Wind two transformer secondaries, each 31 turns of #24 enameled wire on an Amidon T50-3 or equivalent powdered-iron core.

Slip each core over one of the prepared cable pieces (including both the shield and the outer insulation). Mount and connect the transformers as shown in Fig 16, with the wire running through separate holes in the copper-clad PC board. The directional coupler can be mounted separately

Fig 18—Diode matching test setup.

from the rest of the circuitry if desired. If so, use two coaxial cables to carry the forward and reflected-power signals from the directional coupler to the detector inputs. Be aware, however that any losses in the cables will affect power readings.

This directional coupler has not been used at power levels in excess of 100 W. For more information about using the Tandem Match at high power levels, see the section, "High-Power Operation."

Detector and Signal-Processing Circuits

The detector and signal-processing circuits were constructed on a perforated, copper-clad circuit board. These circuits use two separate grounds—*it is extremely important that the grounds be isolated as shown in the circuit diagram.* Failure to do so may result in faulty circuit operation. Separate grounds prevent RF currents on the cable braid from affecting the op-amp circuitry.

The directional coupler requires good 50-Ω loads. They are constructed on the back of female UHF chassis connectors where the cables from the directional coupler enter the wattmeter housing. Each load consists of four 200-Ω resistors connected from the center conductor of the UHF connector to the four holes on the mounting flange, as shown in **Fig 17**. The detector diode is then run from the center conductor of the connector to the 100-pF and 1000-pF bypass capacitors, which are mounted next to the connector. The response of this load and detector combination measures flat to beyond 500 MHz.

Schottky-barrier diodes (type 1N5711) were used in this design because they were readily available. Any RF-detector diode with a low forward voltage drop (less than 300 mV) and reverse break-down voltage greater than 30 V could be used. (Germanium diodes could be used in this circuit, but performance will suffer. If germanium diodes are used, reduce the resistance values for the detector-diode and feedback-diode load resistors by a factor of 10.)

The detector diodes must be matched. This can be done with dc, using the circuit shown in **Fig 18**. Use a high-impedance voltmeter (10 MΩ or greater). For this project, diodes are matched when their forward voltage drops are equal (within a few millivolts). Diodes from the same batch will probably be sufficiently matched.

Table 2
Range-Switch Resistor Values

Full-Scale Power Level (W)	Range Resistor (1% Precision) (kΩ)
1	2.32
2	3.24
3	4.02
5	5.23
10	7.68
15	9.53
20	11.0
25	12.7
30	14.0
50	18.7
100	28.7
150	37.4
200	46.4
250	54 9
300	63.4
500	100.0
1000	237.0
1500	649.0
2000	Open

The rest of the circuit layout is not critical, but keep the lead lengths of the 0.001 and 0.01-pF bypass capacitors short. The capacitors provide additional bypassing for the op-amp circuitry. D6 and D7 form a voltage doubler to detect the presence of a carrier. When the forward power exceeds 1.5 W, Q3 switches on and stays on until about 10 seconds after the carrier drops. (A connection from TP7 to TP9 forces the unit on, even with no carrier present.) The regulated references of +2.5 V and −2.5 V generated by the LM334 and two LM336s are critical. Zener-diode substitutes would significantly degrade performance.

The four op amps in U1 compensate for the nonlinearity of the detector diodes. D1-D2 and D3-D4 are the matched diode pairs discussed above. A RANGE switch selects the meter range. (A six-position switch was used here because it was handy.) The resistor values for the RANGE switch are shown in **Table 2**. Full-scale input power gives an output at U1C or U1D of 7.07 V. The forward and reflected-power detectors are zeroed with R1 and R2.

The forward and reflected-detector voltages are squared by U2, U5 and U6 so that the output voltages are proportional to forward and reflected power. The gain constants are adjusted using R3 and R4 so that an input of 7.07 V to the squaring circuit gives an output of 5 V. The difference between these two voltages is used by U4B to yield an output that is proportional to the power delivered to the transmission line. This voltage is peak detected

(by an RC circuit connected to the OPERATE position of the MODE switch) to hold and indicate the maximum power during CW or SSB transmissions. SWR is computed from the forward and reflected voltages by U3, U4 and U7. When no carrier is present, Q4 forces the SWR reading to be zero (that is, when the forward power is less than 2% of the full-scale setting of the RANGE switch). The SWR computation circuit gain is adjusted by R5. The output is peak detected in the OPERATE mode to steady the SWR reading during CW or SSB transmissions.

Transistor arrays (U5, U6 and U7) are used for the log and antilog circuits to guarantee that the transistors will be well matched. Discrete transistors may be used, but accuracy may suffer. A three-position toggle switch selects the three operating modes. In the OPERATE mode, the power and SWR outputs are peak detected and held for a few seconds to allow meter reading during actual transmissions. In the TUNE mode, the meters display instantaneous output power and SWR.

A digital voltmeter is used to obtain more precise readings than are possible with analog meters. The output power range is 0 to 5 V (0 V = 0 W and 5 V = full scale). SWR output varies from 1 V (SWR = 1:1) to 5 V (SWR = 5:1). Voltages above 5 V are unreliable because of voltage limiting in some of the op amp circuits.

Calibration

The directional wattmeter can be calibrated with an accurate voltmeter. All calibration is done with dc voltages. The directional-coupler and detector circuits are inherently accurate if correctly built. To calibrate the wattmeter, use the following procedure:

1) Set the MODE switch to TUNE and the RANGE switch to 100 W or less.
2) Jumper TP7 to TP8. This turns the unit on.
3) Jumper TP1 to TP2. Adjust R1 for 0 V at TP3.
4) Jumper TP4 to TP5. Adjust R2 for 0 V at TP6.
5) Adjust R1 for 7.07 V at TP3.
6) Adjust R3 for 5.00 V at TP9, or a full-scale reading on M1.
7) Adjust R2 for 7.07 V at TP6.
8) Adjust R4 for 0 V at TP9, or a zero reading on M1.
9) Adjust R2 for 4.71 V at TP6.
10) Adjust R5 for 5.00 V at TP10, or a full-scale reading on M2.
11) Set the RANGE switch to its most sensitive scale.
12) Remove the jumpers from TP1 to TP2 and TP4 to TP5.
13) Adjust R1 for 0 V at TP3.
14) Adjust R2 for 0 V at TP6.
15) Remove the jumper from TP7 to TP8.

This completes the calibration procedure. This procedure has been found to equal calibration with expensive laboratory equipment. The directional wattmeter should now be ready for use.

ACCURACY

Performance of the Tandem Match has been compared to other well-known directional couplers and laboratory test equipment, and it equals any amateur directional wattmeter tested. Power measurement accuracy compares well to a Hewlett-Packard HP-436A power meter. The HP meter has a specified measurement error of less than ± 0.05 dB. The Tandem Match tracked the HP436A within +0.5 dB from 10 mW to 100 W, and within ± 0.1 dB from 1 W to 100 W. The unit was not tested above 100 W because a transmitter with a higher power rating was not available.

SWR performance was equally good when compared to the SWR calculated from measurements made with the HP436A and a calibrated directional coupler. The Tandem Match tracked the calculated SWR within ± 5% for SWR values from 1:1 to 5:1. SWR measurements were made at 8 W and 100 W.

OPERATION

Connect the Tandem Match in the 50-Ω line between the transmitter and the antenna matching network (or antenna if no matching network is used). Set the RANGE switch to a range greater than the transmitter output rating and the MODE switch to TUNE. When the transmitter is keyed, the Tandem Match automatically switches on and indicates both power delivered to the antenna and SWR on the transmission line. When no carrier is present, the OUTPUT POWER and SWR meters indicate zero.

The OPERATE mode includes RC circuitry to momentarily hold the peak-power and SWR readings during CW or SSB transmissions. The peak detectors are not ideal, so there could be about 10% variation from the actual power peaks and the SWR reading. The SWR ×10 mode increases the maximum readable SWR to 50:1. This range should be sufficient to cover any SWR value that occurs in amateur use. (A 50-foot open stub of RG-8 yields a measured SWR of only 43:1, or less, at 2.4 MHz because of cable loss. Higher frequencies and longer cables exhibit a lesser maximum SWR.)

It is easy to use the Tandem Match to adjust an antenna matching network: Adjust the transmitter for minimum output power (at least 1.5 W). With the carrier on and the MODE switch set to TUNE or SWR ×10, adjust the matching network for minimum SWR. Once the minimum SWR is obtained, set the transmitter to the proper operating mode and output power. Place the Tandem Match in the OPERATE mode.

DESIGN VARIATIONS

There are several ways in which this design could be enhanced. The most important is to add UHF capability. This would require a new directional-coupler design for the band of interest. (The existing detector circuit should work to at least 500 MHz.)

Those who desire a low-power directional wattmeter

can build a directional coupler with a 20-dB coupling factor by decreasing the transformer turns ratio to 10:1. That version should be capable of measuring output power from 1 mW to about 150 W (and it should switch on at about 150 mW).

This change should also increase the maximum operating frequency to about 150 MHz (by virtue of the shorter transformer windings). If you desire 1.8-MHz operation, it may be necessary to change the toroidal core material for sufficient reactance (low insertion loss).

The Tandem Match circuit can accommodate coaxial cable with a characteristic impedance other than 50 Ω. The detector terminating resistors, transformer secondaries and range resistors must change to match the new design impedance.

The detector circuitry can be used (without the directional coupler) to measure low-level RF power in 50-Ω circuits. RF is fed directly to the forward detector (J1, Fig 15), and power is read from the output power meter. The detector is quite linear from 10 μW to 1.5 W.

HIGH-POWER OPERATION

This material was condensed from information by Frank Van Zant, KL7IBA, in July 1989 *QST*. In April 1988, Zack Lau, W1VT, described a directional-coupler circuit (based on the same principle as Grebenkemper's circuit) for a QRP transceiver (see the Bibliography at the end of this chapter). The main advantage of Lau's circuit is a very low parts count.

Grebenkemper used complex log-antilog amplifiers to provide good measurement accuracy. This application gets away from complex circuitry, but retains reasonable measurement accuracy over the 1 to 1500-W range. It also forfeits the SWR-computation feature. Lau's coupler uses ferrite toroids. It works well at low power levels, but the ferrite toroids heat excessively with high power, causing erratic meter readings and the potential for burned parts.

The Revised Design

Powdered-iron toroids are used for the transformers in this version of Lau's basic circuit. The number of turns on the secondaries was increased to compensate for the lower permeability of powdered iron.

Two meters display reflected and forward power (see **Fig 19**). The germanium detector diodes (D1 and D2—1N34) provide fairly accurate meter readings, particularly if the meter is calibrated (using R3, R4 and R5) to place the normal transmitter output at mid scale. If the winding sense of the transformers is reversed, the meters are transposed (the forward-power meter becomes the reflected-power meter, and vice versa).

Construction

Fig 20 shows the physical layout of the coupler. The pickup unit is mounted in a $3^1/_2 \times 3^1/_2 \times 4$-inch box. The meters, PC-mount potentiometers and HIGH/LOW power

Fig 19—Schematic diagram of the high-power directional coupler. D1 and D2 are germanium diodes (1N34 or equiv). R1 and R2 are 47 or 51-Ω, ¹/₂-W resistors. C1 and C2 have 500-V ratings. The secondary windings of T1 and T2 each consist of 40 turns of #26 to #30 enameled wire on T-68-2 powdered-iron toroid cores. If the coupler is built into an existing antenna tuner, the primary of T1 can be part of the tuner coaxial output line. The remotely located meters (M1 and M2) are connected to the coupler box at J1 and J2 via P1 and P2.

switch are mounted in a separate box or a compartment in an antenna tuner. Parts for this project are available from the suppliers listed in **Table 3**.

The primary windings of Tl and T2 are constructed much as Grebenkemper described, but use RG-8 with its jacket removed so that the core and secondary winding may fit over the cable. The braid is wrapped with fiberglass tape to insulate it from the secondary winding. An excellent alternative to fiberglass tape—with even higher RF voltage-breakdown characteristics—is ordinary plumber's Teflon pipe tape, available at most hardware stores.

The transformer secondaries are wound on T-68-2 powdered-iron toroid cores. They are 40 turns of #26 to #30 enameled wire spread evenly around each core. By using #26 to #30 wire on the cores, the cores slip over the tape-wrapped RG-8 lines. With #26 wire on the toroids, a single layer of tape (slightly more with Teflon tape) over the braid provides an extremely snug fit for the core. Use care when fitting the cores onto the RG-8 assemblies.

After the toroids are mounted on the RG-8 sections,

Fig 20—Directional-coupler construction details. Grommets or feedthrough insulators can be used to route the secondary winding of T1 and T2 through the PC board shield. A 3 ¹/₂ × 3 ¹/₂ × 4-inch box serves as the enclosure.

Table 3
Parts Sources
(Also see Chapter 21)

Components	Source
TLC-series and CA3146 ICs	Newark Electronics 4801 N Ravenswood St Chicago, IL 60640 773-784-5100
LM334, LM336, 1% resistors, trimmer potentiometers	Digi-Key Corporation 701 Brooks Ave S PO Box 677 Thief River Falls, MN 56701 800-344-4539
Toroid cores, Fiberglass tape	Amidon Associates 240 & 250 Briggs Ave Costa Mesa, CA 92626 714-850-4660
Meters	Fair Radio Sales PO Box 1105 Lima, OH 45804 419-227-6573
Toroid cores	Palomar Engineers PO Box 462222 Escondido, CA 92046 760-747-3343
0-150/1500-W-scale meters, A&M model no. 255-138, 1N5711 diodes	Surplus Sales of Nebraska 1502 Jones St Omaha, NE 68102 402-346-4750

coat the assembly with General Cement Corp Polystyrene Q Dope, or use a spot or two of RTV sealant to hold the windings in place and fix the transformers on the RG-8 primary windings.

Mount a PC-board shield in the center of the box, between T1 and T2, to minimize coupling between the transformers. Suspend T1 between the SO-239 connectors and T2 between two standoff insulators. The detector circuits (C1, C2, D1, D2, R1 and R2) are mounted inside the coupler box as shown.

Calibration, Tune Up and Operation

The coupler has excellent directivity. Calibrate the meters for various power levels with an RF ammeter and a 50-Ω dummy load. Calculate I^2R for each power level, and mark the meter faces accordingly. Use R3, R4 and R5 to adjust the meter readings within the ranges. Diode nonlinearities are thus taken into account, and Grebenkemper's signal-processing circuits are not needed for relatively accurate power readings. Start the tune-up process using about 10 W, adjust the antenna tuner for minimum reflected power, and increase power while adjusting the tuner to minimize reflected power.

This circuit has been built into several antenna tuners with good success. The instrument works well at 1.5-kW output on 1.8 MHz. It also works well from 3.5 to 30 MHz with 1.2 and 1.5-kW output.

The antenna is easily tuned for a 1:1 SWR using the null indication provided. Amplifier settings for a matched antenna, as indicated with the wattmeter, closely agreed with those for a 50-Ω dummy load. Checks with a Palomar noise bridge and a Heath Antenna Scope also verified these findings. This circuit should handle more than 1.5 kW, as long as the SWR on the feed line through the wattmeter is kept at or near 1:1. (On one occasion high power was applied while the antenna tuner was not coupled to a load. Naturally the SWR was extremely high, and the output transformer secondary winding opened like a fuse. This resulted from the excessively high voltage across the secondary. The damage was easily and quickly repaired.)

An Inexpensive VHF Directional Coupler

Precision in-line metering devices capable of reading forward and reflected power over a wide range of frequencies are very useful in amateur VHF and UHF work, but their rather high cost puts them out of the reach of many VHF enthusiasts. The device shown in Figs 14 through 16 is an inexpensive adaptation of their basic principles. It can be made for the cost of a meter, a few small parts, and bits of copper pipe and fittings that can be found in the plumbing stocks at many hardware stores.

Construction

The sampler consists of a short section of handmade coaxial line, in this instance, of 50 Ω impedance, with a reversible probe coupled to it. A small pickup loop built into the probe is terminated with a resistor at one end and a diode at the other. The resistor matches the impedance of the loop, not the impedance of the line section. Energy picked up by the loop is rectified by the diode, and the resultant current is fed to a meter equipped with a calibration control.

The principal metal parts of the device are a brass plumbing T, a pipe cap, short pieces of $^3/_4$-inch ID and $^5/_{16}$-inch OD copper pipe, and two coaxial fittings. Other available tubing combinations for 50-Ω line may be usable. The ratio of outer conductor ID to inner conductor OD should be 2.4/1. For a sampler to be used with other

Fig 21—Circuit diagram for the line sampler.
C1—500-pF feedthrough capacitor, solder-in type.
C2—1000-pF feedthrough capacitor, threaded type.
D1—Germanium diode 1N34, 1N60, 1N270, 1N295, or similar.
J1, J2—Coaxial connector, type N (UG-58A).
L1—Pickup loop, copper strap 1-inch long × $^{3}/_{16}$-inch wide. Bend into "C" shape with flat portion $^{5}/_{8}$-inch long.
M1—0-100 µA meter.
R1—Composition resistor, 82 to 100 Ω. See text.
R3—50-kΩ composition control, linear taper.

Fig 22—Major components of the line sampler. The brass T and two end sections are at the upper left in this picture. A completed probe assembly is at the right. The N connectors have their center pins removed. The pins are shown with one inserted in the left end of the inner conductor and the other lying in the right foreground.

impedances of transmission line, see Chapter 24 for suitable ratios of conductor sizes. The photographs and **Fig 21** show construction details.

Soldering of the large parts can be done with a 300-watt iron or a small torch. A neat job can be done if the inside of the T and the outside of the pipe are tinned before assembling. When the pieces are reheated and pushed together, a good mechanical and electrical bond will result. If a torch is used, go easy with the heat, as an overheated and discolored fitting will not accept solder well.

Coaxial connectors with Teflon or other heat-resistant insulation are recommended. Type N, with split-ring retainers for the center conductors, are preferred. Pry the split-ring washers out with a knife point or small screwdriver. Don't lose them, as they'll be needed in the final assembly.

The inner conductor is prepared by making eight radial cuts in one end, using a coping saw with a fine-toothed blade, to a depth of $^{1}/_{2}$ inch. The fingers so made are then bent together, forming a tapered end, as shown in **Figs 22** and **23**. Solder the center pin of a coaxial fitting into this, again being careful not to overheat the work.

In preparation for soldering the body of the coax connector to the copper pipe, it is convenient to use a similar fitting clamped into a vise as a holding fixture. Rest the T assembly on top, held in place by its own weight. Use the partially prepared center conductor to assure that the coax connector is concentric with the outer conductor. After being sure that the ends of the pipe are cut exactly perpendicular to the axis, apply heat to the coax fitting, using just enough so a smooth fillet of solder can be formed where the flange and pipe meet.

Before completing the center conductor, check its length. It should clear the inner surface of the connector by the thickness of the split ring on the center pin. File to length; if necessary, slot as with the other end, and solder the center pin in place. The fitting can now be soldered onto the pipe, to complete the 50-Ω line section.

The probe assembly is made from a $1^{1}/_{2}$ inch length of the copper pipe, with a pipe cap on the top to support the upper feedthrough capacitor, C2. The coupling loop is mounted by means of small Teflon standoffs on a copper disc, cut to fit inside the pipe. The disc has four small tabs around the edge for soldering inside the pipe. The diode, D1, is connected between one end of the loop and

Fig 23—Cross-section view of the line sampler. The pickup loop is supported by two Teflon standoff insulators. The probe body is secured in place with one or more locking screws through holes in the brass T.

a 500-pF feedthrough capacitor, C1, soldered into the disc. The terminating resistor, R1, is connected between the other end of the loop and ground, as directly as possible.

When the disc assembly is completed, insert it into the pipe, apply heat to the outside, and solder the tabs in place by melting solder into the assembly at the tabs. The position of the loop with respect to the end of the pipe will determine the sensitivity of a given probe. For power levels up to 200 watts the loop should extend beyond the face of the pipe about $^5/_{32}$ inch. For use at higher power levels the loop should protrude only $^3/_{32}$ inch. For operation with very low power levels the best probe position can be determined by experiment.

The decoupling resistor, R2, and feedthrough capacitor, C2, can be connected, and the pipe cap put in place. The threaded portion of the capacitor extends through the cap. Put a solder lug over it before tightening its nut in place. Fasten the cap with two small screws that go into threaded holes in the pipe.

Calibration

The sampler is very useful for many jobs even if it is not accurately calibrated, although it is desirable to calibrate it against a wattmeter of known accuracy. A good 50-Ω VHF dummy load is required.

The first step is to adjust the inductance of the loop, or the value of the terminating resistor, for lowest reflected power reading. The loop is the easier to change. Filing it to reduce its width will increase its impedance. Increas-

ing the cross-section of the loop will lower the impedance, and this can be done by coating it with solder. When the reflected power reading is reduced as far as possible, reverse the probe and calibrate for forward power by increasing the transmitter power output in steps and making a graph of the meter readings obtained. Use the calibration control, R3, to set the maximum reading.

Variations

Rather than to use one sampler for monitoring both forward and reflected power by repeatedly reversing the

Fig 24—Two versions of the line sampler. The single unit described in detail here is in the foreground. Two sections in a single assembly provide for monitoring forward and reflected power without probe reversal.

probe, it is better to make two assemblies by mounting two T fittings end-to-end, using one for forward and one for reflected power. The meter can be switched between the probes, or two meters can be used.

The sampler described was calibrated at 146 MHz, as it was intended for repeater use. On higher bands the meter reading will be higher for a given power level, and it will be lower for lower frequency bands. Calibration for two or three adjacent bands can be achieved by making the probe depth adjustable, with stops or marks to aid in resetting for a given band. Of course more probes can be made, with each probe calibrated for a given band, as is done in some of the commercially available units.

Other sizes of pipe and fittings can be used by mak-ing use of information given in Chapter 24 to select conductor sizes required for the desired impedances. (Since it is occasionally possible to pick up good bar-gains in 75-Ω line, a sampler for this impedance might be desirable.)

Type-N fittings were used because of their constant impedance and their ease of assembly. Most have the split-ring retainer, which is simple to use in this application. Some have a crimping method, as do apparently all BNC connectors. If a fitting must be used and cannot be taken apart, drill a hole large enough to clear a soldering-iron tip in the copper-pipe outer conductor. A hole of up to $3/8$-inch diameter will have very little effect on the operation of the sampler.

A Calorimeter For VHF And UHF Power Measurements

A quart of water in a Styrofoam ice bucket, a roll of small coaxial cable and a thermometer are all the neces-sary ingredients for an accurate RF wattmeter. Its cali-bration is independent of frequency. The wattmeter works on the calorimeter principle: A given amount of RF energy is equivalent to an amount of heat, which can be deter-mined by measuring the temperature rise of a known quantity of thermally insulated material. This principle is used in many of the more accurate high-power watt-meters. This procedure was developed by James Bowen, WA4ZRP, and was first described in December 1975 *QST*.

The roll of coaxial cable serves as a dummy load to convert the RF power into heat. RG-174 cable was cho-sen for use as the dummy load in this calorimeter because of its high loss factor, small size, and low cost. It is a standard 50-Ω cable of approximately 0.11 inch diam-eter. A prepackaged roll marked as 60 feet long, but mea-sured to be 68 feet, was purchased at a local electronics store. A plot of measured RG-174 loss factor as a func-tion of frequency is shown in **Fig 25**.

In use, the end of the cable not connected to the trans-mitter is left open-circuited. Thus, at 50 MHz, the reflected wave returning to the transmitter (after making a round trip of 136 feet through the cable) is 6.7 dB × 1.36 = 9.11 dB below the forward wave. A reflected wave 9.11 dB down represents an SWR to the transmitter of 2.08:1. While this value seems larger than would be desired, keep in mind that most 50-MHz transmitters can be tuned to match into an SWR of this magnitude effi-ciently. To assure accurate results, merely tune the trans-mitter for maximum power into the load before making

ANT0938

Fig 25—Loss factor of RG-174 coax used in the calorimeter.

Table 4

Calculated Input SWR for 68 Feet of Unterminated RG-174 Cable

Freq. (MHz)	SWR
50	2.08
144	1.35
220	1.20
432	1.06
1296	1.003
2304	1.0003

the measurement. At higher frequencies the cable loss increases so the SWR goes down. **Table 4** presents the calculated input SWR values at several frequencies for 68 feet of RG-174. At 1000 MHz and above, the SWR caused by the cable connector will undoubtedly exceed the very low cable SWR listed for these frequencies.

In operation, the cable is submerged in a quart of water and dissipated heat energy flows from the cable into the water, raising the water temperature. See **Fig 26**. The calibration of the wattmeter is based on the physical fact that one calorie of heat energy will raise one gram of liquid water 1° Celsius. Since one quart of water contains 946.3 grams, the transmitter must deliver 946.3 calories of heat energy to the water to raise its temperature 1° C. One calorie of energy is equivalent to 4.186 joules and a joule is equal to 1 W for 1 second. Thus, the heat capacitance of 1 quart of water expressed in joules is 946.3 × 4.186 = 3961 joules/° C.

The heat capacitance of the cable is small with respect to that of the water, but nevertheless its effect should be included for best accuracy. The heat capacitance of the cable was determined in the manner described below. The 68-foot roll of RG-174 cable was raised to a uniform temperature of 100° C by immersing it in a pan of boiling water for several minutes. A quart of tap water was poured into the Styrofoam ice bucket and its temperature

Fig 26—The calorimeter ready for use. The roll of coaxial cable is immersed in one quart of water in the left-hand compartment of the Styrofoam container. Also shown is the thermometer, which doubles as a stirring rod.

was measured at 28.7° C. the cable was then transferred quickly from the boiling water to the water in the ice bucket. After the water temperature in the ice bucket had ceased to rise, it measured 33.0° C. Since the total heat gained by the quart of water was equal to the total heat lost from the cable, we can write the following equation:

$$(\Delta T_{WATER})(C_{WATER}) = -(\Delta T_{CABLE})(C_{CABLE})$$

where

ΔT_{WATER} = the change in water temperature
C_{WATER} = the water heat capacitance
Δ_{CABLE} = the change in cable temperature
C_{CABLE} = the cable heat capacitance

Substituting and solving:

$$(33.0 - 28.7)(3961) = -(33.0 - 100)(C_{CABLE})$$

Thus, the total heat capacitance of the water and cable in the calorimeter is 3961 + 254 = 4215 joules/° C. Since 1° F = 5/9° C, the total heat capacitance can also be expressed as 4215 × 5/9 = 2342 joules/° F.

Materials and Construction

The quart of water and cable must be thermally insulated to assure that no heat is gained from or lost to the surroundings. A Styrofoam container is ideal for this purpose since Styrofoam has a very low thermal conductivity and a very low thermal capacitance. A local variety store was the source of a small Styrofoam cold chest with compartments for carrying sandwiches and drink cans. The rectangular compartment for sandwiches was found to be just the right size for holding the quart of water and coax.

The thermometer can be either a Celsius or Fahrenheit type, but try to choose one that has divisions for each degree spaced wide enough so that the temperature can be estimated readily to one-tenth degree. Photographic supply stores carry darkroom thermometers, which are ideal for this purpose. In general, glass bulb thermometers are more accurate than mechanical dial-pointer types.

The RF connector on the end of the cable should be a constant-impedance type. A BNC type connector especially designed for use on 0.11-inch diameter cable was located through surplus channels. If you cannot locate one of these, wrap plastic electrical tape around the cable near its end until the diameter of the tape wrap is the same as that of RG-58. Then connect a standard BNC connector for RG-58 in the normal fashion. Carefully seal the opposite open end of the cable with plastic tape or silicone caulking compound so no water can leak into the cable at this point.

Procedure for Use

Pour 1 quart of water (4 measuring cups) into the Styrofoam container. As long as the water temperature is not very hot or very cold, it is unnecessary to cover the top of the Styrofoam container during measurements. Since the transmitter will eventually heat the water sev-

eral degrees, water initially a few degrees cooler than air temperature is ideal because the average water temperature will very nearly equal the air temperature and heat transfer to the air will be minimized.

Connect the RG-174 dummy load to the transmitter through the shortest possible length of lower loss cable such as RG-8. Tape the connectors and adapter at the RG-8 to RG-174 joint carefully with plastic tape to prevent water from leaking into the connectors and cable at this point. Roll the RG-174 into a loose coil and submerge it in the water. Do not bind the turns of the coil together in any way, as the water must be able to freely circulate among the coaxial cable turns. All the RG-174 cable must be submerged in the water to ensure sufficient cooling. Also submerge part of the taped connector attached to the RG-174 as an added precaution.

Upon completing the above steps, quickly tune up the transmitter for maximum power output into the load. Cease transmitting and stir the water slowly for a minute or so until its temperature has stabilized. Then measure the water temperature as precisely as possible. After the initial temperature has been determined, begin the test

transmission, measuring the total number of seconds of key-down time accurately. Stir the water slowly with the thermometer and continue transmitting until there is a significant rise in the water temperature, say 5° to 10°. The test may be broken up into a series of short periods, as long as you keep track of the total key-down time. When the test is completed, continue to stir the water slowly and monitor its temperature. When the temperature ceases to rise, note the final indication as precisely as possible.

To compute the transmitter power output, multiply the calorimeter heat capacitance (4215 for C or 2342 for F) by the difference in initial and final water temperature. Then divide by the total number of seconds of key-down time. The resultant is the transmitter power in watts. A nomogram that can also be used to find transmitter power output is given in **Fig 27**. With a straight line, connect the total number of key-down seconds in the time column to the number of degrees change (F or C) in the temperature rise column, and read off the transmitter power output at the point where the straight line crosses the power-output column.

Power Limitation

The maximum power handling capability of the calorimeter is limited by the following. At very high powers the dielectric material in the coaxial line will melt because of excessive heating or the cable will arc over from excessive voltage. As the transmitter frequency gets higher, the excessive-heating problem is accentuated, as more of the power is dissipated in the first several feet of cable. For instance, at 1296 MHz, approximately 10% of the transmitting power is dissipated in the first foot of cable. Overheating can be prevented when working with high power by using a low duty cycle to reduce the average dissipated power. Use a series of short transmissions, such as two seconds on, ten seconds off. Keep count of the total key-down time for power calculation purposes. If the cable arcs over, use a larger-diameter cable, such as RG-58, in place of the RG-174. The cable should be long enough to assure that the reflected wave will be down 10 dB or more at the input. It may be necessary to use more than one quart of water in order to submerge all the cable conveniently. If so, be sure to calculate the new value of heat capacitance for the larger quantity of water. Also you should measure the new coaxial cable heat capacitance using the method previously described.

Fig 27—Nomogram for finding transmitter power output for the calorimeter.

A Noise Bridge For 1.8 Through 30 MHz

The noise bridge, sometimes referred to as an antenna (RX) noise bridge, is an instrument for measuring the impedance of an antenna or other electrical circuits. The unit shown here in **Fig 28**, designed for use in the 1.8 through 30-MHz range, provides adequate accuracy for most measurements. Battery operation and small physical size make this unit ideal for remote-location use. Tone modulation is applied to the wide-band noise generator as an aid for obtaining a null indication. A detector, such as the station receiver, is required for operation.

The noise bridge consists of two parts—the noise generator and the bridge circuitry. See **Fig 29**. A 6.8-V

Fig 28—Exterior and interior views of the noise bridge. The unit is finished in red enamel. Press-on lettering is used for the calibration marks. Note that the potentiometer must be isolated from ground.

Fig 29—Schematic diagram of the noise bridge. Use ¹/₄ W composition resistors. Capacitors are miniature ceramic units unless indicated otherwise. Component designations indicated in the schematic but not called out in the parts list are for text and parts-placement reference only.

BT1—9-V battery, NEDA 1604A or equiv.
C1—15- to 150-pF variable
C2—20-pF mica.
C3—47-pF mica.
C4—82-pF mica.
J1, J2—Coaxial connector.
R1—Linear, 250 Ω, AB type. Use a good grade of resistor.
S1, S2—Toggle, SPST.

T1—Transformer; 3 windings on an Amidon BLN-43-2402 ferrite binocular core. Each winding is three turns of #30 enameled wire. One turn is equal to the wire passing once through both holes in the core. The primary winding starts on one side of the transformer, and the secondary and tertiary windings start on the opposite side.
U1—Timer, NE555 or equiv.

Zener diode serves as the noise source. U1 generates an approximate 50% duty cycle, 1000-Hz square wave signal which is applied to the cathode of the Zener diode. The 1000-Hz modulation appears on the noise signal and provides a useful null detection enhancement effect. The broadband-noise signal is amplified by Q1, Q2 and associated components to a level that produces an approximate S9 signal in the receiver. Slightly more noise is available at the lower end of the frequency range, as no frequency compensation is applied to the amplifier. Roughly 20 mA of current is drawn from the 9-V battery, thus ensuring long battery life—providing the power

Fig 30—Etching pattern for the noise bridge PC board, at actual size. Black represents copper. This is the pattern for the bottom side of the board. The top side of the board is a complete ground plane with a small amount of copper removed from around the component holes.

Fig 31—Parts-placement guide for the noise bridge as viewed from the component or top side of the board. Mounting holes are located in two corners of the board, as shown.

is switched off after use!

The bridge portion of the circuit consists of T1, C1, C2 and R1. T1 is a trifilar wound transformer with one of the windings used to couple noise energy into the bridge circuit. The remaining two windings are arranged so that each one is in an arm of the bridge. C1 and R1 complete one arm and the UNKNOWN circuit, along with C2, comprise the remainder of the bridge. The terminal labeled RCVR is for connection to the detector.

The reactance range of a noise bridge is dependent on several factors, including operating frequency, value of the series capacitor (C3 or C3 plus C4 in Fig 29) and the range of the variable capacitor (C1 in Fig 29). The RANGE switch selects reactance measurements weighted toward either capacitance or inductance by placing C4 in parallel with C3. The zero-reactance point occurs when C1 is either nearly fully meshed or fully unmeshed. The RANGE switch nearly doubles the resolution of the reactance readings.

CONSTRUCTION

The noise bridge is contained in a homemade aluminum enclosure that measures $5 \times 2^3/_8 \times 3^3/_4$ inches. Many of the circuit components are mounted on a circuit board that is fastened to the rear wall of the cabinet. The circuit-board layout is such that the lead lengths to the board from the bridge and coaxial connectors are at a minimum. An etching pattern and a parts-placement guide for the circuit board are shown in **Figs 30** and **31**.

Care must be taken when mounting the potentiometer, R1. For accurate readings the potentiometer must be well insulated from ground. In the unit shown this was accomplished by mounting the control on a piece of plexiglass, which in turn was fastened to the chassis with a piece of aluminum angle stock.

Additionally, a $^1/_4$-inch control-shaft coupling and a length of phenolic rod were used to further isolate the control from ground where the shaft passes through the front panel. A high-quality potentiometer is required if good measurement results are to be obtained.

There is no such problem when mounting the variable capacitor because the rotor is grounded. Use a high-quality capacitor; do not try to save money on that component. Two RF connectors on the rear panel are connected to a detector (receiver) and to the UNKNOWN circuit. Do not use plastic-insulated phono connectors (they might influence bridge accuracy at higher frequencies). Use miniature coaxial cable (RG-174) between the RCVR connector and circuit board. Attach one end of C3 to the circuit board and the other directly to the UNKNOWN circuit connector.

Bridge Compensation

Stray capacitance and inductance in the bridge circuit can affect impedance readings. If a very accurate bridge is required, use the following steps to counter the effects of stray reactance. Because the physical location

Fig 32—Construction details of the resistive loads used to check and calibrate the noise bridge. Each of the loads is constructed inside a coaxial connector that matches those on the bridge. (Views shown are cross-sections of PL-259 bodies; the sleeves are not shown.) Leads should be kept as short as possible to minimize parasitic inductance. A is a 0-Ω load; B depicts a 50-Ω load; C is a 180-Ω load; D shows a variable-resistance load used to determine the loss in a coaxial cable.

of the board, connectors and controls in the cabinet determine where compensation is needed, there is no provision for the compensation components on the printed circuit board.

Good calibration loads are necessary to check the accuracy of the noise bridge. Four are needed here: a 0-Ω (short-circuit) load, a 50-Ω load, a 180-Ω load, and a variable-resistance load. The short-circuit and fixed-resistance loads are used to check the accuracy of the noise bridge; the variable-resistance load is used when measuring coaxial-cable loss.

Construction details of the loads are shown in **Fig 32**. Each load is constructed inside a connector. When building the loads, keep leads as short as possible to minimize parasitic effects. The resistors must be noninductive (*not* wirewound).

Quarter-watt, carbon-composition resistors should work fine. The potentiometer in the variable-resistance

load is a miniature PC-mount unit with a maximum resistance of 100 Ω or less. The potentiometer wiper and one of the end leads are connected to the center pin of the connector; the other lead is connected to ground.

Stray Capacitance

Stray capacitance on the variable-resistor side of the bridge tends to be higher than that on the unknown side. This is so because the parasitic capacitance in the variable resistor, R1, is comparatively high.

The effect of parasitic capacitance is most easily detected using the 180-Ω load. Measure and record the actual resistance of the load, R_L. Connect the load to the UNKNOWN connector, place S2 in the X_L position, tune the receiver to 1.8 MHz, and null the bridge. (See the section, "Finding the Null" for tips.) Use an ohmmeter across R1 to measure its dc resistance. The magnitude of the stray capacitance can be calculated by

$$C_P = C3 \left(\sqrt{\frac{R1}{R2}} - 1 \right) \tag{Eq 4}$$

where

R_L = load resistance (as measured)
R1 = resistance of the variable resistor
C3 = series capacitance.

You can compensate for C_P by placing a variable capacitor, C_C, in the side of the bridge with lesser stray capacitance. If R1 is greater than R_L, stray capacitance is greater on the variable resistor side of the bridge: Place C_C between point U (on the circuit board) and ground. If R1 is less than R_L, stray capacitance is greater on the unknown side: Place C_C between point B and ground. If the required compensating capacitance is only a few picofarads, you can use a gimmick capacitor (made by twisting two short pieces of insulated, solid wire together) for C_C. A gimmick capacitor is adjusted by trimming its length.

Stray Inductance

Parasitic inductance, if present, should be only a few tens of nanohenries. This represents a few ohms of inductive reactance at 30 MHz. The effect is best observed by reading the reactance of the 0-Ω test load at 1.8 and 30 MHz; the indicated reactance should be the same at both frequencies.

If the reactance reading decreases as frequency is increased, parasitic inductance is greater in the known arm, and compensating inductance is needed between point U and C3. If the reactance increases with frequency, the unknown-arm inductance is greater, and compensating inductance should be placed between point B and R1.

Compensate for stray inductance by placing a single-turn coil, made from a 1 to 2-inch length of solid wire, in the appropriate arm of the bridge. Adjust the size of this coil until the reactance reading remains constant from 1.8 to 30 MHz.

Calibration

Good calibration accuracy is necessary for accurate noise-bridge measurements. Calibration of the resistance scale is straightforward. To do this, tune the receiver to a frequency near 10 MHz. Attach the 0-Ω load to the UNKNOWN connector and null the bridge. This is the zero-resistance point; mark it on the front-panel resistance scale. The rest of the resistance range is calibrated by adjusting R1, measuring R1 with an accurate ohmmeter, calculating the increase from the zero point and marking the increase on the front panel.

Most bridges have the reactance scale marked in capacitance because capacitance does not vary with frequency. Unfortunately, that requires calibration curves or non-trivial calculations to arrive at the load reactance. An alternative method is to mark the reactance scale in *ohms* at a reference frequency of 10 MHz. This method calibrates the bridge near the center of its range and displays reactance directly, but it requires a simple calculation to scale the reactance reading for frequencies other than 10 MHz. The scaling equation is:

$$X_{u(f)} = X_{u(10)}\frac{10}{f} \qquad \text{(Eq 5)}$$

where

  f = frequency in MHz
  $X_{u(10)}$ = reactance of the unknown load at 10 MHz
  $X_{u(f)}$ = reactance of the unknown load at f.

A shorted piece of coaxial cable serves as a reactance source. (The reactance of a shorted, low-loss coaxial cable is dependent only on the cable length, the measurement frequency and the cable characteristic impedance.) Radio Shack RG-8M is used here because it is readily available, has relatively low loss and has an almost purely resistive characteristic impedance.

Prepare the calibration cable as follows:

1) Cut a length of coaxial cable that is slightly longer than $^1/_4$ λ at 10 MHz (about 20 feet for RG-8M). Attach a suitable connector to one end of the cable; leave the other end open-circuited.

2) Connect the 0-Ω load to the noise bridge UNKNOWN connector and set the receiver frequency to 10 MHz. Adjust the noise bridge for a null. Do not adjust the reactance control after the null is found.

3) Connect the calibration cable to the bridge UNKNOWN terminal. Null the bridge by adjusting *only* the variable resistor and the receiver frequency. The receiver frequency should be less than 10 MHz; if it is above 10 MHz, the cable is too short, and you need to prepare a longer one.

4) Gradually cut short lengths from the end of the coaxial cable until you obtain a null at 10 MHz by adjusting only the resistance control. Then connect the cable center and shield conductors at the open end with a short length of braid. Verify that the bridge nulls with zero reactance at 20 MHz.

5) The reactance of the coaxial cable (normalized to 10 MHz) can be calculated from:

$$X_{i(10)} = R_0\frac{f}{10}\tan\left(2\pi\frac{f}{40}\right) \qquad \text{(Eq 6)}$$

where

  $X_{i(10)}$ = cable reactance at 10 MHz
  R_0 = characteristic resistance of the coaxial cable (52.5 Ω for Radio Shack RG-8M)
  f = frequency in MHz

The results of Eq 6 have less than 5% error for reactances less than 500 Ω, so long as the test-cable loss is less than 0.2 dB. This error becomes significantly less at lower reactances (2% error at 300 Ω for a 0.2-dB-loss cable). The loss in 18 feet of RG-8M is 0.13 dB at 10 MHz. Reactance data for Radio Shack RG-8M is given in **Table 5**.

Table 5
Noise Bridge Calibration Data: Coaxial-Cable Method

This data is for Radio Shack RG-8M cable (R_0 =52.5 Ω) cut to exactly $^1/_4$ λ at 10 MHz; the reactances and capacitances shown correspond to this frequency.

Reactance				Capacitance	
X_i	f(MHz)	X_i	f(MHz)	C(pF)	f(MHz)
10	3.318	−10	19.376	10	9.798
20	4.484	−20	18.722	20	9.612
30	5.262	−30	18.048	30	9.440
40	5.838	−40	17.368	40	9.280
50	6.286	−50	16.701	50	9.130
60	6.647	−60	16.062	60	8.990
70	6.943	−70	15.471	70	8.859
80	7.191	−80	14.936	80	8.735
90	7.404	−90	14.462	90	8.618
100	7.586	−100	14.044	100	8.508
110	7.747	−110	13.682	110	8.403
120	7.884	−120	13.369	120	8.304
130	8.009	−130	13.097	130	8.209
140	8.119	−140	12.861	140	8.119
150	8.217	−150	12.654		
160	8.306	−160	12.473		
170	8.387	−170	12.313		
180	8.460	−180	12.172		
190	8.527	−190	12.045		
200	8.588	−200	11.932	C(pF)	f(MHz)
210	8.645	−210	11.831	−10	10.219
220	8.697	−220	11.739	−20	10.459
230	8.746	−230	11.655	−30	10.721
240	8.791	−240	11.579	−40	11.010
250	8.832	−250	11.510	−50	11.328
260	8.872	−260	11.446	−60	11.679
270	8.908	−270	11.387	−70	12.064
280	8.942	−280	11.333	−80	12.484
290	8.975	−290	11.283	−90	12.935
300	9.005	−300	11.236	−100	13.407
350	9.133	−350	11.045	−110	13.887
400	9.232	−400	10.905	−120	14.357
450	9.311	−450	10.798	−130	14.801
500	9.375	−500	10.713	−140	15.211

With the prepared cable and calibration values on hand, proceed to calibrate the reactance scale. Tune the receiver to the appropriate frequency for the desired reactance (given in Table 5, or found using Eq 6). Adjust the resistance and reactance controls to null the bridge. Mark the reactance reading on the front panel. Repeat this process until all desired reactance values have been marked. The resistance values needed to null the bridge during this calibration procedure may be significant (more than 100 Ω) at the higher reactances.

This calibration method is much more accurate than using fixed capacitors across the UNKNOWN connector. Also, you can calibrate a noise bridge in less than an hour using this method.

Finding the Null

In use, a receiver is attached to the RCVR connector and some load of unknown value is connected to the UNKNOWN terminal. The receiver allows us to hear the noise present across the bridge arms at the frequency of the receiver passband. The strength of the noise signal depends on the strength of the noise-bridge battery, the receiver bandwidth/sensitivity and the impedance difference between the known and unknown bridge arms. The noise is stronger and the null more obvious with wide receiver passbands. Set the receiver to the widest bandwidth AM mode available.

The noise-bridge output is heard as a 1000-Hz tone. When the impedances of the known and unknown bridge arms are equal, the voltage across the receiver is minimized; this is a null. In use, the null may be difficult to find because it appears only when both bridge controls approach the values needed to balance the bridge.

To find the null, set C1 to mid-scale, sweep R1 slowly through its range and listen for a reduction in noise (it's also helpful to watch the S meter). If no reduction is heard, set R1 to mid-range and sweep C1. If there is still no reduction, begin at one end of the C1 range and sweep R1. Increment C1 about 10% and sweep R1 with each increment until some noise reduction appears. Once noise reduction begins, adjust C1 and R1 alternately for minimum signal.

MEASURING COAXIAL-CABLE PARAMETERS WITH A NOISE BRIDGE

Coaxial cables have a number of properties that affect the transmission of signals through them. Generally, radio amateurs are concerned with cable attenuation and characteristic impedance. If you plan to use a noise bridge or SWR analyzer to make antenna-impedance measurements, however, you need to accurately determine not just cable impedance and attenuation, but also electrical length. Fortunately, all of these parameters are easy to measure with an accurate noise bridge or SWR analyzer.

Cable Electrical Length

With a noise bridge and a general-coverage receiver, you can easily locate frequencies at which the line in question is a multiple of $1/2$ λ, because a shorted $1/2$ λ line has a 0-Ω impedance (neglecting line loss). By locating two adjacent null frequencies, you can solve for the length of line in terms of $1/2$ λ at one of the frequencies and calculate the line length (overall accuracy is limited by bridge accuracy and line loss, which broadens the nulls). As an interim variable, you can express cable length as the frequency at which a cable is 1 λ long. This length will be represented by f λ. Follow these steps to determine f λ for a coaxial cable.

1) Tune the receiver to the frequency range of interest. Attach the short-circuit load to the noise bridge UNKNOWN connector and null the bridge.

2) Disconnect the far end of the coaxial cable from its load (the antenna) and connect it to the 0-Ω test load. Connect the near end of the cable to the bridge UNKNOWN connector.

3) Adjust the receiver frequency and the noise-bridge resistance control for a null. *Do not change the noise bridge reactance-control setting during this procedure.* Note the frequency at which the null is found; call this frequency f_n. The noise-bridge resistance at the null should be relatively small (less than 20 Ω).

4) Tune the receiver upward in frequency until the next null is found. Adjust the resistance control, if necessary, to improve the null, *but do not adjust the reactance control*. Note the frequency at which this second null is found; this is f_{n+2}.

5) Solve Eq 7 for n and the electrical length of the cable.

$$n = \frac{2f_n}{f_{n+2} - f_n} \qquad \text{(Eq 7)}$$

$$f_\lambda = \frac{4f_n}{n} \qquad \text{(Eq 8)}$$

where

n = cable electrical length in quarter waves, at f_n
f_l = frequency at which the cable is 1λ
ℓ = cable electrical length, in λ

For example, consider a 74-foot length of Columbia 1188 foam-dielectric cable (velocity factor = 0.78) to be used on the 10-meter band. Based on the manufacturer's specification, the cable is 2.796 λ at 29 MHz. Nulls were found at 24.412 (f_n) and 29.353 (f_{n+2}) MHz. Eq 7 yields n = 9.88, which produces 9.883 MHz from Eq 8 and 2.934 l for Eq 9. If the manufacturer's specification is correct, the measured length is off by less than 5%, which is very reasonable. Ideally, n would yield an integer. The difference between n and the closest integer indicates that there is some error.

This procedure also works for lines with an open circuit as the termination (n will be close to an odd number). End effects from the PL-259 increase the effective length of the coaxial cable; however, this decreases the calculated f_λ.

Cable Characteristic Impedance

The characteristic impedance of the coaxial cable is found by measuring its input impedance at two frequencies separated by $1/4\, f_\lambda$. This must be done when the cable is terminated in a resistive load.

Characteristic impedance changes slowly as a function of frequency, so this measurement must be done near the frequency of interest. The measurement procedure is as follows.

1) Place the 50-Ω load on the far end of the coaxial cable and connect the near end to the UNKNOWN connector of the noise bridge. (Measurement error is minimized when the load resistance is close to the characteristic impedance of the cable. This is the reason for using the 50-Ω load.)
2) Tune the receiver approximately $1/8$ f below the frequency of interest. Adjust the bridge resistance and reactance controls to obtain a null, and note their readings as R_{f1} and X_{f1}. Remember, the reactance reading must be scaled to the measurement frequency.
3) Increase the receiver frequency by exactly $1/4\, f_\lambda$. Null the bridge again, and note the readings as R_{f2} and X_{f2}.
4) Calculate the characteristic impedance of the coaxial cable using Eqs 10 through 15. A scientific calculator is helpful for this.

$$\ell = \frac{f_0}{f_\lambda} \qquad\qquad\qquad\qquad \text{(Eq 9)}$$

$$R = R_{f1} \times F_{f2} - X_{f1} \times X_{f2} \qquad\qquad \text{(Eq 10)}$$

$$X = R_{f1} \times X_{f2} + X_{f1} \times R_{f2} \qquad\qquad \text{(Eq 11)}$$

$$Z = \sqrt{R^2 + X^2} \qquad\qquad\qquad \text{(Eq 12)}$$

$$R_0 = \sqrt{Z} \cos\left[\frac{1}{2}\tan^{-1}\left(\frac{X}{R}\right)\right] \qquad\qquad \text{(Eq 13)}$$

$$X_0 = \sqrt{Z} \sin\left[\frac{1}{2}\tan_{-1}\left(\frac{X}{R}\right)\right] \qquad\qquad \text{(Eq 14)}$$

$$Z_0 = R_0 + jX_0 \qquad\qquad\qquad \text{(Eq 15)}$$

Let's continue with the example used earlier for cable length. The measurements are:

f1 = 29.000 − (9.883 / 8) = 27.765 MHz
R_{f1} = 64 Ω
X_{f1} = −22 Ω × (10 / 27.765) = −7.9 Ω
f2 = 27.765 + (9.883/4) = 30.236 MHz
R_{f2} = 50 Ω
X_{f2} = −24 Ω × (10 / 30.236) = −7.9 Ω

When used in Eqs 10 through 15, these data yield:

R = 3137.59
X = −900.60
Z = 3264.28
R_0 = 56.58 Ω
X_0 = −7.96 Ω

Cable Attenuation

Cable loss can be measured once the cable electrical length and characteristic resistance are known. The measurement must be made at a frequency where the cable presents no reactance. Reactance is zero when the cable electrical length is an integer multiple of $\lambda/4$. You can easily meet that condition by making the measurement frequency an integer multiple of $1/4\, f_\lambda$. Loss at other frequencies can be interpolated with reasonable accuracy. This procedure employs a resistor-substitution method that provides much greater accuracy than is achieved by directly reading the resistance from the noise-bridge scale.

1) Determine the approximate frequency at which you want to make the loss measurement by using

$$n = \frac{4f_0}{f_\lambda} \qquad\qquad\qquad \text{(Eq 16A)}$$

Round n to the nearest integer, then

$$f1 = \frac{n}{4}\, f_\lambda \qquad\qquad\qquad \text{(Eq 16B)}$$

2) If n is odd, leave the far end of the cable open; if n is even, connect the 0-Ω load to the far end of the cable. Attach the near end of the cable to the UNKNOWN connector on the noise bridge.
3) Set the noise bridge to zero reactance and the receiver to f1. Fine tune the receiver frequency and the noise-bridge resistance to find the null.
4) Disconnect the cable from the UNKNOWN terminal, and connect the variable-resistance calibration load in its place. Without changing the resistance setting on the bridge, adjust the load resistor and the bridge reactance to obtain a null.
5) Remove the variable-resistance load from the bridge UNKNOWN terminal and measure the load resistance using an ohmmeter that's accurate at low resistance levels. Refer to this resistance as R_i.
6) Calculate the cable loss in decibels using

$$a\ell = 8.69\, \frac{R_i}{R_0} \qquad\qquad\qquad \text{(Eq 17)}$$

To continue this example, Eq 16A gives n = 11.74, so measure the attenuation at n = 12. From Eq 16B, f1 = 29.649 MHz. The input resistance of the cable measures 12.1 Ω with 0-Ω load on the far end of the cable; this corresponds to a loss of 1.86 dB.

USING A BRIDGE TO MEASURE THE IMPEDANCE OF AN ANTENNA

The impedance at the end of a transmission line can be easily measured using a noise bridge or SWR analyzer. In many cases, however, you really want to measure the impedance of an antenna—that is, the impedance of the load at the far end of the line. There are several ways to handle this.

1) Measurements can be made with the bridge at the antenna. This is usually not practical because the antenna must be in its final position for the measurement to be accurate. Even if it can be done, making such a measurement is certainly not very convenient.

2) Measurements can be made at the source end of a coaxial cable—if the cable length is an exact integer multiple of $^1/_2$ λ. This effectively restricts measurements to a single frequency.

3) Measurements can be made at the source end of a coaxial cable and corrected using a Smith Chart as shown in Chapter 28. This graphic method can result in reasonable estimates of antenna impedance—as long as the SWR is not too high and the cable is not too lossy. However, it doesn't compensate for the complex impedance characteristics of real-world coaxial cables. Also, compensation for cable loss can be tricky to apply. These problems, too, can lead to significant errors.

4) Last, measurements can be corrected using the transmission-line equation. The *TLW* program included on the CD-ROM in the back of this book, can do these complicated computations for you. This is the best method for calculating antenna impedances from measured parameters, but it requires that you measure the feed-line characteristics beforehand—measurements for which you need access to both ends of the feed line.

The procedure for determining antenna impedance is to first measure the electrical length, characteristic impedance, and attenuation of the coaxial cable connected to the antenna. After making these measurements, connect the antenna to the coaxial cable and measure the input impedance of the cable at a number of frequencies. Then use these measurements in the transmission-line equation to determine the actual antenna impedance at each frequency.

Table 6 and **Fig 33** give an example of such a calculation. The antenna used for this example is a 10-meter inverted V about 30 feet above the ground. The arms of the antenna are separated by a 120° angle. Each arm is exactly 8 feet long, and the antenna is made of #14 wire. The feed line is the 74-foot length of Columbia 1188 characterized earlier.

See Fig 33A. From this plot of impedance measurements, it is very difficult to determine anything about the antenna. Resistance and reactance vary substantially over this frequency range, and the antenna appears to be resonant at 27.7, 29.0 and 29.8 MHz.

The plot in Fig 33B shows the true antenna imped-

Table 6
Impedance Data for Inverted-V Antenna

Freq (MHz)	R_u (Ω)	X_u @ 10 MHz (Ω)	X_u (Ω)	R_L (Ω)	X_L (Ω)
27.0	44	85	31.5	24	−65
27.2	60	95	34.9	26	−56
27.4	75	85	31.0	30	−51
27.6	90	40	14.5	32	−42
27.8	90	−20	−7.2	35	−34
28.0	75	−58	−20.7	38	−24
28.2	65	−65	−23.0	40	−19
28.4	56	−52	−18.3	44	−12
28.6	50	−40	−14.0	44	−6
28.8	48	−20	−6.9	47	1
29.0	50	0	0.0	52	8
29.2	55	20	6.8	57	15
29.4	64	30	10.2	63	21
29.6	78	20	6.8	75	26
29.8	85	0	0	78	30
30.0	90	−50	−16.7	89	33

Fig 33–Impedance plot of an inverted-V antenna cut for 29 MHz. At A, a plot of resistances and reactances, measured using the noise bridge, at the end of a 74-foot length of Columbia 1188 coaxial cable. At B, the actual antenna-impedance plot (found using the transmission-line equation to remove the effects of the transmission line).

ance. This plot has been corrected for the effects of the cable using the transmission-line equation. The true antenna resistance and reactance both increase smoothly with frequency. The antenna is resonant at 28.8 MHz, with a radiation resistance at resonance of 47 Ω. This is normal for an inverted V.

When doing the conversions, be careful not to make measurement errors. Such errors introduce more errors into the corrected data. This problem is most significant when the transmission line is near an odd multiple of a $^1/_4$ λ and the line SWR and/or attenuation is high. Measurement errors are probably present if small changes in the input impedance or transmission-line characteristics appear as large changes in antenna impedance. If this effect is present, it can be minimized by making the measurements with a transmission line that is approximately an integer multiple of $^1/_2$ λ.

A Practical Time-Domain Reflectometer

A time-domain reflectometer (TDR) is a simple but powerful tool used to evaluate transmission lines. When used with an oscilloscope, a TDR displays impedance "bumps" (open and short circuits, kinks and so on) in transmission lines. Commercially produced TDRs cost from hundreds to thousands of dollars each, but you can add the TDR described here to your shack for much less. This material is based on a *QST* article by Tom King, KD5HM (see Bibliography), and supplemented with information from the references.

How a TDR Works

A simple TDR consists of a square-wave generator and an oscilloscope. See **Fig 34**. The generator sends a train of dc pulses down a transmission line, and the oscilloscope lets you observe the incident and reflected waves from the pulses (when the scope is synchronized to the pulses).

A little analysis of the scope display tells the nature and location of any impedance changes along the line. The nature of an impedance disturbance is identified by comparing its pattern to those in **Fig 35**. The patterns are based on the fact that the reflected wave from a disturbance is determined by the incident-wave magnitude and the reflection coefficient of the disturbance. (The patterns shown neglect losses; actual patterns may vary somewhat from those shown.)

The location of a disturbance is calculated with a simple proportional method: The round-trip time (to the disturbance) can be read from the oscilloscope screen (graticule). Thus, you need only read the time, multiply it by the velocity of the radio wave (the speed of light adjusted by the velocity factor of the transmission line) and divide by two. The distance to a disturbance is given by:

$$\ell = \frac{983.6 \times VF \times t}{2}$$ (Eq 18)

Fig 34—The time-domain reflectometer shown here is attached to a small portable oscilloscope.

where
  ℓ = line length in feet
  VF = velocity factor of the transmission line (from 0 to 1.0)
  t = time delay in microseconds (µs).

The Circuit

The time-domain reflectometer circuit in **Fig 36** consists of a CMOS 555 timer configured as an astable multivibrator, followed by an MPS3646 transistor acting as a 15-ns-risetime buffer. The timer provides a 71-kHz square wave. This is applied to the 50-Ω transmission line under test (connected at J2). The oscilloscope is connected to the circuit at J1.

Construction

An etching pattern for the TDR is shown in **Fig 37**. **Fig 38** is the part-placement diagram. The TDR is

(A) OPEN CIRCUIT ... SHORT CIRCUIT

(B) $R = -Z_0 \, ? \dfrac{\rho + 1}{\rho - 1}$ ... $R > Z_o$ ... $R < Z_o$

(C) X_L ... X_C

(D) X_L ... X_C

ANT0945

Fig 35—Characteristic TDR patterns for various loads. The location of the load can be calculated from the transit time, t, which is read from the oscilloscope (see text). R values can be calculated as shown (for purely resistive loads only—$\rho < 0$ when $R < Z_0$; $\rho < 0$ when $R > Z_0$). Values for reactive loads cannot be calculated simply.

designed for a $4 \times 3 \times 1$-inch enclosure (including the batteries). Sl, Jl and J2 are right-angle-mounted components. Two aspects of construction are critical. First use *only* an MPS3646 for Q1. This type was chosen for its good performance in this circuit. If you substitute another transistor, the circuit may not perform properly.

Second, for the TDR to provide accurate measurements, the cable connected to J1 (between the TDR and the oscilloscope) must not introduce impedance mismatches in the circuit. *Do not make this cable from ordinary coaxial cable.* Oscilloscope-probe cable is the best thing to use for this connection.

(It took the author about a week and several phone calls to determine that scope-probe cable isn't "plain old coax." Probe cable has special characteristics that prevent undesired ringing and other problems.)

Mount a binding post at J1 and connect a scope probe to the binding post when testing cables with the TDR. R5 and C2 form a compensation network—much like the networks in oscilloscope probes—to adjust for effects of

Fig 36—Schematic diagram of the time-domain reflectometer. All resistors are ¹/₄-W, 5% tolerance. U1 is a CMOS 555 timer. Circuit current drain is 10 to 25 mA. When building the TDR, observe the construction cautions discussed in the text. C2 is available from Mouser Electronics, part no. ME242-8050. Right-angle BNC connectors for use at J1 and J2 can be obtained from Newark Electronics, part no. 89N1578. S1 can be obtained from All Electronics, part no. NISW-1. An SPST toggle switch can also be used at S1.

Fig 37—Full-size PC-board etching pattern for the TDR. Black areas represent unetched copper foil.

Fig 38—Part-placement diagram for the TDR. Parts are mounted on the nonfoil side of the board; the shaded area represents an X-ray view of the copper pattern. Be sure to observe the polarity markings of C3, C4 and C5.

the probe wire.

The TDR is designed to operate from dc between 3 and 9 V. Two C cells (in series—3 V) supply operating voltage in this version. The circuit draws only 10 to 25 mA, so the cells should last a long time (about 200 hours of operation). U1 can function with supply voltages as low as 2.25 to 2.5.

If you want to use the TDR in transmission-line systems with characteristic impedances other than 50 Ω,

change the value of R_L to match the system impedance as closely as possible.

Calibrating and Using the TDR

Just about any scope with a bandwidth of at least 10 MHz should work fine with the TDR, but for tests in short-length cables, a 50-MHz scope provides for much more accurate measurements. To calibrate the TDR, terminate CABLE UNDER TEST connector, J2, with a 51-Ω

Fig 39—TDR calibration trace as shown on an oscilloscope. Adjust C2 (See Figs 36 and 38) for maximum deflection and sharpest waveform corners during calibration. See text.

Fig 41—TDR display of the impedance characteristics of the 142-foot Hardline run to the 432-MHz antenna at KD5HM. The scope is set for 0.05 ms per division. See text for discussion.

Fig 40—Open-circuited test cable. The scope is set for 0.01 ms per division. See text for interpretation of the waveform.

resistor. Connect the scope vertical input to J1. Turn on the TDR, and adjust the scope timebase so that one square-wave cycle from the TDR fills as much of the scope display as possible (without uncalibrating the timebase). The waveform should resemble **Fig 39**. Adjust C2 to obtain maximum amplitude and sharpest corners on the observed waveform. That's all there is to the calibration process!

To use the TDR, connect the cable under test to J2, and connect the scope vertical input to J1. If the waveform you observe is different from the one you observed during calibration, there are impedance variations in the load you're testing. See **Fig 40**, showing an unterminated test cable connected to the TDR. The beginning of the cable is shown at point A. (AB represents the TDR out-

put-pulse rise time.)

Segment AC shows the portion of the transmission line that has a 50-Ω impedance. Between points C and D, there is a mismatch in the line. Because the scope trace is higher than the 50-Ω trace, the impedance of this part of the line is higher than 50 Ω—in this case, an open circuit.

To determine the length of this cable, read the length of time over which the 50-Ω trace is displayed. The scope is set for 0.01 μs per division, so the time delay for the 50-Ω section is (0.01 μs × 4.6 divisions) = 0.046 μs. The manufacturer's specified velocity factor (VF) of the cable is 0.8. Eq 1 tells us that the 50-Ω section of the cable is

$$\ell = \frac{983.6 \times 0.8 \times 0.046\,\mu s}{2} = 18.1\,\text{feet}$$

The TDR provides reasonable agreement with the actual cable length—in this case, the cable is really 16.5 feet long. (Variations in TDR-derived calculations and actual cable lengths can occur as a result of cable VFs that can vary considerably from published values. Many cables vary as much as 10% from the specified values.)

A second example is shown in **Fig 41**, where a length of $^3/_4$-inch Hardline is being tested. The line feeds a 432-MHz vertical antenna at the top of a tower. Fig 41 shows that the 50-Ω line section has a delay of (6.6 divisions × 0.05 μs) = 0.33 μs. Because the trace is straight and level at the 50-Ω level, the line is in good shape. The trailing edge at the right-hand end shows where the antenna is connected to the feed line.

To determine the actual length of the line, use the same procedure as before: Using the published VF for the Hardline (0.88) in Eq 1, the line length is

$$\ell = \frac{983.6 \times 0.88 \times 0.33\,\mu s}{2} = 142.8\,\text{feet}$$

Again, the TDR-derived measurement is in close agreement with the actual cable length (142 feet).

Final Notes

The time-domain reflectometer described here is not frequency specific; its measurements are not made at the frequency at which a system is designed to be used. Because of this, the TDR cannot be used to verify the impedance of an antenna, nor can it be used to measure cable loss at a specific frequency. Just the same, in two years of use, it has never failed to help locate a transmission-line problem. The vast majority of transmission-line problems result from improper cable installation or connector weathering.

Limitations

Certain limitations are characteristic of TDRs because the signal used to test the line differs from the system operating frequency and because an oscilloscope is a broadband device. In the instrument described here, measurements are made with a 71-kHz square wave. That wave contains components at 71 kHz and odd harmonics thereof, with the majority of the energy coming from the lower frequencies. The leading edge of the trace indicates that the response drops quickly above 6 MHz. (The leading edge in Fig 40 is 0.042 μs, corresponding to a period of 0.168 μs and a frequency of 5.95 MHz.) The result is dc pulses of approximately 7 μs duration. The scope display combines the circuit responses to all of those frequencies. Hence, it may be difficult to interpret any disturbance which is narrowband in nature (affecting only a small range of frequencies, and thus a small portion of the total power), or for which the travel time plus pattern duration exceeds 7 μs. The 432-MHz vertical antenna in Fig 41 illustrates a display error resulting from narrow-band response.

The antenna shows as a major impedance disturbance because it is mismatched at the low frequencies that dominate the TDR display, yet it is matched at 432 MHz. For an event that exceeds the observation window, consider a 1-μF capacitor across a 50-Ω line. You would see only part of the pattern shown in Fig 35C because the time constant ($1 \times 10^{-6} \times 50 = 50$ ms) is much larger than the 7-μs window.

In addition, TDRs are unsuitable for measurements where there are major impedance changes inside the line section to be tested. Such major changes mask reflections from additional changes farther down the line.

Because of these limitations, TDRs are best suited for spotting faults in dc-continuous systems that maintain a constant impedance from the generator to the load. Happily, most amateur stations would be ideal subjects for TDR analysis, which can conveniently check antenna cables and connectors for short and open-circuit conditions and locate the position of such faults with fair accuracy.

Ground Parameters for Antenna Analysis

This section is taken from an article in *The ARRL Antenna Compendium, Vol 5* by R. P. Haviland, W4MB. In the past, amateurs paid very little attention to the characteristics of the earth (ground) associated with their antennas. There are two reasons for this. First, these characteristics are not easy to measure—even with the best equipment, extreme care is needed. Second, almost all hams have to put up with what they have—there are very few who can afford to move because their location has poor ground conditions! Further, the ground is not a dominant factor in the most popular antennas—a tri-band Yagi at 40 feet or higher, or a 2-meter vertical at roof height, for example.

Even so, there has been a desire and even a need for ground data and for ways to use it. It is very important for vertically polarized antennas. Ground data is useful for antennas mounted at low heights generally, and for such specialized ones as Beverages. The performance of such antennas change a lot as the ground changes.

Importance of Ground Conditions

To see why ground conditions can be important, let us look at some values. For a frequency of 10 MHz, *CCIR Recommendation 368*, gives the distance at which the signal is calculated to drop 10 dB below its free-space level as:

Conductivity (mS/meter)	Distance for 10 dB Drop (km)
5000	100
30	15
3	0.3

The high-conductivity condition is for sea-water. Inter-island work in the Caribbean on 40 and 80 meters is easy, whereas 40-meter ground-wave contact is difficult for much of the USA, because of much lower ground conductivity. On the other hand, the Beverage works because of poor ground conductivity.

Fig 42 shows a typical set of expected propagation curves for a range of frequencies. This data is also from *CCIR Recommendation 368* for relatively poor ground, with a dielectric constant of 4 and a conductivity of 3 mS/m (one milliSiemens/meter is 0.001 mho/meter). The same data is available in the *Radio Propagation Handbook*. There are equivalent FCC curves, found in the book *Reference Data for Radio Engineers*, but only the ones near 160 meters are useful. In Florida the author has difficulty hearing stations across town on ground

Fig 42—Variation of field strength with distance. Typical field strengths for several frequencies are shown. This is from CCIR data for fairly poor soil, with dielectric constant of 4 and conductivity of 3 mS/m. The curves for good soil are closer to the free-space line, and those for sea water are much closer to the free-space line.

wave, an indication of the poor soil conditions—reflected sky-wave signals are often stronger.

Securing Ground Data

There are only two basic ways to approach this matter of ground data. One is to use generic ground data typical to the area. The second is to make measurements, which haven't really gotten easier. For most amateurs, the best approach seems to be a combination of these—use some simple measurements, and then use the generic data to make a better estimate. Because of equipment costs and measurement difficulties, none of these will be highly accurate for most hams. But they will be much better than simply taking some condition preset into an analysis program. Having a good set of values to plug into an analysis can help you evaluate the true worth of a new antenna project.

Generic Data

In connection with its licensing procedure for broadcast stations, the FCC has published generic data for the

Numbers on map represent estimated effective ground conductivity in millisiemens per meter. Conductivity of seawater is not shown on map but is assumed to be 500 millisiemens per meter.

Estimated
Effective Ground Conductivity
in the United States

ANT0950

Fig 43—Estimated effective ground conductivity in the United States. FCC map prepared for the Broadcast Service, showing typical conductivity for continental USA. Values are for the band 500 to 1500 KHz. Values are for flat, open spaces and often will not hold for other types of commonly found terrain, such as seashores, river beds, etc.

entire country. This is reproduced in **Fig 43**, a chart showing the "estimated effective ground conductivity in the United States." A range of 30:1 is shown, from 1 to 30 mS/m. An equivalent chart for Canada has been prepared, originally by DOT, now DOC.

Of course, some judgment is needed when trying to use this data for your location. Broadcast stations are likely to be in open areas, so the data should not be assumed to apply to the center city. And a low site near the sea is likely to have better conductivity than the generic chart for, say, the coast of Oregon. Other than such factors, this chart gives a good first value, and a useful cross-check if some other method is used.

Still another FCC-induced data source is the license application of your local broadcast station. This includes calculated and measured coverage data. This may include specific ground data, or comparison of the coverage curves with the CCIR or FCC data to give the estimated ground conductivity. Another set of curves for ground conditions are those prepared by SRI. These give the conductivity and dielectric constant versus frequency for typical terrain conditions. These are reproduced as **Fig 44** and **Fig 45**. By inspecting your own site, you may select the curve most appropriate to your terrain. The curves are based on measurements at a number of sites across the USA, and are averages of the measured values.

Fig 44—Typical terrain conductivities versus frequency for 5 types of soils. This was measured by SRI. Units are mS/m. Conductivity of seawater is usually taken as 5000 mS/m. Conductivity of fresh water depends on the impurities present, and may be very low. To extrapolate conductivity values (for 500 to 1500 KHz) shown in Fig 43 for a particular geographic area to a different frequency, move from the conductivity at the left edge of Fig 44 to the desired frequency. For example, in rocky New Hampshire, with a conductivity of 1 mS/m at BC frequencies, the effective conductivity at 14 MHz would be approximately 4 mS/m.

Figs 46 through 48 are data derived from these measurements. **Fig 46** gives the ground-dissipation factor. Sea water has low loss (a high dissipation factor), while soil in the desert or in the city is very lossy, with a low dissipation factor. **Fig 47** gives the skin depth, the distance for the signal to decease to 63% of its value at the surface. Penetration is low in high-conductivity areas and deep in low-conductivity soil. Finally, **Fig 48** shows the wavelength in the earth. For example, at 10 meters (30 MHz), the wavelength in sea water is less than 0.3 meters. Even in the desert, the wavelength has been reduced to about 6 meters at this frequency. This is one reason why buried antennas have peculiar properties. Lacking other data, it is suggested that the values of Figs 44 and 45 be used in computer antenna modeling programs.

Measuring Ground Conditions

W2FNQ developed a simple technique to measure low-frequency earth conductivity, which has been used by W2FMI. The test setup is drawn in **Fig 49**, and uses a very old technique of 4-terminal resistivity measurements. For probes of $^9/_{16}$-inch diameter, spaced 18 inches and penetrating 12 inches into the earth, the conductivity is:

$$C = 21 \ V_1/V_2 \quad \text{mS/m} \quad \quad \text{(Eq 19)}$$

The voltages are conveniently measured by a digital voltmeter, to an accuracy of about 2%. In soil suitable for farming, the probes can be copper or aluminum. The strength of iron or copperweld may be needed in hard soils. A piece of 2×4 or 4×4 with guide holes drilled through it will help maintain proper spacing and vertical alignment of the probes. Use care when measuring—there is a shock hazard. An isolating transformer with a 24-V secondary instead of 115 V will reduce the danger.

Ground conditions vary quite widely over even small

Fig 45—Typical terrain relative dielectric constant for the 5 soil types of Fig 44, plus sea water. The dashed curve shows the highest measured values reported, and usually indicates mineralization.

Fig 46—Typical values of dissipation factor. The soil behaves as a leaky dielectric. These curves showing the dimensionless dissipation factor versus frequency for various types of soils and for sea water. The dissipation factor is inversely related to soil conductivity. Among other things, a high dissipation factor indicates that a signal penetrating the soil or water will decrease in strength rapidly with depth.

Fig 47—Typical values of skin depth. The skin depth is the depth at which a signal will have decreased to 1/e of its value at the surface (to about 30%). The effective height above ground is essentially the same as the physical height for sea water, but may be much greater for the desert. For practical antennas, this may increase low-angle radiation, but at the same time will increase ground losses.

Fig 48—Typical values of wavelength in soil. Because of its dielectric constant, the wavelength in soils and water will be shorter than that for a wave traveling in air. This can be important, since in a Method of Moment the accuracy is affected by the number of analysis segments per wavelength. Depending on the program being used, adjust the number of segments for antennas wholly or partly in the earth, for ground rods, and for antennas very close to earth.

Fig 49—Low-frequency conductivity measurement system. A 60-Hz measuring system devised by W2FNQ and used by W2FMI. The basic system is widely used in geophysics. Use care to be certain that the plug connection is correct. A better system would use a lower voltage and an isolation transformer. Measure the value of V_2 with no power applied—there may be stray ground currents present, especially if there is a power station or an electric railway close.

areas. It is best to make a number of measurements around the area of the antenna, and average the measured values.

While this measurement gives only the low-frequency conductivity, it can be used to select curves in Fig 44 to give an estimate of the conductivity for the common ham bands. Assume that the 60 Hz value is valid at 2 MHz, and find the correct value on the left axis. Move parallel to the curves on the figure to develop the estimated curve for other soil conditions.

A small additional refinement is possible. If the dielectric constant from Fig 45 is plotted against the conductivity from Fig 44 for a given frequency, a scatter plot develops, showing a trend to higher dielectric constant as conductivity increases. At 14 MHz, the relation is:

$$k = \sqrt{1000/C} \qquad \text{(Eq 20)}$$

where k is the dielectric constant and C is the measured conductivity. Using these values in *MININEC* or *NEC* calculations should give better estimates than countrywide average values.

Direct Measurement of Ground Properties

For really good values, both the conductivity and dielectric constant should be measured at the operating frequency. One way of doing this is the two-probe technique described in George Hagn's article (see Bibliography). This was the technique used to secure the data for Figs 44 through 48. The principle is sketched in **Fig 50**. In essence, the two probes form a short, open-circuited, two-wire transmission line. As shown by the equations for such lines, the input impedance is a function of the conductivity and dielectric constant of the medium. A single measurement is difficult to calculate, since the end effect of the two probes must be determined, a complex task if they are pointed for easy driving. The calculation is greatly simplified if a set of measurements is made with several sets of probes that vary in length by a fixed ratio, since the measured difference is largely due to the increased two-wire length, with some change due to the change in soil moisture with depth.

The impedance to be measured is high because of the short line length, so impedance bridges are not really suitable. An RF vector impedance meter, such as the HP-4193A, is probably the best instrument to use, with a RF susceptance bridge, such as the GR-821A, next best. With care, a Q-meter can be substituted. Because of the rarity of these instruments among amateurs, this method of measurement is not explored further here.

Indirect Measurement

Since the terminal impedance and resonant frequency of an antenna change as the antenna approaches earth, measurement of an antenna at one or more heights permits an analysis of the ground characteristics. The technique is to calculate the antenna drive impedance for an assumed ground condition, and compare this with

Fig 50—High-frequency conductivity/dielectric constant measurement system. System for measuring ground conditions at frequencies up to about 100 MHz, devised by SRI and used to obtain the data in Figs 44 through 48. Basically, this is a section of transmission line with soil as the dielectric. Requires measurement of high impedances to good accuracy.

measured values. If not the same, another set of ground conditions is assumed, and the process is repeated. It is best to have a plan to guide the assumptions.

In connection with his studies of transmission lines, Walt Maxwell, W2DU, made such measurements on 20, 40 and 80 meters. Some of the data was included in his book *Reflections*. The following example is based on his 80-meter data. Data came from his Table 20-1, for a 66-foot, 2-inch dipole of #14 wire at 40 feet above ground. His table gives an antenna impedance of $72.59 + j\,1.38\ \Omega$ at 7.15 MHz.

Table 7 shows calculated antenna impedances for ground conductivities of three different ground conductivities: 10, 1 and 0.1 mS/m, and for dielectric constants of 3, 15 and 80. The nearest value to the measured drive impedance is for a conductivity of 0.1 mS/m and a dielectric constant of 3. Figs 44 and 45 indicate that these are typical of flat desert and city land. The effect on antenna performance is shown in **Fig 51**. The maximum lobe gain for soil typical of a city is over 2 dB lower than that for the high-conductivity, high-dielectric constant value. Note that the maximum lobe occurs for a radiation angle that is directly overhead.

Table 7

Calculated values of drive resistance, in ohms, for an 40 meter dipole at 40 feet elevation versus conductivity and dielectric constant.

Conductivity (mS/m)	Dielectric Constant		
	3	15	50
10	89.78 − j 12.12	88.53 − j 10.69	88.38 − j 7.59
1	80.05 − j 17.54	83.72 − j 10.23	87.33 − j 6.98
0.1	76.44 − j 15.69	83.18 − j 9.85	97.30 − j 6.46

The value measured by W2DU was 72.59 − j 1.28 Ω, and compares closest to the poor soil condition of dielectric constant of 3 and conductivity of 0.1 mS/m.

Fig 51—Plot showing computed elevation patterns for 40-foot high, 40-meter dipole for two different ground conditions: poor ground, with dielectric constant of 3 and conductivity of 0.1 mS/m, and good ground, with dielectric constant of 50 and conductivity of 10 mS/m. Note that for a low horizontal antenna, high-angle radiation is most affected by poor ground, with low-angle radiation least affected by ground characteristics.

The ground at the W2DU QTH is a suburban Florida lot, covered with low, native vegetation. The ground is very sandy (a fossil sand dune), and is some 60-70 feet above sea-level. Measurements were made near the end of the Florida dry season. The water table is estimated to be 20 to 30 feet below the surface. Thus the calculated and measured values are reasonably consistent.

In principle, a further analysis, using values around 0.1 mS/m conductivity and 3 for dielectric constant, will give a better ground parameter estimate. However, the results should be taken with a grain of salt, because the opportunities for error in the computer modeling must be considered. The antenna should have no sag, and its length and height should be accurate. The measurement must be with accurate equipment, free from strays, such as current on the outer conductor of the coax. The feed-point gap effect must be estimated. Further, the ground itself under the antenna must be flat and have constant characteristics for modeling to be completely accurate.

Finally, the feed-line length and velocity constant of the transmission line must be accurately measured for transfer of the measured values at the feeding end of the transmission line to the antenna itself. Because of all the possibilities for error, most attempts at precision should be based on measured values at two or three frequencies, and preferably at two or three heights. Orienting the antenna to right angles for another set of measurements may be useful. Obviously, this can involve a lot of detailed work.

The author was not been able to find any guidelines for the best height or frequency. The data in the book *Exact Image Method for Impedance Computation of Antennas Above the Ground* suggests that a height of 0.3 λ will give good sensitivity to ground conditions. Very low heights may give confusing results, since several combinations of ground parameters can give nearly the same drive impedance. Both this data and experience suggest that sensitivity to ground for heights above 0.75 λ is small or negligible.

If an overall conclusion about ground characteristics is needed, we can just restate from the first paragraph—it is not greatly important for the most common horizontally polarized antenna installations. But it's worth taking a look when you need to depart from typical situations, or when the performance of a vertically polarized antenna is contemplated. Then the techniques outlined here can be helpful.

A Switchable RF Attenuator

A switchable RF attenuator is helpful for making antenna-gain comparisons or for plotting antenna radiation patterns. You may switch attenuation in or out of the line leading to the receiver to obtain an initial reference reading on a signal strength meter. Some form of attenuator is also helpful for locating hidden transmitters, where the real trick is pinpointing the signal source from within a few hundred feet. At such a close distance, strong signals may overload the front end of the receiver, making it impossible to obtain any indication of a bearing.

The attenuator of **Figs 52** and **53** is designed for low power levels, not exceeding $^1/_4$ watt. If for some reason the attenuator will be connected to a transceiver, a means of bypassing the unit during transmit periods must be devised. An attenuator of this type is commonly called a *step attenuator*, because any amount of attenuation from 0 dB to the maximum available (81 dB for this particular instrument) may be obtained in steps of 1 dB. As each switch is successively thrown from the OUT to the IN position, the attenuation sections add in cascade to yield the total of the attenuator steps switched in. The maximum attenuation of any single section is limited to 20 dB because leak-through would probably degrade the accuracy of higher values. The tolerance of resistor values also becomes more significant regarding accuracy at higher attenuation values.

A good quality commercially made attenuator will cost upwards from $150, but for less than $25 in parts and a few hours of work, you can build an attenuator at home. It will be suitable for frequencies up to 450 MHz. Double-sided pc board is used for the enclosure. The version of the attenuator shown in Fig 52 has identification lettering etched into the top surface (or front panel) of the unit. This adds a nice touch and is a permanent means of labeling. Of course rub-on transfers or Dymo tape labels could be used as well.

Female BNC single-hole, chassis-mount connectors are used at each end of the enclosure. These connectors

Fig 52—A construction method for a step attenuator. Double-sided circuit-board material, unetched (except for panel identification), is cut to the desired size and soldered in place. Flashing copper may also be used, although it is not as sturdy. Shielding partitions between sections are necessary to reduce signal leakage. Brass nuts soldered at each of the four corners allow machine screws to secure the bottom cover. The practical limit for total attenuation is 80 or 90 dB, as signal leakage around the outside of the attenuator will defeat attempts to obtain much greater amounts.

Fig 53—Schematic diagram of the step attenuator, designed for a nominal impedance of 50 Ω. Resistance values are in ohms. Resistors are $^1/_4$-watt, carbon-composition types, 5% tolerance. Broken lines indicate walls of circuit-board material. A small hole is drilled through each partition wall to route bus wire. Keep all leads as short as possible. The attenuator is bilateral; that is, the input and output ends may be reversed.

J1, J2—Female BNC connectors, Radio Shack 278-105 or equiv.

S1-S8, incl.—DPDT slide switches, standard size. (Avoid subminiature or toggle switches.) Stackpole S-5022CD03-0 switches are used here.

provide a means of easily connecting and disconnecting the attenuator.

Construction

After all the box parts are cut to size and the necessary holes made, scribe light lines to locate the inner partitions. Carefully tack-solder all partitions in position. A 25-W pencil type of iron should provide sufficient heat. Dress any pc board parts that do not fit squarely. Once everything is in proper position, run a solder bead all the way around the joints. Caution! Do not use excessive amounts of solder, as the switches must later be fit flat inside the sections. Complete the top, sides, ends and partitions. Dress the outside of the box to suit your taste. For instance, you might wish to bevel the box edges. Buff the copper with steel wool, add lettering, and finish off the work with a coat of clear lacquer or polyurethane varnish.

Using a little lacquer thinner, soak the switches to remove the grease that was added during their manufacture. When they dry, spray the inside of the switches lightly with a TV tuner cleaner/lubricant. Use a sharp drill bit (about $3/16$ inch will do), and countersink the mounting holes on the actuator side of the switch mounting plate. This ensures that the switches will fit flush against the top plate. At one end of each switch, bend the two lugs over and solder them together. Cut off the upper halves of the remaining switch lugs. (A close look at Fig 52 will help clarify these steps.)

Solder the series-arm resistors between the appropriate switch lugs. Keep the lead lengths as short as possible and do not overheat the resistors. Now solder the switches in place to the top section of the enclosure by flowing solder through the mounting holes and onto the circuit-board material. Be certain that you place the switches in their proper positions; correlate the resistor values with the degree of attenuation. Otherwise, you may wind up with the 1-dB step at the wrong end of the box how embarrassing!

Once the switches are installed, thread a piece of #18 bare copper wire through the center lugs of all the switches, passing it through the holes in the partitions. Solder the wire at each switch terminal. Cut the wire between the poles of each individual switch, leaving the wire connecting one switch pole to that of the neighboring one on the other side of the partition, as shown in Fig 52. At each of the two end switch terminals, leave a wire length of approximately $1/8$ inch. Install the BNC connectors and solder the wire pieces to the connector center conductors.

Now install the shunt-arm resistors of each section. Use short lead lengths. Do not use excessive amounts of heat when soldering. Solder a no. 4-40 brass nut at each inside corner of the enclosure. Recess the nuts approximately $1/16$-inch from the bottom edge of the box to allow sufficient room for the bottom panel to fit flush. Secure the bottom panel with four no. 4-40, $1/4$-inch machine screws and the project is completed. Remember to use caution, always, when your test setup provides the possibility of transmitting power into the attenuator.

A Portable Field Strength Meter

Few amateur stations, fixed or mobile, are without need of a field-strength meter. An instrument of this type serves many useful purposes during antenna experiments and adjustments. When work is to be done from many wavelengths away, a simple wavemeter lacks the necessary sensitivity. Further, such a device has a serious fault because its linearity leaves much to be desired. The information in this section is based on a January 1973 *QST* article by Lew McCoy, W1ICP.

The field-strength meter described here takes care of these problems. Additionally, it is small, measuring only $4 \times 5 \times 8$ inches. The power supply consists of two 9-volt batteries. Sensitivity can be set for practically any amount desired. However, from a usefulness standpoint, the circuit should not be too sensitive or it will respond to unwanted signals. This unit also has excellent linearity with regard to field strength. (The field strength of a received signal varies inversely with the distance from the source, all other things being equal.) The frequency range includes all amateur bands from 3.5 through

Fig 54—The linear field strength meter. The control at the upper left is for C1 and the one to the right for C2. At the lower left is the band switch, and to its right the sensitivity switch. The zero-set control for M1 is located directly below the meter.

Fig 55—Inside view of the field-strength meter. At the upper right is C1 and to the left, C2. The dark leads from the circuit board to the front panel are the shielded leads described in the text.

148 MHz, with band-switched circuits, thus avoiding the use of plug-in inductors. All in all, it is a quite useful instrument.

The unit is pictured in **Figs 54** and **55**, and the schematic diagram is shown in **Fig 56**. A type 741 op-amp IC is the heart of the unit. The antenna is connected to J1, and a tuned circuit is used ahead of a diode detector. The rectified signal is coupled as dc and amplified in the op amp. Sensitivity of the op amp is controlled by inserting resistors R3 through R6 in the circuit by means of S2.

With the circuit shown, and in its most sensitive setting, M1 will detect a signal from the antenna on the order of 100 µV. Linearity is poor for approximately the first $1/5$ of the meter range, but then is almost straight-line from there to full-scale deflection. The reason for the poor linearity at the start of the readings is because of non-linearity of the diodes at the point of first conduction. However, if gain measurements are being made this is of no real importance, as accurate gain measurements can be made in the linear portion of the readings.

Fig 56—Circuit diagram of the linear field strength meter. All resistors are $1/4$- or $1/2$-W composition types.

C1 — 140 pF variable.
C2 — 15-pF variable
D1, D2 — 1N914 or equiv.
L1 — 34 turns #24 enam. wire wound on an Amidon
   T-68-2 core, tapped 4 turns from ground end.
L2 — 12 turns #24 enam. wire wound on T-68-2 core.
L3 — 2 turns #24 enam. wire wound at ground end of L2.
L4 — 1 turn #26 enam. wire wound at ground end of L5.
L5 — 12 turns #26 enam. wire wound on T-25-12 core.

L6 — 1 turn #26 enam. wire wound at ground end of L7.
L7 — 1 turn #18 enam. wire wound on T-25-12 core.
M1 — 50 or 100 µA dc.
R2 — 10-kΩ control, linear taper.
S1 — Rotary switch, 3 poles, 5 positions, 3 sections.
S2 — Rotary switch, 1 pole, 4 positions.
S3 — DPST toggle.
U1 — Type 741 op amp. Pin numbers shown are for a
   14-pin package.

The 741 op amp requires both a positive and a negative voltage source. This is obtained by connecting two 9-volt batteries in series and grounding the center. One other feature of the instrument is that it can be used remotely by connecting an external meter at J2. This is handy if you want to adjust an antenna and observe the results without having to leave the antenna site.

L1 is the 3.5/7 MHz coil and is tuned by C1. The coil is wound on a toroid form. For 14, 21 or 28 MHz, L2 is switched in parallel with L1 to cover the three bands. L5 and C2 cover approximately 40 to 60 MHz, and L7 and C2 from 130 MHz to approximately 180 MHz. The two VHF coils are also wound on toroid forms.

Construction Notes

The majority of the components may be mounted on an etched circuit board. A shielded lead should be used between pin 4 of the IC and S2. The same is true for the leads from R3 through R6 to the switch. Otherwise, parasitic oscillations may occur in the IC because of its very high gain.

In order for the unit to cover the 144-MHz band, L6 and L7 should be mounted directly across the appropriate terminals of S1, rather than on a circuit board. The extra lead length adds too much stray capacitance to the circuit. It isn't necessary to use toroid forms for the 50- and 144-MHz coils. They were used in the version described here simply because they were available. You may substitute air-wound coils of the appropriate inductance.

Calibration

The field strength meter can be used *as is* for a relative-reading device. A linear indicator scale will serve admirably. However, it will be a much more useful instrument for antenna work if it is calibrated in decibels, enabling the user to check relative gain and front-to-back ratios. If you have access to a calibrated signal generator, connect it to the field-strength meter and use different signal levels fed to the device to make a calibration chart. Convert signal-generator voltage ratios to decibels by using the equation

$$dB = 20 \log (V1/V2) \qquad (Eq\ 21)$$

where

V1/V2 is the ratio of the two voltages

log is the common logarithm (base 10)

Let's assume that M1 is calibrated evenly from 0 to 10. Next, assume we set the signal generator to provide a reading of 1 on M1, and that the generator is feeding a 100-μV signal into the instrument. Now we increase the generator output to 200 μV, giving us a voltage ratio of 2:1. Also let's assume M1 reads 5 with the 200-μV input. From the equation above, we find that the voltage ratio of 2 equals 6.02 dB between 1 and 5 on the meter scale. M1 can be calibrated more accurately between 1 and 5 on its scale by adjusting the generator and figuring the ratio. For example, a ratio of 126 μV to 100 μV is 1.26, corresponding to 2.0 dB. By using this method, all of the settings of S2 can be calibrated. In the instrument shown here, the most sensitive setting of S2 with R3, 1 MΩ, provides a range of approximately 6 dB for M1. Keep in mind that the meter scale for each setting of S1 must be calibrated similarly for each band. The degree of coupling of the tuned circuits for the different bands will vary, so each band must be calibrated separately.

Another method for calibrating the instrument is using a transmitter and measuring its output power with an RF wattmeter. In this case we are dealing with power rather than voltage ratios, so this equation applies:

$$dB = 10 \log (P1/P2) \qquad (Eq\ 22)$$

where P1/P2 is the power ratio.

With most transmitters the power output can be varied, so calibration of the test instrument is rather easy. Attach a pickup antenna to the field-strength meter (a short wire a foot or so long will do) and position the device in the transmitter antenna field. Let's assume we set the transmitter output for 10 W and get a reading on M1. We note the reading and then increase the output to 20 W, a power ratio of 2. Note the reading on M1 and then use Eq 2. A power ratio of 2 is 3.01 dB. By using this method the instrument can be calibrated on all bands and ranges.

With the tuned circuits and coupling links specified in Fig 56, this instrument has an average range on the various bands of 6 dB for the two most sensitive positions of S2, and 15 dB and 30 dB for the next two successive ranges. The 30-dB scale is handy for making front-to-back antenna measurements without having to switch S2.

An RF Current Probe

The RF current probe of **Figs 57** through **59** operates on the magnetic component of the electromagnetic field, rather than the electric field. Since the two fields are precisely related, as discussed in Chapter 23, the relative field strength measurements are completely equivalent. The use of the magnetic field offers certain advantages, however. The instrument may be made more compact for the same sensitivity, but its principal advantage is that it may be used near a conductor to measure the current flow without cutting the conductor.

In the average amateur location there may be substantial currents flowing in guy wires, masts and towers, coaxial-cable braids, gutters and leaders, water and gas pipes, and perhaps even drainage pipes. Current may be flowing in telephone and power lines as well. All of these RF currents may have an influence on antenna patterns or can be of significance in the case of RFI.

The circuit diagram of the current probe appears in Fig 58, and construction is shown in the photo, Fig 59. The winding data given here apply only to a ferrite rod of the particular dimensions and material specified. Almost any microammeter can be used, but it is usually convenient to use a rather sensitive meter and provide a series resistor to swamp out nonlinearity arising from diode conduction characteristics. A control is also used to adjust instrument sensitivity as required during operation. The tuning capacitor may be almost anything that will cover the desired range.

Fig 57—The RF current probe. The sensitivity control is mounted at the top of the instrument, with the tuning and band switches on the lower portion of the front panel. Frequency calibration of the tuning control was not considered necessary for the intended use of this particular instrument, but marks identifying the various amateur bands would be helpful. If the unit is provided with a calibrated dial, it can also be used as an absorption wavemeter.

Fig 58—Schematic diagram of the RF current probe. Resistances are in ohms; k = 1000. Capacitances are in picofarads; fixed capacitors are silver mica. Be sure to ground the rotor of C1, rather than the stator, to avoid hand capacitance. L1, L2 and L3 are each close-wound with #22 enameled wire on a single ferrite rod, 4 inch long and $1/2$ inch diameter, with μ = 125 (Amidon R61-50-400). Windings are spaced approximately $1/4$ inch apart.

C1—Air variable, 6-140 pF; Hammarlund HF140 or equiv.
D1—Germanium diode; 1N34A, 1N270 or equiv.
L1—1.6-5 MHz; 30 turns, tapped at 3 turns from grounded end.
L2—5-20 MHz; 8 turns, tapped at 2 turns from grounded end.
L3—17-39 MHz; 2 turns, tapped at 1 turn.
M1—Any microammeter may be used. The one pictured is a Micronta meter, RadioShack no. 270-1751.
R1—Linear taper.
RFC1—1 mH; Miller no. 4642 or equiv. Value is not critical.
S1—Ceramic rotary switch, 1 section, 2 poles, 2 to 6 positions; Centralab PA2002 or PA2003 or equiv.

ANT0961

Fig 59—The current probe just before final assembly. Note that all parts except the ferrite rod are mounted on a single half of the 3 × 4 × 5-inch Minibox (Bud CU-2105B or equiv.). Rubber grommets are fitted in holes at the ends of the slot to accept the rod during assembly of the enclosure. Leads in the RF section should be kept as short as possible, although those from the rod windings must necessarily be left somewhat long to facilitate final assembly.

As shown in the photos, the circuit is constructed in a metal box. This enclosure shields the detector circuit from the electric field of the radio wave. A slot must be cut with a hacksaw across the back of the box, and a thin file may be used to smooth the cut. This slot is necessary to prevent the box from acting as a shorted turn.

Using the Probe

In measuring the current in a conductor, the ferrite rod should be kept at right angles to the conductor, and at a constant distance from it. In its upright or vertical position, this instrument is oriented for taking measurements in vertical conductors. It must be laid horizontal to measure current in horizontal conductors.

Numerous uses for the instrument are suggested in an earlier paragraph. In addition, the probe is an ideal instrument for checking the current distribution in antenna elements. It is also useful for measuring RF ground currents in radial systems. A buried radial may be located easily by sweeping the ground. Current division at junctions may be investigated. *Hot spots* usually indicate areas where additional radials would be effective.

Stray currents in conductors not intended to be part of the antenna system may often be eliminated by bonding or by changing the physical lengths involved. Guy wires and other unwanted parasitic elements will often give a tilt to the plane of polarization and can make a marked difference in front-to-back ratios. When the ferrite rod is oriented parallel to the electric field lines, there will be a sharp null reading that may be used to locate the plane of polarization quite accurately. When using the meter, remember that the magnetic field is at right angles to the electric field.

You may also use the current probe as a relative signal strength meter. When making measurements on a vertical antenna, locate the meter at least two wavelengths away, with the rod in a horizontal position. For horizontal antennas, hold the instrument at approximately the same height as the antenna, with the rod vertical.

Antenna Measurements

Of all the measurements made in Amateur Radio systems, perhaps the most difficult and least understood are various measurements of antennas. For example, it is relatively easy to measure the frequency and CW power output of a transmitter, the response of a filter, or the gain of an amplifier. These are all what might be called *bench measurements* because, when performed properly, all the factors that influence the accuracy and success of the measurement are under control. In making antenna measurements, however, the "bench" is probably your backyard. In other words, the environment surrounding the antenna can affect the results of the measurement.

Control of the environment is not at all as simple as it was for the bench measurement, because now the work area may be rather spacious. This section describes antenna measurement techniques that are closely allied to those used in an antenna measuring event or contest. With these procedures you can make measurements successfully and with meaningful results. These techniques should provide a better understanding of the measurement problems, resulting in a more accurate and less difficult task. The information in this section was provided by Dick Turrin, W2IMU, and was originally published in November 1974 *QST*.

SOME BASIC IDEAS

An antenna is simply a transducer or coupler between a suitable feed line and the environment surrounding it. In addition to the efficient transfer of power from feed line to environment, an antenna at VHF or UHF is most frequently required to concentrate the radiated power into a particular region of the environment.

To be consistent while comparing different antennas, you must standardize the environment surrounding the antenna. Ideally, you want to make measurements with the measured antenna so far removed from any objects causing environmental effects that it is literally in outer space— a very impractical situation. The purpose of the measurement techniques is therefore to simulate, under practical conditions, a *controlled environment*. At VHF

and UHF, and with practical-size antennas, the environment can be controlled so that successful and accurate measurements can be made in a reasonable amount of space.

The electrical characteristics of an antenna that are most desirable to obtain by direct measurement are: (1) gain (relative to an isotropic source, which by definition has a gain of unity); (2) space-radiation pattern; (3) feed-point impedance (mismatch) and (4) polarization.

Polarization

In general the polarization can be assumed from the geometry of the radiating elements. That is to say, if the antenna consists of a number of linear elements (straight lengths of rod or wire that are resonant and connected to the feed point) the polarization of the electric field will be linear and polarized parallel to the elements. If the elements are not consistently parallel with each other, then the polarization cannot easily be assumed. The following techniques are directed to antennas having polarization that is essentially linear (in one plane), although the method can be extended to include all forms of elliptic (or mixed) polarization.

Feed-Point Mismatch

The feed-point mismatch, although affected to some degree by the immediate environment of the antenna, does not affect the gain or radiation characteristics of an antenna. If the immediate environment of the antenna does not affect the feed-point impedance, then any mismatch intrinsic to the antenna tuning reflects a portion of the incident power back to the source. In a receiving antenna this reflected power is reradiated back into the environment, and can be lost entirely.

In a transmitting antenna, the reflected power travels back down the feed line to the transmitter, where it changes the load impedance presented to that transmitter. The amplifier output controls are customarily altered during the normal tuning procedure to obtain maximum power transfer to the antenna. You can still use a mismatched antenna to its full gain potential, provided the mismatch is not so severe as to cause heating losses in the system, especially the feed line and matching devices. (See also the discussion of additional loss caused by SWR in Chapter 24.)

Similarly, a mismatched receiving antenna may be matched into the receiver front end for maximum power transfer. In any case you should clearly keep in mind that the feed-point mismatch does not affect the radiation characteristics of an antenna. It can only affect the system efficiency when heating losses are considered.

Why then do we include feed-point mismatch as part of the antenna characteristics? The reason is that for efficient system performance, most antennas are resonant transducers and present a reasonable match over a relatively narrow frequency range. It is therefore desirable to design an antenna, whether it be a simple dipole or an array of Yagis, such that the final single feed-point impedance is essentially resistive and matched to the feed line. Furthermore, in order to make accurate, absolute gain measurements, it is vital that the antenna under test accept all the power from a matched-source generator, or that the reflected power caused by the mismatch be measured and a suitable error correction for heating losses be included in the gain calculations. Heating losses may be determined from information contained in Chapter 24.

While on the subject of feed-point impedance, mention should be made of the use of *baluns* in antennas. A balun is simply a device that permits a lossless transition between a balanced system feed line or antenna and an unbalanced feed line or system. If the feed point of an antenna is symmetric, such as with a dipole, and it is desired to feed this antenna with an unbalanced feed line such as coax, you should provide a balun between the line and the feed point. Without the balun, current will be allowed to flow on the outside of the coax. The current on the outside of the feed line will cause radiation, and thus the feed line will become part of the antenna radiation system. In the case of beam antennas, where it is desired to concentrate the radiated energy is a specific direction, this extra radiation from the feed line will be detrimental, causing distortion of the expected antenna pattern. See Chapter 26 for additional details on this problem.

ANTENNA TEST SITE SET-UP AND EVALUATION

Since an antenna is a reciprocal device, measurements of gain and radiation patterns can be made with the test antenna used either as a transmitting or as a receiving antenna. In general and for practical reasons, the test antenna is used in the receiving mode, and the source or transmitting antenna is located at a specified fixed remote site and unattended. In other words the source antenna, energized by a suitable transmitter, is simply required to illuminate or flood the receiving site in a controlled and constant manner.

As mentioned earlier, antenna measurements ideally should be made under free-space conditions. A further restriction is that the illumination from the source antenna be a *plane wave* over the effective aperture (capture area) of the test antenna. A plane wave by definition is one in which the magnitude and phase of the fields are uniform, and in the test-antenna situation, *uniform over the effective area plane of the test antenna*. Since it is the nature of all radiation to expand in a spherical manner at great distance from the source, it would seem to be most desirable to locate the source antenna as far from the test site as possible. However, since for practical reasons the test site and source location will have to be near the earth and not in outer space, the environment must include the effects of the ground surface and other obstacles in the vicinity of both antennas. These effects almost always

dictate that the test range (spacing between source and test antennas) be as short as possible consistent with maintaining a nearly error-free plane wave illuminating the test *aperture*.

A nearly error-free plane wave can be specified as one in which the phase and amplitude, from center to edge of the illuminating field over the test aperture, do not deviate by more than about 30° and 1 decibel, respectively. These conditions will result in a gain-measurement error of no more than a few percent less than the true gain. Based on the 30° phase error alone, it can be shown that the minimum range distance is approximately

$$S_{min} = 2 \frac{D^2}{\lambda} \qquad \text{(Eq 23)}$$

where D is the largest aperture dimension and λ is the free-space wavelength in the same units as D. The phase error over the aperture D for this condition is $^1/_{16}$ wavelength.

Since aperture size and gain are related by

$$Gain = \frac{4\pi A_e}{\lambda^2} \qquad \text{(Eq 24)}$$

where A_e is the effective aperture area, the dimension D may be obtained for simple aperture configurations. For a square aperture

$$D_2 = G \frac{\lambda^2}{4\pi} \qquad \text{(Eq 25)}$$

that results in a minimum range distance for a square aperture of

$$S_{min} = G \frac{\lambda}{2\pi} \qquad \text{(Eq 26)}$$

and for a circular aperture of

$$S_{min} = G \frac{2\lambda}{\pi^2} \qquad \text{(Eq 27)}$$

For apertures with a physical area that is not well defined or is much larger in one dimension that in other directions, such as a long thin array for maximum directivity in one plane, it is advisable to use the maximum estimate of D from either the expected gain or physical aperture dimensions.

Up to this point in the range development, only the conditions for minimum range length, S_{min}, have been established, as though the ground surface were not present. This minimum S is therefore a necessary condition even under free-space environment. The presence of the ground further complicates the range selection, not in the determination of S but in the exact location of the source and test antennas above the earth.

It is always advisable to select a range whose intervening terrain is essentially flat, clear of obstructions, and of uniform surface conditions, such as all grass or all pave-

Fig 60—On an antenna test range, energy reaching the receiving equipment may arrive after being reflected from the surface of the ground, as well as by the direct path. The two waves may tend to cancel each other, or may reinforce one another, depending on their phase relationship at the receiving point.

ment. The extent of the range is determined by the illumination of the source antenna, usually a Yagi, whose gain is no greater than the highest gain antenna to be measured. For gain measurements the range consists essentially of the region in the beam of the test antenna. For radiation-pattern measurements, the range is considerably larger and consists of all that area illuminated by the source antenna, especially around and behind the test site. Ideally you should choose a site where the test-antenna location is near the center of a large open area and the source antenna is located near the edge where most of the obstacles (trees, poles, fences, etc.) lie.

The primary effect of the range surface is that some of the energy from the source antenna will be reflected into the test antenna, while other energy will arrive on a direct line-of-sight path. This is illustrated in **Fig 60**. The use of a flat, uniform ground surface assures that there will be essentially a mirror reflection, even though the reflected energy may be slightly weakened (absorbed) by the surface material (ground). In order to perform an analysis you should realize that horizontally polarized waves undergo a 180° phase reversal upon reflection from the earth. The resulting illumination amplitude at any point in the test aperture is the vector sum of the electric fields arriving from the two directions, the direct path and the reflected path.

If a perfect mirror reflection is assumed from the ground (it is nearly that for practical ground conditions at VHF/UHF) and the source antenna is isotropic, radiating equally in all directions, then a simple geometric analysis of the two path lengths will show that at various point in the vertical plane at the test-antenna site the waves will combine in different phase relationships. At some points the arriving waves will be in phase, and at other points they will be 180° out of phase. Since the field amplitudes are nearly equal, the resulting phase change caused by path length difference will produce an ampli-

Fig 61—The vertical profile, or plot of signal strength versus test-antenna height, for a fixed height of the signal source above ground and at a fixed distance. See text for definitions of symbols.

tude variation in the vertical test site direction similar to a standing wave, as shown in **Fig 61**.

The simplified formula relating the location of h2 for maximum and minimum values of the two-path summation in terms of h1 and S is

$$h2 = n\frac{\lambda}{4} \times \frac{S}{h1}$$ (Eq 28)

with n = 0, 2, 4, . . . for minimums and n = 1, 3, 5, . . . for maximums, and S is much larger than either h1 or h2.

The significance of this simple ground reflection formula is that it permits you to determine the approximate location of the source antenna to achieve a nearly plane-wave amplitude distribution *in the vertical direction* over a particular test *aperture size*. It should be clear from examination of the height formula that as h1 is decreased, the vertical distribution pattern of signal at the test site, h2, expands. Also note that the signal level for h2 equal to zero is always zero on the ground regardless of the height of h1.

The objective in using the height formula then is, given an effective antenna aperture to be illuminated from which a minimum S (range length) is determined and a suitable range site chosen, to find a value for h1 (source antenna height). The required value is such that the *first* maximum of vertical distribution at the test site, h2, is at a practical distance above the ground, and at the same time the signal amplitude over the aperture in the vertical direction does not vary more than about 1 dB. This last condition is not sacred but is closely related to the particular antenna under test.

In practice these formulas are useful only to initialize the range setup. A final check of the vertical distribution at the test site must be made by direct measurement. This measurement should be conducted with a small low-gain but unidirectional probe antenna such as a corner

reflector or 2-element Yagi that you move along a vertical line over the intended aperture site. Care should be exercised to minimize the effects of local environment around the probe antenna and that the beam of the probe be directed at the source antenna at all times for maximum signal. A simple dipole is undesirable as a probe antenna because it is susceptible to local environmental effects.

The most practical way to instrument the vertical distribution measurement is to construct some kind of vertical track, preferably of wood, with a sliding carriage or platform that may be used to support and move the probe antenna. It is assumed of course that a stable source transmitter and calibrated receiver or detector are available so variations of the order of $1/2$ dB can be clearly distinguished.

Once you conduct these initial range measurements successfully, the range is now ready to accommodate any aperture size less in vertical extent than the largest for which S_{min} and the vertical field distribution were selected. Place the test antenna with the center of its aperture at the height h2 where maximum signal was found. Tilt the test antenna tilted so that its main beam is pointed in the direction of the source antenna. The final tilt is found by observing the receiver output for maximum signal. This last process must be done empirically since the apparent location of the source is somewhere between the actual source and its image, below the ground.

An example will illustrate the procedure. Assume that we wish to measure a 7-foot diameter parabolic reflector antenna at 1296 MHz ($\lambda = 0.75$ foot). The minimum range distance, S_{min}, can be readily computed from the formula for a circular aperture.

$$S_{min} = 2\frac{D^2}{\lambda} = 2 \times \frac{49}{0.75} = 131 \text{ feet}$$

Now a suitable site is selected based on the qualitative discussion given before.

Next determine the source height, h1. The procedure is to choose a height h1 such that the first minimum above ground (n = 2 in formula) is at least two or three times the aperture size, or about 20 feet.

$$h1 = n\frac{\lambda}{4}\frac{S}{h1} = 2 \times \frac{0.75}{4} \times \frac{131}{20} = 2.5 \text{ feet}$$

Place the source antenna at this height and probe the vertical distribution over the 7-foot aperture location, which will be about 10 feet off the ground.

$$h2 = n\frac{\lambda}{4}\frac{S}{h1} = 1 \times \frac{0.75}{4} \times \frac{131}{2.5} = 9.8 \text{ feet}$$

Plot the measured profile of vertical signal level versus height. From this plot, empirically determine whether the 7-foot aperture can be fitted in this profile such that the 1-dB variation is not exceeded. If the variation exceeds

Fig 62—Sample plot of a measured vertical profile.

1 dB over the 7-foot aperture, the source antenna should be lowered and h2 raised. Small changes in h1 can quickly alter the distribution at the test site. **Fig 62** illustrates the points of the previous discussion.

The same set-up procedure applies for either horizontal or vertical linear polarization. However, it is advisable to check by direct measurement at the site for each polarization to be sure that the vertical distribution is satisfactory. Distribution probing in the horizontal plane is unnecessary as little or no variation in amplitude should

be found, since the reflection geometry is constant. Because of this, antennas with apertures that are long and thin, such as a stacked collinear vertical, should be measured with the long dimension parallel to the ground.

A particularly difficult range problem occurs in measurements of antennas that have depth as well as cross-sectional aperture area. Long end-fire antennas such as long Yagis, rhombics, V-beams, or arrays of these antennas, radiate as *volumetric arrays* and it is therefore even more essential that the illuminating field from the source antenna be reasonably uniform in depth as well as plane wave in cross section. For measuring these types of antennas it is advisable to make several vertical profile measurements that cover the depth of the array. A qualitative check on the integrity of the illumination for long end-fire antennas can be made by moving the array or antenna axially (forward and backward) and noting the change in received signal level. If the signal level varies less than 1 or 2 dB for an axial movement of several wavelengths then the field can be considered satisfactory for most demands on accuracy. Large variations indicate that the illuminating field is badly distorted over the array depth and subsequent measurements are questionable. It is interesting to note in connection with gain measurements that any illuminating field distortion will always result in measurements that are lower than true values.

ABSOLUTE GAIN MEASUREMENT

Having established a suitable range, the measure-

Fig 63—Standard-gain antenna. When accurately constructed for the desired frequency, this antenna will exhibit a gain of 7.7 dB over a dipole radiator, plus or minus 0.25 dB. In this model, constructed for 432 MHz, the elements are $^3/_8$-inch diameter tubing. The phasing and support lines are of $^5/_{16}$-inch diameter tubing or rod.

ment of gain relative to an isotropic (point source) radiator is almost always accomplished by direct comparison with a calibrated standard-gain antenna. That is, the signal level with the test antenna in its optimum location is noted. Then you remove the test antenna and place the standard-gain antenna with its aperture at the center of location where the test antenna was located. Measure the difference in signal level between the standard and the test antennas and add to or subtract from the gain of the standard-gain antenna to obtain the absolute gain of the test antenna. Here, *absolute* means with respect to a point source with a gain of unity, by definition. The reason for using this reference rather than a dipole, for instance, is that it is more useful and convenient for system engineering. We assume that both standard and test antennas have been carefully matched to the appropriate impedance and an accurately calibrated and matched detecting device is being used.

A standard-gain antenna may be any type of unidirectional, preferably planar-aperture, antenna, which has been calibrated either by direct measurement or in special cases by accurate construction according to computed dimensions. A standard-gain antenna has been suggested by Richard F. H. Yang (see Bibliography). Shown in **Fig 63**, it consists of two in-phase dipoles $^1/_2$ λ apart and backed up with a ground plane 1 λ square.

In Yang's original design, the stub at the center is a balun formed by cutting two longitudinal slots of $^1/_8$-inch width, diametrically opposite, on a $^1/_4$-λ section of $^7/_8$-inch rigid 50-Ω coax. An alternative method of feeding is to feed RG-8 or RG-213 coax through slotted $^7/_8$-inch copper tubing. Be sure to leave the outer jacket on the coax to insulate it from the copper-tubing balun section. When constructed accurately to scale for the frequency of interest, this type of standard will have an absolute gain of 9.85 dBi (7.7 dBd gain over a dipole in free space) with an accuracy of ± 0.25 dB.

RADIATION-PATTERN MEASUREMENTS

Of all antenna measurements, the radiation pattern is the most demanding in measurement and the most difficult to interpret. Any antenna radiates to some degree in all directions into the space surrounding it. Therefore, the radiation pattern of an antenna is a three-dimensional representation of the magnitude, phase and polarization. In general, and in practical cases for Amateur Radio communications, the polarization is well defined and only the magnitude of radiation is important.

Furthermore, in many of these cases the radiation in one particular plane is of primary interest, usually the plane corresponding to that of the Earth's surface, regardless of polarization. Because of the nature of the range setup, measurement of radiation pattern can be successfully made only in a plane nearly parallel to the earth's surface. With beam antennas it is advisable and usually sufficient to take two radiation pattern measurements, one in the polarization plane and one at right angles to the

plane of polarization. These radiation patterns are referred to in antenna literature as the principal E-plane and H-plane patterns, respectively. *E-plane* means parallel to the electric field that is the polarization plane and *H-plane* means parallel to the magnetic field in free space. The electric field and magnetic field are always perpendicular to each other in a plane wave as it propagates through space.

When the antenna is located over real earth, the terms *Azimuth* and *elevation* planes are commonly used, since the frame of reference is the Earth itself, rather than the electric and magnetic fields in free space. For a horizontally polarized antenna such as a Yagi mounted with its elements parallel to the ground, the azimuth plane is the E-plane and the elevation plane is the H-plane.

The technique to obtain these patterns is simple in procedure but requires more equipment and patience than does making a gain measurement. First, a suitable mount is required that can be rotated in the azimuth plane (horizontal) with some degree of accuracy in terms of azimuth-angle positioning. Second, a signal-level indicator calibrated over at least a 20-dB dynamic range with a readout resolution of at least 2 dB is required. A dynamic range of up to about 40 dB would be desirable but does not add greatly to the measurement significance.

With this much equipment, the procedure is to locate first the area of maximum radiation from the beam antenna by carefully adjusting the azimuth and elevation positioning. These settings are then arbitrarily assigned an azimuth angle of zero degrees and a signal level of zero decibels. Next, without changing the elevation setting (tilt of the rotating axis), the antenna is carefully rotated in azimuth in small steps that permit signal-level readout of 2 or 3 dB per step. These points of signal level corresponding with an azimuth angle are recorded and plotted on polar coordinate paper. A sample of the results is shown on ARRL coordinate paper in **Fig 64**.

On the sample radiation pattern the measured points are marked with an X and a continuous line is drawn in, since the pattern is a continuous curve. Radiation patterns should preferably be plotted on a logarithmic radial scale, rather than a voltage or power scale. The reason is that the log scale approximates the response of the ear to signals in the audio range. Also many receivers have AGC systems that are somewhat logarithmic in response; therefore the log scale is more representative of actual system operation.

Having completed a set of radiation-pattern measurements, one is prompted to ask, "Of what use are they?" The primary answer is as a diagnostic tool to determine if the antenna is functioning as it was intended to. A second answer is to know how the antenna will discriminate against interfering signals from various directions.

Consider now the diagnostic use of the radiation patterns. If the radiation beam is well defined, then there is an approximate formula relating the antenna gain to the

Fig 64—Sample plot of a measured radiation pattern, using techniques described in the text. The plot is on coordinate paper available from ARRL HQ. The form provides space for recording significant data and remarks.

measured half-power beamwidth of the E- and H-plane radiation patterns. The half-power beamwidth is indicated on the polar plot where the radiation level falls to 3 dB below the main beam 0-dB reference on either side. The formula is

$$\text{Gain}\,(\text{dBi}) \cong \frac{41{,}253}{\theta_E \phi_H} \qquad\qquad (\text{Eq 29})$$

where θ_E and ϕ_H are the half-power beamwidths in degrees of the E- and H-plane patterns, respectively. This equation assumes a lossless antenna system, where any side-lobes are well suppressed.

To illustrate the use of this equation, assume that we have a Yagi antenna with a boom length of two wavelengths. From known relations (described in Chapter 11) the expected free-space gain of a Yagi with a boom length of 2 λ is about 13 dBi; its gain, G, equals 20. Using the above relationship, the product of $\theta_E \times \phi_H \approx 2062$ square

degrees. Since a Yagi produces a nearly symmetric beam shape in cross section, $\theta_E = \phi_H = 45°$. Now if the measured values of θ_E and ϕ_H are much larger than 45°, then the gain will be much lower than the expected 13 dBi.

As another example, suppose that the same antenna (a 2-wavelength-boom Yagi) gives a measured gain of 9 dBi but the radiation pattern half power beamwidths are approximately 45°. This situation indicates that although the radiation patterns seem to be correct, the low gain shows inefficiency somewhere in the antenna, such as lossy materials or poor connections.

Large broadside collinear antennas can be checked for excessive phasing-line losses by comparing the gain computed from the radiation patterns with the direct-measured gain. It seems paradoxical, but it is indeed possible to build a large array with a very narrow beamwidth indicating high gain, but actually having very low gain because of losses in the feed distribution system.

In general, and for most VHF/UHF Amateur Radio communications, gain is the primary attribute of an antenna. However, radiation in other directions than the main beam, called *sidelobe radiation*, should be examined by measurement of radiation patterns for effects such as nonsymmetry on either side of the main beam or excessive magnitude of sidelobes. (Any sidelobe that is less than 10 dB below the main beam reference level of 0 dB should be considered excessive.) These effects are usually attributable to incorrect phasing of the radiating elements or radiation from other parts of the antenna that was not intended, such as the support structure or feed line.

The interpretation of radiation patterns is intimately related to the particular type of antenna under measurement. Reference data should be consulted for the antenna type of interest, to verify that the measured results are in agreement with expected results.

To summarize the use of pattern measurements, if a beam antenna is first checked for gain (the easier measurement to make) and it is as expected, then pattern measurements may be academic. However, if the gain is lower than expected it is advisable to make pattern measurements to help determine the possible causes for low gain.

Regarding radiation pattern measurements, remember that the results measured under proper range facilities will not necessarily be the same as observed for the same antenna at a home-station installation. The reasons may be obvious now in view of the preceding information on the range setup, ground reflections, and the vertical-field distribution profiles. For long paths over rough terrain where many large obstacles may exist, the effects of ground reflection tend to become diffused, although they still can cause unexpected results. For these reasons it is usually unjust to compare VHF/UHF antennas over long paths.

Vector Network Analyzers

The process of building and properly tuning a phased array often involves making a number of different measurements to achieve a desired level of performance, as was pointed out in Chapter 8, Multielement Arrays. This section was written by Rudy Severns, N6LF.

After erecting an array we would like to measure the resonant frequency of each element, the self-impedances of each element and the mutual impedances between the elements. We will also want to know these impedances over the whole operating band to help design a feed network. When building the feed network, we may need to check the values and Qs of the network elements and we will want to determine the electrical lengths of transmission lines.

Final tuning of the array requires that the relative current amplitudes and phases in each element be measured and adjusted, if necessary. We also will want to determine the SWR at the feed point. Doing all of this even moderately well can require quite a bit of equipment, some of which is heavy and requires ac line power. This can be a nuisance in the field, especially if the weather is not cooperating.

Professionals make these measurements by employing a *vector network analyzer* (VNA) or the somewhat simpler, *reflection-transmission test set*. These instruments can make all the necessary measurements quickly and with great accuracy. However, in the past VNAs have been very expensive, out of reach for general amateur use. But thanks to modern digital technology VNAs that work with a laptop computer are now becoming available at prices an amateur might consider. It's even possible to homebrew a VNA[1] with performance that approaches a professional instrument. Considering the cost of even a simple array, investment in a VNA makes sense.

VNAs are based on reflection and transmission measurements. To use a VNA it is very helpful to have a basic understanding of *Scattering Parameters* (S-parameters). Microwave engineers have long used these because they have to work with circuits that are large in terms of wavelength, where measurements of forward and reflected power are easy.

HF arrays are also large in terms of wavelength. The techniques for measuring forward and reverse powers work well even at 160 meters. For example, even though the array elements may be 100 feet apart, you can place your instruments in a central location and run cables out to each element. The effect of the cables from the VNA to the elements can be absorbed in the initial calibration procedure so the measurements read out at the VNA are effectively those at each element. In other words, the measurement reference points can be placed electrically at the base of the element, regardless of the physical location of the instrumentation and the interconnecting cables.

In a completed array with its feed network, the network can be excited by the VNA at the feed point and the relative current amplitudes and phases at each element can be measured over a frequency band. Then, adjustments can be made as needed. When the final values for the current amplitudes and phases are known, these values can be put back into an array model in a program like *EZNEC* to determine the pattern of the array across the whole frequency band.

S-PARAMETERS

In Chapter 24, Transmission Lines, the reflection coefficient rho (ρ) is defined as the ratio of the reflected voltage (V_r) to the incident voltage (V_i):

$$\rho = \frac{V_r}{V_i} \tag{Eq 30}$$

If we know the load impedance (Z_L) and the transmission line impedance (Z_0) we can calculate ρ from:

$$\rho = \frac{Z_L - Z_0}{Z_L + Z_0} \tag{Eq 31}$$

Keep in mind that ρ is a complex number (a vector), which we represent by either amplitude and phase ($|Z|$, θ) or by real and imaginary parts ($R \pm j\, X$). The two representations are equivalent. From ρ we can then calculate SWR. That's very handy, but here we want to do something different. If we have an instrument that measures ρ and we know Z_0 then we can determine Z_L from:

$$Z_L = Z_0 \left(\frac{1+\rho}{1-\rho} \right) \tag{Eq 32}$$

Measuring ρ is one of the things that VNAs do very well. With a VNA, the measurement can be made at one end of a long transmission line with the load at the other end. The effect of the line can be calibrated out, as mentioned above, so that we are in effect measuring right at the load.

Fig 65—A 2-element array, where h is the element height and S is the spacing between the elements.

This approach can be used directly to measure the impedance and resonant frequency of a single element. By open and short circuiting elements in an array we can determine the mutual as well as self impedances for, and between, all the elements. We can also use this approach to measure component values, inductor Qs, etc.

This is an example of a *one-port* measurement; that is, a load at the end of a transmission line. However, a multi-element array actually behaves as a multi-port network, so to get the most out of a VNA, you need to generalize the above procedure. This is where S-parameters come into play. To illustrate the principles we will use a simple 2-element array like that shown in **Fig 65**.

To design a feed network to drive this array we need to know the input impedance of each element (Z_1 and Z_2) as a function of the drive currents (I_1 and I_2). The input impedances will depend on the self impedance of each element, the coupling between them (the mutual impedance) and the drive currents in each element. To manage this problem we can represent a 2-element array as a two-port network, as shown in **Fig 66**. And we can relate the port voltages, currents and impedances with Eq 33:

$$V_1 = Z_{11}I_1 + Z_{12}I_2$$
$$V_2 = Z_{21}I_1 + Z_{22}I_2 \qquad \text{(Eq 33)}$$

Normally we know I_1 and I_2 from the design of the array, but we need to determine the resulting element impedances. That's the challenge. Fortunately, an array is a linear network, so $Z_{12} = Z_{21}$, which means we need only determine three variables: the self impedances Z_{11} and Z_{22} and the mutual impedance, Z_{12}.

Once we know Z_{11}, Z_{12}, Z_{22} and are given I_1 and I_2, we can determine the feed-point impedances at each element from:

$$Z_1 = Z_{11} + \left(\frac{I_2}{I_1}\right)Z_{12}$$
$$Z_2 = Z_{22} + \left(\frac{I_1}{I_2}\right)Z_{12} \qquad \text{(Eq 34)}$$

This is the conventional approach. However, there are some problems here. We have to be able to accurately measure either voltages and currents or impedances in multiple elements that may be separated by large fractions of a wavelength. In addition, accurate measurements of

Fig 67—Test setup to measure a 2-element array using a VNA.

current, voltage and impedance become increasingly more difficult as we go up in frequency.

It turns out that we can get the information more easily by measuring incident and reflected voltages at the ports and from those measurements determine the feed-point impedances. A VNA is an instrument for measuring these voltages. It turns out to be easier to measure the ratios of two voltages rather than their absolute values.

The measurement setup using a VNA for a 2-element array is shown in **Fig 67**. VNAs usually have at least two RF connections: the transmit port (T) and the receive port (R). Professional units may have more RF connections. The T output provides an signal from a 50-Ω source and the R port is a detector with a 50-Ω input impedance. Basically we have a transmitter and a receiver. The transmit port uses a directional coupler to provide measurements of the forward and reflected signals at that output. The receive port measures the signal transmitted through the network. Transmission lines usually have $Z_0 = 50$ Ω and may be of any length required by the size of the array.

Fig 66—Two-port representation of currents and voltages in the 2-element array in Fig 65.

Using incident and reflected voltages, the two-port network representation is now changed, as shown in **Fig 68**, where:

V_{1i} = incident voltage at port 1
V_{1r} = reflected voltage at port 1
V_{2i} = incident voltage at port 2
V_{2r} = reflected voltage at port 2

In a manner analogous to Eq 33, we can write an expression in terms of the incident and reflected voltages:

$$b_1 = S_{11}a_1 + S_{12}a_2$$
$$b_2 = S_{21}a_1 + S_{22}a_2 \qquad \text{(Eq 35)}$$

where:

$$a_1 \frac{V_{1i}}{\sqrt{Z_0}} \qquad b_1 \frac{V_{1r}}{\sqrt{Z_0}}$$
$$a_2 = \frac{V_{2i}}{\sqrt{Z_0}} \qquad b_2 = \frac{V_{2r}}{\sqrt{Z_0}} \qquad \text{(Eq 36)}$$

We see that the a_n and b_n are simply the incident and reflected voltages at the two ports divided by $\sqrt{Z_o}$. Because this is a linear network, $S_{21} = S_{12}$.

What are the S_{ij} quantities? These are called the *S-parameters*, which are defined by:

$$S_{11} \equiv \left.\frac{b_1}{a_1}\right|_{a_2=0} = \left.\frac{V_{1r}}{V_{1i}}\right|_{V_{2i}=0}$$

$$S_{21} \equiv \left.\frac{b_2}{a_1}\right|_{a_2=0} = \left.\frac{V_{2r}}{V_{1i}}\right|_{V_{2i}=0}$$

$$S_{12} \equiv \left.\frac{b_1}{a_2}\right|_{a_1=0} = \left.\frac{V_{1r}}{V_{2i}}\right|_{V_{1i}=0} \qquad \text{(Eq 37)}$$

$$S_{22} \equiv \left.\frac{b_2}{a_2}\right|_{a_1=0} = \left.\frac{V_{2r}}{V_{2i}}\right|_{V_{1i}=0}$$

Note that the S_{ij} parameters are all ratios of reflected and incident voltages, and they are usually complex numbers. The condition that $a_2 = 0 = V_{2i}$ is the same as saying that port 2 is terminated in a load equal to Z_0 and the network is excited at port 1. This means there is no reflection from the load on port 2, which makes $V_{2i} = 0$. Similarly, if we terminate port 1 with Z_0 and excite port 2, then $V_{1i} = 0 = a_1$.

ANT0659

Fig 68—Two-port network with incident and reflected waves.

If we compare Eq 30 to the first line of Eq 37 we see that $S_{11} = \rho_1$, the reflection coefficient at port 1. We can now restate Eq 32 in terms of S_{11}:

$$Z = Z_0\left(\frac{1+S_{11}}{1-S_{11}}\right) \qquad \text{(Eq 38)}$$

where Z is the impedance looking into port 1 with port 2 terminated in Z_0. In the case where port 2 does not exist—that is, you are measuring a single element (for example, measuring element 1 with element 2 open-circuited) or a component, then Z is simply the self impedance (Z_{11} in Eq 33). Since S_{11} is a standard measurement for VNAs you can calculate Z using Eq 38. In many cases the VNA software will do this calculation for you automatically. You can also measure element 2 with element 1 open and determine Z_{22}.

S_{21} represents the ratio of the signal coming out of port 2 (V_{2r}) to the input signal on port 1 (V_{1i}) and is another standard VNA measurement. S_{21} is a measurement of the signal transmission between the ports through the network, or in the case of an array, the signal transmission due to the coupling between the elements. Again, port 2 is terminated in Z_0.

A full-feature VNA will measure all the S_{ij} parameters at once, but most of the lower-cost units of interest to amateurs are what we call *reflection-transmission test sets*. What this means is that they only measure S_{11} and S_{21}. To obtain S_{22} and S_{12} we have to interchange the test cables at the array elements (see Fig 67) and run the measurements again. Normally the software will accommodate this as a second entry and we end up with the full set of S_{ij} parameters.

If we do run a full set of S_{ij} parameters then we can transform these to Z_{ij} (Eq 33) using the following expressions, assuming that $S_{21} = S_{12}$:

$$Z_{11} = \frac{\left(1+S_{11}\right)\left(1-S_{22}\right)+S_{12}^{\ 2}}{\left(1-S_{11}\right)\left(1-S_{22}\right)-S_{12}^{\ 2}}$$

$$Z_{22} = \frac{\left(1-S_{11}\right)\left(1+S_{22}\right)+S_{12}^{\ 2}}{\left(1-S_{11}\right)\left(1-S_{22}\right)-S_{12}^{\ 2}}$$

$$Z_{12} = \frac{\left(2S_{12}\right)}{\left(1-S_{11}\right)\left(1-S_{22}\right)-S_{12}^{\ 2}} \qquad \text{(Eq 39)}$$

The example to this point has been for a 2-element array. The S-parameters can be determined for an array with any number of elements. In an n-port S-parameter measurement, all ports are terminated in Z_0 at the same time. Measurements are made between one set of ports at a time and repeated until all pairs of ports are measured.

ARRAY MEASUREMENT EXAMPLE

A good way to illustrate the use of a VNA for array measurements is to work through an example with a real array. **Fig 69** is a picture of a 2-element 20-meter phased

array built by Mark Perrin, N7MQ.

Each element is $\lambda/4$ (self resonant at 14.150 MHz) and spaced $\lambda/4$ (17 feet 5 inches). In the ideal case, both elements would have the same current amplitude with a 90° phase difference. This gives the cardioid pattern shown in Chapter 8, Multielement Arrays. There are many schemes for correctly feeding such an array. The one used in this example uses two different 75-Ω transmission lines (one $\lambda/4$ and the other $\lambda/2$, electrically), as described by Roy Lewallen, W7EL.[2,3]

The first task is to resonate the elements individually. With the VNA set to measure S_{11} phase, we will get a graph like that shown in **Fig 70**.

At the $\lambda/4$ resonant frequency (f_r) we will see a sharp phase transition as we go from −180° to +180°. This is typical of any series resonant circuit. The length of each

Fig 69—
2-element
20-meter
phased array
(*Photo
courtesy
N7MQ*).

Fig 70—S_{11} phase plot for an individual element.

element is adjusted until the desired f_r is achieved. This is a very sensitive measurement. You can see the shift in f_r due to the wind blowing, the length of the element changing as it heats up in the sun or any interactions between the feed line and the antenna as you move the feed line around. In fact this is very good point in the process to make sure everything is mechanically stable and free of unexpected couplings. Usually you will find it necessary place choke baluns on each element to reduce stray coupling.

The next step is to determine the self (Z_{11} and Z_{22}) and mutual (Z_{12}) impedances from which the actual driving point impedances present when the array is excited can be determined. See Chapter 8, Multielement Arrays. There are two ways to go.

First, we can simply use the VNA as an impedance bridge—ie, make two S_{11} measurements at one element, first with the other element open (Z_{11} or Z_{22}) and then with it shorted (Z_1 or Z_2). We can convert the S_{11} measurements to impedances using Eq 38. The value for Z_{12} can be obtained from Eq 40:

$$Z_{12} = \pm\sqrt{Z_{11}\left(Z_{11} - Z_1\right)}$$
$$Z_{12} = \pm\sqrt{Z_{22}\left(Z_{22} - Z_2\right)} \qquad \text{(Eq 40)}$$

The second approach is to do a full two-port S-parameter measurement (S_{11}, S_{21}, S_{12} and S_{22}) and derive the impedances using Eq 38. Both approaches will work but the second approach has the advantage that the $\pm$ ambiguity in Eq 40 is eliminated.

For this example, the impedance values from the measurements at 14.150 MHz, turn out to be:

$$Z_{11} = 51.4 + j\,0.35$$
$$Z_{22} = 50.3 + j\,0.299$$
$$Z_{12} = 15.06 - j\,19.26 \qquad \text{(Eq 41)}$$

With these values we can now determine the feed-point impedances from:

$$Z_1{}' = Z_{11} + \frac{I_2}{I_1}Z_{12}$$

$$Z_2{}' = Z_{22} + \frac{I_1}{I_2}Z_{12}$$

$$\frac{I_1}{I_2} = -j \qquad \text{(Eq 42)}$$

Note that $-j$ represents the 90° phase shift between the currents. Substituting the values from Eq 41 into Eq 42:

$$Z_1{}' = 32.09 - j\,14.7$$
$$Z_2{}' = 69.6 + j\,15.32 \qquad \text{(Eq 43)}$$

With these impedances in hand we can now design the feed network. In this particular example however, we have decided to use the $\lambda/4$ and $\lambda/2$ cables as described by Lewallen[2,3] and accept the results. So we now proceed to cut and trim the two cables to length.

Fig 71—Current phase and amplitude ratio test setup.

Fig 73—Measured relative current phase shift over the 20-meter band.

Again, there are two ways to go. First we can determine the frequency at which each cable is λ/4 long. At this point the input impedance of the cable will be equivalent to a series-resonant circuit and we can simply measure the phase of S_{11} as we did earlier for f_r and get a plot like that shown in Fig 70. In this example the λ/4 resonant frequencies of the two cables are 7.075 MHz and 14.150 MHz.

The second approach would be to measure S_{21} for each cable at 14.150 MHz. The phase shift in S_{21} tells you how long the cable is, in degrees, at a given frequency. Because there is a small variation in cable characteristics with frequency (dispersion) this approach is slightly more accurate since it is done at the desired operating frequency. But this is not very large effect at HF.

This brings us down to the final measurements, which are to check that the relative current amplitudes and phases between the two elements are correct. We can then determine

Fig 72—Measured element current ratio over the 20-meter band.

the feed-point SWR. The phase and amplitude ratios are made using the S_{12} capability of the VNA and the test setup shown in **Fig 71**.

The VNA transmit port is connected to the normal feed point. A current sensor (see Chapter 8, Multielement Arrays, for a discussion of current sensors) is inserted at the base of element 1 and the output of the sensor is returned to the detector or receive port of the VNA. A calibration run is then made to normalize this path. That makes it the reference.

Next, the current sensor is shifted to element 2. The amplitude and phase plots for S_{12} obtained at this point will be the desired relative phase shift and amplitude ratio between the currents in the array when driven at the normal feed point. **Figs 72** and **73** show the behavior of the example array over the 20-meter band. Note that the amplitude ratio has been converted from dB. We can now use these values in a *EZNEC* model of the array to determine the actual radiation pattern.

Obviously the W7EL feed scheme is not perfect, but it has a definite advantage of simplicity. If better performance is desired we can use the values of Z_1' and Z_2' determined earlier to design and fabricate a new feed network and then proceed to evaluate its performance in the same way.

The final measurement is to connect the transmit port of the VNA to the feed point and measure S_{11}. From this we can calculate the SWR:

$$SWR = \frac{1+\left|S_{11}\right|}{1-\left|S_{11}\right|} \qquad (Eq\ 44)$$

In this example, the return loss, $\left|S_{11}\right|$, is about −19 dB over the entire 20-meter band. This corresponds to SWR= 1.25:1.

Notes

[1]Paul Kiciak, N2PK, **http://n2pk.com**.
[2]Roy Lewallen, W7EL, *QST*, Aug 1979, Technical Correspondence, pp 42-43.
[3]Orr and Cowan, *Vertical Antennas*, Radio Amateur Call Book, 1986, pp 148-150.

BIBLIOGRAPHY

Source material and more extended discussion of topics covered in this chapter can be found in the references given below.

A. Bailey, "The Antenna Lab, Parts 1 and 2," *Radio Communication*, Aug and Sep 1983.

L. Blake, *Transmission Lines and Waveguides* (New York: John Wiley & Sons, 1969), pp 244-251.

J. H. Bowen, "A Calorimeter for VHF and UHF Power Measurements, *QST*, Dec 1975, pp 11-13.

W. Bruene, "An Inside Picture of Directional Wattmeters," *QST*, Apr 1959.

CCIR Recommendation 368, Documents of the CCIR XII Plenary assembly, ITU, Geneva, 1967.

J. Carr, "Find Fault with Your Coax," *73*, Oct 1984, pp 10-14.

D. DeMaw, "In-Line RF Power Metering," *QST*, Dec 1969.

D. Fayman, "A Simple Computing SWR Meter," *QST*, Jul 1973, pp 23-33.

J. Gibbons and H. Horn, "A Circuit With Logarithmic Response Over Nine Decades," *IEEE Transactions on Circuit Theory*, Vol CT-11, No. 3, Sep 1964, pp 378-384.

J. Grebenkemper, "Calibrating Diode Detectors," *QEX*, Aug 1990.

J. Grebenkemper, "The Tandem Match—An Accurate Directional Wattmeter," *QST*, Jan 1987.

J. Grebenkemper, "Improving and Using R-X Noise Bridges," *QST*, Aug 1989; Feedback, *QST*, Jan 1990, p 27.

G. H. Hagn, SRI, "HF Ground Measurements at the Lawrence Livermore National Laboratory (LLNL) Field Site," *Applied Computational Electromagnetics Society Journal and Newsletter*, Vol 3, Number 2, Fall 1988.

T. King, "A Practical Time-Domain Reflectometer," *QST*, May 1989, pp 22-24.

Z. Lau and C. Hutchinson, "Improving the HW-9 Transceiver," *QST*, Apr 1988, pp 26-29.

V. G. Leenerts, "Automatic VSWR and Power Meter," *Ham Radio*, May 1980, pp 34-43.

J. Lenk, *Handbook of Oscilloscopes* (Englewood Cliffs, NJ: Prentice-Hall, 1982), pp 288-292.

I. Lindell, E. Alanen, K. Mannerslo, "Exact Image Method for Impedance Computation of Antennas Above the Ground," *IEEE Trans. On Antennas and Propagation*, AP-33, Sep 1985.

L. McCoy, "A Linear Field-Strength Meter," *QST*, Jan 1973.

T. McMullen, "The Line Sampler, an RF Power Monitor for VHF and UHF," *QST*, Apr 1972.

M. Walter Maxwell, W2DU, *Reflections* (Newington: ARRL, 1990), p 20-3. [Out of print.]

C. Michaels, "Determining Line Lengths," Technical Correspondence, *QST*, Sep 1985, pp 43-44.

H. Perras, "Broadband Power-Tracking VSWR Bridge," *Ham Radio*, Aug 1979, pp 72-75.

S. Ramo, J. Whinnery and T. Van Duzer, *Fields and Waves in Communication Electronics* (New York: John Wiley & Sons, 1967), Chap 1.

Reference Data for Radio Engineers, 5th edition (Indianapolis: Howard W. Sams, 1968), Chapter 28.

P. N. Saveskie, *Radio Propagation Handbook* (Blue Ridge Summit, PA: TAB Books, 1960).

J. Sevick, "Short Ground-Radial Systems for Short Verticals," *QST*, Apr 1978, pp 30-33.

J. Sevick, "Measuring Soil Conductivity," *QST*, Mar 1981, pp 38- 39.

W. Spaulding, "A Broadband Two-Port S-Parameter Test Set," *Hewlett-Packard Journal*, Nov 1984.

D. Turrin, "Antenna Performance Measurements," *QST*, Nov 1974, pp 35-41.

F. Van Zant, "High-Power Operation with the Tandem Match Directional Coupler," Technical Correspondence, *QST*, Jul 1989, pp 42-43.

R. F. H. Yang, "A Proposed Gain Standard for VHF Antennas," *IEEE Transactions on Antennas and Propagation*, Nov 1966.

Smith Chart Calculations

The Smith Chart is a sophisticated graphic tool for solving transmission line problems. One of the simpler applications is to determine the feed-point impedance of an antenna, based on an impedance measurement at the input of a random length of transmission line. By using the Smith Chart, the impedance measurement can be made with the antenna in place atop a tower or mast, and there is no need to cut the line to an exact multiple of half wavelengths. The Smith Chart may be used for other purposes, too, such as the design of impedance-matching networks. These matching networks can take on any of several forms, such as L and pi networks, a stub matching system, a series-section match, and more. With a knowledge of the Smith Chart, the amateur can eliminate much "cut and try" work.

Named after its inventor, Phillip H. Smith, the Smith Chart was originally described in *Electronics* for January 1939. Smith Charts may be obtained at most university book stores. Smith Charts are also available from ARRL HQ. (See the caption for Fig 3.)

It is stated in Chapter 24 that the input impedance, or the impedance seen when "looking into" a length of line, is dependent upon the SWR, the length of the line, and the Z_0 of the line. The SWR, in turn, is dependent upon the load which terminates the line. There are complex mathematical relationships which may be used to calculate the various values of impedances, voltages, currents, and SWR values that exist in the operation of a particular transmission line. These equations can be solved with a personal computer and suitable software, or the parameters may be determined with the Smith Chart. Even if a computer is used, a fundamental knowledge of the Smith Chart will promote a better understanding of the problem being solved. And such an understanding might lead to a quicker or simpler solution than otherwise. If the terminating impedance is known, it is a simple matter to determine the input impedance of the line for any length by means of the chart. Conversely, as indicated above, with a given line length and a known (or measured) input impedance, the load impedance may be determined by means of the chart—a convenient method of remotely determining an antenna impedance, for example.

Although its appearance may at first seem somewhat formidable, the Smith Chart is really nothing more than a specialized type of graph. Consider it as having curved, rather than rectangular, coordinate lines. The coordinate system consists simply of two families of circles—the resistance family, and the reactance family. The resistance circles, **Fig 1**, are centered on the resistance axis (the only straight line on the chart), and are tangent to the outer circle at the right of the chart. Each circle is assigned a value of resistance, which is indicated at the point where the circle crosses the resistance axis. All points along any one circle have the same resistance value.

The values assigned to these circles vary from zero at the left of the chart to infinity at the right, and actually represent a *ratio* with respect to the impedance value assigned to the center point of the chart, indicated 1.0. This center point is called prime center. If prime center is assigned a value of 100 Ω, then 200 Ω resistance is represented by the 2.0 circle, 50 Ω by the 0.5 circle, 20 Ω by the 0.2 circle, and so on. If, instead, a value of 50 is assigned to prime center,

Fig 1—Resistance circles of the Smith Chart coordinate system.

the 2.0 circle now represents 100 Ω, the 0.5 circle 25 Ω, and the 0.2 circle 10 Ω. In each case, it may be seen that the value on the chart is determined by dividing the actual resistance by the number assigned to prime center. This process is called normalizing.

Conversely, values from the chart are converted back to actual resistance values by multiplying the chart value times the value assigned to prime center. This feature permits the use of the Smith Chart for any impedance values, and therefore with any type of uniform transmission line, whatever its impedance may be. As mentioned above, specialized versions of the Smith Chart may be obtained with a value of 50 Ω at prime center. These are intended for use with 50-Ω lines.

Now consider the reactance circles, **Fig 2**, which appear as curved lines on the chart because only segments of the complete circles are drawn. These circles are tangent to the resistance axis, which itself is a member of the reactance family (with a radius of infinity). The centers are displaced to the top or bottom on a line tangent to the right of the chart. The large outer circle bounding the coordinate portion of the chart is the reactance axis.

Each reactance circle segment is assigned a value of reactance, indicated near the point where the circle touches the reactance axis. All points along any one segment have the same reactance value. As with the resistance circles, the values assigned to each reactance circle are normalized with respect to the value assigned to prime center. Values to the top of the resistance axis are positive (inductive), and those to the bottom of the resistance axis are negative (capacitive).

When the resistance family and the reactance family of circles are combined, the coordinate system of the Smith Chart results, as shown in **Fig 3**. Complex impedances (R + jX) can be plotted on this coordinate system.

IMPEDANCE PLOTTING

Suppose we have an impedance consisting of 50 Ω resistance and 100 Ω inductive reactance (Z = 50 + j 100). If we assign a value of 100 Ω to prime center, we normalize the above impedance by dividing each component of the impedance by 100. The normalized impedance is then 50/100 + j (100/100) = 0.5 + j 1.0. This impedance is plotted on the Smith Chart at the intersection of the 0.5 resistance circle and the +1.0 reactance circle, as indicated in Fig 3. Calculations may now be made from this plotted value.

Now say that instead of assigning 100 Ω to prime center, we assign a value of 50 Ω. With this assignment, the 50 + j 100 Ω impedance is plotted at the intersection of the 50/50 = 1.0 resistance circle, and the 100/50 = 2.0 positive reactance circle. This value, 1 + j 2, is also indicated in Fig 3. But now we have *two* points plotted in Fig 3 to represent the same impedance value, 50 + j 100 Ω. How can this be?

These examples show that the same impedance may be plotted at different points on the chart, depending upon the value assigned to prime center. But two plotted points cannot represent the same impedance *at the same time*! It is customary when solving transmission-line problems to assign to prime center a value equal to the characteristic impedance, or Z_0, of the line being used. This value should always be recorded at the start of calculations, to avoid possible confusion later. (In using the specialized charts with the value of 50 at prime center, it is, of course, not necessary to normalize impedances when working with 50-Ω line. The resistance and reactance values may be read directly from the chart coordinate system.)

Prime center is a point of special significance. As

Fig 2—Reactance circles (segments) of the Smith Chart coordinate system.

Fig 3—The complete coordinate system of the Smith Chart. For simplicity, only a few divisions are shown for the resistance and reactance values. Various types of Smith Chart forms are available from ARRL HQ. At the time of this writing, five 8¹/₂ × 11 inch Smith Chart forms are available for $2.

just mentioned, is is customary when solving problems to assign the Z_0 value of the line to this point on the chart—50 Ω for a 50-Ω line, for example. What this means is that the center point of the chart now represents 50 $+j$ 0 ohms–a pure resistance equal to the characteristic impedance of the line. If this were a load on the line, we recognize from transmission-line theory that it represents a perfect match, with no reflected power and with a 1.0 to 1 SWR. Thus, prime center also represents the 1.0 SWR circle (with a radius of zero). SWR circles are also discussed in a later section.

Short and Open Circuits

On the subject of plotting impedances, two special cases deserve consideration. These are short circuits and open circuits. A true short circuit has zero resistance and zero reactance, or $0 + j$ 0). This impedance is plotted at the left of the chart, at the intersection of the resistance and the reactance axes. By contrast, an open circuit has infinite resistance, and therefore is plotted at the right of the chart, at the intersection of the resistance and reactance axes. These two special cases are sometimes used in matching stubs, described later.

Standing-Wave-Ratio Circles

Members of a third family of circles, which are not printed on the chart but which are added during the process of solving problems, are standing-wave-ratio or SWR circles. See **Fig 4**. This family is centered on prime center, and appears as concentric circles inside the reactance axis. During calculations, one or more of these circles may be added with a drawing compass. Each circle represents a value of SWR, with every point on a given circle representing the same SWR. The SWR value for a given circle may be determined directly from the chart coordinate system, by reading the resistance value where the SWR circle crosses the resistance axis to the right of prime center. (The reading where the circle crosses the resistance axis to the left of prime center indicates the inverse ratio.)

Consider the situation where a load mismatch in a length of line causes a 3-to-1 SWR ratio to exist. If we temporarily disregard line losses, we may state that the SWR remains constant throughout the entire length of this line. This is represented on the Smith Chart by drawing a 3:1 constant SWR circle (a circle with a radius of 3 on the resistance axis), as in **Fig 5**. The design of the chart is such that any impedance encountered *anywhere* along the length of this mismatched line will fall on the SWR circle. The impedances may be read from the coordinate system merely by the progressing around the SWR circle by an amount corresponding to

the length of the line involved.

This brings into use the wavelength scales, which appear in Fig 5 near the perimeter of the Smith Chart. These scales are calibrated in terms of portions of an electrical wavelength along a transmission line. Both scales start from 0 at the left of the chart. One scale, running

Fig 4—Smith Chart with SWR circles added.

Fig 5—Example discussed in text.

counterclockwise, starts at the generator or input end of the line and progresses toward the load. The other scale starts at the load and proceeds toward the generator in a clockwise direction. The complete circle around the edge of the chart represents $1/2 \lambda$. Progressing once around the perimeter of these scales corresponds to progressing along a transmission line for $1/2 \lambda$. Because impedances repeat themselves every $1/2 \lambda$ along a piece of line, the chart may be used for any length of line by disregarding or subtracting from the line's total length an integral, or whole number, of half wavelengths.

Also shown in Fig 5 is a means of transferring the radius of the SWR circle to the external scales of the chart, by drawing lines tangent to the circle. Another simple way to obtain information from these external scales is to transfer the radius of the SWR circle to the external scale with a drawing compass. Place the point of a drawing compass at the center or 0 line, and inscribe a short arc across the appropriate scale. It will be noted that when this is done in Fig 5, the external STANDING-WAVE VOLTAGE-RATIO scale indicates the SWR to be 3.0 (at A)—our condition for initially drawing the circle on the chart (and the same as the SWR reading on the resistance axis).

SOLVING PROBLEMS WITH THE SMITH CHART

Suppose we have a transmission line with a characteristic impedance of 50 Ω and an electrical length of 0.3 λ. Also, suppose we terminate this line with an impedance having a resistive component of 25 Ω and an inductive reactance of 25 Ω (Z = 25 + j 25). What is the input impedance to the line?

The characteristic impedance of the line is 50 Ω, so we begin by assigning this value to prime center. Because the line is not terminated in its characteristic impedance, we know that standing waves will exist on the line, and that, therefore, the input impedance to the line will not be exactly 50 Ω. We proceed as follows. First, normalize the load impedance by dividing both the resistive and reactive components by 50 (Z_0 of the line being used). The normalized impedance in this case is 0.5 + j 0.5. This is plotted on the chart at the intersection of the 0.5 resistance and the +0.5 reactance circles, as in **Fig 6**. Then draw a constant SWR circle passing through this point. Transfer the radius of this circle to the external scales with the drawing compass. From the external STANDING-WAVE VOLTAGE-RATIO scale, it may be seen (at A) that the voltage ratio of 2.62 exists for this radius, indicating that our line is operating with an SWR of 2.62 to 1. This figure is converted to decibels in the adjacent scale, where 8.4 dB may be read (at B), indicating that the ratio of the voltage maximum to the

voltage minimum along the line is 8.4 dB. (This is mathematically equivalent to 20 times the log of the SWR value.)

Next, with a straightedge, draw a radial line from prime center through the plotted point to intersect the wavelengths scale. At this intersection, point C in Fig 6, read a value from the wavelengths scale. Because we are starting from the load, we use the TOWARD GENERATOR or outermost calibration, and read 0.088 λ.

To obtain the line input impedance, we merely find the point on the SWR circle that is 0.3 λ toward the generator from the plotted load impedance. This is accomplished by adding 0.3 (the length of the line in wavelengths) to the reference or starting point, 0.088; 0.3 + 0.088 = 0.388. Locate 0.388 on the TOWARD GENERATOR scale (at D). Draw a second radial line from this point to prime center. The intersection of the new radial line with the SWR circle represents the normalized line input impedance, in this case 0.6 – j 0.66.

To find the unnormalized line impedance, multiply by 50, the value assigned to prime center. The resulting value is 30 – j 33, or 30 Ω resistance and 33 Ω capacitive reactance. *This* is the impedance that a transmitter must match if such a system were a combination of antenna

Fig 6—Example discussed in text.

and transmission line. This is also the impedance that would be measured on an impedance bridge if the measurement were taken at the line input.

In addition to the line input impedance and the SWR, the chart reveals several other operating characteristics of the above system of line and load, if a closer look is desired. For example, the voltage reflection coefficient, both magnitude and phase angle, for this particular load is given. The phase angle is read under the radial line drawn through the plot of the load impedance, where the line intersects the ANGLE OF REFLECTION COEFFICIENT scale. This scale is not included in Fig 6, but will be found on the Smith Chart just inside the wavelengths scales. In this example, the reading is 116.6 degrees. This indicates the angle by which the reflected voltage wave leads the incident wave at the load. It will be noted that angles on the bottom half, or capacitive-reactance half, of the chart are negative angles, a "negative" lead indicating that the reflected voltage wave actually lags the incident wave.

The magnitude of the voltage-reflection-coefficient may be read from the external REFLECTION COEFFICIENT VOLTAGE scale, and is seen to be approximately 0.45 (at E) for this example. This means that 45 percent of the incident voltage is reflected. Adjacent to this scale on the POWER calibration, it is noted (at F) that the power reflection coefficient is 0.20, indicating that 20 percent of the incident power is reflected. (The amount of reflected power is proportional to the square of the reflected voltage.)

ADMITTANCE COORDINATES

Quite often it is desirable to convert impedance information to admittance data—conductance and susceptance. Working with admittances greatly simplifies determining the resultant when two complex impedances are connected in parallel, as in stub matching. The conductance values may be added directly, as may be the susceptance values, to arrive at the overall admittance for the parallel combination. This admittance may then be converted back to impedance data, if desired.

On the Smith Chart, the necessary conversion may be made very simply. The equivalent admittance of a plotted impedance value lies diametrically opposite the impedance point on the chart. In other words, an impedance plot and its corresponding admittance plot will lie on a straight line that passes through prime center, and each point will be the same distance from prime center (on the same SWR circle). In the above example, where the normalized line input impedance is $0.6 - j\,0.66$, the equivalent admittance lies at the intersection of the SWR circle and the extension of the straight line passing from

point D though prime center. Although not shown in Fig 6, the normalized admittance value may be read as $0.76 + j\,0.84$ if the line starting at D is extended.

In making impedance-admittance conversions, remember that capacitance is considered to be a positive susceptance and inductance a negative susceptance. This corresponds to the scale identification printed on the chart. The admittance in siemens is determined by dividing the normalized values by the Z_0 of the line. For this example the admittance is $0.76/50 + j\,0.84/50 = 0.0152 + j\,0.0168$ siemen. Of course admittance coordinates may be converted to impedance coordinates just as easily—by locating the point on the Smith Chart that is diametrically opposite that representing the admittance coordinates, on the same SWR circle.

DETERMINING ANTENNA IMPEDANCES

To determine an antenna impedance from the Smith Chart, the procedure is similar to the previous example. The electrical length of the feed line must be known and the impedance value at the input end of the line must be determined through measurement, such as with an impedance-measuring or a good quality noise bridge. In this case, the antenna is connected to the far end of the line and becomes the load for the line. Whether the

Fig 7—Example discussed in text.

antenna is intended purely for transmission of energy, or purely for reception makes no difference; the antenna is still the terminating or load impedance on the line as far as these measurements are concerned. The input or generator end of the line is that end connected to the device for measurement of the impedance. In this type of problem, the measured impedance is plotted on the chart, and the TOWARD LOAD wavelengths scale is used in conjunction with the electrical line length to determine the actual antenna impedance.

For example, assume we have a measured input impedance to a 50-Ω line of 70 – j 25 Ω. The line is 2.35 λ long, and is terminated in an antenna. What is the antenna feed impedance? Normalize the input impedance with respect to 50 Ω, which comes out 1.4 – j 0.5, and plot this value on the chart. See **Fig 7**. Draw a constant SWR circle through the point, and transfer the radius to the external scales. The SWR of 1.7 may be read from the VOLTAGE RATIO scale (at A). Now draw a radial line from prime center through this plotted point to the wavelengths scale, and read a reference value (at B). For this case the value is 0.195, on the TOWARD LOAD scale. Remember, we are starting at the generator end of the transmission line.

To locate the load impedance on the SWR circle, add the line length, 2.35 λ, to the reference value from the wavelengths scale; 2.35 + 0.195 = 2.545. Locate the new value on the TOWARD LOAD scale. But because the calibrations extend only from 0 to 0.5, we must first subtract a number of half wavelengths from this value and use only the remaining value. In this situation, the largest integral number of half wavelengths that can be subtracted with a positive result is 5, or 2.5 λ. Thus, 2.545 – 2.5 = 0.045. Locate the 0.045 value on the TOWARD LOAD scale (at C). Draw a radial line from this value to prime center. Now, the coordinates at the intersection of the second radial line and the SWR circle represent the load impedance. To read this value closely, some interpolation between the printed coordinate lines must be made, and the value of 0.62 – j 0.19 is read. Multiplying by 50, we get the actual load or antenna impedance as 31 – j 9.5 Ω, or 31 Ω resistance with 9.5 Ω capacitive reactance.

Problems may be entered on the chart in yet another manner. Suppose we have a length of 50-Ω line feeding a base-loaded resonant vertical ground-plane antenna which is shorter than $^1/_4$ λ. Further, suppose we have an SWR monitor in the line, and that it indicates an SWR of 1.7 to 1. The line is known to be 0.95 λ long. We want to know both the input and the antenna impedances.

From the information available, we have no impedances to enter into the chart. We may, however, draw a circle representing the 1.7 SWR. We also know, from the definition of resonance, that the antenna presents a purely resistive load to the line, that is, no reactive component. Thus, the antenna impedance must lie on the resistance axis. If we were to draw such an SWR circle and observe the chart with only the circle drawn, we would see two points which satisfy the resonance requirement for the load. These points are 0.59 + j 0 and 1.7 + j 0. Multiplying by 50, we see that these values represent 29.5 and 85 Ω resistance. This may sound familiar, because, as was discussed in Chapter 24, when a line is terminated in a pure resistance, the SWR in the line equals Z_R/Z_0 or Z_0/Z_R, where Z_R=load resistance and Z_0=line impedance.

If we consider antenna fundamentals described in Chapter 2, we know that the theoretical impedance of a $^1/_4$-λ ground-plane antenna is approximately 36 Ω. We therefore can quite logically discard the 85-Ω impedance figure in favor of the 29.5-Ω value. This is then taken as the load impedance value for the Smith Chart calculations. To find the line input impedance, we subtract 0.5 λ from the line length, 0.95, and find 0.45 λ on the TOWARD GENERATOR scale. (The wavelength-scale starting point in this case is 0.) The line input impedance is found to be 0.63 – j 0.20, or 31.5 – j 10 Ω.

DETERMINATION OF LINE LENGTH

In the example problems given so far in this chapter, the line length has conveniently been stated in wavelengths. The electrical length of a piece of line depends upon its physical length, the radio frequency under consideration, and the velocity of propagation in the line. If an impedance-measurement bridge is capable of quite reliable readings at high SWR values, the line length may be determined through line input-impedance measurements with short- or open-circuit line terminations. Information on the procedure is given later in this chapter. A more direct method is to measure the physical length of the line and calculate its electrical length from

$$N = \frac{Lf}{984VF} \qquad \text{(Eq 1)}$$

where

    N = number of electrical wavelengths in the line
    L = line length in feet
    f = frequency, MHz
    VF = velocity or propagation factor of the line

The velocity factor may be obtained from transmission-line data tables in Chapter 24.

Fig 8—This spiral is the actual "SWR circle" when line losses are taken into account. It is based on calculations for a 16-ft length of RG-174 coax feeding a resonant 28-MHz 300-Ω antenna (50-Ω coax, velocity factor = 66%, attenuation = 6.2 dB per 100 ft). The SWR at the load is 6:1, while it is 3.6:1 at the line input. When solving problems involving attenuation, two constant SWR circles are drawn instead of a spiral, one for the line input SWR and one for the load SWR.

Fig 9—Example of Smith Chart calculations taking line losses into account.

LINE-LOSS CONSIDERATIONS WITH THE SMITH CHART

The example Smith Chart problems presented in the previous section ignored attenuation, or line losses. Quite frequently it is not even necessary to consider losses when making calculations; any difference in readings obtained are often imperceptible on the chart. However, when the line losses become appreciable, such as for high-loss lines, long lines, or at VHF and UHF, loss considerations may become significant in making Smith Chart calculations. This involves only one simple step, in addition to the procedures previously presented.

Because of line losses, as discussed in Chapter 24 the SWR does not remain constant throughout the length of the line. As a result, there is a decrease in SWR as one progresses away from the load. To truly present this situation on the Smith Chart, instead of drawing a constant SWR circle, it would be necessary to draw a spiral inward and clockwise from the load impedance toward the generator, as shown in **Fig 8**. The rate at which the curve spirals toward prime center is related to the attenuation in the line. Rather than drawing spiral curves, a simpler method is used in solving line-loss problems, by means of the external scale TRANSMISSION LOSS 1-DB STEPS. This scale may be seen in **Fig 9**. Because this is only a relative scale, the decibel steps are not numbered.

If we start at the left end of this external scale and proceed in the direction indicated TOWARD GENERATOR, the first dB step is seen to occur at a radius from center corresponding to an SWR of about 9 (at A); the second dB step falls at an SWR of about 4.5 (at B), the third at 3.0 (at C), and so forth, until the

15th dB step falls at an SWR of about 1.05 to 1. This means that a line terminated in a short or open circuit (infinite SWR), and having an attenuation of 15 dB, would exhibit an SWR of only 1.05 at its input. It will be noted that the dB steps near the right end of the scale are very close together, and a line attenuation of 1 or 2 dB in this area will have only slight effect on the SWR. But near the left end of the scale, corresponding to high SWR values, a 1 or 2 dB loss has considerable effect on the SWR.

Using a Second SWR Circle

In solving a problem using line-loss information, it is necessary only to modify the radius of the SWR circle by an amount indicated on the TRANSMISSION-LOSS 1-DB STEPS scale. This is accomplished by drawing a second SWR circle, either smaller or larger than the first, depending on whether you are working toward the load or toward the generator.

For example, assume that we have a 50-Ω line that is 0.282 λ long, with 1-dB inherent attenuation. The line input impedance is measured as $60 + j\,35\,\Omega$. We desire to know the SWR at the input and at the load, and the load impedance. As before, we normalize the $60 + j\,35$-Ω impedance, plot it on the chart, and draw a constant SWR circle and a radial line through the point. In this case, the normalized impedance is $1.2 + j\,0.7$. From Fig 9, the SWR at the line input is seen to be 1.9 (at D), and the radial line is seen to cross the TOWARD LOAD scale, first subtract 0.500, and locate 0.110 (at F); then draw a radial line from this point to prime center.

To account for line losses, transfer the radius of the SWR circle to the external 1-DB STEPS scale. This radius crosses the external scale at G, the fifth decibel mark from the left. Since the line loss was given as 1 dB, we strike a new radius (at H), one "tick mark" to the left (toward load) on the same scale. (This will be the fourth decibel tick mark from the left of the scale.) Now transfer this new radius back to the main chart, and scribe a new SWR circle of this radius. This new radius represents the SWR at the load, and is read as 2.3 on the external VOLTAGE RATIO scale. At the intersection of the new circle and the load radial line, we read $0.65 - j\,0.6$. This is the normalized load impedance. Multiplying by 50, we obtain the actual load impedance as $32.5 - j\,30\,\Omega$. The SWR in this problem was seen to increase from 1.9 at the line input to 2.3 (at I) at the load, with the 1-dB line loss taken into consideration.

In the example above, values were chosen to fall conveniently on or very near the "tick marks" on the 1-dB scale. Actually, it is a simple matter to interpolate between these marks when making a radius correction. When this is necessary, the relative distance between marks for each decibel step should be maintained while counting off the proper number of steps.

Adjacent to the 1-DB STEPS scale lies a LOSS COEFFICIENT scale. This scale provides a factor by which the matched-line loss in decibels should be multiplied to account for the increased losses in the line when standing waves are present. These added losses do not affect the SWR or impedance calculations; they are merely the additional dielectric copper losses of the line caused by the fact that the line conducts more average voltage in the presence of standing waves. For the above example, from Fig 9, the loss coefficient at the input end is seen to be 1.21 (at J), and 1.39 (at K) at the load. As a good approximation, the loss coefficient may be averaged over the length of line under consideration; in this case, the average is 1.3. This means that the total losses in the line are 1.3 times the matched loss of the line (1 dB), or 1.3 dB. This is the same result that may be obtained from procedures given in Chapter 24 for this data.

Smith Chart Procedure Summary

To summarize briefly, any calculations made on the Smith Chart are performed in four basic steps, although not necessarily in the order listed.
1) Normalize and plot a line input (or load) impedance, and construct a constant SWR circle.
2) Apply the line length to the wavelengths scales.
3) Determine attenuation or loss, if required, by means of a second SWR circle.
4) Read normalized load (or input) impedance, and convert to impedance in ohms.

The Smith Chart may be used for many types of problems other than those presented as examples here. The transformer action of a length of line—to transform a high impedance (with perhaps high reactance) to a purely resistive impedance of low value—was not mentioned. This is known as "tuning the line," for which the chart is very helpful, eliminating the need for "cut and try" procedures. The chart may also be used to calculate lengths for shorted or open matching stubs in a system, described later in this chapter. In fact, in any application where a transmission line is not perfectly matched, the Smith Chart can be of value.

ATTENUATION AND Z_0 FROM IMPEDANCE MEASUREMENTS

If an impedance bridge is available to make accurate measurements in the presence of very high SWR values, the attenuation, characteristic impedance and velocity factor of any random length of coaxial transmission line can be determined. This section was written by Jerry Hall, K1TD.

Homemade impedance bridges and noise bridges will seldom offer the degree of accuracy required to use this technique, but sometimes laboratory bridges can be found as industrial surplus at a reasonable price. It may also be possible for an amateur to borrow a laboratory type of bridge for the purpose of making some weekend measurements. Making these determinations is not difficult, but the procedure is not commonly known among

amateurs. One equation treating complex numbers is used, but the math can be handled with a calculator supporting trig functions. Full details are given in the paragraphs that follow.

For each frequency of interest, two measurements are required to determine the line impedance. Just one measurement is used to determine the line attenuation and velocity factor. As an example, assume we have a 100-foot length of unidentified line with foamed dielectric, and wish to know its characteristics. We make our measurements at 7.15 MHz. The procedure is as follows.

1) Terminate the line in an open circuit. The best "open circuit" is one that minimizes the capacitance between the center conductor and the shield. If the cable has a PL-259 connector, unscrew the shell and slide it back down the coax for a few inches. If the jacket and insulation have been removed from the end, fold the braid back along the outside of the line, away from the center conductor.

2) Measure and record the impedance at the input end of the line. If the bridge measures admittance, convert the measured values to resistance and reactance. Label the values as $R_{oc} + j X_{oc}$. For our example, assume we measure $85 + j179$ Ω. (If the reactance term is capacitive, record it as negative.)

3) Now terminate the line in a short circuit. If a connector exists at the far end of the line, a simple short is a mating connector with a very short piece of heavy wire soldered between the center pin and the body. If the coax has no connector, removing the jacket and center insulation from a half inch or so at the end will allow you to tightly twist the braid around the center conductor. A small clamp or alligator clip around the outer braid at the twist will keep it tight.

4) Again measure and record the impedance at the input end of the line. This time label the values as $R_{sc} \pm j$ X. Assume the measured value now is $4.8 - j\,11.2$ Ω.

This completes the measurements. Now we reach for the calculator.

As amateurs we normally assume that the characteristic impedance of a line is purely resistive, but it can (and does) have a small capacitive reactance component. Thus, the Z_0 of a line actually consists of $R_0 + j X_0$. The basic equation for calculating the characteristic impedance is

$$Z_0 = \sqrt{Z_{oc} \times Z_{sc}} \qquad \text{(Eq 2)}$$

where

$$Z_{oc} = R_{oc} + jX_{oc}$$
$$Z_{sc} = R_{sc} + jX_{sc}$$

From Eq 2 the following working equation may be derived.

$$Z_0 = \sqrt{\left(R_{oc}R_{sc} - X_{oc}X_{sc}\right) + j\left(R_{oc}X_{sc} + R_{sc}X_{oc}\right)} \qquad \text{(Eq 3)}$$

The expression under the radical sign in Eq 3 is in the form of $R + j$ X. By substituting the values from our example into Eq 3, the R term becomes $85 \times 4.8 - 179 \times (-11.2) = 2412.8$, and the X term becomes $85 \times (-11.2) + 4.8 \times 179 = -92.8$. So far, we have determined that

$$Z_0 = \sqrt{2412.8 - j\,92.8}$$

The quantity under the radical sign is in rectangular form. Extracting the square root of a complex term is handled easily if it is in polar form, a vector value and its angle. The vector value is simply the square root of the sum of the squares, which in this case is

$$\sqrt{2412.8^2 + 92.8^2} = \sqrt{2414.58}$$

The tangent of the vector angle we are seeking is the value of the reactance term divided by the value of the resistance term. For our example this is arctan $-92.8/2412.8 = $ arctan -0.03846. The angle is thus found to be $-2.20°$. From all of this we have determined that

$$Z_0 = \sqrt{2414.58 \, \underline{/-2.20°}}$$

Extracting the square root is now simply a matter of finding

Fig 10—Determining the line loss and velocity factor with the Smith Chart from input measurements taken with open-circuit and short-circuit terminations.

the square root of the vector value, and taking half the angle. (The angle is treated mathematically as an exponent.)

Our result for this example is $Z_0 = 49.1\underline{/-1.1°}$. The small negative angle may be ignored, and we now know that we have coax with a nominal 50-Ω impedance. (Departures of as much as 6 to 8% from the nominal value are not uncommon.) If the negative angle is large, or if the angle is positive, you should recheck your calculations and perhaps even recheck the original measurements. You can get an idea of the validity of the measurements by normalizing the measured values to the calculated impedance and plotting them on a Smith Chart as shown in **Fig 10** for this example. Ideally, the two points should be diametrically opposite, but in practice they will be not quite 180° apart and not quite the same distance from prime center. Careful measurements will yield plotted points that are close to ideal. Significant departures from the ideal indicates sloppy measurements, or perhaps an impedance bridge that is not up to the task.

Determining Line Attenuation

The short circuit measurement may be used to determine the line attenuation. This reading is more reliable than the open circuit measurement because a good short circuit is a short, while a good open circuit is hard to find. (It is impossible to escape some amount of capacitance between conductors with an "open" circuit, and that capacitance presents a path for current to flow at the RF measurement frequency.)

Use the Smith Chart and the 1-DB STEPS external scale to find line attenuation. First normalize the short circuit impedance reading to the calculated Z_0, and plot this point on the chart. See Fig 10. For our example, the normalized impedance is 4.8/49.1 – j 11.2 / 49.1 or 0.098 – j 0.228. After plotting the point, transfer the radius to the 1-DB STEPS scale. This is shown at A of Fig 10.

Remember from discussions earlier in this chapter that the impedance for plotting a short circuit is $0 + j 0$, at the left edge of the chart on the resistance axis. On the 1-DB STEPS scale this is also at the left edge. The total attenuation in the line is represented by the number of dB steps from the left edge to the radius mark we have just transferred. For this example it is 0.8 dB. Some estimation may be required in interpolating between the 1-dB step marks.

Determining Velocity Factor

The velocity factor is determined by using the TOWARD GENERATOR wavelength scale of the Smith Chart. With a straightedge, draw a line from prime center through the point representing the short-circuit reading, until it intersects the wavelengths scale. In Fig 10 this

point is labeled B. Consider that during our measurement, the short circuit was the load at the end of the line. Imagine a spiral curve progressing from $0 + j 0$ clockwise and inward to our plotted measurement point. The wavelength scale, at B, indicates this line length is 0.464 λ. By rearranging the terms of Eq 1 given early in this chapter, we arrive at an equation for calculating the velocity factor.

$$VF = \frac{Lf}{984N} \qquad \text{(Eq 4)}$$

where

VF = velocity factor
L = line length, feet
f = frequency, MHz
N = number of electrical wavelengths in the line

Inserting the example values into Eq 4 yields VF = $100 \times 7.15/(984 \times 0.464) = 1.566$, or 156.6%. Of course, this value is an impossible number—the velocity factor in coax cannot be greater than 100%. But remember, the Smith Chart can be used for lengths greater than $1/2$ λ. Therefore, that 0.464 value could rightly be 0.964, 1.464, 1.964, and so on. When using 0.964 λ, Eq 4 yields a velocity factor of 0.753, or 75.3%. Trying successively greater values for the wavelength results in velocity factors of 49.6 and 37.0%. Because the cable we measured had foamed dielectric, 75.3% is the probable velocity factor. This corresponds to an electrical length of 0.964 λ. Therefore, we have determined from the measurements and

Fig 11—Smith Chart determination of input impedances for short- and open-circuited line sections, disregarding line losses.

calculations that our unmarked coax has a nominal 50-Ω impedance, an attenuation of 0.8 dB per hundred feet at 7.15 MHz, and a velocity factor of 75.3%.

It is difficult to use this procedure with short lengths of coax, just a few feet. The reason is that the SWR at the line input is too high to permit accurate measurements with most impedance bridges. In the example above, the SWR at the line input is approximately 12:1.

The procedure described above may also be used for determining the characteristics of balanced lines. However, impedance bridges are generally unbalanced

Fig 12—The method of stub matching a mismatched load on coaxial lines.

Fig 13—Smith Chart method of determining the dimensions for stub matching.

devices, and the procedure for measuring a balanced impedance accurately with an unbalanced bridge is complicated.

LINES AS CIRCUIT ELEMENTS

Information is presented in Chapter 24 on the use of transmission-line sections as circuit elements. For example, it is possible to substitute transmission lines of the proper length and termination for coils or capacitors in ordinary circuits. While there is seldom a practical need for that application, lines are frequently used in antenna systems in place of lumped components to tune or resonate elements. Probably the most common use of such a line is in the hairpin match, where a short section of stiff open-wire line acts as a lumped inductor.

The equivalent "lumped" value for any "inductor" or "capacitor" may be determined with the aid of the Smith Chart. Line losses may be taken into account if desired, as explained earlier. See **Fig 11**. Remember that the top half of the Smith Chart coordinate system is used for impedances containing inductive reactances, and the bottom half for capacitive reactances. For example, a section of 600-Ω line $^3/_{16}$-λ long (0.1875 λ) and short-circuited at the far end is represented by $\ell 1$, drawn around a portion of the perimeter of the chart. The "load" is a short-circuit, $0 + j\,0\,\Omega$, and the TOWARD GENERATOR wavelengths scale is used for marking off the line length. At A in Fig 11 may be read the normalized impedance as seen looking into the length of line, $0 + j\,2.4$. The reactance is therefore inductive, equal to $600 \times 2.4 = 1440\,\Omega$. The same line when open-circuited (termination impedance = ∞, the point at the right of the chart) is represented by $\ell 2$ in Fig 11. At B the normalized line-input impedance may be read as $0 - j\,0.41$; the reactance in this case is capacitive, $600 \times 0.41 = 246\,\Omega$. (Line losses are disregarded in these examples.) From Fig 11 it is easy to visualize that if $\ell 1$ were to be extended by $^1/_4$ λ, the total length represented by $\ell 3$, the line-input impedance would be identical to that obtained in the case represented by $\ell 2$ alone. In the case of $\ell 2$, the line is open-circuited at the far end, but in the case of $\ell 3$ the line is terminated in a short. The added section of line for $\ell 3$ provides the "transformer action" for which the $^1/_4$-λ line is noted.

The equivalent inductance and capacitance as determined above can be found by substituting these values in the equations relating inductance and capacitance to reactance, or by using the various charts and calculators available. The frequency corresponding to the line length in degrees must be used, of course. In this example, if the frequency is 14 MHz

the equivalent inductance and capacitance in the two cases are 16.4 µH and 46.2 pF, respectively. Note that when the line length is 45° (0.125 λ), the reactance in either case is numerically equal to the characteristic impedance of the line. In using the Smith Chart it should be kept in mind that the electrical length of a line section depends on the frequency and velocity of propagation, as well as on the actual physical length.

At lengths of line that are exact multiples of $^1/_4$ λ, such lines have the properties of resonant circuits. At lengths where the input reactance passes through zero at the left of the Smith Chart, the line acts as a series-resonant circuit. At lengths for which the reactances theoretically pass from "positive" to "negative" infinity at the right of the Smith Chart, the line simulates a parallel-resonant circuit.

Designing Stub Matches with the Smith Chart

The design of stub matches is covered in detail in Chapter 26. Equations are presented there to calculate the electrical lengths of the main line and the stub, based on a purely resistive load and on the stub being the same type of line as the main line. The Smith Chart may also be used to determine these lengths, without the requirements that the load be purely resistive and that the line types be identical.

Fig 12 shows the stub matching arrangement in coaxial line. As an example, suppose that the load is an antenna, a close-spaced array fed with a 52-Ω line. Further suppose that the SWR has been measured as 3.1:1. From this information, a constant SWR circle may be drawn on the Smith Chart. Its radius is such that it intersects the right portion of the resistance axis at the SWR value, 3.1, as shown at point B in **Fig 13**.

Since the stub of Fig 12 is connected in parallel with the transmission line, determining the design of the matching arrangement is simplified if Smith Chart values are dealt with as admittances, rather than impedances. (An admittance is simply the reciprocal of the associated impedance. Plotted on the Smith Chart, the two associated points are on the same SWR circle, but diametrically opposite each other.) Using admittances leaves less chance for errors in making calculations, by eliminating the need for making series-equivalent to parallel-equivalent circuit conversions and back, or else for using complicated equations for determining the resultant value of two complex impedances connected in parallel.

A complex impedance, Z, is equal to R + j X, as described in Chapter 24. The equivalent admittance, Y, is equal to G – j B, where G is the conductive component and B the susceptance. (Inductance is taken as negative susceptance, and capacitance as positive.) Conductance and susceptance values are plotted and handled on the Smith Chart in the same manner as resistance and reactance.

Assuming that the close-spaced array of our example has been resonated at the operating frequency, it will present a purely resistive termination for the load end of the 52-Ω line. From information in Chapter 24, it is known that the impedance of the antenna equals Z_0/SWR = 52/3.1 = 16.8 Ω. (We can logically discard the possibility that the antenna impedance is SWR × Z_0, or 0.06 Ω.) If this 16.8-Ω value were to be plotted as an impedance on the Smith Chart, it would first be normalized (16.8/52 = 0.32) and then plotted as 0.32 + j 0. Although not necessary for the solution of this example, this value is plotted at point A in Fig 13. What is necessary is a plot of the admittance for the antenna as a load. This is the reciprocal of the impedance; 1/16.8 Ω equals 0.060 siemen. To plot this point it is first normalized by multiplying the conductance and susceptance values by the Z_0 of the line. Thus, (0.060 + j 0) × 52 = 3.1 + j 0. This admittance value is shown plotted at point B in Fig 13. It may be seen that points A and B are diametrically opposite each other on the chart. Actually, for the solution of this example, it wasn't necessary to compute the values for either point A or point B as in the above paragraph, for they were both determined from the known SWR value of 3.1. As may be seen in Fig 13, the points are located on the constant SWR circle which was already drawn, at the two places where it intersects the resistance axis. The plotted value for point A, 0.32, is simply the reciprocal of the value for point B, 3.1. However, an understanding of the relationship between impedance and admittance is easier to gain with simple examples such as this.

In stub matching, the stub is to be connected at a point in the line where the conductive component equals the Z_0 of the line. Point B represents the admittance of the load, which is the antenna. Various admittances will be encountered along the line, when moving in a direction indicated by the TOWARD GENERATOR wavelengths scale, but all admittance plots must fall on the constant SWR circle. Moving clockwise around the SWR circle from point B, it is seen that the line input conductance will be 1.0 (normalized Z_0 of the line) at point C, 0.082 λ toward the transmitter from the antenna. Thus, the stub should be connected at this location on the line.

The normalized admittance at point C, the point representing the location of the stub, is 1 – j 1.2 siemens, having an inductive susceptance component. A capacitive susceptance having a normalized value of + j 1.2 siemens is required across the line at the point of stub connection, to cancel the inductance. This capacitance is to be obtained from the stub section itself; the problem now is to determine its type of termination (open or shorted), and how long the stub should be. This is done by first plotting the susceptance required for cancellation, 0 + j 1.2, on the chart (point D in Fig 13). This point represents the input admittance as seen looking into the stub. The "load" or termination for the stub section is found by moving in the TOWARD LOAD direction around the chart, and will appear at the closest point on the resistance/conductance axis, either at the left or the right

of the chart. Moving counterclockwise from point D, this is located at E, at the left of the chart, 0.139 λ away. From this we know the required stub length. The "load" at the far end of the stub, as represented on the Smith Chart, has a normalized admittance of 0 + *j* 0 siemen, which is equivalent to an open circuit.

When the stub, having an input admittance of 0 + *j* 1.2 siemens, is connected in parallel with the line at a point 0.082 λ from the load, where the line input admittance is 1.0 – *j* 1.2, the resultant admittance is the sum of the individual admittances. The conductance components are added directly, as are the susceptance components. In this case, 1.0 – *j* 1.2 + *j* 1.2 = 1.0 + *j* 0 siemen. Thus, the line from the point of stub connection to the transmitter will be terminated in a load which offers a perfect match. When determining the physical line lengths for stub matching, it is important to remember that the velocity factor for the type of line in use must be considered.

MATCHING WITH LUMPED CONSTANTS

It was pointed out earlier that the purpose of a matching stub is to cancel the reactive component of line impedance at the point of connection. In other words, the stub is simply a reactance of the proper kind and value shunted across the line. It does not matter what physical shape this reactance takes. It can be a section of trans-

mission line or a "lumped" inductance or capacitance, as desired. In the above example with the Smith Chart solution, a capacitive reactance was required. A capacitor having the same value of reactance can be used just as well. There are cases where, from an installation standpoint, it may be considerably more convenient to connect a capacitor in place of a stub. This is particularly true when open-wire feeders are used. If a variable capacitor is used, it becomes possible to adjust the capacitance to the exact value required.

The proper value of reactance may be determined from Smith Chart information. In the previous example, the required susceptance, normalized, was +*j* 1.2 siemens. This is converted into actual siemens by dividing by the line Z_0; 1.2/52 = 0.023 siemen, capacitance. The required capacitive reactance is the reciprocal of this latter value, 1/0.023 = 43.5 Ω. If the frequency is 14.2 MHz, for instance, 43.5 Ω corresponds to a capacitance of 258 pF. A 325-pF variable capacitor connected across the line 0.082 λ from the antenna terminals would provide ample adjustment range. The RMS voltage across the capacitor is

$$E = \sqrt{P \times Z_0}$$

For 500 W, for example, E = the square root of 500 × 52 = 161 V. The peak voltage is 1.41 times the RMS value, or 227 V.

The Series-Section Transformer

The series-section transformer is described in Chapter 26, and equations are given there for its design. The transformer can be designed graphically with the aid of a Smith Chart. This information is based on a *QST* article by Frank A. Regier, OD5CG. Using the Smith Chart to design a series-section match requires the use of the chart in its less familiar off-center mode. This mode is described in the next two paragraphs.

Fig 14 shows the Smith Chart used in its familiar centered mode, with all impedances normalized to that of the transmission line, in this case 75 Ω, and all constant SWR circles concentric with the normalized value r = 1 at the chart center. An actual impedance is recovered by multiplying a chart reading by the normalizing impedance of 75 Ω. If the actual (unnormalized) impedances represented by a constant SWR circle in Fig 14 are instead divided by a normalizing impedance of 300 Ω, a different picture results. A Smith Chart shows all possible impedances, and so a closed path such as a constant SWR circle in Fig 14 must again be represented by a closed path. In fact, it can be shown that the path remains a circle, but that the constant SWR circles are no longer concentric. **Fig 15** shows the circles that result when the

impedances along a mismatched 75-Ω line are normalized by dividing by 300 Ω instead of 75. The constant SWR circles still surround the point corresponding to the characteristic impedance of the line (r = 0.25) but are no longer concentric with it. Note that the normalized impedances read from corresponding points on Figs 14 and 15 are different but that the actual, unnormalized, impedances are exactly the same.

An Example

Now turn to the example shown in **Fig 16**. A complex load of $Z_L = 600 + j\ 900\ Ω$ is to be fed with 300-Ω line, and a 75-Ω series section is to be used. These characteristic impedances agree with those used in Fig 15, and thus Fig 15 can be used to find the impedance variation along the 75-Ω series section. In particular, the constant SWR circle which passes through the Fig 15 chart center, SWR = 4 in this case, passes through all the impedances (normalized to 300 Ω) which the 75-Ω series section is able to match to the 300-Ω main line. The length ℓ1 of 300-Ω line has the job of transforming the load impedance to some impedance on this matching circle.

Fig 17 shows the whole process more clearly, with all

Fig 14—Constant SWR circles for SWR = 2, 3, 4 and 5, showing impedance variation along 75-Ω line, normalized to 75 Ω. The actual impedance is obtained by multiplying the chart reading by 75 Ω.

Fig 15—Paths of constant SWR for SWR = 2, 3, 4 and 5, showing impedance variation along 75-Ω line, normalized to 300 Ω. Normalized impedances differ from those in Fig 14, but actual impedances are obtained by multiplying chart readings by 300 Ω and are the same as those corresponding in Fig 14. Paths remain circles but are no longer concentric. One, the matching circle, SWR = 4 in this case, passes through the chart center and is thus the locus of all impedances which can be matched to a 300-Ω line.

Fig 16—Example for solution by Smith Chart. All impedances are normalized to 300 Ω.

impedances normalized to 300 Ω. Here the normalized load impedance $Z_L = 2 + j\,3$ is shown at R, and the matching circle appears centered on the resistance axis and passing through the points r = 1 and $r = n^2 = (75/300)^2 = 0.0625$. A constant SWR circle is drawn from R to an intersection with the matching circle at Q or Q′ and the corresponding length ℓ1 (or ℓ1′) can be read directly from the Smith Chart. The clockwise distance around the matching circle represents the length of the matching line, from either Q′ to P or from Q to P. Because in this example the distance QP is the shorter of the two for the matching section, we choose the length ℓ1 as shown. By using values from the TOWARD GENERATOR scale, this length is found as 0.045 – 0.213, and adding 0.5 to obtain a positive result yields a value of 0.332 λ.

Although the impedance locus from Q to P is shown in Fig 17, the length ℓ2 cannot be determined directly from this chart. This is because the matching circle is not concentric with the chart center, so the wavelength scales do not apply to this circle. This problem is overcome by forming **Fig 18**, which is the same as Fig 17 except that all normalized impedances have been divided by n = 0.25, resulting in a Smith Chart normalized to 75 Ω instead of 300. The matching circle and the chart center are now concentric, and the series-section length ℓ2, the distance between Q and P, can be taken directly from the chart. By again using the TOWARD GENERATOR scale, this length is found as 0.250 – 0.148 = 0.102 λ.

In fact it is not necessary to construct the entire impedance locus shown in Fig 18. It is sufficient to plot Z_Q/n (Z_Q is read from Fig 17) and $Z_P/n = 1/n$, connect them by a circular arc centered on the chart center, and to determine the arc length ℓ2 from the Smith Chart.

Procedure Summary

The steps necessary to design a series-section transformer by means of the Smith Chart can now be listed:
1) Normalize all impedances by dividing by the characteristic impedance of the main line.
2) On a Smith Chart, plot the normalized load impedance Z_L at R and construct the matching circle

so that its center is on the resistance axis and it passes through the points r = 1 and r = n^2.

3) Construct a constant SWR circle centered on the chart center through point R. This circle should intersect the matching circle at two points. One of these points, normally the one resulting in the shorter clockwise distance along the matching circle to the chart center, is chosen as point Q, and the clockwise distance from R to Q is read from the chart and taken to be ℓ1.

4) Read the impedance Z_Q from the chart, calculate Z_Q/n and plot it as point Q on a second Smith Chart. Also plot r = 1/n as point P.

5) On this second chart construct a circular arc, centered on the chart center, clockwise from Q to P. The length of this arc, read from the chart, represents ℓ2. The design of the transformer is now complete, and the necessary physical line lengths may be determined.

The Smith Chart construction shows that two design solutions are usually possible, corresponding to the two intersections of the constant SWR circle (for the load) and the matching circle. These two values correspond to positive and negative values of the square-root radical in the equation for a mathematical solution of the problem. It may happen, however, that the load circle misses the matching circle completely, in which case no solution is possible. The cure is to enlarge the matching circle by choosing a series section whose impedance departs more from that of the main line.

A final possibility is that, rather than intersecting the matching circle, the load circle is tangent to it. There is then but one solution—that of the $^{1}/_{4}$-λ transformer.

BIBLIOGRAPHY

Source material and more extended discussion of topics covered in this chapter can be found in the references given below and in the textbooks listed at the end of Chapter 2.

W. N. Caron, *Antenna Impedance Matching* (Newington: ARRL, 1989).

C. MacKeand, "The Smith Chart in BASIC," *QST*, Nov 1984, pp 28-31.

M. W. Maxwell, *Reflections—Transmission Lines and Antennas* (Newington: ARRL, 1990).

F. A. Regier, Series-Section Transmission-Line Impedance Matching," *QST*, Jul 1978, pp 14-16.

P. H. Smith, *Electronic Applications of the Smith Chart*, reprint ed. (Malabar, FL: Krieger Pub Co, Inc, 1983).

Fig 17—Smith Chart representation of the example shown in Fig 16. The impedance locus always takes a clockwise direction from the load to the generator. This path is first along the constant SWR circle from the load at R to an intersection with the matching circle at Q or Q′, and then along the matching circle to the chart center at P. Length ℓ1 can be determined directly from the chart, and in this example is 0.332 λ.

Fig 18—The same impedance locus as shown in Fig 17 except normalized to 75 Ω instead of 300. The matching circle is now concentric with the chart center, and ℓ2 can be determined directly from the chart, 0.102 λ in this case.

Appendix

This appendix contains a glossary of terms, a list of common abbreviations, length conversion information (feet and inches), metric equivalents and antenna-gain-reference data.

Glossary of Terms

This glossary provides a handy list of terms that are used frequently in Amateur Radio conversation and literature about antennas. With each item is a brief definition of the term. Most terms given here are discussed more thoroughly in the text of this book, and may be located by using the index.

Actual ground—The point within the earth's surface where effective ground conductivity exists. The depth for this point varies with frequency and the condition of the soil.

Antenna—An electrical conductor or array of conductors that radiates signal energy (transmitting) or collects signal energy (receiving).

Antenna tuner—A device containing variable reactances (and perhaps a balun). It is connected between the transmitter and the feed point of an antenna system, and adjusted to "tune" or resonate the system to the operating frequency.

Aperture, effective—An area enclosing an antenna, on which it is convenient to make calculations of field strength and antenna gain. Sometimes referred to as the "capture area."

Apex—The feed-point region of a V type of antenna.

Apex angle—The included angle between the wires of a V, an inverted-V dipole, and similar antennas, or the included angle between the two imaginary lines touching the element tips of a log periodic array.

Balanced line—A symmetrical two-conductor feed line that has uniform voltage and current distribution along its length.

Balun—A device for feeding a balanced load with an unbalanced line, or vice versa. May be a form of choke, or a transformer that provides a specific impedance transformation (including 1:1). Often used in antenna systems to interface a coaxial transmission line to the feed point of a balanced antenna, such as a dipole.

Base loading—A lumped reactance that is inserted at the base (ground end) of a vertical antenna to resonate the antenna.

Bazooka—A transmission-line balancer. It is a quarter-wave conductive sleeve (tubing or flexible shielding) placed at the feed point of a center-fed element and grounded to the shield braid of the coaxial feed line at the end of the sleeve farthest from the feed point. It permits the use of unbalanced feed line with balanced feed antennas.

Beamwidth—Related to directive antennas. The width, in degrees, of the major lobe between the two directions at which the relative radiated power is equal to one half its value at the peak of the lobe (half power = –3 dB).

Beta match—A form of hairpin match. The two conductors straddle the boom of the antenna being matched, and the closed end of the matching-section conductors is strapped to the boom.

Bridge—A circuit with two or more ports that is used in measurements of impedance, resistance or standing waves in an antenna system. When the bridge is adjusted for a balanced condition, the unknown factor can be determined by reading its value on a calibrated scale or meter.

Capacitance hat—A conductor of large surface area that is connected at the high-impedance end of an antenna to effectively increase the electrical length. It is sometimes mounted directly above a loading coil to reduce the required inductance for establishing resonance. It usually takes the form of a series of wheel spokes or a solid circular disc. Sometimes referred to as a "top hat."

Capture area—See aperture.

Center fed—Transmission-line connection at the electrical center of an antenna radiator.

Center loading—A scheme for inserting inductive reactance (coil) at or near the center of an antenna element for the purpose of lowering its resonant frequency. Used with elements that are less than $^1/_4$ wavelength at the operating frequency.

Coax—See coaxial cable.

Coaxial cable—Any of the coaxial transmission lines that have the outer shield (solid or braided) on the same axis as the inner or center conductor. The insulating material can be air, helium or solid-dielectric compounds.

Collinear array—A linear array of radiating elements (usually dipoles) with their axes arranged in a straight line. Popular at VHF and above.

Conductor—A metal body such as tubing, rod or wire that permits current to travel continuously along its length.

Counterpoise—A wire or group of wires mounted close to ground, but insulated from ground, to form a low-impedance, high-capacitance path to ground. Used at MF and HF to provide an RF ground for an antenna. Also see ground plane.

Current loop—A point of current maxima (antipode) on an antenna.

Current node—A point of current minima on an antenna.

Decibel—A logarithmic power ratio, abbreviated dB. May also represent a voltage or current ratio if the voltages or currents are measured across (or through) identical impedances. Suffixes to the abbreviation indicate references: dBi, isotropic radiator; dBic, isotropic radiator circular; dBm, milliwatt; dBW, watt.

Delta loop—A full-wave loop shaped like a triangle or delta.

Delta match—Center-feed technique used with radiators that are not split at the center. The feed line is fanned near the radiator center and connected to the radiator symmetrically. The fanned area is delta shaped.

Dielectrics—Various insulating materials used in antenna systems, such as found in insulators and transmission lines.

Dipole—An antenna that is split at the exact center for connection to a feed line, usually a half wavelength long. Also called a "doublet."

Direct ray—Transmitted signal energy that arrives at the receiving antenna directly rather than being reflected by any object or medium.

Directivity—The property of an antenna that concentrates the radiated energy to form one or more major lobes.

Director—A conductor placed in front of a driven element to cause directivity. Frequently used singly or in multiples with Yagi or cubical-quad beam antennas.

Doublet—See dipole.

Driven array—An array of antenna elements which are all driven or excited by means of a transmission line, usually to achieve directivity.

Driven element—A radiator element of an antenna system to which the transmission line is connected.

Dummy load—Synonymous with dummy antenna. A nonradiating substitute for an antenna.

E layer—The ionospheric layer nearest earth from which radio signals can be reflected to a distant point, generally a maximum of 2000 km (1250 ml).

E plane—Related to a linearly polarized antenna, the plane containing the electric field vector of the antenna and its direction of maximum radiation. For terrestrial antenna systems, the direction of the E plane is also taken as the polarization of the antenna. The E plane is at right angles to the H plane.

Efficiency—The ratio of useful output power to input power, determined in antenna systems by losses in the system, including in nearby objects.

EIRP—Effective isotropic radiated power. The power radiated by an antenna in its favored direction, taking the gain of the antenna into account as referenced to isotropic.

Elements—The conductive parts of an antenna system that determine the antenna characteristics. For example, the reflector, driven element and directors of a Yagi antenna.

End effect—A condition caused by capacitance at the ends of an antenna element. Insulators and related support wires contribute to this capacitance and lower the resonant frequency of the antenna. The effect increases with conductor diameter and must be considered when cutting an antenna element to length.

End fed—An end-fed antenna is one to which power is applied at one end, rather than at some point between the ends.

F layer—The ionospheric layer that lies above the E layer. Radio waves can be refracted from it to provide communications distances of several thousand miles by means of single- or double-hop skip.

Feed line—See feeders.

Feeders—Transmission lines of assorted types that are used to route RF power from a transmitter to an antenna, or from an antenna to a receiver.

Field strength—The intensity of a radio wave as measured at a point some distance from the antenna. This measurement is usually made in microvolts per meter.

Front to back—The ratio of the radiated power off the front and back of a directive antenna. For example, a dipole would have a ratio of 1, which is equivalent to 0 dB.

Front to rear—Worst-case rearward lobe in the 180°-wide sector behind an antenna's main lobe, in dB.

Front to side—The ratio of radiated power between the major lobe and that 90° off the front of a directive antenna.

Gain—The increase in effective radiated power in the desired direction of the major lobe.

Gamma match—A matching system used with driven antenna elements to effect a match between the transmission line and the feed point of the antenna. It consists of a series capacitor and an arm that is mounted close to the driven element and in parallel with it near the feed point.

Ground plane—A system of conductors placed beneath an elevated antenna to serve as an earth ground. Also see counterpoise.

Ground screen—A wire mesh counterpoise.

Ground wave—Radio waves that travel along the earth's surface.

H plane—Related to a linearly polarized antenna. The plane containing the magnetic field vector of an antenna and its direction of maximum radiation. The H plane is at right angles to the E plane.

HAAT—Height above average terrain. A term used mainly in connection with repeater antennas in determining coverage area.

Hairpin match—A U-shaped conductor that is connected to the two inner ends of a split dipole for the purpose of creating an impedance match to a balanced feeder.

Harmonic antenna—An antenna that will operate on its fundamental frequency and the harmonics of the fundamental frequency for which it is designed. An end-fed half-wave antenna is one example.

Helical—A helically wound antenna, one that consists of a spiral conductor. If it has a very large winding length to diameter ratio it provides broadside radiation. If the length-to-diameter ratio is small, it will operate in the axial mode and radiate off the end opposite the feed point. The polarization will be circular for the axial mode, with left or right circularity, depending on whether the helix is wound clockwise or counter-clockwise.

Helical hairpin—"Hairpin" match with a lumped inductor, rather than parallel-conductor line.

Image antenna—The imaginary counterpart of an actual antenna. It is assumed for mathematical purposes to be located below the earth's surface beneath the antenna, and is considered symmetrical with the antenna above ground.

Impedance—The ohmic value of an antenna feed point, matching section or transmission line. An impedance may contain a reactance as well as a resistance component.

Inverted V—A misnomer, as the antenna being referenced does not have the characteristics of a V antenna. See inverted-V dipole.

Inverted-V dipole—A half-wavelength dipole erected in the form of an upside-down V, with the feed point at the apex. Its radiation pattern is similar to that of a horizontal dipole.

Isotropic—An imaginary or hypothetical point-source antenna that radiates equal power in all directions. It is used as a reference for the directive characteristics of actual antennas.

Lambda—Greek symbol (λ) used to represent a wavelength with reference to electrical dimensions in antenna work.

Line loss—The power lost in a transmission line, usually expressed in decibels.

Line of sight—Transmission path of a wave that travels directly from the transmitting antenna to the receiving antenna.

Litz wire—Stranded wire with individual strands insulated; small wire provides a large surface area for current flow, so losses are reduced for the wire size.

Load—The electrical entity to which power is delivered. The antenna system is a load for the transmitter.

Loading—The process of a transferring power from its source to a load. The effect a load has on a power source.

Lobe—A defined field of energy that radiates from a directive antenna.

Log periodic antenna—A broadband directive antenna that has a structural format causing its impedance and radiation characteristics to repeat periodically as the logarithm of frequency.

Long wire—A wire antenna that is one wavelength or greater in electrical length. When two or more wave-lengths long it provides gain and a multilobe radiation pattern. When terminated at one end it becomes essentially unidirectional off that end.

Marconi antenna—A shunt-fed monopole operated against ground or a radial system. In modern jargon, the term refers loosely to any type of vertical antenna.

Matching—The process of effecting an impedance match between two electrical circuits of unlike impedance. One example is matching a transmission line to the feed point of an antenna. Maximum power transfer to the load (antenna system) will occur when a matched condition exists.

Monopole—Literally, one pole, such as a vertical radiator operated against the earth or a counterpoise.

Nichrome wire—An alloy of nickel and chromium; not a good conductor; resistance wire. Used in the heating elements of electrical appliances; also as conductors in transmission lines or circuits where attenuation is desired.

Null—A condition during which an electrical unit is at a minimum. A null in an antenna radiation pattern is a point in the 360-degree pattern where a minima in field intensity is observed. An impedance bridge is said to be "pulled" when it has been brought into balance, with a null in the current flowing through the bridge arm.

Octave—A musical term. As related to RF, frequencies having a 2:1 harmonic relationship.

Open-wire line—A type of transmission line that resembles a ladder, sometimes called "ladder line." Consists of parallel, symmetrical wires with insulating spacers at regular intervals to maintain the line spacing. The dielectric is principally air, making it a low-loss type of line.

Parabolic reflector—An antenna reflector that is a portion of a parabolic revolution or curve. Used mainly at UHF and higher to obtain high gain and a relatively narrow beamwidth when excited by one of a variety of driven elements placed in the plane of and perpendicular to the axis of the parabola.

Parasitic array—A directive antenna that has a driven element and at least one independent director or reflector, or a combination of both. The directors and reflectors are not connected to the feed line. Except for VHF and UHF arrays with long booms (electrically), more than one reflector is seldom used. A Yagi antenna is one example of a parasitic array.

Phasing lines—Sections of transmission line that are used to ensure the correct phase relationship between the elements of a driven array, or between bays of an array of antennas. Also used to effect impedance transformations while maintaining the desired phase.

Polarization—The sense of the wave radiated by an antenna. This can be horizontal, vertical, elliptical or circular (left or right hand circularity), depending on the design and application. (See H plane.)

Q section—Term used in reference to transmission-line matching transformers and phasing lines.

Quad—A parasitic array using rectangular or diamond shaped full-wave wire loop elements. Often called the "cubical quad." Another version uses delta-shaped elements, and is called a delta loop beam.

Radiation pattern—The radiation characteristics of an antenna as a function of space coordinates. Normally, the pattern is measured in the far-field region and is represented graphically.

Radiation resistance—The ratio of the power radiated by an antenna to the square of the RMS antenna current, referred to a specific point and assuming no losses. The effective resistance at the antenna feed point.

Radiator—A discrete conductor that radiates RF energy in an antenna system.

Random wire—A random length of wire used as an antenna and fed at one end by means of an antenna tuner. Seldom operates as a resonant antenna unless the length happens to be correct.

Reflected ray—A radio wave that is reflected from the earth, ionosphere or a man-made medium, such as a passive reflector.

Reflector—A parasitic antenna element or a metal assembly that is located behind the driven element to enhance forward directivity. Hillsides and large man-made structures such as buildings and towers may act as reflectors.

Refraction—Process by which a radio wave is bent and returned to earth from an ionospheric layer or other medium after striking the medium.

Resonator—In antenna terminology, a loading assembly consisting of a coil and a short radiator section. Used to lower the resonant frequency of an antenna, usually a vertical or a mobile whip.

Rhombic—A rhomboid or diamond-shaped antenna consisting of sides (legs) that are each one or more wavelengths long. The antenna is usually erected parallel to the ground. A rhombic antenna is bidirectional unless terminated by a resistance, which makes it unidirectional. The greater the electrical leg length, the greater the gain, assuming the tilt angle is optimized.

Shunt feed—A method of feeding an antenna driven element with a parallel conductor mounted adjacent to a low-impedance point on the radiator. Frequently used with grounded quarter-wave vertical antennas to provide an impedance match to the feeder. Series feed is used when the base of the vertical is insulated from ground.

Stacking—The process of placing similar directive antennas atop or beside one another, forming a "stacked array." Stacking provides more gain or directivity than a single antenna.

Stub—A section of transmission line used to tune an antenna element to resonance or to aid in obtaining an impedance match.

SWR—Standing-wave ratio on a transmission line in an antenna system. More correctly, VSWR, or voltage standing-wave ratio. The ratio of the forward to reflected voltage on the line, and not a power ratio. A VSWR of 1:1 occurs when all parts of the antenna system are matched correctly to one another.

T match—Method for matching a transmission-line to an unbroken driven element. Attached at the electrical center of the driven element in a T-shaped manner. In effect it is a double gamma match.

Tilt angle—Half the angle included between the wires at the sides of a rhombic antenna.

Top hat—See capacitance hat.

Top loading—Addition of a reactance (usually a capacitance hat) at the end of an antenna element opposite the feed point to increase the electrical length of the radiator.

Transmatch—An antenna tuner.

Trap—Parallel L-C network inserted in an antenna element to provide multiband operation with a single conductor.

Unipole—See monopole.

Velocity factor—The ratio of the velocity of radio wave propagation in a dielectric medium to that in free space. When cutting a transmission line to a specific electrical length, the velocity factor of the particular line must be taken into account.

VSWR—Voltage standing-wave ratio. See SWR.

Wave—A disturbance or variation that is a function of time or space, or both, transferring energy progressively from point to point. A radio wave, for example.

Wave angle—The angle above the horizon of a radio wave as it is launched from or received by an antenna. Also called elevation angle.

Wave front—A surface that is a locus of all the points having the same phase at a given instant in time.

Yagi—A directive, gain type of antenna that utilizes a number of parasitic directors and a reflector. Named after one of the two Japanese inventors (Yagi and Uda).

Zepp antenna—A half-wave wire antenna that operates on its fundamental and harmonics. It is fed at one end by means of open-wire feeders. The name evolved from its popularity as an antenna on Zeppelins. In modern jargon the term refers loosely to any horizontal antenna.

Abbreviations

Abbreviations and acronyms that are commonly used throughout this book are defined in the list below. Periods are not part of an abbreviation unless the abbreviation otherwise forms a common English word. When appropriate, abbreviations as shown are used in either singular or plural construction.

-A-
A—ampere
ac—alternating current
AF—audio frequency
AFSK—audio frequency-shift keying
AGC—automatic gain control
AM—amplitude modulation
ANT—antenna
ARRL—American Radio Relay League
ATV—amateur television
AWG—American wire gauge
az-el—azimuth-elevation

-B-
balun—balanced to unbalanced
BC—broadcast
BCI—broadcast interference
BW—bandwidth

-C-
ccw—counterclockwise
cm—centimeter
coax—coaxial cable
CT—center tap
cw—clockwise
CW—continuous wave

-D-
D—diode
dB—decibel
dBd—decibels referenced to a dipole
dBi—decibels referenced to isotropic
dBic—decibels referenced to isotropic, circular
dBm—decibels referenced to one milliwatt
dBW—decibels referenced to one watt
dc—direct current
deg—degree
DF—direction finding
dia—diameter
DPDT—double pole, double throw
DPST—double pole, single throw
DVM—digital voltmeter
DX—long distance communication

-E-
E—ionospheric layer, electric field
ed.—edition
Ed.—editor
EIRP—effective isotropic radiated power
ELF—extremely low frequency
EMC—electromagnetic compatibility
EME—earth-moon-earth

EMF—electromotive force
ERP—effective radiated power
E_S—ionospheric layer (sporadic E)

-F-
f—frequency
F—ionospheric layer, farad
F/B—front to back (ratio)
F/R—worst-case front to rear (ratio)
FM—frequency modulation
FOT—frequency of optimum transmission
ft—foot or feet (unit of length)
F_1—ionospheric layer
F_2—ionospheric layer

-G-
GDO—grid- or gate-dip oscillator
GHz—gigahertz
GND—ground

-H-
H—magnetic field, henry
HAAT—height above average terrain
HF—high frequency (3-30 MHz)
Hz—hertz (unit of frequency)

-I-
I—current
ID—inside diameter
IEEE—Institute of Electrical and Electronic Engineers
in.—inch
IRE—Institute of Radio Engineers (now IEEE)

-J-
j—vector notation

-K-
kHz—kilohertz
km—kilometer
kW—kilowatt
kW—kilohm

-L-
L—inductance
lb—pound (unit of mass)
LF—low frequency (30-300 kHz)
LHCP—left-hand circular polarization
ln—natural logarithm
log—common logarithm
LP—log periodic
LPDA—log periodic dipole array
LPVA—log periodic V array
LUF—lowest usable frequency

-M-
m—meter (unit of length)
m/s—meters per second
mA—milliampere
max—maximum
MF—medium frequency (0.3-3 MHz)
mH—millihenry
MHz—megahertz
mi—mile
min—minute
mm—millimeter
ms—millisecond
mS—millisiemen
MS—meteor scatter
MUF—maximum usable frequency
mW—milliwatt
MW—megohm

-N-
NC—no connection, normally closed
NiCd—nickel cadmium
NIST—National Institute of Standards and Technology
NO—normally open
no.—number

-O-
OD—outside diameter

-P-
p—page (bibliography reference)
P-P—peak to peak
PC—printed circuit
PEP—peak envelope power
pF—picofarad
pot—potentiometer
pp—pages (bibliography reference)
Proc—Proceedings

-Q-
Q—figure of merit

-R-
R—resistance, resistor
RF—radio frequency
RFC—radio frequency choke
RFI—radio frequency interference
RHCP—right-hand circular polarization
RLC—resistance-inductance-capacitance
r/min—revolutions per minute
RMS—root mean square
r/s—revolutions per second
RSGB—Radio Society of Great Britain
RX—receiver

-S-
s—second
S—siemen

S/NR—signal-to-noise ratio
SASE—self-addressed stamped envelope
SINAD—signal-to-noise and distortion
SPDT—single pole, double throw
SPST—single pole, single throw
SWR—standing wave ratio
sync—synchronous

-T-
tpi—turns per inch
TR—transmit-receive
TVI—television interference
TX—transmitter

-U-
UHF—ultra-high frequency (300-3000 MHz)
US—United States
UTC—Universal Time, Coordinated

-V-
V—volt
VF—velocity factor
VHF—very-high frequency (30-300 MHz)
VLF—very-low frequency (3-30 kHz)
Vol—volume (bibliography reference)
VOM—volt-ohm meter
VSWR—voltage standing-wave ratio
VTVM—vacuum-tube voltmeter

-W-
W—watt
WPM—words per minute
WRC—World Radio Conference
WVDC—working voltage, direct current

-X-
X—reactance
XCVR—transceiver
XFMR—transformer
XMTR—transmitter

-Z-
Z—impedance

-Other symbols and Greek letters-
°—degrees
λ—wavelength
λ/dia—wavelength to diameter (ratio)
μ—permeability
μF—microfarad
μH—microhenry
μV—microvolt
Ω—ohm
φ—angles
π—3.14159
θ—angles

Length Conversions

Throughout this book, equations may be found for determining the design length and spacing of antenna elements. For convenience, the equations are written to yield a result in feet. (The answer may be converted to meters simply by multiplying the result by 0.3048.) If the result in feet is not an integral number, however, it is necessary to make a conversion from a decimal fraction of a foot to inches and fractions before the physical distance can be determined with a conventional tape measure. Table 1 may be used for this conversion, showing inches and fractions for increments of 0.01 foot. The table deals with only the fractional portion of a foot. The integral number of feet remains the same.

For example, say a calculation yields a result of 11.63 feet, and we wish to convert this to a length we can find on a tape measure. For the moment, consider only the fractional part of the number, 0.63 foot. In Table 1 locate the line with "0.6" appearing in the left column. (This is the 7th line down in the body of the table.) Then while staying on that line, move over to the column headed "0.03." Note here that the sum of the column and line heads, 0.6 + 0.03, equals the value of 0.63 that we want to convert. In the body of the table for this column and line we read the equivalent fraction for 0.63 foot, $7^9/_{16}$ inches. To that value, add the number of whole feet from the value being converted, 11 in this case. The total length equivalent of 11.63 feet is thus 11 feet $7^9/_{16}$ inches.

Similarly, Table 2 may be used to make the conversion from inches and fractions to decimal fractions of a foot. This table is convenient for using measured distances in equations. For example, say we wish to convert a length of 19 feet $7^3/_4$ inches to a decimal fraction. Considering only the fractional part of this value, $7^3/_4$ inches, locate the decimal value on the line identified as "7-" and in the column headed "$^3/_4$," where we read 0.646. This decimal value is equivalent to $7 + ^3/_4 = 7^3/_4$ inches. To this value add the whole number of feet from the value being converted for the final result, 19 in this case. In this way, 19 feet $7^3/_4$ inches converts to 19 + 0.646 = 19.646 feet.

Table 2
Conversion, Inches and Fractions to Decimal Feet

	Fractional Increments							
	0	*$^1/_8$*	*$^1/_4$*	*$^3/_8$*	*$^1/_2$*	*$^5/_8$*	*$^3/_4$*	*$^7/_8$*
0-	0.000	0.010	0.021	0.031	0.042	0.052	0.063	0.073
1-	0.083	0.094	0.104	0.115	0.125	0.135	0.146	0.156
2-	0.167	0.177	0.188	0.198	0.208	0.219	0.229	0.240
3-	0.250	0.260	0.271	0.281	0.292	0.302	0.313	0.323
4-	0.333	0.344	0.354	0.365	0.375	0.385	0.396	0.406
5-	0.417	0.427	0.438	0.448	0.458	0.469	0.479	0.490
6-	0.500	0.510	0.521	0.531	0.542	0.552	0.563	0.573
7-	0.583	0.594	0.604	0.615	0.625	0.635	0.646	0.656
8-	0.667	0.677	0.688	0.698	0.708	0.719	0.729	0.740
9-	0.750	0.760	0.771	0.781	0.792	0.802	0.813	0.823
10-	0.833	0.844	0.854	0.865	0.875	0.885	0.896	0.906
11-	0.917	0.927	0.938	0.948	0.958	0.969	0.979	0.990

Table 1
Conversion, Decimal Feet to Inches (Nearest 16th)

	Decimal Increments									
	0.00	*0.01*	*0.02*	*0.03*	*0.04*	*0.05*	*0.06*	*0.07*	*0.08*	*0.09*
0.0	0-0	$0^1/_8$	$0^1/_4$	$0^3/_8$	$0^1/_2$	$0^5/_8$	$0^3/_4$	$0^{13}/_{16}$	$0^{15}/_{16}$	$1^1/_{16}$
0.1	$1^3/_{16}$	$1^5/_{16}$	$1^7/_{16}$	$1^9/_{16}$	$1^{11}/_{16}$	$1^{13}/_{16}$	$1^{15}/_{16}$	$2^1/_{16}$	$2^3/_{16}$	$2^1/_4$
0.2	$2^3/_8$	$2^1/_2$	$2^5/_8$	$2^3/_4$	$2^7/_8$	3-0	$3^1/_8$	$3^1/_4$	$3^3/_8$	$3^1/_2$
0.3	$3^5/_8$	$3^3/_4$	$3^{13}/_{16}$	$3^{15}/_{16}$	$4^1/_{16}$	$4^3/_{16}$	$4^5/_{16}$	$4^7/_{16}$	$4^9/_{16}$	$4^{11}/_{16}$
0.4	$4^{13}/_{16}$	$4^{15}/_{16}$	$5^1/_{16}$	$5^3/_{16}$	$5^1/_4$	$5^3/_8$	$5^1/_2$	$5^5/_8$	$5^3/_4$	$5^7/_8$
0.5	6-0	$6^1/_8$	$6^1/_4$	$6^3/_8$	$6^1/_2$	$6^5/_8$	$6^3/_4$	$6^{13}/_{16}$	$6^{15}/_{16}$	$7^1/_{16}$
0.6	$7^3/_{16}$	$7^5/_{16}$	$7^7/_{16}$	$7^9/_{16}$	$7^{11}/_{16}$	$7^{13}/_{16}$	$7^{15}/_{16}$	$8^1/_{16}$	$8^3/_{16}$	$8^1/_4$
0.7	$8^3/_8$	$8^1/_2$	$8^5/_8$	$8^3/_4$	$8^7/_8$	9-0	$9^1/_8$	$9^1/_4$	$9^3/_8$	$9^1/_2$
0.8	$9^5/_8$	$9^3/_4$	$9^{13}/_{16}$	$9^{15}/_{16}$	$10^1/_{16}$	$10^3/_{16}$	$10^5/_{16}$	$10^7/_{16}$	$10^9/_{16}$	$10^{11}/_{16}$
0.9	$10^{13}/_{16}$	$10^{15}/_{16}$	$11^1/_{16}$	$11^3/_{16}$	$11^1/_4$	$11^3/_8$	$11^1/_2$	$11^5/_8$	$11^3/_4$	$11^7/_8$

Metric Equivalents

Throughout this book, distances and dimensions are usually expressed in English units—the mile, the foot, and the inch. Conversions to metric units may be made by using the following equations:

$\text{km} = \text{mi} \times 1.609$

$\text{m} = \text{ft} (') \times 0.3048$

$\text{mm} = \text{in.} ('') \times 25.4$

An inch is $^1/_{12}$ of a foot. Tables in the previous section provide information for accurately converting inches and fractions to decimal feet, and vice versa, without the need for a calculator.

Gain Reference

Throughout this book, gain is referenced to an isotropic radiator (dBi) or to an isotropic radiator with circular polarization (dBic).

Advertisers Index

Advertising Department Staff
Debra Jahnke, K1DAJ, *Business Services Manager*
Janet Rocco, W1JLR, *Business Services Associate*
Lisa Tardette, KB1MOI, *Business Services Associate*
Diane Szlachetka, KB1OKV, *Advertising Graphic Design*

1-800-243-7768

Direct Line: 860-594-0207 ▪ Fax: 860-594-4285 ▪ e-mail: ads@arrl.org ▪ Web: www.arrl.org/ads

MFJ-259B *Antenna Analyzer*

The world's most popular antenna analyzer gives you a complete picture of your antenna performance 1.8 to 170 MHz. Super easy-to-use -- makes tuning your antenna quick and easy. Read antenna SWR, complex impedance, return loss, reflection coefficient. Determine velocity factor, coax cable loss in dB, length of coax and distance to a short or open in feet. Read inductance in uH and capacitance in pF at RF frequencies. Large easy-to-read two line LCD screen and side-by-side meters clearly display your information. Built-in frequency counter, Ni-Cad charger circuit, battery saver, low battery warning

and smooth reduction drive tuning.

MFJ-259B $279⁹⁵

MFJ-99B, $88.80. Accessory Package for MFJ-259B. Includes MFJ-29C custom foam-filled carrying case, MFJ-66 dip meter adapters, MFJ-1312D 110VAC adapter and 10-pack high capacity Ni-MH MFJ *SuperCell*™ batteries. *Save $7!*

1.8-170 MHz *plus* 415-470 MHz *Antenna Analyzer*

All-in-one handheld antenna test lab lets you quickly check/tune HF, VHF, *UHF* antennas anywhere. Measures: SWR, Return Loss, Reflection Coefficient, R, X, Z, Phase Angle, Coax cable loss, Coax cable length, Distance to short/open in coax, Inductance, Capacitance, Resonant Frequency, Bandwidth, Q, Velocity Factor, Attenuation, more!

MFJ-269 $379⁹⁵

MFJ *Weather-Proof* Antenna *Feedthrough* Panel

Bring three coax-fed HF/VHF/UHF antennas, balanced line, random wire and ground into your hamshack without drilling through walls . . . **New!** MFJ-4602 $59⁹⁵

MFJ's Weather-proof *Antenna Feedthrough Panel* mounts in your window sill. Lets you feed three coax-fed antennas, balanced line, random wire and ground without drilling through walls.

Simply place in window sill and close window. One cut customizes it for any window up to 48 inches. Use horizontally or vertically. High-quality pressure-treated wood with excellent 3/4 inch thick insulating properties is painted with heavy coat of white outdoor enamel paint. Edges sealed by weather-stripping. Seals

and insulates against all weather conditions. Gives years of trouble-free service. ³/₄Dx3¹/₂Hx48W in.

Inside/outside stainless steel plates bond all coax shields to ground. Stainless steel ground post brings outside ground connection inside. 3 *Teflon*⁽ᴿ⁾ SO-239 coax connectors, *ceramic* balanced line/randomwire feedthru insulators.

Indoor View

Stainless Steel Bonding Plate

Outdoor View

Current Balun/Center Insulator

MFJ-918 $24⁹⁵ **True** *1:1 Current Balun/Center Insulator* forces equal antenna currents in dipoles. *Improves all dipoles/doublets!* Reduces coax feedline radiation, field pattern distortion, TVI, RFI, RF hot spots. SO-239. 1.8-30 MHz, 1.5kW. Stainless steel hardware. *Direct* wire connection to antenna. 5x2 inches.

MFJ-915 RF Isolator

MFJ-915 $29⁹⁵ **MFJ-915** *RF Isolator* prevents unwanted RF from traveling on the outside of your coax shield into your transceiver. Clears up RFI. Eliminates painful RF "bites" on your rig or microphone. Keeps your transceiver and vehicle displays and settings from locking up. Plugs between coax and transceiver. 5x2 inches. 1.8-30 MHz, 1.5 kW.

MFJ W9INN Balun Box

Converts unbalanced coax line to balanced ladder transmission line. *Giant* 2-core 4:1 balun wound with *Teflon*⁽ᴿ⁾ wire. 3¹/₄x2¹/₄x7 inches. Heavy duty ceramic feed-through insulators. 1500 Watts full legal limit. SO-239. Ground post, mounting holes.

MFJ-912 $59⁹⁵

Antenna Switches

MFJ-1702C 2 position antenna coax switch. Exclusive lightning arrestor and center pos. ground, lightning arrestor. 2.5 kW PEP, 1 kW CW. Loss below .2 dB. 50 dB isolation @ 450 MHz. 50 Ohms. 3x2x3".

MFJ-1702C $34⁹⁵

MFJ-1704. Like MFJ-1702C but has 4 positions. 6¹/₄x4¹/₄ x1¹/₄ in. 50 load. SWR 1.1: 1 to 30 MHz; 1.5:1, 30-650 MHz. SO-239.

MFJ-1704 $74⁹⁵

All Band G5RV Antennas

160-10 Meters with tuner. 102 foot.1.5 kW. Use as Marconi on 160 Meters with tuner/ground. Ladder line/SO-239. **MFJ-1778M, $34.95.** *Half-size*, 52 ft. G5RV-Jr. 60-10 Meters with tuner. 1.5 kW.

MFJ-1778 $39⁹⁵

33 Foot *fiberglass* Mast

MFJ-1910 **33** foot super strong fiberglass *telescoping* mast collapses to 3.8 feet, weighs 3.3 lbs. Huge, strong 1³/₄ inch bottom section. Flexes to resist breaking. Resists UV. Put up *full size* inverted Vee dipole/vertical antenna in minutes and get *full size performance!*

$79⁹⁵

6-Band *Rotatable* mini-Dipole

MFJ-1775 $239⁹⁵

Low-profile mini 14 foot rotatable dipole has tiny 7-foot turning radius. Fits on smallest roof -- perfect for town houses, apartments and condos.

Easily turned by TV rotator.

It's no Wimp! Good *directivity* reduces QRM/noise and lets you *focus* your signal in the direction that you want -- so you can work some *real* DX.

Operate 40, 20, 15, 10, 6, 2 meters. Run *full 1500 Watts* SSB/CW on all HF bands!

Ham radio's most versatile rotatable dipole features automatic band switching. Uses highly efficient end-loading with its *entire length* always radiating.

No lossy traps! Has separate, efficient end-loading *Teflon*™ coils on fiberglass forms and capacitance hats for each HF band. 6/2 Meters are *full-length* dipoles.

Built-to-last -- super strong solid fiberglass center insulator, 6063 T-6 aircraft strength aluminum tubing. Assembles in an afternoon.

MFJ-1775W, $239.95. WARC band version for 12, 17, 30, 60 Meters only.

MFJ Field Strength Meters

Huge 3" meter. Telescoping ground-independent *dipole*. .1-500 MHz. Sensitivity control. Remote sensor, MFJ-802R, $24.95. **MFJ-801, $24.95.** *Monopole* field strength meter, 1¹/₄" meter.

MFJ-802 $44⁹⁵

Clamp-On RF Ammeter

MFJ-854 $109⁹⁵ *Clamp-On* RF Ammeter snaps over cables up to ½ inch diameter. Measure RF currents in antenna elements, radials, ground wires, coax shield. Five *calibrated* ranges to 3 Amps. 1-30 MHz. 2½Wx5½Hx1½D inches.

Free MFJ Catalog
and Nearest Dealer . . . 800-647-1800

http://www.mfjenterprises.com
• 1 Year *No Matter What*™ warranty • 30 day money back guarantee (less s/h) on orders direct from MFJ

MFJ ENTERPRISES, INC. 300 Industrial Pk Rd, Starkville, MS 39759 **PH:** (662) 323-5869 **Tech Help:** (662) 323-0549 **FAX:** (662) 323-6551 8-4:30 CST, Mon.-Fri. *Add shipping.* *Prices and specifications subject to change.* (c) 2007 MFJ Enterprises, Inc.

Special Advertising Section   AB-3

hy-gain HF VERTICALS

Self-supporting -- no guys required . . . Remarkable DX performance -- low angle radiation, omnidirectional . . . Handles 1500 Watts . . . Low SWR . . . Automatic band switching . . . Aircraft quality aluminum tubing . . . Stainless steel hardware . . . Recessed SO-239 connector . . . Two year limited Warranty . . .

Free Manuals!

AV-18HT $949⁹⁵ AV-14AVQ $169⁹⁵ AV-12AVQ $124⁹⁵ AV-18VS $99⁹⁵ DX-88, $369⁹⁵ DX-77A, $449⁹⁵

hy-gain(R) Classics

All hy-gain multi-band vertical antennas are entirely self supporting -- no guys required.

They offer remarkable DX performance with their extremely low angle of radiation and omni-directional pattern.

All handle 1500 Watts PEP SSB, have low SWR, automatic band-switching (except AV-18VS) and include a 12-inch heavy duty mast support bracket (except AV-18HT).

Heavy duty, slotted, tapered swaged, aircraft quality aluminum tubing with full circumference

compression clamps is used for radiators. Includes all stainless steel hardware. Recessed SO-239 prevents moisture damage. Hy-gain verticals go up easily with just hand tools and their cost is surprisingly low. Two year limited warranty.

AV-18HT, $949.95. (10,12,15,20,40,80 M, 160, 17 Meters optional). 53 ft., 114 lbs.
Standing 53 feet tall, the famous *Hy-Gain HyTower* is the world's best performing vertical! The AV-18HT features automatic band selection achieved through a unique stub-decoupling system which effectively isolates various sections of the antenna so that an electrical 1/4 wavelength (or odd multiple of a 1/4 wavelength) exists on all bands. Approximately 250 kHz bandwidth at 2:1 VSWR on 80 Meters. The addition of a base loading coil (**LC-160Q, $109.95**), provides exceptional 160 Meter performance. **MK-17, $89.95**. Add-on 17 Meter kit. 24 foot tower is all rugged, hot-dip galvanized steel and all hardware is iridited for corrosion resistance. Special tilt-over hinged base for easy raising & lowering.

AV-14AVQ, $169.95. (10,15,20,40 Meters). 18 ft., 9 lbs. The Hy-Gain AV-14AVQ uses the same trap design as the famous Hy-Gain Thunderbird beams. Three separate air dielectric Hy-Q traps with oversize coils give superb stability and 1/4 wave resonance on all bands. Roof mount with Hy-Gain AV-14RMQ kit, $89.95.

AV-12AVQ, $124.95. (10, 15, 20 Meters). 13 ft., 9 lbs. AV-12AVQ also uses Thunder-bird beam design air dielectric traps for extremely Hy-Q performance. This is the way to go for inexpensive tri-band performance in limited space. Roof mount with AV-14RMQ kit, $89.95.

AV-18VS, $99.95. (10,12,15,17,20,30,40,80 Meters). 18 ft., 4 lbs. High quality construction and low cost make the AV-18VS an exceptional value. Easily tuned to any band by adjusting feed point at the base loading coil. Roof mount with Hy-Gain AV-14RMQ kit, $89.95.

DX-88, $369.95. (10, 12, 15,17,20,30,40,80 Meters, 160 Meters optional). 25 ft., 18 lbs.
All bands are *easily* tuned with the DX-88's *exclusive* adjustable capacitors. 80 and 40 Meters can even be tuned from the ground without having to lower the antenna. Super heavy-duty construction. DX-88 OPTIONS: 160 Meter add-on kit, KIT-160-88, $199.95. Ground Radial System, GRK-88, $99.95. Roof Radial System, RRK-88, $99.95.

DX-77A, $449.95. (10, 12, 15, 17, 20, 30, 40 Meters). 29 ft., 25 lbs.
No ground radials required! Off-center-fed Windom has 55% greater bandwidth than competitive verticals. Heavy-duty tiltable base. Each band independently tunable.

hy-gain(R) PATRIOT

Hy-Gain's new PATRIOT HF verticals are the best built, best performing and best priced multiband verticals available today. For exciting DX make full use of your sunspot cycle with the PATRIOT's *low 17 degree angle* signal.

No ground or radials needed
Effective counterpoise replaces radials and ground.
Automatic bandswitching
Single coax cable feed. Each band is individually tunable. Extra wide VSWR bandwidth. End fed with broadband matching unit.
Sleek and low-profile
Low 2.5 sq. ft. wind surface area. Small area required for mounting. Mounts easily on decks, roofs and patios.
Full legal limit
Handles 1500 Watts key down continuous for two minutes.
Built-to-last
High wind survival of 80 mph. Broadband matching unit made from all *Teflon*R insulated wire. Aircraft quality aluminum tubing, stainless steel hardware.
*hy-gain*R *warranty*
Two year limited warranty. All replacement parts in stock.

AV-640, $399.95. (6,10,12, 15,17,20,30,40 Meters). 25.5 ft., 17.5 lbs. The AV-640 uses quarter wave stubs on 6, 10, 12 and 17 meters and efficient end loading coil and capacity hats on 15, 20, 30 and 40 meters -- no traps. Resonators are placed in parallel not in series. End load-ing of the lower HF bands allows efficient operation with a manageable antenna height.

AV-620, $299.95. (6,10,12,15,17,20). 22.5 ft., 10.5 lbs. The AV-620 covers all bands 6 through 20 Meters with no traps, no coils, no radials yielding an uncompromised signal across all bands.

AV-640 $399⁹⁵

Free Hy-Gain Catalog
and Nearest Dealer . . . 800-973-6572
Call your dealer for your best price!

Model #	Price	Bands	Max Power	Height	Weight	Wind Surv.	Rec. Mast
AV-18HT	$949.95	10,15,20,40,80	1500 W PEP	53 feet	114 pounds	75 MPH	------
AV-14AVQ	**$169.95**	**10,15,20,40**	**1500 W PEP**	**18 feet**	**9 pounds**	**80 MPH**	1.5-1.625"
AV-12AVQ	$134.95	10/15/20 M	1500 W PEP	13 feet	9 pounds	80 MPH	1.5-1.625"
AV-18VS	**$99.95**	**10 - 80 M**	**1500 W PEP**	**18 feet**	**4 pounds**	**80 MPH**	1.5-1.625"
DX-88	$369.95	10 - 40 M	1500 W PEP	25 feet	18 pounds	75 mph no guy	1.5-1.625"
DX-77A	**$449.95**	**10 - 80 M**	**1500 W PEP**	**29 feet**	**25 pounds**	**60 mph no guy**	**1.5-1.625"**

hy-gain
Antennas, Rotators & Towers
308 Industrial Park Road, Starkville, MS 39759 USA
Toll-free Customer Sales Hotline: 800-973-6572
• **TECH:** 662-323-9538 • **FAX:** 662-323-6551
http://www.hy-gain.com
Prices and specifications subject to change without notice or obligation. © Hy-Gain®, 2006.

AB-4   Special Advertising Section

Antennas *built-to-last . . . Use hy-gain parts!*

FAMOUS Heavy Duty *hy-gain* BALUNS

BN-86, $79.95. Broadband 50 Ohm ferrite balun. Useable from 3 to 30 MHz. Recommended for all HF Yagi antennas. It provides improved front-to-back ratio. Comes with clamp to bolt to boom, SO-239 connector.

BN-4000B, $109.95. Broadband 50 Ohm Yagi current balun is potted to seal out moisture. Rated at 4000 Watts for increased power handling capabilities. 1 to 54 MHz. SO-239 connector. **BN-4000D, $109.95.** dipoles. **BN-4000N, $119.95.** "N" connector.

hy-gain Center Dipole Insulators

C-1, $29.95. Center Insulator for multiband dipole antenna.

C-1C, $29.95. Similar to C-1, but has SO-239 antenna connector.

E-1, $6.95. 6 inch super high-power, high-voltage *end insulator* for Multi-band doublet antenna. Set of 2.

Arrowpoint Anchor

APA-3, $14.95. Up to 2000 lbs. pull-out resistance to secure antennas, towers. Use one per guy wire. **DR-3, $29.95.** Drive Rod.

Glazed Ceramic Insulator

E-2 **79¢** each

E-26 **$4.56** 6-Pack

Extra-strong -- will not break, arc over or melt even under full legal power. Molded ridges give extra-long path to prevent high-voltage breakdown.

Ground Rod

Durable four foot by 3/8 inch diameter *copper bonded* steel earth ground rod. Sharp point makes it easy to insert into ground. Bleed off static/RFI. Prevent RF hot spots. Use several to form a good RF ground.

GR-1 **$6.95**

hy-gain Rotator

World's most rugged rotator! Many in use after 25 years. Highly resistant to lightning, static, RFI. Bell design gives total weather protection. 15 sq. ft. wind-load, 5-sec. brake delay, 5000 in-lb steel wedge brake, ring gear handles 100,000 PSI, dual 98 ball bearing race, -30°F operation. Max mast 2¹/₁₆"

HAM-IV **$559⁹⁵**

hy-gain Aluminum Tubing

6063 T832 round, drawn aluminum tubing sold in 2 styles: *6' standard* or *6' slitted* one end, (.083" gaps, 1-2" slit lengths). **Tubing** are sized to allow telescoping into one another from .625 OD to 2 inches OD. Select slitted tubing for telescoping. Use Hy-gain Stainless Steel hose clamps to secure.

OD x Wall-Th x ID	6'stnrd; p/n, price/ea	6'slitd p/n, price/ea.	Ad'l/ft.
.625"x.035"x.555"	810-0625C-6U, $5.70	810-0625C-6S, $6.90	$1.00
.750"x.058"x.634"	810-0750E-6U, $10.55	810-0750E-6S, $12.66	$1.85
.875"x.058"x.759"	810-0875E-6U, $8.72	810-0875E-6S, $9.92	$1.53
1.000"x.058"x.884"	810-1000E-6U, $11.46	810-1000E-6S, $12.66	$2.01
1.125"x.058"x1.009"	810-1125E-6U, $10.03	810-1125E-6S, $11.23	$1.76
1.250"x.058"x1.134"	810-1250E-6U, $11.57	810-1250E-6S, $12.77	$2.03
1.375"x.058"x1.259"	810-1375E-6U, $13.17	810-1375E-6S, $14.37	$2.31
1.500"x.058"x1.384"	810-1500E-6U, $17.95	810-1500E-6S, $19.16	$3.15
1.625"x.058"x1.509"	810-1625E-6U, $21.32	810-1625E-6S, $22.52	$3.74
1.750"x.058"x1.634"	810-1750G-6U, $27.86	810-1750G-6S, $29.62	$4.88
2.000"x.120"x1.760"	810-2000I-6U, $38.93	810-2000I-6S, $41.03	$6.83

hy-gain Stainless Steel Hose Clamps

Part No.	Price	Description
745-3106S	$1.00	#6 Clamp for .75" OD to .875" OD tubing
745-3110S	$1.00	#10 Clamp for 1" OD to 1.125" OD tubing
745-3116S	$1.25	#16 Clamp for 1.25" OD to 1.50" OD tubing
745-3128S	$2.84	#28 Clamp for 1.75" OD to 2" OD tubing

hy-gain Telescopic *Aluminum Mast*

ATM-65, $199.95. Pictured left. 11-section *multi-purpose* aluminum telescopic pole can be used as a vertical antenna or as a mast. Great for portable, temporary use and permanent use -- traveling, camping, etc. Includes one size of each slitted tube listed above and ten hose clamps. 65 ft. fully extended, 6 ft. collapsed without clamps. Guying required if mast is extended beyond 30 feet. Top section is .625" OD. Bottom section is 2 inches OD x .120 wall.

810-2000I-6W, $44.95 each. Unique tubing has one end slitted and one end swaged to make it stackable. Slide one end into another tubing for longer poles. Secure with standard host clamp. Strong, 2"OD x .120" wall. Good for base sections of vertical antennas. Standard 6-ft. length, longer sections, to 20 ft. available. Add $6.83 each add'l foot. **6 ft.** lengths ship by UPS, longer units must ship UPS *oversize*/truck.

hy-gain Base Mount Assembly Kit ➤

ATM-65 **$199⁹⁵**

877200, $69.95. *New!* Complete ATM-65 base assembly kit with base mounting plate, insulators, hardware.

---

hy-gain Custom *Precision* Antenna Hardware

BMC-249, $79.95. *Boom to Mast Clamp* Heavy duty 1¹/₄" OD thick aluminum die casted boom to mast clamp designed for heavy antennas. Supports 2-inch boom antennas, such as the TH-11DX, Long John Monobanders and other beams with a 2" boom. The BMC-249 allows mast to extend past the top of the clamp. This feature allows stacking of several antennas on one mast. Clamp is adjustable for mast sizes from 1¹/₄" to 2³/₄" OD. The tilt-over feature permits easy assembly of the elements and simplifies maintenance of the antenna. 4Wx4Hx1¹/₄" thick. Kit comes complete with stainless steel hardware.

Element to Boom Clamps Made from high tensile strength aluminum alloy. Custom die is used to stamp these clamps. No miss-drilled holes. They fit perfect everytime. Required 2 clamps per element. Element Insulators available (left).

Element Insulators These element insulators are made to fit the element bracket (right). Precision injection molded with black UV resisted ABS plastic.

Part No.	Price	Fits these Element sizes	Insulator Size	Fits Element to boom clamp
465216	$3.42	⁷/₁₆" OD	⁷/₈"OD x 2³/₄"	163409
461057	$4.40	⁵/₈" OD	1¹/₄"OD x 3"	165919
463767	$4.40	⁷/₈" OD	1¹/₄"OD x 3"	165919
465833	$4.80	1¹/₄" OD	1¹/₂"OD x 4"	165920

hy-gain TH-series HF Beam Trap Caps
A. 464723, $.75 ea. Trap caps, for large Hy-gain TH-series traps.
B. 466221, $1.59 ea. Trap caps for Hy-gain TH-3Jr. traps.

Part#	Price	Boom OD"	Element OD w/o insulator	Element OD w/insulator	Description	Insulator
161409	$2.71	2"	⁵/₈"	---	2¹/₂x7"x.08 Thick, #12	None
163764	$3.80	2"	⁷/₈"	⁷/₁₆"	2³/₈x7¹/₈"x.08 Thick, #4	465216
165919	$5.32	2"	1¹/₄"	⁵/₈", ⁷/₈"	3¹/₄x7¹/₄"x.125 Thick, #13	463767, 461057
165920	$6.28	2"	1¹/₂"	1¹/₄"	3¹/₄x9¹/₂"x.125 Thick, #14	465833
160055	$1.22	1¹/₄"	⁷/₁₆"	---	³/₄x5"x.063 Thick, #0	None
161422	$3.63	1¹/₄"	⁵/₈"	---	2¹/₄x6¹/₂"x.08 Thick, #11	None
165141	$3.76	1¹/₄"	⁷/₈"	⁷/₁₆"	2⁵/₁₆x6⁵/₈"x.08 Thick, #12	465216
165138	$5.20	1¹/₄"	1¹/₄"	⁵/₈", ⁷/₈"	2³/₄x6¹/₂"x.08 Thick, #1	463767, 461057
872223	$6.60				Stainless steel screws, nuts and washers for 1 set of element-to-boom clamp	

---

hy-gain Vertical Antenna Hardware

A. 463011, $14.00, Base tubing insulator, fits 1¹/₄" OD tube. Six ⁵/₁₆" mounting holes. Super strong fiberglass filled ABS. Used in Hy-tower to isolate tower legs from ground. Tubing not included.
B. 877130, $28.64, Vertical antenna bracket assembly. Includes bracket (C), base cover insulator (D), support insulator (E) and SO-239. Fits 1¹/₄" tubing. Tubing not included.
C. 160043-1, $11.84, Base mount bracket. Custom-tooled ¹/₈" thick x 12 inch length aluminum bracket with vertical ridges for super strength. Pre-punched holes for SO-239 or N-connector.
D. 863427, $6.90, Base tubing insulator. Molded pin connects base tubing to SO-239 or N-connector.
E. 463056, $3.12, Base antenna support insulator. Made to fit top support of antenna bracket (C). Hole fits 1¹/₄" OD tubing.
F. 460316, $12.96, Tubing coupler/insulator. Used to couple/insulate 1" tube to ⁷/₈" tubing. Made of fiberglass filled ABS, 5" long.

hy-Gain Tower Bases

Specially designed for *hy-gain* crank-up towers. Complete with base hinge and foundation welded steel-cage. Specify tower model. *Shipped by truck, call for quote.

Model#	Tower	Price	Weight
TB-37	HG-37SS	$299.95	50 lbs.*
TB-52	HG-52SS	$299.95	80 lbs.*
TB-54	HG-54HD	$299.95	90 lbs.*
TB-70	HG-70HD	$349.95	102 lbs.*

Free *hy-gain* Catalog
and Nearest Dealer . . . 800-973-6572
Call your dealer for your best price!

hy-gain®

Antennas, Rotators & Towers
308 Industrial Park Road, Starkville, MS 39759 USA
Toll-free Customer Sales Hotline: 800-973-6572
• **TECH:** 662-323-9538 • **FAX:** 662-323-6551

http://www.hy-gain.com
Prices and specifications subject to change without notice or obligation. ©) Hy-Gain®, 2007.

Andrew Cinta® Cable Assemblies

From 🌐

CABLE X-PERTS, INC.
Connecting You to the World...

INDEX

D

937

942

944

947

948

Q

952

953

954

U

V

W

958

960

Notes

Notes

Notes

Notes

Notes

Notes

Notes

968

FEEDBACK

Please use this form to give us your comments on this book and what you'd like to see in future editions, or e-mail us at **pubsfdbk@arrl.org** (publications feedback). If you use e-mail, please include your name, call, e-mail address and the book
title, edition and printing in the body of your message. Also indicate whether or not you are an ARRL member.

Where did you purchase this book?
◻ From ARRL directly   ◻ From an ARRL dealer

Is there a dealer who carries ARRL publications within:
◻ 5 miles   ◻ 15 miles   ◻ 30 miles of your location?   ◻ Not sure.

License class:
◻ Novice   ◻ Technician   ◻ Technician with code   ◻ General   ◻ Advanced   ◻ Amateur Extra

---

Name _____   ARRL member? ◻ Yes ◻ No

_____ Call Sign _____

Daytime Phone (   ) _____ Age _____

Address _____

City, State/Province, ZIP/Postal Code_____ E-mail: _____

If licensed, how long? _____

Other hobbies _____

_____

Occupation _____

From _____

_____

_____

EDITOR, ARRL ANTENNA BOOK
ARRL—THE NATIONAL ASSOCIATION FOR
  AMATEUR RADIO
225 MAIN STREET
NEWINGTON CT 06111-1494

— — — — — — — — — — — — — — — — — please fold and tape — — — — — — — — — — — — — — — — — —

Introduction to the CD-ROM Edition
The ARRL Antenna Book, 21st Edition

"In recent years it has been borne home on us most forcibly that there is greater room for increased performance through superior antenna systems than in any other part of the equipment."

—from the Foreword to the First Edition,

Much has changed since 1939, including the possible ways of delivering information—this CD-ROM is evidence of that! One thing that hasn't changed is that antennas and antenna systems are still the make-or-break component of any amateur station. We are pleased to bring you this 21st edition of *The ARRL Antenna Book* on CD-ROM. The CD-ROM book contains all of the text, drawings and photos contained in the printed 21st edition. And exclusive to the CD-ROM are over 70,000 pages of propagation tables that can help you determine what HF propagation to expect throughout the world, throughout the year and throughout the sunspot cycle.

Make sure you try out the software included for the PC. Follow the instructions for installation of the software and data files.

Using this CD-ROM

This CD-ROM is viewed using Adobe's *Reader* software. Version 7.0 of the software is included on the CD-ROM. The book and the companion files include hyperlinks. These links will appear in blue or green text. Clicking on the text of a hyperlink will cause *Reader* to display another, related part of the book. (See the *Reade*r Help documentation for information on configuring this feature.)

The version of *Acrobat Reader* used with this CD-ROM includes Acrobat Search capability, which allows rapid full-text search of the entire book. This functions as an instant index for every chapter and word in the book. We strongly recommend that you take a few minutes to view the on-line documentation available from *Acrobat Reader*'s Help menu.

Note: Adobe *Reader* version 6.0 or higher is required to use the search index included on this CD-ROM. Older versions of *Acrobat Reader* will not work with the search index, but are otherwise functional. Again, Adobe *Reader* 7.0 is included on the CD-ROM, if you need to install this version.

Installing Adobe *Acrobat Reader*

You may not have *Acrobat Reader* installed on your computer or you may have an older version installed. Installing Adobe *Acrobat Reader Ver.7* is optional during the main Setup installation, and you can do it later, after installing the *Antenna Book* software too.

To install *Acrobat Reader* for *Windows*:
Select **Run** from the *Windows* **Start** menu.
1. Type or Browse to **d:\AdbeRdr709_en_US.exe** (where d: is the drive letter of your CD-ROM drive; if the CD-ROM is a different drive on your system, use the appropriate letter) and press **Enter**.
2. Follow the instructions that appear on your screen.

To install *Acrobat Reader* for the Macintosh:
1. From the top-level folder of the CD, double click on the file "Adobe_Reader_MAC_708.dmg" to open up the disk image. Then double click the Adobe Reader Installer icon to launch the installer.

AB21 Intro to CD.DOC   HE:RDS   3/7/2007   8:14 AM   Page 3

971

Choices, Summary and Detailed Propagation Tables

USA

W1B	Boston, MA
W2A	Albany, NY
W2N	NYC, NY
W3D	Washington, DC
W4A	Montgomery, AL
W4F	Miami, FL
W4G	Atlanta, GA
W4K	Louisville, KY
W4N	Raleigh, NC
W4T	Memphis, TN
W5A	Little Rock, AR
W5H	Houston, TX
W5L	New Orleans, LA
W5M	Jackson, MS
W5N	Albuquerque, NM
W5O	Oklahoma City, OK
W5T	Dallas, TX
W6L	Los Angeles, CA
W6S	San Francisco, CA
W7A	Phoenix, AZ
W7I	Boise, ID
W7M	Helena, MT
W7N	Las Vegas, NV
W7O	Portland, OR
W7U	Salt Lake City, UT
W7W	Seattle, WA
W7Y	Cheyenne, WY
W8M	Detroit, MI
W8O	Cincinnati, OH
W8W	Charleston, WV
W9C	Chicago, IL
W9I	Indianapolis, IN
W9W	Milwaukee, WI
WØC	Denver, CO
WØD	Bismarck, ND
WØI	Kansas City, MO
WØK	Middle of US, KS
WØM	St. Louis, MO
WØN	Omaha, NE
WØS	Pierre, SD

Other, North America

6Y	Kingston, Jamaica
8P	Bridgetown, Barbados
HP	Panama City, Panama
KL7	Anchorage, Alaska
KP2	Virgin Islands
TI	San Jose, Costa Rica
V3	Belmopan, Belize
VE1	Halifax, Nova Scotia
VE2	Montreal, Quebec
VE3	Toronto, Ontario
VE4	Winnipeg, Manitoba
VE5	Regina, Saskatchewan
VE6	Edmonton, Alberta
VE7	Vancouver, BC
VE8	Yellowknife, NWT
VO1	St. John's, NFL
VP2	Anguilla
VP5	Turks & Caicos
XE1	Mexico City, Mexico

Europe

CT	Lisbon, Portugal
DL	Bonn, Germany
EA	Madrid, Spain
EI	Dublin, Ireland
ER	Kishinev, Moldava
F	Paris, France
G	London, England
I	Rome, Italy
JW	Svalbard
OH	Helsinki, Finland
OK	Prague, Czech Republic
ON	Brussels, Belgium
OZ	Copenhagen, Denmark
SV	Athens, Greece
TF	Reykjavik, Iceland
UA3	Moscow, Russia
UA6	Rostov, Russia
UR	Kiev, Ukraine
YO	Bucharest, Romania
YU	Belgrade, Yugoslavia

South America

CE	Santiago, Chile
CP	La Paz, Bolivia
FY	Cayenne, French Guiana
HC	Quito, Ecuador
HC8	Galapagos Islands
HK	Bogota, Columbia
LU	Buenos Aires, Argentina
OA	Lima, Peru
P4	Aruba
PY1	Rio de Janeiro, Brazil
PYØ	Fernando de Noronha
YV	Caracas, Venezuela
YVØ	Aves Island
ZP	Asuncion, Paraguay

Asia

1S	Spratly Islands
3W	Ho Chi Minh City, Vietnam
4J	Baku, Azerbaijan
4S	Columbo, Sri Lanka
4X	Jerusalem, Israel
9N	Katmandu, Nepal
A6	Dubai, UAE
AP	Karachi, Pakistan
BY1	Beijing, China
BY4	Shanghai, China
BYØ	Lhasa, China
HS	Bangkok, Thailand
HZ	Riyadh, Saudi Arabia
JA1	Tokyo, Japan
JA3	Osaka, Japan
JA8	Sapporo, Japan
JT	Ulan Bator, Mongolia
TA	Ankara, Turkey
UA9	Perm, Russia
UAØ	Khabarovsk, Russia
UN	Alma-Ata, Kazakh
VR2	Hong Kong
VU	New Delhi, India
VU7	Andaman Islands
XZ	Rangoon, Myanmar

Oceania

3D2	Fiji Islands
DU	Manila, Philippines
FO	Tahiti
H4	Honiara, Solomon Islands
JD1	Ogasawara Island
KHØ	Saipan, Mariana Islands
KH5K	Kingman Reef
KH6	Honolulu, Hawaii
KH8	American Samoa
V7	Kwajalein, Marshall Islands
VK2	Sydney, Australia
VK6	Perth, Australia
VK8	Darwin, Australia
YB	Jakarta, Indonesia
ZL1	Aukland, New Zealand
ZL3	Christchurch, New Zealand

Africa

3B9	Rodrigues
3C	Bata, Equatorial Guinea
3V	Tunis, Tunisia
5N	Lagos, Nigeria
5R	Antananarivo, Madagascar
5U	Niamey, Niger Republic
5Z	Nairobi, Kenya
6W	Dakar, Senegal
7Q	Lolongwe, Malawi
7X	Algiers, Algeria
9J	Lusaka, Zambia
9L	Freetown, Sierra Leone
9X	Kigali, Rwanda

C9	Maputo, Mozambique
CN	Casablanca, Morroco
CT3	Madeira Islands
D2	Luanda, Angola
EA8	Canary Islands
IG9	Lampedusa, Italy
J2	Djibouti
ST	Khartoum, Sudan
SU	Cairo, Egypt
VQ9	Chagos, Diego Garcia
XT	Burkina Faso
ZS1	Capetown, So. Africa
ZS6	Johannesburg, So. Africa

These PDF files contain propagation prediction tables valid from the transmitting site indicated in the filename to seven generalized receiving locations throughout the world in the Summary Tables and for the 40 CQ Zones in the Detailed Tables. The user selects a single transmitting site closest to his/her location. You can access this data by opening *Adobe Acrobat Reader* and selecting **Prop Index.pdf**. Or you can operate from the main table of contents in the left pane of the opening window.

Each transmitting location is organized by five levels of solar activity over the whole 11-year solar cycle:

VL (Very Low: SSN between 0 to 20)
LO (Low: SSN between 20 to 40)
ME (Medium: SSN between 40 to 60)
HI (High: SSN between 60 to 100)
VH (Very High: SSN between 100 to 150)
UH (Ultra High: SSN greater than 150)

The seven generalized locations throughout the world for the Summary Tables are:

EU = Europe (all of Europe)
FE = Far East (centered on Tokyo, Japan)
SA = South America (centered on Asuncion, Paraguay)
AF = Africa (centered on Lusaka, Zambia)
AS = southern Asia (centered on New Delhi, India)
OC = Oceania (centered on Sydney, Australia)
NA = North America (all of USA).

Both types of propagation files show the highest predicted signal strength (in S-units) throughout the generalized receiving area, for a 1500-W transmitter and rather good antennas on both sides of the circuit. The standard antennas are 100-foot high inverted-V dipoles for 80 and 40 meters, a 3-element Yagi at 100 feet for 20 meters, and a 4-element Yagi at 60 feet for 15 and 10 meters. Discount the S-Meter readings in the tables to represent a smaller station:

Subtract 2 S units for a dipole instead of a Yagi
Subtract 3 S units for a dipole at 50 feet instead of a Yagi at 100 feet
Subtract 1 S unit for a dipole at 50 feet rather than a dipole at 100 feet
Subtract 3 S units for 100 W rather than 1500 W.
Subtract 6 S units for 5 W rather than 1500 W.

Shown below is an image of a Summary Table printout from Boston to the rest of the world, for Very High solar activity in January. This table could be used, for example, to help plan which bands to operate when on a DXpedition to some exotic location.

The Detailed Table printout from Boston to the rest of the world on 20 meters for January from Boston during a Very High level of the solar cycle is shown on the following page. It shows the predicted signal strength in each of the 40 CQ Zones around the world. Note that long-path openings are predicted by an asterisk appended to the end of the predicted signal strength.

Also located on the CD-ROM in the \Propagation subdirectory is the **Fig6Tab.pdf** file described in Chapter 3 of the printed book. This set of tables shows the hours open to each of 10 regions throughout the USA for Very-Low/Medium/Very-High levels of SSN.

Enjoy the software. We would appreciate any feedback or bug reports you might have.

73,

R. Dean Straw, N6BV
Editor, *The ARRL Antenna Book*
email: **n6bv@arrl.org**

Sample Summary Propagation-Prediction Table, January from Boston to the World

Jan., MA (Boston), for SSN = Very High, Sigs in S-Units. By N6BV, ARRL.

80 Meters

UTC	EU	FE	SA	AF	AS	OC	NA
0	9+	-	9+	9+	8	-	9+
1	9+	-	9+	9+	8	-	9+
2	9+	-	9+	9+	7	-	9+
3	9+	-	9+	9+	1	2	9+
4	9+	-	9+	9+	-	7	9+
5	9+	-	9+	9+	-	8	9+
6	9+	-	9+	9+	-	8	9+
7	9+	-	9+	9+	-	8	9+
8	9	7	9+	9	-	8	9+
9	8	7	9+	7	-	8	9+
10	5	8	9+	2	3	8	9+
11	1	8	9+	-	4	9	9+
12	-	7	8	-	1	9	9+
13	-	-	-	-	-	2	9+
14	-	-	-	-	-	-	9+
15	-	-	-	-	-	-	9
16	-	-	-	-	-	-	8
17	-	-	-	-	-	-	8
18	-	-	-	-	-	-	9
19	1	-	1	-	-	-	9+
20	4	-	2	5	-	-	9+
21	7	-	8	7	1	-	9+
22	9	2	9+	9	8	-	9+
23	9	-	9+	9	8	-	9+

40 Meters

UTC	EU	FE	SA	AF	AS	OC	NA
0	9+	5	9+	9+	9	-	9+
1	9+	4	9+	9+	9	2	9+
2	9+	4	9+	9+	9	7	9+
3	9+	4	9+	9+	9	9	9+
4	9+	5	9+	9+	8	9	9+
5	9+	6	9+	9+	7	9	9+
6	9+	7	9+	9+	7	9	9+
7	9	8	9+	9+	7	9+	9+
8	9	8	9+	9+	8	9	9+
9	9	9	9+	9	8	9	9+
10	9	9	9+	8	8	9	9+
11	8	9	9+	5	8	9	9+
12	6	9	9+	1	8	9	9+
13	4	8	8	-	7	9	9+
14	2	7	4	-	5	8	9+
15	1	5	1	-	4	5	9+
16	3	4	-	-	3	1	9+
17	5	3	-	2	4	-	9+
18	7	4	2	5	5	-	9+
19	8	5	6	8	7	-	9+
20	9	6	9	9	8	-	9+
21	9+	7	9+	9+	9	1	9+
22	9+	7	9+	9+	9	4	9+
23	9+	7	9+	9+	9	-	9+

20 Meters

UTC	EU	FE	SA	AF	AS	OC	NA
0	1	9+	9+	9+	9+	9	9+
1	1	9	9+	8	9+	9+	9+
2	1	9	9+	8	9	9+	9+
3	-	7	9+	7	8	9+	9
4	-	5	9+	9	9	9	9+
5	-	5	9+	9	9	5	9+
6	-	8	9+	8	9	5	9+
7	-	9	9+	-	7	9	9+
8	-	9	9+	-	4	9+	9+
9	-	6	9+	-	1	9+	9+
10	4	-	9+	9+	1	5	9
11	9+	4*	9+	9+	7	-	8
12	9+	9	9+	9	9	1*	9+
13	9+	9	9+	9	9	9+	9+
14	9+	9	9+	8	9	9	9+
15	9+	9	9+	9	9	9	9+
16	9+	8	9	9+	9	9	9+
17	9+	8	9+	9+	9	9	9+
18	9+	9	9+	9+	9	9	9+
19	9+	9	9+	9+	9	9	9+
20	9+	9	9+	9+	9	9	9+
21	8	9	9+	9+	9	9	9+
22	2	9+	9+	9+	9	9	9+
23	1	9+	9+	9+	9	9	9+

15 Meters

UTC	EU	FE	SA	AF	AS	OC	NA
0	-	9	9+	2	2	9+	9+
1	-	3	9	-	7	9+	9
2	-	-	3	-	-	7	9
3	-	-	-	-	-	-	-
4	-	-	1	-	-	-	-
5	-	-	-	-	-	-	-
6	-	-	-	-	-	-	-
7	-	-	1	-	-	-	-
8	-	-	1	-	-	-	2
9	-	-	-	-	-	-	1
10	-	-	-	-	-	-	-
11	-	-	9	9	-	-	-
12	9	8*	9+	9+	9	5*	-
13	9+	7	9+	9+	9+	3*	9
14	9+	9	9+	9+	9+	9	9+
15	9+	9+	9+	9+	9+	9	9+
16	9+	9+	9+	9+	9	1*	9+
17	9+	9	9+	9+	9+	9+	9+
18	9+	9	9+	9+	1	9+	9+
19	-	9+	9+	9+	2	9	9+
20	-	8	9+	9+	3	9	9+
21	-	6	9+	9+	3	9	9+
22	-	9+	9+	9	1	9+	9+
23	-	9+	9+	9+	-	9	9+

10 Meters

UTC	EU	FE	SA	AF	AS	OC	NA
0	-	1	8	-	-	8	9+
1	-	-	-	-	-	4	2
2	-	-	-	-	-	-	2
3	-	-	-	-	-	-	2
4	-	-	-	-	-	-	2
5	-	-	-	-	-	-	2
6	-	-	-	-	-	-	2
7	-	-	-	-	-	-	2
8	-	-	-	-	-	-	2
9	-	-	-	-	-	-	2
10	-	-	-	-	-	-	2
11	-	-	-	-	-	-	2
12	-	2*	9	9	1	1*	2
13	9	5*	9+	9+	9	6*	2
14	9	6*	9+	9+	9	1*	1
15	9	5	9+	9+	6	6	8
16	9	8	9+	9+	-	8	9
17	9+	8	9+	9+	-	8	9+
18	9+	7	9+	9+	-	9+	9+
19	9+	6	9+	9+	-	9+	9+
20	9	1	9+	9	-	9	9+
21	9+	-	9+	5*	-	9+	9+
22	9	5	9+	4*	-	9	6
23	9+	7	9+	2*	-	9	2

Sample Detailed Propagation Table for 20 Meters, January, Boston to World for Very High SSN

20 Meters: Jan., MA (Boston), for SSN = Very High, Sigs in S-Units. By N6BV, ARRL.

UTC -->

Zone	00	01	02	03	04	05	06	07	08	09	10	11	12	13	14	15	16	17	18	19	20	21	22	23
KL7 = 01	9+	9+	9+	7	-	9	8	-	-	-	-	1	-	-	-	3	9+	9+	9+	9+	9+	9+	9+	9+
VO2 = 02	9+	9	9	9	9	9	8	7	5	3	2	1	5	9+	9+	9+	9+	9+	9+	9+	9+	9+	8	9+
W6 = 03	9+	9+	9+	7	7	1	1	5	5	8	3	-	1	1	9+	9+	9+	9+	9+	9	9	9+	9+	9+
W0 = 04	9+	9+	9+	8	5	5	5	5	3	2	1	-	9+	9+	9+	9+	9+	9+	9+	9	9	9+	9+	9+
W3 = 05	4	2	2	2	2	2	2	3	3	3	3	2	1	1	8	9+	9+	9+	9+	9+	9+	9	9+	9
XE1 = 06	9+	9+	7	9	9+	9+	9+	9+	9+	9+	9	8	9+	9+	9+	9+	9	9	9	9	9+	9+	9+	9+
TI = 07	9+	9+	8	9	9	9	9	9	9	9+	9	9+	9+	9+	9+	9+	9	8	9	9	9+	9+	9+	9+
VP2 = 08	9+	9+	9+	9+	9+	9+	9+	9+	9+	8	9	9+	9+	9+	9+	9+	9	9+	9+	9+	9+	9+	9+	9+
P4 = 09	9+	9+	9+	9	9	9+	9+	9+	9+	9+	9+	9+	9+	9+	9+	9+	9	9	9	9	9+	9+	9+	9+
HC = 10	9+	8	9+	9	9	9	9	9	7	3	1	7	8	9+	9	5	5	5	7	8	9	9	9	9
PY1 = 11	9+	9+	9+	9	9+	9+	9+	9	8	6	9	9+	9	2	1	1	-	1	4	8	7	7	7	7
CE = 12	9+	9+	9+	9	9+	9+	9+	9+	8	8	8	9+	9	8	2	1	1	-	1	4	8	9	9	9
LU = 13	9+	9+	9+	9	9+	9+	9+	9+	8	8	8	9+	9	4	2	1	-	1	1	4	8	9	9	8
G = 14	-	-	-	-	-	-	-	-	-	-	-	9+	9+	9+	9+	9+	9+	9+	9+	9+	9+	2	-	-
I = 15	-	-	-	-	-	-	-	-	-	4	-	9	9	9	9	9	9	8	9	-	8	-	-	1
UR3 = 16	1	1	-	-	-	-	7	1	-	-	-	8	9	9	9	6	-	-	5	4	8	5	5	4
UN = 17	1	7	6	8	7	7	7	7	4	1	-	2	9	8	6	6	5	6	2	4	9	9	8	7
UA9 = 18	6	9	6	6	9	9	8	8	8	-	-	-	8	6	8	8	8	7	7	8	7	9	9+	7
UA0 = 19	9+	6	9	1	5	5	4	8	1	4	1	-	2	8	8	8	9	9	4	4	9	8	7	7
4X = 20	8	6	3	3	-	3	2	-	-	-	1	8	8	8	8	8	9	9	9+	9	9	9	9	9
HZ = 21	9+	9	4	7	8	8	5	-	3	-	1	7	8	9	8	9	9	2	2	2	8	9	9	8
VU = 22	7	5	8	7	6	7	8	-	6	-	-	6	9	9	9	9	3	8	2	2	8	9	9	9
JT = 23	9	9	9	5	7	8	8	6	3	1	-	2*	8	8	5	6	8	8	8	8	9	7	5	6
VS6 = 24	9	9	9	5	4	5	7	8	6	1	-	1*	5	7	1	1	1	1	4	2	9	-	-	9
JA1 = 25	9	9	8	7	5	5	8	9	9	6	-	1	1	2	7	7	6	2	-	-	7	9	9+	9
HS = 26	9	9	6	4	2	-	-	2	1	1	-	2*	9	9	9	9	8	7	5	4	5	-	1*	1
DU = 27	9	8	7	-	-	5	5	7	7	1	-	7	9	8	9	7	6	4	5	3	1*	1*	8	9
YB = 28	9	8	1	-	-	-	-	-	7	1	-	4*	8	5	9	9	8	8	9	9	9	9	9+	9+
VK6 = 29	3*	4*	-	-	-	-	1	3	5	3	4	-	-	5	5	9	9	8	9	9	9	2*	9+	8
VK3 = 30	1*	-	-	-	-	-	1	6	9	9	4	-	-	9+	1*	9	2	1	-	1	1	2*	5*	4*
KH6 = 31	9	9+	9+	9+	8	2	2	6	4	-	-	-	-	-	3*	1*	1	9	8	7	6	4	6	7
KH8 = 32	-	2	9	9	9	-	5	9	9+	9+	-	-	9+	9+	9	9	8	5	3	1	-	-	-	-
CN = 33	-	-	-	-	-	-	-	-	-	-	5	-	-	9+	-	9	9	9	9+	9+	9+	9+	9+	7
SU = 34	9	8	3	3	-	1	4	-	-	-	9	9+	9	9	8	9	9	9	9+	9+	9+	9+	9+	8
6W = 35	9+	8	-	3	2	7	5	-	-	-	2	7	8	8	8	8	7	9	9+	9+	9+	9+	9+	9+
D2 = 36	9+	9+	5	4	9	9	8	-	-	-	3	9+	8	5	5	3	4	7	8	9	9+	9+	9+	9+
5Z = 37	9+	9	2	7	8	8	1	-	-	-	2	-	-	3	5	4	7	8	9	9	9+	9+	9+	9+
ZS6 = 38	9+	9+	8	7	8	9	6	-	-	-	-	-	-	-	1*	1*	2	5	8	7	6	6	6	7
FR = 39	9+	8	2	1	4	1	-	-	-	-	-	-	2*	3*	3*	1*	1	3	3	1	1	-	-	-
FJL = 40	9+	9+	7	4	7	8	7	1	-	-	-	1*	9	9	9	9	9	9	9	9+	9+	9+	9+	9+
Zone	00	01	02	03	04	05	06	07	08	09	10	11	12	13	14	15	16	17	18	19	20	21	22	23

UTC -->

Expected signal levels using 1500 W and 3-element Yagis at 100 feet at each station.

976